



It is understood that neither the scope nor the appurtenant undertaking of the Licence have changed since the original Licence (1BH-BLT1414) was issued by the NWB on August 29, 2014, and that the Licensee asked for an amendment to extend the duration of the Licence by a year solely because they were unable to perform hydrostatic testing duties in 2014. As a change to the duration of the Licence is the only alteration requested to the appurtenant undertaking, the Board has determined that a renewal of the original Licence is the most appropriate step forward. The Licensee is advised to adhere to the comments provided by AANDC during the external review of the Licence Application (1BH-BLT1515)<sup>1</sup>, and is reminded that the comments provided by AANDC during the original Licence Application (1BH-BLT1414)<sup>2</sup> are still valid.

Sincerely,



---

Thomas Kabloona  
Nunavut Water Board  
Chair

TK/bm/mp

Enclosure: Licence No. **1BH-BLT1515**  
Comments – AANDC

Cc: Kivalliq Distribution List

---

<sup>1</sup> AANDC Comments, submitted to NWB January 8, 2015

<sup>2</sup> AANDC Comments, submitted to NWB April 28, 2014

## TABLE OF CONTENTS

<b>DECISION.....</b>	<b>ii</b>
<b>WATER LICENCE .....</b>	<b>3</b>
<b>PART A: SCOPE, DEFINITIONS AND ENFORCEMENT .....</b>	<b>4</b>
1. Scope.....	4
2. Definitions.....	4
3. Enforcement.....	6
<b>PART B: GENERAL CONDITIONS.....</b>	<b>6</b>
<b>PART C: CONDITIONS APPLYING TO THE PROTECTION OF WATER.....</b>	<b>7</b>
<b>PART D: CONDITIONS APPLYING TO WASTE DISPOSAL .....</b>	<b>8</b>
<b>PART E: CONDITIONS FOR CAMPS, ACCESS INFRASTRUCTURES AND OPERATIONS .....</b>	<b>9</b>
<b>PART F: CONDITIONS APPLYING TO DRILLING OPERATIONS .....</b>	<b>9</b>
<b>PART G: CONDITIONS APPLYING TO MODIFICATIONS .....</b>	<b>9</b>
<b>PART H: CONDITIONS APPLYING TO SPILL CONTINGENCY PLANNING .....</b>	<b>10</b>
<b>PART I: CONDITIONS APPLYING TO ABANDONMENT AND RESTORATION OR TEMPORARY CLOSING.....</b>	<b>10</b>
<b>PART J: CONDITIONS APPLYING TO THE MONITORING PROGRAM.....</b>	<b>11</b>

## DECISION

### LICENCE NUMBER: 1BH-BLT1515

This is the decision of the Nunavut Water Board (NWB) with respect to an application dated October 27, 2014 for a Water Licence made by:

### INUKSHUK CONSTRUCTION LTD.

To allow for the use of water and disposal of waste during installation of a 3,400 m<sup>3</sup> fuel storage tank, and corresponding hydrostatic testing activities, located in the community of Baker Lake within the Kivalliq Region of Nunavut, generally located within the following geographical coordinates:

Project Extents:	NW: Latitude: 64° 18' 53.16" N	Longitude: 95° 59' 44.79" W
	NE: Latitude: 64° 18' 53.14" N	Longitude: 95° 59' 34.87" W
	SE: Latitude: 64° 18' 54.90" N	Longitude: 95° 59' 34.28" W
	SW: Latitude: 64° 18' 55.43" N	Longitude: 95° 59' 42.96" W

### DECISION

After having been satisfied that the application was for a location that was in conformity with the Keewatin Regional Land Use Plan<sup>1</sup> and subject to a 12.4.3 Screening Decision by the Nunavut Impact Review Board<sup>2</sup> in accordance with Article 12 of the *Nunavut Land Claim Agreement (NLCA)*, the NWB decided that the application could proceed through the regulatory process. In accordance with S.55.1 of the *Nunavut Waters and Nunavut Surface Rights Tribunal Act (Act)* and Article 13 of the *NLCA*, public notice of the application was given and interested persons were invited to make representations to the NWB.

After reviewing the submission of the Applicant and the comments provided by AANDC, the NWB, having given due regard to the facts and circumstances, the merits of the submissions made to it and to the purpose, scope and intent of the *NLCA* and of the *Act*, waived the requirement to hold a public hearing, and determined that:

**Licence No. 1BH-BLT1414 be renewed as Licence No. 1BH-BLT1515 subject to the terms and conditions contained therein. (Motion #: 2014-B1-038)**

Signed this 16<sup>th</sup> day of \_\_\_\_\_ January \_\_\_\_\_ at Gjoa Haven, NU.



Thomas Kabloona  
Nunavut Water Board  
Chair

<sup>1</sup> Nunavut planning Commission (NPC) Conformity Determination, dated December 15, 2014.

<sup>2</sup> Nunavut Impact Review Board (NIRB) Screening Decision, dated January 9, 2015.



## NUNAVUT WATER BOARD WATER LICENCE RENEWAL

---

Licence No. 1BH-BLT1515

Pursuant to the *Nunavut Waters and Nunavut Surface Rights Tribunal Act* and the *Agreement Between the Inuit of the Nunavut Settlement Area and Her Majesty the Queen in right of Canada*, the Nunavut Water Board, hereinafter referred to as the Board, hereby grants to

INUKSHUK CONSTRUCTION LTD.

(Licensee)

P.O. BOX 654 RANKIN INLET, NUNAVUT, X0G 0G0

(Mailing Address)

hereinafter called the Licensee, the right to alter, divert or otherwise use water or dispose of waste for a period subject to restrictions and conditions contained within this Licence:

Licence Number/Type: 1BH-BLT1515 TYPE "B"

Water Management Area: BAKER LAKE WATERSHED - 8

Location: PETROLEUM SYSTEMS UPGRADE – BAKER LAKE  
KIVALLIQ REGION, NUNAVUT

Classification: INDUSTRIAL UNDERTAKING

Purpose: DIRECT WATER USE AND DEPOSIT OF WASTE

Quantity of Water use not  
to Exceed: TOTAL WATER USE OF 3,400 CUBIC METRES  
(AT RATE OF LESS THAN 300 CUBIC METRES PER DAY)

Date of Licence Issuance: JANUARY 16, 2015

Expiry of Licence: DECEMBER 31, 2015

This Licence issued and recorded at Gjoa Haven, Nunavut, includes and is subject to the annexed conditions.

**Thomas Kabloona,**  
**Nunavut Water Board**  
**Chair**

## **PART A: SCOPE, DEFINITIONS AND ENFORCEMENT**

### **1. Scope**

This Licence allows for the use of water and the disposal of waste for an industrial undertaking classified as per Schedule 1 of the *Regulations* at the Petroleum Systems Upgrade Project for Baker Lake, located within the community boundaries of the Hamlet of Baker Lake, within the Kivalliq Region, Nunavut.

- a. This Licence is issued subject to the conditions contained herein with respect to the taking of water and the depositing of waste of any type in any waters or in any place under any conditions where such waste or any other waste that results from the deposits of such waste may enter any waters. Whenever new *Regulations* are made or existing *Regulations* are amended by the Governor in Council under the *Nunavut Waters and Nunavut Surface Rights Tribunal Act*, or other statutes imposing more stringent conditions relating to the quantity or type of waste that may be so deposited or under which any such waste may be so deposited, this Licence shall be deemed, upon promulgation of such *Regulations*, to be subject to such requirements; and
- b. Compliance with the terms and conditions of this Licence does not absolve the Licensee from responsibility for compliance with the requirements of all applicable Federal, Territorial and Municipal legislation.

### **2. Definitions**

“**Act**” means the *Nunavut Waters and Nunavut Surface Rights Tribunal Act*;

“**Addendum**” means the supplemental text that is added to a full plan or report usually included at the end of the document and is not intended to require a full resubmission of the revised report;

“**Amendment**” means a change to original terms and conditions of this Licence requiring correction, addition or deletion of specific terms and conditions of the Licence; modifications inconsistent with the terms of the set terms and conditions of the Licence;

“**Appurtenant Undertaking**” means an undertaking in relation to which a use of water or a deposit of waste is permitted by a licence issued by the Board;

“**Board**” means the Nunavut Water Board established under the *Nunavut Land Claims Agreement* and the *Nunavut Waters and Nunavut Surface Rights Tribunal Act*;

“**Effluent**” means treated or untreated liquid waste material that is discharged into the environment from a structure such as a settling pond, landfarm or a treatment plant;

**“Engineer”** means a professional engineer registered to practice in Nunavut in accordance with the *Consolidation of Engineers and Geoscientists Act S. Nu 2008, c.2* and the *Engineering and Geoscience Professions Act S.N.W.T. 2006, c.16 Amended by S.N.W.T. 2009, c.12*;

**“Greywater”** means all liquid wastes from showers, baths, sinks, kitchens and domestic washing facilities, but does not include toilet wastes;

**“High Water Mark”** means the usual or average level to which a body of water rises at its highest point and remains for sufficient time so as to change the characteristics of the land (ref. Department of Fisheries and Oceans Canada, Operational Statement: Mineral Exploration Activities);

**“Inspector”** means an Inspector designated by the Minister under Section 85 (1) of the *Act*;

**“Licensee”** means the holder of this Licence;

**“Modification”** means an alteration to a physical work that introduces a new structure or eliminates an existing structure and does not alter the purpose or function of the work, but does not include an expansion;

**“Nunavut Land Claims Agreement (NLCA)”** means the “*Agreement Between the Inuit of the Nunavut Settlement Area and Her Majesty the Queen in right of Canada*”, including its preamble and schedules, and any amendments to that agreement made pursuant to it;

**“Regulations”** means the *Nunavut Waters Regulations* sor 2013/669 18th April, 2013;

**“Sewage”** means all toilet wastes and greywater;

**“Spill Contingency Plan”** means the Plan entitled “Meliadine Gold Project, Spill Contingency Plan, Agnico-Eagle Mines Limited.” revised February 2014, developed to deal with unforeseen petroleum and hazardous materials events that may occur during the operations conducted under the Licence;

**“Sump”** means an excavation in impermeable soil for the purpose of catching or storing water or waste;

**“Toilet Wastes”** means all human excreta and associated products, but does not include greywater;

**“Waste”** means, as defined in S.4 of the *Act*, any substance that, by itself or in combination with other substances found in water, would have the effect of altering the quality of any water to which the substance is added to an extent that is detrimental to its use by people or by any animal, fish or plant, or any water that would have that effect because of the quantity or concentration of the substances contained in it or because it has been treated or changed, by heat or other means;

**“Water” or “Waters”** means waters as defined in section 4 of the *Act*.

### **3. Enforcement**

- a. Failure to comply with this Licence will be a violation of the *Act*, subjecting the Licensee to the enforcement measures and the penalties provided for in the *Act*;
- b. All inspection and enforcement services regarding this Licence will be provided by Inspectors appointed under the *Act*; and
- c. For the purpose of enforcing this Licence and with respect to the use of water and deposit or discharge of waste by the Licensee, Inspectors appointed under the *Act*, hold all powers, privileges and protections that are conferred upon them by the *Act* or by other applicable law.

## **PART B: GENERAL CONDITIONS**

1. The water use fees, payable to the Receiver General for Canada, shall be sent to the Board annually for the right to the use of water in accordance with Section 12 of the *Regulations*.
2. The Licensee shall file an Annual Report on the Appurtenant Undertaking with the Board no later than March 31<sup>st</sup> of the year following the calendar year being reported, containing the following information:
  - a. A summary report of water use and waste disposal activities;
  - b. A list of unauthorized discharges and a summary of follow-up actions taken;
  - c. A description of all progressive and or final reclamation work undertaken, including photographic records of site conditions before, during and after completion of operations;
  - d. Report all artesian flow occurrences as required under Part F, Item 4;
  - e. A summary of all information requested and results of the Monitoring Program; and
  - f. Any other details on water use or waste disposal requested by the Board by November 1 of the year being reported.



3. The Licensee shall notify the NWB of any changes in operating plans or conditions associated with this project at least thirty (30) days prior to any such change.
4. The Licensee shall install flow meters or other such devices, or implement suitable methods required for the measuring of water volumes as required under Part J, Item 1.
5. The Licensee shall ensure a copy of this Licence is maintained at the site of operations at all times. Any communication with respect to this Licence shall be made in writing to the attention of:
  - (a) **Manager of Licensing:**  
 Nunavut Water Board  
 P.O. Box 119  
 Gjoa Haven, NU X0B 1J0  
 Telephone: (867) 360-6338  
 Fax: (867) 360-6369  
 Email: [licensing@nwb-oen.ca](mailto:licensing@nwb-oen.ca)
  - (b) **Inspector Contact:**  
 Manager of Field Operations, AANDC  
 Nunavut District, Nunavut Region  
 P.O. Box 100  
 Iqaluit, NU X0A 0H0  
 Telephone: (867) 975-4295  
 Fax: (867) 979-6445
6. The Licensee shall submit one paper copy and one electronic copy of all reports, studies, and plans to the Board. Reports or studies submitted to the Board by the Licensee shall include a detailed executive summary in Inuktitut.
7. The Licensee shall ensure that any document(s) or correspondence submitted by the Licensee to the NWB is received and acknowledged by the Manager of Licensing.
8. This Licence is assignable as provided for in Section 44 of the *Act*.

**PART C: CONDITIONS APPLYING TO WATER USE**

1. The Licensee shall obtain all water for the purposes of hydrostatic testing from Baker Lake. The volume of water for the purposes of this Licence shall be less than three-hundred (300) cubic metres per day, for a cumulative total not exceeding three thousand and four hundred (3,400) cubic metres per annum.
2. Streams cannot be used as a water source unless authorized and approved by the Board in writing.

3. If the Licensee requires water in sufficient volume that the source water body may be drawn down the Licensee shall, at least thirty (30) days prior to commencement of use of water, submit to the Board for approval in writing, the following: volume required, hydrological overview of the water body, details of impacts, and proposed mitigation measures.
4. The Licensee shall conduct all activities in such a way as to minimize impacts on surface drainage and the Licensee shall immediately undertake corrective measures in the event of any impacts on surface drainage.
5. The Licensee shall equip all water intake hoses with a screen of an appropriate mesh size to ensure that fish are not entrained and shall withdraw water at a rate such that fish do not become impinged on the screen.
6. The Licensee shall not remove any material from below the ordinary high water mark of any water body unless authorized.
7. The Licensee shall not cause erosion to the banks of any body of water and shall provide necessary controls to prevent such erosion.
8. Sediment and erosion control measures shall be implemented prior to and maintained during the undertaking to prevent entry of sediment into water.

**PART D: CONDITIONS APPLYING TO WASTE DISPOSAL**

1. The Licensee shall implement adequate control measures that prevent vegetation damage, soil erosion, and the entry of sediment into the water body when discharging hydrostatic test water on land and back to Baker Lake.
2. The Licensee shall not deposit any type of waste other than hydrostatic test water under this Licence.
3. The Licensee shall locate areas designated for waste disposal at a minimum distance of thirty-one (31) metres from the ordinary high water mark of any water body such that the quality, quantity or flow of water is not impaired, unless otherwise approved by the Board in writing.
4. The Licensee shall not practice on-site land filling of domestic waste, unless otherwise approved by the Board in writing.
5. The Licensee shall not open burn plastics, wood treated with preservatives, electric wire, Styrofoam, asbestos or painted wood to prevent the deposition of waste materials of incomplete combustion and/or leachate from contaminated ash residual, from impacting any surrounding waters, unless otherwise approved by the Board in writing.

6. The Licensee shall provide to the Board, documented authorization from the community of Baker Lake prior to the backhauling and disposal of any waste.
7. The Licensee shall backhaul and dispose of all hazardous wastes, waste oil, and non-combustible waste generated through the course of the operation at a licensed waste disposal site.
8. The Licensee shall maintain records of all waste backhauled and records of confirmation of proper disposal of backhauled waste. These records shall be made available to an Inspector upon request.
9. Any waters utilized in hydrostatic testing operations shall be treated using a hydrophobic sorbent filter system and solid particle collector prior to discharge.
10. All Effluent being discharged should be managed to control flow rate, ensure energy dissipation, and avoid erosion.

**PART E: CONDITIONS FOR CAMPS, ACCESS INFRASTRUCTURES AND OPERATIONS**

1. No camp activities are authorized under the provisions of this Licence.

**PART F: CONDITIONS APPLYING TO DRILLING OPERATIONS**

1. The Licensee is not authorized to drill under the provisions of this Licence,

**PART G: CONDITIONS APPLYING TO MODIFICATIONS**

1. The Licensee may, without written consent from the Board, carry out Modifications to the Waste Disposal Facilities provided that such Modifications are consistent with the terms of this Licence and the following requirements are met:
  - a. the Licensee has notified the Board in writing of such proposed Modifications at least sixty (60) days prior to beginning the Modifications;
  - b. such Modifications do not place the Licensee in contravention of the Licence or the *Act*;
  - c. such Modifications are consistent with the NIRB Screening Decision;
  - d. the Board has not, during the sixty (60) days following notification of the proposed Modifications, informed the Licensee that review of the proposal will require more than sixty (60) days; and
  - e. the Board has not rejected the proposed Modifications.

2. Modifications for which all of the conditions referred to in Part G, Item 1 have not been met can be carried out only with written approval from the Board.
3. The Licensee shall provide as-built plans and drawings of the Modifications referred to in this Licence, within ninety (90) days of completion of the Modification. These plans and drawings shall be stamped by an Engineer.

**PART H: CONDITIONS APPLYING TO SPILL CONTINGENCY PLANNING**

1. All fuel storage containers, including the generator, shall be equipped with secondary containment. All refueling procedures shall be conducted using secondary containment (such as drip pans etc.).
2. The Licensee shall prevent any chemicals, petroleum products or wastes associated with the project from entering water. All sumps and fuel caches shall be located at a distance of at least thirty one (31) metres from the ordinary high water mark of any adjacent water body and inspected on a regular basis.
3. The Licensee shall conduct any equipment maintenance and servicing in designated areas and shall implement special procedures (such as the use of drip pans) to manage motor fluids and other waste and contain potential spills.
4. The proponent must immediately report any spills where the spill is of an amount equal to or greater than the amount set out in Schedule B of Nunavut's Spill Contingency Planning and Reporting Regulations.
5. If during the term of this Licence, an unauthorized discharge of waste occurs, or if such a discharge is foreseeable, the Licensee shall:
  - a. Report the spill immediately to the 24-Hour Spill Line at (867) 920-8130 and to the Inspector at (867) 975-4295; and
  - b. For each spill occurrence, submit to the Inspector, no later than thirty (30) days after initially reporting the event, a detailed report that will include the amount and type of spilled product, the GPS location of the spill, and the measures taken to contain and clean up the spill site.

**PART I: CONDITIONS APPLYING TO ABANDONMENT AND RESTORATION OR TEMPORARY CLOSING**

1. The Licensee shall complete all restoration work prior to the expiry of this Licence.
2. The Licensee shall carry out progressive reclamation of any components of the project no longer required for the Licensee's operations.

3. The Licensee shall backfill and restore all sumps to the pre-existing natural contours of the land.
4. The Licensee shall remove from the site, all infrastructure and site materials, including all fuel caches, drums, barrels, buildings and contents, docks, water pumps and lines, material and equipment prior to the expiry of this Licence.
5. The Licensee shall remove any culverts and restore the drainage to match the natural channel. Measures shall be implemented to minimize erosion and sedimentation.
6. In order to promote growth of vegetation and the needed microclimate for seed deposition, all disturbed surfaces shall be prepared by ripping, grading, or scarifying the surface to conform to the natural topography.
7. Areas that have been contaminated by hydrocarbons from normal fuel transfer procedures shall be reclaimed to meet objectives as outlined in the Government of Nunavut's Environmental Guideline for Site Remediation, 2010. The use of reclaimed soils for the purpose of back fill or general site grading may be carried out only upon consultation and approval by the Government of Nunavut, Department of Environment and an Inspector.
8. The Licensee shall contour and stabilize all disturbed areas to a pre-disturbed state upon completion of work.

**PART J: CONDITIONS APPLYING TO THE MONITORING PROGRAM**

1. The Licensee shall measure and record, in cubic metres, the daily quantities of water utilized for hydrostatic testing and other purposes.
2. The Licensee shall provide the GPS co-ordinates (in degrees, minutes and seconds of latitude and longitude) of all locations where sources of water are utilized for all purposes.
3. The Licensee shall determine the GPS co-ordinates (in degrees, minutes and seconds of latitude and longitude) of all locations where wastes associated with hydrostatic testing activities are deposited.
4. All sampling, sample preservation and analyses shall be conducted in accordance with methods prescribed in the current edition of *Standard Methods for the Examination of Water and Wastewater*, or by such other methods approved by the Board in writing.
5. All analyses shall be performed in a laboratory accredited according to ISO/IEC Standard 17025. The accreditation shall be current and in good standing.
6. The Licensee shall include in the Annual Report required under Part B, Item 2 all data, monitoring results and information required by this Part.