

Atanguyan Naotomik Okaohen: PIN-B Clifton Point-mi Imakmik Atogeagani laeseoyok Nutaguktikniga Hivunikhamilo Amigiyotinun Havaak

PIN-B Clifton Point hinaanetok Amundsen Gulf-goyum (Beaufort Sea-mi) Nunavumi. Kaninikhak nunagiyaoyun ukoa Paulatuk, Nunateami, 220 kilamitamik ugahiknikaktok hivugaata oalikheani, Kugluktuvlo, Nunavumi 220-kilamitaoyok hivugaata kivalikheani. Inigiyaoyok 1kilamitamik ugahiknikaktok takyum hinaanin. PIN-B akulikhihikni Tulaekakveoyugaloak hanahimayok 1957-mi umikhimavlonilo kimaktaoyok 1963-mi.

Kiklimaktiknigagun havaagiyaoyun inigiyaoyumi 2009-min 2010-mun, katitikhimavlogin ahivaktikhogilo inigiyaoyumin igitaovlotik halumaelgun nunan hunalolikaa, agiptiktaovlotiklo iglukpaen napayulo, algaktaovlotiklo katitigaoyun ikakun aalatkenin kuveogaloanin taemani kiklimaktikhogilo aalat inigiyaoyuni ikakun. Tamaeta aniknagitun ikakun ileogaktaoyun aninagitunik ikakukvikmun (NHWL) hanahimayok iglukpakakvikmi talvuna atoktukhak. NHWL-goyok hanahimayok atoktaovlonilo iglukpakakvikmi akungani 2009-min 2010-mun. NHWL-goyok umikhimayok 2010-mi.

Havakveoyomi okageyaktaeni monagiyaagani haohivik umiktaakan, hivunikhami amigiyun havaagiyaolikhimayok PIN-B-mi August-mi 2011-mi. Atoktuk PIN-B-mi imakmik atogeagani ihulitman May 31-mi 2014-mi. Piyotaoyok umiga tukhiktunmik nutaagugeagani ihoakhaklogolo atoktok imakmik atogeagani laeseoyok hivunikhami amigiyotin atokhimaginageagani iglukpakakvikmi.

Ukoa hulilogagutin ilagiyaen PIN-B-mi Hivunikhami Amigiyutinun Havaam:

- Takukataklogo Amiginiga NHWL-goyum;
- Aolaenaktok Kaagani Imavaloen Amiginigagun NHWL-mi;
 - Ilitogakhan piyaoneakun hitamanin amigiyotinun imiktakviknin iliyaohimayun haneani NHWL-goyum. Ukoa ilitogakhan naonaeyaktaoneakun kanogituniginik halomaelgun imagikniganiklo kanoginigilo naonaeyagaoneakun ukunani aheanin ilitokhaktaoyonin nunanin.
- Nuna Amiginiga, piyageakaktok, kuktokakan imaeyaknigilunen takuyaokpata ilagani taotokniganik
 - ihivgeokhinikmik NHWL-mik;
- Avataoyomik Amiginiga

Hivunikhamik Amigiyotinun Opalogaeyaon atokhimaginakneaktok 25-ni ukeoni pihahuni atuni havaani ukuniga:

- Havaak 1: Ukeoni 1, 3 unalo 5
- Havaak 2: (piyageakakan): Ukeoni 7, 10, 15 unalo 25
- Havaak 3: (piyageakakan): Avataanun 25 ukeon

Havaak 1 amigiyotinun pihimayok PIN-B-mi 2011-mi 2013-milo. Kigulik Havaak 1-mi amigiyotinun atokneakok aoyami 2015-mi. Naonaeyakniga Havaam 1 amigiyotinun naonaepkotin havaagiyaoneakun nugulikan 2015-mi havaami naonaegeagani una Havaak 2 amigiyotinun atokatakkniga ihoakhaktaoneakmagaa ikikligeaklogilunen. Agivalaginkata ihomagiyaoyun haohivikmi, amigiyotin atogoekneagunakhiyun (AMSRP 2009). Ilageagutikhan Havaak 2-mi amigiyotinun atogeakakan

piyotikakan nunami imavalokakniganik amigiyotini ihivgeokniganiklunen haohiveom, havaagiyaoneaktun ukeoni 2017-mi, 2020-mi, 2025-mi 2035-milo. Iniknigani

25-ni ukeoni amigiyotinun havaak, ihivgeoktaoneakok amigenageakakmagaalo huli naonaekneakok (Havaak 3 ilitokhaktaneakok).

Naonaeyaotikhan

AMSRP (Kimagaoyun Aguyaktin Iglukpakakvenik Kiklimakniknigagun Havaohikhak). 2009-mi. Ataotimeoyun II – Naonaeyaotinun Ikayutin Titigakpaleanigin, Okaohik 11 – Hanataakata Amigiyotin, makpiknigani 13. Itkilgit Ukeoktatomilo Havaagoyun Kanatami, Ukeoktatomik Havaagoyunik timeoyok, Halomaektonik Iglukpakakviknik Havaak, March 2009-mi.