



CY-2050-FA "D"

Designed for Petroleum, Mining, and Lumber Industries

- **Built In Safety Features**
- **Readily Transportable**
- **Economical Operation**
- **Clean Burning**

Capacity

1.4 m³, 90 kg per hour.
Type No. 1, 2, & 3 waste.

Power Requirements

115 volts 60 cycle single phase.

Stack

Stainless Steel

- 14 gauge.
- 38cm diameter.
- 3m high.
- c/w stainless steel spark arrester.
- a hinged base plate for moving.

Casing

12 gauge steel.
Lining: high heat duty castable refractory over high temperature insulation.

Hearth

Refractory hearth over 6.35mm steel base.

Doors

6.35-cm steel plate c/w heavy-duty blade latch.

Charging: - 61cm-x 71cm clear opening
- Refractory lined over steel plate.

Ash: - 61cm x 40cm clear opening
- Refractory lined over steel plate

Air Supply

Forced air fan c/w duct to primary air jets and to secondary over-fire air jets.

Timers

Cycle timer interconnected to air supply fan and gun type burner enclosed in burner housing.

Burners

650,000 BTU gun type primary burner.
Gun burner enclosed in protective plate steel housing.
450,000 BTU in secondary chamber.

Fuel Supply: Oil Fired Unit Only

1350-liter fuel storage tank c/w filter and flexible hose type connection.

Transporter

Incinerator and fuel storage mounted on skid type frame 4.27m long x 1.83m wide. Height: 3.2m tall, with stack folded. Constructed of W150 I-Beam c/w bumper posts.

Weight

5000 kg.

Options

- * LPG Fired burner.
- * Diesel fired burner.
- * 2.3m Electric power cord.
- * Stack winch.
- * Cold climate assembly.

MANUFACTURED BY:

DISTRIBUTED BY:



Environmental Services Inc.

20204 – 110 Avenue, Edmonton, AB Canada T5S 1X8

Phone: (780) 447-5052 Fax: (780) 447-4912

E-MAIL info@westlandenvironmental.com