

Inspection Report (Airstrip landfill)• Page 2 of 2

Checklist Item	Present Yes / No	Location (Describe relative to existing monuments / features and relative to landfill / area design i.e. surface, berms, toe)	Length	Width	Depth	Extent relative to area extent of Landfill Area (%)	Description	Photographic Records Focal Length Location, view point & direction Feature of note Scale	Additional Comments Preliminary Stability Assessment
Settlement	Yes								
Erosion	Yes	Downstream of landfill, North East	100m	1-3m	2-30cm		Drainage path (North-East corner of landfill) flows into sandy material causing erosion. Drainage towards Baffin Bay.	No 5-2 (down stream of landfill, toward North-East)); No 5-5 (opposite of 5-2)	Water flows into Baffin Bay
		Downstream of landfill, East	20m	1-3m	20-50cm		Erosion down stream (East) of landfill	No 5-10 (toe of eastern edge of landfill)	No stains observed in this erosion/channel
Frost action	No								
Animal Burrows	No								
Vegetation	Yes						Lichen, moss	No 5-6 (Next to F4-8)	No impact on vegetation
Staining	Yes	Downstream of landfill, North East	100m	1-3m	0.1m		Large stains observed in erosion channels. Water flows directly into Baffin Bay	No 5-2 (Down stream of landfill, toward North-East); No 5-5 (opposite of 5-2)	Stained water flows into Baffin Bay
		South-West corner of landfill	40m	0.25m			Pooling and seepage points observed at the South West corner of the landfill	No 5-3 (South-West corner of the landfill)	Minor stains observed near pooling area
Vegetation Stress	No							No 5-1 (Down stream of airstrip landfill) facing South	No vegetation stress observed east of landfill (down stream)
Seepage Points	Yes	South-West corner of landfill	40m	0.25m	0.1m		Pooling and seepage points observed at the South West corner of the landfill	No 5-3 (South-West corner of the landfill)	Minor stains observed near pooling area
Debris Exposed	Yes								
Presence Condition of Monitoring	No								
Other features of note		Beach area, facing SSR fuel tanks					No erosion or stains or pooling near beach area	No 5-4 (facing SSR tanks at the beach area)	No stains or erosion
		Soil sample at F4-10						No 5-7 (At F4-10 sampling location)	No stains or erosion
		Soil sample at F4-9						No 5-8 (At F4-9 sampling location)	No stains or erosion

		Soil sample at F4-25						No 5-9 (At F4-25 sampling location)	
--	--	----------------------	--	--	--	--	--	--	--