

File Name: FOX-M (3.6)

UMA Engineering Ltd.
2540 Kensington Road NW
Calgary, Alberta T2N 3S3
T 403.270.9200 F 403.270.0399 www.uma.aecom.com

January 31, 2007

Phyllis Beaulieu Manager of Licensing Nunavut Impact Review Board P.O. Box 119 Gjoa Haven NU, X0B 1J0

Dear Phyllis:

Re: Amendment to Water Use License 1BR-HAL0308

UMA Engineering Ltd. is submitting the following amendment for Water Use License 1BR-HAL0308 to include additional clean up work at the FOX-M, Hall Beach DEW Line site. The amendment request is being submitted on behalf of Defence Construction Canada and the Department of National Defence.

We trust the information provided is sufficient for you to process the amendment. Please feel free to contact the undersigned if you have any questions or comments.

Sincerely,

UMA Engineering Ltd.

Eva Schulz, P.Ag. Environmental Scientist

Eva.Schulz@uma.aecom.com

EMS

Encl. Amendment Application Form and NIRB Summary

cc: Nahed Farah, DCC



P.O. Box 119 GJOA HAVEN, NU XOB 1J0 TEL: (867) 360-6338 FAX: (867) 360-6369 KNK5 wmoEp5 vtmpq NUNAVUT IMALIRIYIN KATIMAYINGI NUNAVUT WATER BOARD OFFICE DES EAUX DU NUNAVUT

WATER LICENCE APPLICATION FORM

Application for: (check one)	
☐ New ☐ Renewal ☐ Amend	lment
LICENCE NO: (for NWB use only)	
1. NAME AND MAILING ADDRESS OF APPLICANT/LICENSEE	2. ADDRESS OF CORPORATE OFFICE IN CANADA (if applicable)
Nahed Farah, P.Eng Associate Project Manager Defence Construction Canada Ltd. Constitution Square, Suite 1720 350 Albert Street Ottawa, Ontario K1A 0K3	Phone: Fax: e-mail:
Phone: 613-998-7917 Fax: 613-998-0468 e-mail: Nahed.Farah@dcc-cdc.gc.ca	
as administered by: Eva Schulz, P.Ag., Environmental Scientist 2540 Kensington Road NW UMA Engineering Ltd. Calgary, Alberta T2N 3S3	
Phone: <u>403-270-9220</u> Fax: <u>403-270-0399</u> e-mail: <u>Eva.Schulz@uma.aecom.com</u>	
3. LOCATION OF UNDERTAKING (describe and components of the Undertaking)	d attach a topographical map, indicating the main
Latitude: (68°45' "N) Longitude: (81°11' NTS Map Sheet No. <u>47A</u> Scale: <u>1:50,000</u>	"W)
4. DESCRIPTION OF UNDERTAKING (attach p The purpose of the project is to clean up additional buried d	
5. TYPE OF PRIMARY UNDERTAKING (A sup application for undertakings listed in "bold")	plementary questionnaire <u>must</u> be submitted with the
☐ Industrial ☐ Mining and Milling(includes exploration/drill ☐ Municipal (includes camps/lodges)	Agricultural ing) Conservation Recreational

Power	Miscellaneous (describe below):
Additional buried debris clean up.	
	st Territories Waters Regulations for Description of Undertakings
6. WATER USE	
☐ To obtain water ☐ To cross a watercourse ☐ To modify the bed or bar	Flood control To divert a watercourse To alter the flow of, or store, water
Other (describe): comple	te additional clean up work.
7. QUANTITY OF WATER quality to be returned to sour	INVOLVED (cubic metres per day including both quantity to be used and rce)
Water use ☐ 100m³/day or le ☐ Greater than 100 drilling, etc.) Same as current license.	ons of the contract of the con
Water returned to source $\underline{0}$ m ³ /day	
8. WASTE (for each type of w treatment and disposal, etc.)	vaste describe: composition, quantity (cubic metres per day), methods of
Sewage Solid Waste Hazardous Bulky Items/Scrap Metal	☐ Waste oil ☐ Greywater ☐ Sludges ☐ Other describe):
Same as under surrent licens	se.
9. OTHER PERSONS OR PI address and location; attach	ROPERTIES AFFECTED BY THIS UNDERTAKING (give name, mailing if necessary)
Land Use Permit DIAND	Yes No If no, date expected
Regional Inuit Association	Yes No If no, date expected
Commissioner	Yes No If no, date expected
	MENTAL IMPACTS OF UNDERTAKING AND PROPOSED ES (direct, indirect, cumulative impacts, etc.)
NIRB Screening	Yes No If no, date expected

11.	INUIT WATER RI	IGHTS		
	Will the project or activity substantially affect the quality, quantity, or flow of water flowing through Inuit Owned Lands and the rights of Inuit under Article 20 of the Nunavut Land Claims Agreement?			
ľ	N/A			
	compensation for any	ant entered into an agreement with ty loss or damage that may be caused will compensation be determined?		
N/A				
12.	CONTRACTORS A	AND SUB-CONTRACTORS (nam	ne, address and functions)	
		e of this work has not yet been tendend sub-contractors are not available		ne names, addresses and
13. This is a		TAKEN TO DATE (list and attach ental clean up, which was started in		
14.		G DOCUMENTS <u>MUST</u> BE INCI ROCESS TO BEGIN	LUDED WITH THE APPLIC	CATION FOR THE
Supplen	nentary Questionnaire	(where applicable: see section 5)	☐ Yes ⊠ No If no, date	expected
Inuktitu	t and/or Inuinnaqtun/F	English Summary of Project	Yes No If no, date	expected
Applica	tion fee of \$30.00 (Pa	yee Receiver General for Canada)	☐ Yes ☐ No If no, date	expected
	Jse fee of \$30.00 (unle for Canada)	ess otherwise indicated in Section 9	of the NWT Waters Regulation	ns; Payee Receiver
General	101 Canada)		☐ Yes ☐ No If no, date	e expected
15.		SCHEDULE (unless otherwise inc	dicated, the NWB will conside	er the application for
	a five (5) year term)	one year or less (or)	☐ Multi Year	
		Start Date: June 1, 2007Comp	pletion Date: <u>September 30, 20</u>	<u>)07</u>
E	Eva Schulz	Environmental Scientist	ha al	January 31, 2007
Na	ame (Print)	Title (Print)	Signature	Date
For Nun	navut Water Board offic	ce use only		
APPLIC	CATION FEE	Amount: \$ Pay ID No.	:	
WATE	R USE DEPOSIT	Amount: \$ Pay ID No.	:	



SCREENING PART 1 FORM PROJECT PROPOSAL SUMMARY

For more information about the Nunavut Impact Review Board (NIRB) please visit our web site http://nirb.nunavut.ca/ or to access NIRB documents, project screenings, and project reviews please visit the Nunavut Impact Review Board ftp site http://ftp.nunavut.ca/nirb.

IMPORTANT

Please be advised that your application will not be processed until the following sections 1 - 6 are completed in full in English and Inuktitut (+ Inuinnaqtun, if in the Kitikmeot). Translated versions of this form in Inuktitut and Inuinnaqtun are available from NIRB's ftp site at http://ftp.nunavut.ca/nirb/

1. a Plea rela	A) Project Number ase indicate if applicant has submitted any previous appliated to this project proposal? es, please indicate the previous NIRB project number(s): arding an on-going project.	, ,	<u></u>
1. k	o) Project Name Additional Clean Up at the FOX-M	, Hall Beac	ch DEW Line Site
2.	Applicant's full name and mailing address: Nahed Farah, P.Eng Constitution Square, Suite 1720 350 Albert Street Ottawa, ON K1A 0K3	Fax: Phone: Email:	613-998-0468 613-998-7917 Nahed.Farah@dcc-cdc.gc.ca
3.	Primary contact's full name and mailing address: Eva Schulz, P.Ag. 2540 Kensington Road NW Calgary, AB T2N 3S3	_ Fax: _ Phone: _ Email:	403-270-0399 403-270-9200 eva.schulz@uma.aecom.com



4.	Secondary contact's full name and mailing address: N/A	Fax: Phone: Email:
	CTION 2: AUTHORIZATION NEEDED ndicate all authorizations associated with the project	proposal:
X	Regional Inuit Association (RIA) Nunavut Water Board (NWB) Nunavut Planning Commission (NPC) Department of Indian And Northern Development (DIAND Department of Fisheries and Oceans (DFO) Community Government & Services (CG&S) Nunavut Research Institute (NRI) Hamlet Canadian Launch Safety (CLS) Environment Canada (EC) Government of Nunavut (GN) Department of National Defense (DND) Department of Culture, Language, Elders, and Youths (C Parks Canada (PC) Other (please specify):	LEY)
2.	List the <u>active</u> permits, licences, or other rights relate: INAC Land Use Permit (N2005X0041): expiry GN Quarry Permit (04-610-001): expiry 30Ju NWB Water Use License (NWB5HAL0308):	/ 22Jan08 n07



SECTION 3: PROJECT PROPOSAL DESCRIPTION

Indicate the type of project proposal: Exploration (geophysical ground, geophysical air, drilling Advanced Exploration/ Bulk Sampling Mine Development All Weather Roads and Trails Winter Roads and Trails DEW Line Clean up Off-Shore Infrastructure Pit and/or Quarry Other:	ng)
2. Indicate the activities related to the project	oroposal:
Drilling other than geoscientific	X Quarrying
Offshore structure	All season road
X Airport/ landing strip	Winter road
Camp	X Access road
Fuel storage	Road modification
Solid waste disposal	Cabins
X Hazardous waste storage or disposal	Sewage or grey water disposal
Research	Blasting
Abandonment and Restoration	Harvesting
Burning	Burying
Construction	Channeling
Cut and/or Fill	Removal of vegetation
Dam/ Impoundment (construction/ abandonment/ ren modification)	
X Drainage Alteration	X Excavation
Chemical Storage	Ecological survey
Explosives Storage	Geoscientific sampling by trenching
Geoscientific sampling by diamond drilling	Geoscientific sampling by borehole core
Geoscientific sampling by soil sampling	Hydrological testing
River/ stream/ lake crossing or work/ bridge	X Site restoration (fertilization/ grubbing/ scarification/
V Soil testing	spraying/ recontouring) X Soil disposal/ Soil storage
X Soil testing Tunneling	
runneling	Other (please specify):
3. Personnel Total No. of personnel 55 on site = (A)	Total No. of person days = (A) x No. days on site (55 X 30) per month for 2 months



4. Timing Period of operation:	June 2007	to	October 31, 2007
Proposed term of permit:	same	to	Same
Please outline the phases of and scheduling of each phase		ction/ operation/ d	ecommissioning) including the timing
The additional clean up wor See Section 8 of this docume			complete, beginning in mid-June, 2007.
5. Region (check all that apply): X Baffin K	: ivalliq	eot	Transboundary:
6. Land Status (check all that a		face lands	Inuit Owned Sub-Surface Lands
7. Co-ordinates: Min Lat (degree/minute) Max Lat (degree/minute)	68°45' 81°11'	Min Long (de	· · · · · · · · · · · · · · · · · · ·
, •	Hall Lake he project are attached (1:50		<u></u>
If the project proposal include Min Lat (degree/minute) Max Lat (degree/minute)	es a camp , please provide th	ne coordinates Min Long (de Max Long (de	gree/minute)
The camp is located within th	ne Hamlet of Hall Beach		
If different from above for the NTS Map Sheet No: Please ensure that maps of t available from Natural Resou	he camp are attached (1:50,	000 if availab	le, 1:250, 000 Mandatory)

8. Non-Technical Project Proposal Summary

Please include a non-technical description of the project proposal, no more than 500 words, in English and Inuktitut (+Inuinnaqtun, if in the Kitikmeot). The project description should outline the following:

- The project activities, their necessity and duration;
- Method of transportation;
- Any structures that will be erected (permanent/ temporary);
- Alternatives considered; and
- Long-term developments, the projected outcome of the development for the area and its timeline.



In 2003, UMA Engineering Ltd. submitted a Project Description and Environmental Screening Report for the Clean Up of the FOX-M, Hall Beach DEW Line Site (2003 Project Description) on behalf of Defence Construction Canada and the Department of National Defence. The Nunavut Impact Review Board evaluated the submission and approved the project in March 2003. Subsequent to NIRB approval, a land use permit, quarry permit and water use license were obtained for the project. In addition, the project was reviewed and approval by the Canadian Environmental Assessment Agency.

Construction/clean up work began at the site in 2004 and is currently on-going. During the construction activities at the site, an additional area containing buried materials and contaminated soils was discovered outside of the original project area and outside of the DND reserve boundary in the West Communications Area (WCA). An investigation of the area was conducted and surface debris, contaminated soils and buried materials were identified.

The project description is being amended to include the clean up of the WCA, including:

- The excavation, transport, and disposal of soil from two contaminated areas in the WCA.
- The completion of all work associated with the excavation of six buried debris areas in the WCA.
- The completion of surface debris removal from the WCA and disposal of the debris in the Non-Hazardous Waste Landfill.
- The demolition and/or regrade of several concrete tower bases and anchor bases in the WCA.

The specific work components associated with the identified clean up requirements are described in the following sections.

Contaminated Soil Removal: Contaminated soils removal will be completed, including supply and placement of backfill, as shown in the areas delineated on the drawings. The disposal requirements for the excavated soils are outlined in Section 3.4 of the 2003 Project Description.

Surface Debris Removal: Removal and disposal of surface debris will be completed as delineated on the attached drawings. The estimated volume of surface debris is 250 cubic metres. It was noted that some surface debris may contain asbestos. Proper PPE should be worn during debris handling. In addition, there appears to be some debris that could contain PCBs in the form of fluorescent light ballasts, which should be handled according to Section 4.5.1 of the 2003 Project Description. Site debris is to be disposed of as per Section 4.4 of the 2003 Project Description.

Buried Debris Excavation: The buried debris located in close proximity to water bodies will be excavated. Primary landfill excavation includes excavation of all materials to the lateral and vertical extents of the designated landfill area. The depth of the primary landfill excavation extends to competent bedrock or where debris is no longer visible. Secondary landfill excavation includes the excavation of the landfill area beyond the primary landfill excavation limits.

Buried debris excavation at the WCA of the FOX-M site, which is estimated at 8700 cubic metres, will include the following:

Installation/construction of erosion, drainage and sediment control, as required.



- Development of the landfill survey grid.
- Excavation of all waste materials from the landfill area.
- Development, operation and removal of a materials processing area (MPA).

Once excavated, the materials are transported to the MPA for sorting into hazardous and non-hazardous components. Excavated soils are sorted into the contaminated soil classifications (Section 3.4 in the 2003 Project Description), based on the results of sampling and analysis.

The MPA will be developed for the processing of excavated soils. The processing area shall be located a minimum of 30 metres away from any archaeological site or water body, on ice-poor, well-drained soil and as close to the location of work as is practical. Movement of vehicles and equipment between the processing area and the work site is to be minimized to prevent the spread of potentially contaminated materials along the road.

Once the debris and contaminated soils have been removed and all confirmatory samples have been collected and analysed, the area is to be regraded with clean soil/gravel and restored to natural drainage patterns and topography, as much as practical. Drainage controls such as diversion ditches and sediment filters are to be provided, as required, to prevent runoff from reaching water bodies during closure, remediation and construction of landfills. The debris will be collected, sorted into hazardous and non-hazardous materials and disposed of accordingly.

During the excavation, the slope stability is to be inspected and maintained. When excavating in the vicinity of a drainage course or a body of water, silt fences, floating silt curtains and/or containment berms are to be constructed to prevent the release of sediment or deleterious substances into the water.

Any ponded water in the excavation will be dewatered. Prior to dewatering, a sample will be collected and analysed to ensure it meets the discharge criteria (see **Contact Water** below). Any meltwater/groundwater/leachate will be collected at the low point of the excavation. The water will be allowed to settle prior to sampling and testing of the water.

During excavation, a volatile organic compound (VOC) instrument capable of measuring in parts per million (ppm) and Lower Explosive Limit (% LEL) will be used to continuously measure the concentrations of VOC during landfill excavation operations, and prior to the removal of debris from the landfill.

A full range of clean up and protective equipment will be maintained at the site in the event of a spill. The clean up equipment is to include booms (sorbent and containment), sorbents for clean up, fire extinguishers for A-B-C files, overpacks for barrels and contaminated soils, pumps, hand shovels, picks, and containment barriers, such as liner material. Personal protective equipment is to include clothing protective suits, respirators, etc. to comply with potential emergency conditions and in accordance with NIOSH guidelines.

At the conclusion of the excavation, all sediment, erosion and drainage control measures will be removed from the worksite.



Demolition: Demolition includes the removal and disposal of 20 concrete tower foundations in the Non-Hazardous Waste Landfill. Demolition is to be completed as per Section 4.6 of the 2003 Project Description.

Borrow Pit Development: In order to fulfill the backfill and grading requirements for the clean up of the WCA, additional borrow material is required. It is estimated 5000 cubic metres of gravel will be extracted from the existing, permitted borrow area.

Environmental protection measures will be implemented for the purpose of minimizing the impact of borrowing activities on surface patterns, water quality, soil erosion, and in some cases, fish or wildlife. All terms and conditions of the Quarry Permit are to be complied with, including the recontouring/reclamation of the borrow area and site clean up prior to site abandonment.

The borrow areas will be located at least 30 metres from the nearest water body providing potential fish habitat and other sensitive resources. In consultation with the DCC Contract Coordinator, a 30 m buffer zone is to be marked out prior to commencement of gravel quarrying operations. Organic overburden, if present, shall be stripped and stockpiled separately for use in restoring the borrow area. Following excavation, the area is to be recontoured to restore natural drainage patterns and overburden is to be worked into the recontoured area to prevent erosion. Contour the area to blend into the surrounding topography as much as practical. Drainage and runoff control is to be provided using diversion ditches and sediment filters, as required, to prevent sediment laden runoff from reaching water bodies.

During aggregate extraction, vehicle and equipment operations will be controlled in areas adjacent to the borrow pit to minimize the extent of the disturbance. Aggregate is to be stockpiled on-ice-poor, well drained ground such that surface drainage is not impeded. The stockpile is to be located in an area that is a minimum of 30 m from archaeological resources, water bodies, and other sensitive resources. If archaeological features or artifacts are encountered during borrow pit operations, the DCC Contract Coordinator is to be notified, the area of the find avoided, and activities in other areas of the pit restricted until further instruction is received.

Road Construction and Maintenance: There is an existing road to the WCA, however, it will require upgrading such as fill placement and regrading. Emphasis on the preservation of the permafrost regime, vegetation patterns, existing surface drainage patterns, water quality and stream flows shall be maintained. Establishment of new roads off-site is subject to the terms of the land use permit and the approval of the DCC Contract Coordinator. Roads shall not be sited within 30 m of any ecologically sensitive areas. Ice-rich soils, especially peatlands, are also to be avoided during road maintenance. The road-bed shall be prepared with a sufficient thickness of fill to prevent terrain damage. Culverts, if required, shall be installed to maintain natural cross-drainage and prevent ponding. Any culverts installed shall be removed from the roads and drainage restored at the end of the clean up operations. Access roads shall be monitored for signs of erosion and remedial action is to be taken only where necessary. Dust suppression, if required, is to be maintained with water or calcium chloride only.

Potential Environmental Impacts: The WCA is located approximately 300 metres west of the water supply lake and water reservoir for the Hamlet of Hall Beach. The following outlines the potential environmental impacts to the water quality which are identified in association with the clean up of the WCA.



Activity	Description of Impact	Significance
Landfill Closure	 Potential migration of leachate, release of contaminated soils during closure of the landfills may degrade water quality, if not completed according to the specifications. 	Not Significant if work is completed according to design.
	 Closure of the WCA landfills will reduce the risk of negative impact on water quality. The closure of the landfills may potentially disrupt drainage at the 	High - positive Low – temporary.
	site.	Low tomporary.
Contaminated Soil Disposal/Hazardous Materials Removal	The removal of contaminated soil and hazardous materials from the environment will reduce the risk of contamination of surface water.	High - positive
Removal and Transport of Hazardous Material, Fuel and Contaminated Soil	The potential exists for accidental release of hazardous materials, contaminated soil, and/or fuels. An accidental release could impact water quality.	Not Significant if work is completed according to design and in compliance with spill response plan.

Contact Water: The FOX-M site has little elevation, and as such, seepage of water into excavations if often a common occurrence. Because of the presence of contaminated soils in the excavations, there is potential for the contact water to be impacted. In order to reduce and/or prevent the accumulation of contact water from the excavations, the excavations are to be left open as minimal amount of time as possible. All contact water is to be tested prior to being released to the ground surface at a location that is a minimum of 30 metres from natural drainage courses and 100 metres from fish bearing waters. The criteria for the wastewater are provided in the following table:

Parameter	Monitoring Plan Criteria	NWT Guidelines (1992)	Nunavut Effluent Guidelines (2000)	Chlorobiphenyls Regulations (CEPA 1991)
pН	6-9 pH units	N.G.	N.G.	N.G.
Oil & Grease	5	None Visible	N.G.	N.G.
Arsenic (total)	0.05	0.05	0.5	N.G.
Cadmium	0.005	0.005	0.0017	N.G.
(dissolved)				
Chromium (total)	0.1	0.1	0.89 (trivalent)	N.G.
Cobalt (dissolved)	0.1	0.1	N.G.	N.G.
Copper (dissolved)	0.2	0.2	N.G.	N.G.



Lead (total)	0.05	0.05	N.G.	N.G.
Mercury (total)	0.0006	0.0006	0.01	N.G.
Nickel (dissolved)	0.3	0.3	N.G.	N.G.
PCB (total)	1	N.G.	N.G.	5*
Zinc (total)	0.5	0.5	3	N.G.

All units are in mg/L unless otherwise stated.

Any contact water which does not meet these guidelines is to be treated so that it does meet the guidelines. If that is not possible/feasible, it shall be treated as hazardous material.

SECTION 4: MATERIAL USE

1. List equipment (including drills, pumps, aircrafts, etc.): This is a typical equipment list and the type and quantity may vary slightly.

The equipment to be used is the same as listed in the 2003 Project Description.

2. Detail fuel and hazardous material use:

Fuel details are the same as in the 2003 Project Description

SECTION 5: WASTE DISPOSAL AND TREATMENT FACILITIES

1. List the types of waste:

II LIGI IIIO IJ POG OI WAGI	v.		
Type of waste	Projected amount	Method of Disposal	Additional treatment
	generated		procedures
Buried	8700 m ³	On-site landfills	Off-site disposal, if
debris/contaminated soil			material is hazardous
Concrete blocks	10	On-site landfills	n/a

SECTION 6: COMMUNITY INVOLVEMENT & REGIONAL BENEFITS


 List the community 	representatives that have be	een contacted and pro	vide the minutes of t	the
meetings if available:				
n/a				

Applicant: Eva Schulz for Nahed Farah

Gra Sh	Environmental Scientist	January 31, 2007
Signature	Title	Date

N.G. - No Guidelines

^{*} In respect of application to a road surface.





Défense nationale_____

DEW LINE CLEAN UP PROJECT


DRAWING INDEX				
DRAWING No.	TITLE	DRAWING No.	TITLE	
SITING		SITING	•	
H-H11/1-9101-101	OVERALL SITE PLAN	H-H11/1-9101-118	EAST BEACH LANDFILL CROSS — SECTIONS	
H-H11/1-9101-102	PROJECT LAYOUT	H-H11/1-9101-119	MISCELLANEOUS DETAILS	
H-H11/1-9101-103	STATION AREA NORTH SITE PLAN	H-H11/1-9101-120	MISCELLANEOUS DETAILS	
H-H11/1-9101-104	STATION AREA EAST SITE PLAN	H-H11/1-9101-121	WEST COMMUNICATIONS AREA SITE PLAN	
H-H11/1-9101-105	STATION AREA WEST SITE PLAN	H-H11/1-9101-122	WEST COMMUNICATIONS AREA CROSS SECTIONS	
H-H11/1-9101-106	EAST BEACH AREA SITE PLAN	STRUCTURAL		
H-H11/1-9101-107	SEWAGE LAGOON AREA SITE PLAN	H-H11/1-9101-201	MAIN CAMP AREA DEMOLITION SITE PLAN	
H-H11/1-9101-108	WEST BEACH LANDFILL AREA SITE PLAN	H-H11/1-9101-202	AIRSTRIP, NORTH BEACH AND COMMUNICATIONS AREAS DEMOLITION SITE PLANS	
H-H11/1-9101-109	WEST BEACH BORROW AREA SITE PLAN	H-H11/1-9101-203	ARMCO DORMITORY PLAN, SECTIONS AND ELEVATION	
HH11/1-9101-110	NORTH BEACH AREA SITE PLAN	H-H11/1-9101-204	WAREHOUSE B13A PLAN AND SECTION	
H-H11/1-9101-111	AIRSTRIP AREA SITE PLAN	H-H11/1-9101-205	WAREHOUSE B13B PLAN AND SECTION	
H-H11/1-9101-112	SURFACE AND SUBMERGED DEBRIS AREAS	H-H11/1-9101-206	CURLING RINK PLAN AND ELEVATION	
H-H11/1-9101-113	LANDFILL AREAS OVERALL LAYOUT	H-H11/1-9101-207	FUEL TANKS PLAN AND ELEVATIONS	
H-H11/1-9101-114	NON-HAZARDOUS WASTE LANDFILL CROSS - SECTIONS AND DETAIL	H-H11/1-9101-208	POL PUMPHOUSE PLANS AND ELEVATIONS	
H-H11/1-9101-115	TIER II LANDFILL CROSS — SECTIONS	© COPYRIGHT		
H-H11/1-9101-116	EAST BEACH LANDFILL OVERALL LAYOUT	(©) COPYRIGHT HER MAJESTY THE QUEEN IN RIGHT OF CANADA 2006, AS REPRESENTED BY THE MINISTER OF NATIONAL DEFENCE.		
H-H11/1-9101-117	EAST BEACH LANDFILL EXCAVATION			



FOX-M HALL BEACH CHANGE REQUEST No. XX







National Défense

General Notes:

- ALL ELEVATIONS ARE REFERENCED TO CONTROL MONUMENTS.
- 2. ARCHAEOLOGICAL FEATURES LOCATED AS PER ENVIRONMENTAL CLEAN UP STUDY OF 21 DEW LINE SITES IN CANADA, VOL. 18, UMA 1991.
- 3. HORIZONTAL CONTROL REFERENCED TO SURVEY CONTROL MONUMENTS.
- 4. ALL DIMENSIONS ARE IN METRES UNLESS NOTED OTHERWISE.
- 5. ALL LONG RANGE RADAR (LRR)
 FACILITIES ARE CURRENTLY OPERATIONAL
 AND ARE NOT TO BE DISTURBED.
 SEE DWGS. H-H17/1-9101-201 AND 202
 FOR ADDITIONAL DETAILS.

Legend:

□ TBMXX TEMPORARY BENCHMARK

BODY OF WATER

--- PROPERTY LINE

1	06-05-01	CHANGE REQUEST	No. XX	GRH
No.	DATE	REVISION	REVISION	APPR

PERMIT NUMBER P 151 SGE ACRES LIMITED

uma SGE Acres Ltd.

PROJECT - PROJ

FOX-M HALL BEACH

DEW LINE CLEAN UP

© COPYRIGHT


HER MAJESTY THE QUEEN IN RIGHT OF CANADA 2006, AS REPRESENTED BY THE MINISTER OF NATIONAL DEFENCE. TRADE - METIER SITING


SUBJECT - SUJET


PROJECT LAYOUT


PRODUCTION	CONCURRENCE - ASSENTIMENT	
DESIGNED ETUDIE RAW/GRH		DES OFF AGENT CONCEPT
DRAWN OPB/RGM DESSINE	SECT HD CHEF SECT	
CHECKED RRM VERIFIE RRM		DES MGR GEST CONCEPT
COORDINATION SMS	REVIEWED - REVU	
DWG. NO DESSIN NO.		


Canadä














National Défense Defence nationale

Headquarters Quartier général

General Notes:

- 1. SIDE SLOPES ON ALL PRIMARY LANDFILL EXCAVATION AREAS ARE TO BE NO STEEPER THAN 1H:1V.
- AVERAGE DEPTH OF PRIMARY LANDFILL EXCAVATION = 1.5m.

Legend:

	1	06-05-01	CHANGE REQUEST	No. XX	GRH
No. DATE REVISION REVISION	No.	DATE	REVISION	REVISION	APPR.

PERMIT NUMBER P 151 SGE ACRES LIMITED

DATE 2006-05-01

uma SGE Acres Ltd. SCALE - ECHELLE 20 10

PROJECT - PROJET

FOX-M HALL BEACH

DEW LINE CLEAN UP


© COPYRIGHT
HER MAJESTY THE QUEEN IN RIGHT OF
CANADA 2006, AS REPRESENTED BY THE
MINISTER OF NATIONAL DEFENCE.

TRADE - METIER SITING SUBJECT - SUJET

WEST COMMUNICATIONS AREA CROSS - SECTIONS

PRODUCTION	CONCURRENCE - ASSENTIMENT	
DESIGNED ETUDIE RAW/GRH		DES OFF AGENT CONCEPT
DRAWN DESSINE OPB/RGM		SECT HD CHEF SECT
CHECKED VERIFIE RRM		DES MGR GEST CONCEPT
COORDINATION SMS	REVIEWED - REVU	
DWG, NO. – DESSIN NO. H-H11/1-9101-122		

Canadä



- LANDFILL EXCAVATION AREAS ARE TO BE NO STEEPER THAN
- AVERAGE DEPTH OF PRIMARY LANDFILL EXCAVATION = 1.5m.
- FM-WCA-CO4 & FM-WCA-CO5 IS ANTICIPATED TO BE 0.3 m. FINAL EXCAVATION DEPTH WILL

AGENT CONCEPT

Canadä