

**Proposed Monitoring Program – Licence No.: NWB5HAL0308 (FOX-M, Hall Beach)**  
**For Submission to the Nunavut Water Board**

Description	Location	Station Number <sup>1</sup>	Frequency	Analytical Requirements	Maximum Allowable Concentration for Discharge to Receiving Water(s)
Effluent Monitoring <sup>2</sup> (at the point of discharge to the receiving water)	Sewage Disposal Facility	FM-1	Twice. One time 30 days after sewage disposal facility establishment and one time prior to discharge at the end of the construction season.	Oil & Grease Total Suspended Solids Biological Oxygen Demand Faecal Coliforms pH	No visible sheen 180 mg/L 120 mg/L 10,000 CFU/dL 6-9 pH units

**NOTE 1:** GPS coordinates of the Station Numbers will be provided once the contractor is on-site and is able to provide this survey information.

**NOTE 2:** Sampling of the sewage effluent would only be conducted if the Hamlet lagoon is not used by the contractor , and a separate on-site sewage lagoon is constructed.