


P.O. Box 119 Gjoa Haven, NU X0B 1J0

Tel: (867) 360-6338 Fax: (867) 360-6369

NUNAVUT WATER BOARD NUNAVUT IMALIRIYIN KATIMAYINGI

<u>Supplemental Technical Information Required for Water Crossings (linear/bridge/culverts)</u>

- Waterbody name (English and Inuktitut) and location (Lat & Long)
 We did a Geographical Names Search and no designation has been found for the creek.
 Locally, the water body is known as Carney Creek.
 Location: 63.757828,-68.54515 (Lat & Long)
- 2. Site photo, site map or air photo detailing location





- 3. Other Agencies contacted to date
 - a. AANDC, Aboriginal Affairs and Northern Development Canada
 - b. DFO, Department of Fisheries and Oceans Canada
 - c. EPD, Environmental Protection Division of the Government of Nunavut
- 4. Need for the project and alternatives considered:

Please see the Request for Review, produced by JFSA in July 2014.

5. General condition of the site (s)

For a completed description of the Aquatic environment, please see section D of the Request for Review, Iqaluit International Airport Improvement Project (IIAIP), prepared by JFSA in July 2014.

- i. Slope of banks:
 - The slope of banks varies on site, between 100 % and 30 %. Please refer to the following cross-sections.
- ii. Description of substrate:
 - The substrate consists mainly of gravel, along with blocks and sand.
- iii. Vegetation (on banks, in-stream, to be removed):

The vegetation observed on banks during the visit of October 2nd is described in the following table.

Iqaluit, Nunavut	Iqaluit International Airport Improvement Project	
	JFSA Project: 1217-03	
Floristic list		
Scientific Name	English Name	Inuktitut Name
Ameria maritima subsp. sibirica	Arctic thrift	Immulik
Brassiacaceae	Mustards	
Carex membranacea	Membranous sedge	Kilirnait ajjikasangit iv
Chamerion latifolium	Dwarf fireweed	Paunnat
Eriophorum angustifolium	Common cotton grass	Puallunnguat
Festuca brachyphylla	Alpine fescue	Ivilsugait
Oxyria digyna	Mountain sorrel	Qunguliit
Poa glauca	Glaucous bluegrass	Kilirnaujait
Salix artica	Artic willow	Suputiit

iv. Expected flow rates during time of construction (June-July-August):


The flow was measure on October 3rd, 2014, at the exit of the culverts of the Federal road. The result is approximately 0.01 m3/s.


During the work, we expect the flow rates can vary from 0.01 m3/s (minimum base flow) to 1.5 m3/s (flow expected in summer rain).

v. Channel meander pattern:

All the sections where work are expected, the channel is pretty straight, except for the section WC-1, which is more a braided channel.

- 6. Existing Habitat Please refer to the 2014 Fish Study (Fish habitat survey-Iqaluit JFSA 1217-01—P.pdf)
 - i. Fish Community (species/common names) at and near the site
 - ii. Use of impacted are as spawning, nursery, rearing, food supply or migration route
 - iii. Presence of sensitive habitat
 - iv. Assessment of impact to fish and fish habitat
- 7. Construction Details
 - a. No in water construction other than culvert and ditch realignment are planned for the project.
- Bridge
 - a. No bridge work is planned for the project.
- 9. Culvert Installation (refer to plans CC-114 and CC-115 for culvert locations and dimensions, ANNEXE-A)
 - i. Culvert dimensions (height and width or diameter, length)
 13 culverts between 600 and 1500 mm and from 18 to 69 linear meters
 1 culvert with 2.010 and 3.400 mm diameter (not circular) (Refer to plan CC-511, ANNEXE-B)
 - ii. Culvert type/material
 - Corrugated steel
 - iii. Impact to fisheries ability to migrate through the culvert






The fish will not be able to use the 250 m culvert installation. D&B JV has proposed to DFO to replace the existing culvert under the Federal road to offset the 250 meters culverts installation and to allow passage of fish.


The slope in the culvert installed in the watercourse will allow fisheries to migrate through the installation with respect to the fish swimming speed. DFO standards will be respected and applied.

- iv. Need to realign the channel?
 - The creek will be realigned on 450 meters with a 10 to 15 meters displacement
- v. Open bottom or natural substrate inside?
 - Closed bottom at the level of the surrounding substrate levels with no natural substrate
- vi. Slope of culvert
 - Slopes of all culverts are between 0 and 1.1 %
 - The 250 meters culvert will be sloped at 0.68 %
- vii. Installation of baffles, rock weirs or other structures
 - Compensatory improvements have been presented to DFO and were approved. A more detailed plan with installation of baffles, rock weirs or other structures will be presented (refer to Plan 3, ANNEXE-C).


Annexe-A, Site Plan CC-114



Annexe-A, Site Plan CC-115



Annexe-B, Culvert Plan Figure CC-511



Annexe-C, Plan 3

