



CULVERTS TO BE REMOVED:	
* EAST AIRSTRIP	9m LONG 600mm DIA. CMP
* APRON ACCESS-SOUTH	12m LONG 600mm DIA. CMP
* APRON ACCESS-NORTH	18m LONG 600mm DIA. CMP
* BEACH ACCESS	10m LONG 600mm DIA. BARREL
* BEACH POL ACCESS	15m LONG 600mm DIA. BARREL
* STATION ACCESS	11.5m LONG 600mm DIA. CMP
* STATION POL ACCESS	8m LONG 600mm DIA. BARREL
* GARAGE PAD ACCESS	9m LONG 600mm DIA. CMP
* WATER LAKE ROAD	8m LONG 600mm DIA. CMP

NOTE:
ALL CULVERTS FROM THIS SITE ARE TO BE REMOVED AND DISPOSED OF.

- General Notes:
1. ALL STRUCTURES DESIGNATED FOR DEMOLITION TO BE DEMOLISHED TO TOP OF CONCRETE FOUNDATIONS UNLESS NOTED OTHERWISE.
 2. ALL DIMENSIONS ARE IN METRES UNLESS NOTED OTHERWISE.
 3. ALL POLES, INCLUDING GUY WIRES, TO BE REMOVED UNLESS NOTES OTHERWISE.
 4. ALL SHORT RANGE RADAR (SRR) FACILITIES ARE CURRENTLY OPERATIONAL AND ARE NOT TO BE DISTURBED. THESE INCLUDE FUEL STORAGE TANKS AND PIPELINES NOT SCHEDULED FOR DEMOLITION.

- Legend:
- TO BE DEMOLISHED
 - UTILITY POLE TO BE REMOVED
 - POWER/COMMUNICATION CABLE
 - PHOTOGRAPHIC VIEWPOINT
 - BODY OF WATER

No.	DATE	REVISION	REVISION	APPR.
-----	------	----------	----------	-------

DRAFT

UMA | AECOM | SGE Acres

SCALE - ÉCHELLE 20 10 0 20 40 60m

PROJECT - PROJET
CAM-1 JENNY LIND ISLAND

DEW LINE CLEAN UP
© COPYRIGHT
HER MAJESTY THE QUEEN IN RIGHT OF CANADA 2006, AS REPRESENTED BY THE MINISTER OF NATIONAL DEFENCE.

TRADE - MÉTIER
STRUCTURAL
DATE
2006-02-28

SUBJECT - SUJET

**AIRSTRIp AREA AND BEACH AREA
DEMOLITION SITE PLANS**

PRODUCTION		CONCURRENCE -- ASSENTIMENT	
DESIGNED ETUDIE ANP/RRM		DES OFF AGENT CONCEPT	
DRAWN DESSINE LJV		SECT HD CHEF SECT	
CHECKED VERIFIÉ KMS		DES MGR GEST CONCEPT	
COORDINATION CAE		REVIEWED -- REVU	

DWG. NO. - DESSIN NO.
H-J44/1-9101-202