

Nunavut Regional Office (NRO) P.O. Box 2200 Iqaluit, NU, X0A 0H0

March 4, 2010

Mr. Thomas Kabloona A/Chief Administrative Officer Nunavut Water Board P.O. Box 119, Gjoa Haven, NU X0B 1J0

Dear Mr. Kabloona:

RE: Cape Christian Remediation Project: 2009 Annual Report for Water Licence No: 1BR-LOR0813

Please find attached the 2009 Annual report for the Water licence No: 1BR-LOR0813 issued for the remediation of the Cape Christian LORAN Site, Baffin Region, Nunavut.

If you have any questions or comments, please contact the undersigned or the Project Manager, Dele Morakinyo at dele.morakinyo@inac-ainc.gc.ca, or by telephone at (819) 934-9224

Matelle Pato


Natalie Plato, Director,

Contaminated Sites Program (NRO)

Tel: (867) 975-4730; Fax: (867) 975-4736

Email: natalie.plato@inac-ainc.gc.ca

CC: Nunavut Impact Review Board, Cambridge Bay, Nunavut



NWB Annua	l Report			Year being r	eported:	2009 🔻		
License No:	1BR-LOR081	3		Issued Date: Expiry Date:				
	Project Nam	e : [C	Cape Christia	n Site Remed	ation Projec	it		
	Licensee:	Indian a	and Northern	Affairs Canad	la, Contamin	nated Sites Pro	gram	\neg
	Mailing Addı	ress:	PO Box 220 Iqaluit NU X0A 0H0	00				
	Name of Cor relationship bet		_		erent from Nar	me of Licensee pl	lease clarify]
General Bac		ristian sit	e is located r	near the mout		er Clyde, on the neast of the Ha]
	The United St communication	ns statio	n at the site	from From 19	54 to 1974 w	igation (LORAN when the site was stures in disrepa	as	
	The remediati and it is expe	•	,	•		ed during the 2	008 season	
Licence Req	uirements: th	e licens	ee must pro	vide the follo	wing inforn	nation in acco	odance with	
	Part B	▼ Ite	em 1					
	ater; sewage a			-		ng, but not lim nagement; soli		
	Water Source	e(s):	An unnamed Road	d River adjace	nt to the Ca _l	pe Christian to	Clyde River	
	Water Quanti	ity:	15/day 6.2/day (ma	x) Actual C Quantity	uantity Used Allowable D	Domestic (cu.m d Domestic (cu Drilling (cu.m) Drilling (cu.m)	ı.m)	

Waste Management and/or Disposal	
✓ Solid Waste Disposal	
✓ Sewage	
Drill Waste	
✓ Greywater	
✓ Hazardous	
Other:	
Additional Details:	
Soild waste from the Camp was incinerated and the ash residue was stored in large, covered	
metal receptacles to be disposed off in the Non-Hazardous Waste Landfill. Sewage and	
Greywater was stored in the sewage lagoon. All Hazardous Wastes were properly packaged and	l t
stored for shipment to a licenced southern disposal facility	
A list of unauthorized discharges and a summary of follow-up actions taken.	
Spill No.: (as reported to the Spill Hot-line)	
Date of Spill: July 13, 2009	
Date of Notification to an Inspector: July 13, 2009	
Additional Details: (impacts to water, mitigation measures, short/long term monitoring, etc)	
Spill Report Form and Spill clean up report included as Appendix 2	
Revisions to the Spill Contingency Plan	
SCP submitted and approved - no revision required or proposed	
Additional Details:	
None	
Revisions to the Abandonment and Restoration Plan	
AR plan submitted and approved - no revision required or proposed ▼	
Additional Details:	
None	

Progressive Reclamation Work Undertaken
Additional Details (i.e., work completed and future works proposed)

WORK COMPLETED
 □ Mobilization of equipment, materials and supplies to site. □ Demolition of all deteriorating site buildings; □ Construction and operation of non-hazardous waste landfill (NHWL); □ Construction and operation of on-site landfarm; □ Collection and disposal of the site and demolition debris in the NHWL; □ Excavation of all PHC contaminated soil and treatment in the landfarm; □ Excavation and packaging of all contaminated soils impacted by metals and PC; □ Collection and packaging of all hazardous materials; □ Removal of all PCB materials from site for disposal in facilities down south, so the site do not need to be registered as a PCB storage site; □ Excavation of barrels at 3 worked areas (#s 1, 3, 4), venting of the barrels, crushing and disposal in the NHWL; □ Excavation of barrels at worked area # 6. This worked area contained a second layer of barrels that are well into the active layer of the permafrost with their contents solidly frozen, so the barrels could not be vented and crushed until the contents thaw. The barrels were excavated, made to stand upright with a containment berm built around them, to contain barrel contents, waiting for 2010 summer when the contents will thaw and the barrels' content could be removed and the barrel will be crushed and disposed off in the landfill.
FUTURE WORK PROPOSED Continuing operation of the on-site NHWL (placement of further wastes from the site and crushed barrels from the worked areas); Excavation of buried barrels from worked areas 2, 5, 7 and 8, venting, crushing and disposal in the landfill of all barrels, including those at worked area # 6; Completion of the collection of site debris and remaining equipment at the equipment yard and disposal in the NHWL; Continuing operation of the landfarm facility to treat the PHC contaminated soils – the soil, after it has been confirmed to meet the remediation criteria, will be used for backfilling dug-out areas; Decommissioning of the existing water reservoir; Hazardous waste transport and disposal – transport and disposal of packaged hazardous wastes and contaminated soils; Re-grading; Camp and facilities (e.g. sewage lagoon etc) decommissioning; Closure of the on-site NHWL; Project closure inspection / close-out meeting.

Results of the Monitoring Program including: The GPS Co-ordinates (in degrees, minutes and seconds of latitude and longitude) of each

	location where sources of water are utilized;
	Details attached ▼
	Additional Details:
	See GPS Co-ordinates below
	The GPS Co-ordinates (in degrees, minutes and seconds of latitude and longitude) of each location where wastes associated with the licence are deposited;
	Details attached ▼
	Additional Details:
	See GPS Co-ordinates below
	Results of any additional sampling and/or analysis that was requested by an Inspector
	No additional sampling requested by an Inspector or the Board
	Additional Details: (date of request, analysis of results, data attached, etc)
Any other reported.	details on water use or waste disposal requested by the Board by November 1 of the year being
	No additional sampling requested by an Inspector or the Board ▼
	Additional Details: (Attached or provided below)
Any respon	nses or follow-up actions on inspection/compliance reports
	No inspection and/or compliance report issued by INAC ▼
	Additional Details: (Dates of Report, Follow-up by the Licensee)

Any additional comments or information for the Board to consider

Some Before and After photographs are provided in Appendix 3

Date Submitted: March 4, 2010

Submitted/Prepared by: Natalie Plato

 Contact Information:
 Tel:
 (867) 975-4730

 Fax:
 (867) 975-4736

email: natalie.plato@inac-ainc.gc.ca

GPS Coordinates for water sources utilized

Source Description		Latitude			Longitude		
		, Min	Sec	o Deg	, Min	Sec	
An unnamed River adjacent to the Cape Christian to Clyde River Road (Water Source)	70	31	0	68	19	3	

GPS Locations of areas of waste disposal

Location Description (type)	Latitude			Longitude		
	o Deg	, Min	Sec	o Deg	, Min	Sec
Non-Hazardous Waste Landfill	70	31	33.28	68	18	9.3
Camp Wastewater - Permanent Sewage Lagoon	70	30	55.38	68	18	51.35

Appendix 1

Water and Wastewater Tracking / Camp Wastes Management

Water Usage

The source of water at the on-site camp is an unnamed river adjacent to the Cape Christian to Clyde River road. Water use was metered continuously from camp opening on July 4, 2009 to camp close on October 2, 2009. As per the Water Licence, the maximum daily water use rate is 15 m³ per day.

Based on daily information provided to, the following table summarizes the water usage during the 2009 remediation season:

Months	July (July 5 -31)	August (August 1 - 31)	September (September 1 - 30)	October (October 1 - 2)	
Meter Reading - end of month (m ³)	154	345	530	537	
Monthly Water Usage (m³)	154	191	185	7	
Daily Water Usage (m³)	5.7	6.2	6.2	3.5	

Water use was less than the permitted amount at all times in the 2009 season.

Wastewater/Sewage Generated

Sewage generation was not metered; however, as there was no consumptive use of water, the monthly and total volume of sewage generated is assumed to be equal to the water usage.

A single cell sewage lagoon with an approximate capacity of 1,200 m³ was constructed in July of 2009. Sewage decants are planned for the 2010 remediation season; there were no decants in 2009. Based on the water usage and the design capacity of the lagoon, the facility is approximately half full.

Solid Waste Generated

Sorted camp solid waste was incinerated during the 2009 remediation season, and domestic wastes will be incinerated in 2010 as well. To-date, the ash residue is stored in large, covered metal receptacles (flower-posts). The ash will be disposed of in the on-site non-hazardous waste landfill.

APPENDIX 2

Spill Report Form and Spill Initial Clean up Report

Spill Contingency Report

Information of Incident Section A						
7/13/2009 14:00 68 17 55,4 Cape Christian 70 31 35,7 Location Coordinates:						
(State the bearing if possible) Bearing: Unknown Qikiqtaaluk Logistics Inc. Party Responsible for Spill Old diesel Type of Substantial	SW S SE E NE Rate of Movement: Contained fuel stance that Spilled uantity of Substance					
Specific Cause of Incident Section B Please state the causes of the incident above in the following space provided						
While decommissioning old fuel tanks, one of them was dropped on the old fuel line that used to bring fuel from the tanks to the former abandoned station building. The fuel line felt down from its supports and some of the remaining fuel in the line spilled on the ground, by gravity.						
Status of Incident Section C						
Approximate surface area of contamination Containmant Actions Taken: Occurred Naturally Booms used Dyke used No containment implemented Other (specify) Absorbent pads	List any factors affecting the spill such as: wind, temperature, etc. Since the fuel tanks were built on a leveled pad (higher than the natural terrain), the fuel spilled followed the slopes around the pad.					

Phone: (867) 920-8130 Fax: (867) 873-6924

Action Propo Section D	osed to Clean, Contain or I	Dispose of S	Spilled Subst	ance				
Since many supervisors were watching the work and spill kits were on site, dykes were quickly								
built to contain the fuel. Booms and absorbent pads were also deployed. About 70 liters were								
recovered w	rith buckets and contained	in an overp	ack drum. S	Since the e	excavator was on si	te for the		
decommissi	oning of the tanks, 10 cm	of soils wer	e excavated	all over th	ne contaminated su	rface		
(about 3 cub	oic meters). The soils are t	emporarily	stockpiled a	nd will be	placed on the site I	andfarm		
when it will b	pe ready.							
Hazards of Section E	Spill Flammable		Information Section F Organization		nce is Required			
	Combustible Health hazard (specify)		Contact Pe		ics Inc.			
	Corrosive Explosive Radioactive Other (specify)		Contact Nu (604) 75 Hours of Op	59-0910 e	xt. 103 7:00 to 21:00			
Comments a	and Recommendations							
The spill wa	s immediately addressed a	and cleaned	l.					
·	·							
Information Section H	on Person Making Report							
Jonathan Re Full Name Qikiqtaaluk Employer Mr. Clinton	émillard Environmental	(604) 759- Contact Num	0910 ext. 10 ber -		ssistant Engineer sition & Department	_		
Submitted to			- :	Reporter's	s Signature	Date		

APPENDIX 3

Some Select Photos of before and after Remediation



Remediation)




Main Station Area (after Remediation)




Main Station Area's Aboveground Storage Tanks (ASTs) (before Remediation)




Main Station Area's ASTs (after Decomissioning) - Tanks will be cut and disposed off in Landfill



Worked Area # 1 (before remediation)



Worked Area # 1 (after Remediation)



Debris Area # 6 (before/during remediation)

