

Tier II Landfill

- Construction of containment system is complete
- Need to fill with 13,000 m³ of contaminated soil
 - Enough Soil to fill the ice rink at the Bell Centre 25 feet deep
- Once filled the top liner will be sealed to bottom liner, and covered with gravel and rocks

Tier I & II Soil Excavation

- Tier I & II Soil is not considered Hazardous, but it still has low levels of contamination
- Tier II Soil will go to the engineered landfill
- Some Tier I Soil will go to the engineered landfill
- Remainder to regular landfill

Gravel Production

- Gravel is needed for:
 - Completion of the Tier II Landfill
 - Covering landfilled debris
 - Road maintenance
 - Barging area platform

CEPA Soil Excavation

- CEPA Soil is a hazardous waste
- Only 250 m³ left to be excavated at the site
- Soil will be screened, and put in 100 Flower Pots
- Flower Pots will be shipped to a Southern disposal facility

Community Consultations
March 2005

RESOLUTION ISLAND
CLEANUP PROJECT



Approved by the
Quebec Government

Approved by the
Quebec Government

Hydrocarbon Contaminated Soil

- Hydrocarbons come gasoline, diesel, oil, grease, etc.
- 25 m³ of soil contaminated with diesel will be added to the land farm
- 100 m³ contaminated with oil and grease to be excavated and put into flower pots
- Remainder will be covered in place

Site Cleanup

- All remaining debris on site will be collected
- Any metallic debris will be shredded prior to landfilling
- All debris will be landfilled
- All empty drums will also be shredded and landfilled

Community Consultations
March 2005

RESOLUTION ISLAND
CLEANUP PROJECT