

Appendix E

Emergency Response Plans (Spill Contingency Plan; Wildlife Encounter Plan and Heritage Resource Discovery Plan)

EMERGENCY RESPONSE PLANS

***(SPILL CONTINGENCY PLAN, WILDLIFE ENCOUNTER PLAN AND HERITAGE
RESOURCE DISCOVERY PLAN)***

Former CAM-A (Sturt Point) Intermediate DEW Line Site, Nunavut

**Submitted by: Department of Indian Affairs and Northern Development
 (DIAND), Northern Affairs Program
 (Nunavut Regional Office)**

**Prepared by: Public Works and Government Services Canada (PWGSC)
 Real Property Services
 Architectural & Engineering Services
 Environmental Services
 Western Region**

October, 2012

Table of Contents

1	General.....	3
2	Fuel and Hazardous Material Spills Contingency Plan	3
3	Wildlife Encounter Plan.....	6
4	Heritage Resources Discovery Plan.....	7
5	Key Contacts' List	8

1 General

- 1.1 The following contingency plans present the prescribed course of action to be followed in the case of unanticipated events during the site remediation such as *fuel or chemical spills, potentially dangerous wildlife encounters, and the discovery of heritage resources*. The plans will enable persons in a particular contingency situation to maximize the effectiveness of the environmental response and meet all regulatory requirements for reporting to the appropriate authorities. The plans also describe the locations where hydrocarbons (fuel) and spill response equipment will be stored at the site.
- 1.2 Contingency plans for the site will be included in the Site Specific Remediation Plans, which will be posted on-site during the remediation. The following information will be included:
1. a description of pre-emergency planning;
 2. personnel roles, lines of authority and communication;
 3. emergency alerting and response procedures;
 4. evacuation routes and procedures, safe distances and places of refuge;
 5. emergency alerting and response procedures;
 6. directions/methods of getting to the nearest medical facility;
 7. emergency decontamination procedure;
 8. emergency medical treatment and first aid;
 9. emergency equipment and materials;
 10. emergency protective equipment;
 11. procedures for reporting incidents; and
 12. spill response and containment plans for all materials that could potentially be spilled.

2 Fuel and Hazardous Material Spills Contingency Plan

- 2.1 The objective of the fuel-related contingency plan is to protect the environment and human health by minimizing the impacts of spill events through clear and concise instructions to all personnel.
- 2.2 A variety of fuels (diesel, gasoline and lubricating oils) will be used during the site remediation of the CAM-A (Sturt Point) DEW Line site. Fuels will be stored in either barrels of 205 liters or smaller capacity or in double walled tanks. For either storage option, it is anticipated that any spill quantity would likely be small.
- 2.3 Transportation of fuels must comply with the *Transportation of Dangerous Goods Act and Regulations*.

- 2.4 The most common pollution incidents would probably involve spills of diesel or gasoline onto land resulting from: human error during transfer, rupture of barrels from deterioration or damage, seepage from fittings or valves, or equipment failure. Daily checking of equipment and preventative maintenance would also identify damage to the fuel system and reduce the risk of spills or leaks.
- 2.5 In the event of a spill, protection of human health and safety is paramount. Contamination of personnel involved in clean up is a real possibility as is contamination of the surrounding workplace and environment.

The individual responding to a spill shall:

1. Ensure personnel are appropriately trained.
 - a. All employees working on the CAM-A (Sturt Point) Remediation Project, including contractors and sub-contractors, will be trained in the safe operation of all machinery and tools, as well as in the handling of materials to help prevent and respond to hazardous material spills in a timely and effective manner. All employees on site will also be trained for initial spill response in the event of a spill. The recommended training for these purposes consists initially of the 40-Hour Hazardous Waste Operations and Emergency Response (HAZWOPER) course offered by various environmental firms and the 8-Hour HAZWOPER refresher course every two (2) years thereafter.
2. Make use of materials and equipment available for adequate response to fuel spills, such as excavators for creating earthen dykes and hydrocarbon absorbent booms.
3. Warn people in the immediate vicinity and evacuate the area if necessary.
4. Wear protective clothing as required for handling spills.
5. Isolate and eliminate all ignition sources.
6. Identify the spilled material if possible, and take all safety precautions before approaching it.
7. Attempt to immediately stop the leakage and contain the spill, if safe to do so, by implementing the Spill Response Actions summarized in Section 2.5.1 below.
8. Report to the Field Team Leader on the spill location, type of material, volume and extent, status of spill (direction of movement), and prevailing meteorological conditions.

9. Follow all applicable federal/territorial regulations and guidelines or the disposal of spill materials.
10. Document all events and actions taken. Include information required by applicable regulations and guidelines.
11. Notify appropriate government agencies using the contact list in Table 1 below. Report spills immediately on the 24-Hour Spill Report Line (867) 920-8130.

2.6 Spill Response Actions (Fuel and Hazardous Material Spills)

On Land

- Do not flush into ditches or drainage systems.
- Block entry into waterways and contain with earth, snow or other barrier.
- Remove small spills with sorbent pads.
- On tundra use peat moss and leave in place to degrade, if practical.

On Snow & Ice

- Block entry into waterways and contain with snow or other barrier.
- Remove minor spills with sorbent pads and/or snow.
- Use ice augers and pump to recover diesel under ice.
- Slots in ice can be cut over slow moving water to contain oil.
- Burn accumulated diesel from the surface using Tiger Torches if feasible and safe to do so.

On Muskeg

- Do not deploy personnel and equipment on marsh or vegetation.
- Remove pooled diesel with pumps and skimmers.
- Flush with low pressure water to herd diesel to collection point.
- Burn only in localized areas, e.g., trenches, piles or windrows.
- Do not burn if root systems can be damaged (low water table).
- Minimize damage caused by equipment and excavation.

On Water

- Contain spill as close to release point as possible.
- Use spill containment boom to concentrate slicks for recovery.
- On small spills, use sorbent pads to pick up contained oil.

- On larger spills, use skimmer on contained slicks.
- Do not deploy personnel and equipment onto mudflats or into wetlands

Rivers & Streams

- Prevent entry into water, if possible, by building berm or trench.
- Intercept moving slicks in quiet areas using (sorbent) booms.
- Do not use sorbent booms/pads in fast currents and turbulent water.

3 Wildlife Encounter Plan

- 3.1 Polar bears have been, reportedly, seen during the winter months around CAM-A (Sturt Point) site. Bears are a potential hazard to workers at all times and the situation can be exacerbated by the presence of any substance that a bear perceives to be food.
- 3.2 EMPLOY DEDICATED WILDLIFE MONITORS AT ALL TIMES DURING CLEAN UP OPERATIONS.
- 3.3 Be familiar with bear deterrent procedures. Be familiar with the GNWT “Safety in Bear Country” manual and make available a reference copy at the site.
- 3.4 Operators of vehicles and equipment shall make every effort to avoid encounters with large mammals. Congregations of animals near food or garbage are a potential problem, which can be overcome by proper disposal of food wastes. Concentrations of scavenging animals, such as wolves, foxes and bears, increase the risk of diseases, particularly rabies, and danger to personnel. The following precautions and actions are to be taken at each site:
 1. The killing of wildlife for any reason at variance with the Wildlife Act and regulations is an offence. Co-ordinate procedures for handling wildlife problems and incidents with the regional Nunavut wildlife office.
 2. Use vehicle, noisemakers and, if necessary, a firearm to frighten the bear away from the site.
 3. Shoot the bear only if the bear returns repeatedly, refuses to leave or directly threatens human safety. Killing is considered a last resort and, if at all possible, the appropriate wildlife officer should be contacted to alert them of the problem. If a bear is to be shot, assign the task only to a person familiar with and competent with the camp firearm. Wounded or otherwise aggravated bears can be extremely dangerous.

4. Report the death of a bear to the Field Team Leader and the appropriate wildlife officer who will issue instructions as to the disposal of the carcass and the formal reporting procedures to be followed.
5. Due to the possibility of rabies, shoot any animal that bites a human and retain the carcass intact pending instructions from the appropriate wildlife officer. If possible, notify the wildlife officer before any drastic action is taken. Seek medical advice from the appropriate medical facility for treatment of animal-inflicted wounds.

4 Heritage Resources Discovery Plan

- 4.1 In accordance with the Nunavut Archaeological and Palentological Regulations, archaeological assessment of CAM-A was carried out and a couple of heritage sites were found (Appendix B of the WL application) All site personnel are prohibited from knowingly disturbing any archaeological or other heritage site or collecting any artifacts. Removing artifacts is a criminal offence.
- 4.2 In the event of finding new or previously unidentified heritage resources:
 1. Do NOT remove any artifacts or other associated objects from the site unless their integrity is threatened in any way.
 2. Mark the site's visible boundaries and avoid the area.
 3. Report the discovery of the site to the appropriate regulatory agency.
 4. Document the discovery.
- 4.3 In the event of a discovery of human remains:
 1. Advise the PMO of the discovery and they will contact the nearest detachment of the RCMP. The RCMP will make the decision as to whether the territorial coroner or archaeological department should be contacted.
 2. Halt all activities around the area of discovery. Until determined otherwise, the remains should be treated as evidence in a criminal investigation. If the remains are found in the bucket of heavy equipment, the bucket should not be emptied, as physical evidence may be destroyed.
 3. Secure the area and designate it as out of bounds to all personnel. Depending on weather conditions, the human remains should be provided with non-intrusive protection such as a cloth or canvas tarp (non-plastic preferred).
 4. Document the discovery.

5 Key Contacts' List

5.1 24-Hour Spill Report Line

1. In the event of a spill, contact the 24-Hour Spill Report Line and provide them with all the relevant details. The contact details are: Telephone: (867) 920-8130
Fax: (867) 873-6924
2. Environment Canada, as lead agency, shall then be contacted by officials to ensure the appropriate response. The lines are staffed 24 hours a day and can also be used to co-ordinate a response in the event of a non-spill emergency outside of normal working hours.

5.2 Other Contacts

1. In the event of a non-spill emergency (e.g. related to wildlife, fisheries, herirage resources etc.), contacts are provided in Table 1 below.

Table 1: Contact List

Resource	Location	Phone Number	Fax Number
24 Hour Spill Line	NWT/Nunavut	(867) 920-8130	(867) 873-6924
Local Fire Department	Luc Grandmaison, Director / Fire Chief Emergency and Protective Services, Government of Nunavut, Iqaluit, Nunavut	(867) 976-5657	(867) 979-0680
Environment Canada, Enforcement Branch	Curtis Didham Enforcement Officer, Iqaluit, Nunavut	(867) 975-4644	-
Aboriginal Affairs and Northern Development Canada – Operations Department	Andrew Keim Acting Manager / Water Resource Officer, Iqaluit Region District Operations Manager	(867) 975-4289	(867) 979-6445
Government of Nunavut	Robert Eno Director of Environmental	(867) 975-7729	867) 975-7739

Emergency Response Plans for CAM-A (Sturt Point) Remediation Project

	Protection, Government of Nunavut Iqaluit, Nunavut		
Aboriginal Affairs and Northern Development Canada – Project Proponent	HQ - Gatineau Dele Morakinyo, AANDC Project Manager OR Iqaluit Office Natalie Plato, Director, Contaminated Sites	(819) 934-9224 (867) 975-4730	(819) 934-9229 (867) 975-4736
Public Works and Government Services Canada – Project Manager	Program Manager – Matthew McElwaine, PWGSC Project Manager	(780) 497-3690	(780) 497-3842