



Head Office:
71 Wright Avenue
Dartmouth, NS
B3B 1H4

Tel: (902) 468-8792
Fax: (902) 468-8524

Fuel Facility Expansion and Upgrade Hall Beach Nunavut

Reference: Sketch 1

Project summary:

The project consist in building two new tanks (Tank 11 and Tank 12 or reference sketch) and relocate and raise the height by 8 feet of three tanks (Tk 8, 9, & 10) by cutting the tank bottom, and welding a new ring. On completion all tanks will be hydrostatically tested.

Hydrostatic test procedure.

Salt water will be used from Fox Basin to hydrostatically test the tanks shown on sketch #1. All tanks will be cleaned and gas freed prior to test. The same water will be transferred from one tank to an other.

The water will be disposed by pouring the water in a 45 gal drum cut in half, full of holes and hydrophobic pads. This will act as a filter for the water. The total amount of water will be 2686 cubic meters.

030915 NWB4HAL Summary of Project - ILAM

