


Appendix A - Reports



DFO 3.4.1 - 1 Proposed Access Road Fisheries Assessments, Doris North Project, 2015





Memorandum

Date: November 24, 2015

Refer to File: C.1 - 0298923-0038 (Proposed Access Road Fisheries Assessment Memo 2015).docx

To: John Roberts, VP Environmental Affairs
Katsky Venter, Environmental Advisor
Sharleen Hamm, Project Manager

From: Fraser Ross (B.Sc., R.P.Bio.)

Cc: April Hayward (Ph.D.), Project Manager
Marc Wen (M.Sc., R.P.Bio.), Partner in Charge

Subject: **Proposed Access Road Fisheries Assessments, Doris North Project, 2015**

GLOSSARY AND ABBREVIATIONS

Terminology used in this document is defined where it is first used. The following list will assist readers who may choose to review only portions of the document.

CPUE	Catch-per-unit-effort
DELTs	Deformities, Erosion, Lesions, or Tumors
ERM	ERM Consultants Canada Ltd.
FHAP	Fish Habitat Assessment Procedures
FL	Fork Length
SHIM	Sensitive Habitat Inventory Mapping
TMAC	TMAC Resources Inc.

1. INTRODUCTION

ERM Consultants Canada Ltd. (ERM) conducted fisheries assessments along proposed access roads at the request of TMAC Resources Inc. (TMAC) during the open-water season of 2015. The three proposed road routes are:

- Doris Connector Vent Raise Access Road;
- Doris Central Vent Raise Access Road; and
- Roberts Bay Discharge Access Road (Figure 1-1).

The objectives of the 2015 Proposed Access Road Fisheries Assessments were as follows:

- to determine the locations of waterbodies along each of three proposed road routes;
- to sample the fish communities in all waterbodies along each road route;
- to assess the habitat value of each waterbody; and
- to assess the surface connectivity of these waterbodies to other fish-bearing waterbodies.

This memorandum presents the results of these assessments.

A rainfall event in the latter half of July 2015 caused unseasonably high flow conditions in streams around the Doris North Project (the Project) area. At the Doris Creek hydrology station, located downstream of Doris Lake, discharge was greater at that time than during spring freshet ($3.24 \text{ m}^3/\text{s}$ on July 29th whereas the freshet peak on June 15 was $2.92 \text{ m}^3/\text{s}$; ERM 2015 in progress). In 2015, the average discharge in Doris Creek between July 15 and September 15 was $1.54 \text{ m}^3/\text{s}$, whereas during the same period in previous years (2009 to 2014) discharge was $0.60 \text{ m}^3/\text{s}$. Although none of the sample sites reported herein are located on Doris Creek downstream of the lake, the hydrograph data substantiates field observations that discharge levels at the sample sites and in the general Project area were more typical of peak freshet conditions than what would be expected in mid-August.

2. METHODOLOGY

2.1 Desktop Assessment


Prior to fieldwork, the proposed roads were plotted on topographic maps to identify locations where the routes bisect waterbodies. The fisheries values of these locations would later be assessed in the field.

Historical fish community and habitat data were reviewed for waterbodies along and surrounding each road route to determine the proximity of known fish-bearing waterbodies to potential crossing sites.

2.2 Fish Habitat Assessment

Fish habitat was assessed along each road route on August 13 and 14, 2015. A preliminary assessment was completed to determine whether locations identified during the desktop mapping exercise contained habitats that could support fish (e.g., defined stream channels, ponds). Locations were categorized as “potential fish habitat” or as “not fish habitat” (e.g., subsurface flow, surface water with no defined channel). Sites that did not contain fish habitat were not considered further in the assessment.

Figure 1-1
Proposed Access Road Sampling Locations, Doris North Project, 2015



For sites categorized as potential fish habitat, additional habitat data were collected to determine its value. Habitats were surveyed using methods based on the Fish Habitat Assessment Procedures (FHAP; Johnston and Slaney 1996). Representative sections of each reach were chosen for assessment and individual habitat units were measured with respect to length, bankfull and wetted width, depth, substrate composition, residual pool depth, bank stability, bank height, and instream cover. Stream attributes were marked using a handheld GPS unit and representative photographs were taken. Barriers or seasonal restrictions to fish migration were also noted and measured, where appropriate. Habitat suitability for spawning, rearing, and overwintering was described and an overall habitat quality ranking was applied (Table 2-1).

Table 2-1. Overall Habitat Quality Rankings and Criteria

	Habitat Quality Ranking		
	High	Medium	Low
Definition	Habitat that is necessary to sustain an Aboriginal, commercial, or recreational fishery, any species at risk*, or because of the habitat's relative rareness, productivity, and/or sensitivity.	Habitat that is used by fish for feeding, growth, and migration but is not deemed to be essential. This category of habitat usually contains a large amount of similar habitat that is readily available to the fishery.	Habitat that has low productive capacity and contributes marginally to fish production.
Indicators	The presence of high-value spawning or rearing habitat (e.g., locations with an abundance of suitably sized spawning gravels, deep pools, undercut banks, or stable debris, which are necessary to the population), or the presence of any species at risk*, its residence, or its critical habitat.	Migration corridors, the presence of suitable spawning habitat, habitat with moderate rearing potential for the fish species present.	The absence of suitable spawning habitat, and habitat with low rearing potential (e.g., locations with a distinct absence of deep pools, undercut banks, or stable debris, and with little or no suitably sized spawning gravels for the fish species present).

Notes: * those designated by the Committee on the Status of Endangered Wildlife in Canada, or species listed on Schedule 1 of the Species At Risk Act (2002).

The connectivity of each stream to other fish-bearing waterbodies was assessed to help determine whether the stream might provide seasonal habitat to fish. Small Arctic streams flow seasonally; some flow only during freshet then become dry later in the summer, while others flow throughout the ice-free period but freeze to the substrate in winter. These seasonal streams are only of value to fish if they are connected to other habitat types where fish can overwinter, such as lakes or deep ponds.

2.3 Fish Community Assessment

Backpack electrofishing was the primary method used to sample stream fish communities on August 13 and 14, 2015. Figures 2.3-1 and 2.3-2 show the stream sections sampled by electrofishing in an unnamed tributary to Doris Lake and an unnamed tributary to Roberts Bay respectively. A crew leader operated a Smith-Root LR-24 and was accompanied by one dip netter. Anode ring diameter was 28 cm and dip net diameter was 21 cm with 3.2 mm mesh.

A systematic sweep sampling approach was conducted moving in an upstream direction that covered the entire wetted width of the stream, including all channels where flow was braided. Electrofishing effort was not pre-determined because the primary objective was to determine whether fish were present in the stream and, if so, determine fish community composition. Electrofisher voltage (V), duty cycle (%) and frequency (Hz) settings were adapted at each site to maximize catch efficacy.

All captured fish were identified to species and given a unique sample number. Fork Length (FL) was measured to the nearest 1 mm with a measuring board and wet weight was measured to the nearest 0.1 g using an electronic scale for each fish. Where parasites or deformities, erosions, lesions, or tumors (DELTs) were observed, this information was recorded for each fish. In addition, all observations of fish that were seen but not captured were noted.

All captured fish were placed immediately in a holding tank for species identification, enumeration, and biological processing and then released back into the site once collection was complete. Electrofishing effort was standardised as Catch Per Unit Effort (CPUE), which was calculated as the number of fish captured per 100 s.

$$CPUE = \text{number of fish caught} * [100/(\text{electrofishing effort in seconds})]$$

Field crews intended to set minnow traps as a second method of sampling fish communities; however, insufficient water depths prevented their use.

3. RESULTS AND DISCUSSION

3.1 Desktop Assessment

The review of topographic maps identified locations where both the proposed Doris Connector Vent Raise Access Road and the Roberts Bay Discharge Access Road bisect drainages. Conflicting data exists for a third drainage under the proposed Doris Central Vent Raise Access Road; 1:50,000 map data indicates that the drainage turns south and away from the road route before they cross (e.g. Figure 1-1), whereas more recent, site plan map data indicates that this road would cross a drainage (e.g. Figure 2.3-1). Given this uncertainty, the drainage routes would later be assessed in the field.

3.2 Historical Fisheries Data Review

Historical fisheries data are summarized below for waterbodies along and surrounding each road route.

3.2.1 *Doris Connector Vent Raise Access Road*

Topographic mapping indicates that the Doris Connector Vent Raise Access Road bisects one small unnamed surface drainage that discharges directly into Doris Lake. No historical fisheries data exists for this waterbody. Doris Lake has been extensively sampled; the fish community consists of Lake Trout (*Salvelinus namaycush*), Lake Whitefish (*Coregonus clupeiformis*), Cisco (*Coregonus artedii*), and Ninespine Stickleback (*Pungitius pungitius*; Rescan 2010).

Figure 2.3-1
Electrofishing Sample Route along Unnamed Tributary to Doris Lake, Doris North Project, 2015





Figure 2.3-2

Electrofishing Sample Route along Unnamed Tributary to Roberts Bay, Doris North Project, 2015



3.2.2 *Doris Central Vent Raise Access Road*

A review of historical fisheries data found that Sensitive Habitat Inventory Mapping (SHIM) was completed on a drainage that crosses the proposed Doris Central Vent Raise Access Road in 2010 (Rescan 2011). SHIM is a field-based method used to collect reliable, high quality, current and spatially accurate information about freshwater habitats and watercourses (Mason and Knight 2001). SHIM found that the general direction of drainage does cross the proposed access road (despite what 1:50,000 topographic mapping suggested), but there is no defined stream channel in the area; instead the area is covered with terrestrial vegetation that seeps towards Doris Lake through poorly defined pathways. When the SHIM sampling was completed, no fish community sampling could be completed as there was not a defined waterbody to sample.

3.2.3 *Roberts Bay Discharge Access Road*

The proposed Roberts Bay Discharge Access Road crosses one small, unnamed stream that drains into the southern end of Roberts Bay. This stream was sampled on one previous occasion; in August 2009 fish community and fish habitat were sampled (Rescan 2010). In 4,455 seconds of electrofishing effort, 12 Ninespine Sticklebacks were captured (CPUE = 0.27). On August 1, 2009 the lowest 100 m of the stream was flowing; above this section were isolated pockets of water and seepage through terrestrial vegetation. In the flowing section of the creek, the mean wetted depth was 0.2 m and wetted width was 0.3 m. Spawning habitat was rated as fair due to the presence of riffles with gravel substrate that could be used by spawning salmonids and wetted vegetation that could be used by spawning coarse fish species. Overall, fine sediment was the dominant substrate type (90%) and gravels comprised the remainder. Rearing, adult feeding, and migration quality were all rated as poor, and no overwintering habitat was observed.

A small, unnamed pond located in the headwaters of the stream's watershed had not been sampled previously.

3.3 Fish Habitat Assessment

3.3.1 *Doris Connector Vent Raise Access Road*

The desktop assessment identified one location where the Doris Connector Vent Raise Access Road intersects a waterbody; the proposed route crosses a small, unnamed tributary to Doris Lake. The field assessment of the road route completed on August 13, 2015 confirmed that this was the only location where the road bisects a drainage.

The stream is approximately 500 m in length, draining land to the south and east of the existing Float Plane Dock Access Road. Its headwaters consist of a series of discontinuous channel braids, which converge into a poorly connected channel in the vicinity of the proposed stream crossing. From there, the stream flows intermittently in a channel to a culvert under the Float Plane Dock Access Road and into Doris Lake.

The upper section of the watershed provides poor quality fish habitat. The braided channels are poorly defined, narrow (mean width 0.28 m), shallow (mean depth 0.11 m), and have poor connectivity with each other and with the lower section of the creek (Plate 3.2-1). Dense in-channel terrestrial vegetation and low discharge even during peak periods limit fish

movement and the habitat value in this section. Where the proposed road route crosses the stream, the stream channel is poorly defined and is dominated by terrestrial vegetation, suggesting that it contains flow for a short period during most years (Plate 3.2-2). This area did contain a small amount of flow during August 2015 due to anomalous weather conditions; however, it is expected that this area would cease flowing soon after freshet in most years. Habitat throughout this section is of poor quality.



Plate 3.2-1. The upper stream section consists of small, braided channels with poor connectivity to the lower section of the stream, August 13, 2015.

Just upstream of Doris Lake the stream flows through a single 6" diameter culvert under the Doris Lake boat launch ramp. Just upstream of the culvert there is a 3 m section of creek that has a defined channel that could provide some rearing habitat to coarse fish. During the site visit, the channel downstream of the culvert was poorly defined and contained little flow; the majority of water discharging from the culvert percolated subsurface through loose gravels before entering Doris Lake (Plate 3.2-3).

Access to the entire stream for fish in Doris Lake is limited; subsurface flow downstream of the culvert and heavy instream vegetation will restrict fish movement during most flow conditions.



Plate 3.2-2. The stream section upstream of the culvert is poorly defined due to heavy in-channel vegetation, August 13, 2015.



Plate 3.2-3. Discharge from the Doris Lake boat launch culvert percolates into loose gravels, August 13, 2015.

3.3.2 *Doris Central Vent Raise Access Road*

A field crew walked the full length of the proposed Doris Central Vent Raise Access Road but no waterbodies were identified. Similar to results from historical SHIM mapping, the field assessment found that the proposed road route does cross the drainage pathway, but there is no defined stream channel. Instead, the area is covered with terrestrial vegetation and the land drains towards Doris Lake through poorly defined pathways. As no fish habitat exists along this route, no additional habitat data were collected.

3.3.3 *Roberts Bay Discharge Access Road*

The desktop assessment identified one location where the Roberts Bay Discharge Access Road intersects a waterbody; the proposed route crosses a small, unnamed tributary to Roberts Bay. The field assessment of the road route completed on August 13, 2015 confirmed that this was the only location where the road bisects a drainage.

The stream is approximately 500 m in length, draining land at the southern end of Roberts Bay. The stream can be divided into two sections; the upper section has a poorly defined channel and is dominated by terrestrial vegetation, and the lower section contains a well-defined channel that discharges into Roberts Bay.

Marginal fish habitat exists in the upstream section of the stream. No salmonid spawning, rearing, migration, or overwintering habitat exists, but it may provide limited rearing habitat to coarse fish. This section is approximately 400 m in length and has a poorly defined channel where water seeps downslope primarily through dense terrestrial vegetation. Some surface water was flowing through grasses in this section of the stream during the August 2015 fieldwork, but this is likely atypical for this time of year based on the aforementioned high flows observed locally in 2015. Dense terrestrial vegetation indicates that this area typically flows for only a brief period during spring snow melt.

There was poor, but existing, connectivity between the upper reaches of the stream and an unnamed pond during the site visit on August 13, 2015. The dominant outflow of this pond flows to the northwest, but some water does seep through a heavily vegetated area and into the creek when water levels are high. This connection is weak, but small bodied fish may occasionally pass through this avenue.

The downstream section of the stream is approximately 100 m in length, containing multiple braided, well defined channels that gradually merge and provide good connectivity between the creek and Roberts Bay. The proposed road route intersects with the upstream portion of this section of the creek. Similar to the habitat assessment completed in 2009, fine sediments dominated the streambed substrate with lesser amounts of gravel also. The overall value of the creek was rated as poor as the stream has low quality rearing, adult feeding, and migration habitat and has no overwintering habitat; however, the downstream section may provide fair spawning and juvenile rearing habitat.

3.4 Fish Community Assessment

3.4.1 *Doris Connector Vent Raise Access Road*

Fish do inhabit the stream that intersects with the Doris Connector Vent Raise Access Road, but fish density and diversity are both low. In 1962 seconds of electrofishing, four Ninespine Sticklebacks were captured (CPUE = 0.20) and two additional fish were observed but not captured. All of these fish were caught or observed in a 3 m section of stream just upstream of the existing culvert, confirming that fish are able to pass from the lake upstream through the culvert during freshet (Figure 3.4-1). Fish use appears to be restricted to this small section of the stream; no fish were captured or observed in the remainder of the stream, including where the stream and the road intersect, despite a high level of effort. Upstream of this small fish-bearing section of the creek, the channel is poorly defined and is dominated by dense terrestrial vegetation that limits fish passage. The fish-bearing section of stream is approximately 50 m downstream of the intersection of the stream and the proposed road route.

In 2015, stream flow conditions were unusual due to a large rainfall event in July. Channel morphology and an abundance of terrestrial vegetation suggest that this stream typically flows for a far shorter period than was observed in 2015. This stream provides a small amount of poor quality rearing habitat for a short duration to coarse fish in Doris Lake.

3.4.2 *Doris Central Vent Raise Access Road*

No waterbodies exist along the route of the proposed Doris Central Vent Raise Access Road, so no community sampling was completed in this area. Terrestrial drainage passes under the proposed access road, but there is no defined stream channel; instead the area is covered with terrestrial vegetation that seeps towards Doris Lake through poorly defined pathways.

3.4.3 *Roberts Bay Discharge Access Road*

A total of four Ninespine Sticklebacks were captured in the stream that flows under the proposed Roberts Bay Discharge Access Road in 4,284 seconds of electrofishing (CPUE = 0.01). This finding is similar to 2009, where only Ninespine Sticklebacks were captured. All fish were captured in the lower section of the stream downstream of the location where the proposed road intersects (Figure 3.4-2). This indicates that poor habitat conditions and dense vegetation prelimit upstream movement of fish from Roberts Bay beyond the lower 100 m section of the stream.

Figure 3.4-1

Fish-bearing Reach of an Unnamed Stream that Intersects the Doris Connector Vent Raise Access Road on August 13 2015, Doris North Project







Figure 3.4-2

Fish-bearing Reach of an Unnamed Stream that intersects the Roberts Bay Discharge Access Road on August 13 2015, Doris North Project



4. SUMMARY

4.1.1 *Doris Connector Vent Raise Access Road*

One short stream that contains poor quality fish habitat intersects the proposed Doris Connector Vent Raise Access Road. The stream channel throughout is poorly defined and fish movement within the stream is limited by a culvert, dense vegetation growth, and shallow water depths.

Ninespine Sticklebacks inhabit the stream in low densities. Their distribution appears to be restricted to the lowest few metres of the creek just upstream of Doris Lake and approximately 50 m downstream of the proposed road crossing. It appears that fish from Doris Lake can access this section of the creek during peak discharge events, but movement beyond this section is limited as the stream channel is poorly defined and it is dominated by dense terrestrial vegetation.

4.1.2 *Doris Central Vent Raise Access Road*


No fish habitat exists along the proposed route for the Doris Central Vent Raise Access Road. Terrestrial drainage passes under the proposed access road, but there is no defined stream channel; instead the area is covered with terrestrial vegetation that seeps towards Doris Lake through poorly defined pathways.

4.1.3 *Roberts Bay Discharge Access Road*

A single stream intersects the proposed route of the Roberts Bay Discharge Access Road. Upstream of the crossing the stream channel is poorly defined, where dense terrestrial vegetation and shallow water depths limit fish passage and use even during peak flow periods. No fish were captured in this section of the creek during the current sampling program or during the one previous sampling event.


The stream does provide some fish habitat adjacent to and downstream of the location where it intersects with the proposed road route. This section of creek (approximately 100 m in length) has a clearly defined channel and provides some rearing habitat for coarse fish that can access the creek from Roberts Bay. In two years of sampling, Ninespine Stickleback is the only species that has been captured in this stream.

Prepared by:

A handwritten signature in black ink, appearing to read 'Fraser Ross', positioned above a horizontal line.

Fraser Ross, B.Sc., R.P.Bio.
Consultant, Fisheries, ERM

Reviewed by:

A handwritten signature in black ink, appearing to read 'April Hayward', positioned above a horizontal line.

April Hayward, Ph.D.
Project Manager, ERM

REFERENCES

2002. *Species at Risk Act*, S.C. 2002, C. 29.

ERM. In progress. *Doris North Project: 2015 Hydrology Compliance Monitoring Program Memorandum*. Prepared for TMAC Resources Inc. by ERM Rescan: Yellowknife, Northwest Territories.

Johnston, N. T., and P. A. Slaney. 1996. *Fish habitat assessment procedures*. Watershed Restoration Technical Circular No. 8. Vancouver, BC: British Columbia Ministry of Environment, Lands and Parks.

Mason, B., and R. Knight. 2001. *Sensitive Habitat Inventory and Mapping*. Community Mapping Network, Vancouver, British Columbia. 315pp + viii. M. Johannes, Editor.

Rescan. 2010. *2009 Freshwater fish and fish habitat baseline report, Hope Bay Belt Project*. Prepared for Newmont Mining Corporation by Rescan Environmental Services Ltd.: Vancouver, BC.

Rescan. 2011. *2010 Freshwater fish and fish habitat baseline report, Hope Bay Belt Project*. Prepared for Newmont Mining Corporation by Rescan Environmental Services Ltd.: Vancouver, BC.

EC-7 - 1 Threespine Stickleback Toxicity Testing

EC-7 - 2 Groundwater Results QA/QC

EC-7 - 3 Groundwater Analytical Results





Integrated Resource Consultants Inc.

Suite 160, 14480 River Road
Richmond, BC, Canada V6V 1L4
Tel. 604-278-7714 Fax 604-278-7741
info@ircintegratedresource.com

FILE:GOLDER/I011034.STB

DATE: 15 November 2010

TO: Peter Chapman
Golder Associates Ltd.
500-4260 Still Creek Drive
Burnaby, B.C.
V5C 6C6

REPORT ON: THREESPIKE STICKLEBACK TOXICITY TESTING

SAMPLE DESCRIPTION:

IRC Sample ID No.:	1011034
Sample Name:	10WBW001 Zone 6
Date collected:	31 October 2010; 1400 hrs
Date received:	2 November 2010; 1630 hrs
Amount, Container:	4 x 20L plastic containers
Physical description:	Opaque, yellow-orange liquid
Date, time tested:	3 November 2010; 0945 hrs

96 HR TEST RESULTS:

The 96 hour (static) LC₅₀ was greater than 100% (v/v sample).
30% stickleback mortality in 100% concentration.

The LC₅₀ is defined as the median lethal concentration or the concentration at which there is 50% fish mortality. Results are calculated using the method described by Stephan (Methods for calculating an LC₅₀ in: Aquatic Toxicology and Hazard Evaluation, American Society for Testing and Materials, 1977).

The method used for this test was as per the "Biological Test Method: Acute Lethality Test Using Threespine Stickleback (*Gasterosteus aculeatus*)" EPS 1/RM/10, July 1990. Test volume was 20 litres with 10 fish exposed in each test vessel. Aeration was by forced air through airstones at a rate of approximately 6.5 ± 1 ml/L/min. The sample was not pH adjusted or filtered prior to testing.

The initial dissolved oxygen level was 8.5 mg/L at 14.5°C, the conductivity was 49.0 mS/cm and the initial pH was 7.5. Sample salinity was 31.3 ppt. After pre-aerating the sample for 30 minutes, the dissolved oxygen level was 8.8 mg/L. As the dissolved oxygen level was greater than 70% saturation and less than 100% saturation the test was initiated at this time. The test set up technician was KA.

Please call should you have any questions.

IRC Integrated Resource Consultants Inc.

Carolyn Wilson
Laboratory Biologist
enclosure

RAW DATA:

<u>TEST</u> <u>CONCENTRATION</u>	<u>HOURS</u>					
		0	24	48	72	96
100 %	Percent Survival	100%	100%	80%	70%	70%
	Dissolved Oxygen (mg/L)	8.8	8.4	8.2	8.3	8.3
	Temperature (°C)	14.5	14.5	15.0	15.0	15.0
	pH	7.6	7.7	7.8	7.8	7.8
	Conductivity (mS/cm)	49.1				50.0
	Salinity (ppt)	31.4	31.5	31.6	31.9	31.9
	Symptoms	1	2	2	2	2
	Loading Density (g/L)	0.30	0.30	0.24	0.21	0.21
50 %	Percent Survival	100%	100%	90%	90%	90%
	Dissolved Oxygen (mg/L)	8.9	8.3	8.2	8.3	8.2
	Temperature (°C)	14.5	14.5	15.0	15.0	15.0
	pH	8.0	7.9	7.9	7.9	7.9
	Conductivity (mS/cm)	48.2				49.1
	Salinity (ppt)	30.7	30.9	31.1	31.1	31.3
	Symptoms	1	2	2	2	2
	Loading Density (g/L)	0.30	0.30	0.27	0.27	0.27
25 %	Percent Survival	100%	100%	80%	80%	80%
	Dissolved Oxygen (mg/L)	8.9	8.3	8.3	8.4	8.4
	Temperature (°C)	14.5	15.0	15.0	15.0	15.0
	pH	8.2	8.0	8.0	8.0	8.0
	Conductivity (mS/cm)	47.9				48.3
	Salinity (ppt)	30.5	30.7	30.7	30.9	31.0
	Symptoms	1	1,2	1,2	1,2	1,2
	Loading Density (g/L)	0.30	0.30	0.24	0.24	0.24
12.5 %	Percent Survival	100%	100%	100%	100%	100%
	Dissolved Oxygen (mg/L)	8.8	8.4	8.5	8.4	8.3
	Temperature (°C)	14.5	15.0	15.0	15.0	15.0
	pH	8.4	8.2	8.2	8.2	8.2
	Conductivity (mS/cm)	47.7				48.2
	Salinity (ppt)	30.3	30.4	30.6	30.7	30.8
	Symptoms	1	1,2	1,2	1,2	1,2
	Loading Density (g/L)	0.30	0.30	0.30	0.30	0.30
6.2 %	Percent Survival	100%	100%	100%	100%	100%
	Dissolved Oxygen (mg/L)	8.9	8.3	8.3	8.3	8.2
	Temperature (°C)	14.5	15.0	15.0	15.0	14.5
	pH	8.3	8.2	8.1	8.1	8.1
	Conductivity (mS/cm)	47.5				47.5
	Salinity (ppt)	30.2	30.3	30.3	30.4	30.4
	Symptoms	1	1,2	1,2	1,2	1,2
	Loading Density (g/L)	0.30	0.30	0.30	0.30	0.30
CONTROL	Percent Survival	100%	100%	100%	100%	100%
	Dissolved Oxygen (mg/L)	8.9	8.1	8.0	8.0	7.9
	Temperature (°C)	14.5	15.0	14.5	15.0	15.0
	pH	8.4	8.2	8.1	8.1	8.1
	Conductivity (mS/cm)	47.3				47.6
	Salinity (ppt)	30.1	30.1	30.2	30.1	30.2
	Symptoms	1	1	1	1	1
	Loading Density (g/L)	0.30	0.30	0.30	0.30	0.30
	Technician	KA	LH	LH	LH	LH

KEY TO SYMPTOMS:

- 1 = no apparent effect
- 2 = fish showing signs of stress
- 3 = loss of equilibrium





TEST FISH STOCK INFORMATION

Date received:	20 October 2010	
Source:	Ladner Trunk Road	
Species:	<i>Gasterosteus aculeatus</i> (Threespine Stickleback)	
Fork Length:	Mean:	38.4 mm \pm 5.8 mm
	Range:	30.0 mm – 45.0 mm
Wet weight:	Mean:	0.59 g \pm 0.17 g
	Range:	0.29 g – 0.80 g
Condition Factor (100xWt/length ³ cm):	1.04	

Acclimation History	
Acclimation temperature:	14.0 to 15.0 ° CELSIUS
Treatments:	None
Water:	Dechlorinated tap water, adjusted to 30.0ppt using dry ocean salts
Feeding:	Freeze-dried brine shrimp
Salinity:	1.0 to 26.1 ppt
Mortality:	0.92% in week prior to testing

THREESPIN STICKLEBACK REFERENCE TOXICANT DATA

Stock Arrival Date (y/m/d)	Test Date (y/m/d)	Toxicant	Log LC ₅₀ (mg/L)
05.03.01	05.03.30	Phenol	1.33
05.06.02	05.06.17	"	1.26
05.08.16	05.09.07	"	1.21
05.11.10	05.12.02	"	1.30
06.02.22	06.03.15	"	1.16
06.06.02	06.06.26	"	1.36
06.08.18	06.08.31	"	1.10
06.12.08	06.12.20	"	1.03
07.02.14	07.02.14	"	1.02
07.04.24	07.05.16	"	1.14
07.07.17	07.08.08	"	1.23
07.11.02	07.11.16	"	1.11
08.01.23	08.02.08	"	1.13
08.05.10	08.05.24	"	1.22
08.08.19	08.09.05	"	1.16
08.12.04	08.12.16	"	1.29
09.03.04	09.03.19	"	1.10
09.06.05	09.06.18	"	1.30
09.09.21	09.09.30	"	1.29
10.02.27	10.03.19	"	1.10
10.06.03	10.07.06	"	1.28
10.09.09	10.09.24	"	1.19
10.10.20	10.11.09	"	1.11
LAB GEOMETRIC MEAN (LOG) \pm 2 standard deviations:			1.19 mg/L \pm 0.19
Warning Limits (Log Values):			1.01 mg/L to 1.38 mg/L



Data file reference:
J:\01_SITES\Hope.Bay\1CH008.013_2010_Westbay_Installation\020_Project_Data\SRK\07_Water Chemistry Results\Working Files\20110201 Doris Central Purge Graphs.xlsx



2010 West Bay Data Report - Appendix M

Doris Central 10WBW001
Zone 6





Job No: 1CH008.013
Filename: Figures M1-9_DorisCentral_20110202.pptx

HOPE BAY MINING LTD.

Date:
February 2011

Approved:
JH

Figure: **M.4**



Data file reference:
J:\01_SITES\Hope.Bay\1CH008.013_2010_Westbay_Installation\020_Project_Data\SRK\07_Water Chemistry Results\Working Files\20110201 Doris Central Purge Graphs.xlsx



2010 West Bay Data Report - Appendix M

Doris Central 10WBW001
Zone 6


Job No: 1CH008.013
Filename: Figures M1-9_DorisCentral_20110202.pptx

HOPE BAY MINING LTD.

Date:
February 2011

Approved:
JH

Figure: **M.5**



Data file reference:
J:\01_SITES\Hope.Bay\1CH008.013_2010_Westbay_Installation\020_Project_Data\SRK\07_Water Chemistry Results\Working Files\20110201 Doris Central Purge Graphs.xlsx



2010 West Bay Data Report - Appendix M

Doris Central 10WBW001
Zone 6

Job No: 1CH008.013
Filename: Figures M1-9_DorisCentral_20110202.pptx

HOPE BAY MINING LTD.

Date:
February 2011

Approved:
JH

Figure: **M.6**

Table N1: Comparison of Repeated Samples from the Same Port, Over Time

Field Sample ID / Unique ID	Units	Repeated port samples over time	RPD	Repeated port samples over time	RPD	Repeated port samples over time	RPD	Repeated port samples over time	RPD	Repeated port samples over time	RPD	Repeated port samples over time	RPD	Repeated port samples over time	RPD	
10WBW001-101	10WBW001-102	10WBW001-103	10WBW001-104	10WBW001-105	10WBW001-106	10WBW001-107	10WBW001-108	10WBW001-109	10WBW001-110	10WBW001-111	10WBW001-112	10WBW001-113	10WBW001-114	10WBW001-115	10WBW001-116	
Sample From	Westbay Port	Westbay Port	Westbay Port	Westbay Port	Westbay Port	Westbay Port	Westbay Port	Westbay Port	Westbay Port	Westbay Port	Westbay Port	Westbay Port	Westbay Port	Westbay Port	Westbay Port	
Sample label for graph	10WBW001-101	10WBW001-102	10WBW001-103	10WBW001-104	10WBW001-105	10WBW001-106	10WBW001-107	10WBW001-108	10WBW001-109	10WBW001-110	10WBW001-111	10WBW001-112	10WBW001-113	10WBW001-114	10WBW001-115	
Sample Zone	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
Location of port in zone	Top	Top	Top	Top	Top	Top	Top	Top	Top	Top	Top	Top	Top	Top	Top	
Zone port drillhole depth	548.0	548.0	548.0	548.0	548.0	548.0	548.0	548.0	548.0	548.0	548.0	548.0	548.0	548.0	548.0	
Total Lines purged from zone before sample was taken	3186	3189	3189	3192	3192	3192	3192	3192	3192	3192	3192	3192	3192	3192	3192	
Zone volumes purged before sample was taken	27.4	27.4	27.4	27.5	27.5	27.5	27.5	27.5	27.5	27.5	27.5	27.5	27.5	27.5	27.5	
ALS DATA																
ALS Date Sampled	04-AUG-10	19-OCT-10	19-OCT-10	30-OCT-10	30-OCT-10	05-AUG-10	19-OCT-10	19-OCT-10	01-NOV-10	05-AUG-10	20-OCT-10	20-OCT-10	29-OCT-10	29-OCT-10	29-OCT-10	
ALS Time Sampled	13:42	12:00	12:00	13:00	13:00	09:00	15:00	15:00	15:00	11:00	11:00	11:00	15:00	15:00	15:00	
Matrix	Seawater	Seawater	Seawater	Seawater	Seawater	Seawater	Seawater	Seawater	BOTH	Seawater	Seawater	Seawater	Seawater	Seawater	Seawater	
Physical Tests																
Conductivity (EC)	uS/cm	46600	46700	0%	46700	46900	0%	24600	34900	34900	37000	-6%	30300	33800	-11%	
Density		1.01	1.01	0%	1.01	1.01	0%	1.01	1.01	1.01	1.01	-2%	1.01	1.01	0%	
Hardness (as CaCO3)	mg/L	12700	12600	1%	12600	12100	4%	4760	6720	6720	7340	-9%	6020	6360	-5%	
pH		7.43	7.38	1%	7.38	7.38	0%	7.23	7.58	7.29	7.58	3%	7.47	7.46	0%	
Salinity (EC)	g/L	30.50	31.2	2%	30.50	31.2	0%	22.10	23.5	22.10	23.5	-6%	23.10	23.00	-0%	
Total Dissolved Solids	mg/L	47800	42300	12%	42300	47500	-12%	19600	28900	28900	25500	13%	23100	28300	-20%	
Anions and Nutrients																
Alkalinity, Bicarbonate (as CaCO3)	mg/L	<2	<2	<2	<2	<2	44.2	<2	<2	44.2	43.7	1%	77.3	77.3	0%	
Alkalinity, Carbonate (as CaCO3)	mg/L	<2	<2	<2	<2	<2	<2	<2	<2	<2	<2	1%	<1	<1	<2	
Alkalinity, Hydroxide (as CaCO3)	mg/L	<2	<2	<2	<2	<2	<2	<2	<2	<2	<2	1%	<1	<1	<2	
Alkalinity, Total (as CaCO3)	mg/L	<2	<2	<2	<2	<2	44.2	44.2	0%	44.2	43.7	1%	49.7	77.3	-31%	
Ammonia as N	mg/L	100	101	-1%	101	101	0%	21.2	38.1	-57%	38.1	41.3	-8%	27.6	36.4	-24%
Bromide (Br)	mg/L	19000	18000	3%	19000	18000	3%	19000	18000	-57%	13400	14200	-6%	11500	13100	-13%
Chloride (Cl)	mg/L	<0.75	<0.75	0%	<0.75	<0.75	0%	<0.75	<0.75	-0.75	<0.75	0%	<0.75	<0.75	0%	
Fluoride (F)	mg/L	<0.5	0.96	0%	0.96	<0.5	0%	<0.5	<0.5	<0.5	<0.5	0%	<0.5	<0.5	0%	
Nitrate (as N)	mg/L	<0.1	<0.1	0%	<0.1	<0.1	0%	<0.1	<0.1	<0.1	<0.1	0%	<0.1	<0.1	0%	
Ortho Phosphate as P	mg/L	0.0264	0.0264	100%	0.0264	0.0264	100%	0.0264	0.0264	0.0264	0.0264	0%	0.0264	0.0264	0%	
Boron (B)-Total	mg/L	7.8	7.8	0%	7.8	7.8	0%	7.8	7.8	7.8	7.8	0%	7.8	7.8	0%	
Sulfate (as SO4)	mg/L	980	980	0%	980	980	0%	980	980	980	980	0%	980	980	0%	
Sulfate (SO4)	mg/L	980	980	0%	980	980	0%	980	980	980	980	0%	980	980	0%	
Total Metals																
Aluminum (Al)-Total	mg/L	0.0992	0.0136	152%	0.0136	0.0086	45%	0.0281	0.0052	138%	0.0052	0.0059	-13%	0.0146	<0.005	-99%
Antimony (Sb)-Total	mg/L	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	0.00745	0.005	39%	0.005	0.00461	-8%	0.00349	0.00099	112%
Arsenic (As)-Total	mg/L	<0.002	<0.002	0%	<0.002	<0.002	0%	0.003	<0.002	0%	<0.002	<0.002	0%	<0.002	<0.002	0%
Barium (Ba)-Total	mg/L	0.051	0.051	0%	0.051	0.051	0%	0.130	0.175	-30%	0.175	0.169	3%	0.123	0.123	0%
Beryllium (Be)-Total	mg/L	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%
Bismuth (Bi)-Total	mg/L	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%
Boron (B)-Total	mg/L	7.8	7.8	0%	7.8	7.8	0%	7.8	7.8	7.8	7.8	0%	7.8	7.8	0%	
Cadmium (Cd)-Total	mg/L	<0.00012	<0.00005	246%	<0.00012	<0.00005	246%	<0.00012	<0.00005	246%	<0.00012	<0.00005	246%	<0.00012	<0.00005	246%
Calcium (Ca)-Total	mg/L	5070	4960	2%	4960	4700	5%	8005	1140	-34%	1140	1170	-3%	1020	1080	-6%
Cesium (Cs)-Total	mg/L	0.0002	0.00102	406%	0.00102	0.0011	8%	0.0002	0.0002	0%	0.0002	0.0002	0%	0.0002	0.0011	-41%
Chromium (Cr)-Total	mg/L	0.01	0.006	160%	0.006	0.002	104%	0.006	0.002	104%	0.006	0.002	104%	0.006	0.002	104%
Cobalt (Co)-Total	mg/L	<0.0005	<0.000073	1010%	<0.0005	<0.000073	1010%	<0.0005	<0.000073	1010%	<0.0005	<0.000073	1010%	<0.0005	<0.000073	1010%
Copper (Cu)-Total	mg/L	0.0018	0.00059	305%	0.00059	0.00102	35%	<0.001	<0.0005	0%	<0.001	<0.0005	0%	<0.001	<0.0005	0%
Gallium (Ga)-Total	mg/L	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%
Iron (Fe)-Total	mg/L	0.46	0.24	62%	0.24	0.197	20%	0.46	0.24	59%	0.24	0.197	20%	0.46	0.24	59%
Lead (Pb)-Total	mg/L	0.0013	<0.0003	326%	<0.0003	<0.0003	0%	<0.001	<0.0003	0%	<0.001	<0.0003	0%	<0.001	<0.0003	0%
Lithium (Li)-Total	mg/L	0.37	0.346	7%	0.346	0.381	-10%	0.093	0.117	-21%	0.117	0.131	-11%	0.128	0.128	0%
Magnesium (Mg)-Total	mg/L	0.031	0.064	108%	0.064	0.072	-1%	0.031	0.064	108%	0.064	0.072	-1%	0.031	0.064	108%
Manganese (Mn)-Total	mg/L	0.72	0.72	0%	0.72	0.72	0%	0.72	0.72	0%	0.72	0.72	0%	0.72	0.72	0%
Mercury (Hg)-Total	mg/L	<0.00001	<0.00001	0%	<0.00001	<0.00001	0%	<0.00001	<0.00001	0%	<0.00001	<0.00001	0%	<0.00001	<0.00001	0%
Molybdenum (Mo)-Total	mg/L	0.0136	0.0089	42%	0.0089	0.0088	112%	0.0403	0.037	9%	0.037	0.0361	2%	0.0225	0.0244	-8%
Nickel (Ni)-Total	mg/L	0.0007	0.00076	141%	0.00076	0.00076	0%	0.00076	0.00076	0%	0.00076	0.00076	0%	0.00076	0.00076	0%
Phosphorus (P)-Total	mg/L	<1	<1	0%	<1	<1	0%	<1	<1	0%	<1	<1	0%	<1	<1	0%
Potassium (K)-Total	mg/L	0.40	0.40	0%	0.40	0.40	0%	0.40	0.40	0%	0.40	0.40	0%	0.40	0.40	0%
Rhenium (Re)-Total	mg/L	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%
Rubidium (Rb)-Total	mg/L	0.00	0.0026	0%	0.0026	0.0031	-1%	0.00	0.00	0%	0.00	0.002	2%	0.00	0.002	2%
Selenium (Se)-Total	mg/L	<0.002	<0.002	0%	<0.002	<0.002	0%	<0.002	<0.002	0%	<0.002	<0.002	0%	<0.002	<0.002	0%
Silicon (Si)-Total	mg/L	2.61	2.79	-7%	2.79	2.47	12%	2.61	2.47	12%	2.47	2.34	5%	2.61	2.47	7%
Silver (Ag)-Total	mg/L	<0.0001	<0.0001	0%	<0.0001	<0.0001	0%	<0.0001	<0.0001	0%	<0.0001	<0.0001	0%	<0.0001	<0.0001	0%
Sodium (Na)-Total	mg/L	7470	7200	4%	7200	6990	3%	7470	6990	6%	6990	6790	3%	7470	6990	6%
Strontium (Sr)-Total	mg/L	0.060	57.2	5%	57.2	54.6	5%	0.060	54.6	5%	54.6	54.6	0%	0.060	54.6	0%
Tellurium (Te)-Total	mg/L	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%
Thallium (Tl)-Total	mg/L	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%
Thorium (Th)-Total	mg/L	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%
Tin (Sn)-Total	mg/L	<0.001	<0.001	0%	<0.001	<0.001	0%	<0.001	<0.001	0%	<0.001	<0.001	0%	<0.001	<0.001	0%
Titanium (Ti)-Total	mg/L	0.0082	<0.005	60%	<0.005	<0.005	0%	<0.005	<0.005	0%	<0.005	<0.005	0%	<0.005	<0.005	0%
Tungsten (W)-Total	mg/L	<0.001	0.0014	0%	0.0014	0.0016	-13%	0.0014	0.0017	-30%	0.0017	0.0021	-8%	0.0014	0.0021	-33%
Uranium (U)-Total	mg/L	<0.0005	<0.00005	0%	<0.0005	<0.00005	0%	<0.0005	<0.00005	0%	<0.0005	<0.00005	0%	<0.0005	<0.00005	0%
Vanadium (V)-Total	mg/L	0.00	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%
Yttrium (Y)-Total	mg/L	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%
Zinc (Zn)-Total	mg/L	0.503	0.279	57%	0.279	0.285	-2%	0.503	0.285	-43%	0.285	0.285	0%	0.503	0.285	-43%
Zirconium (Zr)-Total	mg/L	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%	<0.0005	<0.0005	0%
Dissolved Metals																
Aluminum (Al)-Dissolved	mg/L	<0.005	<0.005	0%	<0.005	<0.005	0%									

Table N2: Comparison of Duplicate Samples

Field Sample ID / Unique ID	Units	Duplicate		RPD	Duplicate		RPD	Duplicate		RPD	Duplicate		RPD
		10WBW001-03b	10WBW001-04b		10WBW001-15	10WBW001-16		10WBW001-25	10WBW001-26		10WBW001-02a	10WBW001-04a	
Sample From		Westbay Port	Westbay Port		Westbay airlift	Westbay airlift		Westbay airlift	Westbay airlift		Other	Other	
Sample Label		10WBW001- Zone 10-Port Initial-S03b	10WBW001- Zone 10-Port Initial-D-S04b		10WBW001- Zone 10-Airlift Purge-S15	10WBW001- Zone 10-Airlift Final-S16D		10WBW001- Zone 1-Airlift Final-S25	10WBW001- Zone 1-Airlift Final-S26D		10WBW001 Drill Tank	10WBW001 Drill Tank Dup	
Sample Zone		10	10		10	10		1	1		n/a	n/a	
Location of port in zone		Top	Top		Bottom	Bottom		Middle	Middle		n/a	n/a	
Zone port drillhole depth		63.5	63.5		107.50	107.50		554.00	554.00		n/a	n/a	
Total Litres purged from zone before sample was taken		0	2		3008	3008		3065	3065		n/a	n/a	
Zone volumes purged before sample was taken		0.0	0.3		11.0	11.0		26.2	26.2		n/a	n/a	
ALS DATA													
ALS Date Sampled		09-JUL-10	09-JUL-10		21-JUL-10	21-JUL-10		25-JUL-10	25-JUL-10		25-APR-10	25-APR-10	
ALS Time Sampled		14:00	14:00		16:28	17:28		12:37	12:37		16:00	16:00	
Matrix		Water	Water		Water	Water		Water	Water		Water	Water	
Physical Tests													
Conductivity (EC)	uS/cm	27600	27500	0%	46500	46600	0%	47600	47600	0%	335	339	-1%
Density		1.00	1.01	-1%									
Hardness (as CaCO3)	mg/L	4960	5060	-2%	8360	9250	-10%	11500	11100	4%	57.8	59.8	-3%
pH	pH	7.37	7.42	-1%	7.35	7.39	-1%	7.65	7.72	-1%	7.20	7.26	-1%
Total Dissolved Solids	mg/L	18700	18500	1%	32200	32700	-2%	33300	32400	3%	197	202	-3%
Anions and Nutrients													
Alkalinity, Total (as CaCO3)	mg/L	66.3	64.8	2%	82.3	81.7	1%				35.6	35.2	1%
Chloride (Cl)	mg/L	9650	9610	0%	17700	18200	-3%	18700	18800	-1%	83.4	82.5	1%
Fluoride (F)	mg/L	<5	<5		<1	<1		<1	<1		0.069	0.069	0%
Nitrate (as N)	mg/L	<5	<5		<1	<1		<1	<1		0.053	<0.050	
Nitrite (as N)	mg/L	<5	<5		<1	<1		<1	<1		<0.050	<0.050	
Sulfate (SO4)	mg/L	995	991	0%	1750	1790	-2%	0960	0964	0%	4.05	3.70	9%
Additional Anions and Nutrients													
Bicarbonate (HCO3)	mg/L	80.9	79.0	2%	100	99.6	0%	010	010	5%	43.4	43.0	1%
Carbonate (CO3)	mg/L	<5	<5		<5	<5		<5	<5		<5.0	<5.0	
Hydroxide (OH)	mg/L	<5	<5		<5	<5		<5	<5		<5.0	<5.0	
Ion Balance	%	101	103	-2%	96.6	109	-12%	95.5	89.8	6%	93.7	99.3	-6%
Nitrate and Nitrite as N	mg/L	<7.1	<7.1		<1.4	<1.4		<1.4	<1.4		<0.071	<0.071	
TDS (Calculated)	mg/L	16800	16900	-1%	30300	32600	-7%	31000	30500	2%	170	171	-1%
Total Metals													
Aluminum (Al)-Total	mg/L	<0.2	<0.2		<2	<2		<2	<2		0.014	0.021	-40%
Antimony (Sb)-Total	mg/L	<0.008	<0.008		<0.08	<0.08		<0.08	<0.08		<0.00040	<0.00040	
Arsenic (As)-Total	mg/L	<0.08	<0.08		0.083	0.090	-8%	0.296	0.101	98%	0.00076	0.00067	13%
Barium (Ba)-Total	mg/L	0.187	0.185	1%	0.102	0.113	-10%	0.054	0.059	-9%	0.0050	0.0057	-13%
Beryllium (Be)-Total	mg/L	<0.02	<0.02		<0.2	<0.2		<0.2	<0.2		<0.0010	<0.0010	
Boron (B)-Total	mg/L	1.34	1.37	-2%	2.32	2.31	0%	2.56	2.50	2%	<0.050	<0.050	
Cadmium (Cd)-Total	mg/L	<0.001	<0.001		<0.01	<0.01		<0.01	<0.01		<0.000050	<0.000050	
Calcium (Ca)-Total	mg/L	851	867	-2%	1590	1580	1%	4430	4380	1%	10.5	10.8	-3%
Chromium (Cr)-Total	mg/L	<0.016	0.024		0.61	0.66	-8%	0.62	0.74	-18%	<0.0050	<0.0050	
Cobalt (Co)-Total	mg/L	<0.004	<0.004		<0.04	<0.04		<0.04	<0.04		<0.0020	<0.0020	
Copper (Cu)-Total	mg/L	<0.02	<0.02		<0.2	<0.2		<0.2	<0.2		0.0040	0.0054	-30%
Iron (Fe)-Total	mg/L	3.53	3.65	-3%	7.15	7.14	0%	0.15	0.16	-6%	0.118	0.149	-23%
Lead (Pb)-Total	mg/L	<0.002	<0.002		<0.02	<0.02		<0.02	<0.02		0.00063	0.00018	111%
Lithium (Li)-Total	mg/L	0.13	0.14	-7%	<1.2	<1.2		<1.2	<1.2		<0.010	<0.010	
Magnesium (Mg)-Total	mg/L	726	736	-1%	1290	1290	0%	0051	0053	-4%	8.59	8.73	-2%
Manganese (Mn)-Total	mg/L	1.04	1.06	-2%	1.73	1.76	-2%	0.62	0.64	-4%	0.0066	0.0072	-9%
Mercury (Hg)-Total	mg/L	<0.0001	<0.0001		<0.0001	<0.0001		<0.0001	<0.0001		<0.00010	<0.00010	
Molybdenum (Mo)-Total	mg/L	0.0244	0.0237	3%	<0.02	<0.02		<0.02	<0.02		<0.0050	<0.0050	
Nickel (Ni)-Total	mg/L	0.0138	0.0144	-4%	<0.04	<0.04		0.068	0.074	-8%	<0.0020	<0.0020	
Potassium (K)-Total	mg/L	114	116	-2%	294	292	1%	044	045	-3%	3.13	3.14	0%
Selenium (Se)-Total	mg/L	<0.4	<0.4		<0.4	<0.4		<0.4	<0.4		0.00058	0.00057	2%
Silver (Ag)-Total	mg/L	<0.002	<0.002		<0.02	<0.02		<0.02	<0.02		<0.00050	<0.00050	
Sodium (Na)-Total	mg/L	4860	4930	-1%	9260	9580	-3%	7420	7870	-6%	43.0	43.9	-2%
Thallium (Tl)-Total	mg/L	<0.002	<0.002		<0.02	<0.02		<0.02	<0.02		<0.00010	<0.00010	
Tin (Sn)-Total	mg/L	<0.05	<0.05		<0.06	<0.06		<0.06	<0.06		<0.050	<0.050	
Titanium (Ti)-Total	mg/L	<0.012	<0.012		<0.12	<0.12		<0.12	<0.12		<0.0010	<0.0010	
Uranium (U)-Total	mg/L	<0.002	<0.002		<0.02	<0.02		<0.02	<0.02		<0.00010	<0.00010	
Vanadium (V)-Total	mg/L	<0.1	<0.1		0.20	0.22	-10%	0.21	0.23	-9%	<0.0010	<0.0010	
Zinc (Zn)-Total	mg/L	<0.08	<0.08		<0.8	<0.8		<0.8	<0.8		0.0131	0.0252	-63%
Dissolved Metals													
Aluminum (Al)-Dissolved	mg/L	0.13	<0.1		<1	<1		<1	<1		<0.010	<0.010	
Antimony (Sb)-Dissolved	mg/L	<0.008	<0.008		<0.08	<0.08		<0.08	<0.08		<0.00040	<0.00040	
Arsenic (As)-Dissolved	mg/L	<0.08	<0.08		0.091	0.097	-6%	0.08	0.090		0.00066	0.00068	-3%
Barium (Ba)-Dissolved	mg/L	0.186	0.188	-1%	0.100	0.097	3%	0.051	0.052	-2%	0.0040	0.0042	-5%
Beryllium (Be)-Dissolved	mg/L	<0.01	<0.01		<0.1	<0.1		<0.1	<0.1		<0.0010	<0.0010	
Boron (B)-Dissolved	mg/L	1.31	1.38	-5%	2.23	2.32	-4%	2.87	2.74	5%	<0.050	<0.050	
Cadmium (Cd)-Dissolved	mg/L	<0.001	<0.001		<0.01	<0.01		<0.01	<0.01		<0.000050	<0.000050	
Calcium (Ca)-Dissolved	mg/L	822	837	-2%	1420	1560	-9%	4520	4360	4%	10.1	10.3	-2%
Chromium (Cr)-Dissolved	mg/L	0.0178	0.0264	-39%	0.747	0.874	-16%	0.351	0.532	-41%	<0.0050	<0.0050	
Cobalt (Co)-Dissolved	mg/L	<0.002	<0.002		<0.02	<0.02		<0.02	<0.02		<0.0020	<0.0020	
Copper (Cu)-Dissolved	mg/L	<0.012	<0.012		0.19	<0.12		<0.12	<0.12		0.0028	0.0028	0%
Iron (Fe)-Dissolved	mg/L	1.88	1.63	14%	5.77	6.25	-8%	<0.15	<0.15		0.072	0.075	-4%
Lead (Pb)-Dissolved	mg/L	<0.002	<0.002		<0.02	<0.02		<0.02	<0.02		0.00015	0.00012	22%
Lithium (Li)-Dissolved	mg/L	0.128	0.136	-6%	<0.6	<0.6		<0.6	<0.6		0.0034	<0.0030	
Magnesium (Mg)-Dissolved	mg/L	707	721	-2%	1170	1300	-11%	0046	0045	2%	7.90	8.28	-5%
Manganese (Mn)-Dissolved	mg/L	1.01	1.01	0%	1.56	1.72	-10%	0.544	0.53	2%	0.0054	0.0056	-4%
Mercury (Hg)-Dissolved	mg/L	<0.0001	<0.0001		<0.0001	<0.0001		<0.0001	<0.0001		<0.00010	<0.00010	
Molybdenum (Mo)-Dissolved	mg/L	0.0240	0.0239	0%	<0.02	<0.02		<0.02	<0.02		<0.0050	<0.0050	
Nickel (Ni)-Dissolved	mg/L	0.0146	0.0159	-9%	<0.02	<0.02		0.061	0.066	-8%	<0.0020	<0.0020	
Potassium (K)-Dissolved	mg/L	129	131	-2%	206	294	-35%	039	037	4%	2.47	2.67	-8%
Selenium (Se)-Dissolved	mg/L	<0.4	<0.4		<0.4	<0.4		<0.4	<0.4		0.00044	0.00060	-31%
Silver (Ag)-Dissolved	mg/L	<0.002	<0.002		<0.02	<0.02		<0.02	<0.02		<0.00010	<0.00010	
Sodium (Na)-Dissolved	mg/L	4470	4540	-2%	7970	9450	-17%	6730	6260	7%	40.0	42.0	-5%
Thallium (Tl)-Dissolved	mg/L	<0.001	<0.001		<0.01	0.010		<0.01	<0.01		<0.00010	<0.00010	
Tin (Sn)-Dissolved	mg/L	<0.05	<0.05		<0.05	<0.05		<0.05	<0.05		<0.050	<0.050	
Titanium (Ti)-Dissolved	mg/L	0.0135	0.0081	50%	<0.06	<0.06		<0.06	<0.06		<0.0010	<0.0010	
Uranium (U)-Dissolved	mg/L	<0.002	<0.002		<0.02	<0.02		<0.02	<0.02		<0.00010	<0.00010	
Vanadium (V)-Dissolved	mg/L	0.077	0.099	-25%	0.259	0.292	-12%	0.122	0.174	-35%	<0.0010	<0.0010	
Zinc (Zn)-Dissolved	mg/L	0.026	0.022	17%	0.22	<0.2		<0.2	<0.2		0.0032	0.0038	-17%
Isotope Chemistry													
Delta 2H x 1000		-110.12	-109.57	1%	-77.72	-77.67	0%	-138.13	-138.57	0%	-19.16	-19.25	0%
Delta 18O x 1000		-14	-13.96	0%	-10	-10.18	-2%	-19.06	-19.07	0%			

RPDs greater than 20% are highlighted, to show parameters above the recommended duplicate limits.

Table N3: Ion Balance Assessment

Sample label	Alkalinity, Total (as CaCO3)	Chloride (Cl)	Sulfate (SO4)	Calcium (Ca)- Dissolved	Magnesium (Mg)- Dissolved	Potassium (K)- Dissolved	Sodium (Na)- Dissolved	Cation Balance	Anion Balance	Ion Balance
Units	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	meq/L	meq/L	% diff
Doris Lake Winter	34.4	76.6	3.44	9.3	7.37	2.31	38	2.78	2.92	2.38
10WBW001 Drill Tank	35.6	83.4	4.05	10.1	7.9	2.47	40	2.96	3.15	3.10
10WBW001 Casing Flow	52.9	1960	195	111	140	34.2	1110	66.19	60.33	4.63
10WBW001 Drill Tank Dup	35.2	82.5	3.7	10.3	8.28	2.67	42	3.09	3.10	0.25
equipment blank DI										
10WBW001-Zone 1-Port Initial-S01b		18200	1020	4390	172	54	6840	531.98	533.91	0.18
10WBW001-Zone 6-Port Initial-S02b	87.3	20100	2090	1640	1430	251	9080	600.69	611.46	0.89
10WBW001-Zone 10-Port Initial-S03b	66.3	9650	995	822	707	129	4470	296.83	293.87	0.50
10WBW001-Zone 10-Port InitialD-S04b	64.8	9610	991	837	721	131	4540	301.83	292.63	1.55
Doris Lake Summer	31.8	60.3	2.42	9.7	5.96	2.11	29.6	2.32	2.38	1.48
10WBW001-Zone 10-Airlift Purge-S12	90.6	15200	1490	1230	990	225	7130	458.58	461.00	0.26
10WBW001-Zone 10-Airlift Purge-S14	83.3	17100	1700	1340	1070	245	7840	502.03	518.75	1.64
10WBW001-Zone 10-Airlift Purge-S15	82.3	17700	1750	1420	1170	206	7970	518.91	536.67	1.68
10WBW001-Zone 10-Airlift Final-S16D	81.7	18200	1790	1560	1300	294	9450	603.18	551.58	4.47
10WBW001-Zone 1-Port Purge-S17		19100	1010	4480	80.3	42.5	6810	527.33	559.06	2.92
10WBW001-Zone 1-Airlift Purge - S20		19000	997	4260	65.6	39.1	6480	500.71	555.97	5.23
RO Water	<5	0.65	<0.5	0.75	0.12	<0.5	1.4			
10WBW001-Zone 1-Airlift Final-S25		18700	960	4520	46.1	38.5	6730	522.93	546.75	2.23
10WBW001-Zone 1-Airlift Final-S26D		18800	964	4360	45	37	6260	494.39	549.65	5.29
10WBW001-Zone 6-Airlift Purge -S28	63.4	15900	1690	1150	1070	170	6450	430.20	484.34	5.92
10WBW001-Zone 6-Airlift Purge-S31	67.7	16500	1760	1330	1270	186	7910	519.52	502.79	1.64
10WBW001-Zone 6-Airlift Final-S33	70.8	17100	1820	1390	1310	194	8160	536.88	521.00	1.50
Westbay Sampler Bottles Equipment blank	<5	7.03	<0.5	<0.5	0.24	<0.5	1.4			
10WBW001-Zone 1-Port Final-S35		19000	981	4960	69.5	39	7290	571.18	555.64	1.38
10WBW001-Zone 6-Port Final-S36	44.2	9130	940	749	702	117	4130	277.69	277.64	0.01
10WBW001-Zone 10-Port Final-S37	49.7	11500	1160	1010	849	160	5400	359.12	349.09	1.42
10WBW001-Zone 1-Port after 2mths-S100	<2	19000	980	4920	64.1	39	7200			
10WBW001-Zone 6-Port after 2mths-S101	44.2	13400	1390	1100	964	160	6010	399.60	407.29	0.95
10WBW001-Zone 10-Port after 2mths-S102	77.3	13100	1230	1110	869	173	5780	382.61	396.17	1.74
10WBW001-Zone 6-Airlift 160L sample-S103	72.4	19000	2020	1550	1490	233	9130	602.84	578.72	2.04
Gas Can Rinsate blank	<2	<0.5	<0.5	0.224	<0.1	<2	<2			
10WBW001-Zone 10-Port after bulk-S105	106	16500	1580	1560	1250	249	8700	565.31	499.80	6.15
10WBW001-Zone 1-Port after bulk-S106	<2	18400	935	4730	68.1	40	6910			
10WBW001-Zone 6-Airlift 80L sample-S107	76.5	19100	2000	1520	1450	229	8980	591.43	581.20	0.87
10WBW001-Zone 6-Port after bulk-S108	43.7	14200	1500	1160	1080	172	6810	447.22	432.10	1.72
10WBW002-Zone 1-Port Initial-S01	56	114000	<100	72100	113	39	655			
10WBW002-Zone 1-Port Purge-S02	59.5	123000	<100	79800	124	52	300			
10WBW002-Zone 1-Port Purge-S109a				74700	110	<200	1680			
10WBW002-Zone 1-Port Purge-S109b										
Glycol & water mix from inside Westbay 10WBW002	42.8	46800	<500	29400	65	<200	<200			
10WBW002-Zone 1-Port Purge-S121	59	133000	<2500	73100	113	<200	490			
Glycol & water mix prepared at camp	46.1	53	<50	8.55	5.9	31	30			
Spyder Lake	7.9	7.58	1.63	3	1.42	0.72	3.8	0.45	0.41	5.23
10WBW004 - Drill Tank Beginning	41.9	16400	50	8320	84.7	83	439	443.35	463.85	2.26
10WBW004 - Drill Tank End	13	7530	5.28	4330	18.7	12.6	62.7	220.65	212.48	1.89
10WBW004 - Zone 6-Port Initial-S123	35.8	12100	244	5050	311	47	1820	357.91	346.64	1.60
10WBW004 - Zone 6-Port Purge-S124	35.5	12400	264	4630	312	47	1820	337.04	355.50	2.67
10WBW004 - Zone 6-Port Purge-S125	35.3	12400	260	4580	309	47	1790	332.99	355.41	3.26
10WBW004 - Zone 6-Port Purge-S126	40	13700	336	4180	404	48	2410	347.83	393.71	6.19
10WBW004 - Zone 6-Port Purge-S128	48.7	12600	322	4230	365	48	2200	337.99	362.61	3.51
10WBW004 - Zone 6-Port Purge-S129	50.5	13400	349	4350	425	50	2510	362.44	385.74	3.11
10WBW004 - Zone 6-Port Purge-S130	53	13400	347	4620	432	53	2600	380.48	385.75	0.69
10WBW004 - Zone 6-Port Purge Final Dec-S131	53.5	12800	330	4080	387	49	2330	337.99	368.50	4.32

Table N4: Evaluation of Blank Samples

Sample label	Units	10WBW001-Zone 6-Port Final-S36	equipment blank DI	% of ground water sample	RO Water	% of ground water sample	Westbay Sampler Bottles Equipment blank	% of ground water sample	Gas Can Rinsate blank	% of ground water sample	10WBW004 Rinsate blank	% of ground water sample
Field Sample ID		10WBW001-36	10WBW001-05		10WBW001-22		10WBW001-34		10WBW001-104		10WBW004-127	
Sample Comments		Groundwater sample for comparison with blank samples	Equipment blank DI water		RO blank		Rinse blank of Westbay sampler probe bottles		DI water rinsate of gas cans used in bulk samples.		Rinsate blank of Westbay sample probe	
ALS DATA												
ALS File No.		L917645	L880950		L915201		L915201		L948685		L960194	
Date Lab Received		09-Aug-10 09:10	27-Apr-10 15:23		01-Aug-10 11:24		01-Aug-10 11:24		29-Oct-10 10:28		03-Dec-10 17:00	
ALS Report Date		20-Aug-10	06-May-10		13-Aug-10		13-Aug-10		22-Nov-10		22-Dec-10	
RESULTS OF ANALYSIS												
ALS SRK Sample ID		10WBW001-36	10WBW001-05		10WBW001-22		10WBW001-34		10WBW001-104		10WBW004-127	
ALS Date Sampled		05-AUG-10	25-APR-10		26-JUL-10		28-JUL-10		25-OCT-10		26-NOV-10	
ALS Time Sampled		09:00	00:00		09:10		11:00		00:00		18:00	
ALS Sample ID		L917645-2	L880950-5		L915201-8		L915201-22		L948685-1		L960194-8	
Matrix		Seawater	Water		Water		Water		Water		Water	
Physical Tests												
Conductivity (EC)	uS/cm	24600			5.97	0.0%	24.7	0.1%	<2		26.3	0.1%
Density									1.00		1.01	
Hardness (as CaCO3)	mg/L	4760			2.4	0.1%	<1		0.56	0.0%		
pH		7.83			6.38		6.11		7.29		6.34	
Salinity (EC)	g/L											
Total Dissolved Solids	mg/L	19600			10.0	0.1%	18.0	0.1%	<10		12	0.1%
Anions and Nutrients												
Alkalinity, Bicarbonate (as CaCO3)	mg/L								<2		<1.0	
Alkalinity, Carbonate (as CaCO3)	mg/L								<2		<1.0	
Alkalinity, Hydroxide (as CaCO3)	mg/L								<2		<1.0	
Alkalinity, Total (as CaCO3)	mg/L	44.2			<5		<5		<2		<1.0	
Ammonia as N	mg/L								<0.005			
Bromide (Br)	mg/L	21.2							<0.05		<0.050	
Chloride (Cl)	mg/L	9130			0.65	0.0%	7.03	0.1%	<0.5		6.33	0.1%
Fluoride (F)	mg/L	<0.75			<0.05		<0.05		<0.02		<0.020	
Nitrate (as N)	mg/L	<0.5			<0.05		<0.05		<0.005		<0.0050	
Nitrite (as N)	mg/L	<0.1			<0.05		<0.05		<0.001		<0.0010	
Ortho Phosphate as P	mg/L											
Total Phosphate as P	mg/L								0.0052			
Silicate (as SiO2)	mg/L								<1			
Sulfate (SO4)	mg/L	940			<0.5		<0.5		<0.5		<0.50	
Additional Anions and Nutrients												
Bicarbonate (HCO3)	mg/L				<5		<5					
Carbonate (CO3)	mg/L				<5		<5					
Hydroxide (OH)	mg/L				<5		<5					
Ion Balance	%				Low EC		Low EC					
Nitrate and Nitrite as N	mg/L				<0.071		<0.071					
TDS (Calculated)	mg/L				2.9		8.7					
Total Metals												
Aluminum (Al)-Total	mg/L	0.0281	<0.010		<0.01		<0.01		0.0086	30.6%		
Antimony (Sb)-Total	mg/L	0.00745	<0.00040		<0.0004		<0.0004		<0.00001			
Arsenic (As)-Total	mg/L	0.003	<0.00040		<0.0004		<0.0004		<0.00005			
Barium (Ba)-Total	mg/L	0.130	<0.0030		<0.003		<0.003		0.00017	0.1%		
Beryllium (Be)-Total	mg/L	<0.0005	<0.0010		<0.001		<0.001		<0.000005			
Bismuth (Bi)-Total	mg/L	<0.0005							<0.00005			
Boron (B)-Total	mg/L	1.04	<0.050		<0.05		<0.05		0.0097	0.9%		
Cadmium (Cd)-Total	mg/L	<0.00012	<0.000050		<0.00005		0.000190		<0.000005			
Calcium (Ca)-Total	mg/L	0805	<0.50		<0.5		<0.5		<0.05			
Cesium (Cs)-Total	mg/L	0000							<0.000005			
Chromium (Cr)-Total	mg/L	0.00	<0.0050		<0.005		<0.005		<0.0005			
Cobalt (Co)-Total	mg/L	<0.0005	<0.0020		<0.002		<0.002		<0.00005			
Copper (Cu)-Total	mg/L	<0.001	<0.0010		0.0807		<0.001		0.0161			
Gallium (Ga)-Total	mg/L	<0.0005							<0.00005			
Iron (Fe)-Total	mg/L	1.60	<0.010		<0.01		0.037	2.3%	<0.03			
Lead (Pb)-Total	mg/L	<0.001	<0.00010		0.00244		0.00067		0.00114			
Lithium (Li)-Total	mg/L	0.093	<0.010		<0.01		<0.01		<0.0002			
Magnesium (Mg)-Total	mg/L	0739	<0.10		<0.1		<0.1		<0.1			
Manganese (Mn)-Total	mg/L	0.56	<0.0020		<0.002		0.0023	0.4%	<0.0002			
Mercury (Hg)-Total	mg/L		<0.00010		<0.0001		<0.0001		<0.00005			
Molybdenum (Mo)-Total	mg/L	0.0403	<0.0050		<0.005		<0.005		<0.00005			
Nickel (Ni)-Total	mg/L	0.00159	<0.0020		<0.002		<0.002		<0.0002			
Phosphorus (P)-Total	mg/L	<1							<0.3			
Potassium (K)-Total	mg/L	125	<0.10		<0.1		<0.1		<2			
Rhenium (Re)-Total	mg/L	<0.0005							<0.000005			
Rubidium (Rb)-Total	mg/L	000							<0.00002			
Selenium (Se)-Total	mg/L	<0.002	<0.00040		<0.0004		<0.0004		<0.0002			
Silicon (Si)-Total	mg/L	2.88							<0.05			
Silver (Ag)-Total	mg/L	<0.0002	<0.00050		<0.0001		<0.0001		0.0000058			
Sodium (Na)-Total	mg/L	4460	<1.0		<1		<1		<2			
Strontium (Sr)-Total	mg/L	0010							<0.005			
Tellurium (Te)-Total	mg/L	<0.0005							<0.00001			
Thallium (Tl)-Total	mg/L	<0.0005	<0.00010		<0.0001		<0.0001		<0.000002			
Thorium (Th)-Total	mg/L	<0.0005							<0.000005			
Tin (Sn)-Total	mg/L	<0.001	<0.050		<0.05		<0.05		<0.0002			
Titanium (Ti)-Total	mg/L	<0.005	<0.0010		<0.001		<0.001		<0.0002			
Tungsten (W)-Total	mg/L	0.0334							<0.00001			
Uranium (U)-Total	mg/L	<0.0005	<0.00010		<0.0001		<0.0001		0.0000020			
Vanadium (V)-Total	mg/L	<0.0005	<0.0010		<0.001				<0.00005			
Yttrium (Y)-Total	mg/L	<0.0005							<0.000005			
Zinc (Zn)-Total	mg/L	0.195	<0.0040		0.0408	20.9%	0.0300	15.4%	0.0056	2.9%		
Zirconium (Zr)-Total	mg/L	<0.0005							<0.00005			

Sample label	Units	10WBW001-Zone 6-Port Final-S36	equipment blank DI	% of ground water sample	RO Water	% of ground water sample	Westbay Sampler Bottles Equipment blank	% of ground water sample	Gas Can Rinsate blank	% of ground water sample	10WBW004 Rinsate blank	% of ground water sample
Field Sample ID		10WBW001-36	10WBW001-05		10WBW001-22		10WBW001-34		10WBW001-104		10WBW004-127	
Sample Comments		Groundwater sample for comparison with blank samples	Equipment blank DI water		RO blank		Rinse blank of Westbay sampler probe bottles		DI water rinsate of gas cans used in bulk samples.		Rinsate blank of Westbay sample probe	
Dissolved Metals												
Aluminum (Al)-Dissolved	mg/L	<0.005	<0.010		<0.01		<0.01		<0.003			
Antimony (Sb)-Dissolved	mg/L	0.00703	<0.00040		<0.0004		<0.0004		0.000021	0.3%		
Arsenic (As)-Dissolved	mg/L	<0.002	<0.00040		<0.0004		<0.0004		<0.00005			
Barium (Ba)-Dissolved	mg/L	0.120	<0.0030		<0.003		<0.003		0.00044	0.4%		
Beryllium (Be)-Dissolved	mg/L	<0.0005	<0.0010		<0.001		<0.001		<0.000005			
Bismuth (Bi)-Dissolved	mg/L	<0.0005							<0.00005			
Boron (B)-Dissolved	mg/L	0.94	<0.050		<0.05		<0.05		<0.005			
Cadmium (Cd)-Dissolved	mg/L	<0.00012	<0.000050		<0.00005		<0.00005		0.0000102			
Calcium (Ca)-Dissolved	mg/L	749			0.75	0.1%	<0.5		0.224	0.0%		
Cesium (Cs)-Dissolved	mg/L	0.00069							<0.000005			
Chromium (Cr)-Dissolved	mg/L	<0.001	<0.0050		<0.005		<0.005		<0.0005			
Cobalt (Co)-Dissolved	mg/L	<0.0005	<0.0020		<0.002		<0.002		<0.00005			
Copper (Cu)-Dissolved	mg/L	<0.001	<0.0010		0.0031		<0.001		0.0123			
Gallium (Ga)-Dissolved	mg/L	<0.0005							<0.00005			
Iron (Fe)-Dissolved	mg/L	0.06			<0.03		<0.03		<0.03			
Lead (Pb)-Dissolved	mg/L	<0.001	<0.00010		<0.0001		<0.0001		0.00114			
Lithium (Li)-Dissolved	mg/L	0.087	<0.0030		<0.003		<0.003		<0.0002			
Magnesium (Mg)-Dissolved	mg/L	702			0.12	0.0%	0.24	0.0%	<0.1			
Manganese (Mn)-Dissolved	mg/L	0.53			<0.005		<0.005		<0.0002			
Mercury (Hg)-Dissolved	mg/L	<	<0.00010		<0.0001		<0.0001		<0.00005			
Molybdenum (Mo)-Dissolved	mg/L	0.0379	<0.0050		<0.005		<0.005		<0.00005			
Nickel (Ni)-Dissolved	mg/L	0.00076	<0.0020		<0.002		<0.002		<0.0002			
Phosphorus (P)-Dissolved	mg/L	<1							<0.3			
Potassium (K)-Dissolved	mg/L	117			<0.5		<0.5		<2			
Rhenium (Re)-Dissolved	mg/L	<0.0005							<0.000005			
Rubidium (Rb)-Dissolved	mg/L	000							<0.00002			
Selenium (Se)-Dissolved	mg/L	<0.002	<0.00040		<0.0004		<0.0004		<0.0002			
Silicon (Si)-Dissolved	mg/L	2.48							<0.05			
Silver (Ag)-Dissolved	mg/L	<0.0002	<0.00010		<0.0001		<0.0001		<0.000005			
Sodium (Na)-Dissolved	mg/L	4130			1.4	0.0%	1.4	0.0%	<2			
Strontium (Sr)-Dissolved	mg/L	0009							<0.005			
Tellurium (Te)-Dissolved	mg/L	<0.0005							<0.00001			
Thallium (Tl)-Dissolved	mg/L	<0.0005	<0.00010		<0.0001		<0.0001		<0.000002			
Thorium (Th)-Dissolved	mg/L	<0.0005							<0.000005			
Tin (Sn)-Dissolved	mg/L	<0.001	<0.050		<0.05		<0.05		<0.0002			
Titanium (Ti)-Dissolved	mg/L	<0.005	<0.0010		<0.001		<0.001		<0.0002			
Tungsten (W)-Dissolved	mg/L	0.0316							<0.00001			
Uranium (U)-Dissolved	mg/L	<0.0005	<0.00010		<0.0001		<0.0001		<0.000002			
Vanadium (V)-Dissolved	mg/L	<0.0005	<0.0010		<0.001		<0.001		<0.00005			
Yttrium (Y)-Dissolved	mg/L	<0.0005							<0.000005			
Zinc (Zn)-Dissolved	mg/L	0.02	<0.0020		0.0030	16.1%	0.0031	16.7%	0.0109	58.6%		
Zirconium (Zr)-Dissolved	mg/L	<0.0005							<0.00005			
Delta 2H x 1000		-117.72	-144.31		-149.55							
Delta 18O x 1000		-15.00	-15.60		-18.97							
Parameters with detectable concentrations in blanks are highlighted.												

Table N5: Comparison of Airlift and Port Samples

Field Sample ID / Unique ID	Units	Airlift vs Port		RPD	Airlift vs Port		RPD	Airlift vs Port		RPD	Airlift vs Port		RPD
		10WBW001-33	10WBW001-36		10WBW001-26	10WBW001-35		10WBW001-1-16	10WBW001-37		10WBW001-103	10WBW001-108	
Sample From		Westbay airlift	Westbay Port		Westbay airlift	Westbay Port		Westbay airlift	Westbay Port		Westbay airlift	Westbay Port	
Sample label for graph		10WBW001 Zone 6-Airlift Final-S33	10WBW001 Zone 6-Port Final-S36		10WBW001 Zone 1-Airlift Final-S26D	10WBW001 Zone 1-Port Final-S35		10WBW001 Zone 1-Airlift Final-S16D	10WBW001 Zone 1-Port Final-S37		10WBW001 Zone 6-Airlift 160L sample-S103	10WBW001 Zone 6-Port after bulk-S108	
Sample Zone		6	6		1	1		10	10		6	6	
Location of port in zone		Bottom	Top		Middle	Top		Bottom	Top		Bottom	Top	
Zone port drillhole depth		274.00	246.0		554.00	548.0		107.50	63.5		274.00	246.0	
Total Litres purged from zone before sample was taken		6433	8096		3065	3186		3008	3008		10639	13592	
Zone volumes purged before sample was taken		36.7	46.6		26.2	27.4		11.0	11.0		61.7	79.3	
ALS DATA													
ALS Date Sampled		27-JUL-10	05-AUG-10		25-JUL-10	04-AUG-10		21-JUL-10	05-AUG-10		25-OCT-10	01-NOV-10	
ALS Time Sampled		15:21	09:00		12:37	13:42		17:28	11:40		00:00	15:00	
Matrix		Water	Seawater		Water	Seawater		Water	Seawater		Water	BOTH	
Physical Tests													
Conductivity (EC)	uS/cm	44400	24600	57%	47600	46600	2%	46600	30300	42%	48500	37000	27%
Density												1.03	
Hardness (as CaCO3)	mg/L	8870	4760	60%	11100	12700	-13%	9250	6030	42%	10000	7340	31%
pH	pH	7.43	7.83	-5%	7.72	7.43	4%	7.39	7.47	-1%	7.04	7.59	-8%
Salinity (EC)	g/L										32.4	23.5	32%
Total Dissolved Solids	mg/L	30400	19600	43%	32400	47800	-38%	32700	23100	34%	35400	25500	33%
Anions and Nutrients													
Alkalinity, Total (as CaCO3)	mg/L	70.8	44.2	46%				81.7	49.7	49%	72.4	43.7	49%
Ammonia as N	mg/L										3.14	2.32	30%
Bromide (Br)	mg/L		21.2			100			27.6		49.1	41.3	17%
Chloride (Cl)	mg/L	17100	09130	61%	18800	19000	-1%	18200	11500	45%	19000	14200	29%
Fluoride (F)	mg/L	<1	<0.75		<1	<0.75		<1	<0.75		0.091	<0.75	
Nitrate (as N)	mg/L	<1	<0.5		<1	<0.5		<1	<0.5		<0.5	<0.5	
Nitrite (as N)	mg/L	<1	<0.1		<1	<0.1		<1	<0.1		<0.1	<0.1	
Total Phosphate as P	mg/L										0.0262	0.0162	47%
Silicate (as SiO2)	mg/L										6.1	5.8	5%
Sulfate (SO4)	mg/L	1820	0940	64%	0964	0981	-2%	1790	1160	43%	2020	1500	30%
Total Metals													
Aluminum (Al)-Total	mg/L	<2	0.0281		<2	0.0992		<2	0.0146		0.0318	0.0059	137%
Antimony (Sb)-Total	mg/L	<0.08	0.00745		<0.08	<0.0005		<0.08	0.00349		0.00127	0.00461	-114%
Arsenic (As)-Total	mg/L	0.121	0.003	192%	0.101	<0.002		0.090	<0.002		0.007	<0.002	
Barium (Ba)-Total	mg/L	0.107	0.130	-19%	0.059	0.051	14%	0.113	0.179	-45%	0.117	0.169	-36%
Beryllium (Be)-Total	mg/L	<0.2	<0.0005		<0.2	<0.0005		<0.2	<0.0005		<0.0005	<0.0005	
Bismuth (Bi)-Total	mg/L		<0.0005			<0.0005			<0.0005		<0.0005	<0.0005	
Boron (B)-Total	mg/L	1.91	1.04	59%	2.50	2.93	-16%	2.31	1.51	42%	2.65	1.50	55%
Cadmium (Cd)-Total	mg/L	<0.01	<0.00012		<0.01	<0.00012		<0.01	<0.00012		<0.00005	<0.00005	
Calcium (Ca)-Total	mg/L	1280	805	46%	4380	5070	-15%	1580	1020	43%	1600	1170	31%
Cesium (Cs)-Total	mg/L		0.00072			0.00105			0.00097		0.00155	0.00095	48%
Chromium (Cr)-Total	mg/L	0.86	0.00	199%	0.74	0.01	197%	0.66	0.0030	198%	<0.0005	<0.0005	
Cobalt (Co)-Total	mg/L	<0.04	<0.0005		<0.04	<0.0005		<0.04	<0.0005		0.000381	0.000103	115%
Copper (Cu)-Total	mg/L	<0.2	<0.001		<0.2	0.0018		<0.2	<0.001		<0.0005	0.00061	
Gallium (Ga)-Total	mg/L		<0.0005			<0.0005			<0.0005		<0.0005	<0.0005	
Iron (Fe)-Total	mg/L	3.54	1.60	75%	0.16	0.46	-96%	7.14	3.95	58%	4.53	2.28	66%
Lead (Pb)-Total	mg/L	<0.02	<0.001		<0.02	0.0013		<0.02	<0.001		<0.0003	<0.0003	
Lithium (Li)-Total	mg/L	<1.2	0.093		<1.2	0.37		<1.2	0.128		0.228	0.131	54%
Magnesium (Mg)-Total	mg/L	1210	739	48%	53	71	-29%	1290	867	39%	1510	1080	33%
Manganese (Mn)-Total	mg/L	1.81	0.56	106%	0.64	0.72	-11%	1.76	1.09	47%	2.08	0.892	80%
Mercury (Hg)-Total	mg/L	<0.0001			<0.0001			<0.0001			<0.00005		
Molybdenum (Mo)-Total	mg/L	<0.02	0.0403		<0.02	0.0136		<0.02	0.0225		0.0140	0.0361	-88%
Nickel (Ni)-Total	mg/L	<0.04	0.00159		0.074	0.00437	178%	<0.04	0.00237		0.00095	0.00120	-23%
Phosphorus (P)-Total	mg/L		<1			<1			<1		<1	<1	
Potassium (K)-Total	mg/L	203	125	48%	045	040	12%	292	166	55%	240	172	33%
Rhenium (Re)-Total	mg/L		<0.0005			<0.0005			<0.0005		<0.0005	<0.0005	
Rubidium (Rb)-Total	mg/L		0.0765			0.0500			0.0816		0.1420	0.102	33%
Selenium (Se)-Total	mg/L	<0.4	<0.002		<0.4	<0.002		<0.4	<0.002		<0.002	<0.002	
Silicon (Si)-Total	mg/L		2.88			2.61			2.12		3.68	3.82	-4%
Silver (Ag)-Total	mg/L	<0.02	<0.0002		<0.02	<0.0002		<0.02	<0.0002		<0.0001	0.00018	
Sodium (Na)-Total	mg/L	7450	4460	50%	7870	7470	5%	9580	5590	53%	9350	6790	32%
Strontium (Sr)-Total	mg/L		10			60			11.7		21.2	14.6	37%
Tellurium (Te)-Total	mg/L		<0.0005			<0.0005			<0.0005		<0.0005	<0.0005	
Thallium (Tl)-Total	mg/L	<0.02	<0.0005		<0.02	<0.0005		<0.02	<0.0005		<0.00005	<0.00005	
Thorium (Th)-Total	mg/L		<0.0005			<0.0005			<0.0005		<0.0005	<0.0005	
Tin (Sn)-Total	mg/L	<0.08	<0.001		<0.08	<0.001		<0.08	<0.001		<0.001	<0.001	
Titanium (Ti)-Total	mg/L	<0.12	<0.005		<0.12	0.0082		<0.12	<0.005		<0.005	<0.005	
Tungsten (W)-Total	mg/L		0.0334			<0.001			0.0067		0.0056	0.0227	-121%
Uranium (U)-Total	mg/L	<0.02	<0.0005		<0.02	<0.0005	199%	<0.02	<0.0005		0.00023	0.000059	118%
Vanadium (V)-Total	mg/L	0.27	<0.0005		0.23	0.001		0.22	<0.0005		0.00054	<0.0005	
Yttrium (Y)-Total	mg/L		<0.0005			<0.0005			<0.0005		<0.0005	<0.0005	
Zinc (Zn)-Total	mg/L	<0.8	0.195		<0.8	0.503		<0.8	0.261		0.046	0.115	-86%
Zirconium (Zr)-Total	mg/L		<0.0005			<0.0005			<0.0005		<0.0005	<0.0005	
Dissolved Metals													
Aluminum (Al)-Dissolved	mg/L	<1	<0.005		<1	<0.005		<1	<0.005		<0.005	<0.005	
Antimony (Sb)-Dissolved	mg/L	<0.08	0.00703		<0.08	<0.0005		<0.08	0.00306		0.00121	0.00393	-106%
Arsenic (As)-Dissolved	mg/L	0.102	<0.002		0.090	<0.002		0.097	<0.002		0.0066	<0.002	
Barium (Ba)-Dissolved	mg/L	0.120	0.120	0%	0.052	0.052	0%	0.097	0.169	-54%	0.113	0.169	-40%
Beryllium (Be)-Dissolved	mg/L	<0.1	<0.0005		<0.1	<0.0005		<0.1	<0.0005		<0.0005	<0.0005	
Bismuth (Bi)-Dissolved	mg/L		<0.0005			<0.0005			<0.0005		<0.0005	<0.0005	

		Airlift vs Port		RPD	Airlift vs Port		RPD	Airlift vs Port		RPD	Airlift vs Port		RPD
Field Sample ID / Unique ID	Units	10WBW001-33	10WBW001-36		10WBW001-26	10WBW001-35		10WBW001-1-16	10WBW001-37		10WBW001-103	10WBW001-108	
Boron (B)-Dissolved	mg/L	1.97	0.94	71%	2.74	2.99	-9%	2.32	1.42	48%	2.64	1.48	56%
Cadmium (Cd)-Dissolved	mg/L	<0.01	<0.00012		<0.01	<0.00012		<0.01	<0.00012		<0.00005	<0.00005	
Calcium (Ca)-Dissolved	mg/L	1390	749	60%	4360	4960	-13%	1560	1010	43%	1550	1160	29%
Cesium (Cs)-Dissolved	mg/L		0.00069			0.00105			0.00092		0.00154	0.00097	45%
Chromium (Cr)-Dissolved	mg/L	0.682	<0.001		0.532	<0.001		0.874	<0.001		<0.0005	<0.0005	
Cobalt (Co)-Dissolved	mg/L	<0.02	<0.0005		<0.02	<0.0005		<0.02	<0.0005		0.000315	0.000091	110%
Copper (Cu)-Dissolved	mg/L	<0.12	<0.001		<0.12	<0.001		<0.12	<0.001		<0.0005	<0.0005	
Gallium (Ga)-Dissolved	mg/L		<0.0005			<0.0005			<0.0005		<0.0005	<0.0005	
Iron (Fe)-Dissolved	mg/L	3.32	0.06	193%	<0.15	<0.05		6.25	2.68	80%	4.31	0.503	158%
Lead (Pb)-Dissolved	mg/L	<0.02	<0.001		<0.02	<0.001		<0.02	<0.001		<0.003	<0.0003	
Lithium (Li)-Dissolved	mg/L	<0.6	0.087		<0.6	0.37		<0.6	0.121		0.223	0.127	55%
Magnesium (Mg)-Dissolved	mg/L	1310	0702	60%	0045	0070	-43%	1300	849	42%	1490	1080	32%
Manganese (Mn)-Dissolved	mg/L	1.96	0.53	115%	0.53	0.69	-26%	1.72	1.04	49%	2.03	0.888	78%
Mercury (Hg)-Dissolved	mg/L	<0.0001			<0.0001			<0.0001			<0.00005		
Molybdenum (Mo)-Dissolved	mg/L	<0.02	0.0379		<0.02	0.0128		<0.02	0.0211		0.0138	0.0345	-86%
Nickel (Ni)-Dissolved	mg/L	<0.02	0.00076		0.066	<0.0005		<0.02	<0.0005		0.00101	0.00158	-44%
Phosphorus (P)-Dissolved	mg/L		<1			<1			<1		<1	<1	
Potassium (K)-Dissolved	mg/L	194	117	50%	037	039	-5%	294	160	59%	233	172	30%
Rhenium (Re)-Dissolved	mg/L		<0.0005			<0.0005			<0.0005		<0.0005	<0.0005	
Rubidium (Rb)-Dissolved	mg/L		0.0725			0.0504			0.0766		0.1400	0.106	28%
Selenium (Se)-Dissolved	mg/L	<0.4	<0.002		<0.4	<0.002		<0.4	<0.002		<0.002	<0.002	
Silicon (Si)-Dissolved	mg/L		2.48			2.3			1.99		3.49	3.33	5%
Silver (Ag)-Dissolved	mg/L	<0.02	<0.0002		<0.02	<0.0002		<0.02	<0.0002		<0.0001	<0.0001	
Sodium (Na)-Dissolved	mg/L	8160	4130	66%	6260	7290	-15%	9450	5400	55%	9130	6810	29%
Strontium (Sr)-Dissolved	mg/L		9.0			58.9			11.3		21.1	14.6	36%
Tellurium (Te)-Dissolved	mg/L		<0.0005			<0.0005			<0.0005		<0.0005	<0.0005	
Thallium (Tl)-Dissolved	mg/L	<0.01	<0.0005		<0.01	<0.0005		0.010	<0.0005		<0.00005	<0.00005	
Thorium (Th)-Dissolved	mg/L		<0.0005			<0.0005			<0.0005		<0.0005	<0.0005	
Tin (Sn)-Dissolved	mg/L	<0.05	<0.001		<0.05	<0.001		<0.05	<0.001		<0.001	<0.001	
Titanium (Ti)-Dissolved	mg/L	<0.06	<0.005		<0.06	<0.005		<0.06	<0.005		<0.005	<0.005	
Tungsten (W)-Dissolved	mg/L		0.0316			<0.001			0.0059		0.0053	0.0231	-125%
Uranium (U)-Dissolved	mg/L	<0.02	<0.0005		<0.02	<0.0005		<0.02	<0.0005		0.000231	0.000058	120%
Vanadium (V)-Dissolved	mg/L	0.229	<0.0005		0.174	<0.0005		0.292	<0.0005		<0.0005	<0.0005	
Yttrium (Y)-Dissolved	mg/L		<0.0005			<0.0005			<0.0005		<0.0005	<0.0005	
Zinc (Zn)-Dissolved	mg/L	<0.2	0.02		<0.2	0.0897		<0.2	0.0504		0.0384	0.0295	26%
Zirconium (Zr)-Dissolved	mg/L		<0.0005			<0.0005			<0.0005		<0.0005	<0.0005	
Isotope Chemistry													
Delta 2H x 1000		-85.71	-117.72	-31%	-138.57	-138	0%	-77.67	-106.52	-31%			
Delta 18O x 1000		-10.9	-15	-32%	-19.07	-18.83	1%	-10.18	-13.49	-28%			

RPDs greater than 20% are highlighted, to show parameters with the greatest variation between samples.



SRK CONSULTING (CANADA) INC.
ATTN: MELISSA PITZ
SUITE 205
2100 AIRPORT DRIVE
SASKATOON SK S7L 6M6
Phone: 306-955-4732

Date Received: 29-OCT-10
Report Date: 22-NOV-10 09:12 (MT)
Version: FINAL

Certificate of Analysis

Lab Work Order #: L948685
Project P.O. #: NOT SUBMITTED
Job Reference:
Legal Site Desc:
C of C Numbers:

[This report shall not be reproduced except in full without the written authority of the Laboratory.]

ADDRESS: 75 Con Road, PO. Box 2801, Yellowknife, NT, X1A 2R2 Canada | Phone: +1 867 873 5593 | Fax: +1 867 920 4238
ALS CANADA LIMITED Part of the ALS Group A Campbell Brothers Limited Company

ALS LABORATORY GROUP ANALYTICAL REPORT

		Sample ID				
		Description				
		Sampled Date				
		Sampled Time				
		Client ID				
		L948685-1		L948685-2		
		WATER		WATER		
		25-OCT-10		25-OCT-10		
		10WBW001-104		10WBW001-103		
Grouping	Analyte					
WATER						
Physical Tests	Conductivity (uS/cm)	<2.0	48500			
	Hardness (as CaCO3) (mg/L)	0.56	10000			
	pH (pH)	7.29	7.04			
	Total Dissolved Solids (mg/L)	<10	35400			
Leachable Anions & Nutrients	Anion Sum (meq/L)	<0.10	580			
	Cation Sum (meq/L)	<0.10	603			
	Cation - Anion Balance (%)	0.0	2.0			
Anions and Nutrients	Alkalinity, Bicarbonate (as CaCO3) (mg/L)	<2.0				
	Alkalinity, Carbonate (as CaCO3) (mg/L)	<2.0				
	Alkalinity, Hydroxide (as CaCO3) (mg/L)	<2.0				
	Alkalinity, Total (as CaCO3) (mg/L)	<2.0	72.4			
	Ammonia as N (mg/L)	<0.0050	3.14			
	Bromide (Br) (mg/L)	<0.050	49.1			
	Chloride (Cl) (mg/L)	<0.50	19000			
	Fluoride (F) (mg/L)	<0.020	0.091			
	Nitrate (as N) (mg/L)	<0.0050	<0.50			
	Nitrite (as N) (mg/L)	<0.0010	<0.10			
	Total Phosphate as P (mg/L)	0.0052	0.0262			
	Silicate (as SiO2) (mg/L)	<1.0	6.1			
	Sulfate (SO4) (mg/L)	<0.50	2020			
Total Metals	Aluminum (Al)-Total (mg/L)	0.0086	0.0318			
	Antimony (Sb)-Total (mg/L)	<0.000010	0.00127			
	Arsenic (As)-Total (mg/L)	<0.000050	0.0070			
	Barium (Ba)-Total (mg/L)	0.00017	0.117			
	Beryllium (Be)-Total (mg/L)	<0.0000050	<0.00050			
	Bismuth (Bi)-Total (mg/L)	<0.000050	<0.00050			
	Boron (B)-Total (mg/L)	0.0097	2.65			
	Cadmium (Cd)-Total (mg/L)	<0.0000050	<0.000050			
	Calcium (Ca)-Total (mg/L)	<0.050	1600			
	Cesium (Cs)-Total (mg/L)	<0.0000050	0.00155			
	Chromium (Cr)-Total (mg/L)	<0.00050	<0.00050			
	Cobalt (Co)-Total (mg/L)	<0.000050	0.000381			
	Copper (Cu)-Total (mg/L)	0.0161	<0.00050			
	Gallium (Ga)-Total (mg/L)	<0.000050	<0.00050			
	Iron (Fe)-Total (mg/L)	<0.030	4.53			
	Lead (Pb)-Total (mg/L)	0.00114	<0.00030			

ALS LABORATORY GROUP ANALYTICAL REPORT

		Sample ID Description Sampled Date Sampled Time Client ID	L948685-1 WATER 25-OCT-10 10WBW001-104	L948685-2 WATER 25-OCT-10 10WBW001-103		
Grouping	Analyte					
WATER						
Total Metals	Lithium (Li)-Total (mg/L)	<0.00020	0.228			
	Magnesium (Mg)-Total (mg/L)	<0.10	1510			
	Manganese (Mn)-Total (mg/L)	<0.00020	2.08			
	Mercury (Hg)-Total (mg/L)	<0.000050	<0.000050			
	Molybdenum (Mo)-Total (mg/L)	<0.000050	0.0140			
	Nickel (Ni)-Total (mg/L)	<0.00020	0.00095			
	Phosphorus (P)-Total (mg/L)	<0.30	<1.0			
	Potassium (K)-Total (mg/L)	<2.0	240			
	Rhenium (Re)-Total (mg/L)	<0.0000050	<0.00050			
	Rubidium (Rb)-Total (mg/L)	<0.000020	0.142			
	Selenium (Se)-Total (mg/L)	<0.00020	<0.0020			
	Silicon (Si)-Total (mg/L)	<0.050	3.68			
	Silver (Ag)-Total (mg/L)	0.0000058	<0.00010			
	Sodium (Na)-Total (mg/L)	<2.0	9350			
	Strontium (Sr)-Total (mg/L)	<0.0050	21.2			
	Tellurium (Te)-Total (mg/L)	<0.000010	<0.00050			
	Thallium (Tl)-Total (mg/L)	<0.0000020	<0.000050			
	Thorium (Th)-Total (mg/L)	<0.0000050	<0.00050			
	Tin (Sn)-Total (mg/L)	<0.00020	<0.0010			
	Titanium (Ti)-Total (mg/L)	<0.00020	<0.0050			
	Tungsten (W)-Total (mg/L)	<0.000010	0.0056			
	Uranium (U)-Total (mg/L)	0.0000020	0.000230			
	Vanadium (V)-Total (mg/L)	<0.000050	0.00054			
	Yttrium (Y)-Total (mg/L)	<0.0000050	<0.00050			
	Zinc (Zn)-Total (mg/L)	0.0056	0.0456			
	Zirconium (Zr)-Total (mg/L)	<0.000050	<0.00050			
Dissolved Metals	Aluminum (Al)-Dissolved (mg/L)	<0.0030	<0.0050			
	Antimony (Sb)-Dissolved (mg/L)	0.000021	0.00121			
	Arsenic (As)-Dissolved (mg/L)	<0.000050	0.0066			
	Barium (Ba)-Dissolved (mg/L)	0.00044	0.113			
	Beryllium (Be)-Dissolved (mg/L)	<0.0000050	<0.00050			
	Bismuth (Bi)-Dissolved (mg/L)	<0.000050	<0.00050			
	Boron (B)-Dissolved (mg/L)	<0.0050	2.64			
	Cadmium (Cd)-Dissolved (mg/L)	0.0000102	<0.000050			
	Calcium (Ca)-Dissolved (mg/L)	0.224	1550			
	Cesium (Cs)-Dissolved (mg/L)	<0.0000050	0.00154			
	Chromium (Cr)-Dissolved (mg/L)	<0.00050	<0.00050			

ALS LABORATORY GROUP ANALYTICAL REPORT

Sample ID Description Sampled Date Sampled Time Client ID		L948685-1 WATER 25-OCT-10 10WBW001-104	L948685-2 WATER 25-OCT-10 10WBW001-103		
Grouping	Analyte				
WATER					
Dissolved Metals	Cobalt (Co)-Dissolved (mg/L)	<0.000050	0.000315		
	Copper (Cu)-Dissolved (mg/L)	0.0123	<0.00050		
	Gallium (Ga)-Dissolved (mg/L)	<0.000050	<0.00050		
	Iron (Fe)-Dissolved (mg/L)	<0.030	4.31		
	Lead (Pb)-Dissolved (mg/L)	0.00114	<0.0030		
	Lithium (Li)-Dissolved (mg/L)	<0.00020	0.223		
	Lithium (Li)-Dissolved (mg/L)	<0.00020	0.223		
	Magnesium (Mg)-Dissolved (mg/L)	<0.10	1490		
	Manganese (Mn)-Dissolved (mg/L)	<0.00020	2.03		
	Mercury (Hg)-Dissolved (mg/L)	<0.000050	<0.000050		
	Molybdenum (Mo)-Dissolved (mg/L)	<0.000050	0.0138		
	Nickel (Ni)-Dissolved (mg/L)	<0.00020	0.00101		
	Phosphorus (P)-Dissolved (mg/L)	<0.30	<1.0		
	Potassium (K)-Dissolved (mg/L)	<2.0	233		
	Rhenium (Re)-Dissolved (mg/L)	<0.0000050	<0.00050		
	Rubidium (Rb)-Dissolved (mg/L)	<0.000020	0.140		
	Selenium (Se)-Dissolved (mg/L)	<0.00020	<0.0020		
	Silicon (Si)-Dissolved (mg/L)	<0.050	3.49		
	Silicon (Si)-Dissolved (mg/L)	<0.050	3.49		
	Silver (Ag)-Dissolved (mg/L)	<0.0000050	<0.00010		
	Sodium (Na)-Dissolved (mg/L)	<2.0	9130		
	Strontium (Sr)-Dissolved (mg/L)	<0.0050	21.1		
	Tellurium (Te)-Dissolved (mg/L)	<0.000010	<0.00050		
	Thallium (Tl)-Dissolved (mg/L)	<0.0000020	<0.000050		
	Thorium (Th)-Dissolved (mg/L)	<0.0000050	<0.00050		
	Thorium (Th)-Dissolved (mg/L)	<0.0000050	<0.00050		
	Tin (Sn)-Dissolved (mg/L)	<0.00020	<0.0010		
	Titanium (Ti)-Dissolved (mg/L)	<0.00020	<0.0050		
	Tungsten (W)-Dissolved (mg/L)	<0.000010	0.0053		
	Uranium (U)-Dissolved (mg/L)	<0.0000020	0.000231		
	Vanadium (V)-Dissolved (mg/L)	<0.000050	<0.00050		
	Yttrium (Y)-Dissolved (mg/L)	<0.0000050	<0.00050		
	Zinc (Zn)-Dissolved (mg/L)	0.0109	0.0384		
	Zirconium (Zr)-Dissolved (mg/L)	<0.000050	<0.00050		

Reference Information

Test Method References:

ALS Test Code	Matrix	Test Description	Method Reference**
ALK-PCT-VA	Water	Alkalinity by Auto. Titration	APHA 2320 "Alkalinity"
This analysis is carried out using procedures adapted from APHA Method 2320 "Alkalinity". Total alkalinity is determined by potentiometric titration to a pH 4.5 endpoint. Bicarbonate, carbonate and hydroxide alkalinity are calculated from phenolphthalein alkalinity and total alkalinity values.			
ALK-PCT-VA	Water	Alkalinity by Auto. Titration	APHA 2320 Alkalinity
This analysis is carried out using procedures adapted from APHA Method 2320 "Alkalinity". Total alkalinity is determined by potentiometric titration to a pH 4.5 endpoint. Bicarbonate, carbonate and hydroxide alkalinity are calculated from phenolphthalein alkalinity and total alkalinity values.			
ALK-SCR-VA	Water	Alkalinity by colour or titration	EPA 310.2 OR APHA 2320
This analysis is carried out using procedures adapted from EPA Method 310.2 "Alkalinity". Total Alkalinity is determined using the methyl orange colourimetric method.			
OR			
This analysis is carried out using procedures adapted from APHA Method 2320 "Alkalinity". Total alkalinity is determined by potentiometric titration to a pH 4.5 endpoint. Bicarbonate, carbonate and hydroxide alkalinity are calculated from phenolphthalein alkalinity and total alkalinity values.			
ANIONS-BR-IC-VA	Water	Bromide by Ion Chromatography	APHA 4110 B.
This analysis is carried out using procedures adapted from APHA Method 4110 B. "Ion Chromatography with Chemical Suppression of Eluent Conductivity" and EPA Method 300.0 "Determination of Inorganic Anions by Ion Chromatography".			
ANIONS-CL-IC-VA	Water	Chloride by Ion Chromatography	APHA 4110 B.
This analysis is carried out using procedures adapted from APHA Method 4110 B. "Ion Chromatography with Chemical Suppression of Eluent Conductivity" and EPA Method 300.0 "Determination of Inorganic Anions by Ion Chromatography".			
ANIONS-F-IC-VA	Water	Fluoride by Ion Chromatography	APHA 4110 B.
This analysis is carried out using procedures adapted from APHA Method 4110 B. "Ion Chromatography with Chemical Suppression of Eluent Conductivity" and EPA Method 300.0 "Determination of Inorganic Anions by Ion Chromatography".			
ANIONS-NO2-IC-VA	Water	Nitrite by Ion Chromatography	APHA 4110 B.
This analysis is carried out using procedures adapted from APHA Method 4110 B. "Ion Chromatography with Chemical Suppression of Eluent Conductivity" and EPA Method 300.0 "Determination of Inorganic Anions by Ion Chromatography". Specifically, the nitrite detection is by UV absorbance and not conductivity.			
ANIONS-NO3-IC-VA	Water	Nitrate by Ion Chromatography	APHA 4110 B.
This analysis is carried out using procedures adapted from APHA Method 4110 B. "Ion Chromatography with Chemical Suppression of Eluent Conductivity" and EPA Method 300.0 "Determination of Inorganic Anions by Ion Chromatography". Specifically, the nitrate detection is by UV absorbance and not conductivity.			
ANIONS-SO4-IC-VA	Water	Sulfate by Ion Chromatography	APHA 4110 B.
This analysis is carried out using procedures adapted from APHA Method 4110 B. "Ion Chromatography with Chemical Suppression of Eluent Conductivity" and EPA Method 300.0 "Determination of Inorganic Anions by Ion Chromatography".			
EC-PCT-VA	Water	Conductivity (Automated)	APHA 2510 Auto. Conduc.
This analysis is carried out using procedures adapted from APHA Method 2510 "Conductivity". Conductivity is determined using a conductivity electrode.			
F-SIE-VA	Water	Fluoride by SIE	APHA 4500-F "Fluoride"
This analysis is carried out using procedures adapted from APHA Method 4500-F "Fluoride". Fluoride is determined using a selective ion electrode. This method has a significant negative interference (i.e. results could be biased low) when Al ³⁺ is present in the sample at a concentration greater than 2.5 mg/L.			
F-SIE-VA	Water	Fluoride by SIE	APHA 4500-F Fluoride
This analysis is carried out using procedures adapted from APHA Method 4500-F "Fluoride". Fluoride is determined using a selective ion electrode. This method has a significant negative interference (i.e. results could be biased low) when Al ³⁺ is present in the sample at a concentration greater than 2.5 mg/L.			
HARDNESS-CALC-VA	Water	Hardness	APHA 2340B
Hardness is calculated from Calcium and Magnesium concentrations, and is expressed as calcium carbonate equivalents.			
HG-DIS-CVAFS-VA	Water	Dissolved Mercury in Water by CVAFS	EPA SW-846 3005A & EPA 245.7
This analysis is carried out using procedures adapted from "Standard Methods for the Examination of Water and Wastewater" published by the American Public Health Association, and with procedures adapted from "Test Methods for Evaluating Solid Waste" SW-846 published by the United States Environmental Protection Agency (EPA). The procedures may involve preliminary sample treatment by filtration (EPA Method 3005A) and involves a cold-oxidation of the acidified sample using bromine monochloride prior to reduction of the sample with stannous chloride. Instrumental analysis is by cold vapour atomic fluorescence spectrophotometry (EPA Method 245.7).			
HG-TOT-CVAFS-VA	Water	Total Mercury in Water by CVAFS	EPA 245.7
This analysis is carried out using procedures adapted from "Standard Methods for the Examination of Water and Wastewater" published by the American Public Health Association, and with procedures adapted from "Test Methods for Evaluating Solid Waste" SW-846 published by the United States Environmental Protection Agency (EPA). The procedure involves a cold-oxidation of the acidified sample using bromine monochloride prior to reduction of the sample with stannous chloride. Instrumental analysis is by cold vapour atomic fluorescence spectrophotometry (EPA Method 245.7).			
IONBALANCE-VA	Water	Ion Balance Calculation	APHA 1030E

Reference Information

Cation Sum, Anion Sum, and Ion Balance (as % difference) are calculated based on guidance from APHA Standard Methods (1030E Checking Correctness of Analysis). Because all aqueous solutions are electrically neutral, the calculated ion balance (% difference of cations minus anions) should be near-zero.

Cation and Anion Sums are the total meq/L concentration of major cations and anions. Dissolved species are used where available. Minor ions are included where data is present. Ion Balance is calculated as:

$$\text{Ion Balance (\%)} = [\text{Cation Sum} - \text{Anion Sum}] / [\text{Cation Sum} + \text{Anion Sum}]$$

MET-D-L-HRMS-VA Water Diss. Metals in Water by HR-ICPMS EPA 200.8

Trace metals in water are analyzed by high resolution inductively coupled plasma mass spectrometry (HR-ICPMS) modified from US EPA Method 200.8, (Revision 5.5). The procedures may involve laboratory sample filtration modified from APHA Method 3030B.

MET-DIS-ICP-VA Water Dissolved Metals in Water by ICPOES EPA SW-846 3005A/6010B

This analysis is carried out using procedures adapted from "Standard Methods for the Examination of Water and Wastewater" published by the American Public Health Association, and with procedures adapted from "Test Methods for Evaluating Solid Waste" SW-846 published by the United States Environmental Protection Agency (EPA). The procedure involves filtration (EPA Method 3005A) and analysis by inductively coupled plasma - optical emission spectrophotometry (EPA Method 6010B).

MET-T-L-HRMS-VA Water Total Metals in Water by HR-ICPMS EPA 200.8

Trace metals in water are analyzed by high resolution inductively coupled plasma mass spectrometry (HR-ICPMS) modified from US EPA Method 200.8, (Revision 5.5). The procedures may involve preliminary sample treatment by acid digestion modified from APHA Method 3030E.

MET-TOT-ICP-VA Water Total Metals in Water by ICPOES EPA SW-846 3005A/6010B

This analysis is carried out using procedures adapted from "Standard Methods for the Examination of Water and Wastewater" published by the American Public Health Association, and with procedures adapted from "Test Methods for Evaluating Solid Waste" SW-846 published by the United States Environmental Protection Agency (EPA). The procedures may involve preliminary sample treatment by acid digestion, using either hotblock or microwave oven (EPA Method 3005A). Instrumental analysis is by inductively coupled plasma - optical emission spectrophotometry (EPA Method 6010B).

NH3-F-VA Water Ammonia by Fluorescence J. ENVIRON. MONIT., 2005, 7, 37-42, RSC

This analysis is carried out, on sulphuric acid preserved samples, using procedures modified from J. Environ. Monit., 2005, 7, 37 - 42, The Royal Society of Chemistry, "Flow-injection analysis with fluorescence detection for the determination of trace levels of ammonium in seawater", Roslyn J. Waston et al.

PH-MAN-VA Water pH by Manual Meter APHA 4500-H "pH Value"

This analysis is carried out using procedures adapted from APHA Method 4500-H "pH Value". The pH is determined in the laboratory using a pH electrode.

It is recommended that this analysis be conducted in the field.

PH-MAN-VA Water pH by Manual Meter APHA 4500-H pH Value

This analysis is carried out using procedures adapted from APHA Method 4500-H "pH Value". The pH is determined in the laboratory using a pH electrode.

It is recommended that this analysis be conducted in the field.

PO4-T-COL-VA Water Total Phosphate P by Color APHA 4500-P "Phosphorous"

This analysis is carried out using procedures adapted from APHA Method 4500-P "Phosphorus". All forms of phosphate are determined by the ascorbic acid colourimetric method. Dissolved ortho-phosphate (dissolved reactive phosphorous) is determined by direct measurement. Total phosphate (total phosphorous) is determined after persulphate digestion of a sample. Total dissolved phosphate (total dissolved phosphorous) is determined by filtering a sample through a 0.45 micron membrane filter followed by persulfate digestion of the filtrate.

PO4-T-COL-VA Water Total Phosphate P by Color APHA 4500-P Phosphorous

This analysis is carried out using procedures adapted from APHA Method 4500-P "Phosphorus". All forms of phosphate are determined by the ascorbic acid colourimetric method. Dissolved ortho-phosphate (dissolved reactive phosphorous) is determined by direct measurement. Total phosphate (total phosphorous) is determined after persulphate digestion of a sample. Total dissolved phosphate (total dissolved phosphorous) is determined by filtering a sample through a 0.45 micron membrane filter followed by persulfate digestion of the filtrate.

SILICATE-COL-VA Water Silicate by Colourimetric analysis APHA 4500-SiO2 D.

This analysis is carried out using procedures adapted from APHA Method 4500-SiO2 D. "Silica". Silicate (molybdate-reactive silica) is determined by the molybdosilicate-heteropoly blue colourimetric method.

TDS-VA Water Total Dissolved Solids by Gravimetric APHA 2540 C - GRAVIMETRIC

This analysis is carried out using procedures adapted from APHA Method 2540 "Solids". Solids are determined gravimetrically. Total Dissolved Solids (TDS) are determined by filtering a sample through a glass fibre filter, TDS is determined by evaporating the filtrate to dryness at 180 degrees celsius.

** ALS test methods may incorporate modifications from specified reference methods to improve performance.

The last two letters of the above test code(s) indicate the laboratory that performed analytical analysis for that test. Refer to the list below:

Laboratory Definition Code	Laboratory Location
----------------------------	---------------------

Reference Information

VA

ALS LABORATORY GROUP - VANCOUVER, BC, CANADA

Chain of Custody Numbers:

GLOSSARY OF REPORT TERMS

Surrogate A compound that is similar in behaviour to target analyte(s), but that does not occur naturally in environmental samples. For applicable tests, surrogates are added to samples prior to analysis as a check on recovery.

mg/kg milligrams per kilogram based on dry weight of sample.

mg/kg ww milligrams per kilogram based on wet weight of sample.

mg/kg lw milligrams per kilogram based on lipid-adjusted weight of sample.

mg/L milligrams per litre.

< - Less than.

D.L. The reported Detection Limit, also known as the Limit of Reporting (LOR).

N/A Result not available. Refer to qualifier code and definition for explanation.

Test results reported relate only to the samples as received by the laboratory.

UNLESS OTHERWISE STATED, ALL SAMPLES WERE RECEIVED IN ACCEPTABLE CONDITION.

Analytical results in unsigned test reports with the DRAFT watermark are subject to change, pending final QC review.

KIA-8 - 1 Response Memo to Kitikmeot Inuit Association (KIA) for Technical Comment KIA-8



Memorandum



Date: December 8, 2015
To: John Roberts, TMAC Resources Inc.
From: Mike Henry, ERM
CC: Jim Chan, ERM and Derek Chubb, ERM

Subject: TMAC Resources Inc. - Response to KIA - 8 (formally Information Request (KIA-29 IR))

INTRODUCTION

This memorandum responds to the Information Request (KIA-29) provided by the Kitikmeot Inuit Association (KIA) in September 2015 with respect to TMAC Resources Inc.'s (TMAC) amendment application for the Doris North Project Certificate No.003 and the Type A Water Licence (2AM-DOH1323). Provided below is the initial and follow-up responses to the KIA-29 IR.

KIA COMMENT:

What is the distance from the diffuser at which CCME water quality guidelines will be met in Roberts Bay (i.e.: what is the size of the mixing zone)? Please demonstrate how the 20:1 dilution will be achieved. Please provide modeling results for all three discharge scenarios (groundwater only, groundwater and TIA, TIA only) in both the open water season when full exchange with Melville Sound is expected and under ice when the water exchange is negligible. We note these seasonal differences specifically as they were highlighted by TMAC in Package 2.

INITIAL TMAC RESPONSE:

The initial TMAC response to the KIA-29 IR submitted in October 2015 follows:

Dilution will be achieved rapidly given the pumping and small portals. Of the Canadian Council of Ministers of the Environment (CCME) metals in effluent, maximum predicted chromium concentrations (0.0062 mg/L; Table 4.5-3, document P4-1) will require the greatest dilution to meet CCME guideline levels (0.0015 mg/L; Table 4.5-1, document P4-1) in the receiving environment of Roberts Bay (baseline: 0.001 mg/L; Table 4.5-2, document P4-1), in this case a 9.2:1 dilution. This will be reached within 1 m of the diffuser portals, and given this parameter requires the greatest dilution, the 'CCME mixing zone' will be 1 m. Modelling results for the 3 requested scenarios during summer and winter can be provided during the technical review portion of the Amendment review process.

FOLLOW-UP TMAC RESPONSE:

This response provides additional modelling results for the three requested discharge scenarios of discharge of TIA and groundwater combined, TIA water only, and groundwater only. With respect to the mixing zone and simulation results for achievable effluent dilutions within Roberts Bay, additional information can be found in *Doris North Gold Mine Project: Discharge of Treated Water to Roberts Bay* (Rescan 2011).

The objective of this exercise was to estimate the water quality concentrations in Roberts Bay for those parameters with Canadian Council of Ministers of the Environment (CCME) marine water quality guidelines for the protection of aquatic life (PAL) based on the three discharge scenarios. The data used in model calculations and the model assumptions are the same as listed in Section 4.5.2.2 of Package 4, with the following additional information:

- For each of the three modelled scenarios, maximum predicted water quality concentrations for the TIA and groundwater, groundwater only, and TIA only discharge were obtained from Table 6-3 of the *Doris North Project – Water and Load Balance* (Package 6 document 10; SRK 2015);
- Combined TIA and groundwater are discharged at a constant rate of 80 L/s during the summer months (June to September), TIA effluent is discharged at 45 L/s during the summer months only, and groundwater is discharged at 35 L/s continuously over the year.

Table 1 presents the background water quality for Roberts Bay, the predicted water quality concentrations in each of the potential discharge scenarios into Roberts Bay (i.e., TIA and groundwater combined, groundwater only, and TIA effluent only), and the associated CCME water quality guidelines for the protection of marine life. These guidelines are conservative empirical thresholds that are meant to be protective of all forms of aquatic life and all aspects of aquatic cycles, including the most sensitive species over the long term. In the case of the marine CCME metals (arsenic, cadmium, chromium, and mercury), each guideline concentration includes a safety factor that is 10× lower than the toxic threshold concentration for the most sensitive species. For conservatism, the *maximum* predicted concentrations that would be discharged from the three effluent streams were used in the modelling exercise.

Results of Roberts Bay water quality concentrations under the three discharge scenarios are presented in Figures 1a through 1c and in Table 2. Results indicate that the maximum water quality concentrations for all parameters are predicted to occur when combined TIA and groundwater are discharged into Roberts Bay (Table 2). Concentrations of nitrate, arsenic, and cadmium were estimated to increase only slightly over baseline conditions (2.7-13.2%), while increases in chromium and mercury concentrations were projected to be greater, between 30 and 91%. Results for mercury should be interpreted cautiously as the modelling exercise used an undetectable concentration (0.0001 mg/L) as an input and this detection limit was far greater than the typically available ultra-low detection limit of 0.0000005 mg/L. Regardless, the resulting concentrations in Roberts Bay are predicted to be far below CCME guidelines for all water quality parameters, with nitrate, arsenic, chromium, and mercury near or more than an order of magnitude lower than their respective guideline limit. Given these low predicted concentrations and that all marine water quality guidelines have 10× safety factors applied to their limits (CCME

2015), the water quality in Roberts Bay is predicted to be safe for marine life for each of the discharge scenarios.

REFERENCES

CCME. 2015. *Canadian Water Quality Guidelines for the Protection of Aquatic Life: Summary Table*.
<http://ceqg-rcqe.ccme.ca/> (accessed November 2015).

Rescan. 2011. *Doris North Gold Mine Project: Discharge of Treated Water to Roberts Bay*. Prepared for
Hope Bay Mining Limited by Rescan Environmental Services Ltd.

Table 1. Roberts Bay Background Water Quality and Predicted Maximum Water Quality in Marine Outfall Mixing Box.

WQ Parameter	CCME WQ Guideline Concentration	Roberts Bay Background Concentration	Predicted Maximum Outfall Concentration (Groundwater + TIA) ^a	Predicted Maximum Outfall Concentration (Groundwater Only) ^a	Predicted Maximum Outfall Concentration (TIA Only) ^a
Nitrate	45	0.067	0.80	0.93	0.40
Salinity	±10% baseline	27.05	26.7	26.7	0
Arsenic	0.0125	0.00094	0.0035	0.0024	0.0092
Cadmium	0.00012	0.000056	0.00018	0.00012	0.00046
Chromium	0.0015	0.001	0.0039	0.00086	0.01
Mercury ^b	0.000016	0.0000013	<0.0001	0.000049	<0.0001

Note: all concentrations are in mg/L except salinity which is parts per thousand.

^a - all discharge water quality data taken from Table 6-3 of the Doris North project - Water and Load Balance Report (Package 6, Volume 10)

^b - mercury concentrations for TIA discharge were not available because of poor detection limits for the mill effluent (0.0001 mg/L).

Table 2. Predicted Roberts Bay Water Quality Concentrations based on TIA-Groundwater Combined, Groundwater Only, and TIA Only Discharge.

WQ Parameter	Predicted Roberts Bay Concentration using Maximum Predicted Outfall Levels (TIA + Groundwater)	Predicted Roberts Bay Concentration using Maximum Predicted Outfall Levels (Groundwater Only)	Predicted Roberts Bay Concentration using Maximum Predicted Outfall Levels (TIA Only)	Maximum Allowable Concentrations in Discharge to Meet CCME in Roberts Bay ^a	% Increase over Roberts Bay Background Concentration (TIA and Groundwater)	% Increase over Roberts Bay Background Concentration (Groundwater only)	% Increase over Roberts Bay Background Concentrations (TIA only)
Nitrate	0.076	0.075	0.068	3,730	13.2	11.3	1.6
Salinity	27.046	27.047	27.049	0-260	-0.02	-0.01	0.00
Arsenic	0.00097	0.00095	0.00097	0.96	3.3	1.4	2.9
Cadmium	0.000058	0.000057	0.000057	0.0053	2.7	1.0	2.4
Chromium	0.00015	0.00011	0.00013	0.0425	45.8	6.7	32.6
Mercury ^b	0.0000025	0.0000017	0.0000016	0.0013	91.4	32.3	25.0


Note: all concentrations are in mg/L except salinity which is parts per thousand.

^a – concentrations taken from Package 4, Table 4.5-3.

^b – mercury concentrations for TIA discharge were not available because of poor detection limits for the mill effluent (0.0001 mg/L) . The detection limit was used for modelling purposes.

Figure 1a


Time Evolution of Total Arsenic and Total Cadmium Concentrations in Roberts Bay during TIA and Groundwater Discharge



Note: Allowable effluent concentrations are based on continuous 80 L/s of TIA and groundwater discharge during the open-water season, 45 L/s of TIA discharge during the open-water season, and 35 L/s of groundwater discharged over the year.

Figure 1b


Time Evolution of Total Chromium and Total Mercury Concentrations in Roberts Bay during TIA and Groundwater Discharge



Note: Allowable effluent concentrations are based on continuous 80 L/s of TIA and groundwater discharge during the open-water season, 45 L/s of TIA discharge during the open-water season, and 35 L/s of groundwater discharge over the year. Mercury concentrations for TIA and TIA and Groundwater discharge were unavailable because of poor detection limits for the mill effluent.

Figure 1c

Time Evolution of Total Nitrate Concentrations and Salinity in Roberts Bay during TIA and Groundwater Discharge



Note: Allowable effluent concentrations are based on continuous 80 L/s of TIA and groundwater discharge during the open-water season, 45 L/s of TIA discharge during the open-water season, and 35 L/s of groundwater discharged over the year.

AANDC TC-3 — SRK Technical Memo Estimation of the Time Required for the Underground Mine to Fill



Memo

To:	John Roberts, PEng	Client:	TMAC Resources Inc.
From:	Gregory Fagerlund, MSc	Project No:	1CT022.002
Reviewed By:	Maritz Rykaart, PhD, PEng	Date:	December 4, 2015
Subject:	Response to NRCAN IR-3 & AANDC IR#13: Estimation of the Time Required for the Underground Mine to Fill		

1 NRCAN Information Request 3 (NRCAN IR-3)

1.1.1 Subject

Post-mining groundwater flow regime around the underground mine.

1.1.2 Reference

Package 5 (P5-2), Package 6 (P6-3)

1.1.3 Rationale

NRCAN requests clarification as to how groundwater flow into the underground mine will change once mining has ceased. NRCAN requests clarification on how groundwater inflow rates will change and an approximate time frame for when the groundwater system will reach a post-mining state of equilibrium. This information will assist in confirming that the long-term potential contaminants in the underground mine (resulting from disposal of waste) do not have an effect on local groundwater that surrounds the underground mine. Such contamination could potentially occur if there is a groundwater flow reversal once a mine has filled with surface water and groundwater.

1.1.4 Information Request

- a. Please provide clarification on the post-mining groundwater flow regime in the vicinity of the underground mine.
- b. Please provide information on the time required for the underground mine to fill and clarification on post-mining groundwater regime (flow directions and rates) and potential impacts to the groundwater quality.

1.2 AANDC IR#13 – Tailings Management Plan

1.2.1 References

2.2 New Tailings Storage Requirements

Package 6, Part 7, Page 4 (PDF page 104)

Geochemical Characterization of Tailings from the Doris Deposits, Hope Bay 5 Summary and Conclusions

Package 6, Part 7, Page 30 (PDF page 91)

1.2.2 Issue/Concern or Information Deficiency

Concern that the strategy proposed by the proponent will accumulate a large volume of potentially acid generating (PAG) material and detoxified tailings underground. The detoxified tailings with acidic pH and elevated concentration of Cd, Co, Cu, Fe, Mn, Ni, Pb, and Zn can contaminate underground water.

1.2.3 Rationale

About 6% (i.e. 150,000 tonnes or 116,000 m³) of the tailings are comprised of detoxified cyanide leach tailings, and this tailings stream will be sent underground where it will be mixed with underground waste rock for use as structural mine backfill.

The proponent states, that 'The detoxified tailings also showed a propensity for leaching of several metals in the humidity cell tests. In addition to arsenic, neutral pH metal leaching of ammonia, cadmium, copper, iron, selenium and silver was reported in the Doris North detoxified tailings, and cadmium and selenium in the Doris Central detoxified tailings. Acidic conditions developed in the Doris Central detoxified tailings after 202 weeks of testing. At acidic pH, increased metal leaching of Cd, Co, Cu, Fe, Mn, Ni, Pb, and Zn was noted.' The potential leaching of contaminants under low pH conditions can be a significant source of underground water contamination.

1.2.4 Information Request

Please provide an analysis of the combined impact of detoxified tailings and backfilled PAG waste rock on groundwater.


2 TMAC Response

This response relates directly to item b. in NRCAnIR-3 and follows on the response to AANDC-IR#13 which both required an estimate of the time for reflooding the Doris underground mine.

Once mining at Doris ceases, and the mine workings have been prepared for closure, mine dewatering pumps will be switched off and the mine will reflood. Figure 1 shows a plot of the mine volumes over time for the portions of Doris Central and Connector zones which are below the

elevation of Doris Lake, including both talik and non talik zones, which is the maximum level to which the mine would flood. Two curves are represented: one curve corresponds to the total mine volume and the other, the volume of empty space remaining after backfill is deposited. Figure 2 shows a plot of the predicted inflow versus mine level elevation (in mine grid elevations).

The reflood time was estimated using a simplified step-wise approach that uses the groundwater inflow numerical predictions and the planned volume of mine workings. The time to reflood each mine level was calculated based on inflow rate predictions presented in Document P6-3, Groundwater Inflow and Quality Model at the respective mine levels and the planned mine volumes.



Note: A 30% porosity is assumed for tailings and waste rock backfill.

Figure 1: Estimated volume of the mine over time for the Doris Central and Connector Zones




Figure 2: Predicted mine inflow in the Doris Central and Connector Zones versus elevation

The estimated groundwater reflood time at different times throughout the mine life is shown in Figure 3. Three reflood time curves are presented as follows:

- The base case reflood time estimation based on the inflow rates presented in Document P6-3. This corresponds to a mine inflow rate of about 1,450 m³/day when mining ceases;
- A hypothetical case with a constant reflood inflow rate of 500 m³/day for all mine levels. This rate corresponds to the lower end of the predicted inflow rates, when the mine begins to receive groundwater inflow; and
- A hypothetical case with a constant reflood inflow rate of 2,650 m³/day for all mine levels. This rate corresponds to the maximum inflow rate predicted by the numerical model.




Figure 3: Reflood time estimates at different times throughout the mine life of Doris Central and Connector Zones

When the mine has been fully developed, the total reflood time is estimated to be about 2 years (660 days) for the base case. For the two hypothetical reflood scenarios presented in Figure 3, minimum and maximum reflood times of 1 and 5 years respectively can be observed.

It should be noted that these reflood estimates do not account for backfill being placed as mining progress. Over the life of mine approximately 810,000 m³ of backfill is placed. This backfill consists of mine waste rock and filtered tailings. This material will reduce the volume of the mine and as a result the reflood values as presented are conservative, i.e. reflooding would occur much faster. If the two hypothetical scenarios account for backfill deposition, the minimum and maximum reflood times are reduced to 4 months and 1.7 years respectively.

Disclaimer—SRK Consulting (Canada) Inc. has prepared this document for TMAC Resources Inc.. Any use or decisions by which a third party makes of this document are the responsibility of such third parties. In no circumstance does SRK accept any consequential liability arising from commercial decisions or actions resulting from the use of this report by a third party.

The opinions expressed in this report have been based on the information available to SRK at the time of preparation. SRK has exercised all due care in reviewing information supplied by others for use on this project. Whilst SRK has compared key supplied data with expected values, the accuracy of the results and conclusions from the review are entirely reliant on the accuracy and completeness of the supplied data. SRK does not accept responsibility for any errors or omissions in the supplied information, except to the extent that SRK was hired to verify the data.

AANDC TC 9 – SRK Technical Memo Filtering Requirements



Memo

To:	John Roberts, PEng	Client:	TMAC Resources Inc.
From:	Emma Helmers, EIT Arcesio Lizcano, PhD	Project No:	1CT022.002
Reviewed By:	Maritz Rykaart, PhD, PEng	Date:	December 4, 2015
Subject:	Response to AANDC-NIRB IR#22: TIA Interim Dike – Filtering Requirements		

1 AANDC-NIRB IR #22

1.1 Issue

The filtering requirements of the TIA Interim Dike require clarification to determine if the impacts predicted (or lack thereof) are valid.

1.2 Reference

Package 6 Engineering and Design Documents, P6-13 Tailings Management System: Section 1.1 Paragraph 4 “The remaining portion of the TIA between the Interim Dike and the existing North Dam (completed in 2012, SRK (2012)) will not contain any tailings, and will act as a Reclaim Pond.”

P6-13 Tailings Management System: Section 4.2 Paragraph 1 “Tailings will be retained between the South Dam and the Interim Dike”; P6-13 Tailings Management System: Section 4.4.2 Paragraph 1; P6-13 Tailings Management System: Appendix A, Drawing DN-TIA-04.

1.3 Concern

There are statements in the text which describe the purpose of the Interim Dike is to impound tailings between the South Dam and the Interim Dike. Therefore, it is inferred that the Interim Dike is actually a filter dike; retaining the tailings on the upstream side while allowing the supernatant water to flow through the dike to the downstream reclaim pond. However, the drawings show the Interim Dike to be mainly constructed with Run of Quarry material. The concern is if the Run of Quarry material will be a suitable filter material to retain the tailings upstream of the Interim Dike while allowing the water to filter through to the downstream reclaim pond.

It is also noted that P6-13 Tailings Management System: Section 4.4.2 Paragraph 1, does mention “The upstream face of the Interim Dike will, if required be clad with a layer of graded rock that would act as a filter to ensure tailings solids does not migrate through the Dike. Alternately,

the upstream slope will be clad with a geotextile to serve this filtering function.” However, these mitigations may not be practical to employ if the Run of Quarry design does not work, since the tailings facility will already be in operation, and could have tailings and turbid supernatant water encroaching on the upstream face of the Dike. Given the importance of the Interim Dike, it is prudent to implement best practice, and design and construct the Dike in a way that does not require post-construction retrofitting from the onset.

If the Run of Quarry material does not act as a filter it may result in reclaim water turbidity and silting up of the downstream reclaim pond.

1.4 Information Request

Please comment on the rationale for the design process and the proposed mitigation strategy.

Please provide supporting design calculations to show that the Interim Dike constructed of Run of Quarry material will in fact be a suitable filter matrix for retaining the tailings on the upstream side while allowing the supernatant water to flow through the dike to the downstream reclaim pond.

If the Run of Quarry material becomes clogged, how will tailings supernatant water be transferred from the Tailings Management Pond to the downstream Reclaim Pond? Consequently, describe potential effects of possible buildup of hydrostatic head on the upstream side of the Interim Dike, on the dike's stability.

1.5 Importance of Issue

It is important that the Interim Dike function properly to retain tailings on the upstream side of the TIA while allowing filtered tailings water to flow through the dike to the downstream reclaim pond for the proposed TIA to function properly and avoid unpredicted impacts to the environment. This information will assist AANDC in the subsequent technical review of this component of the Project.

2 TMAC Response

2.1 Context

As described in Document P6-13 Tailings Management System, the Interim Dike will retain tailings on the upstream side and allow water flow through its body to the downstream Reclaim Pond. The upstream face of the Interim Dike will, if required, be clad with a layer of graded rock that would act as a filter to ensure tailings solids do not migrate through the Dike. Alternately, the upstream slope may be clad with a geotextile to serve this filtering function.

This memo presents a filter design for the Interim Dike and discusses the performance of the Interim Dike itself as a filter. The memo also includes the alternative design option involving the installation of a geotextile along the upstream face of the Interim Dike.

2.2 Filter Design

2.2.1 Design Considerations

The following six aspects have been considered in the design of the suitable filter material for retaining tailings while allowing the flow of water through it:

- Filter ability;
- Internal stability;
- Self-healing;
- Material segregation; and
- Permeability and Drainage capacity.

The filter has been designed based on the particle size distribution of the Doris North tailings (SRK 2006; Pocock 2009; Knight Piesold 2009) and is presented in Figure 1.

2.2.2 Filter Ability

In order for a coarser material to appropriately retain a finer material, the pore size of the coarser material must be small enough such that grains of the finer material cannot freely pass through. Best practice filter criteria have been developed based on laboratory testing and failure investigations since 1940 (Bertram 1940, Terzaghi and Peck 1948, Sherard and Dunnigan 1989). Table 1 lists these criteria.

Table 1: Filter Criteria (Messerklinger 2013)

Soil Group	Fines Content <0.075 mm	Filter Criteria Determined by Tests after Sherard and Dunnigan (1989)	State-of-the-Art Criteria in Dam Engineering
1	85-100	$D_{15f}^1 = 7d_{85b}^2 \text{ to } 12d_{85b}$	$D_{15f} \leq 9d_{85b}$
2	40-80	$D_{15f} = 0.7 \text{ to } 1.5 \text{ mm}$	$D_{15f} \leq 0.7 \text{ mm}$
3	0-15	$D_{15f} = 7d_{85b} \text{ to } 10d_{85b}^3$	$D_{15f} \leq 4 \text{ to } 5 d_{85b}^4$
4	15-40	Intermediate between group 2 and 3	Intermediate between group 2 and 3

Notes:

¹ Diameter at which 15% of the filter material is finer

² Diameter at which 85% of the tailings material is finer

³ 7 For subrounded grain shape and 10 for angular grain shape

⁴ Incorporates a factor of safety of 2

Figure 1 shows three grain size distribution curves for the Doris North tailings. The average fines content (material finer than 0.075 mm) is approximately 50%, which puts the tailings in the Soil Group 2 of Table 1. Based on the state-of-the-art criteria in dam engineering shown in Table 1, the D_{15f} of the filter (the diameter at which 15% of the filter material is finer) must be less than or equal to 0.7 mm. Therefore, the coarse D_{15f} limit of the filter material was set to 0.7 mm and the fine D_{15f} limit of the filter material to 0.48 mm. The latter was calculated by multiplying the d_{85b} of

the finest tailings specimen by 4 following the piping criterion of Terzaghi (Terzaghi and Peck 1948).

2.2.3 Internal Stability

Filter materials must be internally stable, meaning the finest particles in the filter do not migrate through their coarse particles, even at high hydraulic gradients. Experimental investigations have led to the criteria that the coefficient of uniformity (C_u , which is equal to D_{60} divided by D_{10}) of the filter material should not be greater than 12 (Kenney and Lau 1986).

For the filter design, D_{10f} was calculated by multiplying the d_{10b} of the tailings material by the ratio of the D_{15f} of the filter material to the d_{15b} of tailings in order to get a filter curve of similar shape to the tailings curve. This was done for both the fine and coarse limits of the filter to get an envelope. The D_{60f} was then chosen by applying a coefficient of uniformity of 12.

2.2.4 Self-Healing

A filter material must have less than 5% non-plastic fines ($I_P < 5\%$) so that cracks that open due to e.g. differential settlement (or strains) can close again easily (Messerklinger 2013). However, the Bulletin 141 of the International Commission of Large Dams (ICOLD 2011) Bulletin on CFRD's, No. 141 allows 7% of fines. The maximum fines percentage in the filter design shown in Figure 1 is approximately 7%.

2.2.5 Material Segregation

When a material segregates from itself, meaning that the coarser materials separate from the finer particles, the filter can no longer fulfill its purpose of preventing fine particles moving from the tailings to the filter or within the filter itself (Messerklinger 2013). Based on observations and laboratory investigations, Milligan (2003) presented a segregation criterion shown in Figure 1 as a "coarse limit" for a filter material.

2.2.6 Permeability and Drainage Capacity

In order to ensure that the filter will be several times more permeable than the tailings, thereby avoiding the buildup of excess pore pressure, the filter design followed the Terzaghi permeability criterion $D_{15f}/d_{15b} \geq 4$. The filter also fulfills the Terzaghi criterion $D_{15f}/d_{85b} \geq 4$ and the Sherard recommendation that $D_{15f} \geq 0.2$ mm (Messerklinger 2013), both designed to increase drainage capacity.

2.3 Interim Dike as a Filter

Based on experience with Run-of-Quarry (ROQ) rock during design of the tailings containment area (SRK 2006), the expected D_{50} of the Interim Dike ROQ rock is 114 mm for the coarse fraction, and 2.45 mm for the fine fraction. The ROQ envelopes are shown in Figure 1. The ROQ rock of the Interim Dike will therefore not act as a filter for the tailings material and a specific, filter material as shown in Figure 1 and described in Section 2.2 is required.

2.4 Alternative Design Option

There are no borrow material at site that satisfied the filter criteria and therefore the filter material will be manufactured through crushing and screening. A cost trade-off will be completed at the detailed engineering stage and if the designed filter is difficult and/or expensive to attain by crushing and screening, a geotextile may be installed on the upstream face of the Interim Dike. The geotextile should have a maximum apparent opening size (AOS) of less than 0.7 mm (determined maximum D_{85f}). Subaqueous geotextile installations have been carried out at other mines and remediation sites in Canada such as the Seabee Mine (SRK 2012) and the Lorado Mill Tailings Remediation Project (SRK 2014). A common technique is to attach steel pipe to the end of the geotextile and lower this pipe to the toe of the constructed dam from a boat or with an excavator that has an extended reach. The geotextile is then tied into the crest of the dam, as pictured in Figure 2.

2.5 Filter Clogging


The ROQ material of the Interim Dike will not clog if the filter design as presented is constructed. Consequently, no buildup of hydrostatic head on the upstream side of the Interim Dike is expected.


Disclaimer—SRK Consulting (Canada) Inc. has prepared this document for TMAC Resources Inc.. Any use or decisions by which a third party makes of this document are the responsibility of such third parties. In no circumstance does SRK accept any consequential liability arising from commercial decisions or actions resulting from the use of this report by a third party.

The opinions expressed in this report have been based on the information available to SRK at the time of preparation. SRK has exercised all due care in reviewing information supplied by others for use on this project. Whilst SRK has compared key supplied data with expected values, the accuracy of the results and conclusions from the review are entirely reliant on the accuracy and completeness of the supplied data. SRK does not accept responsibility for any errors or omissions in the supplied information, except to the extent that SRK was hired to verify the data.

3 References

- Bertram, G. E. (1940). *An Experimental Investigation of Protective Filters*. Harvard Soil Mechanics Series No. 7.
- International Commission of Large Dams (ICOLD) (2011). *Concrete Face Rockfill Dams - Concepts for Design and Construction*, Bulletin 141.
- Kenney, T. C. and Lau, D. (1986). *Internal Stability of Granular Filters*. Canadian Geotechnical Journal. (23): 420-423.
- Knight Piesold Consulting (2009). *Hope Bay Project Geotechnical Laboratory Test Results*. Report submitted to Newmont Metallurgical Services June, 2009. Knight Piesold Project No. DV108-00147.04.
- Messerklinger, S. (2013). *The Design of Filter Materials and their Importance in Geotechnical Engineering*. Proceedings of the 18th International Conference on Soil Mechanics and Geotechnical Engineering. Paris, 2013.
- Milligan, V. (2003). *Some Uncertainties in Embankment Dam Engineering*. ASCE. 129(9): 785-797.
- Pocock Industrial, Inc (Pocock). (2009). *Flocculant Screening, Gravity Sedimentation, Pulp Rheology, Pressure Filtration and Vacuum Filtration Studies Conducted for Newmont Mining Corporation, Hope Bay Project*. Report submitted to Newmont Mining Corporation February, 2009.
- Sherard, J. L. and Dunnigan, L. P. (1989). *Filters and Leakage Control in Embankment Dams*. Proceedings of the Symposium on Seepage and Leakage from Dams and Impoundments, American Society of Civil Engineers. New York: 1-29.
- SRK Consulting (Canada) Inc (SRK). (2006). *Design of the Tailings Containment Area – Doris North Project, Hope Bay, Nunavut, Canada*. Report submitted to Miramar Hope Bay Ltd October, 2006. SRK Project No. 1CM014.008.165.
- SRK Consulting (Canada) Inc (SRK). (2012). *Seabee Mine East Lake TMF Expansion Geotechnical Design – UPDATED*. Report submitted to Claude Resources Inc. June, 2012. SRK Project No. 4CC005.010.
- SRK Consulting (Canada) Inc (SRK). (2014). *Detailed Cover Design Report for the Lorado Mill Site Tailings and Peripheral Areas*. Report submitted to Saskatchewan Research Council June, 2014. SRK Project No. 4CS008.003.
- Terzaghi, K. and Peck, R. B. (1948). *Soil Mechanics in Engineering Practice*. John Wiley & Sons. New York.





Legend

— Reclaim Pond Surface

- - - Geotextile Filter



ROQ Fill Material

Notes

1. All dimensions and elevations are in meters unless stated otherwise.
2. Horizontal scale is equivalent to vertical scale
3. Cross section modified from DN-TIA-03 in SRK (2015).

srk consulting

Job No: 1CT022.002

Filename: AANDC_IR22_Figures_FilterDesign_EH_TS_al_20151204.pptx

TMAC
RESOURCES

Hope Bay Project

Type A Water License Information Requests

**Typical Interim Dike Cross Section
Sketch with Geotextile Filter**

Date:
December 2015

Approved:
AL

Figure: **2**

AANDC TC 10 – SRK Technical Memo Closure Cost Estimate Analysis



Memo

To:	John Roberts, PEng	Client:	
From:	Iozsef Miskolczi, PEng	Project No:	1CT022.002
Reviewed by :	Maritz Rykaart, PhD, PEng	Date:	December 18, 2015
Subject:	Response to IR AANDC TC10 - Closure Cost Estimate		

1 Introduction

As part of the supporting documents for Amendment #1 to the Water License No. 2AM-DOH1323, TMAC Resources Inc. submitted an Interim Closure and Reclamation Plan (Document P5-2) and the associated closure cost estimate (Document P6-5).

During the technical review process, Aboriginal Affairs and Northern Development Canada (AANDC) reviewed both documents and provided comments. AANDC also retained Amec Foster Wheeler (AMEC) to provide an Independent Closure Cost Estimate based on the same Document P5-2. This estimate has been calculated using the RECLAIM 7.0 Model for Reclamation and Closure Security Estimate and is based on a geotechnical site inspection that was conducted this past August and a review of TMAC Resources Inc.'s (TMAC) licence amendment application. A total closure cost estimate of \$47,818,382 was calculated, compared to \$25,061,000 estimated by TMAC.

This memorandum presents an analysis of the AANDC cost estimate and provides a summary of the differences between what AANDC is proposing and what TMAC has provided. A complete list of the changes and corrections made to the AANDC estimate is provided in Attachment 1.

2 Review of the AANDC Cost Estimate

The independent cost estimate was summarised in a technical memorandum (AANDC 2015) and details of the estimates for each work area were provided as appendices while select assumptions used to derive the costs were summarised in the body of the memo.

The AANDC cost estimate was completed using the RECLAIM version 7.0 cost model (Brodie 2014), and considerable effort was made to retain as much as possible the functional structure of the TMAC estimate, which was based on a work breakdown structure detailed in Document P5-2. This was achieved by grouping similar activities from the various work areas into the functional sheets provided in the RECLAIM template, and some of those sheets were

renamed or repurposed as necessary. This made it relatively easy to complete a direct comparison of the costs estimated for the similar activities comprising the two cost models.

In general the AANDC estimate follows the structure of the TMAC estimate. Most quantities and many of the task unit rates are the same but in some instances new unit rates or new quantities were introduced in the AANDC estimate; however the assumptions or calculations supporting these new values were not included in the cost model provided for review.

3 Basis for Comparison

3.1 Model Structure

Taking as basis for comparison the AANDC estimate, the main differences in the cost models are as follows:

- Direct Costs
 - A new cost category was introduced representing Interim Care and Maintenance activities.
 - The cost category for off-site disposal of hazardous waste and hydrocarbon contaminated soils was omitted.
- Indirect Costs
 - Some of the costs are calculated as percentage of the direct costs, as opposed to being a first principles approach.
 - An “Engineering” cost category was introduced.
 - The “Hydrocarbon Decontamination” category was omitted.
 - A new category was introduced named “Health & Safety Plans, Monitoring, and QA/QC”.
 - The “General Administration” category was omitted.

To make a direct comparison possible, the cost categories not used under either of the costing models were added as blank lines, such that both estimates have the same number of categories. Except for the omitted cost categories (e.g. hydrocarbon decontamination) all activities and tasks as presented in Document P5-2 are accounted for in the AANDC model.

3.2 Cost Comparison Basis

A detailed review of the AANDC cost estimate was completed by SRK on behalf of TMAC and the findings are summarised in Section 4. The review process was structured in a way that provides a systematic breakdown of the discrepancies between the two cost estimates and detailed notes were prepared documenting each of the changes made to the AANDC estimate (Attachment 1). The analysis was completed in three steps, as follows:

1. Remove obvious “typographical type” errors related to quantities and/or unit rates applied;

2. Correct assumptions made in the AANDC cost estimate to reflect the actual site conditions and the existing Interim Closure Plan (Document P5-2); and
3. Where necessary, replace the unsupported AANDC unit rates with the well-documented TMAC unit rates.

A few general observations were made with regards to the cost discrepancy between the two models, which are summarised in the sub-sections following below.

Direct Costs

- The main source of discrepancy between the costs is the Interim Care and Maintenance category, which was not included in the original TMAC estimate.

Indirect costs

- The AANDC memo states that the main difference in overall costs is partly originating from the fact that the TMAC reclamation costs are based on equipment existing on site at time of closure. This is not accurate, and the Mobilization/Demobilization cost category in the TMAC estimate (Document P6-5) provided detailed costs for shipping the equipment to and from site by barge.
- In the AANDC estimate, owner's costs with camp rental and camp operations are included in the Mobilization/Demobilization category. The TMAC model (Document P6-5) assumed that existing camp facilities will be used for closure; however, this was revised to include an allowance for camp rental cost during the 2.5 years required for active water management post-closure.
- Some of the indirect cost categories were calculated as percentages of the direct costs. This practice is common for interim closure cost estimates, where final closure task definitions are somewhat vague or uncertain. The original TMAC estimate provided an itemised description and costing for these indirect cost items, based on unit rates where appropriate. For compatibility and ease of comparison with the AANDC cost estimate, the percentage method was adopted by TMAC for these categories, but percentages were adjusted as necessary to produce a more realistic cost.

4 Cost Comparison

Once the obvious errors were corrected in the AANDC cost estimate model, the overall cost was reduced from \$47.8 M to \$43.8 M, which we believe represents the true cost as intended by AANDC.

As a next step, the assumptions made in the AANDC estimate were adjusted or corrected to reflect the site conditions and the closure activities detailed in Document P5-2, while the unit rates remained the same as in the previous step. In this step the cost for Interim Care and Maintenance and the camp rental cost for the active water management period were also included. Due to the large amounts removed by eliminating the winter road and the commuter flights, the overall cost was further reduced to \$26.2 M.

In the final step of this analysis, the unit rates used in the AANDC estimate were replaced with the equivalent unit rates in the TMAC estimate. This was done because none of the AANDC unit rates were supported by productivity calculations or third-party quotations and, although these units may be reasonable, cannot be assessed on their merits. The overall closure cost in this case became \$28.9 M. This is about \$3.9 M higher than the original TMAC cost, due to the increase from the Interim Care and Maintenance and mobile camp rental costs.

Table 1 provides a summary of the cost categories as included in the two cost estimate models. The costs are broken out by the three analysis steps detailed in Section 3.2. The detailed cost estimate model is provided in Attachment 2.

Table 1: Summary of Cost Categories

AANDC Cost Categories (RECLAIM V. 7 Model)	TMAC Cost Categories (SRK Model)	AANDC Estimate	TMAC Estimate (Absolute) ¹	TMAC Estimate (Rounded) ²	AANDC Estimate with Errors Corrected	AANDC Estimate with Assumptions Corrected	Revised TMAC Estimate corrected with Select AANDC Assumptions
DIRECT COSTS							
Open Pit	Roberts Bay Area / Airstrip	\$ 947,269	\$ 762,129	\$ 763,000	\$ 919,329	\$ 919,329	\$ 768,158
UG Mine	U/G Workings and Reagent Pads	\$ 255,351	\$ 144,618	\$ 145,000	\$ 246,351	\$ 239,726	\$ 144,561
Tailings	North and South Dams / Interim Dyke	\$ 8,341,610	\$ 8,655,952	\$ 8,656,000	\$ 8,341,610	\$ 8,341,610	\$ 8,655,951
Rock Pile	Doris Windy Road / Secondary Road	\$ 786,873	\$ 547,408	\$ 549,000	\$ 783,581	\$ 783,581	\$ 547,927
Doris Camp	Doris Camp	\$ 4,369,083	\$ 2,996,539	\$ 2,997,000	\$ 4,082,823	\$ 4,182,275	\$ 2,996,446
Chemicals	Quarry #2 / Doris Mtn / Quarry #3 Waste Area / Ocean Discharge System	\$ 900,502	\$ 372,859	\$ 376,000	\$ 895,502	\$ 622,002	\$ 372,923
Surface and Groundwater Management	Surface Water Management	\$ 1,015,000	\$ 3,361,200	\$ 3,361,000	\$ 1,015,000	\$ 507,507	\$ 3,361,200
Interim Care and Maintainance	Not Included	\$ 4,192,002	\$ -	\$ -	\$ 4,173,252	\$ 1,991,028	\$ 2,408,390
Not Included	Off-site Disposal	\$ -	\$ 491,960	\$ 492,000	\$ -	\$ -	\$ 491,960
SUBTOTAL: DIRECT COSTS		\$ 20,807,690	\$ 17,332,665	\$ 17,339,000	\$ 20,457,448	\$ 17,587,059	\$ 19,747,514
INDIRECT COSTS							
Mobilization/Demobilization	Mobilization & Demobilization	\$ 17,289,163	\$ 1,037,786	\$ 1,038,000	\$ 16,209,163	\$ 3,331,424	\$ 2,865,058
Post-Closure Monitoring & Maintenance	Post-Closure Monitoring	\$ 1,814,608	\$ 884,000	\$ 884,000	\$ 1,814,608	\$ 868,500	\$ 868,500
Engineering (8%, reduced to 1%)	Not Included	\$ 1,664,615	\$ -	\$ -	\$ 204,574	\$ 175,871	\$ 197,475
Not Included	Hydrocarbon Decontamination	\$ -	\$ 150,000	\$ 150,000	\$ -	\$ -	\$ -
Project Management (7%, reduced to 2%)	Field Support	\$ 1,456,538	\$ 347,003	\$ 347,000	\$ 409,149	\$ 351,741	\$ 394,950
Health & Safety Plans/Monitoring & QA/QC (2%)	Not Included	\$ 416,154	\$ -	\$ -	\$ 409,149	\$ 351,741	\$ 394,950
Not Included	General Administration ³	\$ -	\$ 1,935,021	\$ 1,935,000	\$ -	\$ -	\$ 618,571
Bonding/Insurance (1%)	Not Included	\$ 208,077	\$ -	\$ -	\$ 208,077	\$ -	\$ -
Contingency (20%)	Contingency (20%) ⁴	\$ 4,161,538	\$ 3,368,141	\$ 3,368,000	\$ 4,091,490	\$ 3,517,412	\$ 3,851,111
Market Price Factor Adjustment (0%)	Not Included	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
SUBTOTAL: INDIRECT COSTS		\$ 27,010,693	\$ 7,721,951	\$ 7,722,000	\$ 23,346,210	\$ 8,596,688	\$ 9,190,615
TOTAL COSTS		\$ 47,818,383	\$ 25,054,616	\$ 25,061,000	\$ 43,803,657	\$ 26,183,747	\$ 28,938,129

NOTES:

1. The TMAC cost estimate is based on precise numbers, but the presented numbers in the supporting documents are rounded (see Note 2 below).
2. The TMAC numbers as shown in the supporting documents are rounded numbers. The rounding occurs at two levels; all line items are rounded to the nearest \$1,000 or a minimum of \$1,000.
3. The TMAC General Administration cost was reduced by an amount equal to H&S Plans/Monitoring & QA/QC, as these tasks are assumed to be part of the camp administrator’s duties.
4. The cost of off-site disposal was subtracted from Direct Costs when calculating the Contingency.

5 References

- AANDC (2015). Reclamation Cost Estimate Amendment No. 1 to Nunavut Water Board License No. 2AM-DOH1323 Doris North Project Kitikmeot Region, Nunavut. Technical Memorandum Prepared by Amec Foster Wheeler Environment & Infrastructure a Division of Amec Foster Wheeler Americas Limited, Project No. TV154011, December 8, 2015.
- Brodie Consulting Ltd., 2014. RECLAIM Version 7.0 User Manual. MS Excel Workbook and User Manual prepared for Aboriginal Affairs and Northern Development Canada – Water Resources Division. March 2014.

Disclaimer—SRK Consulting (Canada) Inc. has prepared this document for John Roberts. Any use or decisions by which a third party makes of this document are the responsibility of such third parties. In no circumstance does SRK accept any consequential liability arising from commercial decisions or actions resulting from the use of this report by a third party.

The opinions expressed in this report have been based on the information available to SRK at the time of preparation. SRK has exercised all due care in reviewing information supplied by others for use on this project. Whilst SRK has compared key supplied data with expected values, the accuracy of the results and conclusions from the review are entirely reliant on the accuracy and completeness of the supplied data. SRK does not accept responsibility for any errors or omissions in the supplied information, except to the extent that SRK was hired to verify the data.

Attachment 1: List of Errors and Assumptions Corrected

1 Listing of Errors and Assumptions Corrected

This list of notes should be read in conjunction with the complete sheets of the cost analysis provided in Attachment 2. The cells highlighted in each of the cost category sheets represent changes made to the AANDC cost model. The following notes describe the changes that were made for each of the highlighted cells.

1.1 Errors corrected

Each of the estimate sheets were reviewed and compared to the original TMAC estimate. In a few cases quantities or unit rates values were obviously erroneous. These include order-of-magnitude differences, mismatch with the referenced unit of measurement, or values not representing the actual site conditions.

These errors were corrected and the notes are summarised below following the AANDC estimate structure.

1_Open Pit

- Roberts Bay Tank Farm: Number of tanks in this tank farm were miscounted (one tank by AANDC instead of four). Quantities were adjusted accordingly for “wash tanks” and dismantle tanks...” tasks.
- Quarry #1 Tank Farm: Number of tanks in this farm was miscounted (four tanks instead of one). Quantities were adjusted to show one 5ML tank for “drain tanks...” and dismantle 5ML diesel...” tasks. Quantity was adjusted to 2 for “Disconnect piping and controls” task.

4_Rock Pile

- Explosives Facility: “Load all waste and debris into containers”: AANDC used the facility surface area as metric for loading waste, which is inappropriate and results in very high cost. Unit rate is also inconsistent with the rate used for the same task in other places. The quantity of waste was revised.

5_Doris Camp

- Accommodation Complex: the number of trailer units in AANDC estimate is 283; we believe this to be a typo, as the actual number is 83. Quantity was revised.
- Tank Farm: the quantities for the tasks “Decommission Fuel Transfer Facility” and “Wash Tanks” were switched in the AANDC estimate. The quantities were revised to reflect the actual task. Unit rates were correct.
- Tank Farm: the unit and quantity for the “prepare pieces for transportation” were erroneous and were corrected to be consistent with the immediately following task.
- Sewage Treatment Plant: the quantity for “Load debris into containers for transport (to Roberts Bay)” was erroneous and inconsistent with the following task. The quantity was revised.

- Fire Water Storage Tank: the last 5 lines in the quantities column were translated, resulting in erroneous task costs. Quantities were corrected to match the TMAC estimate.
- Expanded Laydown Area (Pad U): the unit rate used for the “LHD remaining ore to TIA” task was \$16.35, although RECLAIM rate code SBSH was used, which is \$6.30. The unit rate was corrected to reflect the RECLAIM unit rate.

6_Chemicals

- Communications Tower: AANDC used 11 m³ of waste to be removed from the top of Doris Mountain. This is inconsistent with the other quantities for the same activity, and it was replaced with a value of 9.

8_Interim Care and Maintenance

- Geotechnical Assessment: a quantity of 1.5 was used for the yearly unit rate. This was corrected to 1.

9_Mobilization / Demobilization

- Worker Accommodations: The total number of months for camp operations during active water management was set to 60 (i.e. 5 years). Since 18 months were accounted for under the closure activities, these months were removed from the total and the quantity was revised to the balance of 42.

1.2 Revised Assumptions

Some of the assumptions made to derive the units, quantities, and task unit rates did not represent the existing site conditions and/or were inconsistent with the reclamation tasks described in the Interim Closure and Reclamation Plan (Document P5-2). Where encountered, these assumptions were adjusted or corrected to align with the Plan.

2_UG Mine

- Doris North Vent Raise: the unit rate for the “Prepare units for shipping off-site” was intended as an aggregate rate for preparing all parts at once. The AANDC estimate used multiples of these rates matching the number of equipment parts removed. This was corrected to the unit quantity. This same correction was done for the Doris Connector and Doris Central vent raises.

5_Doris Camp

- Tank Farm: AANDC used a quantity of 5 for the “Dismantle tanks and cut into manageable pieces” task. While this is correct for the tank farm, two more tanks of similar size exist on site (the Fire Water Tank and the water tank for Boston) for which dismantling costs were not accounted for under the AANDC assumption. The quantity was adjusted to 7.
- Tank Farm: the 60 m³ quantity for the waste resulting from the dismantling of the tanks is too high, especially when the selected unit rates are used to calculate the task cost. The quantities were corrected to be equal to the volumes calculated by TMAC.

- Office and Mine Dry Complex: the unit rate for “collect all debris” (C310L) is appropriate for collecting loose debris from pad surface opposed to actual volume of debris, as presented in the AANDC estimate. The quantity was corrected to match the selected unit rate.

6_Chemicals

- Roberts Bay Discharge System: a much higher unit rate was used for the task of “Cut pipelines into manageable pieces” compared to the tailings line at the TIA. As this pipeline is 10 inch HDPE, similar to the tailings lines, it was considered that a similar unit rate is more appropriate. Unit rate was corrected to \$22.

7_Surface and Groundwater Management

- Operate / Maintain Water Management System: AANDC assumed 5 years for the two tasks under this category, and used a quantity of 60 monthly rates for the cost. Given the plan for the water management detailed in the Closure Plan, only 29 months of active water management will be required, with 22 months for direct support (the balance is supported under general closure activities). The quantities were adjusted accordingly.

8_Interim Care and Maintenance

- On-site care-taker: AANDC assumed 5 months per year, which is inconsistent with the other assumptions for this activity (6 months for camp operations). The quantity was increased to 6.
- Mobile camp rental: the AANDC estimate includes camp rental cost, however the existing camp is still functional at this time. The rental allowance was removed.
- Technician: the site caretaker is normally in charge of operating the pumping system. This position was removed.
- Mobilization / Excavator: The AANDC assumptions list articulates the need for a small excavator, yet a 36.1 t (operating weight) machine is specified for mobilization. This was reduced to a 20 t (operating weight) machine.
- Winter Road: AANDC estimate assumed 116 km of winter road will be constructed for mobilization. Since Hope Bay has a barge off-loading facility and all-weather road access to all site facilities, no winter roads will be necessary.

9_Mobilization / Demobilization

- Mobilize Heavy Equipment / Excavators: AANDC assumed 2 excavator to be mobilized, and a third one under the Interim Care and Maintenance activities. This was reduced to 1, for a total of two machines available for closure.
- Mobilize Heavy Equipment / Dozers: AANDC assumed 2 dozers to be mobilized, and a third one under the Interim Care and Maintenance activities. This was reduced to 0, for a total of one machine available for closure.

- Mobilize Heavy Equipment / Loaders: AANDC assumed 2 loaders to be mobilized, and a third one under the Interim Care and Maintenance activities. This was reduced to 1, for a total of two machines available for closure.
- Mobilize Heavy Equipment / Light Duty Vehicles: AANDC assumed 6 vehicles to be mobilized, and 2 more under the Interim Care and Maintenance activities. This was reduced to 2, for a total of 4 vehicles available for closure.
- Mobilize Camp: AANDC estimate assumes 5 seasons for mobile camp rentals. This was reduced to 2.5, representing the time required to complete active water management and breaching the North Dam.
- Mobilize workers: For both winter and summer flights from Yellowknife to Cambridge Bay, the quantities were reduced to 0 as cost of transportation is included in camp operations cost.
- Worker Accommodations: AANDC estimate assumes 18 months of large camp (>25 persons) for 18 months and 60 months of the smaller camp (<10 person) for completion of decommissioning/reclamation and water treatment activities respectively. Based on the AANDC calculations, water discharge from TIA will be completed in 29 months. With decommissioning/reclamation activities completed in 12 months (i.e. larger camp) the water management personnel will spend the balance of 17 months in the smaller camp. The quantities were adjusted accordingly.
- Winter Road: AANDC estimate assumed 116 km of winter road will be constructed for mobilization. Since Hope Bay has a barge off-loading facility and all-weather road access to all site facilities, no winter roads will be necessary.
- Demobilize Heavy Equipment / Excavators: AANDC estimate assumes 3 excavators were on site for completion of the works. This was reduced to 2 to match the total number of equipment mobilized.
- Demobilize Heavy Equipment / Dozers: AANDC estimate assumes 2 dozers were on site for completion of the works. This was reduced to 1 to match the total number of equipment mobilized.
- Demobilize Heavy Equipment / Loaders: AANDC estimate assumes 3 loaders were on site for completion of the works. This was reduced to 2 to match the total number of equipment mobilized.
- Demobilize Heavy Equipment / Light Duty Vehicles: AANDC estimate assumes 6 vehicles were on site for completion of the works. This was reduced to 4 to match the total number of equipment mobilized.
- Demobilize Heavy Equipment / Standard 20' Container: AANDC estimate assumes 10 containers need to be demobilized. This was increased to 12 to account for the 2 containers mobilized under Interim Care and Maintenance activities.

10_Post-Closure Monitoring and Maintenance

The AANDC estimate was calculated by assuming fractions of each task to compute a yearly amalgamated cost of \$235,000. It included a task for vegetation monitoring and a task for decommissioning the water management structures.

This amalgamated yearly rate was applied to each of the 10 years duration of post-closure monitoring, and then the Net Present Value was calculated using a discount rate of 5%. This method results in inaccuracies when estimating the NPV, because in reality different costs will be incurred each year, and the NPV should reflect that.

To correct these assumptions the vegetation monitoring task was removed (no revegetation completed at closure), together with the decommissioning of water management structure task (accounted for under direct costs). The actual yearly expenditures were then computed and the NPV calculated based on these yearly values.

1.3 Revised Unit Rates

The AANDC cost estimate did not detail the methodology for determining the unit rates used in the estimate. By comparison, most of the TMAC task unit rates were calculated from first principles based on contractor's quotations for equipment and labor as well as productivity factors applied for each task or activity. In some instances lump sum rates were used, and these were based on SRK's experience with similar projects.

In most instances the AANDC made use of the TMAC unit rates, and these were left as is. In instances where new unit rates were proposed for certain tasks, these were replaced with the TMAC rates due to the fact that no supporting documentation was provided to provide a base for the evaluation of the suitability of the new unit rate.

Although the quantities and the unit rates from the AANDC estimate were essentially restored to the original TMAC values in the analysis process, the totals for the various cost categories are slightly different. This is because some of the decimal points and fractions of units were lost in the transfer process and could not be restored to their original values.

1.4 Indirect Costs

Engineering

This task category was omitted from the original TMAC cost, due to the fact that no major earthworks will be required under the general closure plan. Therefore the cost representing 8% of the direct costs was considered excessive, and was reduced to 2% of direct costs.

Cost of final tailings covers design was considered as part of separate obligations under the Water License.

Hydrocarbon Decontamination

The engineering and sampling/testing cost for this category in the original TMAC estimate was assumed to be accounted for under the AANDC Engineering cost category, and was therefore removed from this updated estimate.

Project Management

This category is equivalent to the “Field Support” category in the original TMAC estimate; however the 7% of the direct costs was considered excessive. This percentage was reduced to 2% of the direct costs, to match the cost calculated by TMAC from first principles.

General Administration

This category was omitted from the AANDC estimate. The total presented in the original TMAC estimate was split into three parts, to match the AANDC structure and assumptions. The camp operations portion was accounted for under the Mob/Demob activities, while the category cost presented in this revised estimate is the balance between the remainder (after camp operations removed) and the H&S Plans/Monitoring & QA/QC. This was done under the assumption that these H&S tasks will be part of the duties of camp management.

Contingency

The costs of off-site disposal was subtracted from the Direct Costs when calculating the Contingency. This was done because the cost for shipping and disposal is based on contractor quotations, thus the uncertainty in this cost is greatly reduced.

Attachment 2: Detailed Cost Estimate Model

ACTIVITY/MATERIAL	Units	Quantity	Cost Code	Unit Cost	Cost
JETTY					
Remove rock fill to 0.3 m below LLWL, place in surrounding water	m3	1013.8	SSC3L	\$ 8.90	\$ 9,023
Remove on-shore mooring points	LS LS	1 1	OSHRL FSHRL	\$ 1,500.00	\$ 1,500
Remove mooring buoy	m2	1900	c518L	\$ 3,000.00	\$ 3,000
Crown jetty for positive drainage				\$ 0.12	\$ 228
ROBERTS BAY TANK FARM - 20ML					
Drain tanks into portable fuel storage (EnviroTanks)	each	4	C203L	\$ 10,000.00	\$ 40,000
Decommission fuel transfer facilities	each	1	C102L	\$ 550.00	\$ 550
Wash tanks	each	1	C204L	\$ 1,420.00	\$ 1,420
Operate oil/water separator	m3	50	C208L	\$ 30.00	\$ 1,500
Disconnect piping and controls	each	1	C102L	\$ 550.00	\$ 550
Dismantle tanks and cut into manageable pieces	each	1	CUT5L	\$ 100,000.00	\$ 100,000
Load pieces for transportation	m3	43.5	C401L	\$ 13.13	\$ 571
Haul cut metal to Landfill	m3	51.4	C415L	\$ 6.34	\$ 326
Remove and stockpile liner protection cover	m3	5455	SB1L	\$ 4.30	\$ 23,457
Load contained contaminated soils into megabags for shipping off-site	m3	50	C412L	\$ 100.25	\$ 5,013
Haul contaminated material to Roberts Bay laydown	m3	56.8	C404L	\$ 6.34	\$ 360
Clean liner	m2	10300	C210L	\$ 0.39	\$ 4,017
Remove and cut liner into manageable pieces	m2	10300	C302L	\$ 0.56	\$ 5,768
Load Debris into Waste Trucks	m3	92.7	C401L	\$ 13.13	\$ 1,217
Haul containers to Quarry 3	m3	92.7	C415L	\$ 6.34	\$ 588
Landfill Level containment berms	m2	231.3	C505L	\$ 1.58	\$ 365
Regrade area for positive drainage	m2	11530	C518L	\$ 0.12	\$ 1,384
QUARRY 1 TANK FARM					
5ML Drain tanks into portable fuel storage (EnviroTanks)	each	4	C203L	\$ 10,000.00	\$ 40,000
1ML Drain Tanks into portable fuel storage (EnviroTanks)	each	1	C203L	\$ 10,000.00	\$ 10,000
Decommission fuel transfer facilities	each	1	C102L	\$ 550.00	\$ 550
Wash tanks	each	2	C204L	\$ 1,420.00	\$ 2,840
Operate oil/water separator	m3	220	C208L	\$ 30.00	\$ 6,600
Disconnect piping and controls	each	5	C102L	\$ 550.00	\$ 2,750
Dismantle 5ML diesel fuel tank and cut into manageable pieces	each	4	CUT5L	\$ 100,000.00	\$ 400,000
Dismantle 1ML jet fuel tank and cut into manageable pieces	each	1	CUT1L	\$ 50,000.00	\$ 50,000
Prepare pieces for transportation	m3	174	C401L	\$ 13.13	\$ 2,285
Haul cut metal to Landfill	m3	174	C415L	\$ 6.34	\$ 1,103
Remove and stockpile liner protection cover	m3	2190	SB1L	\$ 4.30	\$ 9,417
Load contained contaminated soils into megabags for shipping off-site	m3	50	C412L	\$ 100.25	\$ 5,013
Haul megabags to Roberts Bay laydown	m3	53.4	C404L	\$ 6.34	\$ 339
Clean liner	m2	6521	C210L	\$ 0.39	\$ 2,543
Remove and cut liner into manageable pieces	m2	6521	C302L	\$ 0.56	\$ 3,652
Drain and wash empty fuel drums	each	150	C205L	\$ 60.00	\$ 9,000
Crush empty fuel drums	each	150	C301L	\$ 35.00	\$ 5,250
Load debris for transport to landfill	m3	68.2	C401L	\$ 13.13	\$ 895
Haul waste to Landfill	m3	68.2	C415L	\$ 6.34	\$ 432
Level containment berms	m2	279.3	C505L	\$ 1.58	\$ 441
Regrade area for positive drainage	m2	3650	C5018L	\$ 0.12	\$ 438

Quantity	Unit Cost	Errors Corrected Cost	
1013.8	\$ 8.90	\$ 9,022.82	\$ 13,750.82
1	\$ 1,500.00	\$ 1,500.00	
1	\$ 3,000.00	\$ 3,000.00	
1900	\$ 0.12	\$ 228.00	
4	\$ 10,000.00	\$ 40,000.00	\$ 491,345.07
1	\$ 550.00	\$ 550.00	
4	\$ 1,420.00	\$ 5,680.00	
50	\$ 30.00	\$ 1,500.00	
1	\$ 550.00	\$ 550.00	
4	\$ 100,000.00	\$ 400,000.00	
43.5	\$ 13.13	\$ 571.16	
51.4	\$ 6.34	\$ 325.88	
5455	\$ 4.30	\$ 23,456.50	
50	\$ 100.25	\$ 5,012.50	
56.8	\$ 6.34	\$ 360.11	
10300	\$ 0.39	\$ 4,017.00	
10300	\$ 0.56	\$ 5,768.00	
92.7	\$ 13.13	\$ 1,217.15	
92.7	\$ 6.34	\$ 587.72	
231.3	\$ 1.58	\$ 365.45	
11530	\$ 0.12	\$ 1,383.60	
1	\$ 10,000.00	\$ 10,000.00	\$ 221,347.93
1	\$ 10,000.00	\$ 10,000.00	
1	\$ 550.00	\$ 550.00	
2	\$ 1,420.00	\$ 2,840.00	
220	\$ 30.00	\$ 6,600.00	
1	\$ 550.00	\$ 550.00	
1	\$ 100,000.00	\$ 100,000.00	
1	\$ 50,000.00	\$ 50,000.00	
174	\$ 13.13	\$ 2,284.62	
174	\$ 6.34	\$ 1,103.16	
2190	\$ 4.30	\$ 9,417.00	
50	\$ 100.25	\$ 5,012.50	
53.4	\$ 6.34	\$ 338.56	
6521	\$ 0.39	\$ 2,543.19	
6521	\$ 0.56	\$ 3,651.76	
150	\$ 60.00	\$ 9,000.00	
150	\$ 35.00	\$ 5,250.00	
68.2	\$ 13.13	\$ 895.47	
68.2	\$ 6.34	\$ 432.39	
279.3	\$ 1.58	\$ 441.29	
3650	\$ 0.12	\$ 438.00	

Quantity	Unit Cost	Assumptions Corrected Cost	
1013.8	\$ 8.90	\$ 9,022.82	\$ 13,750.82
1	\$ 1,500.00	\$ 1,500.00	
1	\$ 3,000.00	\$ 3,000.00	
1900	\$ 0.12	\$ 228.00	
4	\$ 10,000.00	\$ 40,000.00	\$ 491,345.07
1	\$ 550.00	\$ 550.00	
4	\$ 1,420.00	\$ 5,680.00	
50	\$ 30.00	\$ 1,500.00	
1	\$ 550.00	\$ 550.00	
4	\$ 100,000.00	\$ 400,000.00	
43.5	\$ 13.13	\$ 571.16	
51.4	\$ 6.34	\$ 325.88	
5455	\$ 4.30	\$ 23,456.50	
50	\$ 100.25	\$ 5,012.50	
56.8	\$ 6.34	\$ 360.11	
10300	\$ 0.39	\$ 4,017.00	
10300	\$ 0.56	\$ 5,768.00	
92.7	\$ 13.13	\$ 1,217.15	
92.7	\$ 6.34	\$ 587.72	
231.3	\$ 1.58	\$ 365.45	
11530	\$ 0.12	\$ 1,383.60	
1	\$ 10,000.00	\$ 10,000.00	\$ 221,347.93
1	\$ 10,000.00	\$ 10,000.00	
1	\$ 550.00	\$ 550.00	
2	\$ 1,420.00	\$ 2,840.00	
220	\$ 30.00	\$ 6,600.00	
1	\$ 550.00	\$ 550.00	
1	\$ 100,000.00	\$ 100,000.00	
1	\$ 50,000.00	\$ 50,000.00	
174	\$ 13.13	\$ 2,284.62	
174	\$ 6.34	\$ 1,103.16	
2190	\$ 4.30	\$ 9,417.00	
50	\$ 100.25	\$ 5,012.50	
53.4	\$ 6.34	\$ 338.56	
6521	\$ 0.39	\$ 2,543.19	
6521	\$ 0.56	\$ 3,651.76	
150	\$ 60.00	\$ 9,000.00	
150	\$ 35.00	\$ 5,250.00	
68.2	\$ 13.13	\$ 895.47	
68.2	\$ 6.34	\$ 432.39	
279.3	\$ 1.58	\$ 441.29	
3650	\$ 0.12	\$ 438.00	

Quantity	AANDC Unit Cost	AANDC Cost	Unit Rates Corrected SRK Unit Cost	SRK Cost
1013.8	\$ 8.90	\$ 9,022.82	\$ 13,750.82	\$ 1.23 \$ 1,244.29 \$ 7,276.25
1	\$ 1,500.00	\$ 1,500.00	\$ 1,200.00	\$ 1,200.00
1	\$ 3,000.00	\$ 3,000.00	\$ 2,500.00	\$ 2,500.00
1900	\$ 0.12	\$ 228.00	\$ 1.23	\$ 2,331.97
4	\$ 10,000.00	\$ 40,000.00	\$ 491,345.07	\$ 256.75 \$ 1,027.01 \$ 435,805.97
1	\$ 550.00	\$ 550.00	\$ 1,288.18	\$ 1,288.18
4	\$ 1,420.00	\$ 5,680.00	\$ 1,123.28	\$ 4,493.14
50	\$ 30.00	\$ 1,500.00	\$ 31.00	\$ 1,549.99
1	\$ 550.00	\$ 550.00	\$ 448.37	\$ 448.37
4	\$ 100,000.00	\$ 400,000.00	\$ 100,000.00	\$ 400,000.00
43.5	\$ 13.13	\$ 571.16	\$ 10.23	\$ 444.91
51.4	\$ 6.34	\$ 325.88	\$ 5.99	\$ 308.06
5455	\$ 4.30	\$ 23,456.50	\$ 2.75	\$ 14,994.13
50	\$ 100.25	\$ 5,012.50	\$ 70.75	\$ 3,537.45
56.8	\$ 6.34	\$ 360.11	\$ 2.52	\$ 143.09
10300	\$ 0.39	\$ 4,017.00	\$ 0.39	\$ 4,017.30
10300	\$ 0.56	\$ 5,768.00	\$ 0.16	\$ 1,652.84
92.7	\$ 13.13	\$ 1,217.15	\$ 10.23	\$ 948.13
92.7	\$ 6.34	\$ 587.72	\$ 5.99	\$ 555.58
231.3	\$ 1.58	\$ 365.45	\$ 1.23	\$ 283.89
11530	\$ 0.12	\$ 1,383.60	\$ 0.01	\$ 113.91
1	\$ 10,000.00	\$ 10,000.00	\$ 221,347.93	\$ 256.75 \$ 256.75 \$ 183,822.79
1	\$ 10,000.00	\$ 10,000.00	\$ 256.75	\$ 256.75
1	\$ 550.00	\$ 550.00	\$ 448.37	\$ 448.37
2	\$ 1,420.00	\$ 2,840.00	\$ 1,123.28	\$ 2,246.57
220	\$ 30.00	\$ 6,600.00	\$ 31.00	\$ 6,819.95
1	\$ 550.00	\$ 550.00	\$ 448.37	\$ 448.37
1	\$ 100,000.00	\$ 100,000.00	\$ 100,000.00	\$ 100,000.00
1	\$ 50,000.00	\$ 50,000.00	\$ 50,000.00	\$ 50,000.00
174	\$ 13.13	\$ 2,284.62	\$ 10.23	\$ 1,779.66
174	\$ 6.34	\$ 1,103.16	\$ 5.99	\$ 1,042.84
2190	\$ 4.30	\$ 9,417.00	\$ 2.75	\$ 6,019.64
50	\$ 100.25	\$ 5,012.50	\$ 70.75	\$ 3,537.45
53.4	\$ 6.34	\$ 338.56	\$ 2.52	\$ 134.52
6521	\$ 0.39	\$ 2,543.19	\$ 0.39	\$ 2,543.38
6521	\$ 0.56	\$ 3,651.76	\$ 0.16	\$ 1,046.42
150	\$ 60.00	\$ 9,000.00	\$ 17.74	\$ 2,661.01
150	\$ 35.00	\$ 5,250.00	\$ 20.64	\$ 3,095.96
68.2	\$ 13.13	\$ 895.47	\$ 10.23	\$ 697.54
68.2	\$ 6.34	\$ 432.39	\$ 5.99	\$ 408.74
279.3	\$ 1.58	\$ 441.29	\$ 1.23	\$ 342.80
3650	\$ 0.12	\$ 438.00	\$ 0.01	\$ 36.06

ACTIVITY/MATERIAL	Units	Quantity	Cost Code	Unit Cost	Cost	Quantity	Unit Cost	Errors Corrected Cost		Quantity	Unit Cost	Assumptions Corrected Cost		Quantity	AANDC Unit Cost	AANDC Cost	Unit Rates Corrected SRK Unit Cost		SRK Cost						
MECHANICAL SHOP COMPLEX																									
Decommission electrical, mechanical, heating (including connections to generator house &	each	7	C105L	\$	640.00	\$	640.00	\$	4,480.00	\$	77,495.98	7	\$	640.00	\$	4,480.00	\$	77,495.98	\$	639.99	\$	4,479.94	\$	56,681.16	
Demolish (steel modular structure)	m3	2204.4	C305L	\$	19.00	\$	19.00	\$	41,883.60	2204.4	\$	19.00	\$	41,883.60	2204.4	\$	19.00	\$	41,883.60	\$	12.90	\$	28,428.61		
Demolish wood structures (warehouse roof, crew lounge)	m3	283.2	C305L	\$	19.00	\$	19.00	\$	5,380.80	283.2	\$	19.00	\$	5,380.80	283.2	\$	19.00	\$	5,380.80	\$	12.90	\$	3,652.23		
Demolish tent structure (light vehicle shop)	m3	460.3	C305L	\$	19.00	\$	19.00	\$	8,745.70	460.3	\$	19.00	\$	8,745.70	460.3	\$	19.00	\$	8,745.70	\$	12.90	\$	5,936.17		
Collect Debris	m2	685.8	C310L	\$	0.18	\$	0.18	\$	123.44	685.8	\$	0.18	\$	123.44	685.8	\$	0.18	\$	123.44	\$	0.17	\$	118.78		
Load debris for transport to landfill	m3	867.1	C401L	\$	13.13	\$	13.13	\$	11,385.02	867.1	\$	13.13	\$	11,385.02	867.1	\$	13.13	\$	11,385.02	\$	10.23	\$	8,868.63		
Haul debris to Landfill	m3	867.1	C415L	\$	6.34	\$	6.34	\$	5,497.41	867.1	\$	6.34	\$	5,497.41	867.1	\$	6.34	\$	5,497.41	\$	5.99	\$	5,196.80		
WASTE MANAGEMENT FACILITY																									
Collect ashes and place in containers	m3	0.5	C207L	\$	13.13	\$	13.13	\$	6.57	\$	22,021.71	0.5	\$	13.13	\$	6.57	\$	22,021.71	\$	747.69	\$	373.85	\$	19,409.63	
Dismantle (welding crew)	each	2	C308L	\$	1,500.00	\$	1,500.00	\$	3,000.00	2	\$	1,500.00	\$	3,000.00	2	\$	1,500.00	\$	3,000.00	\$	511.00	\$	1,022.00		
Demolish wood structures (roof, entryway, etc.)	m3	76.2	C305L	\$	19.00	\$	19.00	\$	1,447.80	76.2	\$	19.00	\$	1,447.80	76.2	\$	19.00	\$	1,447.80	\$	12.90	\$	982.70		
Disconnect containers and prep for shipping off-site	each	11	C108L	\$	1,325.00	\$	1,325.00	\$	14,575.00	11	\$	1,325.00	\$	14,575.00	11	\$	1,325.00	\$	14,575.00	\$	1,321.37	\$	14,535.06		
Collect all debris	m2	128.7	C310L	\$	0.18	\$	0.18	\$	23.17	128.7	\$	0.18	\$	23.17	128.7	\$	0.18	\$	23.17	\$	0.17	\$	22.29		
Load debris for transport to landfill	m3	152.5	C401L	\$	13.13	\$	13.13	\$	2,002.33	152.5	\$	13.13	\$	2,002.33	152.5	\$	13.13	\$	2,002.33	\$	10.23	\$	1,559.76		
Haul debris to Landfill	m3	152.5	C415L	\$	6.34	\$	6.34	\$	966.85	152.5	\$	6.34	\$	966.85	152.5	\$	6.34	\$	966.85	\$	5.99	\$	913.98		
LAYDOWN AREA																									
Decommission vehicle plug system	each	1	C105L	\$	640.00	\$	640.00	\$	640.00	\$	21,216.88	1	\$	640.00	\$	640.00	\$	21,216.88	\$	639.99	\$	639.99	\$	15,778.06	
Remove cables and posts	each	8	C314L	\$	150.00	\$	150.00	\$	1,200.00	8	\$	150.00	\$	1,200.00	8	\$	150.00	\$	1,200.00	\$	403.25	\$	3,225.96		
Collect all debris	m2	24491.6	C310L	\$	0.18	\$	0.18	\$	4,408.49	24491.6	\$	0.18	\$	4,408.49	24491.6	\$	0.18	\$	4,408.49	\$	0.17	\$	4,242.05		
Load debris for transport to landfill	m3	10	C401L	\$	13.13	\$	13.13	\$	131.30	10	\$	13.13	\$	131.30	10	\$	13.13	\$	131.30	\$	10.23	\$	102.28		
Haul debris to Landfill	m3	10	C415L	\$	6.34	\$	6.34	\$	63.40	10	\$	6.34	\$	63.40	10	\$	6.34	\$	63.40	\$	5.99	\$	59.93		
Regrade area for positive drainage	m2	24491.6	C518L	\$	0.12	\$	0.12	\$	2,938.99	24491.6	\$	0.12	\$	2,938.99	24491.6	\$	0.12	\$	2,938.99	\$	0.01	\$	241.97		
Laydown Area Expansion Collect all debris	m2	38800	C310L	\$	0.18	\$	0.18	\$	6,984.00	38800	\$	0.18	\$	6,984.00	38800	\$	0.18	\$	6,984.00	\$	0.17	\$	6,720.33		
Load waste into containers for shipping off-site	m3	10	C401L	\$	13.13	\$	13.13	\$	131.30	10	\$	13.13	\$	131.30	10	\$	13.13	\$	131.30	\$	10.23	\$	102.28		
Haul debris to Landfill	m3	10	C415L	\$	6.34	\$	6.34	\$	63.40	10	\$	6.34	\$	63.40	10	\$	6.34	\$	63.40	\$	5.99	\$	59.93		
Breach safety berms and Regrade area for positive drainage	m2	38800	C518L	\$	0.12	\$	0.12	\$	4,656.00	38800	\$	0.12	\$	4,656.00	38800	\$	0.12	\$	4,656.00	\$	0.01	\$	383.33		
OVERBURDEN DUMP																									
Collect all debris	m2	10448	C310L	\$	0.18	\$	0.18	\$	1,880.64	10448	\$	0.18	\$	1,880.64	10448	\$	0.18	\$	1,880.64	\$	0.17	\$	1,809.64	\$	15,259.14
Load waste into containers for shipping off-site	m3	10	C401L	\$	13.13	\$	13.13	\$	131.30	10	\$	13.13	\$	131.30	10	\$	13.13	\$	131.30	\$	10.23	\$	102.28		
Haul debris to Landfill	m3	10	C415L	\$	6.34	\$	6.34	\$	63.40	10	\$	6.34	\$	63.40	10	\$	6.34	\$	63.40	\$	5.99	\$	59.93		
Grade for positive drainage	m2	10448	C505L	\$	1.58	\$	1.58	\$	16,507.84	10448	\$	1.58	\$	16,507.84	10448	\$	1.58	\$	16,507.84	\$	1.23	\$	12,823.35		
Breach the berm to original ground in several locations (4 locations) to restore natural flow path	m2	378	C505L	\$	1.58	\$	1.58	\$	597.24	378	\$	1.58	\$	597.24	378	\$	1.58	\$	597.24	\$	1.23	\$	463.94		
ROBERTS BAY ACCESS ROAD																									
Crown road for positive drainage	m2	3378	C518L	\$	0.12	\$	0.12	\$	405.36	3378	\$	0.12	\$	405.36	3378	\$	0.12	\$	405.36	\$	0.01	\$	33.37	\$	33.37

ACTIVITY/MATERIAL	Units	Quantity	Cost Code	Unit Cost	Cost
COMMUNICATIONS TOWER					
Decommission Tower	each	1	C105L	\$ 640.00	\$ 640
Remove communication equipment	each	4	C107L	\$ 350.00	\$ 1,400
Dismantle towers	each	1	C311L	\$ 15,500.00	\$ 15,500
Prep tower sections for shipping off-site	m	8	C312L	\$ 1,500.00	\$ 12,000
Collect all debris	m2	1.4	C310L	\$ 0.18	\$ -
Load waste into containers for shipping off-site	m3	10.5	C401L	\$ 13.13	\$ 138
Haul hazardous waste to Roberts Bay	m3	5	C404L	\$ 6.34	\$ 32
Haul debris to Landfill	m2	5.5	C415L	\$ 6.34	\$ 35
ALL WEATHER AIRSTRIP					
Decommission Airstrip	each	1	C109L	\$ 1,500.00	\$ 1,500
Remove lighting fixtures (airstrip lighting, approach lights)	each	70	C110L	\$ 100.00	\$ 7,000
Collect all debris	m2	2850	C310L	\$ 0.18	\$ 513
Load waste for transport to landfill	m3	1.2	C401L	\$ 13.13	\$ 16
Haul debris to Landfill	m3	1.2	C416L	\$ 6.34	\$ 8
Crown airstrip and airstrip expansion for positive drainage	m2	42000	C518L	\$ 0.12	\$ 5,040
Other			#N/A	\$ -	\$ -
SOUTH APRON					
Crown for positive drainage	m2	4500	C518L	\$ 0.12	\$ 540
Other			#N/A	\$ -	\$ -
NORTH APRON					
Decommission electrical, and heating from traffic control tower	each	1	C107L	\$ 350.00	\$ 350
Demolish control tower structure (wood shack)	m3	11.7	C305L	\$ 19.00	\$ 222
Disconnect containers and prep for shipping off-site	each	5	C108L	\$ 1,325.00	\$ 6,625
Collect all debris	m2	12.2	C310L	\$ 0.18	\$ 2
Load waste for transport to landfill	m3	17.6	C401L	\$ 13.13	\$ 231
Haul debris to landfill	m3	17.6	C416L	\$ 6.34	\$ 112
Crown for positive drainage	m2	5517.2	C518L	\$ 0.12	\$ 662
Other			#N/A	\$ -	\$ -
Annual pumping costs				\$ -	
Number of years of pump flooding	years				\$ -
Total pumping costs				\$ -	
Total				\$ 947,269	
% of Total					

Quantity	Unit Cost	Errors Corrected Cost		
1	\$ 640.00	\$ 640.00	\$ 29,744.69	
4	\$ 350.00	\$ 1,400.00		
1	\$ 15,500.00	\$ 15,500.00		
8	\$ 1,500.00	\$ 12,000.00		
1.4	\$ 0.18	\$ 0.25		
10.5	\$ 13.13	\$ 137.87		
5	\$ 6.34	\$ 31.70		
5.5	\$ 6.34	\$ 34.87		
1	\$ 1,500.00	\$ 1,500.00	\$ 14,076.36	
70	\$ 100.00	\$ 7,000.00		
2850	\$ 0.18	\$ 513.00		
1.2	\$ 13.13	\$ 15.76		
1.2	\$ 6.34	\$ 7.61		
42000	\$ 0.12	\$ 5,040.00		
0	\$ -	\$ -		
4500	\$ 0.12	\$ 540.00	\$ 540.00	
0	\$ -	\$ -		
1	\$ 350.00	\$ 350.00	\$ 8,204.23	
11.7	\$ 19.00	\$ 222.30		
5	\$ 1,325.00	\$ 6,625.00		
12.2	\$ 0.18	\$ 2.20		
17.6	\$ 13.13	\$ 231.09		
17.6	\$ 6.34	\$ 111.58		
5517.2	\$ 0.12	\$ 662.06		
0	\$ -	\$ -		
				\$ 919,329.45

Quantity	Unit Cost	Assumptions Corrected Cost		
1	\$ 640.00	\$ 640.00	\$ 29,744.69	
4	\$ 350.00	\$ 1,400.00		
1	\$ 15,500.00	\$ 15,500.00		
8	\$ 1,500.00	\$ 12,000.00		
1.4	\$ 0.18	\$ 0.25		
10.5	\$ 13.13	\$ 137.87		
5	\$ 6.34	\$ 31.70		
5.5	\$ 6.34	\$ 34.87		
1	\$ 1,500.00	\$ 1,500.00	\$ 14,076.36	
70	\$ 100.00	\$ 7,000.00		
2850	\$ 0.18	\$ 513.00		
1.2	\$ 13.13	\$ 15.76		
1.2	\$ 6.34	\$ 7.61		
42000	\$ 0.12	\$ 5,040.00		
0	\$ -	\$ -		
4500	\$ 0.12	\$ 540.00	\$ 540.00	
0	\$ -	\$ -		
1	\$ 350.00	\$ 350.00	\$ 8,204.23	
11.7	\$ 19.00	\$ 222.30		
5	\$ 1,325.00	\$ 6,625.00		
12.2	\$ 0.18	\$ 2.20		
17.6	\$ 13.13	\$ 231.09		
17.6	\$ 6.34	\$ 111.58		
5517.2	\$ 0.12	\$ 662.06		
0	\$ -	\$ -		
				\$ 919,329.45

Quantity	AANDC Unit Cost	AANDC Cost	Unit Rates Corrected SRK Unit Cost		SRK Cost	
1	\$ 640.00	\$ 640.00	\$ 29,744.69	\$ 639.99	\$ 639.99	\$ 22,571.56
4	\$ 350.00	\$ 1,400.00		\$ 352.56	\$ 1,410.25	
1	\$ 15,500.00	\$ 15,500.00		\$ 15,417.42	\$ 15,417.42	
8	\$ 1,500.00	\$ 12,000.00		\$ 619.32	\$ 4,954.53	
1.4	\$ 0.18	\$ 0.25		\$ 0.17	\$ 0.24	
10.5	\$ 13.13	\$ 137.87		\$ 10.23	\$ 107.39	
5	\$ 6.34	\$ 31.70		\$ 1.75	\$ 8.77	
5.5	\$ 6.34	\$ 34.87		\$ 5.99	\$ 32.96	
1	\$ 1,500.00	\$ 1,500.00	\$ 14,076.36	\$ 306.75	\$ 306.75	\$ 4,033.99
70	\$ 100.00	\$ 7,000.00		\$ 40.00	\$ 2,799.96	
2850	\$ 0.18	\$ 513.00		\$ 0.17	\$ 493.63	
1.2	\$ 13.13	\$ 15.76		\$ 10.23	\$ 12.27	
1.2	\$ 6.34	\$ 7.61		\$ 5.36	\$ 6.43	
42000	\$ 0.12	\$ 5,040.00		\$ 0.01	\$ 414.94	
0	\$ -	\$ -		\$ -	\$ -	
4500	\$ 0.12	\$ 540.00	\$ 540.00	\$ 0.01	\$ 44.46	\$ 44.46
0	\$ -	\$ -		\$ -	\$ -	
1	\$ 350.00	\$ 350.00	\$ 8,204.23	\$ 352.56	\$ 352.56	\$ 7,441.25
11.7	\$ 19.00	\$ 222.30		\$ 12.90	\$ 150.89	
5	\$ 1,325.00	\$ 6,625.00		\$ 1,321.37	\$ 6,606.84	
12.2	\$ 0.18	\$ 2.20		\$ 0.17	\$ 2.11	
17.6	\$ 13.13	\$ 231.09		\$ 10.23	\$ 180.01	
17.6	\$ 6.34	\$ 111.58		\$ 5.36	\$ 94.33	
5517.2	\$ 0.12	\$ 662.06		\$ 0.01	\$ 54.51	
0	\$ -	\$ -				
				\$ 919,329.45	\$ 768,157.63	

ACTIVITY/MATERIAL	Unit	Qty	Code	Unit Cost	Cost	Quantity	Unit Cost	Errors Corrected Cost	Quantity	Unit Cost	Assumptions Corrected Cost	Quantity	AANDC Unit Cost	AANDC Cost	Unit Rates Corrected SRK Cost	SRK Unit Cost	SRK Cost	
DORIS NORTH DECLINE PORTAL								\$ 28,816.23			\$ 28,816.23							
Remove ducts, pipes, electrical cables	lm	100	C316L	\$113.00	\$ 11,300.00	100	\$113.00	\$ 11,300.00	100	\$113.00	\$ 11,300.00	100	\$113.00	\$ 11,300.00	\$ 28,816.23	\$112.09	\$ 11,209.30	\$ 28,565.81
Construct portal plug	m3	707	C503L	\$24.53	\$ 17,343.00	707	\$24.53	\$ 17,342.71	707	\$24.53	\$ 17,342.71	707	\$24.53	\$ 17,342.71		\$24.53	\$ 17,342.23	
Regrade area for positive drainage	m2	1446	C518L	\$0.12	\$ 174.00	1446	\$0.12	\$ 173.52	1446	\$0.12	\$ 173.52	1446	\$0.12	\$ 173.52		\$0.01	\$ 14.29	
DORIS NORTH VENT RAISE								\$ 68,815.47			\$ 64,840.47				\$ 74,434.97		\$ 35,012.23	
Remove ducts, pipes, and cables	lm	100	C316L	\$113.00	\$ 11,300.00	100	\$113.00	\$ 11,300.00	100	\$113.00	\$ 11,300.00	100	\$113.00	\$ 11,300.00		\$112.09	\$ 11,209.30	
Construct a concrete cap (0.5 m thick reinforced concrete) to seal the top	each	1	C603L	\$40,000.00	\$ 40,000.00	1	\$40,000.00	\$ 40,000.00	1	\$40,000.00	\$ 40,000.00	1	\$40,000.00	\$ 40,000.00		\$14,007.27	\$ 14,007.27	
Decommission and dismantle all ventilation and heating facilities	each	4	C105L	\$640.00	\$ 2,560.00	4	\$640.00	\$ 2,560.00	4	\$640.00	\$ 2,560.00	4	\$640.00	\$ 2,560.00		\$639.99	\$ 2,559.97	
Prepare units for shipping off-site	each	4	C108L	\$1,325.00	\$ 5,300.00	4	\$1,325.00	\$ 5,300.00	1	\$1,325.00	\$ 1,325.00	1	\$1,325.00	\$ 1,325.00		\$1,321.37	\$ 1,321.37	
Haul units to Roberts Bay	hrs	3	C404AL	\$155.00	\$ 465.00	3	\$155.00	\$ 465.00	3	\$155.00	\$ 465.00	33.2	\$155.00	\$ 5,146.00		\$2.52	\$ 83.64	
Regrade pads for positive drainage	m2	4150	C518L	\$0.12	\$ 498.00	4150	\$0.12	\$ 498.00	4150	\$0.12	\$ 498.00	4150	\$0.12	\$ 498.00		\$0.01	\$ 41.00	
Drain and decommission Enviro Tank	each	1	C203L	\$10,000.00	\$ 10,000.00	1	\$1,000.00	\$ 1,000.00	1	\$1,000.00	\$ 1,000.00	1	\$1,000.00	\$ 1,000.00		\$256.75	\$ 256.75	
Haul Enviro Tank to Roberts Bay	hrs	1.5	C404AL	\$155.00	\$ 233.00	1.5	\$155.00	\$ 232.50	1.5	\$155.00	\$ 232.50	33.2	\$155.00	\$ 5,146.00		\$2.52	\$ 83.64	
Remove liner and cut into manageable pieces	m2	1230	C302L	\$0.56	\$ 689.00	1230	\$0.56	\$ 688.80	1230	\$0.56	\$ 688.80	1230	\$0.56	\$ 688.80		\$0.16	\$ 197.38	
Load waste for transport to landfill	m3	11	C401L	\$13.13	\$ 144.00	11	\$13.13	\$ 144.43	11	\$13.13	\$ 144.43	11	\$13.13	\$ 144.43		\$10.23	\$ 112.51	
Haul waste to landfill	m3	11	C414L	\$6.34	\$ 70.00	11	\$6.34	\$ 69.74	11	\$6.34	\$ 69.74	11	\$6.34	\$ 69.74		\$4.17	\$ 45.92	
Backfill area to prevent permanent ponding	m2	4150	C505L	\$1.58	\$ 6,557.00	4150	\$1.58	\$ 6,557.00	4150	\$1.58	\$ 6,557.00	4150	\$1.58	\$ 6,557.00		\$1.23	\$ 5,093.50	
DORIS CONNECTOR VENT RAISE								\$ 58,102.51			\$ 56,777.51				\$ 56,978.49		\$ 30,074.80	
Remove ducts, pipes, and cables	lm	100	C316L	\$113.00	\$ 11,300.00	100	\$113.00	\$ 11,300.00	100	\$113.00	\$ 11,300.00	100	\$113.00	\$ 11,300.00		\$112.09	\$ 11,209.30	
Decommission and dismantle all ventilation facilities	each	2	C105L	\$640.00	\$ 1,280.00	2	\$640.00	\$ 1,280.00	2	\$640.00	\$ 1,280.00	2	\$640.00	\$ 1,280.00		\$639.99	\$ 1,279.98	
Prepare units for shipping off-site	each	2	C108L	\$1,325.00	\$ 2,650.00	2	\$1,325.00	\$ 2,650.00	1	\$1,325.00	\$ 1,325.00	1	\$1,325.00	\$ 1,325.00		\$1,321.37	\$ 1,321.37	
Haul units to Roberts Bay	hrs	1.5	C404L	\$6.34	\$ 10.00	1.5	\$6.34	\$ 9.51	1.5	\$6.34	\$ 9.51	33.2	\$6.34	\$ 210.49		\$2.52	\$ 83.64	
Construct a concrete cap (0.5 m thick reinforced concrete) to seal the top	each	1	C603L	\$40,000.00	\$ 40,000.00	1	\$40,000.00	\$ 40,000.00	1	\$40,000.00	\$ 40,000.00	1	\$40,000.00	\$ 40,000.00		\$14,007.27	\$ 14,007.27	
Remove culvert	each	1	RCULL	\$2,625.00	\$ 2,625.00	1	\$2,625.00	\$ 2,625.00	1	\$2,625.00	\$ 2,625.00	1	\$2,625.00	\$ 2,625.00		\$2,000.00	\$ 2,000.00	
Crown road for positive drainage	km	0.2	CRWNL	\$1,190.00	\$ 238.00	0.2	\$1,190.00	\$ 238.00	0.2	\$1,190.00	\$ 238.00	0.2	\$1,190.00	\$ 238.00		\$866.22	\$ 173.24	
DORSI CENTRAL VENT RAISE								\$ 58,697.51			\$ 57,372.51				\$ 57,573.49		\$ 30,507.91	
Remove ducts, pipes, and cables	lm	100	C316L	\$113.00	\$ 11,300.00	100	\$113.00	\$ 11,300.00	100	\$113.00	\$ 11,300.00	100	\$113.00	\$ 11,300.00		\$112.09	\$ 11,209.30	
Decommission and dismantle all ventilation facilities	each	2	C105L	\$640.00	\$ 1,280.00	2	\$640.00	\$ 1,280.00	2	\$640.00	\$ 1,280.00	2	\$640.00	\$ 1,280.00		\$639.99	\$ 1,279.98	
Prepare units for shipping off-site	each	2	C108L	\$1,325.00	\$ 2,650.00	2	\$1,325.00	\$ 2,650.00	1	\$1,325.00	\$ 1,325.00	1	\$1,325.00	\$ 1,325.00		\$1,321.37	\$ 1,321.37	
Haul units to Roberts Bay	hrs	1.5	C404L	\$6.34	\$ 10.00	1.5	\$6.34	\$ 9.51	1.5	\$6.34	\$ 9.51	33.2	\$6.34	\$ 210.49		\$2.52	\$ 83.64	

ACTIVITY/MATERIAL	Units	Quantity	Cost Code	Unit Cost	Cost	Errors Corrected				Assumptions Corrected				Unit Rates Corrected						
						Quantity	Unit Cost	Cost		Quantity	Unit Cost	Cost		Quantity	AANDC Unit Cost	AANDC Cost	SRK Unit Cost	SRK Cost		
Load waste into containers for transport to landfill	m3	176.6	C401L	\$ 13.13	\$ 2,319.00	176.6	\$ 13.13	\$ 2,318.76		176.6	\$ 13.13	\$ 2,318.76		176.6	\$13.13	\$ 2,318.76	\$10.23	\$ 1,806.25		
Haul waste to landfill	m3	176.6	C414L	\$ 6.34	\$ 1,120.00	176.6	\$ 6.34	\$ 1,119.64		176.6	\$ 6.34	\$ 1,119.64		176.6	\$6.34	\$ 1,119.64	\$4.70	\$ 829.97		
Level containment berms	m2	962	C505L	\$ 1.58	\$ 1,520.00	962	\$ 1.58	\$ 1,519.96		962	\$ 1.58	\$ 1,519.96		962	\$1.58	\$ 1,519.96	\$1.23	\$ 1,180.71		
Regrade area for positive drainage	m2	4927.7	C518L	\$ 0.12	\$ 591.00	4927.7	\$ 0.12	\$ 591.32		4927.7	\$ 0.12	\$ 591.32		4927.7	\$0.12	\$ 591.32	\$0.01	\$ 48.68		
PERMANAENT POWER GENERATOR																				
Decommission (electrical)	each	8	C106L	\$ 750.00	\$ 6,000.00	8	\$ 750.00	\$ 6,000.00	\$ 62,754.20	8	\$ 750.00	\$ 6,000.00	62754.2044	8	\$750.00	\$ 6,000.00	\$ 60,054.20	\$754.18	\$ 6,033.41	\$ 47,993.55
Disconnect containers and prep for shipping off-site	each	8	C108L	\$ 1,325.00	\$ 10,600.00	8	\$ 1,325.00	\$ 10,600.00		8	\$ 1,325.00	\$ 10,600.00		8	\$1,325.00	\$ 10,600.00	\$1,321.37	\$ 10,570.95		
Haul containers to Roberts Bay laydown	m3	265.66	C404L	\$ 6.34	\$ 1,684.00	265.66	\$ 6.34	\$ 1,684.28		265.66	\$ 6.34	\$ 1,684.28		265.66	\$6.34	\$ 1,684.28	\$2.52	\$ 669.23		
Dismantle stacks	each	2	C313L	\$ 20,000.00	\$ 40,000.00	2	\$ 20,000.00	\$ 40,000.00		2	\$ 20,000.00	\$ 40,000.00		40	\$20,000.00	\$ 40,000.00	\$128.38	\$ 5,135.04	unit rate and quantities non-interchangeable	
Prep stacks for shipping off-site	each	2	C312L	\$ 1,500.00	\$ 3,000.00	2	\$ 1,500.00	\$ 3,000.00		2	\$ 1,500.00	\$ 3,000.00		40	\$1,500.00	\$ 300.00	\$619.32	\$ 24,772.64		
Haul stack sections to Roberts Bay laydown	m3	166	C404L	\$ 6.34	\$ 1,052.00	166	\$ 6.34	\$ 1,052.44		166	\$ 6.34	\$ 1,052.44		166	\$6.34	\$ 1,052.44	\$2.52	\$ 418.18		
Collect all debris	m2	2103	C310L	\$ 0.18	\$ 379.00	2103	\$ 0.18	\$ 378.54		2103	\$ 0.18	\$ 378.54		2103	\$0.18	\$ 378.54	\$0.17	\$ 364.25		
Load waste for shipping to landfill	m3	2	C401L	\$ 13.13	\$ 26.00	2	\$ 13.13	\$ 26.26		2	\$ 13.13	\$ 26.26		2	\$13.13	\$ 26.26	\$10.23	\$ 20.46		
Haul waste to landfill	m3	2	C414L	\$ 6.34	\$ 13.00	2	\$ 6.34	\$ 12.68		2	\$ 6.34	\$ 12.68		2	\$6.34	\$ 12.68	\$4.70	\$ 9.40		
BACKUP POWER GENERATOR																				
Decommission (electrical)	each	4	c105l	\$ 640.00	\$ 2,560.00	4	\$ 640.00	\$ 2,560.00	\$ 8,706.29	4	\$ 640.00	\$ 2,560.00	8706.286	4	\$640.00	\$ 2,560.00	\$ 8,706.29	\$639.99	\$ 2,559.97	\$ 7,324.21
Disconnect generator units and prep for shipping off-site	each	2	c106l	\$ 750.00	\$ 1,500.00	2	\$ 750.00	\$ 1,500.00		2	\$ 750.00	\$ 1,500.00		2	\$750.00	\$ 1,500.00	\$754.18	\$ 1,508.35		
Haul units to Roberts Bay laydown	m3	67.6	C404L	\$ 6.34	\$ 429.00	67.6	\$ 6.34	\$ 428.58		67.6	\$ 6.34	\$ 428.58		67.6	\$6.34	\$ 428.58	\$2.52	\$ 170.29		
Demolish tent housing structure	m3	94.1	C305L	\$ 19.00	\$ 1,788.00	94.1	\$ 19.00	\$ 1,787.90		94.1	\$ 19.00	\$ 1,787.90		94.1	\$19.00	\$ 1,787.90	\$12.90	\$ 1,213.54		
Collect all debris	m2	259.3	C310L	\$ 0.18	\$ 47.00	259.3	\$ 0.18	\$ 46.67		259.3	\$ 0.18	\$ 46.67		259.3	\$0.18	\$ 46.67	\$0.17	\$ 44.91		
Load waste for shipping to landfill	m3	122.4	C401L	\$ 13.13	\$ 1,607.00	122.4	\$ 13.13	\$ 1,607.11		122.4	\$ 13.13	\$ 1,607.11		122.4	\$13.13	\$ 1,607.11	\$10.23	\$ 1,251.90		
Haul waste to landfill	m3	122.4	C414L	\$ 6.34	\$ 776.00	122.4	\$ 6.34	\$ 776.02		122.4	\$ 6.34	\$ 776.02		122.4	\$6.34	\$ 776.02	\$4.70	\$ 575.24		
SEWAGE TREATMENT PLANT																				
Flush and remove sewage plumbing, collect sewage sludge/waste water in 55 gallon drum	each	9	C206L	\$ 657.86	\$ 5,921.00	9	\$ 657.86	\$ 5,920.74	\$ 27,863.27	9	\$ 657.86	\$ 5,920.74	27863.274	9	\$657.86	\$ 5,920.74	\$ 27,863.27	\$657.86	\$ 5,920.78	\$ 25,438.89
Decommission (electrical) 9.0 each	each	9	C105L	\$ 640.00	\$ 5,760.00	9	\$ 640.00	\$ 5,760.00		9	\$ 640.00	\$ 5,760.00		9	\$640.00	\$ 5,760.00	\$639.99	\$ 5,759.93		
Disconnect containers and prep for shipping off-site	each	9	C108L	\$ 1,325.00	\$ 11,925.00	9	\$ 1,325.00	\$ 11,925.00		9	\$ 1,325.00	\$ 11,925.00		9	\$1,325.00	\$ 11,925.00	\$1,321.37	\$ 11,892.32		
Haul containers to Roberts Bay laydown	m3	597.6	C404L	\$ 6.34	\$ 3,789.00	597.6	\$ 6.34	\$ 3,788.78		597.6	\$ 6.34	\$ 3,788.78		597.6	\$6.34	\$ 3,788.78	\$2.52	\$ 1,505.43		
Collect Debris	m2	29.8	C310L	\$ 0.18	\$ 5.00	29.8	\$ 0.18	\$ 5.36		29.8	\$ 0.18	\$ 5.36		29.8	\$0.18	\$ 5.36	\$0.17	\$ 5.16		
Load debris into containers for transport (to Roberts Bay)	m3	2.8	C401L	\$ 13.13	\$ 37.00	23.8	\$ 13.13	\$ 312.49	typo (?)	23.8	\$ 13.13	\$ 312.49		23.8	\$13.13	\$ 312.49	\$10.23	\$ 243.42		
Haul debris to Roberts Bay	m3	23.8	C414L	\$ 6.34	\$ 151.00	23.8	\$ 6.34	\$ 150.89		23.8	\$ 6.34	\$ 150.89		23.8	\$6.34	\$ 150.89	\$4.70	\$ 111.85		
FIRE WATER STORAGE TANK																				
Decommission and disconnect electrical and plumbing	each	3	C105L	\$ 640.00	\$ 1,920.00	3	\$ 640.00	\$ 1,920.00	\$ 42,347.69	3	\$ 640.00	\$ 1,920.00	42347.691	3	\$640.00	\$ 1,920.00	\$ 42,347.69	\$1,288.18	\$ 3,864.54	\$ 44,714.10
Disconnect and remove container housing the pumps and controls, and prep for shipping	each	1	C108L	\$ 1,325.00	\$ 1,325.00	1	\$ 1,325.00	\$ 1,325.00		1	\$ 1,325.00	\$ 1,325.00		1	\$1,325.00	\$ 1,325.00	\$1,321.37	\$ 1,321.37		

ACTIVITY/MATERIAL	Units	Quantity	Cost Code	Unit Cost	Cost	Errors Corrected					Assumptions Corrected					Unit Rates Corrected										
						Quantity	Unit Cost	Cost				Quantity	Unit Cost	Cost				Quantity	AANDC Unit Cost	AANDC Cost	SRK Unit Cost	SRK Cost				
Remove water intake line from Doris Lake	lm	25	PLRH	\$	72.00	\$					25	\$	72.00	\$	1,800.00			10416.092			10,416.09	\$11.13	\$	278.14	\$	7,879.88
Decommission pumping facility (remove electrical)	each	2	C105L	\$	640.00	\$					2	\$	640.00	\$	1,280.00						\$1,288.18	\$	2,576.36			
Prep containers for shipping off-site	each	2	C108L	\$	1,325.00	\$					2	\$	1,325.00	\$	2,650.00						\$1,321.37	\$	2,642.74			
Disconnect and remove generator fuel tank (place in Doris tank farm for cleaning)	each	1	C105L	\$	640.00	\$					1	\$	640.00	\$	640.00						\$93.46	\$	93.46			
Clean Tidy Tank and prep for shipping off-site	each	1	C204L	\$	1,420.00	\$					1	\$	1,420.00	\$	1,420.00						\$23.40	\$	23.40			
Run oil-water separator	m3	3	C208L	\$	30.00	\$					3	\$	30.00	\$	90.00						\$31.00	\$	93.00			
Prep generator container for shipping off-site	each	1	C108L	\$	1,325.00	\$					1	\$	1,325.00	\$	1,325.00						\$1,321.37	\$	1,321.37			
Haul containers to Roberts Bay laydown	m3	66.4	C404L	\$	6.34	\$					66.4	\$	6.34	\$	420.98						\$2.52	\$	167.27			
Collect Debris	m2	2226.2	C310L	\$	0.18	\$					2226.2	\$	0.18	\$	400.72						\$0.17	\$	385.59			
Load debris for transport to landfill	m3	20	C401L	\$	13.13	\$					20	\$	13.13	\$	262.60						\$10.23	\$	204.56			
Haul debris to landfill	m3	20	C414L	\$	6.34	\$					20	\$	6.34	\$	126.80						\$4.70	\$	93.99			
SEDIMENTATION / POLLUTION CONTROL POND																										
Disconnect piping and electrical wiring, remove sump pumps	each	2	C105L	\$	640.00	\$					2	\$	640.00	\$	1,280.00			21406.741			21,406.74	\$639.99	\$	1,279.98	\$	7,715.33
Remove and cut liner into manageable pieces (Sedimentation Pond only)	m2	14110	C302L	\$	0.56	\$					14110	\$	0.56	\$	7,901.60						\$0.16	\$	2,264.23			
Load waste for transport to Landfill	m3	42.3	C401L	\$	13.13	\$					42.3	\$	13.13	\$	555.40						\$10.23	\$	432.64			
Haul Debris to landfill	m3	42.3	C414L	\$	6.34	\$					42.3	\$	6.34	\$	268.18						\$4.70	\$	198.80			
Breach Pollution Control pond and Sedimentation Pond containment berms	m3	2608.2	SB1L	\$	4.30	\$					2608.2	\$	4.30	\$	11,215.26			local excavation, rate too high			\$1.23	\$	3,201.17			
Rip-rap breach for erosion protection	m3	13.8	RR1L	\$	13.50	\$					13.8	\$	13.50	\$	186.30						\$24.53	\$	338.50			
UNDERGROUND SUPPORT MECHANICAL SHOP																										
Decommission electrical, mechanical (including connections to generator house & transt	each	3	C105L	\$	640.00	\$					3	\$	640.00	\$	1,920.00			55821.553			55,821.55	\$639.99	\$	1,919.98	\$	39,377.39
Demolish building	m3	2281.6	C305L	\$	19.00	\$					2281.6	\$	19.00	\$	43,350.40						\$12.90	\$	29,424.20			
Collect Debris	m2	456.3	C310L	\$	0.18	\$					456.3	\$	0.18	\$	82.13						\$0.17	\$	79.03			
Load waste for transport to Landfill	m3	504.5	C401L	\$	13.13	\$					504.5	\$	13.13	\$	6,624.09						\$10.23	\$	5,159.98			
Haul debris to landfill	m3	504.5	C414L	\$	6.34	\$					504.5	\$	6.34	\$	3,198.53						\$4.70	\$	2,371.00			
Load hazardous waste into container for transport off site	m3	33.2	C401L	\$	13.13	\$					33.2	\$	13.13	\$	435.92						\$10.23	\$	339.57			
Haul Waste container to Roberts Bay	m3	33.2	C414L	\$	6.34	\$					33.2	\$	6.34	\$	210.49						\$2.52	\$	83.64			
FRESH WATER PIPELINES																										
Cut pipelines into manageable pieces	lm	830	PLRL	\$	22.00	\$					830	\$	22.00	\$	18,260.00			21465.576			21,465.58	\$11.13	\$	9,234.31	\$	12,492.36
Decommission electrical (heat tracing)	each	4	C105L	\$	640.00	\$					4	\$	640.00	\$	2,560.00						\$639.99	\$	2,559.97			
Collect electrical cables and controllers and prep for shipping off-site	m2	1600	C310L	\$	0.18	\$					1600	\$	0.18	\$	288.00						\$0.17	\$	277.13			
Load debris for transport to landfill	m3	28.2	C404L	\$	6.34	\$					28.2	\$	6.34	\$	178.79						\$10.23	\$	288.43			
Haul debris to landfill	m3	28.2	C414L	\$	6.34	\$					28.2	\$	6.34	\$	178.79						\$4.70	\$	132.53			
HELECOPTER SUPPORT FACILITIES																										
Dismantle helicopter pads and walkway	m3	15	C305L	\$	19.00	\$					15	\$	19.00	\$	285.00			7150.712			7,150.71	\$4.13	\$	61.93	\$	5,018.03
Demolish helishack	m3	27.9	C305L	\$	19.00	\$					27.9	\$	19.00	\$	530.10						\$12.90	\$	359.81			
Demolish washcar and other facilities	m3	81.8	C305L	\$	19.00	\$					81.8	\$	19.00	\$	1,554.20						\$12.90	\$	1,054.92			
Collect Debris	m2	154.2	C310L	\$	0.18	\$					154.2	\$	0.18	\$	27.76						\$0.17	\$	26.71			
Load debris for transport to landfill	m3	234.4	C401L	\$	13.13	\$					234.4	\$	13.13	\$	3,077.67						\$10.23	\$	2,397.42			
Haul debris to landfil	m3	234.4	C414L	\$	6.34	\$					234.4	\$	6.34	\$	1,486.10						\$4.70	\$	1,101.61			
Regrade surface for positive drainage	m2	1582.4	C518L	\$	0.12	\$					1582.4	\$	0.12	\$	189.89						\$0.01	\$	15.63			
WASTE ROCK PAD																										
No decomm required	m2	11500	#N/A	\$	-	\$					11500	\$	-	\$	-			0			-	\$0.00	\$	-	\$	-

ACTIVITY/MATERIAL	Units	Quantity	Cost Code	Unit Cost	Cost	
RUN-OFF DIVERSION BERM						
Breach the berm to original ground in several locations (4 locations) to restore natural flo	m3	378	SB1L	\$ 4.30	\$	1,625.00
Remove cut liners and load for transport to landfill	m3	0.3	C302L	\$ 0.56	\$	-
Haul debris to landfill	m3	0.3	C414L	\$ 6.34	\$	2.00
SEWAGE DISCHARGE LINE						
Flush pipeline prior to decommissioning	each	1	SEWL	\$ 770.00	\$	770.00
Cut pipelines into manageable pieces and place in containers for shipping off-site	lm	1190	PLRL	\$ 22.00	\$	26,180.00
Remove electrical cables and controllers	each	1	C105L	\$ 640.00	\$	640.00
Load debris into containers for shipping off-site	m3	90.8	C412L	\$ 100.25	\$	9,103.00
Haul debris to landfill	m3	90.8	C414L	\$ 6.34	\$	576.00
SEDIMENTATION BERM						
Breach the berm to restore a free drainage path	m2	24	SB1L	\$ 4.30	\$	103.00
Rip-rap breach for erosion protection	m3	3.6	RR1L	\$ 13.50	\$	49.00
SUMPS						
Decommission sumps	each	2	C102L	\$ 550.00	\$	1,100.00
Remove pumps, pipes, cables, culverts	ls	2	RPPCL	\$ 2,000.00	\$	4,000.00
Backfill sump excavation	m3	28.3	SBSL	\$ 3.20	\$	91.00
EXPANDED WASTE ROCK STORAGE (PAD T)						
Regrade Stockpile	m2	50400	SBSL	\$ 3.20	\$	161,280.00
Load waste for transport to landfill	m3	10	C401L	\$ 13.13	\$	131.00
Haul debris to landfill	m3	10	C404L	\$ 6.34	\$	63.00
EXPANDED LAYDOWN AREA (PAD U)						
Remove pumps, pipes, cables, culverts	ls	1	RPPCL	\$ 2,000.00	\$	2,000.00
Breach Sedimentation Pond containment berms	m3	120	SB1L	\$ 4.30	\$	516.00
Collect all debris	m2	35200	C310L	\$ 0.18	\$	6,336.00
LHD remaining ore to TIA	m3	1760	SBSH	\$ 16.35	\$	28,776.00
Load waste into containers for shipping off-site	m3	10	C412L	\$ 100.25	\$	1,003.00
Haul containers to landfill	m3	10	C414L	\$ 6.34	\$	63.00
Total						\$ 4,369,083.00
% of Total						

Errors Corrected					
Quantity	Unit Cost	Cost			
378	\$ 4.30	\$ 1,625.40	\$	1,627.47	
0.3	\$ 0.56	\$ 0.17			
0.3	\$ 6.34	\$ 1.90			
1	\$ 770.00	\$ 770.00	\$	37,268.37	
1190	\$ 22.00	\$ 26,180.00			
1	\$ 640.00	\$ 640.00			
90.8	\$ 100.25	\$ 9,102.70			
90.8	\$ 6.34	\$ 575.67			
24	\$ 4.30	\$ 103.20	\$	151.80	
3.6	\$ 13.50	\$ 48.60			
2	\$ 550.00	\$ 1,100.00	\$	5,190.56	
2	\$ 2,000.00	\$ 4,000.00			
28.3	\$ 3.20	\$ 90.56			
50400	\$ 3.20	\$ 161,280.00	\$	161,474.70	
10	\$ 13.13	\$ 131.30			
10	\$ 6.34	\$ 63.40			
1	\$ 2,000.00	\$ 2,000.00	\$	21,005.90	
120	\$ 4.30	\$ 516.00			
35200	\$ 0.18	\$ 6,336.00			
1760	\$ 6.30	\$ 11,088.00			SBSH in Reclaim is 6.30, not 16.35
10	\$ 100.25	\$ 1,002.50			
10	\$ 6.34	\$ 63.40			
\$ 4,082,822.71					

Assumptions Corrected				
Quantity	Unit Cost	Cost		
378	\$ 4.30	\$ 1,625.40		1627.47
0.3	\$ 0.56	\$ 0.17		
0.3	\$ 6.34	\$ 1.90		
1	\$ 770.00	\$ 770.00		37268.372
1190	\$ 22.00	\$ 26,180.00		
1	\$ 640.00	\$ 640.00		
90.8	\$ 100.25	\$ 9,102.70		
90.8	\$ 6.34	\$ 575.67		
24	\$ 4.30	\$ 103.20		151.8
3.6	\$ 13.50	\$ 48.60		
2	\$ 550.00	\$ 1,100.00		5190.56
2	\$ 2,000.00	\$ 4,000.00		
28.3	\$ 3.20	\$ 90.56		
50400	\$ 3.20	\$ 161,280.00		161474.7
10	\$ 13.13	\$ 131.30		
10	\$ 6.34	\$ 63.40		
1	\$ 2,000.00	\$ 2,000.00		21005.9
120	\$ 4.30	\$ 516.00		
35200	\$ 0.18	\$ 6,336.00		
1760	\$ 6.30	\$ 11,088.00		
10	\$ 100.25	\$ 1,002.50		
10	\$ 6.34	\$ 63.40		
\$ 4,182,275.37				

Unit Rates Corrected					SRK Cost	
Quantity	AANDC Unit Cost	AANDC Cost	SRK Unit Cost			
378	\$4.30	\$ 1,625.40	\$	1,627.47	\$1.23	\$ 463.94
0.3	\$0.56	\$ 0.17			\$10.23	\$ 3.07
0.3	\$6.34	\$ 1.90			\$4.70	\$ 1.41
1	\$770.00	\$ 770.00	\$	37,268.37	\$657.86	\$ 657.86
1190	\$22.00	\$ 26,180.00			\$11.13	\$ 13,239.55
1	\$640.00	\$ 640.00			\$639.99	\$ 639.99
90.8	\$100.25	\$ 9,102.70			\$10.23	\$ 928.69
90.8	\$6.34	\$ 575.67			\$4.70	\$ 426.73
24	\$4.30	\$ 103.20	\$	151.80	\$1.23	\$ 29.46
3.6	\$13.50	\$ 48.60			\$24.53	\$ 88.31
2	\$550.00	\$ 1,100.00	\$	5,190.56	\$639.99	\$ 1,279.98
2	\$2,000.00	\$ 4,000.00			\$2,500.00	\$ 5,000.00
28.3	\$3.20	\$ 90.56			\$16.35	\$ 462.79
50400	\$3.20	\$ 161,280.00	\$	161,474.70	\$0.12	\$ 6,185.84
10	\$13.13	\$ 131.30			\$10.23	\$ 102.28
10	\$6.34	\$ 63.40			\$4.70	\$ 47.00
1	\$2,000.00	\$ 2,000.00	\$	21,005.90	\$2,000.00	\$ 2,000.00
120	\$4.30	\$ 516.00			\$2.75	\$ 329.84
35200	\$0.18	\$ 6,336.00			\$0.17	\$ 6,096.80
1760	\$6.30	\$ 11,088.00			\$5.76	\$ 10,136.38
10	\$100.25	\$ 1,002.50			\$10.23	\$ 102.28
10	\$6.34	\$ 63.40			\$4.70	\$ 47.00
\$ 4,179,575.37					\$ 2,996,445.57	

ACTIVITY/MATERIAL	Units	Quantity	Cost Code	Unit Cost	Cost
QUARRY #2					
No decomm required			#N/A	\$ -	\$ -
OVERBURDEN DUMP					
Reslope to 3H:1V	m3	8781.3	SC1L	\$ 6.80	\$ 59,713.00
Grade top for positive drainage	m2	18441	C505L	\$ 1.58	\$ 29,137.00
Install erosion protection measures (coconut matting)	m2	2634	GSTH	\$ 6.00	\$ 15,804.00
Remove culvert	ls	1	RCULL	\$ 2,625.00	\$ 2,625.00
Other			#N/A	\$ -	\$ -
TREATED SEWAGE DISCHARGE AREAS					
Fill in low-lying areas (assumed sourced within 0.5km)	m3	69.1	SB4H	\$ 11.00	\$ 760.00
Erosion protection: Supply and place cocoa matting	m2	53.2	GSTH	\$ 6.00	\$ 319.00
Other			#N/A	\$ -	\$ -
Quarry #3 -					
No decomm required			#N/A	\$ -	\$ -
Q#3 Access Road					
Crown road for positive drainage	km	0.2	CRWNL	\$ 1,190.00	\$ 238.00
Quarry #3 Landfill					
LHDP ROQ to construct 1m landfill cap	m3	19520	RB4L	\$ 12.50	\$ 244,000.00
COMMUNICATIONS TOWER					
Remove communications equipment	each	12	C107L	\$ 350.00	\$ 4,200.00
Dismantle the communications towers and prepare for shipping off-site	each	2	C311L	\$ 15,500.00	\$ 31,000.00
Demolish equipment housing shack	m3	9	C305L	\$ 19.00	\$ 171.00
Remove electrical and fiber optics cables	each	12	C105L	\$ 640.00	\$ 7,680.00
Remove all equipment, material, and waste from Doris Mountain (helicopter)	m3	11	DEB1L	\$ 2,500.00	\$ 27,500.00
Load waste into trucks for transport to landfill	m3	9	C401L	\$ 13.13	\$ 118.00
Transport Waste to Landfill	m3	9	C415L	\$ 6.34	\$ 57.00
Transport Communications tower equipment to Roberts Bay	m3	33.2	C404L	\$ 6.34	\$ 210.00
LAND FARM					
Load contained contaminated soils into megabags for shipping off-site	m3	100	C412L	\$ 100.25	\$ 10,025.00
Haul megabags to Roberts Bay laydown	m3	100	C404L	\$ 6.34	\$ 634.00
Treat contained water and discharge	ls	1	TRTL	\$ 6,500.00	\$ 6,500.00
Remove and stockpile liner protection cover	m3	2591	SB1L	\$ 4.30	\$ 11,141.00
Clean liner	m2	4384	C210L	\$ 0.39	\$ 1,710.00
Remove and cut liner into manageable pieces	m2	13152	C302L	\$ 0.56	\$ 7,365.00
Load waste for transport to landfill	m3	118.4	C401L	\$ 13.13	\$ 1,555.00
Haul Material to Landfill	m3	118.4	C414L	\$ 6.34	\$ 751.00
Level containment berms	m2	3134.8	C505L	\$ 1.58	\$ 4,953.00
Regrade area for positive drainage	m2	4384	C518L	\$ 0.12	\$ 526.00
Other			#N/A	\$ -	\$ -

Quantity	Unit Cost	Errors Corrected Cost	
0	\$ -	\$ -	\$ -
8781.3	\$ 6.80	\$ 59,712.84	\$ 107,278.62
18441	\$ 1.58	\$ 29,136.78	
2634	\$ 6.00	\$ 15,804.00	
1	\$ 2,625.00	\$ 2,625.00	
0	\$ -	\$ -	
69.1	\$ 11.00	\$ 760.10	\$ 1,079.30
53.2	\$ 6.00	\$ 319.20	
0	\$ -	\$ -	
0	\$ -	\$ -	\$ -
0.2	\$ 1,190.00	\$ 238.00	\$ 238.00
19520	\$ 12.50	\$ 244,000.00	\$ 244,000.00
12	\$ 350.00	\$ 4,200.00	\$ 65,936.72
2	\$ 15,500.00	\$ 31,000.00	
9	\$ 19.00	\$ 171.00	
12	\$ 640.00	\$ 7,680.00	
9	\$ 2,500.00	\$ 22,500.00	
9	\$ 13.13	\$ 118.17	
9	\$ 6.34	\$ 57.06	
33.2	\$ 6.34	\$ 210.49	
100	\$ 100.25	\$ 10,025.00	\$ 45,159.49
100	\$ 6.34	\$ 634.00	
1	\$ 6,500.00	\$ 6,500.00	
2591	\$ 4.30	\$ 11,141.30	
4384	\$ 0.39	\$ 1,709.76	
13152	\$ 0.56	\$ 7,365.12	
118.4	\$ 13.13	\$ 1,554.59	
118.4	\$ 6.34	\$ 750.66	
3134.8	\$ 1.58	\$ 4,952.98	
4384	\$ 0.12	\$ 526.08	

Quantity	Unit Cost	Assumptions Corrected Cost	
0	\$ -	\$ -	\$ -
8781.3	\$ 6.80	\$ 59,712.84	\$ 107,278.62
18441	\$ 1.58	\$ 29,136.78	
2634	\$ 6.00	\$ 15,804.00	
1	\$ 2,625.00	\$ 2,625.00	
69.1	\$ 11.00	\$ 760.10	\$ 1,079.30
53.2	\$ 6.00	\$ 319.20	
0	\$ -	\$ -	
0	\$ -	\$ -	\$ -
0.2	\$ 1,190.00	\$ 238.00	\$ 238.00
19520	\$ 12.50	\$ 244,000.00	\$ 244,000.00
12	\$ 350.00	\$ 4,200.00	\$ 65,936.72
2	\$ 15,500.00	\$ 31,000.00	
9	\$ 19.00	\$ 171.00	
12	\$ 640.00	\$ 7,680.00	
9	\$ 2,500.00	\$ 22,500.00	
9	\$ 13.13	\$ 118.17	
9	\$ 6.34	\$ 57.06	
33.2	\$ 6.34	\$ 210.49	
100	\$ 100.25	\$ 10,025.00	\$ 45,159.49
100	\$ 6.34	\$ 634.00	
1	\$ 6,500.00	\$ 6,500.00	
2591	\$ 4.30	\$ 11,141.30	
4384	\$ 0.39	\$ 1,709.76	
13152	\$ 0.56	\$ 7,365.12	
118.4	\$ 13.13	\$ 1,554.59	
118.4	\$ 6.34	\$ 750.66	
3134.8	\$ 1.58	\$ 4,952.98	
4384	\$ 0.12	\$ 526.08	

Quantity	AANDC Unit Cost	AANDC Cost	Unit Rates Corrected SRK Unit Cost	SRK Cost
0	\$ -	\$ -	\$ -	\$ -
8781.3	\$ 6.80	\$ 59,712.84	\$ 107,278.62	\$ 3.27 \$ 28,740.61 \$ 65,978.37
18441	\$ 1.58	\$ 29,136.78	\$	\$ 1.23 \$ 22,633.56
2634	\$ 6.00	\$ 15,804.00	\$	\$ 4.79 \$ 12,604.20
1	\$ 2,625.00	\$ 2,625.00	\$	\$ 2,000.00 \$ 2,000.00
69.1	\$ 11.00	\$ 760.10	\$ 1,079.30	\$ 16.35 \$ 1,129.98 \$ 1,384.56
53.2	\$ 6.00	\$ 319.20	\$	\$ 4.79 \$ 254.57
0	\$ -	\$ -		
0	\$ -	\$ -	\$ -	\$ - \$ - \$ -
0.2	\$ 1,190.00	\$ 238.00	\$ 238.00	\$ 866.22 \$ 173.24 \$ 173.24
19520	\$ 12.50	\$ 244,000.00	\$ 244,000.00	\$ 6.28 \$ 122,573.28 \$ 122,573.28
12	\$ 350.00	\$ 4,200.00	\$ 65,936.72	\$ 352.56 \$ 4,230.74 \$ 65,592.17
2	\$ 15,500.00	\$ 31,000.00	\$	\$ 15,417.42 \$ 30,834.85
9	\$ 19.00	\$ 171.00	\$	\$ 12.90 \$ 116.07
12	\$ 640.00	\$ 7,680.00	\$	\$ 639.99 \$ 7,679.90
9	\$ 2,500.00	\$ 22,500.00	\$	\$ 2,501.40 \$ 22,512.63
9	\$ 13.13	\$ 118.17	\$	\$ 10.23 \$ 92.05
9	\$ 6.34	\$ 57.06	\$	\$ 4.70 \$ 42.30
33.2	\$ 6.34	\$ 210.49	\$	\$ 2.52 \$ 83.64
100	\$ 100.25	\$ 10,025.00	\$ 45,159.49	\$ 70.75 \$ 7,074.89 \$ 28,927.30
100	\$ 6.34	\$ 634.00	\$	\$ 2.52 \$ 251.91
1	\$ 6,500.00	\$ 6,500.00	\$	\$ 5,000.00 \$ 5,000.00
2591	\$ 4.30	\$ 11,141.30	\$	\$ 2.75 \$ 7,121.87
4384	\$ 0.39	\$ 1,709.76	\$	\$ 0.39 \$ 1,709.89
13152	\$ 0.56	\$ 7,365.12	\$	\$ 0.16 \$ 2,110.50
118.4	\$ 13.13	\$ 1,554.59	\$	\$ 10.23 \$ 1,210.99
118.4	\$ 6.34	\$ 750.66	\$	\$ 4.70 \$ 556.44
3134.8	\$ 1.58	\$ 4,952.98	\$	\$ 1.23 \$ 3,847.50
4384	\$ 0.12	\$ 526.08	\$	\$ 0.01 \$ 43.31

ACTIVITY/MATERIAL	Units	Quantity	Cost Code	Unit Cost	Cost
BATCH PLANT PAD					
Collect all debris	m2	740.3	C310L	\$ 0.18	\$ 133.00
Load waste for transport to landfill	m3	3	C401L	\$ 13.13	\$ 39.00
Haul waste to Landfill	m3	3	C414L	\$ 6.34	\$ 19.00
Regrade area for positive drainage	m2	740.3	C518L	\$ 0.12	\$ 89.00
Other			#N/A	\$ -	\$ -
BURN PAD					
Collect ashes and place in containers	m3	0.1	C207L	\$ 13.13	\$ 1.00
Dismantle (welding crew)	each	1	C308L	\$ 1,500.00	\$ 1,500.00
Load waste into containers for shipping off-site	m3	0.2	C401L	\$ 13.13	\$ 3.00
Haul containers to Roberts Bay laydown	m3	0.2	C404L	\$ 6.34	\$ 1.00
Regrade area for positive drainage	m2	400	C518L	\$ 0.12	\$ 48.00
Other			#N/A	\$ -	\$ -
ROBERTS BAY DISCHARGE SYSTEM					
Cut pipelines into manageable pieces	lm	5470	PLRH	\$ 72.00	\$ 393,840.00
Decommission electrical (heat tracing)	each	11	C106L	\$ 750.00	\$ 8,250.00
Collect electrical cables and controllers and prep for shipping off-site	m2	5470	C310L	\$ 0.18	\$ 985.00
Load debris for transport to landfill	m3	1160	C401L	\$ 13.13	\$ 15,231.00
Haul debris to landfill	m3	1160	C404L	\$ 6.34	\$ 7,354.00
Remove rock fill to 0.3 m below LLWL	m3	485	SC3L	\$ 8.90	\$ 4,317.00

Quantity	Unit Cost	Errors Corrected Cost	
740.3	\$ 0.18	\$ 133.25	\$ 280.50
3	\$ 13.13	\$ 39.39	
3	\$ 6.34	\$ 19.02	
740.3	\$ 0.12	\$ 88.84	
0.1	\$ 13.13	\$ 1.31	\$ 1,553.21
1	\$ 1,500.00	\$ 1,500.00	
0.2	\$ 13.13	\$ 2.63	
0.2	\$ 6.34	\$ 1.27	
400	\$ 0.12	\$ 48.00	
5470	\$ 72.00	\$ 393,840.00	\$ 429,976.30
11	\$ 750.00	\$ 8,250.00	
5470	\$ 0.18	\$ 984.60	
1160	\$ 13.13	\$ 15,230.80	
1160	\$ 6.34	\$ 7,354.40	
485	\$ 8.90	\$ 4,316.50	
\$ 895,502.14			

Quantity	Unit Cost	Assumptions Corrected Cost	
740.3	\$ 0.18	\$ 133.25	\$ 280.50
3	\$ 13.13	\$ 39.39	
3	\$ 6.34	\$ 19.02	
740.3	\$ 0.12	\$ 88.84	
0.1	\$ 13.13	\$ 1.31	\$ 1,553.21
1	\$ 1,500.00	\$ 1,500.00	
0.2	\$ 13.13	\$ 2.63	
0.2	\$ 6.34	\$ 1.27	
400	\$ 0.12	\$ 48.00	
5470	\$ 22.00	\$ 120,340.00	\$ 156,476.30
11	\$ 750.00	\$ 8,250.00	
5470	\$ 0.18	\$ 984.60	
1160	\$ 13.13	\$ 15,230.80	
1160	\$ 6.34	\$ 7,354.40	
485	\$ 8.90	\$ 4,316.50	
\$ 622,002.14			

this pipeline is no different than the tailings line; same unit rate should apply

Quantity	AANDC Unit Cost	AANDC Cost	Unit Rates Corrected SRK Unit Cost	SRK Cost	
740.3	\$ 0.18	\$ 133.25	\$ 280.50	\$ 0.17	\$ 128.22
3	\$ 13.13	\$ 39.39	\$	\$ 10.23	\$ 30.68
3	\$ 6.34	\$ 19.02	\$	\$ 4.70	\$ 14.10
740.3	\$ 0.12	\$ 88.84	\$	\$ 0.01	\$ 7.31
0.1	\$ 13.13	\$ 1.31	\$ 1,553.21	\$ 747.69	\$ 74.77
1	\$ 1,500.00	\$ 1,500.00	\$	\$ 511.00	\$ 511.00
0.2	\$ 13.13	\$ 2.63	\$	\$ 10.23	\$ 2.05
0.2	\$ 6.34	\$ 1.27	\$	\$ 2.52	\$ 0.50
400	\$ 0.12	\$ 48.00	\$	\$ 0.01	\$ 3.95
5470	\$ 22.00	\$ 120,340.00	\$ 156,476.30	\$ 11.13	\$ 60,857.42
11	\$ 750.00	\$ 8,250.00	\$	\$ 639.99	\$ 7,039.91
5470	\$ 0.18	\$ 984.60	\$	\$ 0.17	\$ 947.43
1160	\$ 13.13	\$ 15,230.80	\$	\$ 10.23	\$ 11,864.38
1160	\$ 6.34	\$ 7,354.40	\$	\$ 5.36	\$ 6,216.95
485	\$ 8.90	\$ 4,316.50	\$	\$ 1.23	\$ 595.26
\$ 622,002.14				\$ 372,922.87	

1 Capital Expenditures and Short Term Water Treatment identified in 'Instructions' worksheet						
ACTIVITY/MATERIAL	Units	Quantity	Cost Code	Unit Cost	Cost	
BREACH DYKE EMBANKMENT						
Remove fill	m3		#N/A	\$	-	\$ -
Contour water intake area	m3		#N/A	\$	-	\$ -
INSPECT AND MAINTAIN W ATER						
Inspect and maintain water management structures	ls	5	WTR3L	\$	20,000.00	\$ 100,000.00
OPERATE / MAINTAIN W ATER MANAGEMENT SYSTEM						
Technician (camp support incl under Mob)	month	60	WTR1L	\$	9,450.00	\$ 567,000.00
Site support, consumables	month	60	WTR2L	\$	5,800.00	\$ 348,000.00
CONSTRUCT PASSIVE TREATMENT SYSTEM (e.g. Constructed Wetland)						
Construct access roads	km		#N/A	\$	-	\$ -
Install HDPE piping system from collection pond	m		#N/A	\$	-	\$ -
Inter-cell flow structures	allow		#N/A	\$	-	\$ -
Install liners	m2		#N/A	\$	-	\$ -
Install growth media	m3		#N/A	\$	-	\$ -
Wetland vegetation	ha		#N/A	\$	-	\$ -
CONSTRUCT WATER TREATMENT PLANT						
Build treatment plant	LS		#N/A	\$	-	\$ -
Build sludge containment facility	LS		#N/A	\$	-	\$ -
Total						\$ 1,015,000.00

Errors Corrected			
Quantity	Unit Cost	Cost	
5	\$ 20,000.00	\$ 100,000.00	\$ 100,000.00
60	\$ 9,450.00	\$ 567,000.00	\$ 915,000.00
60	\$ 5,800.00	\$ 348,000.00	
\$ 1,015,000.00			

Assumptions Corrected			
Quantity	Unit Cost	Cost	
5	\$ 20,000.00	\$ 100,000.00	\$ 100,000.00
29.3333333	\$ 9,450.00	\$ 277,200.00	\$ 407,506.67
22.4666667	\$ 5,800.00	\$ 130,306.67	
\$ 507,506.67			

Unit Rates Corrected							
Quantity	AANDC Unit Cost	AANDC Cost	SRK Unit Cost		SRK Cost		
5	\$ 20,000.00	\$ 100,000.00	\$ 100,000.00	\$ 70,000.00	\$ 350,000.00	\$ 350,000.00	
29.333333	\$ 9,450.00	\$ 277,200.00	\$ 407,506.67	\$ 56,700.00	\$ 1,663,200.00	\$ 3,011,200.00	SRK daily rates extrapolated to Monthly to match AANDC quantities
22.466667	\$ 5,800.00	\$ 130,306.67		\$ 60,000.00	\$ 1,348,000.00		SRK daily rates extrapolated to Monthly to match AANDC quantities
\$ 507,506.67			\$ 3,361,200.00				

	Units	Quantity	Cost Code	Unit Cost	Cost	
INTERIM CARE & MAINTENANCE						
on-site caretaker	manmonths	5	MM1L	\$	17,550.00	\$ 87,750.00
extra personnel	manmonths				\$	-
-electrician	manmonths	5	MM2L	\$	25,650.00	\$ 128,250.00
-mechanic	manmonths	5	MM3L	\$	20,250.00	\$ 101,250.00
flights (yellowknife - cambridge bay)		20	FLT1	\$	-	\$ -
mobile camp rental	allow	1	CPRTL	\$	425,000.00	\$ 425,000.00
annual fuel	litre	22500	FCGH	\$	1.40	\$ 31,500.00
misc. supplies	allow		#N/A	\$	-	\$ -
pick-up truck	month	24	EQP1L	\$	2,000.00	\$ 48,000.00
small dozer	month	12	EQP2L	\$	8,000.00	\$ 96,000.00
small excavator	month	12	EQP3L	\$	10,000.00	\$ 120,000.00
snow machine	month	12	EQP4L	\$	10,000.00	\$ 120,000.00
articulated dump truck	month	12	EQP5L	\$	10,000.00	\$ 120,000.00
communications	month		#N/A	\$	-	\$ -
camp operations (<10 persons)	month	6	CPOPL	\$	60,000.00	\$ 360,000.00
SNP/AEMP water sampling & reporting	each	1	WSH	\$	10,000.00	\$ 10,000.00
geotechnical assessment	each	1.5	GEOIL	\$	25,000.00	\$ 37,500.00

Errors Corrected			
Quantity	Unit Cost	Cost	
5	\$17,550.00	\$ 87,750.00	\$ 1,784,250.00
0	\$0.00	\$ -	
5	\$25,650.00	\$ 128,250.00	
5	\$20,250.00	\$ 101,250.00	
20	\$0.00	\$ -	
1	\$425,000.00	\$ 425,000.00	
22500	\$1.40	\$ 31,500.00	
0	\$0.00	\$ -	
24	\$2,000.00	\$ 48,000.00	
12	\$8,000.00	\$ 96,000.00	
12	\$10,000.00	\$ 120,000.00	
12	\$10,000.00	\$ 120,000.00	
12	\$10,000.00	\$ 120,000.00	
12	\$10,000.00	\$ 120,000.00	
0	\$0.00	\$ -	
6	\$60,000.00	\$ 360,000.00	
1	\$10,000.00	\$ 10,000.00	
1	\$25,000.00	\$ 25,000.00	one inspection per year

Assumptions Corrected			
Quantity	Unit Cost	Cost	
6	\$ 17,550.00	\$ 105,300.00	\$ 1,228,300.00 summer months
3	\$ 25,650.00	\$ 76,950.00	half the time on site.
3	\$ 20,250.00	\$ 60,750.00	half the time on site.
0	\$ -	\$ -	
0	\$ 425,000.00	\$ -	existing camp still functional
22,500	\$ 1.40	\$ 31,500.00	
0	\$ -	\$ -	
24	\$ 2,000.00	\$ 48,000.00	
12	\$ 8,000.00	\$ 96,000.00	
12	\$ 10,000.00	\$ 120,000.00	
12	\$ 10,000.00	\$ 120,000.00	
12	\$ 10,000.00	\$ 120,000.00	
0	\$ -	\$ -	
6	\$ 60,000.00	\$ 360,000.00	
1	\$ 10,000.00	\$ 10,000.00	
1	\$ 25,000.00	\$ 25,000.00	

AANDC		AANDC		Unit Rates Corrected SRK		SRK	
Quantity	Unit Cost	Unit Cost	Cost	Unit Cost	SRK Cost		
6	\$ 17,550.00	\$ 105,300.00	\$ 1,228,300.00	\$ 56,700.00	\$ 340,200.00	\$ 1,524,940.78	
3	\$ 25,650.00	\$ 76,950.00		\$ 34,491.60	\$ 103,474.80		
3	\$ 20,250.00	\$ 60,750.00		\$ 32,706.00	\$ 98,118.00		
0	\$ -	\$ -		\$ -	\$ -		
0	\$ 425,000.00	\$ -		\$ 424,703.00	\$ -		
22500	\$ 1.40	\$ 31,500.00		\$ 1.44	\$ 32,400.00		
0	\$ -	\$ -		\$ -	\$ -		
24	\$ 2,000.00	\$ 48,000.00		\$ 3,688.00	\$ 88,512.00		
12	\$ 8,000.00	\$ 96,000.00		\$ 8,000.00	\$ 96,000.00		
12	\$ 10,000.00	\$ 120,000.00		\$ 10,000.00	\$ 120,000.00		
12	\$ 10,000.00	\$ 120,000.00		\$ 7,103.00	\$ 85,236.00		
12	\$ 10,000.00	\$ 120,000.00		\$ 10,000.00	\$ 120,000.00		
0	\$ -	\$ -		\$ -	\$ -		
6	\$ 60,000.00	\$ 360,000.00		\$ 61,000.00	\$ 366,000.00		
1	\$ 10,000.00	\$ 10,000.00		\$ 10,000.00	\$ 10,000.00		
1	\$ 25,000.00	\$ 25,000.00		\$ 25,000.00	\$ 25,000.00		

AL	Units	Quantity	Cost Code	Unit Cost	Cost	
Water Management						
Inspect and maintain water management structures	ls	1	WTR3L	\$	20,000.00	\$ 20,000.00
Operate / maintain pumping system						
technician (camp support incl under Mob)	month	6	WTR1L	\$	9,450.00	\$ 56,700.00
site support, consumables	month	6	WTR2L	\$	5,800.00	\$ 34,800.00
Interim water treatment			#N/A	\$	-	\$ -
equipment mob / demob (see below)	each	1			\$	-
	Annual Interim C&M Cost				\$	1,796,750.00
Number of years of ICM						
EQUIPMENT MOBILIZATION	years	1.5		Total		\$ 4,192,001.64
Excavators						
	tonne	36.1	MOB1L	\$	443.00	\$ 15,992.00
	tonne	36.1	MOB1L	\$	443.00	\$ 15,992.00
Dump trucks						
	tonne	34.4	MOB1L	\$	443.00	\$ 15,239.00
	tonne	34.4	MOB1L	\$	443.00	\$ 15,239.00
Loaders						
	tonne	30	MOB1L	\$	443.00	\$ 13,290.00
	tonne	30	MOB1L	\$	443.00	\$ 13,290.00

Errors Corrected			
Quantity	Unit Cost	Cost	
1	\$20,000.00	\$ 20,000.00	
6	\$9,450.00	\$ 56,700.00	
6	\$5,800.00	\$ 34,800.00	
1	\$0.00	\$ -	
1.5		\$ 2,676,375.00	
36.1	\$443.00	\$ 15,992.30	\$ 162,843.00
36.1	\$443.00	\$ 15,992.30	
34.4	\$443.00	\$ 15,239.20	
34.4	\$443.00	\$ 15,239.20	
30	\$443.00	\$ 13,290.00	
30	\$443.00	\$ 13,290.00	

Assumptions Corrected			
Quantity	Unit Cost	Cost	
1	\$ 20,000.00	\$ 20,000.00	
0	\$ 9,450.00	\$ -	care taker would operate pumps
6	\$ 5,800.00	\$ 34,800.00	
1	\$ -	\$ -	
1.5		\$ 1,842,450.00	
20	\$ 443.00	\$ 8,860.00	\$ 148,578.40 switched to small excavator (CAT 318) consistent with rental cost assumption
20	\$ 443.00	\$ 8,860.00	switched to small excavator (CAT 318) consistent with rental cost assumption
34.4	\$ 443.00	\$ 15,239.20	
34.4	\$ 443.00	\$ 15,239.20	
30	\$ 443.00	\$ 13,290.00	
30	\$ 443.00	\$ 13,290.00	

AANDC		AANDC		Unit Rates Corrected			
Quantity	Unit Cost	Cost		SRK Unit Cost	SRK Cost		
1	\$ 20,000.00	\$ 20,000.00		\$ 20,000.00	\$ 20,000.00		
0	\$ 9,450.00	\$ -		\$ 57,645.00	\$ -		
6	\$ 5,800.00	\$ 34,800.00		\$ 3,333.33	\$ 19,999.98		
1	\$ -	\$ -		\$ -	\$ -		
1.5				\$1,842,450.00	\$ 2,287,411.17		
20	\$ 443.00	\$ 8,860.00	\$ 148,578.40	\$ 443.00	\$ 8,860.00	\$ 120,978.40	
20	\$ 443.00	\$ 8,860.00		\$ 443.00	\$ 8,860.00		
34.4	\$ 443.00	\$ 15,239.20		\$ 443.00	\$ 15,239.20		
34.4	\$ 443.00	\$ 15,239.20		\$ 443.00	\$ 15,239.20		
30	\$ 443.00	\$ 13,290.00		\$ 443.00	\$ 13,290.00		
30	\$ 443.00	\$ 13,290.00		\$ 443.00	\$ 13,290.00		

AL	Units	Quantity	Cost Code	Unit Cost	Cost	
Light duty vehicles						
	each	2	MOB3L	\$	5,050.00	\$ 10,100.00
	each	2	MOB3L	\$	5,050.00	\$ 10,100.00
Standard 20' containers						
	each	2	MOB2L	\$	13,400.00	\$ 26,800.00
	each	2	MOB2L	\$	13,400.00	\$ 26,800.00
WINTER ROAD						
Construction and operation						
	km	116	WRCH	\$	11,500.00	\$ 1,334,000.00
Limited winter use	km	116	WRUL	\$	0.29	\$ 34.00
Total Equipment Mobilization					\$	1,496,877.00

Errors Corrected			
Quantity	Unit Cost	Cost	
2	\$5,050.00	\$	10,100.00
2	\$5,050.00	\$	10,100.00
2	\$13,400.00	\$	26,800.00
2	\$13,400.00	\$	26,800.00
116	\$11,500.00	\$ 1,334,000.00	\$ 1,334,033.64
116	\$0.29	\$	33.64
			\$4,173,252

Assumptions Corrected			
Quantity	Unit Cost	Cost	
2	\$ 5,050.00	\$	10,100.00
2	\$ 5,050.00	\$	10,100.00
2	\$ 13,400.00	\$	26,800.00
2	\$ 13,400.00	\$	26,800.00
0	\$ 11,500.00	\$ -	\$ -
0	\$ 0.29	\$ -	
			\$ 1,991,028.40

AANDC		AANDC		Unit Rates Corrected			
Quantity	Unit Cost	Unit Cost	Cost	SRK	Unit Cost	SRK Cost	
2	\$ 5,050.00	\$ 10,100.00		\$	5,050.00	\$ 10,100.00	
2	\$ 5,050.00	\$ 10,100.00		\$	5,050.00	\$ 10,100.00	
2	\$ 13,400.00	\$ 26,800.00		\$	6,500.00	\$ 13,000.00	
2	\$ 13,400.00	\$ 26,800.00		\$	6,500.00	\$ 13,000.00	
0	\$ 11,500.00	\$ -		0	\$ 18,236.00	\$ -	\$ -
0	\$ 0.29	\$ -		\$	-	\$ -	
			\$	1,991,028.40		\$	2,408,389.57

ACTIVITY/MATERIAL	Notes	Units	Quantity	Cost Code	Unit Cost	Cost	Errors Corrected			Assumptions Corrected			Unit Rates Corrected														
							Quantity	Unit Cost	Cost	Quantity	Unit Cost	Cost	Quantity	AANDC Unit Cost	AANDC Cost	SRK Unit Cost	SRK Cost										
MOBILIZE HEAVY EQUIPMENT																											
Excavators																											
	Edmonton to Hay River (2 x 36.1 tonnes)	tonne	72.2	MOB1L	\$443.00	\$31,985	\$596,528	72.2	\$443.00	\$ 31,984.60	\$ 596,526.40	36.1	\$ 443.00	\$ 15,992.30	\$ 438,199.80	one excavator mobilized under ICM	36.1	\$ 443.00	\$ 15,992.30	\$ 438,199.80	\$443.00	\$ 15,992.30	\$ 300,199.80				
Dump trucks	Hay River to Roberts Bay (2 x 36.1 tonnes)	tonne	72.2	MOB1L	\$443.00	\$31,985		72.2	\$443.00	\$ 31,984.60		36.1	\$ 443.00	\$ 15,992.30			36.1	\$ 443.00	\$ 15,992.30		\$443.00	\$ 15,992.30					
	Edmonton to Hay River (3 x 34.4 tonnes)	tonne	103.2	MOB1L	\$443.00	\$45,718		103.2	\$443.00	\$ 45,717.60		103.2	\$ 443.00	\$ 45,717.60			103.2	\$ 443.00	\$ 45,717.60		\$443.00	\$ 45,717.60					
Dozers	Hay River to Roberts Bay (3 x 34.4 tonnes)	tonne	103.2	MOB1L	\$443.00	\$45,718		103.2	\$443.00	\$ 45,717.60		103.2	\$ 443.00	\$ 45,717.60			103.2	\$ 443.00	\$ 45,717.60		\$443.00	\$ 45,717.60					
	Edmonton to Hay River (2 x 33.5 tonnes)	tonne	67	MOB1L	\$443.00	\$29,681		67	\$443.00	\$ 29,681.00		0	\$ 443.00	\$ -		on dozer mobilized under ICM	0	\$ 443.00	\$ -		\$443.00	\$ -					
Loaders	Hay River to Roberts Bay (2 x 33.5 tonnes)	tonne	67	MOB1L	\$443.00	\$29,681		67	\$443.00	\$ 29,681.00		0	\$ 443.00	\$ -			0	\$ 443.00	\$ -		\$443.00	\$ -					
	Edmonton to Hay River (2 x 30 tonnes)	tonne	60	MOB1L	\$443.00	\$26,580		60	\$443.00	\$ 26,580.00		30	\$ 443.00	\$ 13,290.00		one loader mobilized under ICM	30	\$ 443.00	\$ 13,290.00		\$443.00	\$ 13,290.00					
Light duty vehicles	Hay River to Roberts Bay (2 x 30 tonnes)	tonne	60	MOB1L	\$443.00	\$26,580		60	\$443.00	\$ 26,580.00		30	\$ 443.00	\$ 13,290.00			30	\$ 443.00	\$ 13,290.00		\$443.00	\$ 13,290.00					
		each	6	MOB3L	\$5,050.00	\$30,300		6	\$5,050.00	\$ 30,300.00		2	\$ 5,050.00	\$ 10,100.00		two pickups already mobilized under ICM; 5 considered sufficient	2	\$ 5,050.00	\$ 10,100.00		\$5,050.00	\$ 10,100.00					
Standard 20' containers		each	6	MOB3L	\$5,050.00	\$30,300		6	\$5,050.00	\$ 30,300.00		2	\$ 5,050.00	\$ 10,100.00			2	\$ 5,050.00	\$ 10,100.00		\$5,050.00	\$ 10,100.00					
	Edmonton to Hay River	each	10	MOB2L	\$13,400.00	\$134,000		10	\$13,400.00	\$ 134,000.00		10	\$ 13,400.00	\$ 134,000.00			10	\$ 13,400.00	\$ 134,000.00		\$6,500.00	\$ 65,000.00	NTCL rate for shipping containers is lower				
	Hay River to Roberts Bay	each	10	MOB2L	\$13,400.00	\$134,000		10	\$13,400.00	\$ 134,000.00		10	\$ 13,400.00	\$ 134,000.00			10	\$ 13,400.00	\$ 134,000.00		\$6,500.00	\$ 65,000.00	NTCL rate for shipping containers is lower				
MOBILIZE MISC. EQUIPMENT																											
Pump shipping		each		#N/A	\$0.00	\$0	\$0	0	\$0.00	\$ -	\$ -	0	\$ -	\$ -	\$0		0	\$ -	\$ -	\$ -	\$0.00	\$ -	\$ -				
Pipe shipping		m		#N/A	\$0.00	\$0		0	\$0.00	\$ -		0	\$ -	\$ -			0	\$ -	\$ -		\$0.00	\$ -					
Minor tools and equipment		allow		#N/A	\$0.00	\$0		0	\$0.00	\$ -		0	\$ -	\$ -			0	\$ -	\$ -		\$0.00	\$ -					
Truck tires		allow		#N/A	\$0.00	\$0		0	\$0.00	\$ -		0	\$ -	\$ -			0	\$ -	\$ -		\$0.00	\$ -					
Other				#N/A	\$0.00	\$0		0	\$0.00	\$ -		0	\$ -	\$ -			0	\$ -	\$ -		\$0.00	\$ -					
MOBILIZE CAMP																											
						\$2,125,000																					
Reclamation activities		year	5	CPRTL	\$425,000.00	\$2,125,000		5	\$425,000.00	\$ 2,125,000.00	\$ 2,125,000.00	2.5	\$ 425,000.00	\$ 1,062,500.00		\$1,062,500 accounted for under WM	2.5	\$ 425,000.00	\$ 1,062,500.00	\$ 1,062,500.00	\$424,703.00	\$ 1,061,757.50	existing camp facilities will be used				
Long term reclamation activities (eg pump flooding)		allow		#N/A	\$0.00	\$0		0	\$0.00	\$ -																	
MOBILIZE WORKERS																											
						\$3,672,000																					
flights from Yellowknife to Cambridge Bay in summer months		month	9	FLT1L	\$340,000.00	\$3,060,000		9	\$340,000.00	\$ 3,060,000.00	\$ 3,672,000.00	0	\$ 340,000.00	\$ -		flights cost included in camp operations cost	0	\$ 340,000.00	\$ -	0	\$17,800.00	\$ -	\$ -				
flights from Yellowknife to Cambridge Bay in winter months		month	9	FLT2L	\$68,000.00	\$612,000		9	\$68,000.00	\$ 612,000.00		0	\$ 68,000.00	\$ -		there are no reclamation activities in the winter	0	\$ 68,000.00	\$ -		\$17,800.00	\$ -					
Long term reclamation activities (eg pump flooding) - transport		each		#N/A	\$0.00	\$0		0	\$0.00	\$ -		0	\$ -	\$ -			0	\$ -	\$ -								
Long term reclamation activities (eg pump flooding) - travel time		each		#N/A	\$0.00	\$0		0	\$0.00	\$ -		0	\$ -	\$ -			0	\$ -	\$ -								
Monitoring airfare		each		#N/A	\$0.00	\$0		0	\$0.00	\$ -		0	\$ -	\$ -			0	\$ -	\$ -								

ACTIVITY/MATERIAL	Notes	Units	Quantity	Cost Code	Unit Cost	Cost	Errors Corrected				Assumptions Corrected				Unit Rates Corrected							
							Quantity	Unit Cost	Cost		Quantity	Unit Cost	Cost		Quantity	AANDC Unit Cost	AANDC Cost	SRK Unit Cost	SRK Cost			
WORKER ACCOMODATIONS																						
						\$3,870,000																
camp operations (winter months , <10.5 full years for water management persons incl food, maintenance, air travel) activities																						
		month	60	CPOPL	\$60,000.00	\$3,600,000	42	\$60,000.00	\$ 2,520,000.00	\$ 2,790,000.00	18 out of 60 months	17	\$ 60,000.00	\$ 1,020,000.00		17	\$ 60,000.00	\$ 1,020,000.00	\$ 1,200,000.00	\$60,000.00	\$ 1,020,000.00	\$ 1,200,000.00
camp operations (winter months , >25 persons, incl food, maintenance, air travel) activities																						
		month	18	CPOPAL	\$15,000.00	\$270,000	18	\$15,000.00	\$ 270,000.00			12	\$ 15,000.00	\$ 180,000.00		12	\$ 15,000.00	\$ 180,000.00	\$15,000.00	\$ 180,000.00		
Long term reclamation activities (eg pump flooding)																						
		manmonths		#N/A	\$0.00	\$0	0	\$0.00	\$ -			0	\$ -	\$ -		0	\$ -	\$ -	\$0.00	\$ -		
MOBILIZE FUEL																						
		litre		#N/A	\$0.00	\$0	0	\$0.00	\$ -	\$ -		0	\$ -	\$ -	\$0	0	\$ -	\$ -	0	\$0.00	\$ -	\$ -
Fuel freight - reclamation activities																						
		litre		#N/A	\$0.00	\$0	0	\$0.00	\$ -			0	\$ -	\$ -		0	\$ -	\$ -	\$0.00	\$ -		
Fuel freight accomodations																						
		litre		#N/A	\$0.00	\$0	0	\$0.00	\$ -			0	\$ -	\$ -		0	\$ -	\$ -	\$0.00	\$ -		
WINTER ROAD																						
						\$1,334,034																
Construction and operation																						
		km	116	WRCH	\$11,500.00	\$1,334,000	116	\$11,500.00	\$ 1,334,000.00	\$ 1,334,033.64		0	\$ 11,500.00	\$ -		0	\$ 11,500.00	\$ -	0	\$18,236.00	\$ -	\$ -
Limited winter use																						
		km	116	WRUL	\$0.29	\$34	116	\$0.29	\$ 33.64			0	\$ 0.29	\$ -		0	\$ 0.29	\$ -		\$0.00	\$ -	
Winter road tariff																						
		km		#N/A	\$0.00	\$0	0	\$0.00	\$ -			0	\$ -	\$ -		0	\$ -	\$ -		\$0.00	\$ -	
DEMOLIBLIZE HEAVY EQUIPMENT																						
						\$685,570				\$ 685,569.40					\$630,724				\$ 630,723.80		\$ 303,100.80	
Excavators																						
	Edmonton to Hay River (3 x 36.1 tonnes)	tonne	108.3	MOB1L	\$443.00	\$47,977	108.3	\$443.00	\$ 47,976.90			72.2	\$ 443.00	\$ 31,984.60		72.2	\$ 443.00	\$ 31,984.60	\$288.00	\$ 20,793.60		return NTCL rates are lower for both equipment and containers
Dump trucks	Hay River to Roberts Bay (3 x 36.1 tonnes)	tonne	108.3	MOB1L	\$443.00	\$47,977	108.3	\$443.00	\$ 47,976.90			72.2	\$ 443.00	\$ 31,984.60		72.2	\$ 443.00	\$ 31,984.60	\$288.00	\$ 20,793.60		return NTCL rates are lower for both equipment and containers
	Edmonton to Hay River (4 x 34.4 tonnes)	tonne	137.6	MOB1L	\$443.00	\$60,957	137.6	\$443.00	\$ 60,956.80			137.6	\$ 443.00	\$ 60,956.80		137.6	\$ 443.00	\$ 60,956.80	\$288.00	\$ 39,628.80		return NTCL rates are lower for both equipment and containers
Dozers	Hay River to Roberts Bay (4 x 34.4 tonnes)	tonne	137.6	MOB1L	\$443.00	\$60,957	137.6	\$443.00	\$ 60,956.80			137.6	\$ 443.00	\$ 60,956.80		137.6	\$ 443.00	\$ 60,956.80	\$288.00	\$ 39,628.80		return NTCL rates are lower for both equipment and containers
	Edmonton to Hay River (2 x 33.5 tonnes)	tonne	67	MOB1L	\$443.00	\$29,681	67	\$443.00	\$ 29,681.00			33.5	\$ 443.00	\$ 14,840.50		33.5	\$ 443.00	\$ 14,840.50	\$288.00	\$ 9,648.00		return NTCL rates are lower for both equipment and containers
	Hay River to Roberts Bay (2 x 33.5 tonnes)	tonne	67	MOB1L	\$443.00	\$29,681	67	\$443.00	\$ 29,681.00			33.5	\$ 443.00	\$ 14,840.50		33.5	\$ 443.00	\$ 14,840.50	\$288.00	\$ 9,648.00		return NTCL rates are lower for both equipment and containers

ACTIVITY/MATERIAL	Notes	Units	Quantity	Code	Unit Cost	Cost
MONITORING & INSPECTIONS						
Annual geotechnical inspection	(for first 5 years)	each	0.5	GEOI2L	\$ 70,000.00	\$ 35,000.00
Cover monitoring	every 2 years	each	0.5	GEOI2L	\$ 70,000.00	\$ 35,000.00
Regulatory costs*		each	1	RPTL	\$ 20,000.00	\$ 20,000.00
Water sampling and testing		each	1	WTR4L	\$ 60,000.00	\$ 60,000.00
Vegetation Monitoring	(every 2 years)	each	0.5	GEOI2L	\$ 70,000.00	\$ 35,000.00
Decommission water management structures			0.1	DITCL	\$ 500,000.00	\$ 50,000.00
SPILLWAY MAINTENANCE						
Repair erosion		m3		#N/A	\$ -	\$ -
Clear spillway		each		#N/A	\$ -	\$ -
CWTS MAINTENANCE						
Maintain flow, restore vegetation		allow		#N/A	\$ -	\$ -
POST-CLOSURE WATER TREATMENT						
Annual water treatment cost, from "Water Treatment"						\$ -
Subtotal, Annual post-closure costs						\$ 235,000.00
Discount rate for calculation of net present value of post-closure cost %			5.00%			
Number of years of post-closure activity			10 years			
Number of years of post-closure activity			10 years			
Present Value of Payment Stream						\$ 1,814,608.00
*Regulatory costs - annual reporting, management plans, progress reports etc.						

		Errors Corrected		included under direct tasks
Quantity	Unit Cost	Cost		
0.5	\$70,000.00	\$ 35,000.00		
0.5	\$70,000.00	\$ 35,000.00		
1	\$20,000.00	\$ 20,000.00		
1	\$60,000.00	\$ 60,000.00		
0.5	\$70,000.00	\$ 35,000.00		
0.1	\$500,000.00	\$ 50,000.00		
			\$ 235,000.00	
	5%			
	10		\$1,814,607.71	

		Assumptions Corrected		no revegetation will be completed included under direct tasks
Quantity	Unit Cost	Cost		
1	\$ 70,000.00	\$ 70,000.00	\$ 270,000.00	
1	\$ 70,000.00	\$ 70,000.00		
1	\$ 20,000.00	\$ 20,000.00		
1	\$ 60,000.00	\$ 60,000.00		
0	\$ 70,000.00	\$ -		
0.1	\$ 500,000.00	\$ 50,000.00		
	5%			
	10		\$ 868,499.66	

	cost per event	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	
Annual geotechnical inspection	\$ 70,000.00		1	1	1	0	0	0	0	0	0	
Cover monitoring	\$ 70,000.00		0	1	0	1	0	1	0	1	0	1
Regulatory costs	\$ 20,000.00		1	1	1	1	1	1	1	1	1	1
Water sampling and testing	\$ 60,000.00		1	1	1	1	1	0	0	0	0	
undiscounted	\$ 150,000.00	\$ 220,000.00	\$ 150,000.00	\$ 150,000.00	\$ 150,000.00	\$ 80,000.00	\$ 90,000.00	\$ 20,000.00	\$ 90,000.00	\$ 20,000.00	\$ 90,000.00	\$ 1,060,000.00
npv		\$142,857.14	\$199,546.49	\$129,575.64	\$123,405.37	\$62,682.09	\$67,159.39	\$14,213.63	\$60,915.54	\$12,892.18	\$55,252.19	\$868,499.66

AANDC TC 11 – Particle Size Analysis





A Division of AMEC Engineering Pty Limited ABN 73 003 066 715
12 Collingwood Street, Osborne Park WA 6017
Telephone: (08) 9244 1199 Facsimile: (08) 9244 1457
E-mail: src@amecaust.com.au

TEST CERTIFICATE


Client: MIRAMAR HOPE BAY LIMITED
Project: DORIS NORTH COMBINED FINAL MILL TAILING

Sheet No.: 2 OF 10
Job No.: S9645
Date Tested: 25.08.03

Sample ID: TAILS

Particle Size Distribution of a Soil AS 1289.3.6.2: Sieving with Hydrometer

Sieving				Hydrometer			
Sieve Size	% Passing	Sieve Size	% Passing	Diameter	% Passing	Diameter	% Passing
75.0mm		1.18 mm		67 micron	49	10 micron	14
37.5 mm		600 micron		49 micron	40	7 micron	14
19.0 mm		425 micron		35 micron	34	5 micron	12
9.50 mm		300 micron	100	26 micron	25	1 micron	10
4.75 mm		150 micron	92	18 micron	21		
2.36mm		75 micron	56	13 micron	18		



Remarks: Sampling Method/s - Submitted by Client.



This laboratory is accredited by the National Association of Testing Authorities, Australia. The test(s) reported herein have been performed in accordance with its terms of accreditation. This document shall not be reproduced except in full.

Approved:

W Rozmianico

Date: 17.09.03

POCOCK INDUSTRIAL, INC. PARTICLE SIZE ANALYSIS DATA SHEET

Company: **Newmont Mining Corporation**
Project: **Hope Bay**

Table No.: **BB**
Test Date: **12/30/08**
By: **GDW/NNN**
Location: **P.I. Lab**

Material: **Doris Flotation Tailing**

Purpose: To determine the particle size distribution of the sample.

Procedure: The sample was wet screened at 400 mesh and the oversize fraction dry screened on a Ro-tap.


Results:

Screen Size		Sample Weights			
	U.S.	Grams	Wt. %	Cumulative Wt. %	
micron	mesh	Retained	Retained	Passing	Retained
212	70	46.85	3.95	96.05	3.95
150	100	129.26	10.90	85.15	14.85
106	140	175.64	14.81	70.33	29.67
75	200	125.04	10.55	59.79	40.21
53	270	107.16	9.04	50.75	49.25
45	325	47.00	3.96	46.79	53.21
38	400	35.50	2.99	43.79	56.21
-38	-400	519.25	43.79		
Totals:		1185.70	100%		

Product Size Passing 90% (P_{90})	174 microns
Product Size Passing 80% (P_{80})	133 microns
Product Size Passing 50% (D_{50})	51 microns

FIGURE BB: PARTICLE SIZE DISTRIBUTION

Newmont Mining Corporation
Hope Bay



Material: Doris Flotation Tailing


Product Size Passing 90% (P90) 174 microns

Product Size Passing 80% (P80) 133 microns

Product Size Passing 50% (D50) 51 microns

See Table BB For Parameters

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.0	0.0	0.0	37.4	51.2	11.4

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
#20	100.0		
#40	100.0		
#60	98.1		
#100	86.5		
#200	62.6		
0.0571 mm.	56.5		
0.0418 mm.	50.5		
0.0303 mm.	46.0		
0.0199 mm.	38.5		
0.0118 mm.	32.5		
0.0061 mm.	22.0		
0.0031 mm.	14.5		
0.0013 mm.	9.1		

* (no specification provided)

<u>Soil Description</u>		
sandy silt		
<u>Atterberg Limits</u>		
PL= NP	LL= 16	PI= NP
<u>Coefficients</u>		
D ₈₅ = 0.1435	D ₆₀ = 0.0674	D ₅₀ = 0.0404
D ₃₀ = 0.0099	D ₁₅ = 0.0033	D ₁₀ = 0.0016
C _u = 42.69	C _c = 0.92	
<u>Classification</u>		
USCS= ML	AASHTO= A-4(0)	
<u>Remarks</u>		

Sample No.: 9 Source of Sample: Doris Central Flotation Tailings

Date: 3/3/09
Elev./Depth:

Knight Piésold
CONSULTING

Client: Newmont Metallurgical Services
Project: Hope Bay
Project No: 108-147.03

Fig.