


Instrumentation installed at Node A.



Instrumentation installed at Node B.



The foundation for the South Thermosyphons.





Rust observed at the weld between the evaporator pipe and the radiators.



The foundation for the North Thermosyphons, looking west.



Erosion on the foundation of the North Thermosyphons.

▽ srk consulting

Job No: 1CT022.009

Filename: 2016GeotechInsp_rev1_ab.pptx

WAC

2016 Geotechnical Inspection

North Dam Instrumentation and Thermosyphons

Doris Mine

Date: Approved: March 2017 PL

Figure: **7**



Aerial view of the TIA, looking north towards the dam.



South end of the TIA.



West side of the TIA, looking southwest from above the dam.



End of the latest road construction on the east side of the TIA, looking south east.



MAC

2016 Geotechnical Inspection

Job No: 1CT022.009


Filename: 2016GeotechInsp_rev1_ab.pptx

Doris Mine

TIA Shoreline Erosion

Approved: ch 2017 PL


Figure: 8





Appendix A Page 1


DATALOGGER DOWNLOAD TRACKING

				CR1000#1		CR1000#2		
Date	Folder Name(s)	Monitored by	Processed?					Comments
4-Sep-15	017_Sept 4, 2015	Instrumentation (Chris C.)	Υ	28/Aug/15	4/Sep/15	28/Aug/15	4/Sep/15	
9-Oct-15	018_Oct 10, 2015	Instrumentation (Chris C.)	Υ	20/May/15	28/Aug/15	20/May/15	28/Aug/15	Not full data set, site to redownload
27-Oct-15	018_Oct 27, 2015	Instrumentation (Chris C.)	Υ	12/Aug/12	27/Oct/15	12/Aug/12	27/Oct/15	Data missing for CR1000_#1 Station Status prior to Oct 10, 2015 (Duplicated data from CR1000#2)
25-Nov-15	020_Nov 25, 2015	Instrumentation (Chris C.)	Υ	27/Oct/15	25/Nov/15	27/Oct/15	25/Nov/15	
30-Dec-15	021_Dec 31, 2015	Instrumentation (Chris C.)	Υ	25/Nov/15	30/Dec/15	25/Nov/15	30/Dec/15	
8-Feb-16	022_Feb 08, 2016	Instrumentation (Chris C.)	Υ	30/Dec/15	8/Feb/16	30/Dec/15	8/Feb/16	
7-Mar-16	023_Mar 07, 2016	Instrumentation (Chris C.)	Υ	8/Feb/16	7/Mar/16	None	None	Data only provided for CR1000_#1, (orange LED issue for CR1000_#2)
11-Apr-16	024_Apr 11, 2016	Instrumentation (Chris C.)	Υ	7/Mar/16	11/Apr/16	12/Aug/12	11/Apr/16	Full download of CR1000_#2
2-Jul-16	025_Jul 02, 2016	Instrumentation (Chris C.)	Υ	11/Apr/16	2/Jul/16	11/Apr/16	2/Jul/16	
14-Aug-16	026_Aug 14, 2016	Instrumentation (Chris C.)	Υ	2/Jul/16	14/Aug/16	2/Jul/16	14/Aug/16	
DATA CUT O	FF FOR 2016 AGI							










Ground Temperature Cable Status:



Notes:

• Bead numbers increase from downstream to upstream (horizontal) and top to bottom (vertical)

The order consulting		TMAC	2016 Geotechnical Inspection			
	srk consulting	RESOURCES	Station 0+40 Ground Temperature Cable			
			Temperature Vs. Time			
-	Job No: 1CT022.009	DORIS MINE	Date:	Approved:	Figure:	
	Filename: AppA_1CT022009_ND_GTC_20170320	DOI TO MITTE	Jan. 2017	PL	. A.1	