

**Executive Office**

340 Park Place, 666 Burrard Street
Vancouver, BC V6C 2X8

Tel 604 682 4667 Fax 604 682 4473
Email general@nunalogistics.com

August 5, 2011

Delivered via Email
pstrand@shearminerals.com

Pamela Strand, M.Sc., P.Geol.
President
Shear Minerals Ltd.
Suite 220, 6 Adelaide Street East
Toronto, Ontario
M5C 1H6

Dear Sirs:

RE: Jericho Site Reclamation – Crown-Owned Lands Only

Nuna Logistics is pleased to provide our updated cost estimate for the reclamation of the Crown-Owned Lands at the Jericho Mine Site. The cost estimate is for the reclamation of the site and does not include remediation, re-vegetation or on-going monitoring. The cost estimate is based on a scenario in which the property is left abandoned but intact and Nuna mobilizes equipment and fuel to site, utilize the abandoned camp, shop, tankage and other facilities throughout the demolition period; and demobilize contractor equipment and Jericho equipment and certain facilities. This approach requires three camp "openings" which are included in the estimate. The first opening is to prepare for mobilization during the first winter road season. The second opening is for the reclamation program beginning early spring. The third opening is to prepare for the demobilization over the second winter road.

We have based the estimate on our current schedule of rates in constant current dollars with no allowance for escalation. The estimate includes reclamation of the current existing site only and does not allow for expanded footprint or upset events such as significant spills, breaches, etc.

Our cost estimate includes the labour and equipment required to complete the work and the mobilization and demobilization of the equipment including an allowance for a minor out-haul of hazardous materials and Shear's mobile equipment and a portion of the reclaimed facilities and equipment. We have added line items for establishing the winter road accesses, camp catering and personnel flights. These items were Tahera-provided in some of the previous cost estimates. It should be understood that establishing winter road access and mobilization/demobilization are items which may be shared by the Crown and Inuit-Owned Lands (IOL) scopes, however, they are presented as stand-alone costs in this estimate.

The estimate is based on quantities and requirements provided in the past by Tahera Corporation and modified to reflect the existing site reality. As such, some of the quantities and the facilities sizing have been recalculated.

Originally, it was proposed that forward-thinking environmental design and practices such as stepped waste dumps and water management ponds would be employed throughout the mine life. The stepped waste dumps carry the same net overall slope as the post-reclamation slope. Therefore, dozing the bench crests creates the required slope. The water management ponds provide, as a secondary benefit, erosion control which is important from a reclamation standpoint. In the current existing state, the waste dumps are not sufficiently high to have required stepping and the erosion control structures appear to be sufficient and as per design with the exception of some minor dam slope work which would be done during reclamation.

COST ESTIMATE HISTORY

Nuna Logistics has provided reclamation estimates for Jericho from the early pre-feasibility days.

Prefeasibility Stage – June, 2000	\$6,130,200
▪ Preliminary Scope, Nuna/Tahera Joint Estimate	
Permitting Stage – June, 2003	\$7,195,607
▪ Nuna/Tahera Joint Estimate, Cost Escalation, Refined Scope	
▪ Reviewed Considering INAC's Paper, "Mine Site Reclamation Policy for Nunavut" of 2002	
Allocation Stage – September, 2003	\$7,195,607
▪ Crown Lands \$5,945,174	
▪ Inuit Owned Lands \$1,250,433	
Post-Closure Plan – August, 2004	\$9,279,958
▪ Based on Abandoned Site	
Allocation – December, 2004	\$9,279,958
▪ Crown Lands \$7,483,981	
▪ Inuit Owned Lands \$1,795,977	
Update for KIA Lands – September, 2008	\$1,923,500
▪ Re-Estimate from Base Principles, Assumes Provision of Owner Items from Care and Maintenance Program	
Update for KIA Lands – December, 2010	\$3,151,800
▪ Re-estimate to include escalation, explosives plant demolition, pit rim smoothing, winter road access, camp catering, and flight charters	

RECLAMATION MODEL

The Reclamation Model developed for DIAND by Brodie Consulting Ltd. offers a listing of relevant reclamation items and objectives. In previous Crown estimates, we have referenced these items and objectives to assist in clarifying the approach taken in the estimate. The items, objectives, and our approach are listed as follows:

Open Pit

A. Objective: Control Access

A control berm was constructed around the ultimate pit boundary during operations with minor completions (pit accesses, pit rim smoothing) proposed during reclamation. Fencing and signage are not included in the estimate.

B. Objective: Stabilize Slopes

Not expected to be required. Additionally, it is planned that the pit will be naturally flooded. The pit rim edge will be smoothed during closure.

C. Objective: Cover/Contour Slopes

Not required.

D. Objective: Spillway

The equivalent functionality of the spillway was included in the construction and operation phases. The spillway equivalent will not be required to operate until after the pit naturally fills (approximately 20 years after closure).

E. Objective: Flood Pit

This is expected to occur naturally. Dewatering pipes will be removed during reclamation and this is included in facilities demolition in the estimate. Water quality additives are not included in the estimate. During the monitoring stage, it may be determined if the requirement exists or not.

F. Objective: Develop Wetland

Not applicable.

Underground

A. Objective: Control Access

Seal openings as required.

PKC Area

A. Objective: Control Access

Not required.

B. Objective: Stabilize Embankment

For the most part, the dams were constructed as relatively low angle stable structures. Minor earthworks are included in the estimate to flatten existing structures by adding rock to the toe.

C. Objective: Cover Tailings

PK containment will be covered with 500 mm of coarse processed kimberlite and topped with 300 mm of overburden/waste rock.

D. Objective: Flood PKC

Not applicable.

E. Objective: Treat Supernatant

Not required.

F. Objective: Upgrade Spillway

As required, the spillway or dam will be lowered to allow clean water overflow resulting in a small PKC area settling pond to remain.

G. Objective: Stabilize Decant System

Not applicable.

H. Objective: Remove Tailings Discharge

The removal of the tailings discharge is included in the facilities demolition.

I. Objective: Specialized Items

Not applicable.

Waste Dump

A. Objective: Stabilize Slopes

The waste dumps will be dozed to a slope of about 18 degrees (approximately ½ the natural angle of repose of the material).

B. Objective: Cover Dump

The top bench will be covered with 300 mm of overburden material.

C. Objective: Relocate Dumps

Not applicable.

D. Objective: Collect and Treat

Waste dump runoff will be diverted to the open pit via existing collection structures.

E. Objective: Develop Wetland

Not applicable.

F. Objective: Specialized Items

Not applicable.

Buildings and Equipment

A. Objective: Dispose Mobile Equipment

The required mobile equipment will be contractor-supplied and will be demobilized off-site. Some owner-provided equipment will augment the contractor fleet. It will be demobilized off-site.

B. Objective: Dispose Stationary Equipment

C. Objective: Dispose Ore Concentration Equipment

D. Objective: Dispose Water Treatment Equipment

The estimate allows for a portion of the facilities and equipment to be encapsulated in the waste dump or PK containment and the remainder to be demobilized and transported off-site.

E. Objective: Decontaminate Buildings and Tanks

Because there are no significant chemicals involved in the process, no allowance has been made to decontaminate.

F. Objective: Mothball Buildings

G. Objective: Remove Buildings

The estimate includes building demolition and burial in the waste dump or PK containment.

H. Objective: Break Basement Slabs

In the estimate, concrete slabs are left intact and covered.

I. Objective: Remove Buried Tanks

J. Objective: Landfill for Demolition Waste

Not applicable.

K. Objective: Grade and Contour

L. Objective: Reclaim Roads

Grading and contouring of dams, pads, roads, and airstrip are included in the estimate. The grading and contouring consists of flattening the shoulder areas and scarifying the surfaces if required. Culverts will be removed as required.

M. Objective: Specialized Items

Not applicable.

Chemicals

A. Objective: Laboratory Chemicals

Laboratory chemicals will be hauled off site and disposed of appropriately.

B. Objective: PCB's

Not applicable.

C. Objective: Fuel

D. Objective: Waste Oil

Excess fuel and waste oil will be hauled off-site.

E. Objective: Process or Treatment Chemicals

Not applicable.

F. Objective: Explosives

Explosives will be hauled off-site.

G. Objective: Contaminated Soils

No allowance has been made in the estimate for significant spills. We do not know of a significant spill on site to date. It is expected that subsequent contaminated soils will be remediated when/if the events occur. The material underlying the tank farm and power plant will be tested and, if required, encapsulated within the PK containment as a precautionary measure.

H. Objective: Hazardous Material Testing and Assessment

Not applicable.

Water

A. Objective: Stabilize Embankment

The estimate allows for excavation of the causeway to below water level.

B. Objective: Upgrade Spillway

C. Objective: Stabilize Sediment Containment Ponds

The water management structures were developed during construction and operations and are intended to remain in operation post-closure with excess water diverted to the open pit.

D. Objective: Breach Embankment

Not applicable.

E. Objective: Stabilize Ditches

The CI Diversion ditch is intended to remain in operation post-closure.

F. Objective: Breach Ditches

Not applicable.

G. Objective: Remove Pipelines

H. Objective: Remove Storage Tanks

Pipelines and storage tank removal are included in facilities demolition in the estimate. The materials will be buried in the waste dump or PK containment.

I. Objective: Collect Drainage for Treatment

The water management structures and drainage collection are established during construction and operations and remain in operation post-closure with excess water diverted to the open pit.

J. Objective: Treat Drainage

Ongoing Treatment costs are not included in the estimate. This will not be required until after the open pit fills (15 to 20 years). No treatment is expected to be required.

Mobilization

A. Objective: Mobilize Heavy Equipment

Included in estimate.

B. Objective: Mobilize Camp

We have included the openings of the operations camp and the mobilization of a small well-site during final demolition of the operations camp.

C. Objective: Mobilize Workers

D. Objective: Mobilize Miscellaneous Supplies

E. Objective: Mobilize and House Workers

F. Objective: Winter Road

Included in estimate.

G. Objective: Bonding

H. Objective: Taxes

Performance bonding and GST are not included in the estimate.

I. Objective: Insurance

Typical contractor insurances are included in the estimate.

Monitoring

A. Objective: Monitoring

Monitoring costs, if required, are not included in the scope of this estimate.

Post-Closure Site Maintenance

A. Objective: Post-Closure Site Maintenance

In the closure plan, there is no requirement for site maintenance.

Ongoing Water Treatment Costs

A. Objective: Ongoing Water Treatment Costs

Ongoing water treatment costs, if required, are not included in the scope of this estimate.

EQUIPMENT AND FACILITIES

The following equipment will be mobilized for the work on Crown lands. It should be noted that the earthworks-related equipment may also be used for the work on KIA lands.

Contractor Equipment

Cat D10 Dozer

Cat 980 Loaders

Cat 730 & 740 Trucks

Cat 345 Ultra High Demolition Excavator

Cat MP30 Demolition Shears, Tank Shears, and Concrete Pulverisor

RT Crane – 75-90T Class

Fuel/Lube Truck

Mechanic/Welder Truck

Tractor/Lowboy

Ford F550 Flatdecks

Crewcabs

Light towers



Owner-Provided Equipment

We have assumed that the existing on-site mobile equipment can be used during reclamation. We have carried the operating cost but not the ownership costs in the estimate. These pieces include a motorgrader, bobcats, snow machines, small dozers and loaders, support equipment, and all camp and facilities.

EARTHWORKS RECLAMATION BASIS

With the exception of smaller waste dumps, the current site disturbance is not significantly different than that considered in the original estimates. The equipment fleet proposed in the original estimates consisted of mine-class equipment from the end of the mine life. The current proposed fleet consists of smaller equipment more conducive to the proposed hotshot style mobilization. Therefore, we applied current pricing and current fleet to the original earthworks quantities, perimeters, and layouts.

FACILITIES DEMOLITION BASIS

The original facilities sizing estimates were provided by Tahera. Nuna has done a high level reassessment of the scope and sizing of the facilities for this estimate. In general terms, the footprint sizing is as follows:

	<u>sq m</u>	
Plant	1,850	(23m building height)
Shop	800	(11m building height)
Camp	2,950	
Power Plant	650	
Utilidors/Walkways	740	
Other Facilities	650	

Therefore, we have applied current pricing and current specialized equipment to the reassessed facilities scope and sizing.

COST ESTIMATE

This current estimate for the Jericho reclamation on Crown-Owned Lands is \$11,671,300 on a fully stand-alone basis; assuming free usage of existing infrastructure and equipment.

POTENTIAL OPPORTUNITIES & SYNERGIES

With the current estimate, there are no allowances for synergies and existing supplies and the estimate assumes a substantial haul south. It is reasonable to assume that the Crown work could be planned for the same year as the KIA work and that the existing fuel supply on site could be allocated to the reclamation work. It is also reasonable to assume that far fewer loads need to be transported south, and that the value of the loads south would recoup the freight costs. With these opportunities, it is reasonable to consider the following deductions:

Base Current Estimate	\$ 11,671,300
Crown / KIA Synergy	<1,323,300>
Fuel	< 596,200>
Transport	<1,464,000> (or some portion thereof)
Net Estimate	<u>\$ 8,287,800</u>

If one considers the base Crown-Owned Lands standalone estimate and the IOL standalone estimate, then considers completing both portions in the same year, a savings of \$1,323,300 may be realized. This is as a result of non-duplication of mobilization, site establishment and demobilization.

Further, should existing on-site fuel be dedicated to the Crown land reclamation (approximately 600,000 liters) a further savings of \$596,200 may be realized. An outgoing transport cost of \$1,464,000 is included in the estimate consisting of 130 loads of site related demolition materials and on-site equipment plus 20 loads of contractor equipment. It is reasonable to assume that a portion or all of the 130 loads may be offset by either disposal on-site or value of equipment transported.

Thank you for the opportunity to present our reclamation estimate. If you have questions regarding this estimate, please contact me at (604) 682-4667.

Yours truly,

NUNA LOGISTICS LIMITED
per:



Court Smith, P.Eng.
Executive Vice President
CS/jm

cc: Michelle Tanguay, Environment Manager, Shear Minerals Ltd. (email: michelle@shearminerals.com)
Julie Lassonde, Chief Executive Officer, Executive Chairman, Shear Minerals Ltd. (email: julie@shearminerals.com)
Allison Rippin Armstrong, Environment & Permitting Consultant, Shear Minerals Ltd. (email: ar_enviro@yahoo.ca)

**Nuna Group of Companies
Shear Diamonds Ltd.**

Schedule 1: Cost Summary - 2011 Basis

Prepared by Nuna Logistics Ltd.

Draft Cost Estimate

5-Aug-11

Jericho Reclamation - Crown Owned Lands

C.D.S.

Estimated Costs (\$ thousands)

	Jan Month 1	Feb Month 2	Mar Month 3	Apr Month 4	May Month 5	June Month 6	July Month 7	Aug Month 8	Sept Month 9	Oct Month 10	Nov Month 11	Dec-Mar Month 12+	2011 Basis Total
Mobilization													
Freight	\$0.0	\$391.8	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$391.8
	\$0.0	\$391.8	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$391.8
Labour													
Supervision & Administration	\$0.0	\$7.7	\$0.0	\$0.0	\$110.1	\$108.0	\$110.1	\$110.1	\$106.6	\$0.0	\$0.0	\$0.0	\$560.3
Operations	\$0.0	\$23.8	\$0.0	\$0.0	\$191.7	\$185.5	\$191.7	\$191.7	\$185.5	\$0.0	\$0.0	\$0.0	\$993.8
Maintenance and Trades	\$0.0	\$0.0	\$0.0	\$0.0	\$13.4	\$13.0	\$13.4	\$13.4	\$13.0	\$0.0	\$0.0	\$0.0	\$66.3
Surveying	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$30.3	\$0.0	\$0.0	\$0.0	\$30.3
	\$0.0	\$31.5	\$0.0	\$0.0	\$315.3	\$306.6	\$315.3	\$315.3	\$335.4	\$0.0	\$0.0	\$31.5	\$1,650.7
Equipment													
Production Equipment	\$0.0	\$0.0	\$0.0	\$0.0	\$139.4	\$139.4	\$163.3	\$139.4	\$139.4	\$0.0	\$0.0	\$0.0	\$720.7
Support Equipment	\$0.0	\$7.4	\$0.0	\$0.0	\$42.4	\$41.0	\$42.4	\$42.4	\$47.9	\$0.0	\$0.0	\$7.4	\$230.7
Facilities	\$0.0	\$2.8	\$0.0	\$0.0	\$12.2	\$11.8	\$12.2	\$12.2	\$25.2	\$0.0	\$0.0	\$5.9	\$82.3
Surveying	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$8.0	\$0.0	\$0.0	\$0.0	\$8.0
	\$0.0	\$10.1	\$0.0	\$0.0	\$193.9	\$192.2	\$217.9	\$193.9	\$220.5	\$0.0	\$0.0	\$13.2	\$1,041.7
Other													
Fuel/Lubes for Equipment	\$0.0	\$0.9	\$0.0	\$0.0	\$127.3	\$127.2	\$135.5	\$122.3	\$93.4	\$0.0	\$0.0	\$0.9	\$607.5
Access and Camp Commissioning	\$0.0	\$371.3	\$0.0	\$17.9	\$3.0	\$3.0	\$3.0	\$3.0	\$14.9	\$3.0	\$3.0	\$682.8	\$1,107.9
Supplies and Services	\$0.0	\$7.8	\$0.0	\$0.0	\$132.0	\$127.9	\$132.0	\$132.0	\$127.8	\$0.0	\$0.0	\$7.8	\$667.4
Demolition Items	\$0.0	\$0.0	\$0.0	\$0.0	\$749.8	\$749.8	\$749.8	\$703.9	\$456.9	\$0.0	\$0.0	\$0.0	\$3,410.2
	\$0.0	\$380.1	\$3.0	\$17.9	\$1,012.2	\$1,007.9	\$1,020.4	\$961.3	\$692.9	\$3.0	\$3.0	\$691.5	\$5,793.0
Demobilization													
Freight	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$1,733.0	\$1,733.0
	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$1,733.0	\$1,733.0
Contingency	\$0.0	\$81.4	\$0.3	\$1.8	\$152.1	\$150.7	\$155.3	\$147.0	\$124.9	\$0.3	\$0.3	\$246.9	\$1,061.0
Total Estimated Costs	\$0.0	\$894.9	\$3.3	\$19.7	\$1,673.5	\$1,657.3	\$1,708.8	\$1,617.5	\$1,373.6	\$3.3	\$3.3	\$2,716.1	\$11,671.3
Operating Days	-	7	-	-	31	30	31	31	30	-	-	7	167
Shifts per Day	-	1	-	-	1	1	1	1	1	-	-	1	1
Labour Hours/Shift	12.0	12.0	12.0	12.0	12.0	12.0	12.0	12.0	12.0	12.0	12.0	12.0	12.0
Equipment Hours/Shift	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5

Note: Fuel Costs are included in the costs. Transportation Costs are included in the costs. (in Labour Rates) Camp Catering Costs are not included in the costs. (in Camp Catering above)



**Nuna Group of Companies
Shear Diamonds Ltd.**

Schedule 2: Earthworks Equipment Requirements - 2011 Basis

Prepared by Nuna Logistics Ltd.

Draft Cost Estimate

Jericho Reclamation - Crown Owned Lands

5-Aug-11

C.D.S.

Production Equipment

Operating Hours	Jan Month 1	Feb Month 2	Mar Month 3	Apr Month 4	May Month 5	June Month 6	July Month 7	Aug Month 8	Sept Month 9	Oct Month 10	Nov Month 11	Dec-Mar Month 12+	2011 Basis Total
Cat D400/740 Trucks	-	-	-	-	513	513	513	513	513	-	-	-	2,566
Cat 980 Loaders	-	-	-	-	171	171	171	171	171	-	-	-	856
Cat D10 Dozers	-	-	-	-	135	135	230	135	135	-	-	-	770
Production Equipment Costs (\$ thousands)													
Cat D400/740 Trucks	\$ -	\$ -	\$ -	\$ -	\$ 80.7	\$ 80.7	\$ 80.7	\$ 80.7	\$ 80.7	\$ -	\$ -	\$ -	\$ 403.6
Cat 980 Loaders	\$ -	\$ -	\$ -	\$ -	\$ 24.7	\$ 24.7	\$ 24.7	\$ 24.7	\$ 24.7	\$ -	\$ -	\$ -	\$ 123.3
Cat D10 Dozers	\$ -	\$ -	\$ -	\$ -	\$ 34.0	\$ 34.0	\$ 57.9	\$ 34.0	\$ 34.0	\$ -	\$ -	\$ -	\$ 193.8
	\$ -	\$ -	\$ -	\$ -	\$ 139.4	\$ 139.4	\$ 163.3	\$ 139.4	\$ 139.4	\$ -	\$ -	\$ -	\$ 720.7

Note: Equipment Hours reflects requirement before taking availability and usage into account. Equipment on-site reflects the requirement after taking availability and usage into account.

Support Equipment (Hourly)

Support Equipment Operating Hours

Cat 16 Grader (Oper. Only)	-	15	-	-	65	63	65	65	63	-	-	15	351
Cat 345 Excavators	-	-	-	-	16	16	16	16	16	-	-	-	116
Fuel/Lube Truck	-	-	-	-	65	63	65	65	63	-	-	-	321
Mechanic/Welder Truck	-	7	-	-	33	32	33	33	32	-	-	7	175
Support Equipment Required On-Site													
Cat 16 Grader (Oper. Only)	-	1	-	-	1	1	1	1	1	-	-	1	
Cat 345 Excavators	-	-	-	-	1	1	1	1	1	-	-	-	
Fuel/Lube Truck	-	-	-	-	1	1	1	1	1	-	-	-	
Mechanic/Welder Truck	-	1	-	-	1	1	1	1	1	-	-	1	
Support Equipment Costs (\$ thousands)													
Cat 16 Grader (Oper. Only)	\$ -	\$ 1.4	\$ -	\$ -	\$ 6.3	\$ 6.1	\$ 6.3	\$ 6.3	\$ 6.1	\$ -	\$ -	\$ 1.4	\$ 33.9
Cat 345 Excavators	\$ -	\$ -	\$ -	\$ -	\$ 3.1	\$ 3.0	\$ 3.1	\$ 3.1	\$ 2.9	\$ -	\$ -	\$ -	\$ 22.2
Fuel/Lube Truck	\$ -	\$ -	\$ -	\$ -	\$ 6.7	\$ 6.5	\$ 6.7	\$ 6.7	\$ 6.5	\$ -	\$ -	\$ -	\$ 33.0
Mechanic/Welder Truck	\$ -	\$ 0.4	\$ -	\$ -	\$ 1.8	\$ 1.8	\$ 1.8	\$ 1.8	\$ 1.8	\$ -	\$ -	\$ 0.4	\$ 9.9
	\$ -	\$ 1.8	\$ -	\$ -	\$ 17.9	\$ 17.4	\$ 17.9	\$ 17.9	\$ 24.2	\$ -	\$ -	\$ 1.8	\$ 99.1

Note: Equipment Hours reflects requirement before taking availability and usage into account. Equipment on-site reflects the requirement after taking availability and usage into account.



**Nuna Group of Companies
Shear Diamonds Ltd.**

Schedule 3: Support Equipment - 2011 Basis

Prepared by Nuna Logistics Ltd.

Draft Cost Estimate

5-Aug-11

Jericho Reclamation - Crown Owned Lands

C.D.S.

Support Equipment (Monthly)

Support Equipment Operating Hours

	Jan Month 1	Feb Month 2	Mar Month 3	Apr Month 4	May Month 5	June Month 6	July Month 7	Aug Month 8	Sept Month 9	Oct Month 10	Nov Month 11	Dec-Mar Month 12+	2011 Basis Total
Tractor/Lowboy (85 tonne)	4	18	-	-	16	16	16	16	16	-	-	4	88
F550 Flatdeck	-	59	-	-	81	79	81	81	79	-	-	18	438
Crewcab	-	15	-	-	260	252	260	260	252	-	-	59	1,403
Light Tower	-	-	-	-	65	63	65	65	63	-	-	15	351
Tractor/Lowboy (85 tonne)	1	1	-	-	1	1	1	1	1	-	-	1	1
F550 Flatdeck	1	1	-	-	1	1	1	1	1	-	-	1	1
Crewcab	2	2	-	-	2	2	2	2	2	-	-	2	2
Light Tower	2	2	-	-	2	2	2	2	2	-	-	2	2
Tractor/Lowboy (85 tonne)	\$ 2.3	\$ 0.9	\$ -	\$ -	\$ 10.1	\$ 9.8	\$ 10.1	\$ 10.1	\$ 9.8	\$ -	\$ -	\$ 2.3	\$ 54.7
F550 Flatdeck	\$ -	\$ 0.9	\$ -	\$ -	\$ 4.0	\$ 3.9	\$ 4.0	\$ 4.0	\$ 3.9	\$ -	\$ -	\$ 0.9	\$ 21.7
Crewcab	\$ -	\$ 1.6	\$ -	\$ -	\$ 6.9	\$ 6.7	\$ 6.9	\$ 6.9	\$ 6.7	\$ -	\$ -	\$ 1.6	\$ 37.3
Light Tower	\$ -	\$ 0.8	\$ -	\$ -	\$ 3.3	\$ 3.2	\$ 3.3	\$ 3.3	\$ 3.2	\$ -	\$ -	\$ 0.8	\$ 18.0
	\$ -	\$ 5.5	\$ -	\$ -	\$ 24.4	\$ 23.7	\$ 24.4	\$ 24.4	\$ 23.7	\$ -	\$ -	\$ 5.5	\$ 131.7

Note: Equipment Hours reflects requirement before taking availability and usage into account. Equipment on-site reflects the requirement after taking availability and usage into account.

Support Facilities

Support Facilities Required On-Site

Wellsite	1	1	1	1	1	1	1	1	1	1	1	1	1
Communications - Radios	3	3	3	3	3	3	3	3	3	3	3	3	3
Communications - Sat Phones	1	1	1	1	1	1	1	1	1	1	1	1	1
Wellsite	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 13.4	\$ -	\$ -	\$ 3.1	\$ 16.5
Communications - Radios	\$ -	\$ 0.2	\$ -	\$ -	\$ 0.7	\$ 0.7	\$ 0.7	\$ 0.7	\$ 0.7	\$ -	\$ -	\$ 0.2	\$ 3.7
Communications - Sat Phones	\$ -	\$ 2.6	\$ -	\$ -	\$ 11.5	\$ 11.2	\$ 11.5	\$ 11.5	\$ 11.2	\$ -	\$ -	\$ 2.6	\$ 62.1
	\$ -	\$ 2.8	\$ -	\$ -	\$ 12.2	\$ 11.8	\$ 12.2	\$ 12.2	\$ 25.2	\$ -	\$ -	\$ 5.9	\$ 82.3



**Nuna Group of Companies
Shear Diamonds Ltd.**

Schedule 4: Labour Requirements - 2011 Basis

Prepared by Nuna Logistics Ltd.

Draft Cost Estimate

Jericho Reclamation - Crown Owned Lands

5-Aug-11

C.D.S.

Labour Requirement (per 24 hour day)
Supervision & Administration

Project Manager
Foreman
Safety Superintendent
Administrator

Operations

Excavator Operator - Finish
Loader Operator (988+)
Dozer Operator (D8+)
Grader Operator
Operator (multi-purpose)
Rock Trucks (<789)
Labour (entry level)

Maintenance and Trades

Mechanic Level 1 Journeyman
Welder Level 1 Journeyman
Serviceman (fuel & lube)

Facilities Demolition

Operators and Drivers
Labourers/Riggers
Tradesmen

Surveying

Survey Crew Chief

Total On-Site (per 24 hour day)

Camp Man-Days
Round Trip Airfares

	Jan Month 1	Feb Month 2	Mar Month 3	Apr Month 4	May Month 5	June Month 6	July Month 7	Aug Month 8	Sept Month 9	Oct Month 10	Nov Month 11	Dec-Mar Month 12+	2011 Basis Total
-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	1.0	-	-	1.0	1.0	1.0	1.0	1.0	-	-	-	-
-	-	-	-	-	0.5	0.5	0.5	0.5	0.5	-	-	1.0	-
-	-	-	-	-	0.5	0.5	0.5	0.5	0.5	-	-	-	-
-	-	-	-	-	1.0	1.0	1.0	1.0	1.0	-	-	-	-
-	-	1.0	-	-	1.0	1.0	1.0	1.0	1.0	-	-	1.0	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	2.0	2.0	2.0	2.0	2.0	-	-	-	-
-	-	4.0	-	-	2.0	2.0	2.0	2.0	2.0	-	-	4.0	-
-	-	-	-	-	1.0	1.0	1.0	1.0	1.0	-	-	1.0	-
-	-	1.0	-	-	1.0	1.0	1.0	1.0	1.0	-	-	1.0	-
-	-	-	-	-	0.5	0.5	0.5	0.5	0.5	-	-	-	-
-	-	-	-	-	5.5	5.5	5.5	5.5	5.0	-	-	-	-
-	-	-	-	-	8.0	8.0	8.0	8.0	8.0	-	-	-	-
-	-	-	-	-	3.5	3.5	3.5	3.5	3.0	-	-	-	-
-	-	-	-	-	-	-	-	-	1.0	-	-	-	-
-	-	8	-	-	31	31	31	31	31	-	-	8	-
-	-	56	-	-	946	916	946	946	915	-	-	56	4,780
-	-	4	-	-	68	65	68	68	65	-	-	4	341



**Nuna Group of Companies
Shear Diamonds Ltd.**

Schedule 5: Manhours Estimate - 2011 Basis

Prepared by Nuna Logistics Ltd.

Draft Cost Estimate

Jericho Reclamation - Crown Owned Lands

5-Aug-11

Manhours - (Includes Incidental O/T)
Supervision & Administration

Project Manager
Foreman
Safety Superintendent
Administrator

Operations

Excavator Operator - Finish
Loader Operator (988+)
Dozer Operator (D8+)
Grader Operator
Operator (multi-purpose)
Rock Trucks (<789)
Labour (entry level)

Maintenance and Trades

Mechanic Level 1 Journeyman
Welder Level 1 Journeyman
Serviceman (fuel & lube)

Facilities Demolition

Operators and Drivers
Labourers/Riggers
Tradesmen

Surveying

Survey Crew Chief

Total Manhours

	Jan Month 1	Feb Month 2	Mar Month 3	Apr Month 4	May Month 5	June Month 6	July Month 7	Aug Month 8	Sept Month 9	Oct Month 10	Nov Month 11	Dec-Mar Month 12+	Total
Project Manager	-	-	-	-	372	372	372	372	360	-	-	-	1,848
Foreman	-	84	-	-	372	360	372	372	360	-	-	84	2,004
Safety Superintendent	-	-	-	-	186	180	186	186	180	-	-	-	918
Administrator	-	-	-	-	186	180	186	186	180	-	-	-	918
Excavator Operator - Finish	-	-	-	-	372	360	372	372	360	-	-	-	1,836
Loader Operator (988+)	-	-	-	-	372	360	372	372	360	-	-	-	1,836
Dozer Operator (D8+)	-	-	-	-	372	360	372	372	360	-	-	-	1,836
Grader Operator	-	84	-	-	372	360	372	372	360	-	-	84	2,004
Operator (multi-purpose)	-	-	-	-	-	-	-	-	-	-	-	-	-
Rock Trucks (<789)	-	-	-	-	744	720	744	744	720	-	-	-	3,672
Labour (entry level)	-	336	-	-	744	720	744	744	720	-	-	336	4,344
Mechanic Level 1 Journeyman	-	84	-	-	372	360	372	372	360	-	-	84	2,004
Welder Level 1 Journeyman	-	84	-	-	372	360	372	372	360	-	-	84	2,004
Serviceman (fuel & lube)	-	-	-	-	186	180	186	186	180	-	-	-	918
Operators and Drivers	-	-	-	-	2,046	1,980	2,046	2,046	1,800	-	-	-	9,918
Labourers/Riggers	-	-	-	-	2,976	2,880	2,976	2,976	2,880	-	-	-	14,688
Tradesmen	-	-	-	-	1,302	1,260	1,302	1,302	1,080	-	-	-	6,246
Survey Crew Chief	-	-	-	-	-	-	-	-	360	-	-	-	360
Total Manhours	-	672	-	-	11,346	10,992	11,346	11,346	10,980	-	-	672	57,354



**Nuna Group of Companies
Shear Diamonds Ltd.**

Schedule 6: Labour Cost Estimate - 2011 Basis

Prepared by Nuna Logistics Ltd.

Draft Cost Estimate

5-Aug-11

Jericho Reclamation - Crown Owned Lands

	Jan Month 1	Feb Month 2	Mar Month 3	Apr Month 4	May Month 5	June Month 6	July Month 7	Aug Month 8	Sept Month 9	Oct Month 10	Nov Month 11	Dec-Mar Month 12+	2011 Basis Total
Labour Cost (\$ thousands)													
Supervision & Administration													
Project Manager	\$ -	\$ -	\$ -	\$ -	\$ 46.1	\$ 46.1	\$ 46.1	\$ 46.1	\$ 44.6	\$ -	\$ -	\$ -	\$ 228.8
Foreman	\$ -	\$ 7.7	\$ -	\$ -	\$ 34.0	\$ 32.9	\$ 34.0	\$ 34.0	\$ 32.9	\$ -	\$ -	\$ 7.7	\$ 183.2
Safety Superintendent	\$ -	\$ -	\$ -	\$ -	\$ 17.2	\$ 16.6	\$ 17.2	\$ 17.2	\$ 16.6	\$ -	\$ -	\$ -	\$ 84.9
Administrator	\$ -	\$ -	\$ -	\$ -	\$ 12.8	\$ 12.4	\$ 12.8	\$ 12.8	\$ 12.4	\$ -	\$ -	\$ -	\$ 63.4
Operations													
Excavator Operator - Finish	\$ -	\$ -	\$ -	\$ -	\$ 26.7	\$ 25.8	\$ 26.7	\$ 26.7	\$ 25.8	\$ -	\$ -	\$ -	\$ 131.6
Loader Operator (988+)	\$ -	\$ -	\$ -	\$ -	\$ 27.1	\$ 26.2	\$ 27.1	\$ 27.1	\$ 26.2	\$ -	\$ -	\$ -	\$ 133.6
Dozer Operator (D8+)	\$ -	\$ -	\$ -	\$ -	\$ 25.6	\$ 24.8	\$ 25.6	\$ 25.6	\$ 24.8	\$ -	\$ -	\$ -	\$ 126.3
Grader Operator	\$ -	\$ 5.8	\$ -	\$ -	\$ 25.6	\$ 24.8	\$ 25.6	\$ 25.6	\$ 24.8	\$ -	\$ -	\$ 5.8	\$ 137.9
Operator (multi-purpose)	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Rock Trucks (<789)	\$ -	\$ -	\$ -	\$ -	\$ 46.9	\$ 45.3	\$ 46.9	\$ 46.9	\$ 45.3	\$ -	\$ -	\$ -	\$ 231.3
Labour (entry level)	\$ -	\$ 18.0	\$ -	\$ -	\$ 39.9	\$ 38.6	\$ 39.9	\$ 39.9	\$ 38.6	\$ -	\$ -	\$ 18.0	\$ 233.1
Maintenance and Trades													
Mechanic Level 1 Journeyman	N/C	N/C	N/C	N/C	N/C	N/C	N/C	N/C	N/C	N/C	N/C	N/C	\$ -
Welder Level 1 Journeyman	N/C	N/C	N/C	N/C	N/C	N/C	N/C	N/C	N/C	N/C	N/C	N/C	\$ -
Serviceman (fuel & lube)	\$ -	\$ -	\$ -	\$ -	\$ 13.4	\$ 13.0	\$ 13.4	\$ 13.4	\$ 13.0	\$ -	\$ -	\$ -	\$ 66.3
Facilities Demolition													
Operators and Drivers	Included in Facilities Demolition Estimates												
Labourers/Riggers	Included in Facilities Demolition Estimates												
Tradesmen	Included in Facilities Demolition Estimates												
Surveying													
Survey Crew Chief	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 30.3	\$ -	\$ -	\$ -	\$ 30.3
Total Labour Cost Estimate	\$ -	\$ 31.5	\$ -	\$ -	\$ 315.3	\$ 306.6	\$ 315.3	\$ 315.3	\$ 335.4	\$ -	\$ -	\$ 31.5	\$ 1,650.7

Note: Supervisory & Administration Personnel denoted N/C are non-chargeable (included as overheads in hourly rates). Mechanics & Welders denoted N/C are non-chargeable (included in equipment rates).



**Nuna Group of Companies
Shear Diamonds Ltd.**

Schedule 7: Mobilization & Demobilization - 2011 Basis

Prepared by Nuna Logistics Ltd.

Draft Cost Estimate

Jericho Reclamation - Crown Owned Lands

5-Aug-11

Mobilization

C.D.S.

	Jan Month 1	Feb Month 2	Mar Month 3	Apr Month 4	May Month 5	June Month 6	July Month 7	Aug Month 8	Sept Month 9	Oct Month 10	Nov Month 11	Dec-Mar Month 12+	2011 Basis Total
Land Freight													
Loads to Site from Yellowknife	-	20	-	-	-	-	-	-	-	-	-	-	
Loads to Site from Edmonton	-	12	-	-	-	-	-	-	-	-	-	-	
Mobilization & Freight Costs (\$ thousands)													
Preparation Off-Site	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0
Freight to Site from Yellowknife	\$0.0	\$197.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$197.0
Freight to Site from Edmonton	\$0.0	\$194.9	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$194.9
Mobile Equipment Assembly	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0
Support Equipment Setup	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0
Facilities Setup	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0
	\$0.0	\$391.8	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$391.8

Demobilization

Land Freight													
Loads from Site to Yellowknife	-	-	-	-	-	-	-	-	-	-	-	110	
Loads from Site to Edmonton	-	-	-	-	-	-	-	-	-	-	-	40	
Demobilization & Freight Costs (\$ thousands)													
Preparation On-Site	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0
Freight from Site to Yellowknife	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$1,083.4	\$1,083.4
Freight from Site to Edmonton	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$649.5	\$649.5
Mobile Equipment Disassembly	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0
Support Equipment Disassembly	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0
Facilities Disassembly	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0
	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$1,733.0	\$1,733.0



**Nuna Group of Companies
Shear Diamonds Ltd.**

Schedule 8: Materials, Services, & Demolition - 2011 Basis

Prepared by Nuna Logistics Ltd.

Draft Cost Estimate

5-Aug-11

Jericho Reclamation - Crown Owned Lands

	Jan Month 1	Feb Month 2	Mar Month 3	Apr Month 4	May Month 5	June Month 6	July Month 7	Aug Month 8	Sept Month 9	Oct Month 10	Nov Month 11	Dec-Mar Month 12+	2011 Basis Total
Access and Camp Commissioning (\$ thousands)													
Winter Road Construction	\$0.0	\$257.1	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$257.1	\$514.2
Open Camp	\$0.0	\$14.9	\$0.0	\$14.9	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$14.9	\$44.7
Close Camp	\$0.0	\$14.9	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$14.9	\$0.0	\$0.0	\$14.9	\$44.7
TCWR Fee	\$0.0	\$84.4	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$395.9	\$480.3
Wellsite & Genset Carrying Costs	\$0.0	\$0.0	\$3.0	\$3.0	\$3.0	\$3.0	\$3.0	\$3.0	\$0.0	\$3.0	\$3.0	\$0.0	\$24.0
	\$0.0	\$371.3	\$3.0	\$17.9	\$3.0	\$3.0	\$3.0	\$3.0	\$14.9	\$3.0	\$3.0	\$682.8	\$1,107.9
Supplies and Services (\$ thousands)													
Camp Catering	\$0.0	\$3.9	\$0.0	\$0.0	\$66.2	\$64.1	\$66.2	\$66.2	\$64.1	\$0.0	\$0.0	\$3.9	\$334.6
Charters (Kugluktuk & Yellowknife)	\$0.0	\$3.9	\$0.0	\$0.0	\$65.8	\$63.8	\$65.8	\$65.8	\$63.7	\$0.0	\$0.0	\$3.9	\$332.9
	\$0.0	\$7.8	\$0.0	\$0.0	\$132.0	\$127.9	\$132.0	\$132.0	\$127.8	\$0.0	\$0.0	\$7.8	\$667.4
Demolition Items (\$ thousands)													
Plant Demolition	\$0.0	\$0.0	\$0.0	\$0.0	\$749.8	\$749.8	\$749.8	\$249.9	\$0.0	\$0.0	\$0.0	\$0.0	\$2,499.4
Shop Demolition	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$454.0	\$0.0	\$0.0	\$0.0	\$0.0	\$454.0
Camp Demolition	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$276.2	\$0.0	\$0.0	\$0.0	\$276.2
Power Plant Removal/Demolition	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$51.3	\$0.0	\$0.0	\$0.0	\$51.3
Utilidors/Walkways Demolition	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$69.0	\$0.0	\$0.0	\$0.0	\$69.0
Other Buildings Demolition	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$0.0	\$60.4	\$0.0	\$0.0	\$0.0	\$60.4
	\$0.0	\$0.0	\$0.0	\$0.0	\$749.8	\$749.8	\$749.8	\$703.9	\$456.9	\$0.0	\$0.0	\$0.0	\$3,410.2



**Nuna Group of Companies
Shear Diamonds Ltd.**

Jericho Reclamation - Crown Owned Lands

Attachment A: Fuel Requirements - 2011 Basis

Prepared by Nuna Logistics Ltd.

Draft Cost Estimate

5-Aug-11

C.D.S.

Fuel Consumption (Litres)	Jan Month 1	Feb Month 2	Mar Month 3	Apr Month 4	May Month 5	June Month 6	July Month 7	Aug Month 8	Sept Month 9	Oct Month 10	Nov Month 11	Dec-Mar Month 12+	2011 Basis Total
Earthworks Equipment													
Cat D400/740 Trucks	-	-	-	-	20,528	20,528	20,528	20,528	20,528	-	-	-	102,640
Cat 980 Loaders	-	-	-	-	5,650	5,650	5,650	5,650	5,650	-	-	-	28,248
Cat D10 Dozers	-	-	-	-	11,340	11,340	19,320	11,340	11,340	-	-	-	64,680
Support Equipment (Hourly)													
Cat 16 Grader (Oper. Only)	-	515	-	-	2,279	2,205	2,279	2,279	2,205	-	-	515	12,275
Cat 345 Excavators	-	-	-	-	651	630	651	651	2,070	-	-	-	4,653
Fuel/Lube Truck	-	-	-	-	977	945	977	977	945	-	-	-	4,820
Support Equipment (Monthly)													
Tractor/Lowboy (85 tonne)	-	74	-	-	326	315	326	326	315	-	-	74	1,754
F550 Flatdeck	-	55	-	-	244	236	244	244	236	-	-	55	1,315
Crewcab	-	118	-	-	521	504	521	521	504	-	-	118	2,806
Genset 400 to 600 kW (Camp)	-	-	-	-	-	-	-	-	-	-	-	-	-
Light Tower	-	88	-	-	391	378	391	391	378	-	-	88	2,104
Fuel for Demolition	-	-	-	-	82,260	82,260	82,260	77,214	46,930	-	-	-	370,924
Total Litres	-	849	-	-	125,165	124,991	133,145	120,119	91,101	-	-	849	596,217

Note: Fuel Costs are included in Nuna Logistics Total Costs.



Nuna Group of Companies
Shear Diamonds Ltd.
Jericho Reclamation - Crown Owned Lands

Item 1 - Plant Demolition - Page 1

Prepared by Nuna Ltd

Item:		Description:		Units:		Takeoff Quantity:		Bid Quantity:	
1		Plant Demolition		SF		20000		20000	
Labour		Supervision, Administration, & Technical Services		Hours per Unit		Cost per hour		Cost	
				Hours (hours)		Cost (\$)		Cost (\$)	
		none		Included in main estimate		\$			
		Operations		20,000.00 SF					
		Excavator Operator - Finish		20,000.00 SF		0.070		1,400 \$	
		Loader Operator (<986)		20,000.00 SF		0.070		1,400 \$	
		Rock Trucks (<789)		20,000.00 SF		0.210		4,200 \$	
		Labour (entry level)		20,000.00 SF		0.350		7,000 \$	
		Crane Operator		20,000.00 SF		0.008		160 \$	
		Maintenance and Trades		20,000.00 SF		0.210		4,200 \$	
		Welder Level 1 Journeyman		20,000.00 SF		0.005		100 \$	
		Electrician Journeyman		20,000.00 SF		0.005		100 \$	
		Equipment							
		Mobile Production Equipment							
		Cat 345 Excavators		20,000.00 SF		0.070		1,400 \$	
		MP30 Shears		20,000.00 SF		0.070		1,400 \$	
		Cat 980 Loaders		20,000.00 SF		0.070		1,400 \$	
		Cat D400/740 Trucks		20,000.00 SF		0.210		4,200 \$	
		Stationary Production Equipment							
		none		Included in main estimate					
		Hourly Support Equipment							
		Mechanic/Welder Truck		20,000.00 SF		0.070		1,400 \$	
		Crane (75T class)		20,000.00 SF		0.008		160 \$	
		Monthly Support Equipment							
		none		Included in main estimate					
		Materials							
		none							
		Subcontractors							
		none							
		none							
		Total Item				18,460		\$ 1,203,938	
		Fuel Requirement (litres)		274,200					
		Engine Oil Requirement (litres)		1,113					
		Hydraulic Oil Requirement (litres)		2,554					
		Total				9,950		\$ 1,295,429	
		Materials							
		Subs							



Nuna Group of Companies
Shear Diamonds Ltd.

Jericho Reclamation - Crown Owned Lands

Item: **2** Description: **Shop Demolition**

Item 2 - Shop Demolition - Page 1
 Draft Cost Estimate

Prepared by Nuna Lt

Description:		Shop Demolition		Units:		Takeoff Quantity:		Bid Quantity:	
2				SF		8600		8600	
Item	Description	Quantity	Units	Labour		Equipment		Materials	Subs
				Hours per Unit (hours)	Cost per hour (\$)	Hours (hours)	Cost per hour (\$)		
Supervision, Administration, & Technical Services									
none		8,600.00	SF	\$					
Operations									
Excavator Operator - Finish		8,600.00	SF	0.030	\$ 71.67	\$ 18,492			
Loader Operator (<988)		8,600.00	SF	0.030	\$ 68.80	\$ 17,750			
Rock Trucks (<789)		8,600.00	SF	0.090	\$ 774	\$ 48,751			
Labour (entry level)		8,600.00	SF	0.150	\$ 1,290	\$ 69,217			
Maintenance and Trades									
Welder Level 1 Journeyman		8,600.00	SF	0.090	\$ 774	\$ 82.23	\$ 63,647		
Electrician Journeyman		8,600.00	SF	0.010	\$ 86	\$ 84.55	\$ 7,272		
Equipment									
Mobile Production Equipment									
Cat 345 Excavators		8,600.00	SF	0.030	258	\$ 191	\$ 49,324		
MP30 Shears		8,600.00	SF	0.030	258	\$ 42	\$ 10,926		
Cat 980 Loaders		8,600.00	SF	0.030	258	\$ 144	\$ 37,149		
Cat D400/740 Trucks		8,600.00	SF	0.090	774	\$ 157	\$ 121,750		
Stationary Production Equipment									
none		8,600.00	SF	Included in main estimate		-	\$ -		
Hourly Support Equipment									
Mechanic/Welder Truck		8,600.00	SF	0.020	172	\$ 57	\$ 9,723		
Monthly Support Equipment									
none		8,600.00	SF	Included in main estimate		-	\$ -		
Materials									
Other		8,600.00	SF					\$ -	
Subcontracts									
Other		8,600.00	SF						\$ -
Total Item				3,440		\$ 225,129		\$ -	
						1,720		\$ 228,873	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	
								\$ -	



Nuna Group of Companies
Shear Diamonds Ltd.

Jericho Reclamation - Crown Owned Lands

Item 3 - Camp Demolition - Page 1

Prepared by Nuna Ltd


Item: **3** Description: **Camp Demolition**


Units: **SF**

Bid Quantity: **32000**

Takeoff Quantity: **32000**

0%									
Labour				Equipment			Materials	Subs	
Item	Description	Quantity	Units	Hours per Unit (hours)	Hours (hours)	Cost per hour (\$)	Cost (\$)		
Supervision, Administration, & Technical Services									
none				Included in main estimate					
Operations				32,000.00 SF					
Excavator Operator - Finish				32,000.00 SF					
Loader Operator (<988)				160 \$ 71.67 \$ 11,468					
Rock Trucks (<789)				160 \$ 68.80 \$ 11,008					
Labour (entry level)				480 \$ 62.99 \$ 30,233					
Maintenance and Trades				800 \$ 53.66 \$ 42,925					
Carpenter Journeyman				320 \$ 76.07 \$ 24,342					
Electrician Journeyman				320 \$ 84.55 \$ 27,057					
Equipment									
Mobile Production Equipment									
Cat 345 Excavators				0.005 160 \$ 191 \$ 30,589					
Cat 980 Loaders				0.005 160 \$ 144 \$ 23,038					
Cat D400/740 Trucks				0.015 480 \$ 157 \$ 75,504					
Stationary Production Equipment									
none				- - \$ -					
Hourly Support Equipment				- - \$ -					
none				- - \$ -					
Monthly Support Equipment				- - \$ -					
none				- - \$ -					
Materials									
Other				\$ -					
Subcontracts									
Other				\$ -					
Total Item				2,240 \$ 147,033					
Fuel Requirement (litres)									
30,880									
Engine Oil Requirement (litres)									
127									
Hydraulic Oil Requirement (litres)									
292									





Nuna Group of Companies
Shear Diamonds Ltd.

Jericho Reclamation - Crown Owned Lands

Item 5 - Utilidors/Walkways Demolition - Page 1

Prepared by Nuna L.

Draft Cost Estimate

Item:		Description:		Units:		Takeoff Quantity:		Bid Quantity:	
5		Utilidors/Walkways Demolition		SF		8000		8000	
Item	Description	Quantity	Units	Labour		Equipment		Materials	Subs
				Hours per Unit (hours)	Cost per hour (\$)	Hours (hours)	Cost per hour (\$)		
Labour	Supervision, Administration, & Technical Services	8,000.00	SF	Included in main estimate					
	Operations								
	Excavator Operator - Finish	8,000.00	SF	0.005	\$ 71.67	40	\$ 2,867		
	Loader Operator (<988)	8,000.00	SF	0.005	\$ 40	40	\$ 2,752		
	Rock Trucks (<789)	8,000.00	SF	0.015	\$ 120	120	\$ 7,558		
	Labour (entry level)	8,000.00	SF	0.025	\$ 200	200	\$ 10,731		
	Maintenance and Trades								
	Carpenter Journeyman	8,000.00	SF	0.010	\$ 80	80	\$ 6,085		
	Electrician Journeyman	8,000.00	SF	0.010	\$ 80	80	\$ 6,764		
Equipment									
	Mobile Production Equipment								
	Cat 245 Excavators	8,000.00	SF	0.005	\$ 40	40	\$ 191	\$ 7,547	
	Cat 580 Loaders	8,000.00	SF	0.005	\$ 40	40	\$ 144	\$ 5,760	
	Cat D400/740 Trucks	8,000.00	SF	0.015	\$ 120	120	\$ 157	\$ 18,876	
	Stationary Production Equipment								
	none	8,000.00	SF	Included in main estimate		-	\$ -	\$ -	
	Hourly Support Equipment								
	none	8,000.00	SF	-	\$ -	-	\$ -	\$ -	
	Monthly Support Equipment								
	none	8,000.00	SF	-	\$ -	-	\$ -	\$ -	
Materials									
	Other	8,000.00	SF					\$ -	
Subcontracts									
	Other	8,000.00	SF						\$ -
	Total Item			560	\$ 36,758	200	\$ 32,283	\$ -	\$ -
	Fuel Requirement (litres)	7,720							
	Engine Oil Requirement (litres)	32							
	Hydraulic Oil Requirement (litres)	73							

