

Water Resources Division Nunavut Regional Office Igaluit, NU X0A 0H0

March 4, 2019

Richard Dwyer Manager of Licensing Nunavut Water Board PO Box 119 Gjoa Haven, NU X0A 1J0 CIDM # 1243143

Re: 2AM-LUP1520 – Review of Lupin Mines Incorporated (LMI) Water Licence Renewal and Amendment Application and Final Closure and Reclamation Plan - Lupin Mine Property - Kitikmeot Region, Nunavut

Thank you for the email notice received on February 6, 2019, regarding the opportunity to comment on the Renewal application for the Lupin Mine Property.

Crown-Indigenous Relations and Northern Affairs Canada (CIRNAC) has reviewed the water licence renewal application documents provided by the Nunavut Water Board (NWB) located on the Nunavut Water Board FTP site as it relates to 2AM-LUP1520.

CIRNAC's comments are provided pursuant to its mandated responsibilities from the Nunavut Waters and Nunavut Surface Rights Tribunal Act and the Department of Indian Affairs and Northern Development Act.

If you have any questions or require further information with respect to this matter, contact me at (867) 222-9278 or by email at <a href="mailto:ian.parsons@canada.ca">ian.parsons@canada.ca</a>.

Sincerely,

Original signed by

Ian Parsons Regional Coordinator, Water Resources Division

# **Memorandum**

To: Richard Dwyer, Manager of Licensing, NWB

From: Ian Parsons, Regional Coordinator, Water Resources CIRNAC, Nunavut Regional Office

Date: March 1, 2019

Re: 2AM-LUP1520 – Review of Lupin Mines Incorporated (LMI) Water Licence Renewal and Amendment Application and Final Closure and Reclamation Plan – Lupin Mine Property – Kitikmeot Region, Nunavut

Applicant: Lupin Mines Inc. (LMI)
Project: Lupin Mine Project

Region: Kitikmeot

# **Background**

The Lupin Mine Site is situated in Nunavut's Kitikmeot region, approximately 250 km West of Arviat, 285 km southeast of Kugluktuk, Nunavut, and about 400 km north of Yellowknife, Northwest Territories. The airstrip serving this Site is at 65° 46'00" N and 111° 14'41" W. The Site is on the western shore of Contwoyto Lake, approximately 60 km south of the Arctic Circle.

The mine property is currently owned by Mandalay Resources with the licensee of the site being LMI. The Lupin Mine was in operation from 1982 to 2005 with temporary suspensions of activities between January 1998 and April 2000, and between August 2003 and March 2004. The mine resumed production in March 2004 until February 2005. The site has remained in Care and Maintenance since 2005.

Currently LMI is actively closing their property as per their approved Interim Closure and Reclamation Plan (FCRP) under their water licence 2AM-LUP1520. Part of the renewal application is the review of their FCRP.

CIRNAC reviewed the documentation associated with the renewal application for adequacy and validation of security requirements for the Lupin site. Attached below are CIRNAC's comments and recommendations on the renewal application and the FCRP document.

# A) General Application

Comment: CIRNAC notes in its review of the application that some management plans typical of any licence were not attached. These include, but are not limited to: Spill management Plan, Solid Waste management Plan, and Sewage Waste management Plan. If the licensee intends to use their plans that have been previously approved under their current licence, this should be stated and the plans submitted with the renewal application. If the licensee is aware of any changes to their operations arising from their intent to proceed with full reclamation of the site, these changes should be updated in the associated plans and submitted to the Nunavut Water Board.

Recommendation: The licensee should submit either updated management plans for their site or the management plans that were previously approved under their current license as part of the water license renewal application.

# B) Final Reclamation and Closure Plan Document

# i) **SUMMARY REVIEW COMMENTS**

The closure plan is not yet at the level of detail expected of a final closure plan. Some of the points that require more details include, but are not limited to:

- Geochemistry: Despite the large quantities of ARD waste rock and tailings, the plan does
  not provide much analysis to explain why this is not a long-term water quality concern.

  LMI needs to include geochemical source term and load modelling to verify that ARD at
  the site will not be an issue.
- 2. Thermal modelling: The active zone is around 2m, similar to other sites in the area. However, climate change predictions typically result in the active zone increasing to >4m within 100 years. That would presumably have an influence on the load model. In alignment with common practice in Nunavut, modelling is done for 100 years and we expect it for Lupin.
- Options analysis: The plan generally tends to select the preferred option without clear consideration of alternatives. Given that this is the final plan, more analysis of the alternatives and rationale for selection of preferred options is expected.
- Changes from ICRP: Major changes are proposed to earlier ICRP commitments without provision of rationale for those changes. LMI should present an acknowledgement of these changes and provide a comparison discussion as to why such changes should be considered.
- 5. Tailings: A variety of potential issues exist with respect to closure of the tailings system. These include, but are not limited to, changes to proposed stability and erosion plans, lack of geochemical modelling, proposed approaches to management of exposed tailings pursuant to dewatering, and an absence of details for proposed final closure works. LMI needs to provide sufficient details in its FCRP to provide confidence to CIRNAC that the

final designs and specifications will be appropriate to achieve the long term closure objectives for the site.

# ii) COMMENTS BY SECTION

The following comments are provided based on the structure of the FRCP layout. CIRNAC has made comments on each section following the layout of LMI's document.

# **EXECUTIVE SUMMARY**

The following observations are provided with respect to the Executive Summary.

- Section 5a): This section does not indicate permanent closure of the Access Ramp
- Section 5c): The reference for information on geochemical characterization needs to be corrected
- Section 5d.1): Clarification required for what "treatment plant" is being referred to in paragraph two.
- Section 5d.2): Last paragraph indicates permanent closure spillways will be constructed through Dam 1A and J Dam. Further details should be provided for these structures in the report.
- Section 5d.3): Last sentence notes that if exposed tailings are encountered when pond water level is lowered, they will either be relocated and covered with 1 m of esker material. The rationale for this decision should be provided.
- Section 5d.4/f(v): Given that 67% of PAG waste rock, additional assessment of ARD potential of mill site, airstrip access roads, and dams is warranted in the FCRP.
- Section 5f(viii): This section should indicate that burning of residual fuel, and placing PHC impacted soils underground would need to be approved by the regulator. Furthermore, clear provisions should be discussed with respect to verification testing to confirm clean up. If an Human Health Environmental Risk Assessment (HHERA) is being done then it should be a DQHHERA and not a screening level RA as costed in the RECLAIM estimate.
- Section 7: Amending the post closure monitoring from the current 25 years in the KP RECLAIM estimate to five years post remediation requires acceptance by the NWB.

ISSUE: Comments identify questions for clarity in the referred sections. REQUEST: The referenced sections require further clarification from LMI.

#### **SECTION 2 PROJECT DESCRIPTION**

Section 2.1.2

- The discussion on Climate Change is limited to temperature rise of 1 degree Celsius over the next century.

ISSUE: Ensuring climate change considerations are addressed in closure is critical to many aspects of the closure plan, particularly as it relates to ARD potential of the PAG waste rock distribution around the site and tailings system closure components REQUEST: LMI should provide additional information to support 100 year Climate

Change predictions

#### Section 2.1.8

- States that 40% of seeps at mine/mill site complex sampled in 2005 were acidic (Morrow 2006).
- The section also indicates 67% of waste rock is PAG, and PAG samples were distributed throughout the site, direct measurement of groundwater and seepage water confirmed ARD occurring (Golder 2017a).

ISSUE: There is no information on general locations of these samples and elements of the site that were sampled; did they include roadways, dams, pipelines, airstrip, etc. REQUEST: LMI should provide additional clarification on the extent of the sampling and confirm their strategy to manage PAG issues on parts of the site that are located away

## Section 2.3.2

from the Mill area.

- States that rip rap will be recovered and placed to stabilize dams and enhance embankment stability.

ISSUE – The FCRP did not provide conceptual figures or further details on where the rip rap will be recovered from (quarry or from existing dams) or where it will be placed as part of the reclamation works.

REQUEST – LMI9 should provide a conceptual plan for each location where rip rap is to be provided and detail the source of the rip rap so as to ascertain if there is a potential PAG concern that needs to be addressed before the design can be accepted.

# SECTION 4 PERMANENT CLOSURE and RECLAMATION

#### Section 4.3.2

 Table 14 is incomplete, not all activities have timelines for when they are expected to occur

ISSUE: Schedule of proposed work needs to be consistent and understood.

REQUEST: LMI should update Table 14 with missing timelines.

# Section 4.3.2 Reclamation Objectives and Closure Criteria

- States that technical specification for engineered cover will be established.

ISSUE: Without detailed specification of cover, it cannot be assessed properly.

REQUEST: LMI should provide cover specification details?

# Section 4.3.2.3 Synthesis of Preferred Activities into Reclamation Plan

- This section indicates that regrading of excavated depressions will be achieved by bringing in waste rock from perimeter areas.

ISSUE: Potential exists for the placement of PAG materials.

REQUEST: LMI should provide information on materials handling/management to avoid PAG materials.

 States that HHERA will be completed during final closure planning to develop site specific soil quality remediation objectives (see also section 6.2 which says HHERA is underway and is expected ready for review in July 2018).

ISSUE: There no clarity on the status of the report and if it is available for review? REQUEST – LMI should provide the HHERA assessment report.

## Section 4.3.2.3 Management and Accountability Structure

 States that a QA/QC document will be developed to verify remedial activities are implemented as planned.

ISSUE: There are concerns on how the proponent will verify that the PHC soil clean-up work is done in accordance with the site-specific standards established for the site in the HHERA or using NU regulations, and what standards will be established for the management of PAG concerns in the waste rock.

REQUEST: LMI should provide the QA/QC program (QA/QC document) that will be implemented during the implementation of the FCRP.

#### Section 4.3.2.3 Uncertainties and Information Needs

- States that HHERA results may affect final soil volumes.

ISSUE: The uncertainties associated with soils needs to be reduced as per results of HHERA

REQUEST- LMI should incorporate results of HHERA.

# Section 4.3.2.3 Monitoring, Maintenance, and Reporting Program

- States that the engineered cover (to risk manage arsenic impacted soils) will be monitored post closure and repairs made if and as needed.

ISSUE: No information is provided on nature of performance monitoring other than visual inspection.

REQUEST: LMI should provide additional details on monitoring program

- States Groundwater and seepage will be monitored on completion of remedial works.

ISSUE: There is no clear information provided on the nature of the groundwater and seepage monitoring.

REQUEST: LMI should provide additional details on the groundwater and seepage monitoring.

# **Section 4.3.2.3 Contingency Program**

- This section states that if post-closure monitoring identifies significant deficiencies with the engineered cover a more robust cover could be implemented.

ISSUE: There is no clear information provided with respect to how this post closure robust cover activity will be carried out.

REQUEST: LMI should provide information on how this robust cover activity would be carried out post closure.

 This section also states that the Nunavut industrial land clean up criteria will be used.

ISSUE: Not clear if this has been accepted by the NWB for this site or other sites in NU. REQUEST: LMI should confirm the specific official standards that will be applied for the reclamation/remediation works.

# Section 4.3.2.4 Underground Workings Contingency Program

- This section states that it may be necessary to pump water out of the crown pillars to the shaft. On page 13, it is noted that discharge to the environment may be considered as a contingency if water quality meets acceptable criteria.

ISSUE: It is unclear whether surface discharge is an option only if shaft discharge is not possible and water treatment is not needed.

REQUEST: LMI should clarify if surface discharge of treated mine water is considered an option.

 In this section there is no mention of an ice plug or permafrost related issued within the underground workings, and if there is, what approach will be used for mitigation in order to allow for disposal of PAG waste rock and PHC impacted soils into the underground.

ISSUE: It is unclear whether there are ice related issues that could impact the placement of waste and PHC impacted soils within the underground.

REQUEST: LMI should clarify if ice/permafrost related issues have been investigated, and how any potential concerns will be mitigated in advance of the reclamation works.

# Section 4.3.2.7 Waste Rock - Project Description

 States 67% of 1,000,000 m3 are PAG and most of the WR was used for construction at Mill.

ISSUE: The estimated PAG increase from less than 10% to 67% is a significant increase in PAG materials.

REQUEST: Given the present high percentage of PAG, can LMI provide any estimates on potential waste rock distribution across the property (e.g. mill areas, roads, dams, air strip, etc.).

## Section 4.3.2.7 Waste Rock – Possible Reclamation Options & Preferred Activities

 This section states that contouring and covering with a 1 m esker cover will result in minimal contact between water and the waste rock. It also states that the 1m cover will be partially frozen during spring freshet and infiltration through the cover will be small.

ISSUE: About 1 million cubic meters of waste rock (67% PAG) are proposed to be left in place, sloped and contoured for drainage using a nominal 1 m of esker cover.

REQUEST: (1) LMI should provide geochemical model of the proposed mill pile, and other features constructed of PAG waste rock (e.g. the airstrip, dams, roads) for current conditions and long-term climate change conditions. (2) LMI should provide estimates of contaminant loads released to the environment under these conditions. (3) LMI should provide confirmation that the current thermal monitoring program is sufficient to address the issues relating to the waste rock, the TCA, and the proposed mill waste rock pile.

- Figure 10 provides conceptual outline of materials to be excavated from perimeter and outline of central consolidated area.

ISSUE: The illustration does not clearly indicate if the waste rock from roads and pipelines are being removed, and to what degree excavation will occur at the airstrip. REQUEST: LMI should clarify the nature and extent of the excavation proposed.

# Section 4.3.2.7 Waste Rock - Contingency Program

- Figure 10 provides surface plan of proposed excavation and placement areas. The notes indicate that Figure 10 is an estimate, and the actual boundary will be based on field conditions.

ISSUE: The section does not provide conceptual cross-section or details on potential slopes. REQUEST – LMI should provide conceptual sections illustrating proposed height of central waste rock, typical details of cover placement and the means by which the loss of fine grained soils from the esker cap into the waste rock will be mitigated.

# Section 4.3.2.8 Tailings Impoundment and Containment Systems - Project Description

This section notes that when natural drainage is re-established and water is drawn down, it is possible that spilled tailings presently under water may become "exposed" and these tailings will either be covered in place with esker material or relocated to the TMA and eventually covered.

ISSUE: Tailings are known to be acid generating and seepage will be acidic. It is not acceptable to leave unconfined tailings outside of the tailings dams even if covered by esker materials.

REQUEST: LMI should provide justification for leaving exposed tailings outside of the tailings basin.

- States that "stability of all dams will continue to be assessed, and where required, for example on the downstream side of Dam 4, minor grading, rip rap placement, and backfilling may occur in response to recommendations provided by the TCA engineer of record."

ISSUE – The ICRP in Section 6.5.3 stated that "a major program of dam enhancement is planned during closure activities. The sides of all dams will be brought to at least a 2.5:1 slope by the addition of quarried waste rock. This will significantly enhance both stability of the dam and erosion protection of all dams." The current closure plan is a departure from the ICRP commitment.

REQUEST: LMI should provide information supporting this material departure from the previous commitment to rip rap armor all dams to enhance stability and erosion protection.

# Section 4.3.2.10 Transportation and Infrastructure Support

No other significant concerns with this section aside from issues previously raised with respect to waste rock being used in the construction of site access roads and the airstrip as it relates to potential PAG waste rock having been used in their construction.

#### Section 4.3.2.12 Landfarm

No significant concerns with the FCRP, however the RECLAIM estimate does not appear to have a cost to decommission the landfarm once PHC impacted soils have been successfully treated or the material is placed underground.

# Section 4.3.2.13 Waste Management Systems - Project Description

Missing Project Description Section.

ISSUE: Inconsistency with other sections.

REQUEST: LMI to add Project Description Section

# Section 4.3.2.13 Waste Management Systems – Synthesis of Preferred Activities into a Reclamation Plan

This section notes that to achieve natural drainage, two engineered riprap spillways will be constructed, along with a swale consisting of riprap on geotextile.

ISSUE: No information is provided on the design of the spillways.

REQUEST: LMI should provide the design basis for the spillways and conceptual designs of the spillways.

#### Section 4.3.2.13 Waste Management Systems –Contingency Program

This section states that if water quality fails, construction of spillways will be deferred.

ISSUE: Table 14 indicates spillways will be constructed in 2025. It is unclear if implications of deferring spillway construction beyond the stated period are considered with respect to final closure of the site.

REQUEST: LMI should confirm timing of planned spillway construction, and consideration of the deferral in its cost estimate.

## **Section 4.4 Material Balance**

No significant concerns. However on Table 17 the volume of demolition rubble (30,000 m<sup>3</sup>) does not match what is described earlier in the FCRP document (55,290 m<sup>3</sup>).

ISSUE – Inconsistency in the reported numbers.

REQUEST: The volume of demolition waste, including the waste being generated from the local bone yards, should be consistent in all reports and clearly outlined in Table 17.

## Section 4.5 Schedule

 On the Table 14, some only activities have timelines for when they are expected to occur.

ISSUE: Schedule of all proposed work on the Table 14 should have timelines. REQUEST: LMI should update Table 14 with missing timelines.

# **SECTION 5 MONITORING**

- The Phase 3 Passive Closure Period Monitoring is stated to be for a period of 5 years.

ISSUE: The ICRP anticipated a closure phase annual monitoring period of ten (10) years, and post closure monitoring every three (3) years thereafter to the 25 year mark. REQUEST: LMI should explain the basis for their proposed reduced monitoring period.

# SECTION 6 POST REMEDIATION SITE AND ENVIRONMENTAL CONDITIONS

#### **Section 6.1 Post Remediation Site Conditions**

- LMI has not included any commitments to monitor site conditions, post remediation. These include, but are not limited to, water quality, waste rock seepage and Acid Rock Drainage (ARD), stability of esker cover, etc.

Request: LMI to provide information on post closure monitoring of site.

# Section 6.2 Post Remediation Environment Conditions /Post Remediation Risks to Human Health and Environmental Health

Notes commitment to HHERA being carried out.

ISSUE: The HHERA document has not been provided REQUEST: LMI should provide the HHERA document

# **SECTION 7 FINACIAL SECURITY**

General comments and questions are as presented below.

# Underground

- Costs associated with the relocation of waste rock to complete a 3 m thick cover are too low as the material to be used in the construction of the cap will likely need to be excavated, hauled, placed and graded rather than simply dozed into place. This is particularly true if PAG rock issues are identified in the waste rock immediately adjacent the crown pillar.
- It is unclear where any ice or water management costs are included as may be required in advance of the PHC impacted soil and PAG waste rock placement into the underground workings.

ISSUE: Clarification is needed with respect to the basis for the costing.

REQUEST: LMI should provide additional information on the basis for the costing.

# **Tailings**

- How was the volume of 15,000 m<sup>3</sup> derived for the riprap to be placed on the M Dam?
- The time being allotted here seems low for the amount of work to be done however in the absence of a conceptual plan it is difficult to comments on this work item. How was the quantity of time derived for the grading of the M Dam?
- There is little clarity on how the basis for the cost is related to the Cell 4 allowance.
- What is the basis for the number of thermal units to be installed and monitored? More information is required to confirm the count.
- It would help if there was a plan in the FCRP to help the reviewer understand if there is sufficient number of thermistors on site to address future monitoring requirements for both the TCA and the PAG waste rock areas.

ISSUE: Clarification is needed with respect to basis for costing.

REQUEST: LMI should provide additional information for clarity on the basis for the costing.

## **Waste Rock**

- There is a lack of clarity on the basis for the volume of esker material required to cap the consolidated PAG waste rock.
- The rate for the relocation of the waste rock is relatively low given the amount of work required. May consider using the rate for SC4L (\$9.30/m³).

- How has the volume of PAG waste rock in the access roads and airstrip been accounted for?
- The rate for the load, haul, dump/doze the impacted PAG waste rock should include for an additional \$1.05/m³ as the current rate only accounts for the load, haul and tip with no allowance for grading.

ISSUE: Clarification is needed with respect to basis for costing.

REQUEST: LMI should provide additional information for clarity on the basis for the costing.

#### Chemical

- The rational for the decontamination costs for the oil, fuel and glycol systems is unknown. The cost seems low especially for the large diesel fuel tanks.
- The asbestos abatement rates for the floor tile seem low given the level of effort, typically greater for the tile as compared to the vinyl sheeting. Would use the same rate for both pieces of work.
- No costs provided for the burning of waste oil and/or residual fuel as the costs provided are for off-site removal. Also, the rate for the removal of waste oil and fuel should be the same given the level of effort required to consolidate, containerize, and ship off site for recycling or disposal.
- The cost to complete the HHERA seems low given the need to complete a Detailed Quantitative HHERA.
- It is unclear where the verification sampling costs have been accounted for in the estimate.
- Where is the cost to manage the 500 m<sup>3</sup> of PHC impacted soil currently in the landfarm?
- Where is the cost to decommission the landfarm?
- It is unclear where the costs are for the decontamination and decommissioning of above ground equipment has been included.

ISSUE: Clarification is needed with respect to basis for costing.

REQUEST: LMI should provide additional information for clarity on the basis for the costing.

#### **Buildings**

- The production rate for the hoe ram to break the concrete floor seems high. What is the basis for the production rate?
- What is the basis for the consolidation of the boneyard cost?
- It is unclear where the Non-PAG waste rock that will be used in the capping of demolition waste will come from?

- The volume (30,000 m<sup>3</sup>) of demolition waste does not align with the FCRP indicated volume of 55,290 m<sup>3</sup>.
- What is the basis for the cost allowance to operate the landfill?

ISSUE: Clarification is needed with respect to basis for costing.

REQUEST: LMI should provide additional information for clarity on the basis for the costing.

#### **Interim Care and Maintenance**

The time period for ICM should be five years. LMI should update their closure cost estimate to include a time period of five years for their ICM.

# **Post Closure Monitoring & Maintenance**

The use of a discounted rate is not appropriate as the discounted rate is effectively equivalent to CPI and as such the two net out.

#### **Mobilization**

Not clear why no cost has been assigned for the worker cross shift travel time and any associated costs with accommodations related to worker cross shifts (i.e. hotels in Edmonton or Yellowknife).

Request: These costs should be included in any closure cost estimate.

# C) Conclusion

CIRNAC has provided these comprehensive comments to facilitate information clarity, and discussions if required for the water licence application review.