

\\ca0200-ppfs01\shared\_projects\129500081\disc\drafting\05\_tca structures detailed design\plan view-cell 5

2020.05.15 4:17:47 PM

TABLE 1. FOUNDATION PREPARATION SPECIFICATIONS

| FOUNDATION                                  |  |
|---|--|
| GENERAL                                     | <ul style="list-style-type: none"><li>FOUNDATION SURFACES THAT WILL BE RECEIVING COVER FILL SHALL BE CLEARED OF SNOW, ICE, AND OTHER DETERIORATIVE MATERIAL. THE FOUNDATION SHALL BE INSPECTED BY THE CONTRACTOR’S FOREMAN AND OWNERS SITE ENGINEER (WHEN THEY ARE ON SITE) AND DOCUMENTED USING GPS REFERENCED PHOTOS TO CONFIRM ADHERENCE WITH FOUNDATION PREPARATION SPECIFICATIONS.</li><li>WRITTEN FOUNDATION APPROVAL BY AREA SHALL BE PROVIDED BY THE OWNERS SITE ENGINEER (WHEN THEY ARE ON SITE) OR THE ENGINEER OF RECORD (REMOTELY WHEN THE OWNERS SITE ENGINEER IS NOT ON SITE) PRIOR TO PLACEMENT. WHEN THE OWNERS SITE ENGINEER IS NOT ON SITE THE GPS REFERENCED PHOTO DOCUMENTATION SHALL BE PROVIDED TO THE ENGINEER 72HRS PRIOR TO PLANNED PLACEMENT TO ALLOW FOR SUFFICIENT TIME FOR REVIEW AND APPROVAL. THE PHOTO DOCUMENTATION PROVIDED SHALL CAPTURE DIRECTIONS IN SUCH A WAY THAT ALL LIMITS OF THE CONSTRUCTION AREA WILL BE DOCUMENTED FOR REVIEW.</li><li>SITE DRAINAGE AND DEWATERING MEASURES ARE THE RESPONSIBILITY OF THE EARTHWORKS CONTRACTOR. TEMPORARY AND FINAL CONSTRUCTION SURFACES SHOULD BE GRADED TOWARD THE DITCHES AND/OR AWAY FROM THE DAM CREST TO ENSURE THERE IS NO PONDING OF WATER NEAR THE DAM TO PREVENT OVERFLOW OR OVERTOPPING.</li><li>DEVIATIONS FROM THE SPECIFICATIONS MUST BE APPROVED BY THE TAILINGS CONTAINMENT AREA (TCA) ENGINEER OF RECORD.</li><li>CONTRACTOR SHALL PRESERVE SURVEY CONTROL STAKES FOR PROGRESSION AS LONG AS POSSIBLE BETWEEN SURVEY PERIODS, OR BE RESPONSIBLE TO REPLACE THEM AS NEEDED. ONCE THE CONTROL STAKE IS REMOVED, THE CONTRACTOR MUST MOVE CONSTRUCTION ACTIVITIES TO AN AREA WITH SUFFICIENT SURVEY CONTROL. THE CONTRACTOR MUST PROVIDE THE OWNER 1 WEEKS’ NOTICE IN ADVANCE OF WHEN THEY REQUIRE THE DAMAGED SURVEY CONTROL POINTS REPAIRED.</li><li>THE CONTRACTOR IS RESPONSIBLE TO MANAGE SURROUNDING SURFACE RUN-ON TO TAILINGS COVER TO MINIMIZE THE AMOUNT OF IMPACTED WATER WITHIN THE COVER PLACEMENT AREA.</li></ul> |
| COVER FOUNDATION PREPARATION SPECIFICATIONS | <ul style="list-style-type: none"><li>THE FOUNDATION SHALL BE CAPABLE OF SUPPORTING COVER FILL AND CONSTRUCTION EQUIPMENT TO THE SATISFACTION OF THE CONTRACTOR, SUBJECTED TO ENGINEER’S APPROVAL.</li><li>PRIOR TO AND DURING FILL PLACEMENT, APPROVED FOUNDATION SURFACES SHALL BE CLEARED OF ALL ICE, HARDEN SNOWBANKS THICKER THAN 30 MM, LARGE BODIES OF PONDED WATER THAT ARE GREATER THAN 5M X 5M AND GREATER THAN DEPTH, AND ANY OTHER MATERIAL DEEMED UNSUITABLE BY THE OWNERS SITE ENGINEER. A THIN LAYER OF FRESH, UNCOMPACTED SNOW (&lt;50MM) IS PERMITTED TO REMAIN IN PLACE DURING COVER CONSTRUCTION.</li></ul>   |
| DAM OUTFALL CHANNEL AREA FOUNDATION         | <ul style="list-style-type: none"><li>THE FOUNDATION SHALL BE CAPABLE OF SUPPORTING FILL AND CONSTRUCTION EQUIPMENT TO THE REGULATED SAFETY STANDARDS AND TO THE SATISFACTION OF THE CONTRACTOR AND SUBJECT TO APPROVAL OF THE ENGINEER.</li><li>THE EXCAVATED SURFACE MUST BE SURVEYED TO ENSURE DESIGN IS MET PRIOR TO BACKFILL. THE CONTRACTOR IS RESPONSIBLE TO SCHEDULE THE WORK IN LINE WITH THE MONTHLY SURVEY.</li><li>100% OF THE SURFACE OF THE FOUNDATION AND PREVIOUSLY PLACED LIFTS SHALL BE CLEAR OF ALL SNOW OR ICE PRIOR TO THE PLACEMENT OF GEOTEXTILE AND/OR RIPRAP.</li><li>THE FINAL RIPRAP SURFACE MUST BE BLENDED INTO THE TOP OF COVER TO ENSURE A SMOOTH TRANSITION. THE ENGINEER MUST INSPECT AND APPROVE THE SURVEYED EXCAVATION AND FINAL STRUCTURES.</li></ul>   |

TABLE 2. FILL PLACEMENT SPECIFICATIONS

| COVER   |                           |   |
|---|---------------------------|---|
| <ul style="list-style-type: none"><li>ALL TEMPORARY AND FINAL SLOPES SHALL BE TRACK PACKED TO LIMIT SURFACE EROSION.</li><li>UNLESS OTHERWISE APPROVED BY THE OWNERS SITE ENGINEER, FILL MATERIALS SHALL BE PLACED, AND SPREAD, IN –HORIZONTAL LIFTS AND IN SUCH A MANNER TO PREVENT SEGREGATION AND STRATIFICATION.</li><li>IMPACTED WATER FROM THE TAILINGS CELLS DISPLACED DURING COVER MATERIAL PLACEMENT MUST BE MANAGED AND DISCHARGE IN SUCH A WAY THAT WILL NOT IMPACT THE WATER TREATMENT IN POND 1 AND POND 2.</li><li>FILL MATERIALS SHALL JOIN ONTO COMPETENT NATURAL, EXCAVATED, OR APPROVED FILL BY BLENDING INTO THE EXISTING TERRAIN SLOPES OR BY TERRACING OR STEPPING INTO SLOPES AS APPROVED BY THE OWNERS SITE ENGINEER.</li><li>FINISHED COVER SURFACE SHALL BE WITHIN 50MM OF ESTABLISHED ROUGH GRADES AND CROSS SECTIONS, BUT NOT UNIFORMLY HIGH OR LOW. THE FINAL SURFACE SHALL BE FREE DRAINING TOWARDS THE DESIGN WATER MANAGEMENT STRUCTURES.</li><li>DEVIATIONS FROM THE SPECIFICATIONS MUST BE APPROVED BY THE TAILINGS CONTAINMENT AREA (TCA) ENGINEER OF RECORD (EOR).</li><li>THE CONTRACTOR IS RESPONSIBLE FOR ANY SHORT-TERM SETTLEMENT AND DEFORMATION ON THE COVER DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE TO PLACE ADDITIONAL FILL WHERE IT IS NECESSARY TO MEET MINIMUM 1m COVER THICKNESS OR TO MEET DESIGN LINES.</li><li>CONTRACTOR SHALL PRESERVE SURVEY CONTROL STAKES FOR PROGRESSION AS LONG AS POSSIBLE BETWEEN SURVEY PERIODS OR BE RESPONSIBLE TO REPLACE THEM AS NEEDED. ONCE THE CONTROL STAKE IS REMOVED, THE CONTRACTOR MUST MOVE CONSTRUCTION ACTIVITIES TO AN AREA WITH SUFFICIENT SURVEY CONTROL. THE CONTRACTOR MUST PROVIDE THE OWNER 1 WEEKS’ NOTICE IN ADVANCE OF WHEN THEY REQUIRE THE DAMAGED SURVEY CONTROL POINTS REPAIRED.</li></ul> |                           |   |
| FILL TYPE   | PERMITTED MATERIALS       | PLACEMENT SPECIFICATIONS  |
| COVER FILL  | •ESKER                    | <ul style="list-style-type: none"><li>MAXIMUM SIZE OF MATERIAL SHALL BE 250 MM OR 50% OF THE LIFT THICKNESS, WHICHEVER IS SMALLER.</li><li>PLACEMENT OF FROZEN FILL IS RESTRICTED UNLESS APPROVED BY THE ENGINEER. SOME FROZEN COVER FILL IS PERMITTED PROVIDED THAT:<ul style="list-style-type: none"><li>THE DIAMETER OF THE FROZEN LUMPS IS LESS THAN 250 M IN DIAMETER OR 50% OF THE LIFT THICKNESS, WHICHEVER IS SMALLER</li><li>THEY MAKE UP LESS THAN 5% BY VOLUME OF ANY GIVEN TRUCK LOAD</li><li>THE FROZEN MATERIALS ARE APPROVED IN CONSULTATION WITH THE RESIDENT ENGINEER.</li></ul></li></ul>   |
| RIPRAP  | •CLASS 1                  | <ul style="list-style-type: none"><li>MATERIAL SHALL MEET OR EXCEED THE CLASS 1 GRADATION RECOMMENDATION PRESENTED IN TABLE 3.</li><li>CONTRACTOR’S QC SHALL VERIFY SIZE DISTRIBUTION IN ACCORDANCE WITH ‘STANDARD METHOD OF TEST FOR DETERMINING RIPRAP GRADATION BY WOLMAN COUNT’ CONSULTATION WITH THE OWNERS SITE ENGINEER.</li><li>EXTENT OF PLACEMENT SHOWN AT TOE OF CELL 5 OUTFLOW (STA 0+050 TO 0+075) MAY BE REDUCED BASED ON FIELD CONDITIONS, UPON APPROVAL BY THE TCA EOR, IF:<ul style="list-style-type: none"><li>LARGER DIAMETER MATERIAL IS AVAILABLE</li><li>EXISTING GROUND AT TOE OF STRUCTURE IS DEEMED COMPETENT BY THE OWNERS SITE ENGINEER</li></ul></li></ul>  |
| GEOTEXTILE FILTER FABRIC  | •GEOTEXTILE FILTER FABRIC | <ul style="list-style-type: none"><li>GEOTEXTILE SHALL BE A COMPOSITE NON-WOVEN GEOTEXTILE AND EXTRUDED GEOGRID COMPOSITE PRODUCT (NILEX EASYGRID OR EQUIVALENT) AND SHALL MEET THE SPECIFICATIONS PROVIDED IN TABLE 4.</li><li>GEOTEXTILE SHALL BE INSTALLED IN OVERLAPPING CONFIGURATION WITH A MINIMUM 0.3 M OVERLAP BETWEEN PANELS AS SPECIFIED BY MANUFACTURER’S INSTALLATION GUIDANCE, OR AS APPROVED BY THE TCA EOR.</li><li>GEOTEXTILE SHALL BE STORED ON DRY, LEVEL GROUND TO PREVENT FILTRATION OF WATER AND FREEZING, AND GEOTEXTILE ROLLS SHOULD BE STACKED ACCORDING TO THE MANUFACTURER’S RECOMMENDATIONS. THEY MUST BE STORED WITHIN THEIR PROTECTIVE WRAPPING TO PREVENT UV DEGRADATION. THE GEOTEXTILE ROLLS MUST BE HANDLED WITH PROPER EQUIPMENT OR SLINGS TO PREVENT DAMAGE TO THE PRODUCT.</li><li>THE CONTRACTOR MUST PROVIDE MANUFACTURERS’ QA/QC DATASHEETS AND SHIPPING MANIFESTS FOR THE RESIDENT GEOTECHNICAL ENGINEER’S REVIEW PRIOR TO DEPLOYMENT.</li></ul> |

TABLE 3. MATERIALS SIZE SPECIFICATIONS

| GRADATION                                  | RIP RAP CLASS 1 |                       |
|--|-----------------|-----------------------|
|  | MASS (KG)       | DIAMETER (mm) PASSING |
| NOMINAL                                    | 40              | 300                   |
| 100%                                       | 130             | >=450                 |
| 25% TO 50%                                 | 70              | 350                   |
| 50% TO 80%                                 | 40              | 300                   |
| 100% GREATER THAN                          | 10              | 200                   |
| • SIZES ARE EQUIVALENT SPHERICAL DIAMETERS |                 |                       |

TABLE 4. GEOTEXTILE SPECIFICATIONS

| PARAMETER                         | VALUE                 |
|-----------------------------------|-----------------------|
| GRAB TENSILE STRENGTH (KN/m)      | DIAMETER (mm) PASSING |
| ELONGATION                        | 300                   |
| PESISTANCE TO STATIC PUNCTURE (N) | 2100                  |
| APPARENT OPENING SIZE (MICRONS)   | 350                   |
| PERMITTIVITY (SEC <sup>-1</sup> ) | 300                   |
| GRID OPENING SIZE (mm)            | 200                   |



Stantec  
111 Dunsmir Street  
Vancouver, BC, V6B 6A3  
Tel: +1(604) 696-8000  
www.stantec.com

**APPROVED**

By Alvin Tong, P.Eng. at 4:16 pm, Jul 06, 2020

Client  
LUPIN MINES INC.


Project  
LUPIN MINE CLOSURE

Title  
TAILING CONTAINMENT AREA CLOSURE SPECIFICATION


Scale:- Drawing No. 001  
SS PK AT 2020.05.15  
Dwn. Dsgn. Chkd. YYYY.MM.DD Revision: B  
Project No.: 129500081







CHANNEL CENTERLINE PROFILE (STA 0+450 TO STA 0+900)  
VERTICAL EXAGGERATION: 10X



CHANNEL CENTERLINE PROFILE (STA 0+00 TO STA 0+450)  
VERTICAL EXAGGERATION: 10X

**APPROVED**  
By Alvin Tong, P.Eng. at 4:20 pm, Jul 06, 2020

*Alvin Tong*



Stantec  
111 Dunsmuir Street  
Vancouver, BC, V6B 6A3  
Tel: +1(604) 696-8000  
www.stantec.com

LEGEND  
--- EXISTING GROUND PROFILE  
--- DESIGN COVER  
--- NO DATA (SEE NOTE 3)  
ESKER COVER FILL MATERIAL  
OUTFLOW CHANNEL MATERIAL. SEE DRAWING 005



NOTE  
1. EXISTING TOPOGRAPHIC CONTOURS AND WATER COVERED AREAS DELINEATED FROM LIDAR SURVEY COMPLETED AUGUST 2019 AND BATHYMETRY SURVEYS COMPLETED JUNE 2019.  
2. COORDINATES ARE PRESENTED IN NAD83 UTM, ZONE 12.  
3. TOPOGRAPHY AND BATHYMETRY SURVEYS NOT AVAILABLE FOR THESE AREAS DUE TO PONDED WATER. THE CONTRACTOR SHALL REMOVE ANY PONDED WATER PRIOR TO PLACEMENT OF COVER FILL IN THESE AREAS. THE CONTRACTOR SHALL ALSO ADJUST THE COVER FILL SURFACE ELEVATIONS AND/OR SUBEXCAVATE IN THESE AREAS TO ENSURE A MINIMUM 1.0m FILL COVER OVER TAILINGS AS DIRECTED BY THE RESIDENT GEOTECHNICAL ENGINEER.  
4. OUTLINE OF FILL COVER PLACEMENT IS APPROXIMATE BASED ON INTERPRETATION OF PREVIOUS SURVEYS AND AERIAL PHOTOGRAPHY. THE CONTRACTOR SHALL CONFIRM THE LOCATION AND MINIMUM THICKNESS OF FILL COVER ALONG THE TIE IN LIMITS.  
5. DEPTH OF COVER BELOW EXISTING GROUND HAS NOT BEEN CONFIRMED. THE CONTRACTOR SHALL CONDUCT SUBEXACATION AND BACKFILL ACTIVITIES IN THESE AREAS AS DIRECTED BY THE RESIDENT GEOTECHNICAL ENGINEER TO ENSURE A MINIMUM 1.0m FILL COVER OVER TAILINGS.

Client  
LUPIN MINES INC.

Project  
LUPIN MINE CLOSURE

Title  
CELL 5 CLOSURE  
PROFILE ALONG CHANNEL CENTERLINE  
Scale:- Drawing No. 003  
SS PK AW 2020.04.15  
Dwn. Dgn. Chkd. YYYY.MM.DD Revision: A  
Project No.: 129500081

\\ca0200-ppfs01\shared\_projects\129500081\disc\drafting\05\_1ca structures detailed design\plan view-cell 5



**APPROVED**  
By Alvin Tong, P.Eng. at 4:22 pm, Jul 06, 2020

*Alvin Tong*



Stantec  
111 Dunsmuir Street  
Vancouver, BC, V6B 6A3  
Tel: +1(604) 696-8000  
www.stantec.com

LEGEND  
--- EXISTING GROUND PROFILE  
— DESIGN COVER  
--- DRAINAGE CHANNEL CENTERLINE  
--- NO DATA (SEE NOTE 3)  
ESKER COVER FILL MATERIAL

NOTE  
1. EXISTING TOPOGRAPHIC CONTOURS AND WATER COVERED AREAS DELINEATED FROM LIDAR SURVEY COMPLETED AUGUST 2019 AND BATHYMETRY SURVEYS COMPLETED JUNE 2019.  
2. COORDINATES ARE PRESENTED IN NAD83 UTM, ZONE 12.  
3. TOPOGRAPHY AND BATHYMETRY SURVEYS NOT AVAILABLE FOR THESE AREAS DUE TO PONDED WATER. THE CONTRACTOR SHALL REMOVE ANY PONDED WATER PRIOR TO PLACEMENT OF COVER FILL IN THESE AREAS. THE CONTRACTOR SHALL ALSO ADJUST THE COVER FILL SURFACE ELEVATIONS AND/OR SUBEXCAVATE IN THESE AREAS TO ENSURE A MINIMUM 1.0m FILL COVER OVER TAILINGS AS DIRECTED BY THE RESIDENT GEOTECHNICAL ENGINEER.  
4. OUTLINE OF FILL COVER PLACEMENT IS APPROXIMATE BASED ON INTERPRETATION OF PREVIOUS SURVEYS AND AERIAL PHOTOGRAPHY. THE CONTRACTOR SHALL CONFIRM THE LOCATION AND MINIMUM THICKNESS OF FILL COVER ALONG THE TIE IN LIMITS.


Client  
LUPIN MINES INC.  
  
Project  
LUPIN MINE CLOSURE

Title  
CELL 5 CLOSURE  
CROSS-SECTIONS  
Scale:- Drawing No.004  
SS PK AW 2020.04.15  
Dwn Dgn Chkd YYYY.MM.DD Revision: A  
Project No.: 129500081

2020.04.15 2:56:16 PM




\\ca0200-ppfs01\shared\_projects\129500081\disc\drafting\05\_1ca\_structures\_detailed\_design\plan view-cell 5

2020.04.15 5:09:55 PM



| POINT NUMBER | NORTHING | EASTING | ELEVATION | POINT NUMBER | NORTHING | EASTING | ELEVATION | POINT NUMBER | NORTHING | EASTING | ELEVATION |
|--------------|----------|---------|-----------|--------------|----------|---------|-----------|--------------|----------|---------|-----------|
| 100          | 7289826  | 487526  | 484.1     | 107          | 7289872  | 487481  | 486.7     | 114          | 7289859  | 487481  | 487.5     |
| 101          | 7289842  | 487508  | 486.1     | 108          | 7289861  | 487493  | 486.7     | 115          | 7289855  | 487483  | 487.5     |
| 102          | 7289859  | 487490  | 486.7     | 109          | 7289845  | 487510  | 486.1     | 116          | 7289837  | 487503  | 486.9     |
| 103          | 7289823  | 487523  | 484.6     | 110          | 7289828  | 487528  | 484.5     | 117          | 7289820  | 487520  | 484.5     |
| 104          | 7289840  | 487506  | 486.1     | 111          | 7289831  | 487530  | 484.5     | 118          | 7289882  | 487471  | 486.6     |
| 105          | 7289857  | 487487  | 486.7     | 112          | 7289847  | 487513  | 486.9     | 119          | 7289881  | 487469  | 486.6     |
| 106          | 7289869  | 487478  | 486.7     | 113          | 7289868  | 487492  | 487.5     | 120          | 7289849  | 487501  | 486.7     |
|              |          |         |           |              |          |         |           | 121          | 7289847  | 487498  | 486.7     |
|              |          |         |           |              |          |         |           | 122          | 7289851  | 487503  | 486.7     |

WORK POINTS DESCRIPTION



Stantec  
111 Dunsmir Street  
Vancouver, BC, V6B 6A3  
Tel: +1(604) 696-8000  
www.stantec.com

LEGEND

- 2m EXISTING GROUND CONTOURS
- 0.5m EXISTING GROUND CONTOURS
- 2m DESIGN CONTOURS
- 0.5m DESIGN CONTOURS
- APPROXIMATE OUTFLOW CHANNEL WORKS EXTENT
- GEOTEXTILE
- NO DATA. SEE NOTE 3.
- WATERLINE

- WATER COVERED AREA
- ESKER COVER FILL MATERIAL
- RIPRAP-CLASS 1
- RIPRAP-CLASS 1 (EXTENDED PLACEMENT. SEE NOTE 3)

NOTE

- EXISTING TOPOGRAPHIC CONTOURS AND WATER COVERED AREAS DELINEATED FROM LIDAR SURVEY COMPLETED AUGUST 2019 AND BATHYMETRY SURVEYS COMPLETED JUNE 2019.
- COORDINATES ARE PRESENTED IN NAD83 UTM, ZONE 12.
- PLACEMENT SHOWN AT TOE OF STRUCTURE (STA 0+050 TO 0+075) MAY NOT BE REQUIRED. REFER TO CONSTRUCTION SPECIFICATIONS DRAWING 001 TABLE 2, CLASS 1 PLACEMENT SPECIFICATIONS FOR ADDITIONAL INFORMATION
- FILL OUTER BERM SIDE SLOPE
  - IS 40% FROM GROUND CONTACT IN POND 1 TO STA 0+055
  - IS 20% BETWEEN STA 0+070 AND CONTACT WITH SIDE SLOPE OF J DAM.
  - TRANSITIONS SMOOTHLY FROM 40% TO 20% BETWEEN STA 0+050 AND STA 0+070

Client  
LUPIN MINES INC.

Project  
LUPIN MINE CLOSURE

Title  
CELL 5 CLOSURE

OUTFLOW CHANNEL

Scale: 1:4000 Drawing No.005

|      |       |       |            |
|------|-------|-------|------------|
| SS   | PK    | AW    | 2020.04.15 |
| Dwn. | Dsgn. | Chkd. | YYYY.MM.DD |

Project No.: 129500081


Revision: A

File Name: PLAN VIEW-CELL 5



c:\data\129500081\disc\drafting\05\_tca structures detailed design\plan view-cell 3

2020.05.05 11:21:33 AM



WORK POINTS DESCRIPTION

| POINT NUMBER       |    | NORTHING | EASTING | ELEVATION |
|--------------------|----|----------|---------|-----------|
| CHANNEL CENTERLINE | 1  | 7288600  | 487305  | 487.0     |
|                    | 2  | 7288596  | 487205  | 487.0     |
|                    | 3  | 7288618  | 487163  | 487.1     |
|                    | 4  | 7288757  | 487110  | 487.9     |
|                    | 5  | 7288833  | 487044  | 488.8     |
|                    | 6  | 7288916  | 486950  | 489.8     |
|                    | 7  | 7288996  | 487019  | 490.8     |
|                    | 8  | 7289045  | 486995  | 491.3     |
| COVER DESIGN       | 9  | 7289022  | 487023  | 491.0     |
|                    | 10 | 7289028  | 487048  | 490.9     |
|                    | 11 | 7288968  | 487075  | 490.2     |
|                    | 12 | 7288854  | 487146  | 489.0     |
|                    | 13 | 7288788  | 487064  | 489.0     |
|                    | 14 | 7288841  | 487017  | 489.5     |
|                    | 15 | 7288914  | 486909  | 490.0     |
|                    | 16 | 7288974  | 486876  | 490.5     |
|                    | 17 | 7289002  | 486983  | 490.5     |
|                    | 39 | 487168   | 7288821 | 488.6     |
|                    | 40 | 7288803  | 487237  | 488.5     |
|                    | 41 | 7288788  | 487290  | 488.5     |
|                    | 42 | 7288717  | 487298  | 488.3     |
|                    | 43 | 7288626  | 487308  | 487.5     |
|                    | 44 | 7288551  | 487308  | 487.6     |
|                    | 45 | 7288456  | 487307  | 487.7     |
|                    | 46 | 7288436  | 487283  | 487.8     |
|                    | 47 | 7288522  | 487141  | 487.9     |
|                    | 48 | 7288590  | 487107  | 487.8     |
|                    | 49 | 7288649  | 487098  | 487.9     |
|                    | 50 | 7288704  | 487107  | 488.3     |
|                    | 51 | 7288745  | 487097  | 488.5     |

**APPROVED**  
By Alvin Tong, P.Eng. at 4:25 pm, Jul 06, 2020

B

Stantec  
111 Dunsmuir Street  
Vancouver, BC, V6B 6A3  
Tel: +1(604) 696-8000  
www.stantec.com

LEGEND

- 2m EXISTING GROUND CONTOURS
- 0.5m EXISTING GROUND CONTOURS
- 2m DESIGN CONTOURS
- 0.5m DESIGN CONTOURS
- CHANNEL BOUNDARY
- DESIGN COVER EXTENT. TIE TO EXISTING GROUND. SEE NOTE 4.
- BATHYMETRY SURVEY WATERLINE (JUNE 2019)
- NO DATA. SEE NOTE 3
- SEE NOTE 5
- WATER COVERED AREA

NOTE

- EXISTING TOPOGRAPHIC CONTOURS AND WATER COVERED AREAS DELINEATED FROM LIDAR SURVEY COMPLETED AUGUST 2019 AND BATHYMETRY SURVEYS COMPLETED JUNE 2019.
- COORDINATES ARE PRESENTED IN NAD83 UTM, ZONE 12.
- TOPOGRAPHY AND BATHYMETRY SURVEYS NOT AVAILABLE FOR THESE AREAS DUE TO PONDED WATER. THE CONTRACTOR SHALL REMOVE ANY PONDED WATER PRIOR TO PLACEMENT OF COVER FILL IN THESE AREAS. THE CONTRACTOR SHALL ALSO ADJUST THE COVER FILL SURFACE ELEVATIONS AND/OR SUBEXCAVATE IN THESE AREAS TO ENSURE A MINIMUM 1.0M FILL COVER OVER TAILINGS AS DIRECTED BY THE RESIDENT GEOTECHNICAL ENGINEER.
- OUTLINE OF FILL COVER PLACEMENT IS APPROXIMATE BASED ON INTERPRETATION OF PREVIOUS SURVEYS AND AERIAL PHOTOGRAPHY. THE CONTRACTOR SHALL CONFIRM THE LOCATION AND MINIMUM THICKNESS OF FILL COVER ALONG THE TIE IN LIMITS.
- COVER TIE IN WILL BE FIELD FITTED UNDER DIRECTION OF THE RESIDENT GEOTECHNICAL ENGINEER DEPENDING ON ACTUAL FIELD CONDITION AND TOPOGRAPHIC INFORMATION.

Client  
LUPIN MINES INC.

Project  
LUPIN MINE CLOSURE

Title  
CELL 3 CLOSURE  
PLAN VIEW


Scale: 1:3000 Drawing No. 006

|      |        |       |            |
|------|--------|-------|------------|
| SS   | PK     | AT    | 2020.05.05 |
| Dwn. | Desgn. | Chkd. | YYYY.MM.DD |


Revision: B

Project No.: 129500081

c:\data\129500081\disc\drafting\05\_tca structures detailed design\plan view-cell 3



CHANNEL CENTERLINE PROFILE (STA 0+350 TO STA 0+760)  
VERTICAL EXAGGERATION: 10X



CHANNEL CENTERLINE PROFILE (STA 0+00 TO STA 0+350)  
VERTICAL EXAGGERATION: 10X

**APPROVED**  
By Alvin Tong, P.Eng. at 4:25 pm, Jul 06, 2020

*Alvin Tong*



Stantec  
111 Dunsmuir Street  
Vancouver, BC, V6B 6A3  
Tel: +1(604) 696-8000  
www.stantec.com

LEGEND  
--- EXISTING GROUND PROFILE  
— DESIGN COVER  
--- NO DATA (SEE NOTE 3)  
ESKER COVER FILL MATERIAL  
OUTFLOW CHANNEL MATERIAL.  
SEE DRAWING 005  
SEE NOTE 4

NOTE  
1. EXISTING TOPOGRAPHIC CONTOURS AND WATER COVERED AREAS DELINEATED FROM LIDAR SURVEY COMPLETED AUGUST 2019 AND BATHYMETRY SURVEYS COMPLETED JUNE 2019.  
2. COORDINATES ARE PRESENTED IN NAD83 UTM, ZONE 12.  
3. TOPOGRAPHY AND BATHYMETRY SURVEYS NOT AVAILABLE FOR THESE AREAS DUE TO PONDED WATER. THE CONTRACTOR SHALL REMOVE ANY PONDED WATER PRIOR TO PLACEMENT OF COVER FILL IN THESE AREAS. THE CONTRACTOR SHALL ALSO ADJUST THE COVER FILL SURFACE ELEVATIONS AND/OR SUBEXCAVATE IN THESE AREAS TO ENSURE A MINIMUM 1.0m FILL COVER OVER TAILINGS AS DIRECTED BY THE RESIDENT GEOTECHNICAL ENGINEER.  
4. OUTLINE OF FILL COVER PLACEMENT IS APPROXIMATE BASED ON INTERPRETATION OF PREVIOUS SURVEYS AND AERIAL PHOTOGRAPHY. THE CONTRACTOR SHALL CONFIRM THE LOCATION AND MINIMUM THICKNESS OF FILL COVER ALONG THE TIE IN LIMITS.  
5. DEPTH OF COVER BELOW EXISTING GROUND HAS NOT BEEN CONFIRMED. THE CONTRACTOR SHALL CONDUCT SUBEXACATION AND BACKFILL ACTIVITIES IN THESE AREAS AS DIRECTED BY THE RESIDENT GEOTECHNICAL ENGINEER TO ENSURE A MINIMUM 1.0m FILL COVER OVER TAILINGS.

Client  
LUPIN MINES INC.  
Project  
LUPIN MINE CLOSURE


Title  
CELL 3 CLOSURE  
PROFILE ALONG CHANNEL CENTERLINE  
Scale:- Drawing No. 007  
SS PK AT 2020.04.29  
Dwn. Dsgn. Chkd. YYYY.MM.DD Revision: A  
Project No.: 129500081

2020.04.29 1:57:50 PM


ORIGINAL SHEET - ANSI B (11"x17")

c:\data\129500081\disc\drafting\05\_tca structures detailed design\plan view-cell 3

2020.05.08 12:01:18 PM



CROSS-SECTION E-E  
VERTICAL EXAGGERATION: 10X



CROSS-SECTION F-F  
VERTICAL EXAGGERATION: 10X

**APPROVED**  
By Alvin Tong, P.Eng. at 4:25 pm, Jul 06, 2020

*Alvin Tong*



Stantec  
111 Dunsmuir Street  
Vancouver, BC, V6B 6A3  
Tel: +1(604) 696-8000  
www.stantec.com

- LEGEND
- EXISTING GROUND PROFILE
  - DESIGN COVER
  - - - - - DRAINAGE CHANNEL CENTERLINE
  - NO DATA (SEE NOTE 3)
  - ☁ SEE NOTE 6
  - ▨ ESKER COVER FILL MATERIAL

- NOTE
- EXISTING TOPOGRAPHIC CONTOURS AND WATER COVERED AREAS DELINEATED FROM LIDAR SURVEY COMPLETED AUGUST 2019 AND BATHYMETRY SURVEYS COMPLETED JUNE 2019.
  - COORDINATES ARE PRESENTED IN NAD83 UTM, ZONE 12.
  - TOPOGRAPHY AND BATHYMETRY SURVEYS NOT AVAILABLE FOR THESE AREAS DUE TO PONDED WATER. THE CONTRACTOR SHALL REMOVE ANY PONDED WATER PRIOR TO PLACEMENT OF COVER FILL IN THESE AREAS. THE CONTRACTOR SHALL ALSO ADJUST THE COVER FILL SURFACE ELEVATIONS AND/OR SUBEXCAVATE IN THESE AREAS TO ENSURE A MINIMUM 1.0m FILL COVER OVER TAILINGS AS DIRECTED BY THE RESIDENT GEOTECHNICAL ENGINEER.
  - OUTLINE OF FILL COVER PLACEMENT IS APPROXIMATE BASED ON INTERPRETATION OF PREVIOUS SURVEYS AND AERIAL PHOTOGRAPHY. THE CONTRACTOR SHALL CONFIRM THE LOCATION AND MINIMUM THICKNESS OF FILL COVER ALONG THE TIE IN LIMITS.
  - DEPTH OF COVER BELOW EXISTING GROUND HAS NOT BEEN CONFIRMED. THE CONTRACTOR SHALL CONDUCT SUBEXCAVATION AND BACKFILL ACTIVITIES IN THESE AREAS AS DIRECTED BY THE RESIDENT GEOTECHNICAL ENGINEER TO ENSURE A MINIMUM 1.0m FILL COVER OVER TAILINGS.
  - COVER TIE IN WILL BE FIELD FITTED UNDER DIRECTION OF THE RESIDENT GEOTECHNICAL ENGINEER DEPENDING ON ACTUAL FIELD CONDITION AND TOPOGRAPHIC INFORMATION.
  - ILLUSTRATES APPROXIMATE FLOW DEPTH FOR 1-IN-100-YEAR, 24-HOUR STORM EVENT.

Client  
**LUPIN MINES INC.**

Project  
**LUPIN MINE CLOSURE**


Title  
**CELL 3 CLOSURE**  
**CROSS-SECTIONS**

Scale:- Drawing No. 008

|      |        |       |            |
|------|--------|-------|------------|
| SS   | PK     | AT    | 2020.05.08 |
| Dwn. | Desgn. | Chkd. | YYYY.MM.DD |


Project No.: 129500081 Revision: B





PLAN VIEW - OUTFLOW CHANNEL

SCALE 1:750




PROFILE - OUTFLOW CHANNEL

VERTICAL EXAGGERATION: 2.5X

| POINT NUMBER | NORTHING | EASTING | ELEVATION |
|--------------|----------|---------|-----------|
| 18           | 7288604  | 487270  | 487.0     |
| 19           | 7288592  | 487270  | 487.0     |
| 20           | 7288608  | 487290  | 487.5     |
| 21           | 7288599  | 487290  | 487.0     |
| 22           | 7288591  | 487290  | 487.5     |
| 23           | 7288610  | 487295  | 488.0     |


| POINT NUMBER | NORTHING | EASTING | ELEVATION |
|--------------|----------|---------|-----------|
| 24           | 7288588  | 487295  | 488.0     |
| 25           | 7288599  | 487312  | 487.0     |
| 27           | 7288600  | 487330  | 486.0     |
| 37           | 7288601  | 487353  | 485.0     |
| 38           | 7288597  | 487255  | 487.0     |

OUTFLOW WORK POINTS




CROSS SECTION G-G

N.T.S



CROSS-SECTION H-H

N.T.S



CROSS-SECTION I-I

N.T.S

**APPROVED**

By Alvin Tong, P.Eng. at 4:26 pm, Jul 06, 2020

NOTE

- EXISTING TOPOGRAPHIC CONTOURS AND WATER COVERED AREAS DELINEATED FROM LIDAR SURVEY COMPLETED AUGUST 2019 AND BATHYMETRY SURVEYS COMPLETED JUNE 2019.
- COORDINATES ARE PRESENTED IN NAD83 UTM, ZONE 12.
- CLOSURE ELEVATION WATER EXTENT SHOWN IS APPROXIMATE. RIPRAP SHALL EXTEND AT LEAST TO THE EDGE OF WATER.
- ROCK PLACEMENT AND TIE IN TO EXISTING TOPOGRAPHY SHALL BE FIELD FITTED UNDER THE DIRECTION OF THE RESIDENT GEOTECHNICAL ENGINEER AND MAY BE ADJUSTED DEPENDING ON TOPOGRAPHY, GEOLOGY, AND/OR AVAILABILITY OF LARGER ROCK MATERIALS. REFER TO CONSTRUCTION SPECIFICATIONS DRAWING 001 TABLE 2.
- COVER TIE IN WILL BE FIELD FITTED UNDER DIRECTION OF THE RESIDENT GEOTECHNICAL ENGINEER DEPENDING ON ACTUAL FIELD CONDITION AND TOPOGRAPHIC INFORMATION.
- TOPOGRAPHY AND BATHYMETRY SURVEYS NOT AVAILABLE FOR THESE AREAS DUE TO PONDED WATER. THE CONTRACTOR SHALL REMOVE ANY PONDED WATER PRIOR TO PLACEMENT OF COVER FILL IN THESE AREAS. THE CONTRACTOR SHALL ALSO ADJUST THE COVER FILL SURFACE ELEVATIONS AND/OR SUBEXCAVATE IN THESE AREAS TO ENSURE A MINIMUM 1.0m FILL COVER OVER TAILINGS AS DIRECTED BY THE RESIDENT GEOTECHNICAL ENGINEER.
- ILLUSTRATES APPROXIMATE FLOW DEPTH AND FLOW RATE (Q) FOR 1-IN-100-YEAR, 24-HOUR STORM EVENT.



Stantec  
111 Dunsmir Street  
Vancouver, BC, V6B 6A3  
Tel: +1(604) 696-8000  
www.stantec.com

LEGEND

- 2m EXISTING GROUND CONTOURS
- 0.5m EXISTING GROUND CONTOURS
- 2m DESIGN CONTOURS
- 0.5m DESIGN CONTOURS
- APPROXIMATE OUTFLOW CHANNEL WORKS EXTENT
- GEOTEXTILE
- NO DATA. SEE NOTE 6.
- WATERLINE
- SEE NOTE 5
- WATER COVERED AREA
- ESKER COVER FILL MATERIAL
- RIPRAP-CALSS 1
- RIPRAP-CALSS 1 EXTENDED PLACEMENT. (SEE NOTE 3)

Client

LUPIN MINES INC.

Project

LUPIN MINE CLOSURE

Title


CELL 3 CLOSURE  
OUTFLOW CHANNEL

Scale:- Drawing No. 009

SS PK AT 2020.05.08  
Dwn. Dsgn. Chkd. YYYY.MM.DD  
Project No.: 129500081 Revision: A

c:\data\12950008\disc\drafting\05\_1ca\_structures detailed design\plan view-m dam

2020.05.13 3:42:49 PM



NOTE

1. EXISTING TOPOGRAPHIC CONTOURS AND WATER COVERED AREAS DELINEATED FROM LIDAR SURVEY COMPLETED AUGUST 2019 AND BATHYMETRY SURVEYS COMPLETED JUNE 2019.
2. COORDINATES ARE PRESENTED IN NAD83 UTM, ZONE 12.
3. TOPOGRAPHY AND BATHYMETRY SURVEYS NOT AVAILABLE FOR THESE AREAS DUE TO PONDED WATER. THE CONTRACTOR SHALL REMOVE ANY PONDED WATER PRIOR TO PLACEMENT OF FILL IN THESE AREAS.
4. REFER TO DRAWING 001 FOR GENERAL MATERIAL FILL SPECIFICATION AND FOUNDATION PREPARATION.
5. THE RESLOPED DOWNSTREAM FACE MUST BE 2.1H:1V OR FLATTER, MEASURED FROM THE EXISTING CREST.
6. ANY LOOSE AND OVERHANG MATERIAL MUST BE REMOVED TO THE APPROVED OF SITE ENGINEERING REPRESENTATIVE. THE REMOVED SAND AND GRAVEL MATERIAL CAN BE USED ELSEWHERE ALONG THE RESLOPE SUBJECT TO ENGINEER'S APPROVAL.
7. ALL SAND AND GRAVEL (ESKER) MATERIAL TO BE PLACED WITHIN THE RESLOPE MUST BE TRACK COMPACTED, SUBJECTED TO EQUIPMENT SIZE AND OPERATION PATTERN AS APPROVED BY THE ENGINEER.
8. ALL EROSION GULLIES ALONG THE DOWNSTREAM CREST INCURRED PREVIOUSLY MUST BE REPAIRED TO PROVIDE A UNIFORMLY ALIGNED CREST LINE. THE REPAIRED SHALL BE DONE WITH COMPACTED SAND AND GRAVEL (ESKER) MATERIAL, WITH ALL LOOSE OR OVERHANG MATERIAL MUST BE REMOVED, TO THE APPROVED OF THE ENGINEER.
9. THE FINAL SURFACE SHOULD BE AN EVEN, FIRM, SMOOTH SURFACE THAT MEETS THE SLOPE REQUIREMENT ABOVE AT THE DOWNSTREAM FACE OF THE DAM.

WORK POINTS DESCRIPTION

| WORK POINTS | NORTHING | EASTING | ELEVATION |
|-------------|----------|---------|-----------|
| 1           | 7289813  | 487376  | 488.5     |
| 2           | 7289840  | 487346  | 488.4     |
| 3           | 7289868  | 487318  | 488.4     |
| 4           | 7289897  | 487291  | 487.9     |
| 5           | 7289925  | 487262  | 487.5     |
| 6           | 7289952  | 487233  | 488       |
| 7           | 7289978  | 487202  | 487.7     |
| 8           | 7290006  | 487174  | 487.8     |

| WORK POINTS | NORTHING | EASTING | ELEVATION |
|-------------|----------|---------|-----------|
| 9           | 7290039  | 487151  | 487.8     |
| 10          | 7290073  | 487130  | 488       |
| 11          | 7290108  | 487109  | 488.5     |
| 12          | 7290142  | 487089  | 488.1     |
| 13          | 7290176  | 487068  | 488       |
| 14          | 7290209  | 487044  | 488       |
| 15          | 7290234  | 487028  | 487.7     |

APPROVED

By Alvin Tong, P.Eng. at 4:26 pm, Jul 06, 2020



Stantec  
111 Dunsmir Street  
Vancouver, BC, V6B 6A3  
Tel: +1(604) 696-8000  
www.stantec.com

LEGEND

- 2m EXISTING GROUND CONTOURS
- 0.5m EXISTING GROUND CONTOURS
- 2m DESIGN CONTOURS
- 0.5m DESIGN CONTOURS
- DESIGN M DAM — RESLOPE
- - - - SECTION LINES
- BATHYMETRY SURVEY WATERLINE (JUNE 2019)
- NO DATA. SEE NOTE 3
- WATER COVERED AREA

Client  
LUPIN MINES INC.

Project  
LUPIN MINE CLOSURE

Title  
M DAM REPAIR  
PLAN VIEW

Scale: 1:2000 Drawing No. 010


|      |       |       |            |
|------|-------|-------|------------|
| SS   | PK    | AT    | 2020.05.13 |
| Dwn. | Dsgn. | Chkd. | YYYY.MM.DD |

Revision: A


Project No.: 129500081

c:\data\12950008\disc\drafting\05\_1ca structures detailed design\plan view-m dam


2020.05.13 3:43:52 PM




SECTION 0+040




SECTION 0+080




SECTION 0+120




SECTION 0+160




SECTION 0+200




SECTION 0+240




SECTION 0+280




SECTION 0+400




SECTION 0+440



SECTION 0+480



SECTION 0+520



SECTION 0+560

**APPROVED**  
By Alvin Tong, P.Eng. at 4:27 pm, Jul 06, 2020

*Alvin Tong*

**Stantec**  
Stantec  
111 Dunsmir Street  
Vancouver, BC, V6B 6A3  
Tel: +1(604) 696-8000  
www.stantec.com

LEGEND  
----- EXISTING GROUND  
——— DESIGN DAM  
----- CELL 5 DESIGN COVER  
COMPACTED FILL  
—○— NO DATA. SEE NOTE 3  
ESKER COVER FILL MATERIAL

NOTE  
1. EXISTING TOPOGRAPHIC CONTOURS AND WATER COVERED AREAS DELINEATED FROM LIDAR SURVEY COMPLETED AUGUST 2019 AND BATHYMETRY SURVEYS COMPLETED JUNE 2019.  
2. COORDINATES ARE PRESENTED IN NAD83 UTM, ZONE 12.  
3. TOPOGRAPHY AND BATHYMETRY SURVEYS NOT AVAILABLE FOR THESE AREAS DUE TO PONDED WATER. THE CONTRACTOR SHALL REMOVE ANY PONDED WATER PRIOR TO PLACEMENT OF FILL IN THESE AREAS.

Client  
LUPIN MINES INC.  
  
Project  
LUPIN MINE CLOSURE



Title  
M DAM REPAIR  
CROSS SECTIONS - 1

Scale: 1:500 Drawing No. 011  
SS PK AT 2020.05.13  
Dwn. Dsgn. Chkd. YYYY.MM.DD Revision: A  
Project No.: 129500081



\\ca0200-ppfs01\shared\_projects\129500081\disc\drafting\05\_tca\_structures\_detailed\_design\plan view-m dam

2020.05.13 4:51:57 PM



**APPROVED**  
By Alvin Tong, P.Eng. at 4:28 pm, Jul 06, 2020

*Alvin Tong*



Stantec  
111 Dunsmir Street  
Vancouver, BC, V6B 6A3  
Tel: +1(604) 696-8000  
www.stantec.com

LEGEND  
--- EXISTING GROUND  
— DESIGN DAM  
..... WATER LEVEL  
- - - - - CELL 5 DESIGN COVER  
[Pattern] COMPACTED FILL  
—○— NO DATA. SEE NOTE 3  
[Pattern] ESKER COVER FILL MATERIAL

NOTE

1. EXISTING TOPOGRAPHIC CONTOURS AND WATER COVERED AREAS DELINEATED FROM LIDAR SURVEY COMPLETED AUGUST 2019 AND BATHYMETRY SURVEYS COMPLETED JUNE 2019.
2. COORDINATES ARE PRESENTED IN NAD83 UTM, ZONE 12.
3. TOPOGRAPHY AND BATHYMETRY SURVEYS NOT AVAILABLE FOR THESE AREAS DUE TO PONDED WATER. THE CONTRACTOR SHALL REMOVE ANY PONDED WATER PRIOR TO PLACEMENT OF FILL IN THESE AREAS.

Client  
LUPIN MINES INC.


Project  
LUPIN MINE CLOSURE

Title  
M DAM REPAIR  
CROSS SECTIONS - 2

|                        |       |       |            |                 |  |
|------------------------|-------|-------|------------|-----------------|--|
| Scale: 1:500           |       |       |            | Drawing No. 012 |  |
| SS                     | PK    | AT    | 2020.05.13 |                 |  |
| Dwn.                   | Dsgn. | Chkd. | YYYY.MM.DD | Revision: A     |  |
| Project No.: 129500081 |       |       |            |                 |  |

c:\data\12950008\disc\drafting\05\_1ca structures detailed design\plan view-k dam

2020.05.22 1:00:19 PM



NOTE:

1. EXISTING TOPOGRAPHIC CONTOURS AND WATER COVERED AREAS DELINEATED FROM LIDAR SURVEY COMPLETED AUGUST 2019 AND BATHYMETRY SURVEYS COMPLETED JUNE 2019.
2. COORDINATES ARE PRESENTED IN NAD83 UTM, ZONE 12.
3. TOPOGRAPHY AND BATHYMETRY SURVEYS NOT AVAILABLE FOR THESE AREAS DUE TO PONDED WATER. THE CONTRACTOR SHALL REMOVE ANY PONDED WATER PRIOR TO PLACEMENT OF FILL IN THESE AREAS.
4. REFER TO DRAWING 001 FOR GENERAL MATERIAL FILL SPECIFICATION AND FOUNDATION PREPARATION.
5. THE RESLOPED DOWNSTREAM FACE MUST BE 2.1H:1V OR FLATTER, MEASURED FROM THE EXISTING CREST.
6. THE DOWNSTREAM TOE AND THE DAM CREST WERE ERODED BASED ON 2019 OBSERVATION. THE EXTENT OF THE CREST EROSIONS AND OVERHANG WILL BE CONFIRMED BY ENGINEER REPRESENTATIVE. ALL ERODED SECTION OF THE DAM MUST BE REPLACED WITH SUITABLE SAND AND GRAVEL (ESKER) MATERIAL ACCORDING TO THE SPECIFICATIONS AND NOTE HEREIN.
7. ANY LOOSE AND OVERHANG MATERIAL MUST BE REMOVED TO THE APPROVED OF SITE ENGINEERING REPRESENTATIVE. THE REMOVED SAND AND GRAVEL MATERIAL CAN BE USED ELSEWHERE ALONG THE RESLOPE SUBJECT TO ENGINEER'S APPROVAL.
8. ALL SAND AND GRAVEL (ESKER) MATERIAL TO BE PLACED WITHIN THE RESLOPE MUST BE TRACK COMPACTED, SUBJECT TO EQUIPMENT SIZE AND OPERATION PATTERN AS APPROVED BY THE ENGINEER.
9. ALL EROSION GULLIES ALONG THE DOWNSTREAM CREST INCURRED PREVIOUSLY MUST BE REPAIRED TO PROVIDE A UNIFORMLY ALIGNED CREST LINE. THE REPAIRED SHALL BE DONE WITH COMPACTED SAND AND GRAVEL (ESKER) MATERIAL, WITH ALL LOOSE OR OVERHANG MATERIAL MUST BE REMOVED, TO THE APPROVED OF THE ENGINEER.
10. THE FINAL SURFACE SHOULD BE AN EVEN, FIRM, SMOOTH SURFACE THAT MEETS THE SLOPE REQUIREMENT ABOVE AT THE DOWNSTREAM FACE OF THE DAM.

WORK POINTS DESCRIPTIONS

| WORK POINTS | NORTHING | EASTING | ELEVATION |
|-------------|----------|---------|-----------|
| 1           | 7289015  | 486648  | 490.3     |
| 2           | 7289031  | 486684  | 490.0     |
| 3           | 7289048  | 486720  | 490.0     |
| 4           | 7289066  | 486756  | 490.0     |
| 5           | 7289086  | 486791  | 490.0     |
| 6           | 7289106  | 486826  | 489.7     |
| 7           | 7289123  | 486861  | 490.0     |
| 8           | 7289144  | 486896  | 489.9     |
| 9           | 7289163  | 486931  | 489.9     |

| WORK POINTS | NORTHING | EASTING | ELEVATION |
|-------------|----------|---------|-----------|
| 10          | 7289183  | 486966  | 490.0     |
| 11          | 7289202  | 487001  | 490.1     |
| 12          | 7289222  | 487035  | 490.1     |
| 13          | 7289241  | 487070  | 490.2     |
| 14          | 7289262  | 487104  | 490.2     |
| 15          | 7289281  | 487140  | 490.3     |
| 16          | 7289301  | 487174  | 491.0     |
| 17          | 7289315  | 487189  | 491.6     |
| 18          | 7289328  | 487195  | 491.9     |

**APPROVED**

By Alvin Tong, P.Eng. at 4:28 pm, Jul 06, 2020

*Alvin Tong*



Stantec  
111 Dunsmir Street  
Vancouver, BC, V6B 6A3  
Tel: +1(604) 696-8000  
www.stantec.com

LEGEND

- 2m EXISTING GROUND CONTOURS
- 0.5m EXISTING GROUND CONTOURS
- 2m DESIGN CONTOURS
- 0.5m DESIGN CONTOURS
- DESIGN K DAM - RESLOPE
- SECTION LINES
- BATHYMETRY SURVEY WATERLINE (JUNE 2019)
- EXISTING WATER MANAGEMENT FEATURES (APPROXIMATE)



APPROXIMATE TOE UNDERCUT EXTENT  
(SEE NOTE 6)



WATER COVERED AREA

Client  
LUPIN MINES INC.

Project  
LUPIN MINE CLOSURE

Title  
K DAM REPAIR  
PLAN VIEW

Scale: 1:2000 Drawing No. 013


SS PK AT 2020.05.22

Dwn Dgn Chkd YYYY.MM.DD Revision: A


Project No.: 129500081

c:\data\12950008\disc\drafting\05\_tca structures detailed design\plan view-k dam


2020.05.22 1:03:10 PM




SECTION 0+000




SECTION 0+040




SECTION 0+080




SECTION 0+120




SECTION 0+160




SECTION 0+200




SECTION 0+240




SECTION 0+360




SECTION 0+400




SECTION 0+440




SECTION 0+480




SECTION 0+520




SECTION 0+560



SECTION 0+600



SECTION 0+620



SECTION 0+635



Stantec  
111 Dunsmir Street  
Vancouver, BC, V6B 6A3  
Tel: +1(604) 696-8000  
www.stantec.com

LEGEND

- EXISTING GROUND
- DESIGN DAM
- WATER LEVEL
- CELL 5 DESIGN COVER
- COMPACTED FILL
- APPROXIMATE TOE UNDERCUT EXTENT (SEE NOTE 4)

NOTE

- EXISTING TOPOGRAPHIC CONTOURS AND WATER COVERED AREAS DELINEATED FROM LIDAR SURVEY COMPLETED AUGUST 2019 AND BATHYMETRY SURVEYS COMPLETED JUNE 2019.
- COORDINATES ARE PRESENTED IN NAD83 UTM, ZONE 12.
- TOPOGRAPHY AND BATHYMETRY SURVEYS NOT AVAILABLE FOR THESE AREAS DUE TO PONDED WATER. THE CONTRACTOR SHALL REMOVE ANY PONDED WATER PRIOR TO PLACEMENT OF FILL IN THESE AREAS.
- THE DOWNSTREAM TOE AND THE DAM CREST WERE ERODED BASED ON 2019 OBSERVATION. THE EXTENT OF THE CREST EROSIONS AND OVERHANG WILL BE CONFIRMED BY ENGINEER REPRESENTATIVE. ALL ERODED SECTION OF THE DAM MUST BE REPLACED WITH SUITABLE SAND AND GRAVEL (ESKER) MATERIAL ACCORDING TO THE SPECIFICATIONS AND NOTE HEREIN.

Client

LUPIN MINES INC.

Project

LUPIN MINE CLOSURE

Title

K DAM REPAIR  
CROSS SECTIONS - 1

Scale: 1:500 Drawing No. 014

SS PK AT 2020.05.22  
Dwn. Dsgn. Chkd. YYYY.MM.DD Revision: A

Project No.: 129500081



**APPROVED**

By Alvin Tong, P.Eng. at 4:29 pm, Jul 06, 2020



c:\data\12950008\disc\drafting\05\_tca structures detailed design\plan view-k dam

2020.05.22 1:04:47 PM



**APPROVED**  
By Alvin Tong, P.Eng. at 4:29 pm, Jul 06, 2020

*Alvin Tong*



Stantec  
111 Dunsmir Street  
Vancouver, BC, V6B 6A3  
Tel: +1(604) 696-8000  
www.stantec.com

- LEGEND
- EXISTING GROUND
  - DESIGN DAM
  - ..... WATER LEVEL
  - CELL 5 DESIGN COVER
  - COMPACTED FILL
  - APPROXIMATE TOE UNDERCUT EXTENT (SEE NOTE 4)

- NOTE
- EXISTING TOPOGRAPHIC CONTOURS AND WATER COVERED AREAS DELINEATED FROM LIDAR SURVEY COMPLETED AUGUST 2019 AND BATHYMETRY SURVEYS COMPLETED JUNE 2019.
  - COORDINATES ARE PRESENTED IN NAD83 UTM, ZONE 12.
  - TOPOGRAPHY AND BATHYMETRY SURVEYS NOT AVAILABLE FOR THESE AREAS DUE TO PONDED WATER. THE CONTRACTOR SHALL REMOVE ANY PONDED WATER PRIOR TO PLACEMENT OF FILL IN THESE AREAS.
  - THE DOWNSTREAM TOE AND THE DAM CREST WERE ERODED BASED ON 2019 OBSERVATION. THE EXTENT OF THE CREST EROSIONS AND OVERHANG WILL BE CONFIRMED BY ENGINEER REPRESENTATIVE. ALL ERODED SECTION OF THE DAM MUST BE REPLACED WITH SUITABLE SAND AND GRAVEL (ESKER) MATERIAL ACCORDING TO THE SPECIFICATIONS AND NOTE HEREIN.

Client  
LUPIN MINES INC.

Project  
LUPIN MINE CLOSURE

Title  
K DAM REPAIR  
CROSS SECTIONS - 2

Scale: 1:250 Drawing No. 015

|      |       |       |            |
|------|-------|-------|------------|
| SS   | PK    | AT    | 2020.05.22 |
| Dwn. | Dsgn. | Chkd. | YYYY.MM.DD |

Revision: A

Project No.: 129500081