

Golder Associates Ltd.

500 – 4260 Still Creek Drive
Burnaby, British Columbia, Canada V5C 6C6
Telephone 604 296-6623
Fax 604 298-5253



**FINAL REPORT
DETAILED DESIGN OF DEWATERING DIKES
MEADOWBANK GOLD PROJECT
VOLUME 3**

Submitted to:

Meadowbank Mining Corporation
Suite 950, One Bentall Center
505 Burrard Street
Vancouver, BC
V7X 1M4

DISTRIBUTION:

- 1 Copy Dr. N. Morgenstern
- 3 Copies - Meadowbank Mining Corporation
- 3 Copies - Golder Associates Ltd.

March 13, 2007

06-1413-081/6000
Doc. No. 342 Ver. 0



APPENDIX VII
FEASIBILITY LEVEL DESIGN REPORT

The feasibility-level design for the dewatering dikes at the Meadowbank Gold Project was presented in the report:

Golder, 2003. Design of Dikes with Soil-Bentonite Cutoff Wall – Meadowbank Gold Project. Report. Golder Associates Ltd. October 2003.

Key differences between the feasibility level design and the final design are noted as follows.

- Dike alignments updated with 2006 bathymetry. The main differences include:
 - removal of a dogleg and causeway in the East Dike, and
 - design criteria for setback (distance from downstream dike toe to pit crest) changed from 80 m to 70 m. Change in setback based on review of pit wall stability by Golder (2007a).
- Granular filter changed from one zone to two zone.
- Cutoff changed from soil bentonite cutoff only to soil cement bentonite cutoff and jet grout cutoff to increase erosion resistance in deeper portions of the dikes. Selection of cutoff type based on hydraulic gradient across the cutoff.
- Bedrock grouting program added for near surface bedrock.
- Cutoff-bedrock contact grouting program added – removes the reliance on a key of the cutoff into bedrock.
- Instrumentation program added.
- East Dike crest elevation raised to 136.1 masl to provide additional freeboard across the dike at closure.
- The mine plan was changed requiring Goose Dike construction prior to Year 2 of the mine life, rather than Year 5.
- Minor changes in material parameters reflect updated laboratory test results.

Golder Associates Ltd.

500 – 4260 Still Creek Drive
Burnaby, British Columbia, Canada V5C 6C6
Telephone (604) 296-4200
Fax (604) 298-5253



REPORT ON

**DESIGN OF DIKES WITH
SOIL- BENTONITE CUTOFF WALL
MEADOWBANK GOLD PROJECT**

Submitted to:

Cumberland Resources Ltd.
Suite 950, One Bentall Centre
505 Burrard Street
Vancouver, BC
V7X 1M4

DISTRIBUTION:

- 3 Copies - Cumberland Resources Ltd.
- 2 Copies - Golder Associates Ltd.

October 23, 2003

03-1413-427/4200



EXECUTIVE SUMMARY

This report presents a basic engineering design of the proposed dikes at the Meadowbank Gold Project near Baker Lake, in Nunavut. The proposed dikes are required to allow mining of the proposed open pits at the Third Portage and North Portage Deposits (including the Connector Zone and Bay Zone), and the Goose Island Deposit.

The three dikes included in this report are:

- Second Portage dike (including a causeway) – to be constructed prior to mill startup
- Bay Zone dike – to be constructed prior to mill startup
- Goose Island dike – to be constructed in Year 5 of the mine life.

The typical dike section comprises two rockfill embankments with a till core, a filter zone and a soil-bentonite cutoff wall excavated to the underlying bedrock. The causeway section will consist of run-of-mine rockfill. The dike crest will be surfaced with material suitable as haul road running course.

The rockfill to be used for construction will initially come from pre-stripping operations and through the development of a starter pit at the Third Portage Deposit. Quantity estimates indicate that between 360,000 m³ and 420,000 m³ of rockfill and between 80,000 m³ and 110,000 m³ of till will be required for the dikes prior to startup.

Based on current materials balance calculations, sufficient quantities of suitable rockfill and till borrow materials will be available from pre-mining activities. The material for the till core will be derived from pre-stripping activities at the North Portage and Third Portage Deposits.

Similarly, sufficient quantities of rockfill and till will be available from ongoing mining activities in Year 5 to build the Goose Island dike.

The construction quantities are sensitive to the sideslopes that will be achieved on the rockfill embankments. These slopes are likely to be in the range of 1.5H:1V to 2.0H:1V but in some areas could be as flat as 2.5H:1V.

Slope stability analyses show that the dikes will be stable under static and earthquake load conditions.

Seepage modeling indicates that the total seepage through all of the dikes will be in the range of approximately 2.4 to 48.3 L/s. This value varies depending on potential cracking in the soil-bentonite cutoff wall and/or a potential gap in the cutoff wall at the bedrock contact.

Cracks through the cutoff wall in the section through the overburden would result in the largest increase in seepage through the cutoff wall. The increase is in the range of one to two orders of magnitude more than a wall with no cracks or defects in the overburden section. Cracks within the till core section have a negligible effect on seepage.

A gap in the soil-bentonite cutoff wall at the bedrock contact would result in an increase in seepage of approximately one order of magnitude more than a wall with no gap at the bedrock contact.

For the Bay Zone and Second Portage dikes, the soil-bentonite cutoff wall trench will be excavated to depths less than 12 m. This can be achieved with standard long-reach excavation equipment.

For the Goose Island dike, the soil-bentonite cutoff wall trench will be excavated to depths greater than 12 m. This will require custom-made long-reach excavators or booms.

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
1.0 INTRODUCTION.....	1
1.1 Mining.....	1
2.0 PREVIOUS DIKE DESIGN STUDIES	2
3.0 GENERAL SITE CONDITIONS.....	3
3.1 Topography and Lake Bathymetry	3
3.2 Surficial Geology	3
3.3 Permafrost.....	4
3.4 Climate	4
3.5 Seismicity	5
4.0 DESIGN BASIS AND CRITERIA.....	7
5.0 PROPOSED DIKE AND CAUSEWAY SECTIONS	8
6.0 GEOTECHNICAL ANALYSES	10
6.1 Slope Stability.....	10
6.1.1 Results of Analyses for End-of-Construction Conditions	11
6.1.2 Results of Analyses for Long-Term Static and Pseudostatic Conditions	12
6.2 Seepage	13
7.0 VOLUME ESTIMATES.....	16
7.1 Dike and Causeway Materials	16
7.2 Available Till and Rockfill Quantities.....	17
8.0 CONSTRUCTION METHODOLOGY	19
8.1 Construction of Dike Embankments	19
8.2 Construction of Soil-Bentonite Cutoff Wall	20
9.0 EXCAVATION EQUIPMENT FOR THE SOIL-BENTONITE CUTOFF WALL	21
10.0 CONSTRUCTION MATERIAL GUIDELINES.....	23
10.1 Rockfill for Embankment Shoulders	23
10.2 Till Core	24
10.3 Bentonite Slurry	24
10.4 Soil-Bentonite Backfill.....	25
11.0 CONCLUSIONS AND RECOMMENDATIONS	26
12.0 CLOSING REMARKS	28
REFERENCES	29

LIST OF TABLES

Table 3-1	Annual Precipitation Data 1998 – 2002
Table 3-2	Summary of Monthly Climate Data
Table 3-3	Peak Horizontal Ground Accelerations for Meadowbank Site
Table 6-1	Material Properties – Slope Stability Analyses
Table 6-2	Summary of Long-Term Slope Stability Analyses
Table 6-3	Material Properties – Seepage Analyses
Table 6-4	Seepage Fluxes through the Soil-Bentonite Cutoff Wall
Table 6-5	Seepage Flows through the Dikes
Table 7-1	Estimated Volumes of Required Fill Materials

Table 7-2	Variation of Depth of Cutoff Wall Excavation with Embankment Sideslope at Section B
Table 7-3	Estimated Volumes of Available Dike Fill Materials at Third Portage and North Portage Deposits Combined
Table 10-1	Typical Properties of a 5% Bentonite Slurry

LIST OF CHARTS

Chart 9.1:	Cutoff Wall Excavation Equipment – Bay Zone Dike
Chart 9.2:	Cutoff Wall Excavation Equipment – Second Portage Dike
Chart 9.3:	Cutoff Wall Excavation Equipment – Goose Island Dike

LIST OF FIGURES

Figure 1.1	Key Plan
Figure 1.2	Meadowbank Mine – Site Plan
Figure 1.3	Proposed Dike Alignments
Figure 3.1	Seismic Zoning Map showing the Meadowbank Project Location
Figure 5.1	Typical Dike Cross-Section – Second Portage, Goose Island and Bay Zone Dikes
Figure 5.2	Typical Cross-Section – Second Portage Causeway
Figure 5.3	Goose Island Dike – Sections
Figure 5.4	Second Portage Lake Dike and Causeway – Sections
Figure 8.1	Soil-Bentonite Cutoff Wall Construction Operation – Conceptual Layout
Figure 8.2	Soil-Bentonite Cutoff Wall Construction Operation – Conceptual Section
Figure 9.1	Second Portage and Bay Zone Dikes – Centreline Profile
Figure 9.2	Goose Island Dike – Centreline Profile
Figure 9.3	Geotechnical Boreholes – Dikes
Figure 10.1	Material Guidelines Proposed Grain Size Distribution – Till Core and Rockfill

LIST OF APPENDICES

Appendix I	Stability Analyses
Appendix II	Seepage Analyses
Appendix III	Preliminary Materials Balance
Appendix IV	Sample Excavators
Appendix V	Geotechnical Borehole Logs
Appendix VI	Seismic Risk Calculation for Meadowbank Site

1.0 INTRODUCTION

Cumberland Resources Ltd. (CRL) is currently evaluating the feasibility of developing the Meadowbank Gold Project. The project is located approximately 70 km north of the hamlet of Baker Lake in Nunavut, as shown on Figure 1.1.

The Meadowbank Gold Project consists of several gold bearing deposits within reasonably close proximity to one another. A site plan of the Meadowbank Mine is shown in Figure 1.2. The four main deposits are:

- Vault Deposit.
- Third Portage Deposit (including Bay Zone and Connector Zone).
- North Portage Deposit.
- Goose Island Deposit.

The Third Portage Deposit is located on a peninsula, and extends northward under Second Portage Lake, and southward under Third Portage Lake. The North Portage Deposit is located on the northern shore of Second Portage Lake. The Third Portage Deposit, Bay Zone, Connector Zone, and North Portage Deposit will be mined from a single pit that will extend approximately 2 km in a north-south direction, and between about 200 m and 400 m in an east-west direction.

The Goose Island Deposit lies approximately 1000 m to the south of the Third Portage Deposit, and beneath Third Portage Lake.

1.1 Mining

Mining of the deposits will be primarily a truck and shovel open pit operation. About 87% of the overall mine production will be from the open pits. Underground mining methods may be employed to extract the ore from deeper areas of the various deposits where open pit mining may no longer be appropriate.

The deposits are situated adjacent to and beneath lakes. Consequently, a series of dikes will be required to isolate the mining activities from the lakes. (see Figure 1.3). It is proposed to construct the dikes using materials available on site.

This report presents a design for the proposed dikes around the Third Portage, North Portage, and Goose Island Deposits.

2.0 PREVIOUS DIKE DESIGN STUDIES

A preliminary study identifying dike design concepts for the project was completed in 2000. The results were presented in the report titled “Review of Seepage Cutoff Alternatives Open Pit De-Watering Dikes, Meadowbank Gold Project, Nunavut Territory” by Golder Associates Ltd. and dated March 9, 2000.” In that report, Golder recommended that the design of a zoned embankment with a low-permeability core within rockfill shells constructed on the overburden materials overlying bedrock be evaluated. Based on the information available at that time, it was assumed the overburden materials would be a till having a low permeability. Subsequent geotechnical drilling investigations along the proposed dike alignments have indicated that the foundation overburden materials may be pervious. Consequently, a seepage cutoff barrier is required through the overburden materials and extending into the underlying bedrock.

3.0 GENERAL SITE CONDITIONS

Much of the following description of general site conditions is summarized from site studies carried out by Golder, or from the Project Description Report (“Meadowbank Gold Property, Project Description Report”, Cumberland Resources Ltd. March, 2003).

3.1 Topography and Lake Bathymetry

The general site area consists of low, rolling hills with numerous small lakes. The topography in the immediate vicinity of the main deposits (Third Portage, Connector Zone, North Portage, and Goose Island Deposits) is generally flat, with topographic relief on the order of 10 m to 12 m, but as high as 60 m locally. Elevations vary from about 133 m Above Sea Level (A.S.L.) along the Third and Second Portage Lake shorelines, and up to maximum elevations of approximately 200 m A.S.L. to the northwest of the deposits.

Elevations in the vicinity of the Vault Deposit range from about 139 m A.S.L. at the Vault Lake shoreline to about 160 m A.S.L. just west of the deposit.

Bathymetric surveys of the lakes adjacent to and overlying the main deposits have been carried out previously (see Ref. 5). The results of the surveys indicate the lake depths to be extremely variable, ranging from less than 1 m to about 38 m in areas of Second Portage Lake. The current dike alignments have been selected to take advantage of shallow water areas to simplify construction methods and to minimize construction costs.

3.2 Surficial Geology

The project area is covered by laterally extensive deposits of glacial till. In general terms, the till can be described as a silty sand/gravel till, having a fines (silt plus clay) content between about 30% and 40%, based on laboratory grain size analyses (see Refs. 6, 7, 8). The material also contains up to boulder-sized particles.

Glaciofluvial sand and gravel deposits reportedly occur in three areas: on the north shore of Second Portage Lake, the north shore of the eastern arm of Tern Lake, and to the south of the Vault Deposit (see Ref. 9).

The material that has been recovered from beneath the lakes during geotechnical drilling along the proposed dike alignments generally can be described as cobbles and gravel with traces of sand, silt, and clay. Locally, samples of sand have been obtained. Samples of clayey sand material have been recovered using split spoon sampling methods.

3.3 Permafrost

The project is located within the zone of continuous permafrost. The land surface in the project area is underlain by continuous permafrost, while lakes that are deeper than about 2 m will be underlain by a talik, or zone of permanently unfrozen ground. Based on thermal studies carried out to date, the depth of permafrost is estimated to be on the order of 400 m to 500 m. The depth of the active layer is estimated to be between 2 m and 4 m. The depth of permafrost and of the active layer will vary based on proximity to lakes, overburden thickness, vegetation, climate conditions, and slope direction.

Based on recent ground conductivity surveys and compilation of regional data, the ground ice content is expected to be low. Locally on land, ice lenses and ice wedges are present, as indicated by ground conductivity, and by permafrost features such as peat palsas. These areas of local ground ice are generally associated with low lying areas of poor drainage.

3.4 Climate

Table 3-1 summarizes precipitation data from the Meadowbank site.

Table 3-1: Annual Precipitation Data 1998 – 2002

Year	Recorded Precipitation (mm)
1998	177.1
1999	190.2
2000	100.5
2001	84.1
2002	146.7

Source: Meadowbank Gold Property – Project Description, 2003.

The annual precipitation at the site generally falls as rain between June and September, while snow falls generally between October and May. Snowfall may, however, occur at any time of year. Table 3-2 summarizes mean monthly climate data collected from the site since 1997.

Table 3-2: Summary of Monthly Climate Data

Month	Air Temperature					Mean Soil Temp. (°C)	Wind Speed	
	Extreme Day		Average Monthly				Mean (km/h)	Monthly Max (km/h)
	Max (°C)	Min (°C)	Max (°C)	Min (°C)				
January	-4.9	-43.0	-28.9	-35.6	-32.3	-25.4	15.6	54.5
February	-9.1	-43.4	-26.9	-34.4	-30.8	-27.6	15.4	45.2
March	-3.1	-40.1	-21.0	-29.1	-24.9	-23.6	16.8	51.8
April	2.1	-35.4	-12.5	-22.1	-17.1	17.5	16.9	40.1
May	8.0	-22.3	-2.5	-9.4	-5.7	-8.0	18.9	56.6
June	22.7	-12.9	8.1	0.2	4.1	1.6	16.2	37.6
July	26.9	1.3	17.0	7.6	12.4	11.0	14.9	44.2
August	27.4	-0.4	13.4	6.6	9.9	9.5	18.2	46.7
September	20.5	-7.9	6.1	1.4	3.6	4.0	18.2	81.9
October	5.3	-24.1	-4.9	-10.4	-7.5	-3.2	21.6	62.5
November	-1.3	-32.3	-14.3	-20.9	-17.5	-12.1	16.9	46.1
December	-6.3	-39.6	-22.6	-29.0	-25.9	-19.4	18.4	47.3

Source: Meadowbank Gold Property – Project Description, 2003.

Wind speeds of greater than 100 km/h have been reported at the site. Estimates of wave heights on Third Portage Lake during one such event were reportedly on the order of 2 ft to 3 ft (0.6 m to 0.9 m), based on personal communication with CRL site personnel during 2002.

Based on data obtained during recent geotechnical drilling investigations carried out between late April and early June of 2003, ice thickness on the lakes is expected to vary from about 1.5 m to about 2.5 m,

3.5 Seismicity

The Meadowbank project is located in an area of low seismicity, as shown in Figure 3.1 and Table 3.3.

Table 3-3: Peak Horizontal Ground Accelerations for Meadowbank Site

Return Period of Seismic Event (years)	Peak Horizontal Ground Acceleration (g)
100	0.018
200	0.025
475	0.034
975	0.044

Source: Seismic Risk Calculation for Meadowbank Project Site,
Geological Survey of Canada, Natural Resources Canada, Sidney, B.C., July, 2003 – See Appendix VI.

4.0 DESIGN BASIS AND CRITERIA

The following form the design basis and criteria for the current dike design.

- Dikes are to be constructed to allow open pit mining operations to be carried out year round.
- A portion of the crests of the Second Portage and Goose Island dikes will be used as mine truck haul roads between the open pit and the crusher.
- The dike sections should maximize the use of materials obtained during pre-stripping operations of the open pits, and during mining of a starter pit at the Third Portage Deposit. These materials are till and run-of-mine rockfill.
- A minimum setback of 80 m between the open pit side toe of the dike and the edge of the open pit has been assumed, based on similar setback distances at the Diavik Project.
- Part of the southeast dike on Second Portage Lake will be constructed as a rockfill causeway to reduce haul distances between North Portage and Third Portage.
- The dike crest width should comply with NWT Mine Health and Safety Act and Regulations, or equivalent regulations for Nunavut, for minimum width of haul roads (see Ref. 2). For single lane traffic the minimum width is twice the width of the widest haulage vehicle used on the road; for double lane traffic the minimum width is three times the width of the widest haulage vehicle. A shoulder barrier of at least three-quarters the height of the largest tire on any vehicle using the road is required.
- The dike alignment should be selected to minimize the height of the dike.
- The dike section incorporates a soil-bentonite cutoff wall keyed into bedrock where possible.
- The dike will be a high consequence structure, based on Canadian Dam Association criteria (see Ref. 1).
- The minimum required Factor-of-Safety for static load conditions is 1.5 (see Ref. 1).
- The minimum required Factor-of-Safety for earthquake load conditions is 1.2 (see Ref. 1).
- The minimum required Factor-of-Safety for end-of-construction condition is 1.3. The end-of-construction condition for these dikes ends when men and equipment begin to enter the area within the dikes. (See Ref. 1).
- The maximum design earthquake acceleration corresponds to the 1000-year (nominal) return period event (see Ref. 1).
- The minimum allowable freeboard between crest of the dikes and lake surface will be 2 m. This is required to provide allowance for settlement, and protection for wave and ice run-up.
- The minimum freeboard between the top of the soil-bentonite cutoff wall and the lake surface must be 1 m.

5.0 PROPOSED DIKE AND CAUSEWAY SECTIONS

The proposed typical dike section is shown on Figure 5.1 and the proposed typical Second Portage causeway section is shown on Figure 5.2.

The dike section has rockfill “shoulders” constructed from run-of-mine waste rock supporting an inverted wedge core constructed from till. The till will be excavated during pre-stripping from the pit areas. The section also includes a soil-bentonite cutoff wall to control seepage through the foundation and a granular filter material between the till core material and the downstream rockfill.

The key dimension for the dike is the separation between the inside toe of the upstream rockfill embankment, and the toe of the filter zone. A minimum width of 5 m has been specified to reduce the possibility that large rocks will roll onto the cutoff wall alignment or the zones of large, segregated rockfill that will develop along the embankment toes do not encroach and produce a highly permeable section through which the cutoff wall must be constructed.

The separation between the upstream rockfill and the downstream filter must be carefully controlled during construction to minimize interference with the cutoff wall construction. It is expected that the location of the toes will be measured on a frequent basis, and the locations of the crests adjusted as required.

The sideslopes of the rockfill embankments will depend on the strength of the foundation soil, the gradation of the rockfill and the depth of the water into which it is pushed. It is expected that, along most of the shallow sections of the alignment, sideslopes in the range of 1.5H:1V will be achieved for the rockfill, within a range of about 1.4H:1V to 1.8H:1V. Slopes of about 2.0H:1V to 2.5:1V are expected for the filter material. In the deeper sections, or where the shallow foundation soils are weak and spread under the load of the advancing rockfill, the rockfill slopes could be in the range of 1.8H:1V to 2.5H:1V. The overall width of the dike, from crest to crest, will vary depending on the depth of the water. Along most of the dike alignment, the crest width will be in the range of about 70 m to 85 m.

Foundation preparation will not be achievable along the dike alignment, as the dikes will be constructed through open water. It is expected that the thin layer of soft, lakebed sediment will be displaced by the advancing rockfill, or incorporated into the voids in the base of the rockfill.

Cross-sections of the dike at the locations identified on Figure 1.2 are presented in Figures 5.3 and 5.4. These sections show the rockfill embankments with 1.8H:1V sideslopes and a 5 m to 10 m separation between the inside toes of the rockfill

embankments. Separation of the rockfill toes of greater than 5 m occurs in areas where the depth of the lake varies over short distances along the dike alignment and maintaining the 5 m width would result in abrupt changes in the alignment of the cutoff wall that would reduce the efficiency of the construction operation.

The proposed section for the Second Portage causeway is a simple run-of-mine rockfill embankment with a running surface. Sideslopes are shown at 1.8H:1V, but steeper sideslopes on the order of 1.5H:1V might be achievable.

6.0 GEOTECHNICAL ANALYSES

6.1 Slope Stability

Slope stability analyses were carried out for three sections along the Goose Island dike. Section locations are shown on Figure 1.3 and the sections are shown on Figure 5.3. Section A is located on a relatively flat foundation, Section B is the deepest section with the foundation sloping away from the pit, and Section C is the deepest section where the foundation is sloping toward the pit. Failure of Section A could potentially occur on the inside of the dike towards the open pit. Section B has the deepest water and steepest lake bottom slope along the dike alignment. The lake bottom slopes away from the pit at Section B, and failure of the dike at this location could potentially occur on the outside of the dike towards the lake. Section C is similar to Section A.

Limit equilibrium analyses were carried out using the commercially available software SLIDE™.

The slope stability scenarios modeled for each of Sections A, B, and C. The scenarios were based on combining the following variables:

1. The surface with the minimum factor-of-safety that would breach the cutoff wall. This scenario is considered most critical, since it would result in a failure of the dike.
2. The surface with the minimum factor-of-safety located completely within the rockfill sections. This scenario would require repair of the dikes, but would not reduce the performance of the cutoff.
3. The end-of-construction period was modeled by applying an undrained strength parameter to the soil foundation materials.
4. Long-term conditions were analyzed using effective strength parameters.
5. Static and pseudostatic conditions were modeled. Pseudostatic analyses for earthquake load conditions were carried out for the long-term condition using effective strength parameters.
6. Both circular and block-type failures were considered. In all cases, circular failures were more critical.
7. The analyses were carried out for rockfill embankment sideslopes inclined at 1.5H:1V.
8. Material properties used in the analyses are summarized in Table 6-1.

Table 6-1: Summary of Material Properties used in Slope Stability Analyses

Material	Unit Weight (kN/m ³)	Effective Stress Parameters		Undrained Strength Parameter, c_u (kPa)	Basis for Property Selection
		Cohesion, c (kPa)	Angle of Internal Friction (°)		
Till Core	15.7	0	22 to 32	n/a	Direct shear testing ¹
Rockfill	18.6	0	40	n/a	Previous experience with similar material
Overburden	17	0	24 to 32	10 to 100	Previous experience with material with similar grain size distribution
Soil-Bentonite Backfill	15.7	0	32	n/a	Direct shear testing ¹ – based on testing done on till

Notes: 1. Factual Report - Meadowbank Spring 2002 Geotechnical Investigations – see Ref. 6
 2. For till core material, assumed $c'=0$ for effective stress case.

The pseudostatic analyses have been done using a horizontal acceleration of 0.022g. This value corresponds to one-half of the firm ground acceleration for the 1000-year return period event. The 1000-year return period is considered appropriate, given that:

- The dikes will be retaining water while men and equipment are working in the pits, and;
- The design life of the dikes is less than 20 years.

Results of the stability analyses are included in Appendix I.

6.1.1 Results of Analyses for End-of-Construction Conditions

Slope stability analyses were carried out to evaluate the short-term, end of construction situation. The soil foundation material was assumed to be undrained. Sections A, B, and C were analyzed to determine the values of the undrained shear strength (c_u) which would yield Factors of Safety (FOS) of 1.0 and 1.3.

The analyses show that the minimum required undrained strength of the foundation must be in the range of 20 to 30 kPa, to achieve Factors-of-Safety of 1.0 and 1.3, respectively. The foundation soils that have been recovered during the geotechnical investigations carried out along the proposed dike alignments range from a silty till material containing significant proportions of gravel and cobbles to silty sand and gravel. Undrained strengths of this material are expected to be at least equal to if not greater than 20 to 30 kPa. Undrained shear strength testing will be required during the detailed engineering design stage for the dikes.

The full results of the short-term stability analyses are included in Appendix I.

6.1.2 Results of Analyses for Long-Term Static and Pseudostatic Conditions

Slope stability analyses were done to evaluate the stability of the dikes under long-term, steady-state seepage conditions.

The full results of the long-term analyses are included in Appendix I, and are summarized in Table 6-2.

As seen in Table 6-2, the minimum calculated FOS for static conditions is 1.9, and the minimum calculated FOS for pseudostatic conditions is 1.5, both at Section B.

These values exceed the minimum values indicated by the Dam Safety Guidelines (see Ref. 1).

The minimum yield acceleration (the peak horizontal ground acceleration (PGA) that produces a Factor-of-Safety of 1.0) indicated in Table 6-2 is 0.16g. This value corresponds to a firm ground horizontal acceleration of approximately 0.3g. For the Meadowbank site, the predicted PGA is 0.044 g for a seismic event with a return period of 975 years (see Table 3-3.). Since the predicted PGA is well below the minimum calculated yield acceleration, the dikes are considered stable for the design earthquake event.

Based on the analyses, the dikes will be stable in the long-term, for static and pseudostatic loading conditions.

Table 6-2: Summary of Long-Term Slope Stability Analyses

Failure Mode	Minimum Calculated Factors of Safety		
	Section A	Section B	Section C
Failure through Cutoff Wall Static Conditions (Minimum = 1.5)	4.1	3.5	3.9
Failure through Cutoff Wall Pseudostatic Conditions (Minimum = 1.2)	3.5	3.0	3.3
Failure through Rockfill only Static Conditions (Minimum = 1.5)	2.7	1.9	3.2
Failure through Rockfill only Pseudostatic Conditions (Minimum = 1.2)	2.5	1.7	2.4
Calculated Yield Acceleration (g)			
	Section A	Section B	Section C
Failure through Cutoff Wall	0.41	0.27	0.37
Failure through Rockfill only	0.36	0.16	0.36

Notes: 1. FOS = 1.5 is minimum specified for long-term – see Ref. 1.
 2. FOS = 1.2 is minimum specified for pseudostatic – see Ref. 1.

6.2 Seepage

Seepage analyses were carried out for Sections A and B (see Figure 1.3) using the commercially available software SEEP/W™. The material parameters used in the analyses are presented in Table 6-3.

The cutoff wall was modelled for the following scenarios:

1. A cutoff wall with no gaps at the bedrock contact, and no cracking within the wall.
2. A gap through the soil-bentonite cutoff wall at the bedrock interface.
3. A crack through the soil-bentonite cutoff wall, in the overburden till material
4. A crack through the soil-bentonite cutoff wall, in the till core material.
5. Combinations of 2, 3, and 4.

Table 6-3: Summary of Material Properties used in Seepage Analyses

Material	Hydraulic Conductivity (m/s)	Basis for Properties
Till Core	1×10^{-5}	- Falling head tests from Dec 2002 geotechnical testing and; - Experience with materials with similar genesis and grain size distribution
Rockfill	1×10^{-2}	Experience with similar materials
Overburden	1×10^{-5}	- Falling head tests from Dec 2002 geotechnical testing and; - Experience with materials with similar genesis and grain size distribution
Soil-Bentonite Backfill	1×10^{-9} 1×10^{-8}	Published values
Bedrock	4.7×10^{-7} (Section A) 2.2×10^{-7} (Section B)	- BH 03GT-GI-6 packer tests - BH 03GT-GI-3 packer tests - previous geotechnical field investigations

Fluxes were computed through the soil-bentonite cutoff wall for each scenario. Table 6-4 shows the predicted fluxes for each of the scenarios modelled. Seepage flow-nets are included in Appendix II.

Table 6-4: Seepage Fluxes through the Soil-Bentonite Cutoff Wall

Scenario Modelled	Predicted Flux (L/s/m of length of dike)	
	Section A	Section B
No gap at bedrock contact; no crack in soil-bentonite wall	5.8×10^{-4}	5.6×10^{-4}
No gap at bedrock contact; crack in soil-bentonite wall within overburden till	1.5×10^{-2}	7.5×10^{-3}
No gap at bedrock contact; crack in soil-bentonite wall within till core	5.9×10^{-4}	5.6×10^{-4}
0.5 m gap at bedrock contact; no crack in soil-bentonite wall	1.9×10^{-3}	6.7×10^{-3}
0.5 m gap at bedrock contact; crack in soil-bentonite wall within overburden till	1.5×10^{-2}	1.2×10^{-2}
0.5 m gap at bedrock contact; crack in soil-bentonite wall within till core	1.9×10^{-3}	5.9×10^{-3}

The predicted fluxes result in the following conclusions:

1. Cracks through the cutoff wall in the section through the overburden would result in the largest increase in seepage. The increase is in the range of one to two orders of magnitude more than a wall with no cracks or defects in the overburden section. Cracks within the till core section have a negligible effect on seepage.
2. A gap in the soil-bentonite cutoff wall at the bedrock contact results in an increase in seepage of approximately one order of magnitude.

Preliminary estimates of the range of seepage flows to be expected through the cutoff wall during operations are summarized on Table 6-5.

The estimates were made by applying the predicted seepage flux over the complete lengths of dike. This method results in a “worst case” or maximum seepage for each scenario. Section A is considered to be a more typical section for the Bay Zone, and Second Portage dikes, and for the majority of the Goose Island dike. Section B is the deepest section, and has been applied over 30% of the length of the Goose Island dike.

Table 6-5: Seepage Flows through Dikes

Dike	Predicted Flux (l/s/m of length of dike)		Length of Dike (m)	Predicted Flow through Dike and Overburden (see Note 1) (l/s)
	Section A	Section B		
<i>No gap at bedrock contact, no crack within overburden</i>				
Second Portage	6×10^{-4}	n/a	950	0.6
Bay Zone	6×10^{-4}	n/a	720	0.6
Goose Island	6×10^{-4}	6×10^{-4}	1724	1.2
<i>0.5 m gap at bedrock contact, no crack within overburden (along complete length of dike)</i>				
Second Portage	2×10^{-3}	n/a	950	1.9
Bay Zone	2×10^{-3}	n/a	720	1.4
Goose Island	2×10^{-3}	2×10^{-3}	1724	3.4
<i>Crack in cutoff wall within overburden (along complete length of dike)</i>				
Second Portage	1.5×10^{-2}	n/a	950	14.2
Bay Zone	1.5×10^{-2}	n/a	720	10.8
Goose Island	1.5×10^{-2}	1×10^{-2}	1724	23.3

Notes:

1. To calculate total flow at Second Portage and Bay Zone dikes, the seepage flux at Section A flux was applied over the total length of the dikes. To calculate total flow at the Goose Island dike, the Section A and B seepage fluxes were each applied over 70% and 30% of the dike length, respectively.

It is anticipated that the majority of the seepage flows would be captured in toe drains excavated near the downstream toe of the dikes and pumped, most likely to the water treatment plant. The seepage captured at the drains will likely be pumped to the water treatment plant. The remaining flow would report to the open pit dewatering systems.

The seepage analyses show that the soil-bentonite is effective at controlling seepage through the dike.

7.0 VOLUME ESTIMATES

7.1 Dike and Causeway Materials

Based on the alignments shown in Figure 1.2, and on the typical sections shown in Figures 5.1 and 5.2, volumes of construction fill materials were estimated using previous bathymetry studies, and the 3D terrain modeling software SURPAC™. Table 7-1 summarizes the estimated fill volumes for each section of the dike or causeway. A range of sideslopes from 1.5 to 2.5H:1V were used in the calculation to determine the sensitivity of the construction quantities to this variable.

Table 7-1: Quantity Estimates for Dike Fill Materials

Dike Segment	1.5H:1V		1.8H:1V		2.5H:1V		Approximately Equal for All Rockfill Sideslopes	
	Rockfill (m ³)	Till (m ³)	Rockfill (m ³)	Till (m ³)	Rockfill (m ³)	Till (m ³)	Filter (m ³)	Road Surfacing (m ³)
<i>Materials Required for Construction Prior to Startup</i>								
Second Portage Dike	157,000	40,000	167,000	44,000	181,000	47,000	5,000	8,000
Second Portage Causeway	52,000	0	54,000	0	57,000	0	0	5,000
Bay Zone Dike	153,000	41,000	161,000	47,000	181,000	61,000	5,000	5,000
<i>Totals Prior to Startup</i>	<i>362,000</i>	<i>81,000</i>	<i>382,000</i>	<i>91,000</i>	<i>419,000</i>	<i>108,000</i>	<i>10,000</i>	<i>18,000</i>
<i>Materials Required for Construction in Year 5</i>								
Goose Island Dike	689,000	172,000	852,000	269,000	1,050,000	330,000	30,000	18,000
Grand Totals	1,051,000	253,000	1,234,000	360,000	1,469,000	438,000	40,000	36,000

Notes: Filter and Road Surfacing quantities are based on dimensions shown on Figures 5.1 and 5.2.

Given the large variation in quantity with the rockfill embankment sideslope, it is recommended that field trials be conducted to determine what slope will be achieved for the rockfill. Field trials could consist of advancing a test embankment from shore into an area of water 5 m deep and measuring the resulting fill slopes. The field trials should also include use of the filter material, to determine its slope when pushed off the sideslope of the rockfill, into the water.

Table 7.1 also indicates, based on the current mine plan, the volume of materials required to construct the dikes prior to startup, and in Year 5.

It is important to note that, for a given dike alignment, changes in the rockfill slope will also change the required depth of excavation for the soil-bentonite cutoff wall. For example, in the area near section B, where the lake bottom slopes away from the pit area,

flatter rockfill sideslopes result in the centreline of the dike being moved into deeper water, which increases the depth of cutoff wall excavation.

Section 8.0 includes a detailed discussion of the maximum depths of excavation for the cutoff wall.

7.2 Available Till and Rockfill Quantities

Both till and rockfill for the dikes and causeway will come from pre-stripping at the proposed North Portage and Third Portage pit areas, and from mining at a proposed starter pit at the Third Portage Deposit. Currently, the only viable initial source of rockfill will be a Third Portage starter pit. The starter pit would be entirely enclosed by land at the Third Portage Deposit.

Material from the starter pit could be used to construct an initial causeway portion of the Second Portage Lake southeast de-watering dike to allow access to the North Portage Deposit. This would allow construction materials to then be developed from both the North and Third Portage Deposit areas concurrently, if necessary.

The volumes of available till and rockfill are based on the latest mine plan. (see Appendix III).

Materials to construct the Bay Zone and Second Portage dikes will consist of:

- Intermediate volcanic (IV) rock – in the downstream rockfill;
- Iron formation (IF) rock – in the upstream rockfill;
- Ultramafic (UM) rock – ‘capping’ material for IF rock at the upstream rockfill, and
- Till overburden.

Rockfill to construct the Goose Island dike will also consist of IV, IF, and UM rock types. However, it is possible that the proportion of UM waste rock produced from the pits could be greater in Year 5 than in prior years, which could result in a greater volume of UM being placed at the dikes. Construction of the Goose Island dike will require the till overburden from pit stripping operations be stockpiled, starting in Year 2 of the mine life.

The final determination of the appropriate use of one rock type or the other as fill for either the upstream or downstream rockfills will depend on considerations such as potential for acid generation, and metal to leach. Additional geochemical testing, water balance studies, and lake basin hydraulic modeling will help to address questions relating to the appropriate usage of the particular rock types. These studies are underway.

Preliminary material balance estimates (see Appendix III) indicate that:

- Sufficient quantities of rockfill borrow material will be available through a combination of mining of the Third Portage starter pit, and stripping of the North Portage Deposit.
- Sufficient quantities of till borrow material will be available from stripping of the Third Portage and North Portage deposits.
- The required volumes of till and rockfill material for construction of the Goose Island dike in Year 5 will be sufficient. These materials will come from on-going mining activities at the Portage pit.

8.0 CONSTRUCTION METHODOLOGY

The proposed construction sequence consists of two main components:

1. Construction of rockfill and till core dike, and
2. Construction of soil-bentonite cutoff wall.

The following sections discuss the issues related to each of these components. It is important to note that a sediment control barrier such as a floating or anchored turbidity curtain will be required to minimize the distribution of suspended solids into the lakes during fill placement. This technique has been used on similar projects, including Diavik.

8.1 Construction of Dike Embankments

The dikes will be constructed by ‘bulkheading’ the two rockfill embankments, leaving sufficient space between them to subsequently place the till. ‘Bulkheading’ consists of dumping rockfill at the furthest end of the active rockfill berm in the water, then pushing the rockfill over the edge with a bulldozer. This process is shown schematically in Figure 8.1. The crest of each rockfill embankment will be 20 m wide, which is enough to safely accommodate one-lane haul truck traffic, including safety berms (see Ref. 2).

The volumetric estimates in this report are based on 1.8H:1V sideslopes on the rockfill embankments. It is likely that during construction the sideslopes of the rockfill will vary. If the sideslopes are steeper than 1.8H:1V, then the overall crest can be narrower, which will reduce the quantities of both the rockfill and the till. Conversely, if the sideslopes are flatter than 1.8H:1V, then it will be necessary to widen the overall crest of the dike in order to maintain the 5 m minimum base width of the till.

Mine equipment will blast (where necessary), excavate, load, haul, and dump the fill materials. It has been assumed that 60-ton haul trucks (Caterpillar 777 or equivalent) will be used to haul all fill materials.

The rockfill borrow and haul operation will consist of the following:

1. Blast;
2. Excavate;
3. Load onto haul trucks. Attempt to exclude oversize material (particle size greater than about 1000 mm in diameter);
4. Haul to the dike;
5. Dump at the advancing crest of the fill; and
6. Push by bulldozer into the water. Oversized material should be selectively pushed to the outside of the embankments.

Where it is possible (i.e., in excavatable or rippable material) the till borrow operation will comprise the following steps:

1. Excavate;
2. Pass material through a grizzly to remove oversize material;
3. Re-load after screening;
4. Haul to the dike;
5. Dump at the advancing crest of the core fill; and
6. Push by dozer into the water, between the two rockfill shoulders.

Where the till material is frozen at the borrow area, it will have to be ripped, if possible. If necessary, some of till may need to be blasted, crushed and screened. Handling the till in this way is more complex and expensive than the procedure described above for unfrozen till.

In order to produce filter material, it will be necessary to process the rockfill. Depending on the characteristics of the blasted rock, it might be possible to screen the material through an 8" grizzly to obtain the required particle size distribution. The exact method for processing to obtain filter materials will be finalized during construction.

8.2 Construction of Soil-Bentonite Cutoff Wall

The construction of the soil-bentonite cutoff wall will follow behind the placement of the till inside the rockfill shoulders. A typical soil-bentonite wall construction operation is shown schematically in Figures 8.1 and 8.2.

The basic steps of the construction operation are:

1. Excavate the trench through the till core and foundation soil and into the bedrock. The excavated trench material is placed away from the trench to prevent collapse of the sidewall of the trench due to weight of the spoiled material. The trench walls are held stable by the bentonite slurry in the trench.
2. Excavated material is mixed with bentonite slurry to obtain a suitable soil-bentonite mixture. The mixing is usually done with a dozer, in an area away from the excavation activities so that there is no contamination by waste materials.
3. The soil-bentonite mixture is pushed into the trench by the dozer. Typically, the angle of repose of the fill in the trench is about 10H:1V. This means that, if the trench is 8 m deep, the total length of the backfill slope will be approximately 80 m. In addition, a 20-m separation is required between the toe of the backfill and the active excavation area, in order to prevent contamination by excavated material. This means that there would be approximately 100-m length of trench open.
4. As the soil-bentonite backfill is placed into the trench, it displaces the bentonite slurry. This slurry is pumped back to a de-sanding plant, where suspended solids are removed, and new bentonite is added. The slurry is then reused in the trench.

9.0 EXCAVATION EQUIPMENT FOR THE SOIL-BENTONITE CUTOFF WALL

This section deals with the excavation of the trench for the soil-bentonite cutoff wall, and the types of excavators which will be required.

Figures 9.1 and 9.2 show profiles along the centerlines of the dikes (for a 1.8H:1V rockfill sideslope). These figures show dike crest elevations, lake bottom surface (from bathymetry), and possible bedrock contact surface (interpolated/extrapolated from borehole information). The total depth of excavation is taken from the dike crest to the bedrock contact.

As a preliminary assessment of the types of excavators which could be required, three types of excavators were identified that could be used to excavate the cutoff trench, as follows:

- “Standard” – Caterpillar 320 – up to 6 m depth.
- “Standard Long Reach” – Caterpillar 320BL – up to 12 m depth.
- “Custom” Long Reach Excavator or Stick/Boom – up to 30 m depth.




These excavators are intended to be examples of the type of excavator which could be appropriate for the construction of the dikes. There is a wide range of suitable manufacturers and models available.

On Figures 9.1 and 9.2, the profiles have been divided into coloured sections, to display where each type of excavator would be used. Note that the “Standard” excavator would significantly more efficient than the longer-reach models for shallower depths.

Charts 9.1, 9.2, and 9.3 summarize the total horizontal distance along the dikes where each type of excavator would be required. Charts 9.1 to 9.3 indicate the following:

- The standard excavator, and the standard long-reach excavator will be sufficient for the Bay Zone and Second Portage dikes. The custom long reach excavator will not be required for these two dikes.
- The custom long reach excavator will be required for the Goose Island dike.

Based on the currently proposed mine schedule, the Goose Island dike will be constructed in Year 5 of the mine life. Therefore, the custom long reach excavator might not be required to construct dewatering dikes until Year 5.

Chart 9.1: Cutoff Wall Excavation Equipment – Bay Zone Dike**Chart 9.2: Cutoff Wall Excavation Equipment – Second Portage Dike****Chart 9.3: Cutoff Wall Excavation Equipment – Goose Island Dike**

Details of the example excavators are provided in Appendix IV.

10.0 CONSTRUCTION MATERIAL GUIDELINES

10.1 Rockfill for Embankment Shoulders

The function of the rockfill is to support the core. This material should be a durable, coarse, free-draining material with high shear strength.

The design criteria for the rockfill include the following:

1. The material should be free-draining. Material with a fines content (passing the No. 200 sieve) of less than approximately 8% to 10% is acceptable.
2. It should be non-acid generating and non-metal leaching. The typical dike section could comprise (see Section 7.2):
 - IF rock in the upstream rockfill;
 - IV rock in the downstream rockfill;
 - Till core material;
 - Filter material, and
 - UM rock as a surface capping over the IF rock.

While the intermediate volcanic rock is indicated to be potentially acid generating, during mining the seepage through the dikes and run-off from the dikes will be collected at the downstream toe and treated. After operation the pits will be flooded and the portions of the dikes above water would be reclaimed to approximately 3 m below final lake surface thus submerging the dikes and minimizing acid generation. The intermediate volcanic rock and ultramafic rock are indicated to be metal leaching under neutral pH conditions. However, some of the key factors that will influence the degree to which metal leaching will occur, and the degree to which it will impact on the environment, are metal release rates, dispersion rates, water balance, and lake hydraulics, which have not yet been fully evaluated and modeled. Laboratory testing and other studies are currently underway to resolve some of these issues.

3. Particles should be large and durable enough to resist wave and ice erosion.
4. The grain size distribution of the filter adjacent to the till core must meet filter requirements with the till. This might require adjusting the blast pattern to produce a finer material than would normally be blasted during pre-strip operations. Additionally, it might be necessary to screen the blast-run rockfill to obtain a fine rockfill filter material.

Based on the above, it is recommended that the rockfill gradation limits be set, on a preliminary basis, as shown on Figure 10.1.

Rockfill placed in the upstream (lakeside) embankment, and the rockfill used in the Second Portage Causeway can consist of run-of-mine rockfill, provided it meets geochemical criteria for these fill materials.

10.2 Till Core

The purpose of the core material is to provide material suitable for the soil-bentonite mixture. The core material should also allow a filter cake to form when the slurry trench is filled with bentonite slurry. Literature indicates (see Ref. 10) that the primary requirement to satisfy these criteria is that the materials contain approximately 20% to 40% of the particle size passing the No. 200 (0.074 mm) sieve. A material guideline grain size distribution for the till core material is shown on Figure 10.1. Grain size determinations of till materials recovered from the Meadowbank project area indicate that the till available from the pre-stripped materials at the Third and North Portage Deposits is within these limits.

10.3 Bentonite Slurry

The bentonite slurry in the active excavation area of the trench is designed with four major properties in mind. These properties are:

- **Density.** The density of the slurry provides the hydrostatic force necessary to stabilize the sides of the trench during excavation.
- **Viscosity.** The slurry suspension should have sufficient viscosity to limit the penetration of slurry into the till core material prior to formation of the filter cake.
- **Gel strength.** The slurry suspension should have sufficient gel strength to maintain a given amount of solids in suspension, for the required slurry density.
- **Filtrate loss.** The formation of the low-permeability filter cake is the primary means by which the full hydrostatic force of the slurry is applied to the sides of the trench.

Table 10-1: Typical Properties of a 5% Bentonite Slurry

Property	Typical Value	QC Test
Density	1050 kg/m ³ (fresh) 1160 kg/m ³ (in trench)	Slurry density cup
Viscosity	40 to 50 seconds	Marsh funnel viscosity
Gel Strength	0.5 to 0.7 kPa	10-minute gel strength
Filtrate Loss	20 ml	30-minutes at 100 psi filtrate loss test

The bentonite should be a Wyoming-type, sodium cation-base bentonite.

The bentonite slurry is produced by hydrating dry bentonite for approximately 24 hours. This 'fresh' slurry is then pumped into the trench, where it mixes with 'working' bentonite, which contains suspended solids from the excavation.

10.4 Soil-Bentonite Backfill

The permeability of a soil-bentonite backfill material is dependent on the soil gradation and the quantity of bentonite used in mixing. Typically, the permeability of the backfill is reduced an order of magnitude for each 1% increase in the bentonite concentration by dry weight of backfill.

The soil is usually mixed with bentonite slurry. The slurry typically contains approximately 5% bentonite by dry weight, to obtain a soil-bentonite mixture that is approximately 1% bentonite by weight.

The slump of the backfill should be between 50 mm and 150 mm. Material with this slump will generally form a slope of about 10H:1V in the trench.

11.0 CONCLUSIONS AND RECOMMENDATIONS

The following are conclusions and recommendations based on the results of the Meadowbank dike design study.

1. The dike cross-sections will consist of two rockfill embankments, with a till core zone, a filter zone downstream of the till core, and a soil-bentonite cutoff wall. The cutoff wall will be keyed into bedrock by excavating approximately 0.5 m depth into the bedrock.
2. The slope stability analyses indicate that the dikes will be stable under short-term, undrained, static load conditions, and under long-term, static and earthquake load conditions. The slope stability analyses were done for rockfill sideslopes of 1.5H:1V.
3. Seepage modeling indicates that the total seepage through all of the dikes will be in the range of approximately 2.4 to 48.3 L/s. This value varies depending on potential cracking in the soil-bentonite cutoff wall and/or a potential gap in the cutoff wall at the bedrock contact.
4. Cracks through the cutoff wall in the section through the overburden would result in the largest increase in seepage through the cutoff wall. The increase is in the range of one to two orders of magnitude more than a wall with no cracks or defects in the overburden section. Cracks within the till core have a negligible effect on seepage.
5. A gap in the soil-bentonite cutoff wall at the bedrock contact results in an increase in seepage of approximately one order of magnitude more than a wall with no gap at the bedrock contact.
6. The proposed construction sequence consists of placing the two rockfill shoulders first, then the filter material, leaving a minimum 5-m wide gap between the toes of the filter and the upstream rockfill embankment at the lake bottom. Next, the till core material will be placed between the embankments. The soil-bentonite cutoff wall will be excavated through the till core, through the overburden, and will be keyed into bedrock.
7. The rockfill sideslopes will likely be between 1.5H:1V and 2.5H:1V. Based on these sideslopes, the required rockfill and till volumes in the dikes will be:
 - Between approximately 360,000 m³ and 420,000 m³ of rockfill, and 80,000 m³ to 110,000 m³ of till prior to startup (for Bay Zone and Second Portage dikes).
 - Between approximately 640,000 m³ and 1,050,000 m³ of rockfill, and 170,000 m³ to 330,000 m³ of till in Year 5 (for Goose Island dike).
8. Based on preliminary material balance modeling, the quantities of till and rockfill available from mining activities will be sufficient.

The required volumes of till and rockfill material for construction of dikes prior to startup will be generated during mining of a proposed starter pit at the Third Portage

Deposit, and during on-land pre-stripping activities at the North Portage Deposit. This will require careful sequencing.

The required volumes of till and rockfill material for construction of the Goose Island dike in Year 5 will be sufficient. These materials will come from on-going mining activities at the Portage pit.

9. The construction quantities are sensitive to the sideslopes that will be achieved on the rockfill. A test embankment should be constructed to reduce the uncertainty in the sideslope estimate and quantity estimate. This test will also be useful in determining the anticipated rollout distance of larger particles in the rockfill.

Vibrating wire piezometers should be installed in the foundation till prior to placing the rockfill. This will allow measurement of the pore pressure response of the foundation till, which will provide more accurate data for future stability analyses.

10. 'Standard' long reach excavators (such as a Caterpillar 320 BL) with a digging depth reach greater than 6 m will be required to construct the Bay Zone and Second Portage dikes. This construction will occur prior to startup.

'Custom' long reach excavators with a digging depth reach greater than 12 m will be required to construct the Goose Island dike. This construction will take place in Year 5 of the mine life.

11. Currently, it is proposed that the mined materials be placed in the dike section as follows, at the Bay Zone and Second Portage dikes:
 - Intermediate volcanic rock – in the downstream rockfill;
 - Iron formation rock – in the upstream rockfill;
 - Ultramafic rock – capping material for IF rock at the upstream rockfill;
 - Filter material, and
 - Till overburden.

The Goose Island deposit could have a greater usage of UM rock, depending on availability in Year 5.

12. During mining, any acidic drainage through the dikes would be collected at the downstream toe, and treated. At closure, the dikes would be reclaimed to 2 m to 3 m below lake surface, preventing further acid generation. Additional geochemical testing and lake hydraulic modeling are currently underway to provide additional information on the possible impact of constructing the dikes with the various rock types.

12.0 CLOSING REMARKS

We trust the information contained in the above report meets your requirements at this time. Please feel free to contact us if you need more detailed information on any of the information presented in the report.

GOLDER ASSOCIATES LTD.

Don Hickson, P.Eng.
Geotechnical Engineer

Cam Clayton, P.Geo.
Geological Engineer

Terry Eldridge, P.Eng.
Principal

DAH/CJC/TLE/vee
03-1413-427/4200


N:\FINAL\2003\1413\03-1413-427\RPT1023 - DIKE DESIGN.DOC

REFERENCES

1. Dam Safety Guidelines, Canadian Dam Association, January 1999.
2. Northwest Territories and Nunavut Consolidation of Mine Safety and Health Regulations R-125-95, 1995.
3. Rationalizing the Seismic Coefficient Method, M. Hynes-Griffin and A. Franklin, USACE, WES, Miscellaneous Paper GI-84-13, 1984
4. Rumer, R.R. and Mitchell, J.K. (Eds), Assessment of Containment Technologies for Environmental Remediation Applications, published by US EPA, US DOE, and DuPont Company, 1996.
5. Lake Bathymetry Survey, Meadowbank Project, Golder Associates Ltd., November 2002.
6. Summary Report on Winter 2002 Field Geotechnical Studies, Meadowbank Project, Nunavut; Golder Associates.
7. Summary Report on Summer 2002 Field Geotechnical Studies, Meadowbank Project, Nunavut; Golder Associates.
8. Summary Report on Spring 2003 Field Geotechnical Studies, Meadowbank Project, Nunavut; Golder Associates, September, 2003.
9. Meadowbank Gold Property, Project Description Report”, Cumberland Resources Ltd. March, 2003.
10. Design Standards Embankment Dams No. 13 Chapter 16 Cutoff Walls, U.S. Dept. of the Interior, Bureau of Reclamation, Denver, Colorado.



PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE		KEY PLAN			
		PROJECT No. 03-1413-427		FILE No. key	
		DESIGN	CJC 21NOV02	SCALE	NTS
		CADD	GG 21NOV02	REV 0	
		CHECK	DAH 21OCT03	FIGURE 1.1	
		REVIEW			



NOTES

- 1) Contour information on land supplied by Cumberland Resources Ltd.
- 2) Contours below lake surface are based on bathymetric surveys by Golder Associates Ltd., 2002 and 2003.
- 3) Lake contours are based on surveyed lake surface elevations:
2nd Portage Lake = 133.1 m
3rd Portage Lake = 134.1 m

0 3000 6000 9000 12000 15000
Scale in Meters

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT	
TITLE		MEADOWBANK MINE - SITE PLAN	
PROJECT No. 03-1413-427		FILE No.	Figure 1.2
DESIGN	DAH	21/OCT/03	SCALE AS SHOWN
CADD	SRR	21/OCT/03	REV. 0
CHECK	DAH	21/OCT/03	
REVIEW			



FIGURE 1.2



NOTE

1) Contour information on land supplied by Cumberland Resources Ltd.

2) Contours below lake surface are based on bathymetric surveys by Golder Associates Ltd., 2002 and 2003.

3) Lake contours are based on surveyed lake surface elevations:
2nd Portage Lake = 133.1 m
3rd Portage Lake = 134.1 m

PROJECT

CUMBERLAND RESOURCES LTD.
MEADOWBANK GOLD PROJECT
NUNAVUT


TITLE

PROPOSED DIKE ALIGNMENTS



PROJECT No.	03-1413-427	FILE No.	Figure 1.2
DESIGN	DAH	01/APR/03	SCALE: AS SHOWN
CADD	WSL	10/JUL/03	REV. 0
CHECK	DAH	03/OCT/03	
REVIEW			

FIGURE 1.3



LEGEND


- Meadowbank Project
- Town/Village
- Peak Horizontal Ground Acceleration (g),
for 10% in 50 Years Event
 - 0 - 0.039
 - 0.04 - 0.079
 - 0.08 - 0.109
- Provincial Border
- Water
- Primary Highway
- Railroad

REFERENCE

Ground Acceleration data obtained from National Atlas of Canada,
Base digital data obtained from ESRI Inc.,
DATUM: WGS84 PROJECTION: Geographic

200 0 200 Kilometers
Scale - 1:10,000,000


PROJECT	CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE	SEISMIC ZONING MAP SHOWING MEADOWBANK PROJECT LOCATION			
	PROJECT No.	03-1413-427	SCALE AS SHOWN	REV. 0
	DESIGN	CJC 18 Jun. 2003	FIGURE 3.1	
	GIS	CDB 18 Jun. 2003		
	CHECK			
	REVIEW			



NOTES

- 1) Sideslopes for rockfill as shown are 1.8H:1V.
Actual slopes will vary depending on water depth, rockfill grain size and foundation conditions.
- 2) NWT Mine Safety and Health Act(1995) states that minimum width of haul road is:
 - for one-lane traffic: 2X width of largest vehicle
 - for two-lane traffic: 3X width of largest vehicle
 - minimum height of safety berm = 0.75X diameter of tire of largest vehicle
- 3) The 80m minimum setback is based on a similar set back of Diavik and to be confirmed during detailed engineering design.
- 4) Largest vehicle assumed to be a 777 haul truck.

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE		TYPICAL DIKE CROSS - SECTION SECOND PORTAGE, GOOSE ISLAND AND BAY ZONE DIKS			
		PROJECT No. 03-1413-427		FILE No. Figure 5.1	
		DESIGN	DAH	01/APR/03	SCALE 1:400
		CADD	WSL	19/JUN/03	REV. 0
		CHECK	DAH	03/OCT/03	
		REVIEW			
		FIGURE 5.1			




NOTES

- 1) Sideslopes for rockfill as shown are 1.8H:1V.
Actual slopes will vary depending on water depth, rockfill grain size and foundation conditions.
- 2) NWT Mine Safety and Health Act(1995) states that minimum width of haul road is:
 - for one-lane traffic: 2X width of largest vehicle
 - for two-lane traffic: 3X width of largest vehicle
 - minimum height of safety berm = 0.75X diameter of tire of largest vehicle
- 3) Largest vehicle assumed to be a 777 haul truck.


PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE		TYPICAL CROSS - SECTION SECOND PORTAGE CAUSEWAY			
		PROJECT No. 03-1413-427		FILE No. Figure 5.2	
		DESIGN	DAH	01/APR/03	SCALE 1:250
		CADD	WSL	19/JUN/03	REV. 0
		CHECK	DAH	03/OCT/03	
		REVIEW			
		FIGURE 5.2			

CADD FILE: O:\Active\2003\1413\03-1413-427 CRLFeasibility\4200_DykeDesign\Draft report text\Figures\Figures 5.3 and 5.4.dwg
REVISION DATE: 03/10/14 4:51pm By: sreddy




NOTES

1. Sections are shown for 1.8H:1.0V sideslopes of rockfill. Actual slopes will vary, depending on water depth, rockfill grain size, and foundation conditions.
2. Overburden depth has been estimated based on results from the 2003 Golder geotechnical drilling investigations. Actual overburden depths will vary.
3. All dimensions are in metres unless noted otherwise.




PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE		GOOSE ISLAND DIKE SECTIONS				
 Golder Associates	PROJECT No.	03-1413-427		FILE No.	Figure 5.3 and 5.4	
	DESIGN	DAH	13/JUN/03	SCALE	AS SHOWN	REV. 0
	CADD	NV/WSL	19/JUN/03	FIGURE 5.3		
	CHECK	DAH	03/OCT/03			
	REVIEW					


CADD FILE: O:\Active\2003\1413\03-1413-427 CRLFeasibility\4200_DykeDesign\Draft report text\Figures\Figures 5.3 and 5.4.dwg
REVISION DATE: 03/10/14 4:51pm By: sreddy



D NEAR RIGHT ABUTMENT
1.3




E SECTION THROUGH CAUSEWAY AND DIKE
1.3




F NEAR LEFT ABUTMENT
1.3

NOTES


1. Sections are shown for 1.8H:1.0V sideslopes of rockfill. Actual slopes will vary, depending on water depth, rockfill grain size, and foundation conditions.
2. Overburden depth has been estimated based on results from the 2003 Golder geotechnical drilling investigations. Actual overburden depths will vary.
3. All dimensions are in metres unless noted otherwise.



PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE		SECOND PORTAGE DIKE AND CAUSEWAY SECTIONS			
	PROJECT No.	03-1413-427	FILE No.	Figure 5.3 and 5.4	
	DESIGN	DAH	13/JUN/03	SCALE	AS SHOWN
	CADD	NV/WSL	19/JUN/03	REV.	0
	CHECK	DAH	03/OCT/03	FIGURE 5.4	
REVIEW					




PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE		SOIL-BENTONITE CUTOFF WALL CONSTRUCTION OPERATION CONCEPTUAL LAYOUT			
		PROJECT No. 03-1413-427		FILE No. Figure 8.1	
		DESIGN	DAH	17/APR/03	SCALE N.T.S. REV. 0
		CADD	JK/WSL	19/JUN/03	
		CHECK	DAH	03/OCT/03	
		REVIEW			
FIGURE 8.1					



NOT TO SCALE

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE		SOIL-BENTONITE CUTOFF WALL CONSTRUCTION OPERATION CONCEPTUAL SECTION			
		PROJECT No.	03-1413-427	FILE No.	Figure 8.2
		DESIGN	DAH	17/APR/03	SCALE N.T.S.
		CADD	JK/WSL	19/JUN/03	REV. 0
		CHECK	DAH	03/OCT/03	
		REVIEW			

FIGURE 8.2





LEGEND

- Up to 6 meters - CAT 320
- 6 to 12 meters - CAT 320BL LONG REACH
- Possible Bedrock contact
- Lake bottom
- 03-GT-BZ-5 Borehole - Golder 2003
- 02GT-01 Borehole - Golder 2002

NOTES


- 1) Numbers in brackets are the offset from centreline of dike.
- 2) Lake bottom determined from Bathymetric surveys by Golder in 2002 and 2003.
- 3) Depths to bedrock contact based on boreholes logged and tested by Golder in 2002 and 2003. See Appendix V for complete logs. See Figure 1.2 for borehole locations.




PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE		SECOND PORTAGE AND BAY ZONE DIKE - CENTRELINE PROFILE			
PROJECT No. 031413427.4200		FILE No. DiKe Alignment Sec-			
DESIGN	DSH	10/07/03	SCALE	AS SHOWN	REV. 0
CADD	WSL	29/07/03			
CHECK	DAH	03/08/03			
REVIEW					



FIGURE 9.1





NOTES

- 1) Contour information on land supplied by Cumberland Resources Ltd.
- 2) Contours below lake surface are based on bathymetric surveys by Golder Associates Ltd., 2002 and 2003.
- 3) Lake contours are based on surveyed lake surface elevations:
2nd Portage Lake = 133.1 m
3rd Portage Lake = 134.1 m

0100200300400500

Scale in Meters

PROJECT

CUMBERLAND RESOURCES LTD.
MEADOWBANK GOLD PROJECT
NUNAVUT

TITLE


GEOTECHNICAL BOREHOLES - DIKES



Golder Associates

DESIGN	DAH	16/OCT/03	FILE No.	Figure 9.3
CADD	SRR	16/OCT/03	SCALE:	AS SHOWN
CHECK	DAH	16/OCT/03	REV.	0
REVIEW				

FIGURE 9.3



NOTES

- 1) Till core gradation based on samples analyzed as reported in Winter 2002 and Summer 2002 factual reports by Golder.
- 2) Fine rockfill filter and downstream rockfill designed to be filter-compatible using criteria developed by Sherard, et.al. (self filtering not considered), and presented by U.S. Army Corps of Engineers.

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT					
TITLE		MATERIAL GUIDELINES PROPOSED GRAIN SIZE DISTRIBUTION TILL CORE AND ROCK FILL					
		PROJECT No. 03-1413-427		FILE No. CumberlandFigures			
		DESIGN	WSL	20/06/03	SCALE	N/A	REV. 0
		CADD	WSL	20/06/03	Figure 10.1		
		CHECK	DAH	03/09/03			
		REVIEW					



APPENDIX I
SLOPE STABILITY ANALYSES

**Table AI-1: Summary of Limit Equilibrium Slope Stability Analyses –
Meadowbank Dikes**



(Page 1 of 2)

Figure No. (I-)	Section Analyzed	Conditions Modelled	Calculated Minimum FOS	Calculated Yield Acceleration (g)	Maximum Required Undrained Shear Strength of Overburden Till (kPa)	
					FOS=1.0	FOS=1.3
		End of Construction				
A1	A	Failure through Cutoff Wall; Circular Surfaces			13	19
A2		Failure through Cutoff Wall; Block Surfaces			13	18
A3		Failure through Rockfill; Circular Surfaces			20	28
A4		Failure through Rockfill; Block Surfaces			18	24
B1	B	Failure through Cutoff Wall; Circular Surfaces			n/a	n/a
B2		Failure through Cutoff Wall; Block Surfaces			16	23
B3		Failure through Rockfill; Circular Surfaces			n/a	5
B4		Failure through Rockfill; Block Surfaces			20	30
C1	C	Failure through Cutoff Wall; Circular Surfaces			7	9
C2		Failure through Cutoff Wall; Block Surfaces			9	13
C3		Failure through Rockfill; Circular Surfaces			11	16
C4		Failure through Rockfill; Block Surfaces			10	14
		Long-Term Effective Strength				
A5	A	Failure through Cutoff Wall; Circular Surfaces – Static	4.1			
A6		Failure through Cutoff Wall; Block Surfaces - Static	4.3			
A7		Failure through Rockfill; Circular Surfaces – Static	2.7			
A8		Failure through Rockfill; Block Surfaces - Static	2.8			
A9		Failure through Cutoff Wall; Circular Surfaces – Pseudostatic	3.5			
A10		Failure through Cutoff Wall; Block Surfaces - Pseudostatic	3.7			
A11		Failure through Rockfill; Circular Surfaces – Pseudostatic	2.5			
A12		Failure through Rockfill; Block Surfaces - Pseudostatic	2.6			
A13		Failure through Cutoff Wall; Circular Surfaces – Yield Acceleration		0.41		
A14		Failure through Cutoff Wall; Block Surfaces - Yield Acceleration		0.41		
A15		Failure through Rockfill; Circular Surfaces – Yield Acceleration		0.36		
A16		Failure through Rockfill; Block Surfaces - Yield Acceleration		0.38		

**Table AI-1: Summary of Limit Equilibrium Slope Stability Analyses –
Meadowbank Dikes
(Page 2 of 2)**

Figure No. (I-)	Section Analyzed	Conditions Modelled	Calculated Minimum FOS	Calculated Yield Acceleration (g)
B5	B	Failure through Cutoff Wall; Circular Surfaces – Static	3.5	
B6		Failure through Cutoff Wall; Block Surfaces - Static	5.9	
B7		Failure through Rockfill; Circular Surfaces – Static	1.9	
B8		Failure through Rockfill; Block Surfaces - Static	3.1	
B9		Failure through Cutoff Wall; Circular Surfaces – Pseudostatic	3.0	
B10		Failure through Cutoff Wall; Block Surfaces - Pseudostatic	4.9	
B11		Failure through Rockfill; Circular Surfaces – Pseudostatic	1.7	
B12		Failure through Rockfill; Block Surfaces - Pseudostatic	2.8	
B13		Failure through Cutoff Wall; Circular Surfaces – Yield Acceleration		0.27
B14		Failure through Cutoff Wall; Block Surfaces - Yield Acceleration		0.40
B15		Failure through Rockfill; Circular Surfaces – Yield Acceleration		0.16
B16		Failure through Rockfill; Block Surfaces - Yield Acceleration		0.34
C5	C	Failure through Cutoff Wall; Circular Surfaces – Static	5.0	
C6		Failure through Cutoff Wall; Block Surfaces - Static	3.9	
C7		Failure through Rockfill; Circular Surfaces – Static	3.4	
C8		Failure through Rockfill; Block Surfaces - Static	3.2	
C9		Failure through Cutoff Wall; Circular Surfaces – Pseudostatic	3.7	
C10		Failure through Cutoff Wall; Block Surfaces - Pseudostatic	3.3	
C11		Failure through Rockfill; Circular Surfaces – Pseudostatic	2.4	
C12		Failure through Rockfill; Block Surfaces - Pseudostatic	2.8	
C13		Failure through Cutoff Wall; Circular Surfaces – Yield Acceleration		0.48
C14		Failure through Cutoff Wall; Block Surfaces - Yield Acceleration		0.37
C15		Failure through Rockfill; Circular Surfaces – Yield Acceleration		0.42
C16		Failure through Rockfill; Block Surfaces - Yield Acceleration		0.36

FOS vs. undrained Shear Strength of Overburden Till



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT CUMBERLAND RESOURCES LTD.
MEADOWBANK GOLD PROJECT
NUNAVUT



TITLE SECTION A - END OF CONSTRUCTION
CUTOFF FAILURE - CIRCULAR



PROJECT No. 03-1413-427			FILE No.		SECTION A	
DESIGN	DAH	16/OCT/03	SCALE	N/A	REV.	0
CADD	SRP	16/OCT/03	FIGURE I-A1			
CHECK	DAH	18/OCT/03				
REVIEW	KE	23 OCT 03				

FIGURE I-A1

CADD FILE: 0:\Active\2003\1413\03-1413-427 CRU Feasibility\4200_DynoDesign\Slope Stability Analysis\dwg\SECTION A.dwg
REVISION DATE: 03/10/17 10:31am By: sreddy





NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT					
TITLE SECTION A - END OF CONSTRUCTION CUTOFF FAILURE - BLOCK					
	PROJECT No.	03-1413-427	FILE No.	SECTION A	
	DESIGN	DAH	16/OCT/03	SCALE	N/A
	CADD	SRR	16/OCT/03	REV	0
	CHECK	DAH	16/OCT/03	FIGURE I-A2	
REVIEW		230803			

CADD FILE: 0:\Active\2003\1413\03-1413-427 CR Feasibility\4200_DykeDesign\Slope Stability Analysis\dwg\SECTION A.dwg



REVISION DATE: 03/10/17 10:31am By: sreelax



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.


PROJECT CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE SECTION A - END OF CONSTRUCTION ROCKFILL FAILURE - CIRCULAR			
		FIGURE I-A3	
PROJECT No. 03-1413-427 DESIGN DAH 16/OCT/03 CADD SRR 16/OCT/03 CHECK DAH 16/OCT/03 REVIEW <i>[Signature]</i> 23 OCT 03		FILE No. SECTION A SCALE N/A REV. 0	



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT				CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE				SECTION A - END OF CONSTRUCTION ROCKFILL FAILURE - BLOCK			
		PROJECT No. 03-1413-427		FILE No.		SECTION A	
		DESIGN	DAH	16/OCT/03	SCALE	N/A	REV. 0
		CADD	SRR	16/OCT/03	FIGURE I-A4		
		CHECK	DAH	16/OCT/03			
		REVIEW	Z	23 OCT 03			




MATERIAL TYPE	STRENGTH		UNIT WT.
	COHESION	PHI	kN/m³
TILL CORE	0	28	15.7
OVERBURDEN	0	28	17.0
ROCKFILL	0	40	18.6
S-B CUTOFF	0	28	15.7
BEDROCK	INFINITE STRENGTH		20.0

NOTES


- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT				CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE				SECTION A CUTOFF FAILURE - CIRCULAR - STATIC			
				PROJECT No. 03-1413-427		FILE No. SECTION A	
				DESIGN	DAH	15/OCT/03	SCALE N/A REV 0
				CADD	SRR	15/OCT/03	
				CHECK	DAH	15/OCT/03	
				REVIEW	220307	FIGURE I-A5	



1) All values of Phi are in degrees.
2) All values of Cohesion are in kPa.

PROJECT	CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT																					
TITLE	SECTION A CUTOFF FAILURE - BLOCK - STATIC																					
																						
<table style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="3">PROJECT No. 03-1413-427</td> </tr> <tr> <td>DESIGN</td> <td>DAH</td> <td>15/OCT/03</td> </tr> <tr> <td>CADD</td> <td>SRR</td> <td>15/OCT/03</td> </tr> <tr> <td>CHECK</td> <td>SAH</td> <td>15/OCT/03</td> </tr> <tr> <td>REVIEW</td> <td><i>22</i></td> <td><i>23 OCT 03</i></td> </tr> </table>	PROJECT No. 03-1413-427			DESIGN	DAH	15/OCT/03	CADD	SRR	15/OCT/03	CHECK	SAH	15/OCT/03	REVIEW	<i>22</i>	<i>23 OCT 03</i>	<table style="width: 100%; border-collapse: collapse;"> <tr> <td>FILE No.</td> <td>SECTION A</td> </tr> <tr> <td>SCALE</td> <td>N/A</td> </tr> <tr> <td>REV.</td> <td>0</td> </tr> </table>	FILE No.	SECTION A	SCALE	N/A	REV.	0
PROJECT No. 03-1413-427																						
DESIGN	DAH	15/OCT/03																				
CADD	SRR	15/OCT/03																				
CHECK	SAH	15/OCT/03																				
REVIEW	<i>22</i>	<i>23 OCT 03</i>																				
FILE No.	SECTION A																					
SCALE	N/A																					
REV.	0																					
FIGURE I-A6																						




MATERIAL TYPE	STRENGTH		UNIT WT.
	COHESION	PHI	kN/m³
TILL CORE	0	28	15.7
OVERBURDEN	0	28	17.0
ROCKFILL	0	40	18.6
S-B CUTOFF	0	28	15.7
BEDROCK	INFINITE STRENGTH		20.0

NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.


PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE		SECTION A ROCKFILL FAILURE - CIRCULAR - STATIC			
	PROJECT No.	03-1413-427	FILE No.	SECTION A	
	DESIGN	DAH	16/OCT/03	SCALE	N/A
	CADD	SRR	16/OCT/03	REV.	0
	CHECK	DAH	16/OCT/03	FIGURE I-A7	
	REVIEW	2/2	23/05/03		



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT	
TITLE		SECTION A ROCKFILL FAILURE - BLOCK - STATIC	
		PROJECT No.	03-1413-427
		DESIGN	SAH 16/OCT/03
		CADD	SRP 18/OCT/03
		CHECK	SAH 16/OCT/03
		REVIEW	JK 23/OCT/03
		FILE No.	SECTION A
		SCALE	N/A REV. 0
		FIGURE I-A8	




NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE		SECTION A CUTOFF FAILURE - CIRCULAR PSEUDOSTATIC				
		PROJECT No.	03-1413-427	FILE No.	SECTION A	
		DESIGN	DAH	16/OCT/03	SCALE	N/A
		CADD	SRR	16/OCT/03	REV.	0
		CHECK	DAH	16/OCT/03	FIGURE I-A9	
		REVIEW	KC	23/OCT/03		

CADD FILE: G:\Active\2003\1413\03-1413-427 CR Feasibility\4200_DikeDesign\Slope Stability Analysis\dwg\SECTION A.dwg

REVISION DATE: 03/10/17 10:31am By: sreddy




NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT				CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE				SECTION A CUTOFF FAILURE - BLOCK PSEUDOSTATIC				
		PROJECT No. 03-1413-427		FILE No.		SECTION A		
		DESIGN	DAH	16/OCT/03	SCALE	N/A	REV	0
		GADO	SRR	16/OCT/03				
		CHECK	DAH	16/OCT/03				
		REVIEW	JCE	23 OCT 03	FIGURE I-A10			


REVISION DATE: 03/10/17 10:31am By: sreedy CADD FILE: O:\Active\2003\1413\03-1413-427 CRI Feasibility\4200 DyseDesign\Slope Stability Analysis\dwg\SECTION A.dwg



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT				CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE				SECTION A ROCKFILL FAILURE - CIRCULAR PSEUDOSTATIC				
		PROJECT No. 03-1413-427		FILE No.		SECTION A		
		DESIGN	DAH	15/OCT/03	SCALE	N/A	REV	0
		CADD	SRK	18/OCT/03	FIGURE I-A11			
		CHECK	DAH	15/OCT/03				
		REVIEW	ZXC	23/OCT/03				




NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT	
TITLE		SECTION A ROCKFILL FAILURE - BLOCK PSEUDOSTATIC	
		PROJECT No. 03-1413-427	FILE No. SECTION A
DESIGN	DAH	18/OCT/03	SCALE N/A REV. 0
CADD	SRR	18/OCT/03	FIGURE I-A12
CHECK	DAH	18/OCT/03	
REVIEW	KE	23/OCT/03	






NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.
- 3) Yield acceleration is the value of the horizontal acceleration for FOS = 1.0

PROJECT	CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE	SECTION A CUTOFF FAILURE - CIRCULAR YIELD ACCELERATION			
	PROJECT No.	03-1413-427	FILE No.	SECTION A
	DESIGN	DAH	18/OCT/03	SCALE N/A REV. 0
	CADD	SRR	18/OCT/03	
	CHECK	DAH	18/OCT/03	FIGURE I-A13
	REVIEW	BS	23/OCT/03	




YIELD ACCELERATION; $k_y = 0.41g$

NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.
- 3) Yield acceleration is the value of the horizontal acceleration for FOS = 1.0

PROJECT	CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE	SECTION A CUTOFF FAILURE - BLOCK YIELD ACCELERATION				
 Golder Associates	PROJECT No.	03-1413-427		FILE No.	SECTION A
	DESIGN	DAH	15/OCT/03	SCALE	N/A
	CADD	SRR	15/OCT/03	REV	0
	CHECK	DAH	15/OCT/03	FIGURE I-A14	
	REVIEW	KE	23NOV03		




YIELD ACCELERATION; $k_y = 0.36g$

MATERIAL TYPE	STRENGTH		UNIT WT. kN/m ³
	COHESION	PHI	
TILL CORE	0	28	15.7
OVERBURDEN	0	28	17.0
ROCKFILL	0	40	18.6
S-B CUTOFF	0	28	15.7
BEDROCK	INFINITE STRENGTH		20.0

NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.
- 3) Yield acceleration is the value of the horizontal acceleration for FOS = 1.0

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE		SECTION A ROCKFILL FAILURE - CIRCULAR YIELD ACCELERATION				
		PROJECT No.	03-1413-427	FILE No.	SECTION A	
		DESIGN	DAH	16/OCT/03	SCALE	N/A REV. 0
		CADD	SRP	16/OCT/03		
		CHECK	DAH	16/OCT/03	FIGURE I-A15	
		REVIEW	ZC	230303		





YIELD ACCELERATION; $k_y = 0.38g$

NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.
- 3) Yield acceleration is the value of the horizontal acceleration for FOS = 1.0

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE		SECTION A ROCKFILL FAILURE - BLOCK YIELD ACCELERATION				
		PROJECT No. 03-1413-427		FILE No.	SECTION A	
		DESIGN	DAH	15/OCT/03	SCALE	N/A
		CADD	SRR	15/OCT/03	REV	0
		CHECK	DAH	15/OCT/03	FIGURE I-A16	
		REVIEW	23 OCT 03			



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.



PROJECT
CUMBERLAND RESOURCES LTD.
MEADOWBANK GOLD PROJECT
NUNAVUT

TITLE
**SECTION B - END OF CONSTRUCTION
CUTOFF FAILURE - CIRCULAR**



PROJECT No. 03-1413-427			FILE No. CumberlandFigures		
DESIGN	WSL	15/06/03	SCALE	N/A	REV 0
CADD	WSL	18/06/03	FIGURE I-B1		
CHECK	DAH	03/09/03			
REVIEW	KE	23 OCT 03			

FIGURE I-B1





NOTES


- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT				CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE				SECTION B - END OF CONSTRUCTION CUTOFF FAILURE - BLOCK			
		PROJECT No.		FILE No.		SECTION B	
		DESIGN		SCALE		REV.	
		CADD					
		CHECK					
		REVIEW					

FIGURE I-B2



MATERIAL TYPE	STRENGTH		UNIT WT. kN/m³
	COHESION	PHI	
FILL CORE	0	28	15.7
OVERBURDEN	31	0	17.0
ROCKFILL	0	40	18.8
S-B CUTOFF	0	28	15.7
BEDROCK	INFINITE STRENGTH		20.0





NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE		SECTION B - END OF CONSTRUCTION ROCKFILL FAILURE - CIRCULAR			
 Golder Associates	PROJECT No. 03-1413-427		FILE No. CumberlandFigures		
	DESIGN	WSL	18/05/03	SCALE	N/A
	CADD	WSL	18/05/03		REV. 0
	CHECK	DAH	03/09/03	FIGURE I-B3	
	REVIEW	<i>RK</i>	<i>23/02/03</i>		


REVISION DATE: 03/10/17 10:27am By: srodey C:\Active\2003\1413\03-1413-427 CR\Facility\4200_DykeDesign\Slope_Stability_Analysis\dwg\SECTION B.dwg



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.


PROJECT	CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE	SECTION B - END OF CONSTRUCTION ROCKFILL FAILURE - BLOCK				
	PROJECT No.	03-1413-427	FILE No.	SECTION B	
	DESIGN	DAH	16/OCT/03	SCALE	N/A
	CADD	SRR	16/OCT/03	REV	0
	CHECK	DAH	16/OCT/03		
REVIEW	23 OCT 03				
FIGURE I-B4					



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.


PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE		SECTION B CUTOFF FAILURE - CIRCULAR - STATIC				
	PROJECT No. 03-1413-427		FILE No. CumberlandFigures		FIGURE I-B5	
	DESIGN	WSL	18/05/03	SCALE		N/A
	CADD	WSL	18/05/03			
	CHECK	DAH	03/09/03			
	REVIEW	KS	18/05/09			



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.


PROJECT				CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE				SECTION B CUTOFF FAILURE - BLOCK - STATIC			
		PROJECT No. 03-1413-427		FILE No.		SECTION B	
		DESIGN	DAH	16/OCT/03	SCALE	N/A	REV D
		CADD	SRB	16/OCT/03	FIGURE I-B6		
		CHECK	DAH	16/OCT/03			
		REVIEW	7KE	23/05/03			



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT				CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE				SECTION B ROCKFILL FAILURE - CIRCULAR - STATIC			
				PROJECT No. 03-1413-427		FILE No. CumberlandFigures	
				DESIGN	WSL	18/08/03	SCALE N/A REV 0
				CADD	WSL	18/08/03	
				CHECK	DAH	03/09/03	
				REVISED	JK	23/05/03	
				FIGURE I-B7			




MATERIAL TYPE	STRENGTH		UNIT WT. kN/m ³
	COHESION	PHI	
TILL CORE	0	28	15.7
OVERBURDEN	0	28	17.0
ROCKFILL	0	40	18.6
S-B CUTOFF	0	28	15.7
BEDROCK	INFINITE STRENGTH		20.0

NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.


PROJECT				CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE				SECTION B ROCKFILL FAILURE - BLOCK - STATIC			
		PROJECT No. 03-1413-427		FILE No.		SECTION B	
		DESIGN	DAH	16/OCT/03	SCALE	N/A	REV. 0
		CADD	SRR	16/OCT/03	FIGURE I-B8		
		CHECK	DAH	18/OCT/03			
		REVIEW	ZK	29 OCT 03			



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.


PROJECT				CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE				SECTION B CUTOFF FAILURE - CIRCULAR PSEUDOSTATIC			
				PROJECT No. 03-1413-427		FILE No. SECTION B	
				DESIGN CAH 15/OCT/03		SCALE N/A REV 0	
				CADD SRR 15/OCT/03			
				CHECK CAH 18/OCT/03			
				REVIEW <i>RC</i> 23 OCT 03		FIGURE I-B9	



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.


PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT	
TITLE		SECTION B ROCKFILL FAILURE - BLOCK PSEUDOSTATIC	
PROJECT No.		03-1413-427	FILE No. SECTION B
DESIGN	DAH	16/OCT/03	SCALE N/A REV. 0
CADD	SRR	16/OCT/03	
CHECK	DAH	16/OCT/03	
REVIEW			
FIGURE I-B10			



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT					
TITLE		SECTION B ROCKFILL FAILURE - CIRCULAR PSEUDOSTATIC					
		PROJECT No. 03-1413-427		FILE No.		SECTION B	
		DESIGN	DAH	16/OCT/03	SCALE	N/A	REV. 0
		CADD	SRR	16/OCT/03	FIGURE I-B11		
		CHECK	DAH	16/OCT/03			
		REVIEW	JLC	23/OCT/03			




MATERIAL TYPE	STRENGTH		UNIT WT.
	COHESION	PHI	kN/m³
TILL CORE	0	28	15.7
OVERBURDEN	0	28	17.0
ROCKFILL	0	40	18.6
S-B CUTOFF	0	28	15.7
BEDROCK	INFINITE STRENGTH		20.0

NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT	
TITLE		SECTION B ROCKFILL FAILURE - BLOCK PSEUDOSTATIC	
		PROJECT No.	03-1413-427
		DESIGN	DAH 18/OCT/03
		CADD	SRR 18/OCT/03
		CHECK	DAH 18/OCT/03
		REVIEW	23 OCT 03
		FILE No.	SECTION B
		SCALE	N/A REV. 0
		FIGURE I-B12	




NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.
- 3) Yield acceleration is the value of the horizontal acceleration for FOS = 1.0

PROJECT	CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT		
TITLE	SECTION B CUTOFF FAILURE - CIRCULAR YIELD ACCELERATION		
	PROJECT No.	03-1413-427	FILE No.
	DESIGN	WSL	18/06/03
	CADD	WSL	18/06/03
	CHECK	DAH	03/09/03
	REVIEW	KZ	23/06/03
			SCALE: N/A REV: 0
			FIGURE I-B13


MATERIAL TYPE	STRENGTH		UNIT WT.
	COHESION	PHI	kN/m³
TILL CORE	0	28	15.7
OVERBURDEN	0	28	17.0
ROCKFILL	0	40	18.6
S-B CUTOFF	0	28	15.7
BEDROCK	INFINITE STRENGTH		20.0



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.
- 3) Yield acceleration is the value of the horizontal acceleration for FOS = 1.0

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE		SECTION B CUTOFF FAILURE - BLOCK YIELD ACCELERATION				
 Golder Associates		PROJECT No.	03-1413-427	FILE No.	SECTION B	
		DESIGN	DAH	18/OCT/03	SCALE	N/A REV. 0
		CADD	SRH	18/OCT/03		
		CHECK	DAH	18/OCT/03		
		REVIEW	28/10/03	23/01/03		
		FIGURE I-B14				




NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.
- 3) Yield acceleration is the value of the horizontal acceleration for FOS = 1.0

PROJECT	CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT		
TITLE	SECTION B ROCKFILL FAILURE - CIRCULAR YIELD ACCELERATION		
	PROJECT No.	03-1413-427	FILE No. CumberlandFigures
	DESIGN	WSL 18/06/03	SCALE N/A REV 0
	CADD	WSL 18/06/03	
	CHECK	DAH 03/08/03	
	REVIEW	<i>[Signature]</i> 23/08/03	
FIGURE I-B15			

MATERIAL TYPE	STRENGTH		UNIT WT. kN/m³
	COHESION	PHI	
TILL CORE	0	28	15.7
OVERBURDEN	0	28	17.0
ROCKFILL	0	40	18.6
S-B CUTOFF	0	28	15.7
BEDROCK	INFINITE STRENGTH		20.0




YIELD ACCELERATION; $k_y = 0.34g$

NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.
- 3) Yield acceleration is the value of the horizontal acceleration for FOS = 1.0



PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT						
TITLE		SECTION B ROCKFILL FAILURE - BLOCK YIELD ACCELERATION						
		PROJECT No.	03-1413-427	FILE No.	SECTION B			
		DESIGN	DAH	16/OCT/03	SCALE	N/A	REV	0
		CADD	SRR	16/OCT/03	FIGURE I-B16			
		CHECK	DAH	16/OCT/03				
		REVIEW	JLH	23 OCT 03				



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT	
TITLE		SECTION C - END OF CONSTRUCTION CUTOFF FAILURE - CIRCULAR	
PROJECT No. 03-1413-427		FILE No. CumberlandFigures	
DESIGN	WSL	18/05/03	SCALE N/A REV. 0
CADD	WSL	18/05/03	
CHECK	DAH	03/09/03	
REVIEW	JKH	23 Oct 03	
		FIGURE I-C1	




NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT					
TITLE		SECTION C - END OF CONSTRUCTION CUTOFF FAILURE - BLOCK					
 Golder Associates		PROJECT No.		03-1413-427	FILE No.	SECTION C	
		DESIGN	DAH	16/OCT/03	SCALE	N/A	REV. 0
		CADD	SRR	16/OCT/03			
		CHECK	DAH	16/OCT/03			
		REVIEW	JCC	23 OCT 03			
		FIGURE I-C2					





NOTES



- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT				CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE				SECTION C - END OF CONSTRUCTION ROCKFILL FAILURE - CIRCULAR			
PROJECT No. 03-1413-427				FILE No. CumberlandFigures			
DESIGN		WSL		18/06/03		SCALE N/A REV. 0	
CADD		WSL		18/06/03			
CHECK		DAH		01/09/03			
REVIEW		JKE		23/06/03			


FIGURE I-C3



F.O.S. vs. Undrained Shear Strength of Overburden Till




MATERIAL TYPE	STRENGTH		UNIT WT. kN/m³
	COHESION	PHI	
TILL CORE	0	28	15.7
OVERBURDEN	31	0	17.0
ROCKFILL	0	40	18.6
S-B CUTOFF	0	28	15.7
BEDROCK	INFINITE STRENGTH		20.0



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.


PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE		SECTION C - END OF CONSTRUCTION ROCKFILL FAILURE - BLOCK				
 Golder Associates		PROJECT No.	03-1413-427	FILE No.	SECTION C	
		DESIGN	DAH	16/OCT/03	SCALE	N/A
		CADD	SRH	16/OCT/03	REV.	0
		CHECK	DAH	16/OCT/03	FIGURE I-C4	
		REVIEW	JRC	23/OCT/03		



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT				CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE				SECTION C CUTOFF FAILURE - CIRCULAR - STATIC			
				PROJECT No. 03-1413-427		FILE No. CumberlandFigures	
				DESIGN	WSL	18/06/03	SCALE N/A
				CADD	WSL	18/06/03	REV. 0
				CHECK	DAH	03/09/03	
				REVIEW	KE	23 Oct 03	
				FIGURE I-C5			




1) All values of Phi are in degrees.
2) All values of Cohesion are in kPa.

PROJECT	CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT
TITLE	SECTION C CUTOFF FAILURE - BLOCK - STATIC

 Golder Associates	PROJECT No. 03-1413-427	FILE No.	SECTION C
	DESIGN DAH 16/OCT/03	SCALE	N/A
	CADD SRR 16/OCT/03		REV. 0
	CHECK DAH 16/OCT/03	FIGURE I-C6	
	REVIEW <i>PC</i> 2305/03		


MATERIAL TYPE	STRENGTH		UNIT WT.
	COHESION	PHI	kN/m³
TILL CORE	0	28	15.7
OVERBURDEN	0	28	17.0
ROCKFILL	0	40	18.6
S-B CUTOFF	0	28	15.7
BEDROCK	INFINITE STRENGTH		20.0



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE SECTION C ROCKFILL FAILURE - CIRCULAR - STATIC			
	PROJECT No.	03-1413-427	FILE No. CumberlandFigures
	DESIGN	WSL	18/06/03
	CADD	WSL	18/06/03
	CHECK	DAH	03/09/03
	REVIEW	7/2/2003	13/09/03
FIGURE I-C7			




MATERIAL TYPE	STRENGTH		UNIT WT.
	COHESION	PHI	kN/m³
TILL CORE	0	28	15.7
OVERBURDEN	0	28	17.0
ROCKFILL	0	40	18.6
S-B CUTOFF	0	28	15.7
BEDROCK	INFINITE STRENGTH		20.0

NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT						
TITLE		SECTION C ROCKFILL FAILURE - BLOCK - STATIC						
		PROJECT No. 03-1413-427		FILE No.		SECTION C		
		DESIGN	DAH	18/OCT/03	SCALE	N/A	REV. 0	
		CADD	SRR	18/OCT/03	FIGURE I-C8			
		CHECK	DAH	18/OCT/03				
		REVIEW		23 OCT 03				




NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT					
TITLE		SECTION C CUTOFF FAILURE - CIRCULAR PSEUDOSTATIC					
 Golder Associates		PROJECT No.	03-1413-427	FILE No.	SECTION C		
		DESIGN	DAH	16/OCT/03	SCALE	N/A	REV. 0
		CADD	SRB	16/OCT/03	FIGURE I-C9		
		CHECK	DAH	16/OCT/03			
		REVIEW	7KE	13/OCT/03			



CADD FILE: 0:\Active\2003\1413\05-1413-427 CRI Feasibility\4200_Dykedesign\Slope Stability Analysis\dwg\SECTION A.dwg
 REVISION DATE: 03/10/17 10:31am By: sreedy




NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT				CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE				SECTION C CUTOFF FAILURE - BLOCK PSEUDOSTATIC				
		PROJECT No. 03-1413-427		FILE No.		SECTION C		
		DESIGN	DAH	16/OCT/03	SCALE	N/A	REV	0
		CADD	SRR	16/OCT/03				
		CHECK	DAH	16/OCT/03				
		REVIEW	KE	23 Oct 03	FIGURE I-C10			


REVISION DATE: 03/10/17 10:31am By: steady
CADD FILE: O:\Active\2003\1413\03-1413-427 CRU Feasibility\4200_DykeDesign\Slope Stability Analysis\dwg\SECTION A.dwg



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT	CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE	SECTION C ROCKFILL FAILURE - CIRCULAR - STATIC				
	PROJECT No.	03-1413-427	FILE No.	SECTION C	
	DESIGN	CAH	16/OCT/03	SCALE	N/A
	CADD	SRR	18/OCT/03	REV	0
	CHECK	CAH	16/OCT/03	FIGURE I-C11	
REVIEW	JCC	23 Oct 03			




NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT					
TITLE		SECTION C ROCKFILL FAILURE - BLOCK PSEUDOSTATIC					
		PROJECT No. 03-1413-427		FILE No.		SECTION C	
		DESIGN DAH 16/OCT/03		SCALE		N/A	
		CADD SRR 16/OCT/03		CHECK DAH 18/OCT/03		FIGURE I-C12	
		REVIEW KE 23 Oct 03					

MATERIAL TYPE	STRENGTH		UNIT WT. kN/m³
	COHESION	PHI	
TILL CORE	0	28	15.7
OVERBURDEN	0	28	17.0
ROCKFILL	0	40	18.6
S-B CUTOFF	0	28	15.7
BEDROCK	INFINITE STRENGTH		20.0




Yield Acceleration; $k_y = 0.48g$

NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.
- 3) Yield acceleration is the value of the horizontal acceleration for FOS = 1.0


PROJECT				CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE				SECTION C CUTOFF FAILURE - CIRCULAR YIELD ACCELERATION			
		PROJECT No. 03-1413-427		FILE No. CumberlandFigures			
		DESIGN WSL	18/06/03	SCALE	N/A	REV 0	
		CADD WSL	18/06/03				
		CHECK DAK	03/08/03				
		REVIEW <i>JK</i>		23 Oct 03			
						FIGURE I-C13	



NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.
- 3) Yield acceleration is the value of the horizontal acceleration for FOS = 1.0

PROJECT				CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE				SECTION C CUTOFF FAILURE - BLOCK YIELD ACCELERATION			
				PROJECT No. 03-1413-427		FILE No. SECTION C	
				DESIGN	DAH	16/OCT/03	SCALE N/A REV 0
				CADD	SRR	16/OCT/03	
				CHECK	DAH	16/OCT/03	
				REVIEW	DAH	23/OCT/03	FIGURE I-C14




Yield Acceleration; $k_y = 0.42g$

NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.
- 3) Yield acceleration is the value of the horizontal acceleration for FOS = 1.0

PROJECT	CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE	SECTION C ROCKFILL FAILURE - CIRCULAR YIELD ACCELERATION			
	PROJECT No.	03-1413-427	FILE No.	CumberlandFigures
	DESIGN	WSL 18/06/03	SCALE	N/A
	CADD	WSL 18/06/03	REV.	0
	CHECK	CAH 03/09/03	FIGURE I-C15	
	REVIEW	 23/09/03		

CADD FILE: C:\Active\2003\1413\03-1413-427 CRI Feasibility\4200_DykeDesign\Slope Stability Analysis\dwg\SECTION A.dwg
REVISION DATE: 03/10/17 10:3am By: sreedy



YIELD ACCELERATION; $k_y = 0.36g$

NOTES

- 1) All values of Phi are in degrees.
- 2) All values of Cohesion are in kPa.
- 3) Yield acceleration is the value of the horizontal acceleration for FOS = 1.0

PROJECT	CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE	SECTION C ROCKFILL FAILURE - BLOCK YIELD ACCELERATION				
	PROJECT No.	03-1413-427	FILE No.	SECTION C	
	DESIGN	DAH	16/OCT/03	SCALE	N/A REV 0
	CADD	SRR	16/OCT/03	CHECK	DAH
	CHECK	DAH	16/OCT/03	REVIEW	72523000


FIGURE I-C16

APPENDIX II
SEEPAGE ANALYSES

Table AII-1: Summary of Seepage Analyses – Meadowbank Dikes

Figure No. (II-)	Section Analyzed	Conditions Modelled	Flux through Dike (L/s/m)
A1	A	No gap at bedrock contact; no crack in soil-bentonite wall	5.8×10^{-4}
A2		No gap at bedrock contact; crack in soil-bentonite wall within overburden till	1.5×10^{-2}
A3		No gap at bedrock contact; crack in soil-bentonite wall within till core	5.9×10^{-4}
A4		0.5 m gap at bedrock contact; no crack in soil-bentonite wall	1.9×10^{-3}
A5		0.5 m gap at bedrock contact; crack in soil-bentonite wall within overburden till	1.5×10^{-2}
A6		0.5 m gap at bedrock contact; crack in soil-bentonite wall within till core	1.9×10^{-3}
B1	B	No gap at bedrock contact; no crack in soil-bentonite wall	5.6×10^{-4}
B2		No gap at bedrock contact; crack in soil-bentonite wall within overburden till	7.5×10^{-3}
B3		No gap at bedrock contact; crack in soil-bentonite wall within till core	5.6×10^{-3}
B4		0.5 m gap at bedrock contact; no crack in soil-bentonite wall	6.7×10^{-3}
B5		0.5 m gap at bedrock contact; crack in soil-bentonite wall within overburden till	1.2×10^{-2}
B6		0.5 m gap at bedrock contact; crack in soil-bentonite wall within till core	6.6×10^{-3}

Description: Meadowbank Dike Design
Comments: 03-1413-427/4200 File
Name: Section 3A10-8_no gap, no crack.sez
Last Saved Date: 10/15/2003
Last Saved Time: 1:04:43 PM
Analysis Type: Steady-State
Analysis View: 2-D



NOTES

1) See section A on Figure 1.3


MATERIAL HYDRAULIC CONDUCTIVITY (m/s)

Till core	1×10^{-5}
Rockfill	1×10^{-2}
Overburden	1×10^{-5}
Soil-bentonite backfill	1×10^{-8}
Bedrock	1×10^{-7}

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT						
TITLE		SECTION A - NO GAP OR CRACK IN SOIL-BENTONITE WALL						
 Golder Associates		PROJECT No.		03-1413-427				
		DESIGN		DAH 05/OCT/03				
		CADD		SRR 05/OCT/03				
		CHECK		DAH 05/OCT/03				
		REVIEW		KE 23 OCT 03				
		SCALE		N/A				
		FILE No.		Section 3A104				
				SCALE		N/A	REV.	0
						FIGURE II-A1		



Description: Meadowbank Dike Design
 Comments: 03-1413-427/4200
 File Name: Section 3A10-8_no gap, 0.25m crack
 at 2m above bedrock.sez
 Last Saved Date: 20-Oct-2003
 Last Saved Time: 8:19:09 AM
 Analysis Type: Steady-State
 Analysis View: 2-D



NOTES


- 1) See section A on Figure 1.3
- 2) Cracks modelled as 0.25m thick.

MATERIAL HYDRAULIC CONDUCTIVITY (m/s)

Till core	1×10^{-5}
Rockfill	1×10^{-2}
Overburden	1×10^{-5}
Soil-bentonite backfill	1×10^{-8}
Bedrock	1×10^{-7}

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT	
TITLE		SECTION A - NO GAP; CRACK IN SOIL-BENTONITE WALL WITHIN OVERBURDEN	
PROJECT No.		03-1413-427	FILE No. Section 3A10-8
DESIGN	DAH	06OCT03	SCALE N/A REV. 0
CADD	SRR	06OCT03	
CHECK	DAH	06OCT03	
REVIEW	ZK	23oct03	
		FIGURE II-A2	

Description: Meadowbank Dike Design
 Comments: 03-1413-427/4200
 File Name: Section 3A10-8_no gap, 0.25m crack
 at 3m above bedrock sez
 Last Saved Date: 20-Oct-2003
 Last Saved Time: 8:18:22 AM
 Analysis Type: Steady-State
 Analysis View: 2-D



NOTES

- 1) See section A on Figure 1.3
- 2) Cracks modelled as 0.25m thick.


MATERIAL HYDRAULIC CONDUCTIVITY (m/s)

Till core	1×10^{-5}
Rockfill	1×10^{-2}
Overburden	1×10^{-5}
Soil-bentonite backfill	1×10^{-8}
Bedrock	1×10^{-7}

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE		SECTION A - NO GAP; CRACK IN SOIL-BENTONITE WALL WITHIN TILL CORE			
PROJECT No.		03-1413-427	FILE No.		Section 3A10-8
DESIGN	DAH	09OCT03	SCALE	N/A	REV. 0
CADD	SRR	09OCT03	FIGURE II-A3		
CHECK	DAH	09OCT03			
REVIEW	ZK	23OCT03			



Description: Meadowbank Dike Design
 Comments: 03-1413-427/4200
 File Name: Section 3A10-8_0.50m gap, no crack.sez
 Last Saved Date: 20-Oct-2003
 Last Saved Time: 8:20:02 AM
 Analysis Type: Steady-State
 Analysis View: 2-D



NOTES


- 1) See section A on Figure 1.3

MATERIAL HYDRAULIC CONDUCTIVITY (m/s)

Till core	1×10^{-5}
Rockfill	1×10^{-2}
Overburden	1×10^{-5}
Soil-bentonite backfill	1×10^{-8}
Bedrock	1×10^{-7}

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT	
TITLE		SECTION A - 0.5m GAP; NO CRACK IN SOIL-BENTONITE WALL	
PROJECT No.		03-1413-427	FILE No. Section 3A10-8
DESIGN	DAH	08/OCT/03	SCALE N/A REV. 0
CADD	SRR	08/OCT/03	
CHECK	DAH	08/OCT/03	
REVIEW	KE	23 OCT 03	
		FIGURE II-A4	

Description: Meadowbank Dike Design
 Comments: 03-1413-427/4200
 File Name: Section 3A10-8_0.50m gap, 0.25m crack at 3m above bedrock.sez
 Last Saved Date: 20-Oct-2003
 Last Saved Time: 8:22:24 AM
 Analysis Type: Steady-State
 Analysis View: 2-D



NOTES

- 1) See section A on Figure 1.3
- 2) Cracks modelled as 0.25m thick.


MATERIAL HYDRAULIC CONDUCTIVITY (m/s)

Till core	1×10^{-5}
Rockfill	1×10^{-2}
Overburden	1×10^{-5}
Soil-bentonite backfill	1×10^{-8}
Bedrock	1×10^{-7}

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT				
TITLE		SECTION A - 0.5m GAP; CRACK IN SOIL-BENTONITE WALL WITHIN OVERBURDEN				
 Golder Associates		PROJECT No.	03-1413-427		FILE No.	Section 3A10-8
		DESIGN	DAH	09/OCT/03	SCALE	N/A
		CADD	SRR	09/OCT/03	REV.	
		CHECK	DAH	09/OCT/03	FIGURE II-A5	
		REVIEW	ZC	23 Oct 03		



Description: Meadowbank Dike Design
 Comments: 03-1413-427/4200
 File Name: Section 3A10-8_0.50m gap, 0.25m
 crack at 2m above bedrock.sez
 Last Saved Date: 20-Oct-2003
 Last Saved Time: 8:20:56 AM
 Analysis Type: Steady-State
 Analysis View: 2-D



NOTES

- 1) See section A on Figure 1.3
- 2) Cracks modelled as 0.25m thick.


MATERIAL HYDRAULIC CONDUCTIVITY (m/s)

Till core	1×10^{-5}
Rockfill	1×10^{-2}
Overburden	1×10^{-5}
Soil-bentonite backfill	1×10^{-8}
Bedrock	1×10^{-7}

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE		SECTION A - 0.5m GAP; CRACK IN SOIL-BENTONITE WALL WITHIN TILL CORE			
PROJECT No.		03-1413-427	FILE No.		Section 3A10-8
DESIGN	DAH	06/OCT/03	SCALE	N/A	REV. 0
CADD	SRR	06/OCT/03	FIGURE II-A6		
CHECK	DAH	06/OCT/03			
REVIEW	KE	23/OCT/03			



Description: Meadowbank Dike Design
 Comments: 03-1413-427/4200
 File Name: Section 3B10-8_no gap, no crack.sez
 Last Saved Date: 10/15/2003
 Last Saved Time: 11:36:13 AM
 Analysis Type: Steady-State
 Analysis View: 2-D



NOTES


- 1) See section B on Figure 1.3

MATERIAL HYDRAULIC CONDUCTIVITY (m/s)	
Till core	1×10^{-5}
Rockfill	1×10^{-2}
Overburden	1×10^{-5}
Soil-bentonite backfill	1×10^{-8}
Bedrock	2.2×10^{-7}

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT			
TITLE		SECTION B - NO GAP OR CRACK IN SOIL-BENTONITE WALL			
		PROJECT No.	03-1413-427	FILE No.	Section 3B10-8
		DESIGN	DAH 06/OCT/03	SCALE	N/A REV. 0
		CADD	SRR 06/OCT/03	FIGURE II-B1	
		CHECK	DAH 06/OCT/03		
		REVIEW	KE 23 OCT 03		



Description: Meadowbank Dike Design
Comments: 03-1413-427/4200
File Name: Section 3B10-8_no gap, 0.25m crack
at 1.5m above bedrock (OB).sez
Last Saved Date: 10/16/2003
Last Saved Time: 2:28:38 PM
Analysis Type: Steady-State
Analysis View: 2-D



NOTES

- 1) See section B on Figure 1.3
- 2) Cracks modelled as 0.25m thick.


MATERIAL HYDRAULIC CONDUCTIVITY (m/s)	
Till core	1×10^{-5}
Rockfill	1×10^{-2}
Overburden	1×10^{-5}
Soil-bentonite backfill	1×10^{-8}
Bedrock	2.2×10^{-7}

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT	
TITLE		SECTION B - NO GAP; CRACK IN SOIL-BENTONITE WALL WITHIN OVERBURDEN	
PROJECT No.		03-1413-427	FILE No. Section 3B10-8
DESIGN	DAH	06/02/03	SCALE N/A REV. 0
CADD	SRR	06/02/03	
CHECK	DAH	06/02/03	
REVIEW	JLC	23 OCT 03	



FIGURE II-B2

Description: Meadowbank Dike Design
 Comments: 03-1413-427/4200
 File Name: Section 3B10-8_no gap, 0.25m crack
 at 3m above bedrock (till).sez
 Last Saved Date: 10/15/2003
 Last Saved Time: 5:03:16 PM
 Analysis Type: Steady-State
 Analysis View: 2-D



NOTES

- 1) See section B on Figure 1.3
- 2) Cracks modelled as 0.25m thick.


MATERIAL HYDRAULIC CONDUCTIVITY (m/s)	
Till core	1×10^{-5}
Rockfill	1×10^{-2}
Overburden	1×10^{-5}
Soil-bentonite backfill	1×10^{-8}
Bedrock	2.2×10^{-7}

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT	
TITLE		SECTION B - NO GAP; CRACK IN SOIL-BENTONITE WALL WITHIN TILL CORE	
PROJECT No.		03-1413-427	FILE No. Section 3B10-8
DESIGN	DAH	06OCT03	SCALE: N/A REV. 0
CADD	SRR	06OCT03	
CHECK	DAH	06OCT03	
REVIEW	KE	23oct03	



FIGURE II-B3

Description: Meadowbank Dike Design
 Comments: 03-1413-427/4200
 File Name: Section 3B10-8_0.50m gap, no crack.sez
 Last Saved Date: 10/15/2003
 Last Saved Time: 11:57:30 AM
 Analysis Type: Steady-State
 Analysis View: 2-D



NOTES

- 1) See section B on Figure 1.3


MATERIAL HYDRAULIC CONDUCTIVITY (m/s)

Till core	1×10^{-5}
Rockfill	1×10^{-2}
Overburden	1×10^{-5}
Soil-bentonite backfill	1×10^{-8}
Bedrock	2.2×10^{-7}

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT	
TITLE		SECTION B - 0.5m GAP; NO CRACK IN SOIL-BENTONITE WALL	
PROJECT No.		03-1413-427	FILE No. Section 3B10-8
DESIGN	DAH	06OCT03	SCALE: N/A REV. 0
CADD	SRR	06OCT03	FIGURE II-B4
CHECK	DAH	06OCT03	
REVIEW	JKC	23 OCT 03	



Description: Meadowbank Dike Design
Comments: 03-1413-427/4200
File Name: Section 3B10-8_0.50m gap, 0.25m crack at 1.5m above bedrock (OB) sez
Last Saved Date: 10/16/2003
Last Saved Time: 2:33:20 PM
Analysis Type: Steady-State
Analysis View: 2-D



NOTES

- 1) See section B on Figure 1.3
- 2) Cracks modelled as 0.25m thick.


MATERIAL HYDRAULIC CONDUCTIVITY (m/s)	
Till core	1×10^{-5}
Rockfill	1×10^{-2}
Overburden	1×10^{-5}
Soil-bentonite backfill	1×10^{-8}
Bedrock	2.2×10^{-7}

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT	
TITLE		SECTION B - 0.5m GAP; CRACK IN SOIL-BENTONITE WALL WITHIN OVERBURDEN	
PROJECT No.		03-1413-427	FILE No. Section 3B10-8
DESIGN	DAH	06/OCT/03	SCALE N/A REV. 0
CADD	SRR	06/OCT/03	
CHECK	DAH	06/OCT/03	
REVIEW	ZCE	23/OCT/03	



FIGURE II-B5

Description: Meadowbank Dike Design
 Comments: 03-1413-427/4200
 File Name: Section 3B10-8_0.50m gap, 0.25m crack at 3m above bedrock (till).sez
 Last Saved Date: 10/15/2003
 Last Saved Time: 12:00:25 PM
 Analysis Type: Steady-State
 Analysis View: 2-D



NOTES

- 1) See section B on Figure 1.3
- 2) Cracks modelled as 0.25m thick.

MATERIAL HYDRAULIC CONDUCTIVITY (m/s)	
Till core	1×10^{-5}
Rockfill	1×10^{-2}
Overburden	1×10^{-5}
Soil-bentonite backfill	1×10^{-8}
Bedrock	2.2×10^{-7}

PROJECT		CUMBERLAND RESOURCES LTD. MEADOWBANK GOLD PROJECT NUNAVUT	
TITLE		SECTION B - 0.5m GAP; CRACK IN SOIL-BENTONITE WALL WITHIN TILL CORE	
PROJECT No.		03-1413-427	FILE No. Section 3B10-8
DESIGN	DAH	08/OCT/03	SCALE N/A REV. 0
CADD	SRR	08/OCT/03	
CHECK	DAH	08/OCT/03	
REVIEW	KE	23/NOV/03	



FIGURE II-B6

APPENDIX III

PRELIMINARY MATERIALS BALANCE

Meadowbank Mined Tonnages and Volumes

Year		2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	Total
TONNES	Assumptions	-2	-1	1	2	3	4	5	6	7	8	9	10	11	
Mined Ore Open Pit			514492	1352183	1866975	3595715	1866975	1866975	1866975	1866975	1866975	1866975	1478244	1478244	21487703
Grade			7	5	4	4	4	4	4	4	3	4	6	6	4
Recovery	t	-	1	1	1	1	1	1	1	1	1	1	1	1	
Tailings Produced	t	-	514489	1352176	1866968	3595702	1866968	1866967	1866968	1866968	1866969	1866968	1478235	1478235	21487613
Portage Pit															
Overburden	t	-	915145	1181899	344052	1415052	858362	0	0	0	0	0	0	0	4714510
UM	t	-	161424	870165	2047706	2606760	4030192	2756831	2869373	4230059	2320748	2422948	680212	53835	25050256
IV	t	-	1350376	3505432	3766198	4674081	3716710	3329997	2872252	2808018	1860802	1610966	905506	312928	30713265
IF	t	-	1749376	3096487	3468825	3693520	3131945	2601659	2692840	1744856	608850	426829	127400	45150	23387736
QZ	t	-	1013	138407	161194	541603	125157	186388	16364	0	0	0	0	0	1170126
Total	t	0	4177333	8792390	9787975	12931016	11862366	8874875	8450830	8782934	4790400	4460743	1713119	411913	85035893
Goose Island Pit															
Overburden	t	-	0	0	0	0	0	0	1028930	151364	0	0	0	0	1180294
UM	t	-	0	0	0	0	0	0	494268	2632476	3196324	2391415	812413	0	9526897
IF	t	-	0	0	0	0	0	0	354271	466229	453435	626081	663942	0	2563958
IV	t	-	0	0	0	0	0	0	572477	943310	1068105	815196	232219	0	3631307
QZ	t	-	0	0	0	0	0	0	133913	484366	143185	0	0	0	761463
Total	t	0	0	0	0	0	0	0	2583859	4677745	4861049	3832692	1708575	0	17663920
Vault Pit															
Overburden	t	-	0	0	0	0	0	0	0	0	0	0	0	0	0
UM	t	-	0	0	0	0	0	0	0	0	0	0	0	0	0
IF	t	-	0	0											0
IV	t	-	0	5870425	6719315	3547203	4815741	7336539	6864792	4495692	6765350	4826036	2298941		53540034
QZ	t	-	0	0	0	0	0	0	0	0	0	0	0	0	0
Total	t	-	0	5870425	6719315	3547203	4815741	7336539	6864792	4495692	6765350	4826036	2298941	0	53540034
ALL PITS															
Overburden	t	-	915145	1181899	344052	1415052	858362	0	1028930	151364	0	0	0	0	5894804
UM	t	-	161424	870165	2047706	2606760	4030192	2756831	3363641	6862535	5517072	4814364	1492626	53835	34577153
IF	t	-	1350376	3505432	3766198	4674081	3716710	3329997	3226523	3274247	2314237	2237047	1569448	312928	33277223
IV	t	-	1749376	8966911	10188140	7240723	7947686	9938197	10130110	7183858	8442305	6068060	2658560	45150	80559077
QZ	t	-	1013	138407	161194	541603	125157	186388	150277	484366	143185	0	0	0	1931590
Total Pit	t	-	4177333	14662815	16507291	16478219	16678107	16211414	17899481	17956370	16416799	13119471	5720635	411913	155827935
VOLUMES															
Portage and Goose Pits															
Construction Rock Required															
Overburden	m3	0	0	0	0	0	0	0	0	0	0	0	0	0	
UM+QZ	m3	0	89380	0	0	0	0	29483	0	0	0	0	0	0	118864
IF	m3	0	0	0	0	0	0	0	0	0	0	0	0	0	0
IV	m3	0	301632	0	0	0	0	0	0	0	0	0	0	0	301632
Dike Rock Required															
Overburden	m3	0	323101	62728	62728	62728	62728	331728	62728	62728	62728	62728	0	0	1156652
UM+QZ	m3	0	0	19138	0	0	0	11082	0	0	0	0	0	0	30220
IF	m3	0	375132	0	0	0	0	426000	0	0	0	0	0	0	801132
IV	m3	0	400223	62728	62728	62728	62728	488728	62728	62728	62728	62728	0	0	1390774
Capping Volume Required															
UM+QZ	m3	0	0	236364	676364	676364	676364	676364	676364	676364	676364	676364	676364	2576364	8900000
Portage Waste Rock Dump															
Overburden	m3	0	158554	559324	118352	682036	389042	-331728	478814	16937	-62728	-62728	0	0	1945876
Overburden Cumulative	m3	0	158554	717878	836230	1518267	1907308	1575581	2054395	2071332	2008604	1945876	1945876	1945876	1945876
UM+QZ	m3	0	-3887	275326	486216	980670	1510662	832134	1173067	3190426	2302719	1857512	109229	-2548029	10166044
UM+QZ Cumulative	m3	0	-3887	271438	757654	1738323	3248986	4081120	5254187	8444613	10747332	12604844	12714073	10166044	10166044
IF	m3	0	545592	1629730	1825697	1943958	1648392	943294	1603743	1163729	559098	554163	416496	23763	12857655
IV	m3	0	8869	1782236	1919481	1263902	1893435	1263902	1750287	1911655	1478802	1214199	598803	164699	16383684
Net Waste Rock	m3	0	863794	5235932	5943631	9260569	10597825	8364303	12314493	16798694	17033827	18113868	15784477	9752353	130063767
Cumulative Waste Rock	m3	0	863794	6099727	12043358	21303926	31901752	40266054	52580548	69379242	86413069	104526937	120311414	130063767	130063767
Vault Pit															
Construction and Dike Rock Required															
Overburden	m3	0	14557	0	0	0	0	0	0	0	0	0	0	0	14557
IV	m3	0	41152	0	0	0	0	0	0	0	0	0	0	0	41152
Capping UM+QZ Required	m3	0	0	0	440000	440000	440000	440000	440000	440000	440000	440000	440000	440000	4400000
Vault Pit Dump															
Overburden	m3	0	-14557	0	0	0	0	0	0	0	0	0	0	0	-14557
IV	m3	0	-41152	3089697	3536482	1866949	2534600	3861336	3613048	2366153	3560710	2540019	1209969	0	28137813
Net Waste Rock	m3	0	-55709	3089697	3536482	1866949	2534600	3861336	3613048	2366153	3560710	2540019	1209969	0	28123256
Cumulative Waste Rock	m3	0	-55709	3033988	6570470	8437419	10972020	14833356	18446405	20812558	24373268	26913287	28123256	28123256	28123256
Tailings Produced	m3	0	233858	614626	848622	1634410	848622	848621	848622	848622	848622	848622	671925	671925	9767097
Cumulative Tailings	m3	0	233858	848484	1697106	3331515	4180137	5028759	5877381	6726002	7574625	8423247	9095172	9767097	9767097

[illegible]

12345678										12345678										12345678										
3										4										5										
		Portage			Vault		Goose		Total			Portage			Vault		Goose		Total			Portage			Vault		Goose		Total	
starter	lower	south	north	starter	middle	end	only	Total	starter	lower	south	north	starter	middle	end	only	Total	starter	lower	south	north	starter	middle	end	only	Total	ore tonnes			
ore tonnes	138,235	965,309	11,852	216,034	535,545			1,866,975	ore tonnes	1,080,258	54,527	119,051	522,444	59,944	30,751		1,866,975	ore tonnes	471,261		673,388	389,436	332,890			1,866,975	ore tonnes			
grade	6.39	3.66	3.86	4.06	4.04			4.02	grade	4.36	4.35	4.83	3.65	2.07	1.51		4.07	grade	4.45		5.38	4.48	2.42			4.43	grade			
low grade		39,445	3,407	72	30,435			73,360	low grade	41,904	35,327	1,503	32,749	7,972	2,064		121,519	low grade	7,140		18,399	5,428	51,257			82,224	low grade			
grade		1.29	1.07	1.45	1.10			1.20	grade	1.32	1.04	1.44	1.19	1.66	1.24		1.23	grade	1.27		1.37	1.06	1.15			1.20	grade			
ovbd			737,125	679,722				1,416,847	ovbd			781,066	77,539				858,605	ovbd									ovbd			
IV_CHLOR									IV_CHLOR									IV_CHLOR									IV_CHLOR			
ULT_MAF	65,950	1,740,999	7,935	710,297				2,525,181	ULT_MAF	2,723,297	978,124	328,351					4,029,771	ULT_MAF	1,484,999		1,250,671					2,735,669	ULT_MAF			
IR_FORM	137,590	2,184,916	149,618	2,226,190				4,698,314	IR_FORM	1,728,094	1,044,928	958,608					3,731,630	IR_FORM	605,213		2,745,498					3,350,711	IR_FORM			
INT_VOLC	67,125	1,628,845	141,713	1,873,103				3,710,787	INT_VOLC	1,259,975	1,008,522	874,876					3,143,374	INT_VOLC	302,488		2,314,172					2,616,660	INT_VOLC			
QUARTZ_V									QUARTZ_V									QUARTZ_V									QUARTZ_V			
MAF_VOL				96,655				96,655	MAF_VOL				20,300				20,300	MAF_VOL				45,140				45,140	MAF_VOL			
FEL_POR									FEL_POR									FEL_POR									FEL_POR			
QTZITE				543,037				543,037	QTZITE				125,550				125,550	QTZITE				187,312				187,312	QTZITE			
G_R									G_R									G_R									G_R			
Waste					3,557,078			3,557,078	Waste				2,130,985	1,924,340	767,241		4,822,566	Waste				734,823	6,625,600			7,360,423	Waste			
	1.96	5.80	87.73	28.37	6.70			16,547,900		5.33	70.57	20.05	4.14	32.24	25.02		16,731,796		5.09		9.74	1.90	20.06			16,295,916				
		Portage				Vault	Goose				Portage			Vault		Goose			Portage			Vault		Goose						


ore tonnes	138,235	965,309	11,852	216,034	535,545			1,866,975	ore tonnes	1,080,258	54,527	119,051	522,444	59,944	30,751			1,866,975	ore tonnes	471,261		673,388	389,436	332,890			1,866,975	ore tonnes
grade	6.39	3.66	3.86	4.06	4.04			4.02	grade	4.36	4.35	4.83	3.65	2.07	1.51			4.07	grade	4.45		5.38	4.48	2.42			4.43	grade
dilution	10,405	72,658	892	16,261	40,310			140,525	dilution	81,310	4,104	8,961	39,324	4,512	2,315			140,525	dilution	35,471		50,685	29,312	25,056			140,525	dilution
dilution gra	1.00	1.16	1.07	1.00	1.08			1.10	dilution gra	1.16	1.04	1.07	1.16	1.66	1.22			1.17	dilution gra	1.05		1.13	1.01	1.15			1.09	dilution gra
LG Dilution		39,445	892	72	30,435			70,845	LG Dilution	41,904	4,104	1,503	32,749	4,512	2,064			86,837	LG Dilution	7,140		18,399	5,428	25,056			56,023	LG Dilution
barren dilu	10,405	33,212		16,188	9,875			69,680	barren dilu	39,406		7,458	6,575		251			53,689	barren dilu	28,331		32,286	23,884				84,502	barren dilu
Feed								2,007,500	Feed									2,007,500	Feed								2,007,500	Feed
grade								3.82	grade									3.87	grade								4.20	grade
to Waste Dump									to Waste Dump										to Waste Dump									to Waste D
low grade			2,515					2,515	low grade		31,222			3,460				34,682	low grade				26,201				26,201	low grade
ovbd			737,125	677,927				1,415,052	ovbd		781,066	77,296						858,362	ovbd									ovbd
IV_CHLOR									IV_CHLOR										IV_CHLOR									IV_CHLOR
ULT_MAF	63,414	1,730,590	7,935	708,421				2,510,360	ULT_MAF	2,704,508	978,124	327,324						4,009,955	ULT_MAF	1,467,415		1,244,499					2,711,914	ULT_MAF
IR_FORM	132,301	2,171,852	149,618	2,220,310				4,674,081	IR_FORM	1,716,171	1,044,928	955,610						3,716,710	IR_FORM	598,047		2,731,950					3,329,997	IR_FORM
INT_VOLC	64,545	1,619,106	141,713	1,868,156				3,693,520	INT_VOLC	1,251,282	1,008,522	872,140						3,131,945	INT_VOLC	298,906		2,302,753					2,601,659	INT_VOLC
QUARTZ_v									QUARTZ_v										QUARTZ_v									QUARTZ_v
MAF_VOL				96,400				96,400	MAF_VOL				20,237					20,237	MAF_VOL				44,917				44,917	MAF_VOL
FEL_POR									FEL_POR										FEL_POR									FEL_POR
QTZITE				541,603				541,603	QTZITE				125,157					125,157	QTZITE				186,388				186,388	QTZITE
G_R									G_R										G_R									G_R
Waste					3,547,203			3,547,203	Waste				2,124,410	1,924,340	766,990			4,815,741	Waste				710,939	6,625,600			7,336,539	Waste

6										7										8														
Portage			Vault			Goose				Portage			Vault			Goose				Portage			Vault			Goose								
starter	lower	south	north	starter	middle	end	only	Total	ore tonnes	starter	lower	south	north	starter	middle	end	only	Total	ore tonnes	starter	lower	south	north	starter	middle	end	only	Total	ore tonnes					
	142,790	40,145	875,541	130,061	565,542	28,811	84,085	1,866,975	ore tonnes		610,642	77,001	408,961		542,769	17,391	210,211	1,866,975	ore tonnes		351,992	82,637	133,415		901,437	125,549	271,945	1,866,975	ore tonnes					
	4.44	3.83	4.42	5.86	2.56	1.59	2.95	3.84	grade		4.97	4.04	5.03		2.58	2.26	3.15	4.02	grade		5.29	3.23	4.63		2.55	1.98	4.52	3.49	grade					
	331	6,835	12,140		44,124	934	2,171	66,536	low grade			6,893	613		30,646	9,286	7,549	54,987	low grade		281	4,137			47,620	14,199	972	67,210	low grade					
	1.42	1.05	1.38		1.39	1.32	1.45	1.35	grade			1.16	1.09		1.06	0.89	1.31	1.08	grade		1.28	1.28			1.19	0.98	1.25	1.15	grade					
							1,030,585	1,030,585	ovbd								151,632	151,632	ovbd										ovbd					
									IV_CHLOR										IV_CHLOR										IV_CHLOR					
	640,382	1,172,730	1,048,687				495,063	3,356,862	ULT_MAF		1,637,369	2,185,410	441,840				2,637,132	6,901,751	ULT_MAF		467,659	1,732,541	136,512				3,209,144	5,545,856	ULT_MAF					
	232,220	808,136	1,853,670				354,841	3,248,867	IR_FORM		704,563	1,465,780	659,310				467,053	3,296,707	IR_FORM		481,356	1,239,375	156,485				455,254	2,332,470	IR_FORM					
	161,385	372,584	2,183,390				573,398	3,290,757	INT_VOLC		327,754	445,550	991,489				944,978	2,709,771	INT_VOLC		64,012	350,000	200,798				1,072,389	1,687,199	INT_VOLC					
									QUARTZ_V										QUARTZ_V										QUARTZ_V					
			25,286					25,286	MAF_VOL										MAF_VOL										MAF_VOL					
									FEL_POR										FEL_POR										FEL_POR					
			16,537				134,129	150,666	QTZITE								485,222	485,222	QTZITE								143,759	143,759	QTZITE					
									G_R										G_R										G_R					
				87,630	4,784,542	2,003,644		6,875,816	Waste						3,201,482	1,304,417		4,505,899	Waste						3,348,022	3,437,558		6,785,580	Waste					
	7.24	58.79	5.87	0.67	8.54	69.58	30.80	17,978,840			4.37	53.29	5.12		5.95	75.54	22.33	18,050,983			2.88	40.25	3.70		3.77	27.49	17.95	16,494,864						
	Portage				Vault			Goose				Portage				Vault			Goose					Portage				Vault			Goose			
	142,790	40,145	875,541	130,061	565,542	28,811	84,085	1,866,975	ore tonnes		610,642	77,001	408,961		542,769	17,391	210,211	1,866,975	ore tonnes		351,992	82,637	133,415		901,437	125,549	271,945	1,866,975	ore tonnes					
	4.44	3.83	4.42	5.86	2.56	1.59	2.95	3.84	grade		4.97	4.04	5.03		2.58	2.26	3.15	4.02	grade		5.29	3.23	4.63		2.55	1.98	4.52	3.49	grade					
	10,748	3,022	65,901	9,790	42,568	2,169	6,329	140,525	dilution		45,962	5,796	30,782		40,854	1,309	15,822	140,525	dilution		26,494	6,220	10,042		67,850	9,450	20,469	140,525	dilution					
	1.01	1.05	1.07	1.00	1.39	1.14	1.15	1.16	dilution gra		1.00	1.16	1.00		1.04	0.89	1.15	1.04	dilution gra		1.00	1.19	1.00		1.13	0.98	1.01	1.07	dilution gra					
	331	3,022	12,140		42,568	934	2,171	61,166	LG Dilution			5,796	613		30,646	1,309	7,549	45,913	LG Dilution		281	4,137			47,620	9,450	972	62,461	LG Dilution					
	10,416		53,761	9,790		1,235	4,158	79,359	barren dilu		45,962		30,169		10,207		8,274	94,613	barren dilu		26,213	2,083	10,042		20,230		19,497	78,065	barren dilu					
								2,007,500	Feed									2,007,500	Feed									2,007,500	Feed					
								3.65	grade									3.81	grade									3.32	grade					
ump									to Waste Dump										to Waste Dump										to Waste Dump					
		3,813			1,556			5,369	low grade			1,097				7,977		9,074	low grade						4,749		4,749	low grade						
							1,028,930	1,028,930	ovbd								151,364	151,364	ovbd										ovbd					
									IV_CHLOR										IV_CHLOR										IV_CHLOR					
		633,931	1,172,730	1,037,691			494,268	3,338,620	ULT_MAF		1,609,179	2,185,410	435,470				2,632,476	6,862,535	ULT_MAF		455,558	1,731,455	133,735				3,196,324	5,517,072	ULT_MAF					
		229,880	808,136	1,834,235			354,271	3,226,523	IR_FORM		692,433	1,465,780	649,805				466,229	3,274,247	IR_FORM		468,901	1,238,598	153,303				453,435	2,314,237	IR_FORM					
		159,759	372,584	2,160,497			572,477	3,265,318	INT_VOLC		322,111	445,550	977,195				943,310	2,688,166	INT_VOLC		62,355	349,781	196,714				1,068,105	1,676,955	INT_VOLC					
									QUARTZ_V										QUARTZ_V										QUARTZ_V					
									25,021	MAF_VOL										MAF_VOL									MAF_VOL					
										FEL_POR										FEL_POR									FEL_POR					
			16,364				133,913	150,277	QTZITE								484,366	484,366	QTZITE								143,185	143,185	QTZITE					
									G_R										G_R										G_R					
				77,841	4,784,542	2,002,409		6,864,792	Waste						3,191,275	1,304,417		4,495,692	Waste						3,327,792	3,437,558		6,765,350	Waste					

APPENDIX IV
SAMPLE EXCAVATORS

- Shipping Dimensions
- Major Component Weights

Excavators



LONG REACH ATTACHMENT SHIPPING DIMENSIONS

Model	320B L		320 L*		322B L		317 L	
	m	ft	m	ft	m	ft	m	ft
A Overall Transport Length (Boom Folded)	12.65	41'6"	12.69	42'7"	14.24	46'9"	11.23	36'10"
B Overall Height (To Top of Boom)	3.21	10'6"	3.36	10'0"	3.17	10'5"	2.93	9'7"
Overall Width (To Widest Point)	3.18	10'5"	3.7	12'2"	3.29	11'1"	2.48	8'2"

*Belgian sourced. Extra with gauge and 860 mm (35") track shoes.
 Note: For other main machine dimensions, see section on machines with GP attachments.

LONG REACH ATTACHMENT COMPONENT WEIGHTS

Model	320B L		320 L*		322B L		317 L	
	kg	lb	kg	lb	kg	lb	kg	lb
Additional Counterweight	980	2116	1100	2425	1450	3197	—	—
Long Reach Boom: Includes boom, stick cylinder, hydraulic lines, and pins for stick, stick cylinder, and boom rod end	2185	4917	2504	5519	3130	6900	1610	3560
Long Reach Stick: Includes stick, bucket linkage and pins, bucket cylinder and pin, and hydraulic lines	1200	2778	1290	2841	1570	3461	993	2185

*Belgian sourced. Includes extra wide gauge and reinforced underframe.

Excavators

Long Reach

- Introduction
- Arrangement Description
- Range Dimensions

INTRODUCTION

Long reach excavators are designed specifically for those jobs requiring reach capability beyond the range of normal excavators. Applications for which long reach excavators are ideally suited include ditch cleaning, slope finishing, river conservation, and other work formerly reserved for draglines.


Caterpillar offers two hydraulic excavator models in long reach arrangements. Each model uses purpose-built booms and sticks designed by Caterpillar for maximized performance and durability.

320 L LONG REACH

325 L LONG REACH

Long Reach Front Includes: Boom, stick, linkage cylinders (boom, stick, and bucket), hydraulic lines, and additional counterweight for stability while working over the side. Dimensions include ditch cleaning bucket.

Note: All dimensions are with ditch cleaning bucket.



Long Reach Model	320B L		320 L*		322B L		317 L	
	mm	ft	mm	ft	mm	ft	mm	ft
A Maximum Reach at Ground Level	16 725	51'7"	16 540	54'3"	16 430	50'6"	13 000	42'5"
B Maximum Digging Depth	11 880	39'0"	12 800	42'0"	14 720	48'4"	10 100	33'2"
C Maximum Cutting Height	13 290	43'7"	13 400	43'11"	14 230	46'8"	11 640	38'2"
D Maximum Dumping Height	11 010	36'1"	11 350	37'3"	12 005	39'5"	10 670	35'0"
E Minimum Loading Height	1970	6'6"	2300	7'6"	1360	4'8"	980	3'1"

320B L • Long Reach • Japan/U.S. Sourced

Bucket Type	Bucket Width		Tip Radius		SAE Hooped Cap.		Bucket Weight		No. of Teeth	Bucket Curl Force		Stick Crowd Force	
	mm	in	mm	in	L	yd ³	kg	lb		kN	lb	kN	lb
General Purpose	810	32	1220	48	150	0.59	365	805	5	—	—	—	—
Ditch Cleaning	1140	45	1080	43	800	0.78	200	517	0	—	—	—	—

320 L* • Long Reach • Belgium Sourced

General Purpose	—	—	—	—	—	—	—	—	—	—	—	—	—
Ditch Cleaning	1600	70.8	780	30.7	600	0.78	400	882	—	63.25	14,231	82.82	14,134

322B L • Long Reach • Japan/U.S. Sourced

General Purpose	700	28	1220	48	350	0.58	355	739	4	—	—	—	—
Ditch Cleaning	995	39	1090	43	480	0.63	265	584	0	—	—	—	—


317 • Long Reach • France Sourced


General Purpose	—	—	—	—	—	—	—	—	—	—	—	—	—
Ditch Cleaning	1010	40	1310	52	500	0.66	350	770	0	—	—	—	—

*Belgium sourced.

1266

KOEHRING	DESCRIPTION	DIG DEPTH	REACH
1266	w/ medium front (265,000#)	31 feet	50 feet
	w/ long front	39.5 feet	61 feet
	w/ extended arm - 1250	67 feet	89 feet
	w/ extended arm - 1258-2	75 feet	98 feet
	w/ extended arm - 1275-2	91 feet	114 feet
	w/ extended boom/arm - 1250-40	75 feet	98 feet
	w/ extended boom/arm - 1258-2-40	79 feet	102 feet





Long Reach Model	A	B	C	D	E
LR 2/50	10' - 1"	33' - 2"	51' - 2"	38' - 1"	36' - 8"
LR 2/60	10' - 6"	39' - 0"	60' - 2"	45' - 0"	43' - 9"
LR 3/55	10' - 11"	35' - 4"	54' - 11"	44' - 5"	40' - 2"
LR 3/60	11' - 6"	39' - 1"	60' - 6"	47' - 9"	43' - 10"
LR 4/55	12' - 9"	37' - 5"	58' - 1"	41' - 11"	36' - 9"
LR 4/60	12' - 8"	39' - 7"	60' - 10"	46' - 4"	37' - 7"
LR 4/65	12' - 11"	42' - 1"	66' - 3"	48' - 7"	37' - 7"
LR 4/75	12' - 10"	47' - 0"	75' - 0"	57' - 2"	49' - 11"
LR 5/65	12' - 10"	42' - 0"	65' - 4"	48' - 1"	47' - 8"
LR 7/60	14' - 2"	40' - 3"	62' - 2"	45' - 8"	45' - 5"
LR 7/75	14' - 9"	49' - 3"	76' - 11"	59' - 10"	44' - 4"
LR 7/80	14' - 9"	51' - 1"	81' - 10"	60' - 10"	55' - 3"
LR 11/75	NA	NA	74' - 11"	56' - 2"	37' - 2"
LR 11/85	NA	NA	85' - 0"	66' - 0"	50' - 4"
LR 11/85			85' - 0"		
LR 11/100			100' - 0"		

APPENDIX V

GEOTECHNICAL BOREHOLE LOGS

PROJECT No.: 03-1413-427

RECORD OF BOREHOLE: 03GT-BZ-1

SHEET 1 OF 6

LOCATION: Bay Zone Dyke


DRILLING DATE: 07-Aug-03

DATUM: Local

N: 7213129.491 E: 639153.134

DRILL RIG: LF-70

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES			CORE			GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION		
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %			GRAVEL	SAND	FINES	WATER CONTENT PERCENT					
									80	60	40				20	Wp			W	Wi
0		Ground Surface		135.78 0.00																
1	HQ3	Coarse to fine gravel of granitic rock, rounded, slightly weathered (Ground surface to top of bedrock)			1	RC	1													
2																				
3		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.		133.62																
4																				
5																				
6																				
7																				
8																				
9																				
10																				

DEPTH SCALE

1 : 50



LOGGED: TS/MT

CHECKED: CJC

CUSTOM LOG 3 03-1413-427_OCT11_2003.GPJ GLDR_CAN.GDT 1/10/03

SHEET 2 OF 6

DATUM: Local

DRILL RIG: LF-70

DRILLING CONTRACTOR: Boart-Longyear

[illegible]

CHECKED: CJC

DRILLHOLE 03-1413-427 OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

SHEET 3 OF 6

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

[illegible]

DEPTH SCALE

1 : 50



LOGGED: TS/MT

CHECKED: CJC

SHEET 4 OF 6

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

[illegible]

DEPTH SCALE

1 : 50



LOGGED: TS/MT

CHECKED: CJC

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-BZ-1

SHEET 5 OF 6

LOCATION: Bay Zone Dyke

DRILLING DATE: 07-Aug-03

DATUM: Local

N: 7213129.491 E: 639153.134

DRILL RIG: LF-70

INCLINATION: -59.59°

AZIMUTH: 213°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (mm/min)	FLUSH	COLOUR % RETURN	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	MB-MECH. BREAK	NOTES WATER LEVELS INSTRUMENTATION									
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	B-BEDDING										
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY											
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED										
									RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX	WEATHERING INDEX							
									TOTAL CORE %	SOLID CORE %			DIP w.r.t CORE AXIS	TYPE AND SURFACE DESCRIPTION	R ₅	R ₄	R ₃	R ₂	R ₁	W ₁	W ₂	W ₃	W ₄
33	Boart-Longyear HQ3	Fresh, closely foliated, grey green, fine grained, medium strength. INTERMEDIATE VOLCANICS (continued)	▽▽▽																				

CONTINUED NEXT PAGE

DEPTH SCALE

1 : 50



LOGGED: TS/MT

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-BZ-1

SHEET 6 OF 6

LOCATION: Bay Zone Dyke

DRILLING DATE: 07-Aug-03

DATUM: Local

N: 7213129.491 E: 639153.134

DRILL RIG: LF-70

INCLINATION: -59.59°

AZIMUTH: 213°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	CORRELATION CHART																		NOTES WATER LEVELS INSTRUMENTATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
				ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	FLUSH	COLOUR % RETURN	FR-FRACTURE		F-FAULT		SM-SMOOTH		FL-FLEXURED		BC-BROKEN CORE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK	B-BEDDING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
VN-VEIN		S-SLICKENSIDED		PL-PLANAR	C-CURVED	CH-CHLORITIZED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX		WEATH- ERING INDEX																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
TOTAL CORE %	SOLID CORE %			DIP w.r.t. CORE AXIS	TYPE AND SURFACE DESCRIPTION	R ₂	R ₃	R ₁	W ₁	W ₂	W ₃	W ₄																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																</

DEPTH SCALE

1 : 50



LOGGED: TS/MT

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF BOREHOLE: 03GT-BZ-2

SHEET 1 OF 2

LOCATION: Bay Zone Dyke
N: 7212931 E: 639000

DRILLING DATE: 28-Apr-03

DATUM: Local

DRILL RIG: LY38

Reference: Ice Surface

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE			SAMPLES		CORE		GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s					ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %	GRAVEL	SAND	FINES	10 ⁻⁶ 10 ⁻⁵ 10 ⁻⁴ 10 ⁻³						
													WATER CONTENT PERCENT						
													Wp	W					Wi
								80 60 40 20					10	20	30	40			
0		Ice Surface		134.00 0.00															
1	HQ3	ICE																	
2				132.44 1.56															
3		LAKE WATER																	
4																			
5																			
6																			
7		Loose COBBLES and GRAVEL with trace sand composed of Granite		128.50 5.50															
8		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.		126.34															
9																			
10																			

DEPTH SCALE

1 : 50



LOGGED: JC/PP

CHECKED: CJC

CUSTOM LOG 3 03-1413-427_OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

SHEET 2 OF 2

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

DRILLHOLE 03-1413-427 OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

CHECKED: CJC

PROJECT No.: 03-1413-427

RECORD OF BOREHOLE: 03GT-BZ-3

SHEET 1 OF 2

LOCATION: Bay Zone Dyke
N: 7212991 E: 638793

DRILLING DATE: 29-Apr-03

DATUM: Local

DRILL RIG: LY38

Reference: Ice Surface

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES			CORE		GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION
		DESCRIPTION	STRATA PLOT	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %	GRAVEL	SAND	FINES	WATER CONTENT PERCENT					
0		Ice Surface															
1		ICE															
	HQ3	LAKE WATER															
2		GRAVEL and COBBLES															
3		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.															
4																	
5																	
6																	
7																	
8																	
9																	
10																	

DEPTH SCALE

1 : 50



LOGGED: JC/PP

CHECKED: CJC

CUSTOM LOG 3 03-1413-427_OCT11_2003.GPJ GLDR CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-BZ-3

SHEET 2 OF 2

LOCATION: Bay Zone Dyke
N: 7212991 E: 638793

DRILLING DATE: 29-Apr-03

DATUM: Local

INCLINATION: -90°

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (mm/min)	FLUSH	COLOUR % RETURN	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK	
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING	
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED	
RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX		WEATH- ERING INDEX						
TOTAL CORE %	SOLID CORE %			DIP w.r.t CORE AXIS	TYPE AND SURFACE DESCRIPTION	R1	R2	R3	R4	W1	W2	W3	W4	
80	80	80	80	0										
60	60	60	60	30										
40	40	40	40	60										
20	20	20	20	90										
0	0	0	0	120										
Continued from SOIL LOG.														
3	Boart-Longyear HQ3	Fresh to slightly weathered, light grey, fine grained/closely foliated, medium strength, INTERMEDIATE VOLCANICS with trace pyrite.	▽▽▽											

6.35m to 9.35
Falling Head
Packer Test
k=3.1x10⁻⁴ cm/s

DEPTH SCALE

1 : 50



LOGGED: JC/PP

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF BOREHOLE: 03GT-BZ-4

SHEET 1 OF 6

LOCATION: Bay Zone Dyke

DRILLING DATE: 06-Aug-03

DATUM: Local

N: 7213201.335 E: 638647.027

DRILL RIG: LF-70

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES			CORE			GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION		
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %			GRAVEL	SAND	FINES	WATER CONTENT PERCENT					
									80	60	40				20	Wp			W	Wi
0		Ground Surface		137.31 0.00																
1	HQ3	COBBLES with trace GRAVEL of Granite and Intermediate Volcanics			1	RC		1												
2				135.44																
3		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.																		
4																				
5																				
6																				
7																				
8																				
9																				
10																				

DEPTH SCALE

1 : 50



LOGGED: TS/MT

CHECKED: CJC

CUSTOM LOG 3 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

SHEET 2 OF 6

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

[illegible]

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

SHEET 3 OF 6

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

[illegible]

DEPTH SCALE

1 : 50



LOGGED: TS/MT

CHECKED: CJC

SHEET 4 OF 6

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

[illegible]

CHECKED: CJC

DRILLHOLE 03-1413-427 OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

SHEET 5 OF 6

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

[illegible]

CHECKED: CJC

DRILLHOLE 03-1413-427 OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-BZ-4

SHEET 6 OF 6

LOCATION: Bay Zone Dyke

DRILLING DATE: 06-Aug-03

DATUM: Local

N: 7213201.335 E: 638647.027

DRILL RIG: LF-70

INCLINATION: -51.39°

AZIMUTH: 155°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (mm/min)	FLUSH	COLOUR % RETURN	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION		
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK			
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING			
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED			
									RECOVERY		R.Q.D. %	DISCONTINUITY DATA			ROCK STRENGTH INDEX	
TOTAL CORE %	SOLID CORE %		FRACT. INDEX PER 0.25	DIP w.r.t. CORE AXIS	TYPE AND SURFACE DESCRIPTION	R5 R4 R3 R2 R1	W1 W2 W3 W4									
80 60 40 20	80 60 40 20	80 60 40 20	2 4 6 8	0 20 40 60 80												
43	Boart-Longyear HQ3	Fresh, closely foliated, light gray green, fine grained, medium strength, ULTRAMAFIC (with thin quartz layering) (continued)		29												
44				30												
45																
46																
47																
48		End of BOREHOLE.		99.80 48.00												
49																
50																
51																
52																

DEPTH SCALE

1 : 50



LOGGED: TS/MT

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT11_2003.GPJ GLDR_CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-BZ-5

SHEET 2 OF 2

LOCATION: Bay Zone
N: 7213096 E: 638703

DRILLING DATE: 30-31 May 03

DATUM: Local

INCLINATION: -90°

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	FLUSH % RETURN	COLOUR % RETURN	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK	
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING	
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED	
RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX		WEATH- ERING INDEX						
TOTAL CORE %	SOLID CORE %			DIP w.r.t. CORE AXIS	TYPE AND SURFACE DESCRIPTION	R ₂	R ₃	R ₁	W ₁	W ₂	W ₃	W ₄		
80 60 40 20	80 60 40 20	80 60 40 20	80 60 40 20	0 30 60 90										
1	8.41	1												
9														
10		2												
11		3												
12		4												
13														
14		5												
15		6												
16														
17														
18														

DEPTH SCALE

1 : 50



LOGGED: TS/CS

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF BOREHOLE: 03GT-BZ-6

SHEET 1 OF 2

LOCATION: Bay Zone
N: 7212952 E: 638906

DRILLING DATE: 31 May 03 - 01 June 03

DATUM: Local

DRILL RIG: LY38

Reference: Ice Surface

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES		CORE		GRADATION %		HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %	GRAVEL	SAND	FINES	10 ⁻⁶ 10 ⁻⁵ 10 ⁻⁴ 10 ⁻³																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
													WATER CONTENT PERCENT																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
													Wp			t	W	WI																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													</

DEPTH SCALE

1 : 50



LOGGED: TS/CS

CHECKED: CJC

CUSTOM LOG 3 03-1413-427_OCT11_2003.GPJ GLDR_CAN.GDT 1/10/03

SHEET 2 OF 2

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

CHECKED: CJC

DRILLHOLE 03-1413-427 OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF BOREHOLE: 03GT-GI-1

SHEET 1 OF 2

LOCATION: Goose Island Dyke
N: 7212775 E: 638924

DRILLING DATE: 29-Apr-03

DATUM: Local

DRILL RIG: LY38

Reference: Ice Surface

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE			SAMPLES			CORE			GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %	GRAVEL	SAND	FINES	WATER CONTENT PERCENT						
								80 60 40 20					10 ⁻⁶ 10 ⁻⁵ 10 ⁻⁴ 10 ⁻³	Wp	W	Wi			
0		Ice Surface		134.00 0.00										10	20	30	40		
1	HQ3	ICE																	
2		Single Boulder composed on INTERMEDIATE VOLCANICS.		132.39 1.61			1												
3				130.89 3.11															
4		COBBLES and GRAVEL with trace clay and sand composed of granite, quartz, and mafic volcanics.					2												
5		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.		129.08															
6																			
7																			
8																			
9																			
10																			

DEPTH SCALE

1 : 50



LOGGED: JC/PP

CHECKED: CJC

CUSTOM LOG 3 03-1413-427_OCT1_2003.GPJ GLDR CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-GI-1

SHEET 2 OF 2

LOCATION: Goose Island Dyke
N: 7212775 E: 638924

DRILLING DATE: 29-Apr-03

DATUM: Local

INCLINATION: -90°

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (mm/min)	FLUSH % RETURN	COLOUR (mm)	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION														
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK															
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING															
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED															
									RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX		WEATH- ERING INDEX											
									TOTAL CORE %	SOLID CORE %			DIP w.r.t. CORE AXIS	TYPE AND SURFACE DESCRIPTION		R ₅	R ₄	R ₃	R ₂	R ₁	W ₁	W ₂	W ₃	W ₄				
		Continued from SOIL LOG.		129.08 4.92																								
5		Fresh, weak close foliated, fine grained, light grey, strong strength, INTERMEDIATE VOLCANICS with trace stringers of quartz.		1																								
6																												
7																												
8																												
8	Boat-Longyear HQ3	Fresh, moderate to closely foliated, fine grained, grey, strong strength, INTERMEDIATE VOLCANIC, @8.88-9.09 fragment with foliation parallel to core axis.		3																								
9																												
10		Fresh, moderate to closely foliated, fine grained, grey, strong strength, INTERMEDIATE VOLCANIC, @11.0-11.25 mafic volcanic/quartz fragment/inclusion.		4																								
11																												
11		Fresh, moderate to closely foliated, fine-medium grained, grey-green, INTERMEDIATE VOLCANIC.		5																								
12																												
12																												
		End of BOREHOLE.		121.89 12.11																								
13																												
14																												

7.61m to 12.11m
Falling Head
Packer Test
k=2.5x10⁻⁶ cm/s

DEPTH SCALE

1 : 50



LOGGED: JC/PP

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT11_2003.GPJ GLDR CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF BOREHOLE: 03GT-GI-2

SHEET 1 OF 2

LOCATION: Goose Island Dyke
N: 7212535 E: 638938

DRILLING DATE: 6-May-03

DATUM: Local

DRILL RIG: LY38

Reference: Ice Surface

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES		CORE		GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION		
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %	GRAVEL	SAND	FINES	10 ⁻⁶ 10 ⁻⁵ 10 ⁻⁴ 10 ⁻³					
													WATER CONTENT PERCENT					
													Wp	W			Wi	
								80 60 40 20										
0		Ice Surface		134.00 0.00														
	HC3	ICE																
		COBBLES and Gravel																
		Silty Clay with some sand and trace gravel						1										
2		Sandy clay with gravel			131.79 2.21	1	DO	40			17.7	47.5	34.8					
									2									
3				130.99 3.01	2	SC				40.2	28.1	31.7	○					
		Sandy clay and gravel with cobbles						3										
4																		
					3	SC				35.8	30.1	34.1	○					
				129.49														
5		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.																
6																		
7																		
8																		
9																		
10																		

DEPTH SCALE

1 : 50



LOGGED: JC/PP

CHECKED: CJC

SHEET 2 OF 2

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

CHECKED: CJC

LOCATION: Goose Island Dyke
N: 7212073 E: 638912

DRILLING DATE: 7-May-03
DRILL RIG: LY38
DRILLING CONTRACTOR: Boart-Longyear

SHEET 1 OF 3

DATUM: Local

Reference: Ice Surface

DEPTH SCALE
1 : 50



LOGGED: JC/PP
CHECKED: CJC

CUSTOM LOG 3 03-1413-427 OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

SHEET 2 OF 3

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

[illegible]

DEPTH SCALE

1 : 50

LOGGED: JC/PP

CHECKED: CJC

PROJECT No.: 03-1413-427
LOCATION: Goose Island Dyke
N: 7212073 E: 638912
INCLINATION: -90°

RECORD OF DRILLHOLE: 03GT-GI-3

SHEET 3 OF 3
DATUM: Local

DRILLING DATE: 7-May-03
DRILL RIG: LY38
DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No. PENETRATION RATE (m/min)	FLUSH COLOUR % RETURN	FR-FRACTURE		F-FAULT		SM-SMOOTH		FL-FLEXURED		BC-BROKEN CORE		NOTES WATER LEVELS INSTRUMENTATION		
							CL-CLEAVAGE		J-JOINT		R-ROUGH		UE-UNEVEN		MB-MECH. BREAK				
							SH-SHEAR		P-POLISHED		ST-STEPPED		W-WAVY		B-BEDDING				
							VN-VEIN		S-SLICKENSIDED		PL-PLANAR		C-CURVED		CH-CHLORITIZED				
							RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX			WEATH- ERING INDEX			
TOTAL CORE %		SOLID CORE %		DIP w.r.t. CORE AXIS		TYPE AND SURFACE DESCRIPTION		R8			R4	R3	R2	R1	W1	W2	W3	W4	
		Continued from SOIL LOG.		122.20															
12	Boart-Longyear HQ3	Fresh, closely foliated, light grey, fine grained, medium strong, INTERMEDIATE VOLCANICS.	▽▽▽																

15.35m to 18.35m
Falling Head
Packer Test
k=1.3x10⁻⁴ cm/s

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR CAN.GDT 1/10/03

DEPTH SCALE
1 : 50



LOGGED: JC/PP
CHECKED: CJC

PROJECT No.: 03-1413-427
 LOCATION: Goose Island Dyke
 N: 7211999 E: 638676

RECORD OF BOREHOLE: 03GT-GI-4

DRILLING DATE: 7-May-03
 DRILL RIG: LY38
 DRILLING CONTRACTOR: Boart-Longyear

SHEET 1 OF 2
 DATUM: Local
 Reference: Ice Surface

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES		CORE		GRADATION %		HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION			
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %	GRAVEL	SAND	FINES	10 ⁻⁶ 10 ⁻⁵ 10 ⁻⁴ 10 ⁻³					
													WATER CONTENT PERCENT					
													Wp			W	Wi	
0		Ice Surface		134.00														
	HQ3	ICE		0.00														
1		COBBLES and gravel with trace sand and clay		133.39														
				0.61														
2																		
		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.		131.58														
3																		
4																		
5																		
6																		
7																		
8																		
9																		
10																		

CUSTOM LOG 3 03-1413-427_OCT1_2003.GPJ GLDR CAN.GDT 1/10/03

DEPTH SCALE
 1 : 50



LOGGED: JC/PP
 CHECKED: CJC

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-GI-4

SHEET 2 OF 2

LOCATION: Goose Island Dyke
N: 7211999 E: 638676

DRILLING DATE: 7-May-03

DATUM: Local

DRILL RIG: LY38

INCLINATION: -90°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (mm/min)	FLUSH COLOUR % RETURN	FR-FRACTURE		F-FAULT		SM-SMOOTH		FL-FLEXURED		BC-BROKEN CORE		NOTES WATER LEVELS INSTRUMENTATION
								CL-CLEAVAGE		J-JOINT		R-ROUGH		UE-UNEVEN		MB-MECH. BREAK		
								SH-SHEAR		P-POLISHED		ST-STEPPED		W-WAVY		B-BEDDING		
								VN-VEIN		S-SLICKENSIDED		PL-PLANAR		C-CURVED		CH-CHLORITIZED		
RECOVERY		R.Q.D. %		FRACT. INDEX PER 0.25		DISCONTINUITY DATA		ROCK STRENGTH INDEX		WEATH- ERING INDEX								
TOTAL CORE %	SOLID CORE %			DIP w.r.t CORE AXIS	TYPE AND SURFACE DESCRIPTION		R ₁	R ₂	R ₃	R ₄	W ₁	W ₂	W ₃	W ₄				
80 60 40 20	80 60 40 20	80 60 40 20	80 60 40 20	0 30 60 90														
Continued from SOIL LOG.																		
131.58																		
2.42																		
1																		
Fresh, weak to moderate spaced foliation, light grey, fine grained, medium strong to strong, INTERMEDIATE VOLCANICS.																		
2																		
3																		
127.99																		
6.01																		
4																		
Fresh, weak to moderate spaced foliation, light grey, fine to medium grained, medium strong to strong, INTERMEDIATE VOLCANICS.																		
126.49																		
7.51																		
5																		
Fresh, moderate spaced foliation, light grey, fine, medium strong to strong, INTERMEDIATE VOLCANICS.																		
124.99																		
9.01																		
End of BOREHOLE.																		

DEPTH SCALE

1 : 50



LOGGED: JC/PP

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF BOREHOLE: 03GT-GI-5

SHEET 1 OF 2

LOCATION: Goose Island Dyke
N: 7212091 E: 638502

DRILLING DATE: 8-May-03

DATUM: Local

DRILL RIG: LY38

Reference: Ice Surface

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE			SAMPLES		CORE		GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %	GRAVEL	SAND	FINES	10 ⁻⁶ 10 ⁻⁵ 10 ⁻⁴ 10 ⁻³					
													WATER CONTENT PERCENT					
													Wp	W	Wi			
								80 60 40 20					10	20	30	40		
0		Ice Surface		134.00 0.00														
1	HQ3	ICE																
2		LAKE WATER		132.19 1.81														
3		GRAVEL composed of granite (very little sample collected from rock coring)		131.59 2.41														
4																		
5		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.		129.74														
6																		
7																		
8																		
9																		
10																		

DEPTH SCALE

1 : 50



LOGGED: JC/PP

CHECKED: CJC

CUSTOM LOG 3 03-1413-427_OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-GI-5

SHEET 2 OF 2

LOCATION: Goose Island Dyke
N: 7212091 E: 638502

DRILLING DATE: 8-May-03

DATUM: Local

INCLINATION: -90°

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	FLUSH	COLOUR % RETURN	FR-FRACTURE										FL-FLEXURED										BC-BROKEN CORE										NOTES WATER LEVELS INSTRUMENTATION		
									CL-CLEAVAGE		J-JOINT		R-ROUGH		UE-UNEVEN		MB-MECH. BREAK		B-BEDDING		CH-CHLORITIZED		SM-SMOOTH		F-FAULT		R-ROUGH		UE-UNEVEN		MB-MECH. BREAK		B-BEDDING		CH-CHLORITIZED						
									SH-SHEAR		P-POLISHED		ST-STEPPED		W-WAVY		S-SLICKENSIDED		PL-PLANAR		C-CURVED		S-SLICKENSIDED		PL-PLANAR		C-CURVED		S-SLICKENSIDED		PL-PLANAR		C-CURVED		S-SLICKENSIDED		PL-PLANAR			C-CURVED	
									VN-VEIN		S-SLICKENSIDED		PL-PLANAR		C-CURVED		S-SLICKENSIDED		PL-PLANAR		C-CURVED		S-SLICKENSIDED		PL-PLANAR		C-CURVED		S-SLICKENSIDED		PL-PLANAR		C-CURVED		S-SLICKENSIDED		PL-PLANAR			C-CURVED	
RECOVERY		R.Q.D.		FRACT.		DISCONTINUITY DATA		ROCK		WEATH-		WEATH-		WEATH-		WEATH-		WEATH-		WEATH-		WEATH-		WEATH-		WEATH-		WEATH-		WEATH-		WEATH-									
TOTAL CORE %		SOLID CORE %		%		INDEX PER 0.25		DIP w.r.t. CORE AXIS		TYPE AND SURFACE DESCRIPTION		STRENGTH INDEX		ERING INDEX		ERING INDEX		ERING INDEX		ERING INDEX		ERING INDEX		ERING INDEX		ERING INDEX		ERING INDEX		ERING INDEX		ERING INDEX									
80 60 40 20		80 60 40 20		80 60 40 20		80 60 40 20		80 60 40 20		80 60 40 20		80 60 40 20		80 60 40 20		80 60 40 20		80 60 40 20		80 60 40 20		80 60 40 20		80 60 40 20		80 60 40 20		80 60 40 20		80 60 40 20		80 60 40 20									
Continued from SOIL LOG.		129.74		4.26		1		2		3		4		5		6		7		8		9		10		11		12		13		14									
Slightly weathered, moderately banded-closely spaced, grey black, fine grained, strong to very strong, BANDED IRON FORMATION with iron staining throughout.		127.57		6.43		3		4		5		6		7		8		9		10		11		12		13		14		15		16									
Fresh, closely foliated, light grey, fine grained, medium to strong, INTERMEDIATE VOLCANICS with sericite alteration (10.6-10.9m Fault Zone with FE staining and gouge (drillers reported loss of water return)).		124.89		9.11		5		6		7		8		9		10		11		12		13		14		15		16		17		18									
Fresh, closely foliated, light grey, fine grained, medium to strong, INTERMEDIATE VOLCANICS with sericite alteration.		123.39		10.61		6		7		8		9		10		11		12		13		14		15		16		17		18		19									
Fresh, closely foliated, light grey, fine grained, medium strong, INTERMEDIATE/FELSIC VOCANICS with sericite alteration.		121.89		12.11		End of BOREHOLE.		13		14		15		16		17		18		19		20		21		22		23		24		25									

DEPTH SCALE

1 : 50

Golder Associates

LOGGED: JC/PP

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR CAN.GDT 1/10/03

DEPTH SCALE

1 : 50



LOGGED: JC/PP

CHECKED: CJC

LOCATION: Goose Island Dyke
N: 7212236 E: 638398

DRILLING DATE: 26-Apr-03
DRILL RIG: LY38
DRILLING CONTRACTOR: Boart-Longyear

SHEET 1 OF 3

DATUM: Local

Reference: Ice Surface

DEPTH SCALE
1 : 50



LOGGED: JC/PP
CHECKED: CJC

CUSTOM LOG 3 03-1413-427 OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF BOREHOLE: 03GT-GI-6

SHEET 2 OF 3

LOCATION: Goose Island Dyke
N: 7212236 E: 638398

DRILLING DATE: 26-Apr-03

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES			CORE		GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %	GRAVEL	SAND	FINES	WATER CONTENT PERCENT					
													10 ⁻⁶	10 ⁻⁵	10 ⁻⁴			10 ⁻³
10	HQ3	Loose, COBBLES and GRAVEL with trace sand, composed of granite and quartz (<i>continued</i>)																
11				1	DO	53												
12				2	DO	48												
13		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.		121.00														
14																		
15																		
16																		
17																		
18																		
19																		
20																		

DEPTH SCALE

1 : 50



LOGGED: JC/PP

CHECKED: CJC

CUSTOM LOG 3 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

PROJECT No.: 03-1413-427
 LOCATION: Goose Island Dyke
 N: 7212236 E: 638398
 INCLINATION: -90°

RECORD OF DRILLHOLE: 03GT-GI-6

SHEET 3 OF 3
 DATUM: Local

DRILLING DATE: 26-Apr-03
 DRILL RIG: LY38
 DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (mm/hr)	FLUSH	CORE COLOUR % RETURN	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX	WEATH- ERING INDEX																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
TOTAL CORE %	SOLID CORE %			DIP w.r.t. CORE AXIS	TYPE AND SURFACE DESCRIPTION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
		80 60 40 20	80 60 40 20	80 60 40 20	2 4 6 8	0 20 40 60																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
13		Continued from SOIL LOG.		121.00 13.00																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
	Boart-Long/year HQ3	Fresh, weak to moderate planar to wavy foliation, light grey, QUARTZITE with sericite alteration and quartz patches, vuggs @14.78-14.9 and 15.52-15.61		1																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
			Fresh to slightly weathered along joints, weak to moderate planar foliation, grey, strong, QUARTZITE strongly fractured with epidote and iron staining along discontinuities		2																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							</

15.00m to 18.75m
 Falling Head
 Packer Test
 k=4.7x10-5 cm/s

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

DEPTH SCALE
 1 : 50



LOGGED: JC/PP
 CHECKED: CJC

PROJECT No.: 03-1413-427

RECORD OF BOREHOLE: 03GT-GI-7

SHEET 1 OF 6

LOCATION: Goose Island Dyke Abut.

DRILLING DATE: 25-26 April 2003


DATUM: Local

N: 7212245.771 E: 638251.184

DRILL RIG: LY38

Reference: Ground Surface

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES			CORE			GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION		
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %			GRAVEL	SAND	FINES	WATER CONTENT PERCENT					
									80	60	40				20	Wp			W	Wi
0		Ground Surface		134.97 0.00																
1	HQ3	GRAVEL and COBBLES					1													
2																				
3																				
4																				
5																				
5		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.		130.59																
6																				
7																				
8																				
9																				
10																				

DEPTH SCALE

1 : 50



LOGGED: JC/PP/CC

CHECKED: CJC

CUSTOM LOG 3 03-1413-427_OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-GI-7

SHEET 2 OF 6

LOCATION: Goose Island Dyke Abut.

DRILLING DATE: 25-26 April 2003

DATUM: Local

N: 7212245.771 E: 638251.184

DRILL RIG: LY38

INCLINATION: -61.04° AZIMUTH: 86°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	PENETRATION RATE RUN No. (m/min)	FLUSH % RETURN	COLOUR % RETURN	FR-FRACTURE F-FAULT SM-SMOOTH FL-FLEXURED BC-BROKEN CORE										NOTES WATER LEVELS INSTRUMENTATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
								CL-CLEAVAGE		J-JOINT		R-ROUGH		UE-UNEVEN		MB-MECH. BREAK																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
								SH-SHEAR		P-POLISHED		ST-STEPPED		W-WAVY		B-BEDDING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
								VN-VEIN		S-SLICKENSIDED		PL-PLANAR		C-CURVED		CH-CHLORITIZED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
								RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX		WEATH- ERING INDEX																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
TOTAL CORE %	SOLID CORE %	DIP w.r.t. CORE AXIS	TYPE AND SURFACE DESCRIPTION	R2 R3	R4 R1	W1 W2	W3 W4																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
								80 60 40 20	80 60 40 20	80 60 40 20	80 60 40 20	2 4 6 8	0 30 60 90																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												</

DEPTH SCALE

1 : 50



LOGGED: JC/PP/CC

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

SHEET 3 OF 6

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

[illegible]

CHECKED: CJC

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-GI-7

SHEET 4 OF 6

LOCATION: Goose Island Dyke Abut.

DRILLING DATE: 25-26 April 2003

DATUM: Local

N: 7212245.771 E: 638251.184

DRILL RIG: LY38

INCLINATION: -61.04°

AZIMUTH: 86°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No. PENETRATION RATE (m/min)	COLOUR % RETURN FLUSH	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION										
							CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK											
							SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING											
							VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED											
							RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX	WEATH- ERING INDEX								
TOTAL CORE %	SOLID CORE %			DIP w.r.t. CORE AXIS	TYPE AND SURFACE DESCRIPTION	R3 R2 R1	W1 W2 W3 W4															
25	Baart-Longyear HQ3	Fresh, weak foliated, fine grained, strong, INTERMEDIATE VOLCANICS		25.00								FO,PL,SM FO,CU,SM										
26				16																		
				27	17										JN,PL,Ro							
													JN,PL,Ro									
												JN,PL,VR										
28				17											FO,PL,SM							
																JN,PL,Ro						
																JN,PL,Ro						
29				110.19	28.32	18									JN,CU,Ro							
				Fresh, weak to moderate foliated, green, strong, INTERMEDIATE VOLCANICS with a small fold @ 28.84, trace sulphides and quartz veins and patches												FO,PL,Ro FO,CU,SM						
																	FO,PL,Ro					
																	JN,PL,Ro					
	109.16	29.50	19										JN,IR,Ro									
Fresh, massive to weak foliated, dark green, fine grained, strong, INTERMEDIATE VOLCANIC to ULTRA MAFIC													FLT,PL,SM Ch JN,UN,Ro									
														FO,PL,Ro								
														FO,PL,SM								
														JN,PL,Ro Qz								
	31	20											JN,IR,Ro Qz									
													JN,PL,Ro Cl									
													JN,PL,Ro Cl									
32	20												FO,PL,Ro									
													JN,PL,Ro Cl									
													FO,PL,Ro									
33	21												JN,PL,Ro									
													VN,IR,Ro Ca									
														JN,PL,Ro Su FO,PL,SM								
34	105.22 34.00	22										JN,PL,Ro Su										
														FO,PL,SM Ca								
															CO,UN,SM							
35		CONTINUED NEXT PAGE																				

CONTINUED NEXT PAGE

DEPTH SCALE

1 : 50



LOGGED: JC/PP/CC

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

SHEET 5 OF 6

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

[illegible]

CHECKED: CJC

SHEET 6 OF 6

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

[illegible]

DEPTH SCALE

1 : 50



LOGGED: JC/PP/CC

CHECKED: CJC

LOCATION: Goose Island
N: 7212300 E: 638967

DRILLING DATE: 2-3 June 2003
DRILL RIG: LY38
DRILLING CONTRACTOR: Boart-Longyear

SHEET 1 OF 3

DATUM: Local

Reference: Ice Surface

CUSTOM LOG 3 03-1413-427 OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

**Golder
Associates**

LOGGED: TS/CS
CHECKED: CJC

SHEET 2 OF 3

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

[illegible]

CHECKED: CJC

DRILLHOLE 03-1413-427 OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

SHEET 3 OF 3

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

[illegible]

DEPTH SCALE

1 : 50



LOGGED: TS/CS

CHECKED: CJC

DRILLHOLE 03-1413-427 OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF BOREHOLE: 03GT-SE-1

SHEET 1 OF 2

LOCATION: 2nd Portage Lake
N: 7214176 E: 639458

DRILLING DATE: 17-May-03

DATUM: Local

DRILL RIG: LY38

Reference: Ice Surface

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES		CORE		GRADATION %		HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %	GRAVEL	SAND	FINES	10 ⁻⁶ 10 ⁻⁵ 10 ⁻⁴ 10 ⁻³																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
													WATER CONTENT PERCENT																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
													Wp			W	Wi																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																

DEPTH SCALE

1 : 50



LOGGED: JC/PP

CHECKED: CJC

CUSTOM LOG 3 03-1413-427_OCT11_2003.GPJ GLDR_CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-SE-1

SHEET 2 OF 2

LOCATION: 2nd Portage Lake
N: 7214176 E: 639458

DRILLING DATE: 17-May-03

DATUM: Local

INCLINATION: -90°

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	CORRELATION CHART																NOTES WATER LEVELS INSTRUMENTATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
				ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	FLUSH	COLOUR % RETURN	FR-FRACTURE		F-FAULT		SM-SMOOTH		FL-FLEXURED		BC-BROKEN CORE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
									CL-CLEAVAGE		J-JOINT		R-ROUGH		UE-UNEVEN		MB-MECH. BREAK																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
									SH-SHEAR		P-POLISHED		ST-STEPPED		W-WAVY		B-BEDDING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
									VN-VEIN		S-SLICKENSIDED		PL-PLANAR		C-CURVED		CH-CHLORITIZED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX	WEATH- ERING INDEX																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
TOTAL CORE %	SOLID CORE %			DIP w.r.t. CORE AXIS	TYPE AND SURFACE DESCRIPTION		R3 R2 R1	W1 W2 W3 W4																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
		Continued from SOIL LOG.	124.67 8.33																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					</

11.32m to 15.82m
Falling Head
Packer Test
k=7.2x10⁻⁴ cm/s

DEPTH SCALE

1 : 50



LOGGED: JC/PP

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF BOREHOLE: 03GT-SE-2

SHEET 1 OF 2

LOCATION: 2nd Portage Lake
N: 7213945 E: 639527

DRILLING DATE: 17-May-03

DATUM: Local

DRILL RIG: LY38

Reference: Ice Surface

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES			CORE			GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION		
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %			GRAVEL	SAND	FINES	WATER CONTENT PERCENT					
									80	60	40				20	Wp			W	Wi
0		Ice Surface		133.00																
		ICE		132.70																
				0.30																
1	HQ3	COBBLES and GRAVEL of granite and int. volcanics																		
				131.16																
2		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.																		
3																				
4																				
5																				
6																				
7																				
8																				
9																				
10																				

DEPTH SCALE

1 : 50



LOGGED: JC/PP

CHECKED: CJC

CUSTOM LOG 3 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-SE-2

SHEET 2 OF 2

LOCATION: 2nd Portage Lake

DRILLING DATE: 17-May-03

DATUM: Local

N: 7213945 E: 639527

DRILL RIG: LY38

INCLINATION: -90°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	COLOUR % RETURN	FLUSH	FR-FRACTURE F-FAULT R-SMOOTH FL-FLEXURED BC-BROKEN CORE CL-CLEAVAGE J-JOINT R-ROUGH UE-UNEVEN MB-MECH. BREAK SH-SHEAR P-POLISHED ST-STEPPED W-WAVY B-BEDDING VN-VEIN S-SLICKENSIDED PL-PLANAR C-CURVED CH-CHLORITIZED												NOTES WATER LEVELS INSTRUMENTATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
									RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA				ROCK STRENGTH INDEX		WEATH- ERING INDEX																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
									TOTAL CORE %	SOLID CORE %			DIP w.r.t. CORE AXIS				R1	R2	R3	W1		W2	W3	W4																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
									80 60 40 20	80 60 40 20			0 30 60 90	TYPE AND SURFACE DESCRIPTION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
									4 2 0	4 2 0			0 30 60 90																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
2		Continued from SOIL LOG.		131.16																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			

5.84m to 10.34m
Falling Head
Packer Test
k=7.9x10⁻⁶ cm/s

DEPTH SCALE

1 : 50



LOGGED: JC/PP

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR CAN.GDT 1/10/03

LOCATION: 2nd Portage Lake
N: 7213853.491 E: 639415.404

DRILLING DATE: 23-28 May 2003
DRILL RIG: LY38
DRILLING CONTRACTOR: Boart-Longyear

SHEET 1 OF 18

DATUM: Local

Reference: Ice Surface

CUSTOM LOG 3 03-1413-427 OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

**Golder
Associates**

LOGGED: CS/TS
CHECKED: CJC

SHEET 2 OF 18

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

CHECKED: CJC

DRILLHOLE 03-1413-427 OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

SHEET 3 OF 18

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

CHECKED: CJC

SHEET 4 OF 18

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

[illegible]

CHECKED: CJC

DRILLHOLE 03-1413-427 OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-SPEC-F2

SHEET 5 OF 18

LOCATION: 2nd Portage Lake

DRILLING DATE: 23-28 May 2003

DATUM: Local

N: 7213853.491 E: 639415.404

DRILL RIG: LY38

INCLINATION: -58.19°

AZIMUTH: 232°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	FLUSH	COLOUR % RETURN	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK	
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING	
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED	
									RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA	
TOTAL CORE %	SOLID CORE %	DIP w.r.t. CORE AXIS	TYPE AND SURFACE DESCRIPTION	R5 R4 R3 R2 R1	W1 W2 W3 W4									
38				23										
39				24								JN,PL,Ro JN,PL,SM JN,CU,SM FO,PL,SM FO,PL,SM Bt Qz FO,PL,SM Bt Qz FO,PL,SM Bt Qz FO,PL,SM Bt Qz		
40				25								JN,PL,SM Bt Qz JN,PL,SM Bt Qz JN,PL,SM Bt Qz JN,PL,SM Bt Qz FO,PL,SM Bt Qz FO,PL,SM x2 Bt Qz		
41				26								JN,PL,SM Bt Qz JN,PL,SM Bt Qz JN,PL,SM Bt Qz JN,PL,SM Bt Qz FO,PL,SM Bt Qz FO,PL,SM Bt Qz		
42				27								JN,PL,SM Bt Qz JN,CU,SM Bt Qz JN,PL,SM JN,IR,SM FO,IR,SM		
43				28								FO,PL,SM		
44				29										
45														
46														
47														
CONTINUED NEXT PAGE														

CONTINUED NEXT PAGE

DEPTH SCALE

1 : 50



LOGGED: CS/TS

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-SPEC-F2

SHEET 6 OF 18

LOCATION: 2nd Portage Lake

DRILLING DATE: 23-28 May 2003

DATUM: Local

N: 7213853.491 E: 639415.404

DRILL RIG: LY38

INCLINATION: -58.19°

AZIMUTH: 232°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	COLOUR % RETURN FLUSH	FR-FRACTURE		F-FAULT		SM-SMOOTH		FL-FLEXURED		BC-BROKEN CORE		NOTES WATER LEVELS INSTRUMENTATION	
								CL-CLEAVAGE		J-JOINT		R-ROUGH		UE-UNEVEN		MB-MECH. BREAK			
								SH-SHEAR		P-POLISHED		ST-STEPPED		W-WAVY		B-BEDDING			
								VN-VEIN		S-SLICKENSIDED		PL-PLANAR		C-CURVED		CH-CHLORITIZED			
								RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX		WEATH- ERING INDEX			
TOTAL CORE %		SOLID CORE %		DIP w.r.t. CORE AXIS		TYPE AND SURFACE DESCRIPTION		R5	R4			R3	R2	R1	W1	W2	W3	W4	
								80 60 40 20	80 60 40 20	80 60 40 20	80 60 40 20	4 2 1 0	0 10 20 30 40 50 60 70 80						
48				30										JN,IR,Ro JN,IR,Ro FO,ST,Ro					
														FO,PL,SM JN,PL,SM					
49														JN,IR,Ro					
50				31										JN,CU,Ro JN,PL,Ro FO,CU,Ro					
51				32										FO,CU,SM FO,PL,SM x4 FO,PL,SM FO,PL,SM FO,PL,SM					
52				33										FO,PL,SM x3 FO,PL,SM FO,IR,Ro JN,PL,SM JN,ST,Ro					
53														FO,PL,SM FO,PL,SM JN,CU,SM JN,PL,SM JN,CU,Ro					
54				34										FO,PL,SM FO,PL,SM					
55				35										FO,PL,SM FO,PL,SM					
56														FO,PL,SM FO,PL,SM					
57				36										FO,PL,SM FO,IR,Ro FO,PL,SM JN,IR,Ro FO,PL,SM					
		CONTINUED NEXT PAGE																	

Fresh, fine grained, closely foliated,
greenish white/grey, medium strong,
MAFIC to ULTRA MAFIC (continued)51.88m to 74.38m
Falling Head
Packer Test
k=1.3x10⁻⁴ cm/s

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

DEPTH SCALE

1 : 50



LOGGED: CS/TS

CHECKED: CJC

SHEET 7 OF 18

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	COLOUR % RETURN FLUSH	FR-FRACTURE		F-FAULT		SM-SMOOTH		FL-FLEXURED		BC-BROKEN CORE		NOTES WATER LEVELS INSTRUMENTATION											
								CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK																	
								SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING																	
								VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED																	
RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA			ROCK STRENGTH INDEX			WEATH- ERING INDEX																			
TOTAL CORE %	SOLID CORE %			DIP w.r.t. CORE AXIS			R3	R2	R1	W1	W2	W3	W4																
80	60	40	20	80	60	40	20	80	60	40	20	4	3	2	1	0	30	60	90										
58																													
59																													
60																													
61																													
62																													
63																													
64																													
65																													
66																													
67																													
68																													
69																													
70																													
71																													
72																													
73																													
74																													
75																													
76																													
77																													
78																													
79																													
80																													
81																													
82																													
83																													
84																													
85																													
86																													
87																													
88																													
89																													
90																													
91																													
92																													
93																													
94																													
95																													
96																													
97																													
98																													
99																													
100																													
101																													
102																													
103																													
104																													
105																													
106																													
107																													
108																													
109																													
110																													
111																													
112																													
113																													
114																													
115																													
116																													
117																													
118																													
119																													
120																													
121																													
122																													
123																													
124																													
125																													
126																													
127																													
128																													
129																													
130																													
131																													
132																													
133																													
134																													
135																													
136																													
137																													
138																													
139																													
140																													
141																													
142																													
143																													
144																													
145																													
146																													
147																													
148																													
149																													
150																													
151																													
152																													
153																													
154																													
155																													
156																													
157																													
158																													
159																													
160																													
161																													
162																													
163																													
164																													
165																													
166																													
167																													
168																													
169																													
170																													
171																													
172																													
173																													
174																													
175																													
176																													
177																													
178																													
179																													
180																													
181																													
182																													
183																													
184																													
185																													
186																													
187																													
188																													
189																													
190																													
191																													
192																													
193																													
194																													
195																													
196																													
197																													
198																													
199																													
200																													
201																													
202																													
203																													
204																													
205																													
206																													
207																													
208																													
209																													
210																													
211																													
212																													
213																													
214																													
215																													
216																													
217																													
218																													
219																													
220																													
221																													
222																													
223																													
224																													
225																													
226																													
227																													
228																													
229																													
230																													
231																													
232																													
233																													
234																													
235																													
236																													
237																													
238																													
239																													
240																													
241																													
242																													
243																													
244																													
245																													
246																													
247																													
248																													
249																													
250																													
251																													
252																													
253																													
254																													
255																													
256																													
257																													
258																													
259																													
260																													
261																													
262																													
263																													
264																													
265																													
266																													
267																													
268																													
269																													
270																													
271																													
272																													
273																													
274																													
275																													
276																													
277																													
278																													
279																													
280																													
281																													
282																													
283																													
284																													
285																													
286																													
287																													
288																													
289																													
290																													
291																													
292																													
293																													
294																													
295																													
296																													
297																													
298																													
299																													
300																													
301																													
302																													
303																													
304																													
305																													
306																													
307																													
308																													
309																													
310																													
311																													
312																													
313																													
314																													
315																													
316																													
317																													
318																													
319																													
320																													
321																													
322																													
323																													
324																													
325																													
326																													
327																													
328																													
329																													
330																													
331																													
332																													
333																													
334																													
335																													
336																													
337																													
338																													
339																													
340																													
341																													
342																													
343																													
344																													
345																													
346																													
347																													
348																													
349																													
350																													
351																													
352																													
353																													
354																													
355																													
356																													
357																													
358																													
359																													
360																													
361																													
362																													
363																													
364																													
365																													
366																													
367																													
368																													
369																													
370																													
371																													
372																													
373																													
374																													
375																													
376																													
377																													
378																													
379																													
380																													
381																													
382																													
383																													
384																													
385																													
386																													
387																													
388																													
389																													
390																													
391																													
392																													
393																													
394																													
395																													
396																													
397																													
398																													
399																													
400																													
401																													
402																													
403																													
404																													
405																													
406																													
407																													
408																													
409																													
410																													
411																													
412																													
413																													
414																													
415																													
416																													
417																													
418																													
419																													
420																													
421																													
422																													
423																													
424																													
425																													
426																													
427																													
428																													
429																													
430																													
431																													
432																													
433																													
434																													
435																													
436																													
437																													
438																													
439																													
440																													
441																													
442																													
443																													
444																													
445																													
446																													
447																													
448																													
449																													
450																													
451																													
452																													
453																													
454																													
455																													
456																													
457																													
458																													
459																													
460																													
461																													
462																													
463																													
464																													
465																													
466																													
467																													
468																													
469																													
470																													
471																													
472																													
473																													
474																													
475																													
476																													
477																													
478																													
479																													
480																													
481																													
482																													
483																													
484																													
485																													
486																													
487																													
488																													
489																													
490																													
491																													
492																													
493																													
494																													
495																													
496																													
497																													
498																													
499																													
500																													
501																													
502																													
503																													
504																													
505																													
506																													
507																													
508																													
509																													
510																													
511																													
512																													
513																													
514																													
515																													
516																													
517																													
518																													
519																													
520																													
521																													
522																													
523																													
524																													
525																													
526																													
527																													
528																													
529																													
530																													
531																													
532																													
533																													
534																													
535																													
536																													
537																													
538																													
539																													
540																													
541																													
542																													
543																													
544																													
545																													
546																													
547																													
548																													
549																													
550																													
551																													
552																													
553																													
554																													
555																													
556																													
557																													
558																													
559																													
560																													
561																													
562																													
563																													
564																													
565																													
566																													
567																													
568																													
569																													
570																													
571																													
572																													
573																													
574																													
575																													
576																													
577																													
578																													
579																													
580																													
581																													
582																													
583																													
584																													
585																													
586																													
587																													
588																													
589																													
590																													
591																													
592																													
593																													
594																													
595																													
596																													
597																													
598																													
599																													
600																													
601																													
602																													
603																													
604																													
605																													
606																													
607																													
608																													
609																													
610																													
611																													
612																													
613																													
614																													
615																													
616																													
617																													
618																													
619																													
620																													
621																													
622																													
623																													
624																													
625																													
626																													
627																													
628																													
629																													
630																													
631																													
632																													
633																													
634																													
635																													
636																													
637																													
638																													
639																													
640																													
641																													
642																													
643																													
644																													
645																													
646																													
647																													
648																													
649																													
650																													
651																													
652																													
653																													
654																													
655																													
656																													
657																													
658																													
659																													
660																													
661																													
662																													
663																													
664																													
665																													
666																													
667																													
668																													
669																													
670																													
671																													
672																													
673																													
674																													
675																													
676																													
677																													
678																													
679																													
680																													
681																													
682																													
683																													
684																													
685																													
686																													
687																													
688																													
689																													
690																													
691																													
692																													
693																													
694																													
695																													
696																													
697																													
698																													
699																													
700																													
701																													
702																													
703																													
704																													
705																													
706																													
707																													
708																													
709																													
710																													
711																													
712																													
713																													
714																													
715																													
716																													
717																													
718																													
719																													
720																													
721																													
722																													
723																													
724																													
725																													
726																													
727																													
728																													
729																													
730																													
731																													
732																													
733																													
734																													
735																													
736																													
737																													
738																													
739																													
740																													
741																													
742																													
743																													
744																													
745																													
746																													
747																													
748																													
749																													
750																													
751																													
752																													
753																													
754																													
755																													
756																													
757																													
758																													
759																													
760																													
761																													
762																													
763																													
764																													
765																													
766																													
767																													
768																													
769																													
770																													
771																													
772																													
773																													
774																													
775																													
776																													
777																													
778																													
779																													
780																													
781																													
782																													
783																													
784																													
785																													
786																													
787																													
788																													
789																													

CHECKED: CJC

DRILLHOLE 03-1413-427 OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-SPEC-F2

SHEET 8 OF 18

LOCATION: 2nd Portage Lake

DRILLING DATE: 23-28 May 2003

DATUM: Local

N: 7213853.491 E: 639415.404

DRILL RIG: LY38

INCLINATION: -58.19°

AZIMUTH: 232°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (mm/min)	FLUSH	COLOUR % RETURN	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
									RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX	WEATH- ERING INDEX																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
TOTAL CORE %	SOLID CORE %	DIP w.r.t. CORE AXIS	TYPE AND SURFACE DESCRIPTION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
68	Beart-Longyear HQ3	Fresh, fine grained, closely foliated to massive, grey, medium strong to strong, MAFIC with quartzite stringers. (continued)		43																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											

CONTINUED NEXT PAGE

DEPTH SCALE

1 : 50



LOGGED: CS/TS

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

SHEET 9 OF 18

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

CHECKED: CJC

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-SPEC-F2

SHEET 10 OF 18

LOCATION: 2nd Portage Lake

DRILLING DATE: 23-28 May 2003

DATUM: Local

N: 7213853.491 E: 639415.404

DRILL RIG: LY38

INCLINATION: -58.19°

AZIMUTH: 232°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	FLUSH % RETURN	COLOUR % RETURN	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK	
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING	
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED	
RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX	WEATH- ERING INDEX							
TOTAL CORE %	SOLID CORE %			DIP w.r.t. CORE AXIS	TYPE AND SURFACE DESCRIPTION		R5 R4 R3 R2 R1	W1 W2 W3 W4						
88				56										
				57										
89														
				58										
90		Fresh, fine grained, closely foliated, grey medium strong, MAFICS with Quartz veinlets and chlorite.(continued)												
				59										
91														
				60										
92														
				61										
93														
				62										
94														
				63										
95		Fresh, fine grained, chlorite bands, blackish grey, weak, SOAPSTONE with frequent quartz and chlorite veinlets.												

DEPTH SCALE

1 : 50



LOGGED: CS/TS

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-SPEC-F2

SHEET 11 OF 18

LOCATION: 2nd Portage Lake

DRILLING DATE: 23-28 May 2003

DATUM: Local

N: 7213853.491 E: 639415.404

DRILL RIG: LY38

INCLINATION: -58.19°

AZIMUTH: 232°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (mm/min)	FLUSH % RETURN	COLOUR % RETURN	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX	WEATH- ERING INDEX																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
TOTAL CORE %	SOLID CORE %			DIP w.r.t CORE AXIS	TYPE AND SURFACE DESCRIPTION			R5	R4	R3	R2	R1	W1	W2	W3	W4																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
98	Boart-Longyear HQ3	Fresh, fine grained, chlorite bands, blackish grey, weak, SOAPSTONE with frequent quartz and chlorite veinlets. (continued)		63																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					

DEPTH SCALE

1 : 50



LOGGED: CS/TS

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

SHEET 12 OF 18

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

CHECKED: CJC

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-SPEC-F2

SHEET 13 OF 18

LOCATION: 2nd Portage Lake

DRILLING DATE: 23-28 May 2003

DATUM: Local

N: 7213853.491 E: 639415.404

DRILL RIG: LY38

INCLINATION: -58.19°

AZIMUTH: 232°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (mm/min)	COLOUR % RETURN FLUSH	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION								
								CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK									
								SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING									
								VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED									
								RECOVERY		R.Q.D. %	DISCONTINUITY DATA		ROCK STRENGTH INDEX		WEATH- ERING INDEX						
TOTAL CORE %		SOLID CORE %				FRACT. INDEX PER 0.25		DIP w.r.t CORE AXIS		TYPE AND SURFACE DESCRIPTION		R ₅	R ₄	R ₃	R ₂	R ₁	W ₁	W ₂	W ₃	W ₄	
118																					
119																					
120																					
121																					
122																					
123																					
124																					
125																					
126																					
127																					
		CONTINUED NEXT PAGE																			

DEPTH SCALE

1 : 50



LOGGED: CS/TS

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-SPEC-F2

SHEET 14 OF 18

LOCATION: 2nd Portage Lake

DRILLING DATE: 23-28 May 2003

DATUM: Local

N: 7213853.491 E: 639415.404

DRILL RIG: LY38

INCLINATION: -58.19°

AZIMUTH: 232°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	FLUSH % RETURN	COLOUR % RETURN	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION																																			
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK																																				
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING																																				
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED																																				
										RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX			WEATH- ERING INDEX																														
TOTAL CORE %	SOLID CORE %	DIP w.r.t. CORE AXIS		TYPE AND SURFACE DESCRIPTION		R2	R4	R3	R2	R1	W1			W2	W3	W4																																	
									80 60 40 20	80 60 40 20	80 60 40 20	80 60 40 20	2 4 6 8	0 30 60 90																																			
128					83																																												
129					84																																												
130					85																																												
131					86																																												
132					87																																												
133					88																																												
134					89																																												
135																																																	
136																																																	
137																																																	
																																								</									

Fresh, fine grained, greyish white,
strong, MAFICS with quartz veinlets.
(continued)JN,CU,Ro
JN,IR,Ro

JN,CU,Ro

JN,IR,Ro

JN,UN,Ro

JN,PL,SM CH

136.88m to 174.38m
Falling Head
Packer Test
k=4.3x10⁻⁷ cm/s

CONTINUED NEXT PAGE

DEPTH SCALE

1 : 50



LOGGED: CS/TS

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-SPEC-F2

SHEET 15 OF 18

LOCATION: 2nd Portage Lake

DRILLING DATE: 23-28 May 2003

DATUM: Local

N: 7213853.491 E: 639415.404

DRILL RIG: LY38

INCLINATION: -58.19°

AZIMUTH: 232°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	COLOUR % RETURN	FLUSH	FR-FRACTURE CL-CLEAVAGE SH-SHEAR VN-VEIN	F-FAULT J-JOINT P-POLISHED S-SLICKENSIDED	SM-SMOOTH R-ROUGH ST-STEPPED PL-PLANAR	FL-FLEXURED UE-UNEVEN W-WAVY C-CURVED	BC-BROKEN CORE MB-MECH. BREAK B-BEDDING CH-CHLORITIZED	NOTES WATER LEVELS INSTRUMENTATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
														RECOVERY	R.Q.D. %	FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX			WEATH- ERING INDEX																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
																	DIP w.r.t. CORE AXIS	TYPE AND SURFACE DESCRIPTION	R3 R4	R3 R2	R1	W1 W2	W3 W4																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
138		Fresh, fine grained, greyish white, strong, MAFICS with quartz veinlets. (continued)		90																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						

138.88m to 147.38m
Falling Head
Packer Test
k=2.1x10⁻⁶ cm/s

DEPTH SCALE

1 : 50



LOGGED: CS/TS

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

PROJECT No.: 03-1413-427

RECORD OF DRILLHOLE: 03GT-SPEC-F2

SHEET 16 OF 18

LOCATION: 2nd Portage Lake

DRILLING DATE: 23-28 May 2003

DATUM: Local

N: 7213853.491 E: 639415.404

DRILL RIG: LY38

INCLINATION: -58.19°

AZIMUTH: 232°

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	COLOUR % RETURN	FLUSH	FR-FRACTURE		F-FAULT		SM-SMOOTH		FL-FLEXURED		BC-BROKEN CORE		NOTES WATER LEVELS INSTRUMENTATION	
									CL-CLEAVAGE		J-JOINT		R-ROUGH		UE-UNEVEN		MB-MECH. BREAK			
									SH-SHEAR		P-POLISHED		ST-STEPPED		W-WAVY		B-BEDDING			
									VN-VEIN		S-SLICKENSIDED		PL-PLANAR		C-CURVED		CH-CHLORITIZED			
RECOVERY		R.Q.D.		FRACT. INDEX PER 0.25	DISCONTINUITY DATA		ROCK STRENGTH INDEX		WEATH- ERING INDEX											
TOTAL CORE %	SOLID CORE %	%	DIP w.r.t. CORE AXIS		TYPE AND SURFACE DESCRIPTION		R8 R4	R3 R2	R1	W1 W2	W3 W4									
									80 60 40 20	80 60 40 20	80 60 40 20	80 60 40 20	80 60 40 20	80 60 40 20	80 60 40 20	80 60 40 20	80 60 40 20	80 60 40 20		

154.88m to 174.38m
Falling Head
Packer Test
k=1.5x10-6 cm/s

DEPTH SCALE

1 : 50



LOGGED: CS/TS

CHECKED: CJC

DRILLHOLE 03-1413-427_OCT1_2003.GPJ GLDR_CAN.GDT 1/10/03

SHEET 17 OF 18

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

CHECKED: CJC

SHEET 18 OF 18

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DRILLHOLE 03-1413-427 OCT1 2003.GPJ GLDR CAN.GDT 1/10/03

CHECKED: CJC

PROJECT No.: 022-1427A Task 2000

RECORD OF DRILLHOLE: 02GT-01

SHEET 1 OF 2

LOCATION: East Dyke

DRILLING DATE: 7 May, 2002

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES			CORE		GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %	GRAVEL	SAND	FINES	WATER CONTENT PERCENT					
0		Ice Surface		0.00														
		Grounded Ice.																
1																		
2		At 0.5-3.5m depth cobbles and gravel recovered. Very poor recovery even with triple tube. - No soil material recovered. - Fresh cobbles and gravel of variable origin; Granite, intermediate volcanics, quartz [OVERBURDEN].																
3	Boart-Longyear LY38 - HQ3																	
4		At 3.5-5.6m depth cobbles and gravel. - No soil material recovered. - Fresh cobbles and gravel of variable origin; Granite, intermediate volcanics, quartz, [OVERBURDEN].		3.50														
5																		
6		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.																
7																		
8																		
9																		
10																		

DEPTH SCALE

1 : 50



LOGGED: CJC/JRT

CHECKED:

CUSTOM LOG 3 022-14-1.GPJ GLDR CAN.GDT 30/9/03

PROJECT No.: 022-1427A Task 2000

RECORD OF DRILLHOLE: 02GT-01

SHEET 2 OF 2

LOCATION: East Dyke

DRILLING DATE: 7 May, 2002

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (mm/min)	FLUSH	COLOUR % RETURN	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
									RECOVERY				DISCONTINUITY DATA				ROCK STRENGTH INDEX		WEATH- ERING INDEX																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
TOTAL CORE %	SOLID CORE %	R.Q.D. %	FRACT. INDEX PER 0.3	DIP w.r.t CORE AXIS	TYPE AND SURFACE DESCRIPTION		R ₂	R ₄	R ₃	R ₁	W ₁	W ₂	W ₃	W ₄																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
80	80	80	5	0																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												</

DEPTH SCALE

1 : 50



LOGGED: CJC/JRT

CHECKED:

DRILLHOLE 022-14~1.GPJ GLDR_CAN.GDT 30/9/03

PROJECT No.: 022-1427A Task 2000

RECORD OF DRILLHOLE: 02GT-02A

SHEET 1 OF 2

LOCATION: East Dyke

DRILLING DATE: 8 May, 2002

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES			CORE		GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %	GRAVEL	SAND	FINES	WATER CONTENT PERCENT					
													10 ⁻⁵	10 ⁻⁴	10 ⁻³			10 ⁻²
0		Ice Surface		0.00														
1		Ice.																
2																		
3	LY38-HQ3	Water.		2.40														
4																		
5		Loose, homogenous, wet, dark grey, well graded, clean SAND (lake bottom). [OVERBURDEN]		3.90														
6																		
7		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.																
8																		
9																		
10																		

DEPTH SCALE

1 : 50



LOGGED: CJC/JRT

CHECKED:

CUSTOM LOG 3 022-14-1.GPJ GLDR CAN.GDT 24/10/03

LOCATION: East Dyke

DRILLING DATE: 8 May, 2002

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DATUM: Local

1 : 50



PROJECT No.: 022-1427A Task 2000

RECORD OF DRILLHOLE: 02GT-02B

SHEET 1 OF 2

LOCATION: East Dyke

DRILLING DATE: 8 May, 2002

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES			CORE		GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %	GRAVEL	SAND	FINES	WATER CONTENT PERCENT					
													10 ⁻⁵	10 ⁻⁴	10 ⁻³			10 ⁻²
0		Ice Surface		0.00														
1		Ice.																
2																		
3		Water.		2.40														
4																		
5																		
6																		
7																		
8																		
9																		
10																		

DEPTH SCALE

1 : 50



LOGGED: CJC/JRT

CHECKED:

CUSTOM LOG 3 022-14-1.GPJ GLDR CAN.GDT 24/10/03

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (mm/min)	COLOUR % RETURN FLUSH	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION
								CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK	
								SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING	
								VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED	
RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.3	DISCONTINUITY DATA		ROCK STRENGTH INDEX	WEATH- ERING INDEX						
TOTAL CORE %	SOLID CORE %			DIP w/1 CORE AXIS	TYPE AND SURFACE DESCRIPTION								
80 60 40 20	80 60 40 20	80 60 40 20	80 60 40 20	5 10 15 20	0 30 60 90	R1 R2 R3 R2 R1	W1 W2 W3 W4						
7		Continued from SOIL LOG.		7.00									
	Boart-Longyear LY38 - HQ/HW	Fresh, grey, laminated, fine to medium grained, strong, INTERMEDIATE VOLCANICS. - Rock very competent, very few natural breaks, remainder are mechanical. - Interbeds of silicified material, up to 10cm thick. - Broken core zones due to re-drill of hole.	▽▽▽										

PROJECT No.: 022-1427A Task 2000

RECORD OF DRILLHOLE: 02GT-04

SHEET 1 OF 4

LOCATION: East Dyke

DRILLING DATE: 10 May, 2002

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES			CORE		GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %	GRAVEL	SAND	FINES	WATER CONTENT PERCENT					
													10 ⁻⁵	10 ⁻⁴	10 ⁻³			10 ⁻²
0		Ground Surface		0.00														
1	LY38 - HQ3	Loose homogeneous, moist, subrounded to rounded cobbles, coarse gravel, some sand (TILL) [OVERBURDEN].																
2																		
3		Loose homogeneous, moist, subangular to subrounded boulders and cobbles, coarse gravel, trace sand (TILL) [OVERBURDEN].		2.75														
4		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.																
5																		
6																		
7																		
8																		
9																		
10																		

3.5m to 8.5m
Packer Test #1
Test Data Unreliable.

DEPTH SCALE

1 : 50



LOGGED: CJC/JRT

CHECKED:

CUSTOM LOG 3 022-14-1.GPJ GLDR CAN.GDT 24/10/03

PROJECT No.: 022-1427A Task 2000

RECORD OF DRILLHOLE: 02GT-04

SHEET 2 OF 4

LOCATION: East Dyke

DRILLING DATE: 10 May, 2002

DATUM: Local

INCLINATION: -50.304° AZIMUTH: 22°

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (mm/min)	FLUSH	COLOUR % RETURN	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	MB-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION										
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK											
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING											
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED											
									RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.3	DISCONTINUITY DATA		ROCK STRENGTH INDEX		WEATH- ERING INDEX							
									TOTAL CORE %	SOLID CORE %			DIP w.r.t CORE AXIS	TYPE AND SURFACE DESCRIPTION		R ₅	R ₄	R ₃	R ₂	W ₁	W ₂	W ₃	W ₄	
4		Continued from SOIL LOG.		3.85																				
4																								
5					1																			
5		- Pervasive silicification and potassic alteration.																						
5		- Foliation approx. 15 degrees TCA.																						
6																								
6		Fresh, grey, foliated, medium grained, strong to very strong, INTERMEDIATE VOLCANICS.																						
7					2																			
7																								
8																								
8																								
9																								
9					8.77																			
9		- Small shear zone, pitting of core.																						
9		- Chloritic margins.																						
10																								
10		- Matrix is soapy to the touch; Sericite visible on surfaces.			3																			
11																								
11		- 11.0m Iron Staining on foliation surfaces.																						
11		- 11.27m Iron Staining on foliation surfaces.																						
11		Fresh, grey-green, foliated, fine grained, chloritic, weak to medium strong, INTERMEDIATE VOLCANICS.																						
12		- 11.5m to 12.07m Iron Staining along foliation surfaces.																						
12		- 12.07m Increase in rock strength.																						
13					4																			
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								
13																								

DEPTH SCALE

1 : 50



LOGGED: CJC/JRT

CHECKED:

DRILLHOLE 022-14~1.GPJ GLDR_CAN.GDT 24/10/03

PROJECT No.: 022-1427A Task 2000

RECORD OF DRILLHOLE: 02GT-04

SHEET 3 OF 4

LOCATION: East Dyke

DRILLING DATE: 10 May, 2002

DATUM: Local

INCLINATION: -50.304° AZIMUTH: 22°

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	FLUSH	COLOUR % RETURN	FR-FRACTURE				F-FAULT				SM-SMOOTH				FL-FLEXURED				BC-BROKEN CORE				NOTES WATER LEVELS INSTRUMENTATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
									CL-CLEAVAGE				J-JOINT				R-ROUGH				UE-UNEVEN				MB-MECH. BREAK																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
									SH-SHEAR				P-POLISHED				ST-STEPPED				W-WAVY				B-BEDDING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
									VN-VEIN				S-SLICKENSIDED				PL-PLANAR				C-CURVED				CH-CHLORITIZED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
									RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.3	DISCONTINUITY DATA				ROCK STRENGTH INDEX	WEATH- ERING INDEX																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			

CONTINUED NEXT PAGE

18.5m to 29.5m
Falling Head
Packer Test
k=2.2x10-6 cm/s

DEPTH SCALE

1 : 50



LOGGED: CJC/JRT

CHECKED:

DRILLHOLE 022-14~1.GPJ GLDR_CAN.GDT 24/10/03

SHEET 4 OF 4

DATUM: Local

DRILLING CONTRACTOR: Boart-Longyear

DRILLHOLE 022-14~1.GPJ GLDR_CAN.GDT 24/10/03

CHECKED:

PROJECT No.: 022-1427A Task 2000

RECORD OF DRILLHOLE: 02GT-03

SHEET 1 OF 4

LOCATION: East Dyke

DRILLING DATE: 11 May, 2002

DATUM: Local

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES			CORE		GRADATION %			HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION														
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	RUN No.	RECOVERY %	GRAVEL	SAND	FINES	WATER CONTENT PERCENT																		
													10 ⁻⁵	10 ⁻⁴	10 ⁻³			10 ⁻²	Wp	W	Wi										
0		Ground Surface		0.00																											
1	LY38 - HQ3	Boulder TILL. [OVERBURDEN] - Attempted SPT's with borehole oriented vertically but could not drive.			1	50	DO	>50																							
2																															
3																															
4		Bedrock Encountered. Refer to ROCK LOG for continuation of rock description.																													
5																															
6																															
7																															
8																															
9																															
10																															

DEPTH SCALE

1 : 50



LOGGED: CJC/JRT

CHECKED:

CUSTOM LOG 3 022-14-1.GPJ GLDR CAN.GDT 30/9/03

PROJECT No.: 022-1427A Task 2000

RECORD OF DRILLHOLE: 02GT-03

SHEET 2 OF 4

LOCATION: East Dyke

DRILLING DATE: 11 May, 2002

DATUM: Local

INCLINATION: -50.879° AZIMUTH: 175°

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	FLUSH % RETURN	COLOUR % RETURN	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION											
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK												
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING												
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED												
									DISCONTINUITY DATA						ROCK STRENGTH INDEX	WEATH- ERING INDEX									
RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.3	DIP w.r.t. CORE AXIS	TYPE AND SURFACE DESCRIPTION																				
		TOTAL CORE %	SOLID CORE %			0 30 60 90						R2	R3	R1	W1	W2	W3	W4							
3		Continued from SOIL LOG.		3.00																					
4		Slightly weathered, green-grey, foliated, fine to medium grained, medium strong INTERMEDIATE VOLCANICS.		1																					
																				J,PL,R J,PL,R Fe BC,,					
																				BC,, FO,PL,R G J,PL,R G BC,,					
																				BC,, FO,PL,R Fe J,PL,R Fe J,PL,R J,PL,R BC,,					
5		Fresh, green-grey, foliated, fine to medium grained, medium strong, INTERMEDIATE VOLCANICS.		2																					
																				BC,, J,PL,R J,PL,R J,PL,R					
																				BC,, FR,, J,PL,R					
6		Fresh, grey, foliated, small to medium grained, strong, INTERMEDIATE VOLCANICS.		3																					
																				FO,PL,R FO,PL,R F,PL,R ,, MB					
																				BC,, BC,,					
7		Fresh, grey, foliated, small to medium grained, strong, INTERMEDIATE VOLCANICS.		4																					
																				FO,PL,R FO,PL,R FO,PL,R FO,PL,R					
8		CONTINUED NEXT PAGE																							

DEPTH SCALE

1 : 50



LOGGED: CJC/JRT

CHECKED:

DRILLHOLE 022-14-1.GPJ GLDR_CAN.GDT 30/9/03

PROJECT No.: 022-1427A Task 2000

RECORD OF DRILLHOLE: 02GT-03

SHEET 3 OF 4

LOCATION: East Dyke

DRILLING DATE: 11 May, 2002

DATUM: Local

INCLINATION: -50.879° AZIMUTH: 175°

DRILL RIG: LY38

DRILLING CONTRACTOR: Boart-Longyear

DEPTH SCALE METRES	DRILLING RECORD	DESCRIPTION	SYMBOLIC LOG	ELEV. DEPTH (m)	RUN No.	PENETRATION RATE (m/min)	FLUSH	COLOUR % RETURN	FR-FRACTURE	F-FAULT	SM-SMOOTH	FL-FLEXURED	BC-BROKEN CORE	NOTES WATER LEVELS INSTRUMENTATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
									CL-CLEAVAGE	J-JOINT	R-ROUGH	UE-UNEVEN	MB-MECH. BREAK																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
									SH-SHEAR	P-POLISHED	ST-STEPPED	W-WAVY	B-BEDDING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
									VN-VEIN	S-SLICKENSIDED	PL-PLANAR	C-CURVED	CH-CHLORITIZED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
									DISCONTINUITY DATA						ROCK STRENGTH INDEX	WEATH- ERING INDEX																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
RECOVERY		R.Q.D. %	FRACT. INDEX PER 0.3	DIP w.r.t. CORE AXIS	TYPE AND SURFACE DESCRIPTION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
TOTAL CORE %	SOLID CORE %					0 30 60 90	0 30 60 90	R ₂	R ₃	R ₁	W ₁	W ₂	W ₃	W ₄																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
13	Baart-Longyear LY38 - HQ3	Fresh, grey, foliated, small to medium grained, strong, INTERMEDIATE VOLCANICS. <i>(continued)</i>		4																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															

16m to 30m
Falling Head
Packer Test #3.
No recovery.22.26m to 22.45m
Sample Taken

DRILLHOLE 022-14~1.GPJ GLDR CAN.GDT 30/9/03

DEPTH SCALE

1 : 50



LOGGED: CJC/JRT

CHECKED:

APPENDIX VI

SEISMIC RISK CALCULATION FOR MEADOWBANK SITE

NATURAL RESOURCES CANADA
GEOLOGICAL SURVEY OF CANADA

RESSOURCES NATURELLES CANADA
COMMISSION GEOLOGIQUE DU CANADA

SEISMIC RISK CALCULATION *

CALCUL DE RISQUE SEISMIQUE *

REQUESTED BY/ DEMANDE PAR

Don Hickson, Golder Assoc., Vancouver

SITE

Tenek Lake, Nunavut

LOCATED AT/ SITUE AU

65.00 NORTH/NORD

96.05 WEST/OUEST

PROBABILITY OF EXCEEDENCE
PER ANNUM/ PROBABILITE DE
DEPASSEMENT PAR ANNEE

0.010 0.005 0.0021 0.001

PROBABILITY OF EXCEEDENCE
IN 50 YEARS/ PROBABILITE
DE DEPASSEMENT EN 50 ANS

40 % 22 % 10 % 5 %

PEAK HORIZONTAL GROUND
ACCELERATION (G)

0.018 0.025 0.034 0.044

ACCELERATION HORIZONTALE
MAXIMALE DU SOL (G)

PEAK HORIZONTAL GROUND
VELOCITY (M/SEC)

0.011 0.017 0.029 0.039

VITESSE HORIZONTALE
MAXIMALE DU SOL (M/SEC)

* REFERENCES

1. NEW PROBABILISTIC STRONG SEISMIC GROUND MOTION MAPS
OF CANADA: A COMPILATION OF EARTHQUAKE SOURCE ZONES, METHODS AND RESULTS.
P.W. BASHAM, D.H. WEICHERT, F.M. ANGLIN, AND M.J. BERRY
EARTH PHYSICS BRANCH OPEN FILE NUMBER 82-33, OTTAWA, CANADA 1982.
2. ENGINEERING APPLICATIONS OF NEW PROBABILISTIC
SEISMIC GROUND-MOTION MAPS OF CANADA.
A.C. HEIDEBRECHT, P.W. BASHAM, J.H. RAINER, AND M.J. BERRY
CANADIAN JOURNAL OF CIVIL ENGINEERING, VOL. 10, NO. 4, P. 670-680, 1983.
3. NEW PROBABILISTIC STRONG GROUND MOTION MAPS OF CANADA.
P.W. BASHAM, D.H. WEICHERT, F.M. ANGLIN, AND M.J. BERRY, BULLETIN OF
THE SEISMOLOGICAL SOCIETY OF AMERICA, VOL. 75, NO. 2, P. 563-595, 1985.
- 4A. SUPPLEMENT TO THE NATIONAL BUILDING CODE OF CANADA 1990, NRCC NO. 30629.
CHAPTER 1: CLIMATIC INFORMATION FOR BUILDING DESIGN IN CANADA.
CHAPTER 4: COMMENTARY J: EFFECTS OF EARTHQUAKES.
- 4B. SUPPLEMENT DU CODE NATIONAL DU BATIMENT DU CANADA 1990, CNRC NO 30629F.
CHAPITRE 1: DONNEES CLIMATIQUES POUR LE CALCUL DES BATIMENTS AU CANADA.
CHAPITRE 4: COMMENTAIRE J: EFFETS DES SEISMES.

Tenek Lake, Nunavut

ZONING FOR ABOVE SITE/ ZONAGE DU SITE CI-DESSUS

1990 NBCC/CNBC: ZA = 0; ZV = 0; V = 0.00 M/S

ACCELERATION ZONE/ ZONE D'ACCELERATION ZA=0
ZONAL ACCELERATION/ ACCELERATION ZONALE 0.00 G

VELOCITY ZONE/ ZONE DE VITESSE ZV=0
ZONAL VELOCITY/ VITESSE ZONALE 0.00 M/S

1990 NBCC/CNBC **
SEISMIC ZONING MAPS/ CARTES DU ZONAGE SEISMIQUE

PROBABILITY LEVEL: 10% IN 50 YEARS
NIVEAU DE PROBABILITE: 10% EN 50 ANNEES

G OR M/S	ZONE	ZONAL VALUE/ VALEUR ZONALE
0.00	0	0.00
0.04	1	0.05
0.08	2	0.10
0.11	3	0.15
0.16	4	0.20
0.23	5	0.30
0.32	6*	0.40

* ZONE 6: NOMINAL VALUE/ VALEUR NOMINALE 0.40;
SITE-SPECIFIC STUDIES SUGGESTED FOR IMPORTANT PROJECTS/
ETUDES COMPLEMENTAIRES SUGGEREES POUR DES PROJETS D'IMPORTANCE.

** FOR NBCC APPLICATIONS, CALCULATED ZONE VALUES AT A SITE SHOULD BE
REPLACED BY EFFECTIVE ZONE VALUES [ZA(EFF) OR ZV(EFF)] AS SHOWN BELOW/
POUR APPLICATIONS SELON LE CNBC, ON DOIT REMPLACER LES VALEURS ZONALES
CALCULEES POUR UN SITE PAR LES VALEURS EFFECTIVES [ZA(EFF) OU ZV(EFF)]
COMME MONTRE CI-DESSOUS:

1. IF/SI $(ZA - ZV) > 1$, $\implies ZA(EFF) = ZV + 1$.
OR/OU
2. IF/SI $(ZA - ZV) < 1$, $\implies ZA(EFF) = ZV - 1$.
OR/OU
3. IF/SI $ZV=0$ AND/ET $ZA > 0$, $\implies ZV(EFF) = 1$.

(SEE REFERENCE 2 CITED ABOVE, PAGE 677)
(VOIR PAGE 677 DE LA REFERENCE 2 CI-DESSUS)

Jul 9 2003 12:44