Golder Associates Ltd.

500 - 4260 Still Creek Drive Burnaby, British Columbia V5C 6C6 Telephone 604-296-4200 Fax 604-298-5253



REPORT ADDENDUM DETAILED DESIGN OF DEWATERING DIKES MEADOWBANK GOLD PROJECT

Submitted to:

Meadowbank Mining Corporation Suite 950, One Bentall Center 505 Burrard Street Vancouver, BC V7X 1M4

DISTRIBUTION:

1 Copy Dr. N. Morgenstern

2 Copies - Meadowbank Mining Corporation

2 Copies - Golder Associates Ltd.

July 12, 2007 07-1413-0047/3000

Doc. No. 492 Ver. 0





EXECUTIVE SUMMARY

This report addendum presents an update to: Detailed Design of Dewatering Dikes, Meadowbank Gold Project, March 13, 2007. The alignment of the south end of the Bay Zone Dike has been revised, resulting in water depths of less than 7.2 metres at dike centreline. Updated tables of volumes, quantities, specifications, and drawings presented here supersede those presented in the original design report.

TABLE OF CONTENTS

SECT	<u>ION</u>	<u>PAGE</u>
1.0	INTRO	DDUCTION 1
2.0		GN CRITERIA2
3.0		CLIMATE AND HYDROGEOLOGICAL CONDITIONS
4.0		OGICAL AND GEOTECHNICAL CONDITIONS
5.0		DESIGN2
	5.1	Design Concept2
	5.2	Stability Analyses
	5.3	Seepage2
		5.3.1 Summary of Results2
		5.3.2 Predicted Seepage2
6.0	CONS	STRUCTION AND OPERATION4
	6.1	Mine Development Plan4
	6.2	Materials Balance4
	6.3	Geotechnical Investigations4
	6.4	Dike Construction Sequence and Techniques5
	6.5	Instrumentation and Monitoring5
7.0	OPPC	PRTUNITIES10
CLOS	URE	
		ES11
IMPO	RTANT	INFORMATION AND LIMITATIONS OF THIS REPORT 12
	OF TAI	-
Table 1		Dike Characteristics
Table 5		Predicted Seepage Rates
Table 5		Summary of Dike Lengths
Table 5		Summary of Seepage Volumes
Table 6		Lake Volumes Inside Dewatering Dikes
Table 6		Geotechnical Instrumentation Summary
Table 6		Summary of Thermistor Strings
Table 6	5.5	Summary of Slope Inclinometer Locations
APPE	NDIX	
Appen	dix IV	Dike Construction and Cutoff Wall Review
Appen		Specifications
Appen		Drawings

1.0 INTRODUCTION

This addendum presents an update to the report: Detailed Design of Dewatering Dikes, Meadowbank Gold Project, March 13, 2007.

The alignment of the south end of the Bay Zone Dike has been revised, resulting in water depths of less than 7.2 metres at dike centreline.

The report addendum follows the layout of the original report, with identical numbering for updated tables and text sections. Only portions of the original report affected by the design changes are included.

Table 1.1 presents updated characteristics for the Bay Zone Dike. Revised estimates of the cutoff wall areas for the Goose Island Dike are also included. Areas of cutoff walls are taken to the surface of bedrock and do not account for embedment. Cutoff walls at abutments are not included in Table 1.1. A 30 m portion of the Goose Island Dike will be built as part of the Bay Zone Dike and the cutoff for this portion is therefore included with quantities for the Bay Zone Dike.

TABLE 1.1: Dike Characteristics

	East Dike	Bay Zone Dike	Goose Island Dike
Maximum water depth at cutoff wall (m)	5.8	7.2	20.1
Crest length at centreline excluding abutments (m)	840	1,479 Includes 30 m Goose Island Dike stub	1,735
Crest width (m)	77-93	86-102	82-134
Outer slopes	1.6 horizontal: 1 vertical	1.6 horizontal: 1 vertical	1.6 horizontal: 1 vertical
Crest elevation (masl)	136.1	136.1	136.1
Top cutoff elevation (masl)	135.1	135.1	135.1
Area of soil bentonite cutoff Wall (m ²)	5,160	3,832	4,890
Area of soil cement bentonite cutoff wall (m ²)	-	9,520	10,600
Area of jet grout cutoff wall (m ²)	-	-	7,790

2.0 DESIGN CRITERIA

No changes.

3.0 SITE CLIMATE AND HYDROGEOLOGICAL CONDITIONS

No changes.

4.0 GEOLOGICAL AND GEOTECHNICAL CONDITIONS

No changes.

5.0 DIKE DESIGN

5.1 Design Concept

No changes.

5.2 Stability Analyses

No changes. Revision of the alignment does not change the critical section for stability.

5.3 Seepage

The average length of the Bay Zone Dike increases from 1210 m to 1480 m. The average depth of the dike does not change significantly. Consequently, the average flow increases.

5.3.1 Summary of Results

Seepage analyses have been updated as follows:

• Seepage into Third Portage Pit is estimated to be on the order of 350 m³/day to 2,560 m³/day over the mine life.

5.3.2 Predicted Seepage

Predicted seepage rates are unchanged, as summarized in Table 5.7. Updated equivalent lengths of the Bay Zone Dike are shown in Table 5.8. Volumes of seepage for the dikes

- 3 -

based on the summation of the flow rates for each section are shown in Table 5.9, which has been updated to reflect changes in the Bay Zone Dike length.

TABLE 5.7: Predicted Seepage Rates

Section	Flux (l/day/m)						
	Water Depth (m)	At end of Drawdown	Pit Half Open	Pit Open	Closure		
Shallow	2	96	946	1081	39		
Medium	5.6	232	1009	1122			
Deep	20.1	372	1475	1538			

TABLE 5.8: Summary of Dike Lengths

Dike	Total Alignment Length (m)	Length Medium (m)	Length Deep (m)	Length Shallow (m)
East	830	Not applicable	Not applicable	680
Bay Zone	1480	1480	Not applicable	Not applicable
Goose Island	1720	1420	300	Not applicable

TABLE 5.9: Summary of Seepage Volumes

Dike	Total Seepage Volume (m³/day)						
Dike	At end of Drawdown	Pit Half Excavated	Pit Fully Excavated	Closure			
East Dike	80	820	900	30			
Bay Zone Dike	340	1500/670*	1660/740*				
Goose Island Dike	450	1900	2000				

^{*}Bay Zone Dike volumes given for Goose Island Dike not present/present.

July 2007

6.0 **CONSTRUCTION AND OPERATION**

6.1 **Mine Development Plan**

No changes.

6.2 **Materials Balance**

The increase in length of the Bay Zone Dike will require additional materials for dike construction. Requirements are provided in Appendix V, Administration Specification.

Table 6.2 summarizes estimates of total volume of water inside the proposed dewatering dikes for Second Portage Lake Arm, Third Portage Lake, and Vault Lake, based on bathymetry carried out at the site in 2002, 2003 and 2006. The total quantity of water inside the Bay Zone Dike and the Goose Island Dike does not change. However, volume estimates in Table 6.2 have been updated.

TABLE 6.2: Lake Volumes Inside Dewatering Dikes

Location	Location Lake Section				
	Northwest Basin (attenuation pond)	2.0			
Second Portage Lake Arm	Main Basin	10.5			
(elevation 133.1 masl)	East Basin (adjacent to East Dike)	2.0			
	Total Second Portage Lake Arm within East Dike	14.5			
	Inside Bay Zone Dike	0.7			
Third Portage Lake – Goose Island Area	Between Bay Zone Dike and Goose Island Dike	2.2			
	Total Third Portage Lake –Area within Goose Island Dike	2.9			
Vault Lake (elevation 139.4 m masl) Total Vault Lake within Vault Dike		2.2			
	Total				

6.3 **Geotechnical Investigations**

No changes.

6.4 Dike Construction Sequence and Techniques

No changes.

6.5 Instrumentation and Monitoring

Instrumentation requirements have been updated, as summarized in Tables 6.3, 6.4, and 6.5, and shown in Drawings 6000-30 to 32.

TABLE 6.3: Geotechnical Instrumentation Summary

Instrumentation	East Dike (840 m length)	Bay zone Dike (1480 m length)	Goose Island Dike (1735 m length)
Multi-level Piezometer	36	84	84
Thermistor Strings	7	17	9
Slope Inclinometers	3	7	7
Surface Prisms (25m spacing)	33	59	70
Surface Monuments (25m spacing)	33	59	70
Surface Control Monuments	2 (one at each abutment)	(one at each abutment and one on land southeast of dike)	2 (one at abutment and one on island south of dike)
Seismographs		2	

TABLE 6.4: Summary of Thermistor Strings

Dike	Thermistor String ID	Station	Offset (m) to Cut off wall	Bead Locations	Bedrock Surface El. (masl)	Lake Bed Till Surface El. (masl)	Thermistor String Length (m) from Crest El. 136.1 masl
	T1	30+260	0		122	128	17
	T2	30+540		First bead at surface	119	126	20
	Т3	30+680		• 0.5m, 1.0m, 1.5m, 2.0m, 2.5m, 3.0m, 4.0m, and 5.0m	106	114	33
	T4	30+840		depths for first 5m5m spacing afterwards	118	123	21
Goose Island	T5	31+140		Last bead embedded 3m into	128	132	11.1
	T6	31+400		bedrock	120	127	19
	T7	31+500			120	126	19
	Т8	31+720		First bead at surface	134.1	136.1	25
	Т9	25m downchainage of 31+720		5m spacing for 25m depth	134.1	136.1	25
	T10	0+160			132	133	8
.	T11	0+320		• First bead at surface • 0.5m, 1.0m, 1.5m, 2.0m,	132	134	7
Bay Zone	T12	0+520		2.5m, 3.0m, 4.0m, and 5.0m depths for first 5m5m spacing afterwards	121	127	18
	T13	0+720			126	130	13
	T14	0+920		Last bead embedded 3m into bedrock	121	127	19
	T15	1+120			128	134	11

Dike	Thermistor String ID	Station	Offset (m) to Cut off wall	Bead Locations	Bedrock Surface El. (masl)	Lake Bed Till Surface El. (masl)	Thermistor String Length (m) from Crest El. 136.1 masl
	T16		-22				5
	T17	0+520	-15		121	127	5
	T18		15	First bead at surface0.5m, 1.0m, 1.5m, 2.0m,			5
	T19		-22	2.5m, 3.0m, 4.0m, and 5.0m depths			5
	T20	0+920	-15	чериз	121	127	5
	T21		15				5
	T22	0+000	0		134.1	136.1	25
	T23	25m upchainage of 0+000		First bead at surface	134.1	136.1	25
	T24	1+479		• 5m spacing for 25m depth	134.1	136.1	25
Bay Zone	T25	25m down chainage of 1+479			134.1	136.1	25
Lone	Т33	1+280		 First bead at surface 0.5m, 1.0m, 1.5m, 2.0m, 2.5m, 3.0m, 4.0m, and 5.0m depths for first 5m 5m spacing afterwards Last bead embedded 3m into bedrock 	120.0	129.1	19.1

Dike	Thermistor String ID	Station	Offset (m) to Cut off wall	Bead Locations	Bedrock Surface El. (masl)	Lake Bed Till Surface El. (masl)	Thermistor String Length (m) from Crest El. 136.1 masl
	T26	60+240	0	First bead at surface0.5m, 1.0m, 1.5m, 2.0m,	128.1	130.1	11
	T27	60+440		2.5m, 3.0m, 4.0m, and 5.0m depths for first 5m • 5m spacing afterwards	126.0	128.0	13
_	T28	60+700		Last bead embedded 3m into bedrock	127.5	129.4	12
East	T29	60+000			134.1	136.1	25
	T30	25m upchainage of 60+000		First bead at surface5m spacing for 25m depth	134.1	136.1	25
	T31	60+839			134.1		25
	T32	25m down chainage of 60+839			134.1		25

TABLE 6.5: Summary of Slope Inclinometer Locations

Dike	Inclinometer String ID	5m upchainage from Station	Offset (m) to Cut off wall	Bedrock Surface El. (masl)	Lake Bed Till Surface El. (masl)	Inclinometer Casing Length (m) from Crest El. 136.1 masl
	S1	30+260		122	128	17
	S2	30+540		119	126	20
	S 3	30+680		106	114	33
Goose Island	S4	30+840		118	123	21
1014114	S 5	31+140		128	132	11
	S 6	31+400		120	127	19
	S7	31+500		120	126	19
	S8	0+160		132	133	8
	S 9	0+320	0	132	134	7
	S10	0+520		121	127	18
Bay Zone	S11	0+720		125	129	13
	S12	0+920		121	127	18
	S13	1+120		128	134	11
	S17	1+280		120	129	19
	S14	60+240		128	130	11
East	S15	60+440		126	128	13
	S16	60+700		127	129	12

7.0 OPPORTUNITIES

Opportunities to move the Bay Zone Dike alignment to eliminate the deep water section have been addressed by this report addendum.

CLOSURE

The reader is referred to the "Important Information and Limitations of This Report" which follows the text but forms an integral part of this document.

If you have any questions please do not hesitate to contact us.

GOLDER ASSOCIATES LTD.

ORIGINAL SIGNED BY

Ben Wickland, Ph.D., P.Eng. Geotechnical Engineer

ORIGINAL SIGNED AND SEALED BY

Terry L. Eldridge, P.Eng. Principal

BEW/TLE/aaf/mrb

 $O:\ \ Devatering\ Dikes\ Design\ Report\ Addendum\ Ver\ 0. Doc\ Ad$

REFERENCES

Golder, 2006. Detailed Design of Dewatering Dikes, Meadowbank Gold Project, Nunavut. Golder Associates Ltd. 2006

IMPORTANT INFORMATION AND LIMITATIONS OF THIS REPORT

Standard of Care: Golder Associates Ltd. (Golder) has prepared this report in a manner consistent with that level of care and skill ordinarily exercised by members of the engineering and science professions currently practising under similar conditions in the jurisdiction in which the services are provided, subject to the time limits and physical constraints applicable to this report. No other warranty, expressed or implied is made.

Basis and Use of the Report: This report has been prepared for the specific site, design objective, development and purpose described to Golder by the Client. The factual data, interpretations and recommendations pertain to a specific project as described in this report and are not applicable to any other project or site location. Any change of site conditions, purpose, development plans or if the project is not initiated within eighteen months of the date of the report may alter the validity of the report. Golder can not be responsible for use of this report, or portions thereof, unless Golder is requested to review and, if necessary, revise the report.

The information, recommendations and opinions expressed in this report are for the sole benefit of the Client. No other party may use or rely on this report or any portion thereof without Golder's express written consent. If the report was prepared to be included for a specific permit application process, then upon the reasonable request of the client, Golder may authorize in writing the use of this report by the regulatory agency as an Approved User for the specific and identified purpose of the applicable permit review process. Any other use of this report by others is prohibited and is without responsibility to Golder. The report, all plans, data, drawings and other documents as well as all electronic media prepared by Golder are considered its professional work product and shall remain the copyright property of Golder, who authorizes only the Client and Approved Users to make copies of the report, but only in such quantities as are reasonably necessary for the use of the report by those parties. The Client and Approved Users may not give, lend, sell, or otherwise make available the report or any portion thereof to any other party without the express written permission of Golder. The Client acknowledges that electronic media is susceptible to unauthorized modification, deterioration and incompatibility and therefore the Client can not rely upon the electronic media versions of Golder's report or other work products.

The report is of a summary nature and is not intended to stand alone without reference to the instructions given to Golder by the Client, communications between Golder and the Client, and to any other reports prepared by Golder for the Client relative to the specific site described in the report. In order to properly understand the suggestions, recommendations and opinions expressed in this report, reference must be made to the whole of the report. Golder can not be responsible for use of portions of the report

without reference to the entire report.

Unless otherwise stated, the suggestions, recommendations and opinions given in this report are intended only for the guidance of the Client in the design of the specific project. The extent and detail of investigations, including the number of test holes, necessary to determine all of the relevant conditions which may affect construction costs would normally be greater than has been carried out for design purposes. Contractors bidding on, or undertaking the work, should rely on their own investigations, as well as their own interpretations of the factual data presented in the report, as to how subsurface conditions may affect their work, including but not limited to proposed construction techniques, schedule, and safety and equipment capabilities.

Soil, Rock and Groundwater Conditions: Classification and identification of soils, rocks, and geologic units have been based on commonly accepted methods employed in the practice of geotechnical engineering and related disciplines. Classification and identification of the type and condition of these materials or units involves judgment, and boundaries between different soil, rock or geologic types or units may be transitional rather than abrupt. Accordingly, Golder does not warrant or guarantee the exactness of the descriptions.

Special risks occur whenever engineering or related disciplines are applied to identify subsurface conditions and even a comprehensive investigation, sampling and testing program may fail to detect all or certain subsurface conditions. The environmental, geologic, geotechnical, geochemical and hydrogeologic conditions that Golder interprets to exist between and beyond sampling points may differ from those that actually exist. In addition to soil variability, fill of variable physical and chemical composition can be present over portions of the site or on adjacent properties. The professional services retained for this project include only the geotechnical aspects of the subsurface conditions at the site, unless otherwise specifically stated and identified in the report. The presence or implication(s) of possible surface and/or subsurface contamination resulting from previous activities or uses of the site and/or resulting from the introduction onto the site of materials from off-site sources are outside the terms of reference for this project and have not been investigated or addressed.

Soil and groundwater conditions shown in the factual data and described in the report are the observed conditions at the time of their determination or measurement. Unless otherwise noted, those conditions form the basis of the recommendations in the report. Groundwater conditions may vary between and beyond reported locations and can be affected by annual, seasonal and meteorological conditions. The condition of the soil, rock and groundwater may be significantly altered by construction activities (traffic, excavation, groundwater level lowering, pile driving, blasting, etc.) on the site or on adjacent sites. Excavation may expose the soils to changes due to wetting, drying or

frost. Unless otherwise indicated the soil must be protected from these changes during construction.

Sample Disposal: Golder will dispose of all uncontaminated soil and/or rock samples 90 days following issue of this report or, upon written request of the Client, will store uncontaminated samples and materials at the Client's expense. In the event that actual contaminated soils, fills or groundwater are encountered or are inferred to be present, all contaminated samples shall remain the property and responsibility of the Client for proper disposal.

Follow-Up and Construction Services: All details of the design were not known at the time of submission of Golder's report. Golder should be retained to review the final design, project plans and documents prior to construction, to confirm that they are consistent with the intent of Golder's report.

During construction, Golder should be retained to perform sufficient and timely observations of encountered conditions to confirm and document that the subsurface conditions do not materially differ from those interpreted conditions considered in the preparation of Golder's report and to confirm and document that construction activities do not adversely affect the suggestions, recommendations and opinions contained in Golder's report. Adequate field review, observation and testing during construction are necessary for Golder to be able to provide letters of assurance, in accordance with the requirements of many regulatory authorities. In cases where this recommendation is not followed, Golder's responsibility is limited to interpreting accurately the information encountered at the borehole locations, at the time of their initial determination or measurement during the preparation of the Report.

Changed Conditions and Drainage: Where conditions encountered at the site differ significantly from those anticipated in this report, either due to natural variability of subsurface conditions or construction activities, it is a condition of this report that Golder be notified of any changes and be provided with an opportunity to review or revise the recommendations within this report. Recognition of changed soil and rock conditions requires experience and it is recommended that Golder be employed to visit the site with sufficient frequency to detect if conditions have changed significantly.

Drainage of subsurface water is commonly required either for temporary or permanent installations for the project. Improper design or construction of drainage or dewatering can have serious consequences. Golder takes no responsibility for the effects of drainage unless specifically involved in the detailed design and construction monitoring of the system.

APPENDIX IV

DIKE CONSTRUCTION AND CUTOFF WALL REVIEW

APPENDIX V SPECIFICATIONS

1000-01	Meadowbank Dewatering Dikes Administration Specification	07-1413-0047/3000	
July 6, 2007	Page 1 of 20	Rev E	

PREPARED FOR:

PREPARED BY:



Е	06/JUL/07	ISSUED FOR BIDDING-QUANTITIES REVISED	BW	V.W.
D	13/MAR/07	ISSUED FOR BIDDING	AS	TLE
С	20/FEB/07	ISSUED FOR CLIENT REVIEW	AS	НН
Α	18/FEB/07	ISSUED FOR REVIEW	AS	НН
REV.	DATE	REASON FOR REVISION	BY	APP

1000-01	Meadowbank Dewatering Dikes	07-1413-0047/3000
	Administration Specification	
July 6, 2007	Page 2 of 20	Rev E

TABLE OF CONTENTS

SECT.	<u>ION</u>		<u>PAGE</u>
1.0	SCO	PE	4
2.0	GEN	ERAL	4
	2.1	General Site Conditions	4
	2.2	Definitions	5
	2.3	Codes and Regulations	7
3.0	EXEC	CUTION	8
	3.1	Scope of Work	
	3.2	Sequencing Description	9
		3.2.1 MMC Work Concurrent with Contractor Work	9
		3.2.2 Contractor work	9
4.0	MEE	ΓINGS	10
5.0	ENVI	RONMENTAL ISSUES	10
6.0	HEAL	.TH AND SAFETY	10
7.0	COO	PERATION	11
8.0	CON	STRUCTION FACILITIES AND TEMPORARY CONTROLS.	11
	8.1	Power Supply	11
	8.2	Construction Water	12
	8.3	Dust Control	12
	8.4	Surface Water Control	12
	8.5	Work Area	12
	8.6	Traffic Control	12
9.0		ILIZATION AND DEMOBILIZATION	
10.0	SUBN	MITTALS	13
11.0	COM	PLETION OF THE WORK	14
12.0	EXCL	LUSIONS	15
13.0	SITE	INSPECTION	15
14.0	MEAS	SUREMENT AND PAYMENT	15
15.0	PREL	IMINARY LIST OF QUANTIITES	15
16.0	REFE	ERENCE DRAWINGS AND SPECIFICATIONS	17

1000-01	Meadowbank Dewatering Dikes Administration Specification	07-1413-0047/3000
	Administration specification	
July 6, 2007	Page 3 of 20	Rev E

LIST OF TABLES

Table 1	Dewatering Dikes – Preliminary Quantities for Bidding Purposes
Table 2	Dewatering Dikes - List of Drawings
Table 3	Dewatering Dikes Construction - List of Specifications
Table 4	Mine Development Plan

1000-01	Meadowbank Dewatering Dikes Administration Specification	07-1413-0047/3000
July 6, 2007	Page 4 of 20	Rev E

1.0 SCOPE

This Specification provides general administrative requirements related to the Dewatering Dikes construction for Meadowbank Mining Corporation (MMC) at Meadowbank Gold Project site in Nunavut, Canada.

2.0 GENERAL

The gold ore deposits at Meadowbank Gold Project site are situated adjacent to and beneath Second Portage lake and Third Portage lake. Three dewatering dikes are required to isolate open pit mining activities from the lakes:

- East Dike— to be constructed prior to mill startup;
- Bay Zone Dike to be constructed prior to mill startup; and
- Goose Island Dike to be constructed by Year 2 of the mine life.

The construction methodology consists of:

- 1. Construction of rockfill dike, granular filter with glacial till core.
- 2. Construction of cutoff wall through the glacial till core.
- 3. Construction of grout curtain into the bedrock.

The dikes will be constructed by "bulkheading" the two rockfill embankments, leaving sufficient space between the two dikes to subsequently place the glacial till core zone. "Bulk heading" consists of dumping rockfill at the furthest or leading end of the active rockfill berm located in the lake, then pushing the rockfill over the edge with a bulldozer. The filter zone construction, either by clamshell or by bucket placement, will follow behind the rock dike embankment construction. The glacial till core backfill will be placed by bulkheading. The cutoff wall will be excavated through the glacial till core backfill. The type of cutoff wall (jet grout, soil-bentonite or cement-soil-bentonite) depends on the depth to the bedrock. A grout curtain will be constructed into the bedrock through the cutoff wall alignment.

A site investigation will be carried out prior to or concurrently with construction to characterize foundation conditions.

2.1 General Site Conditions

A summary of the subsurface conditions is presented in Golder Associates March 2007 Meadowbank Gold Project Dewatering Dike Detailed Design Report.

1000-01	Meadowbank Dewatering Dikes Administration Specification	07-1413-0047/3000
July 6, 2007	Page 5 of 20	Rev E

2.2 Definitions

Work	All activities associated with the construction of the dewatering dikes including quality control and instrumentation installation.
Manager	Meadowbank Mining Corporation (MMC) responsible for providing items noted in the contract package as being supplied by MCC, obtaining all relevant permits, and providing the contactor reasonable access to the general open areas surrounding the work site.
Contractor	A construction contracting company to be selected by MCC to carry out the Dewatering Dikes Construction Work.
	 Responsible to provide all other items and incidentals not supplied by the Manager to bring the construction Work or additional Work as requested by the Manager to final completion.
	 Contractor is responsible for proper construction of the work including any work performed by its Sub Contractors.
	 Shall provide survey control and Quality Control (QC) for the work it undertakes.
Engineer	• Reports to CM.
Engineer Construction Manager (CM)	 Golder Associates Ltd. (Golder) Represents the Manager on site and has the authority to direct all aspects of the work. Responsible for all project communications, arranging daily and weekly meetings as required, holding problem resolution meetings for resolution of Quality Assurance and Quality Control QA/QC issues.
	Work that has been stopped because of non- compliance with the QA/QC Plan shall resume only after a plan for corrective action prepared by the Contractor has been approved by the Construction Manager.

1000-01	Meadowbank Dewatering Dikes Administration Specification	07-1413-0047/3000
July 6, 2007	Page 6 of 20	Rev E

ı	
Quality Assurance Manager	 Represents the Engineer on site and has the authority to approve aspects of the work as following the design intent and specifications Responsible for performing tasks outlined in QC Requirements Specification 1000-08. QA manager has authority to stop any aspects of work that is not in compliance with the QA/QC Plan.
Approval	A written engineering or geotechnical opinion, concerning the progress and completion of the Work.
Quality Assurance (QA)	 Planned and systematic activities that provide adequate confidence to the Owner and various stakeholders that quality control is being implemented effectively.
Quality Control (QC)	 A planned system of inspection and testing carried out according to accepted standard specifications to ensure the quality of construction work.
Ice-rich Soil	 Frozen soils that contain more than 10 percent visible ice and/or have a moisture content greater than 30%. Normally ice lenses are present.
Ice-poor Soil	 Frozen soils that contain less than 10 percent visible ice and have a moisture content less than 30%. No visible ice lensing.
Rockfill IV	 Intermediate Volcanic waste rock material that is produced from the Portage Pit excavation meeting the design specification.
Rockfill IF	 Iron Formation waste rock material that is produced from the Portage Pit excavation meeting the design specification.
Rockfill UM+Q	 Ultramafic and quartzite waste rock material that is produced from the Portage Pit excavation meeting the design specification.
Coarse Filter	Material produced from IV rockfill and meeting the design specification.
Fine Filter	 Material produced from crushing of IV rockfill and meeting the design specification.

1000-01	Meadowbank Dewatering Dikes	07-1413-0047/3000
	Administration Specification	
July 6, 2007	Page 7 of 20	Rev E

Glacial till	 Glacial till soil consisting of clay, silt, and sand with gravel and cobble and meeting the design specification. Till and glacial till used interchangeably.
Bentonite-water slurry	• A stable colloidal suspension of powdered bentonite in water. The terms "slurry" and "bentonite-water slurry" are used interchangeably in Dewatering Dikes specifications.
Soil-Bentonite (SB) Backfill	A homogenous mixture of glacial till, bentonite and water.
Soil-Cement-Bentonite (SCB) Backfill	A homogenous mixture of glacial till, cement, bentonite and water.
Jet Grout Mixture	A homogenous mixture of cement and soil with or without bentonite used in Jet Grouting.
Work Completion Report	Summary report prepared by Contractor

2.3 Codes and Regulations

Work shall conform to, but not limited to the requirements of the latest editions of the following standards and codes which are part of this Specification:

ASTM D422	Test Method for Particle-Size Analysis of Soils
ASTM D1140	Test Method for Amount of Material in Soils Finer Than the No. 200 (75 µm) Sieve
ASTM C136	Test Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM D2216	Test Method for Laboratory Determination of Water (Moisture) Content of Soil and Rock
ASTM D2922	Test Methods for Density of Soil and Soil-Aggregate in Place by Nuclear Methods (shallow depths)
ASTM D6910	Standard Test Method for Marsh Funnel Viscosity of Clay Construction Slurries
ASTM D 422	Particle-Size Analysis of Soils
ASTM D 1140	Materials Finer than No. 200 Sieve

1000-01	Meadowbank Dewatering Dikes Administration Specification	07-1413-0047/3000
July 6, 2007	Page 8 of 20	Rev E

ASTM D 4318	Liquid Limit, Plastic Limit and Plasticity Index of Soils	
ASTM D 4380	Density of Bentonite Slurries	
ASTM D 4381	Sand Content by Volume of Bentonite Slurries	
ASTM D 2434	Hydraulic Conductivity Using a Rigid Wall Permeameter	
Mine Health and Safety Act (Nunavut)		
Mine Health and Safety Regulations (Nunavut)		

ASTM: American Society for Testing and Materials

API: American Petroleum Institute

Codes specific to the cutoff wall construction are provided in Soil-Bentonite and Soil-Cement-Bentonite Cutoff Wall Construction Specification 1000-05 and in Jet Grout Cutoff Wall Construction Specification 1000-04. QC Plan details are presented in QC Requirements Specification 1000-08.

3.0 EXECUTION

The Dewatering Dikes construction package includes Work to be carried out by both MMC and the Contractor. The following describes the scope of work and defines work to be carried out by each of MMC and the Contractor, and presents the expected sequencing of the work.

3.1 Scope of Work

The scope or work is presented in the construction Drawings listed in Table 2 and the Specifications listed in Table 3. A plan for mine development is presented in Table 4. A general description of the Dewatering Dikes construction includes the following:

- Pre-construction geotechnical investigations;
- rockfill embankment construction;
- coarse and Fine Filter placement;
- glacial till core backfill placement;
- cutoff wall construction;
- grout curtain installation; and
- instrumentation installation and monitoring.

1000-01	Meadowbank Dewatering Dikes	07-1413-0047/3000
	Administration Specification	
July 6, 2007	Page 9 of 20	Rev E

3.2 Sequencing Description

The following describes the expected general sequence for Dewatering Dikes construction and indicates work which is the responsibility of MMC and work which is the responsibility of the Contractor.

3.2.1 MMC Work Concurrent with Contractor Work

MMC will supply and place rockfill directly from the pit excavations.

3.2.2 Contractor work

The following work can be carried out by the Contractor:

- Coarse and Fine Filter production and placement;
- glacial till core backfill processing and placement;
- cutoff wall construction;
- grout curtain installation; and
- instrumentation installation and monitoring.

1000-01	Meadowbank Dewatering Dikes Administration Specification	07-1413-0047/3000
July 6, 2007	Page 10 of 20	Rev E

4.0 MEETINGS

Weekly progress meeting will be held and chaired by the CM and shall be attended by all parties. Minutes of meetings shall be prepared and distributed by the CM.

Other meetings may be called as required by the CM.

5.0 ENVIRONMENTAL ISSUES

The Contractor and his Sub Contractors are entirely responsible for prevention of pollution and other environmental problems related to the construction activities of the Dewatering Dikes construction.

The Contractor and his Sub Contractors shall incorporate environmental considerations while developing and implementing his own work procedures.

A draft copy of the Contractor's site specific Environmental Management plan (EMP) shall be prepared and submitted to the CM for review a minimum of 1 month prior to mobilization to Meadowbank. The CM and MMC will review and provide comments on the draft Environmental Management Plan to the Contractor.

The Contractor must have a MMC approved Environmental Management Plan prior to mobilization to the site.

The Contractor must maintain an up to date and approved Environmental Management Plan covering all work activities being conducted throughout the Work.

Any spill or environmental concern shall be reported immediately to the CM.

6.0 HEALTH AND SAFETY

The Contractor is entirely responsible for the Health and Safety (H&S) at the work site.

The Contractor and his Sub Contractors shall incorporate H&S considerations while developing and implementing their own work procedures.

The Contractor shall also comply with relevant H&S regulations and MMC H&S protocols and procedures.

The Contractor shall comply with any additional MCC H&S Safety Plan.

1000-01	Meadowbank Dewatering Dikes Administration Specification	07-1413-0047/3000
July 6, 2007	Page 11 of 20	Rev E

The Contractor shall observe the regulations, procedures and restriction for the ingress to the construction area.

The Contractor shall prepare and submit to the CM for review and approval a site-specific health and safety plan that compiles with MMC regulations and in addition covers any additional health and safety requirements specifically related to the Contractor's work. Following approval of the plan, the plan shall be implemented.

A draft copy of the Contractor's site specific H&S plan shall be prepared and submitted to the CM for review a minimum of 1 month prior to mobilization to Meadowbank. The CM and MCC will review and provide comments on the draft H&S plan to the Contractor.

The Contractor must have a MMC approved H&S Plan covering all work activities being conducted.

Any accident, near accident or H&S concern shall be reported immediately to the CM.

7.0 COOPERATION

The Contractor and his Sub Contractors shall cooperate with other parties to allow time and provide a safe work condition to carry out any site visit required to check environmental or health & safety concerns, perform control surveys and QA/QC operations. The Contractor and his Sub Contractors shall provide labour and equipment as required to contain and/or clean up any environmental spills.

8.0 CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS

Access to the site will be provided by the CM. The Contractor will not have sole access to the Work area and must be prepared to share and coordinate activities and access with others, through the CM. The Contractor shall coordinate with the CM the location of any staging areas, temporary facilities, haul roads or access roads.

8.1 Power Supply

The contractor shall provide any temporary power required for the Work.

1000-01	Meadowbank Dewatering Dikes Administration Specification	07-1413-0047/3000
July 6, 2007	Page 12 of 20	Rev E

8.2 Construction Water

Water for dust control, moisture conditioning material to be placed as fill, and for maintaining in-place fill soils shall be obtained by the Contractor. The Contractor must supply all the pumps and tanks necessary. Water will be available at a location determined by the CM.

8.3 Dust Control

During performance of the Work defined by the Specifications or any related operations, the Contractor shall control dust emissions.

8.4 Surface Water Control

The Contractor is responsible for controlling surface water and protecting Work from damage caused by this water.

8.5 Work Area

The Contractor shall:

- Store and dispense fuel, lubricating oils, and chemicals in such a manner to prevent or contain spills and prevent materials from entering local streams or groundwater according to applicable regulatory requirements.
- Maintain copies of Material Safety Data Sheets (MSDS) on file at the site for all hazardous materials.
- Avoid damaging instrumentation or instrumentation cables, such piezometers, used at the site.

8.6 Traffic Control

MCC mine heavy equipment and haulage traffic has the right of way at all times.

The Contractor shall provide a flag person or persons at intersections with limited visibility and heavy traffic.

1000-01	Meadowbank Dewatering Dikes Administration Specification	07-1413-0047/3000
July 6, 2007	Page 13 of 20	Rev E

9.0 MOBILIZATION AND DEMOBILIZATION

Comprises mobilization to the mine of all materials, supplies, equipment and tools required to carry out the Work. It includes demobilization out of the mine of all remaining materials, equipment, and tools, hauled on site by the Contractor to carry out the Work.

All the means of transportation shall be the exclusive responsibility of the Contractor. MMC shall not provide any transportation service to or within the mine.

The Contractor is solely responsible for the planning and mobilization of materials and construction equipment, in accordance with the construction schedule. It is also the responsibility of the Contractor that Sub Contractors and their transportation equipment comply with the same safety regulations as the Contractor.

It is required that all Contractor's and Sub Contractor's equipment to be used in the Work pass a technical inspection conducted by MMC Operations' personnel.

Upon completion of the Work, the Contractor shall remove any temporary structure built during the Work and/or shall require or remove any temporary construction that he may have installed during the Work.

The Contractor shall comply with all regulations at MCC regarding mobilization towards and within the mine.

10.0 SUBMITTALS

The Contractor must submit the following information to the CM:

With Bid:

- Summary of Company Experience;
- resumes of Proposed Contractor's Superintendent, Grouting and Drilling Operations Manager, Drillers, Grouting Operators, and other key personnel;
- a proposed schedule; and
- minimum equipment list, identifying the minimum equipment proposed to complete the Work.

1000-01	Meadowbank Dewatering Dikes	07-1413-0047/3000
	Administration Specification	
July 6, 2007	Page 14 of 20	Rev E

Prior to Mobilization:

- Site-specific Environmental Management Plan;
- site-specific Health and Safety Plan;
- description outlining the proposed methods for conducting the Work, including excavation, drilling, grouting, cutoff wall construction, earthwork;
- OC Plan; and
- revised schedule.

During Construction:

- Maintain an up-to-date construction schedule;
- maintain an up-to-date Environmental Management Plan covering all aspects of the Work; and
- maintain an up-to-date Health and Safety Plan covering all aspects of the Work.

11.0 COMPLETION OF THE WORK

Immediately upon completion of the Work the Contractor shall prepare the Work Completion Report (WCR) that shall provide as a minimum the following:

- Descriptive report;
- original construction record:
- copies of meeting minutes, Field Change Notices (FCN), Site Instructions (SI), Request for information (RFI), and any other format that has been part of the Work;
- original protocols of field or lab tests, duly signed by both parities (Contractor and Site Engineer);
- As Built Drawings based on as-built survey information for foundation preparation, placement for each construction material, and instrumentation installation layout in electronic AutoCAD and hard copy format;
- liner installation As-Built panel layout drawings in electronic AutoCAD and hard copy format;
- calculation sheets for actual quantities of work executed, duly signed by both parities (Contractor and Site Engineer);
- Liquidation of the Work;
- installation details of instrumentation in electronic and hard copy format; and
- final Safety Report.

1000-01	Meadowbank Dewatering Dikes Administration Specification	07-1413-0047/3000
July 6, 2007	Page 15 of 20	Rev E

The Contractor shall demonstrate compliance with all legal, tax, social security and other obligations required by MMC. Submittal of such documents shall be attached to each payment request.

12.0 EXCLUSIONS

Excluded from the scope of work are the materials furnished by MMC.

13.0 SITE INSPECTION

A compulsory site inspection will be held for all bidders. It is essential for all contractors intending on submitting a bid to attend this inspection. Contractors shall provide the following minimum PPE for each staff member attending the meeting:

- Steel toe boots;
- reflective vest:
- bard hat;
- safety glasses;
- hearing protection;
- gloves; and
- appropriate cold climate protection.

14.0 MEASUREMENT AND PAYMENT

Details on measurement and payment for bidding purposes will be added at a later date.

15.0 PRELIMINARY LIST OF QUANTIITES

For bidding purposes, a list of quantities associated with the work proposed in this document is provided in Table 1.

1000-01	Meadowbank Dewatering Dikes	07-1413-0047/3000
	Administration Specification	
July 6, 2007	Page 16 of 20	Rev E

TABLE 1: Dewatering Dikes – Preliminary Quantities for Bidding Purposes

Material	Approximate Quantity		
Material	Goose Dike	Bay Zone	East Dike
Rockfill Iron Formation	882 245 m ³	267 626 m ³	146 569 m ³
Rockfill Intermediate Volcanic	384 482 m ³	213 929 m ³	86 035 m ³
Rockfill Ultramafic and Quartzite	270 794 m ³	250 155 m ³	192 435 m ³
Fine Filter	26 601 m ³	10 245 m ³	6 492 m ³
Coarse Filter	26 601 m ³	10 245 m ³	6 492 m ³
Glacial Till Core Backfill	396 985 m ³	123 517 m ³	59 286 m ³
Soil-Bentonite Cutoff wall	4 890 m ³	3 832 m ³	5 158 m ³
Soil-Cement-Bentonite Cutoff wall	10 564 m ³	9 520 m ³	100 m ³
Jet Grout Cutoff wall	7 787 m ³	0 m^3	0 m^3
Bedrock Grouting	1 720 Linear m	1 470 Linear m	840 Linear m
Abutment Cutoff Excavation in Rock	50 m ³	100 m ³	100 m ³

1000-01	Meadowbank Dewatering Dikes	07-1413-0047/3000	
	Administration Specification		
July 6, 2007	Page 17 of 20	Rev E	

16.0 REFERENCE DRAWINGS AND SPECIFICATIONS

TABLE 2: Dewatering Dike - List of Drawings

Drawing	Number	Title	Revision
6000	00	Location Map And Drawing Index	В
6000	01	Overall Site Plan	В
6000	02	Borehole Location Plan	В
6000	03	Proposed Dike Layout Plan 1 Of 3) Goose Island Dike	В
6000	04	Proposed Dike Layout Plan (2 Of 3)- Bay Zone Dike	В
6000	05	Proposed Dyke Layout Plan (3 Of 3)- East Dike	A
6000	07	Proposed Dike Layout Plan (1 Of 3) - Goose Island Dike With Depth Of Lakebed Contours	В
6000	08	Proposed Dike Layout Plan (2 Of 3) - Bay Zone Dike With Depth Of Lakebed Contours	В
6000	09	Proposed Dike Layout Plan (3 Of 3) - East Dike With Depth Of Lakebed Contours	A
6000	11	Proposed Dike Layout Plan (1 Of 3) - Goose Island Dike With Soil Thickness Isopach Contours	В
6000	12	Proposed Dike Layout Plan (2 Of 3) - Bay Zone Dike With Soil Thickness Isopach Contours	В
6000	13	Proposed Dike Layout Plan (3 Of 3) - East Dike Soil Thickness Isopach Contours	A
6000	19	Proposed Sections (1 Of 5) - Goose Island Dike & Typical Section	В
6000	20	Proposed Sections (2 Of 5) - Goose Island Dike & Typical Section	В
6000	21	Proposed Sections (3 Of 5) - Goose Island Dike & Typical Section	В
6000	22	Proposed Sections (4 Of 5) - Goose Island Dike & Typical Section	В
6000	23	Proposed Sections (5 Of 5) - Goose Island Dike & Typical Section	В

1000-01	Meadowbank Dewatering Dikes	07-1413-0047/3000
	Administration Specification	
July 6, 2007	Page 18 of 20	Rev E

Drawing	Number	Title	Revision
6000	24	Proposed Sections (1 Of 4) - Bay Zone Dike & Typical Section	В
6000	25	Proposed Sections (2 Of 4) - Bay Zone Dike & Typical Section	В
6000	26	Proposed Sections (3 Of 4) - Bay Zone Dike & Typical Section	В
6000	27	Proposed Sections (4 Of 4) - Bay Zone Dike & Typical Section	В
6000	28	Proposed Sections (1 Of 2) - East Dike & Typical Section	В
6000	29	Proposed Sections (2 Of 2) - East Dike & Typical Section	В
6000	30	Dewatering Dike Instrumentation – Plan Location	В
6000	31	Dewatering Dike Instrumentation – Typical Section (1 Of 2)	В
6000	32	Dewatering Dike Instrumentation – Typical Section (2 Of 2)	В
6000	40	Geology Profile (1 Of 3) –East Dike	A
6000	41	Geology Profile (2 Of 3) - Bay Zone Dike	В
6000	42	Geology Profile (3 Of 3)- Goose Island Dike	В

1000-01	Meadowbank Dewatering Dikes	07-1413-0047/3000
	Administration Specification	
July 6, 2007	Page 19 of 20	Rev E

TABLE 3: Dewatering Dike Construction List of Specifications

Specification Number	Title	Revision
1000-01	Administration	E
1000-02	On Land Foundation Preparation and Excavation	D
1000-03	Fill Placement	D
1000-04	Jet Grout Cutoff Wall Construction	D
1000-05	Soil-Bentonite or Soil-Cement-Bentonite Cutoff Wall Construction	D
1000-06	Drilling and Grouting	D
1000-07	Instrumentation Installation	D
1000-08	Quality Control Requirements	D
1000-09	Care of Water	D
1000-10	Turbidity Barrier	D

TABLE 4: Mine Development Plan

Year	Key Issues		
-2 and -1	 Stripping at Third Portage peninsula for construction materials Construct Second Portage (East) dike and Bay Zone dikes Begin constructing Goose Island dike as construction material becomes available Lower water level behind East and Bay Zone dikes Construct plant site 		
1	 Commence mining of Third Portage pit, south end Portage pit water pumped to water sump at process plant Continue and complete construction of Goose Island dike. Dewater behind dike. Commence stripping of overburden materials 		

1000-01	Meadowbank Dewatering Dikes	07-1413-0047/3000
	Administration Specification	
July 6, 2007	Page 20 of 20	Rev E

Year	Key Issues
2	Commence mining at Goose Island pit
	Portage and Goose Island pit waters, and plant site and airstrip runoff to be directed to attenuation pond, or pumped to water sump at process plant for use as process water as required before discharge of excess to attenuation pond
3-4	 Portage and Goose Island pit waters, and plant site runoff waters, pumped to water sump at process plant for monitoring and treatment and use as process water as required before discharge of excess to attenuation pond.
	Begin construction of Vault haul road
	Construct Vault dike and dewater Vault Lake
5	Complete mining of Goose Island pit, and start abandonment
	Goose Island pit is available for storage of pit water
	• Pump pit water from Third Portage pit to Goose Island pit for early flooding, water quality monitoring, and in-pit treatment as required. Small quantity to be pumped to the process plant for treatment and use as process water
	• Begin mining northward at Third Portage pit towards North Portage deposit. Selective placement of waste rock into south end of Third Portage pit, or into Goose Island pit. Selective placement of ultramafic rock at Portage RSF for future use during closure.
	Commence mining at Vault
6-7	Continue and complete mining of Portage pit (north end)
	Continue mining of Vault pit
	Continue pumping Portage pit water to Goose Island pit lake until Portage pits are mined-out then allow pits to fill
	Monitor water quality within flooded pits, treating in-situ as required and/or pumping to process plant for use as process water
8	Complete mining in Vault
	• Continue pumping Portage pit water to Goose Island pit lake until Portage pits are mined-out, then allow pits to fill
	Monitor water quality within flooded pits treating in-situ as required and/or pumping to process plant for use as process water
	• Continue Goose Island pit flooding, monitoring and water treatment; commence Portage pit flooding, monitoring and water treatment.
9	Mining complete, start final abandonment and restoration
	Commence Vault pit flooding.

 $BW/mrb \\ \text{O:|ACTIVE|_2007|1413|07-1413-0047} \ \text{MEADOWBANK 2007 ENGINEERING|3000 BAY ZONE DIKE REALIGNMENT|SPEC1000-01-REVE-DEWATERING DIKES ADMINISTRATION .DOC}$

APPENDIX VI DRAWINGS

MEADOWBANK

MINING CORPORATION MEADOWBANK GOLD PROJECT

DE-WATERING DIKE DESIGN

	DRAWINGS INDEX	
DWG NO.	DRAWING TITLE	REVISION
6000-00	LOCATION MAP AND DRAWINGS INDEX	В
6000-01	OVERALL SITE PLAN	В
	BOREHOLE LOCATIONS PLAN	В
	PROPOSED DIKE LAYOUT PLAN (1 OF 3) - GOOSE ISLAND DIKE	В
	PROPOSED DIKE LAYOUT PLAN (2 OF 3) - BAY ZONE DIKE	В
	PROPOSED DYKE LAYOUT PLAN (3 OF 3) - EAST DIKE	A
	PROPOSED DIKE LAYOUT PLAN (1 OF 3) - GOOSE ISLAND DIKE WITH DEPTH OF LAKEBED CONTOURS	В
	PROPOSED DIKE LAYOUT PLAN (2 OF 3) - BAY ZONE DIKE WITH DEPTH OF LAKEBED CONTOURS	В
	PROPOSED DIKE LAYOUT PLAN (3 OF 3) - EAST DIKE WITH DEPTH OF LAKEBED CONTOURS	A
	PROPOSED DIKE LAYOUT PLAN (1 OF 3) - GOOSE ISLAND DIKE SOIL THICKNESS ISOPACH CONTOURS	В
6000-12	PROPOSED DIKE LAYOUT PLAN (2 OF 3) - BAY ZONE DIKE SOIL THICKNESS ISOPACH CONTOURS	В
6000-13	PROPOSED DIKE LAYOUT PLAN (3 OF 3) - EAST DIKE SOIL THICKNESS ISOPACH CONTOURS	Α
	PROPOSED SECTIONS (1 OF 5) - GOOSE ISLAND DIKE & TYPICAL SECTION	В
6000-20	PROPOSED SECTIONS (2 OF 5) - GOOSE ISLAND DIKE & TYPICAL SECTION	В
6000-21	PROPOSED SECTIONS (3 OF 5) - GOOSE ISLAND DIKE & TYPICAL SECTION	В
	PROPOSED SECTIONS (4 OF 5) - GOOSE ISLAND DIKE & TYPICAL SECTION	В
	PROPOSED SECTIONS (5 OF 5) - GOOSE ISLAND DIKE & TYPICAL SECTION	В
6000-24	PROPOSED SECTIONS (1 OF 4) - BAY ZONE DIKE & TYPICAL SECTION	В
6000-25	PROPOSED SECTIONS (2 OF 4) - BAY ZONE DIKE & TYPICAL SECTION	В
6000-26	PROPOSED SECTIONS (3 OF 4) - BAY ZONE DIKE & TYPICAL SECTION	В
6000-27	PROPOSED SECTIONS (4 OF 4) - BAY ZONE DIKE & TYPICAL SECTION	В
6000-28	PROPOSED SECTIONS (1 OF 2) - EAST DIKE & TYPICAL SECTION	В
6000-29	PROPOSED SECTIONS (2 OF 2) - EAST DIKE & TYPICAL SECTION	В
6000-30	DEWATERING DIKE INSTRUMENTATION - PLAN LOCATIONS	В
6000-31	DEWATERING DIKE INSTRUMENTATION - TYPICAL SECTION (1 OF 2)	В
6000-32	DEWATERING DIKE INSTRUMENTATION - TYPICAL SECTION (2 OF 2)	В
6000-40	GEOLOGY PROFILE (1 OF 3) - EAST DIKE	A
6000-41	GEOLOGY PROFILE (2 OF 3) - BAY ZONE DIKE	В
6000-42	GEOLOGY PROFILE (3 OF 3) - GOOSE ISLAND DIKE	В

Melville I.

Bathurs I.

Bathurs II.

Comwaits I.

Resolute

Comwaits I.

Persolute

Comwaits I.

Persolute

Comwaits I.

Persolute

Comwaits I.

Persolute

Comperiment

Cambridge Bay

Contha Denn.

NUNAVUT.

Cambridge Bay

Combia

Combia

Cambridge Bay

Combia

Combi

Nunavut 0 100 200 300 400 W. Kilometers

@ World Sites Atlas (sites atlas .com)

	LIST OF SPECIFICATIONS	
SPECIFICATION NO.	TITLE	REVISION
1000-01	ADMINISTRATION	E
1000-02	ON LAND FOUNDATION PREPARATION AND EXCAVATION	D
1000-03	FILL PLACEMENT	D
1000-04	JET GROUT CUTOFF WALL CONSTRUCTION	D
1000-05	SOIL-BENTONITE OR SOIL-CEMENT-BENTONITE CUTOFF WALL CONSTRUCTION	D
1000-06	DRILLING AND GROUTING	D
1000-07	INSTRUMENTATION INSTALLATION	D
1000-08	QUALITY CONTROL REQUIREMENTS	D
1000-09	CARE OF WATER	D
1000-10	TURBIDITY BARRIER	D

OCEAN QUEEN ELIZABETH IS.

NOTE:

UNUSED DWG NOS:

6000-06,

6000-10,

6000-14, 6000-15, 6000-16, 6000-17, 6000-18, 6000-37, 6000-38, 6000-39

NOT FOR CONSTRUCTION

NOT FOR CONSTRUCTION

STAPP

SEED FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOMEWING TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOMEWING TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOMEWING TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOMEWING TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOMEWING TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOMEWING TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOMEWING TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOMEWING TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOMEWING TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOMEWING TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOMEWING TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOMEWING TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOMEWING TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOMEWING TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOME TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOME TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOME TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOME TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOME TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOME TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOME TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOME TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOME TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOME TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOME TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT

A SOME TO SERVER FOR TENDER - BAYZONE DIRE RE-ALGRED, WEST ABUTHENT


A SOME TO SERVER


MEADOWBANK
MINING CORPORATION


MEADOWBANK GOLD PROJECT LOCATION MAP AND DRAWINGS INDEX



ROJECT N	0.	06-1413-081	FILE No.	071413004	7-3000_B	_00
ESIGN	SA	27NOV06	SCALE	AS SHOWN	REV.	В
CADD	EA	27NOV06				
HECK	AS	13MAR07	6000-00		00	
EVIEW	BW	13MAR07	1 ~		-	







LAND-BASED TOPOGRAPHIC MAJOR CONTOURS INTERVAL 10m LAND-BASED TOPOGRAPHIC MINOR CONTOURS INTERVAL 2m

BATHYMETRIC MAJOR CONTOURS INTERVAL 10m BATHYMETRIC MINOR CONTOURS INTERVAL 2m

- ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE NOTED.
 ALL ELEVATIONS ARE IN METRES ABOVE SEA LEVEL (MASL), UNLESS OTHERWISE NOTED.
 GRID REFERENCE: NAD 83, UTM ZONE 14
- CONTOURS BELOW LAKE SURFACE ARE BASED ON BATHYMETRIC AND SEISMIC SURVEYS BY GOLDER ASSOCIATES LTD., 2006.
- 6) LAKE CONTOURS ARE BASED ON SURVEYED LAKE SURFACE ELEVATIONS: 2ND PORTAGE LAKE = 133.1M, 3RD PORTAGE LAKE = 134.1M

POINT	POINT DESC.	CHAINAGE	EASTING	NORTHING	CURVE DATA
50	B.P.	40+000.00	638948.9	7212810.1	
51	P.C.	40+295.61	639001.3	7212520.3	A= 20d11'18"
	P.I.	10.230.02	639019.1	7212443.6	R= 442
	C.C.		638570.8	7212420.3	T= 78.7
52	P.T.	40+451.34	639009.4	7212365.5	L= 155.7
53	P.C.	40+507.79	639002.4	7212309.5	A= 12d23'27°
	P.I.		638999.7	7212288	R= 200
	C.C.		638803.9	7212334.3	T= 21.7
54	P.T.	40+551.04	638992.5	7212267.5	L= 43.3
55	P.C.	40+695.54	638944.2	7212131.3	A= 26d29'12"
	P.I.	10080864680A	638923.3	7212072.2	R= 266.5
	C.C.		638693	7212220.3	T= 62.7
56	P.T.	40+818.72	638878.2	7212028.6	L= 123.2
57	P.C.	40+989.35	638755.4	7211910.1	A= 32d5'52"
	P.I.		638737	7211892.3	R= 89
	C.C.		638693.6	7211974.1	T= 25.6
58	P.T.	41+039.23	638712	7211887	L= 49.9
59	P.C.	41+069.08	638682.8	7211880.8	A= 37d57'4"
	P.I.		638659.2	7211875.9	R= 70.1
	C.C.		638668.3	7211949.4	T= 24.1
60	P.T.	41+115.50	638637.5	7211886.4	L= 46.4
61	P.C.	41+195.91	638565.3	7211921.7	A= 25d9'15"
	P.I.	200020000000000000000000000000000000000	638539.5	7211934.4	R= 128.8
	C.C.		638621.8	7212037.5	T= 28.7
62	P.T.	41+252.47	638521.4	7211956.8	L= 56.6
63	P.I.	41+419.76	638416.6	7212087.1	
64	P.C.	41+516.89	638367.3	7212170.8	A= 12d40'16'
	P.I.		638357.1	7212188.2	R= 181.4
	C.C.		638211	7212078.8	T= 20.1
65	P.T.	41+557.00	638343.3	7212202.9	L= 40.1
66	E.P.	41+669.66	638266.2	7212285	

POINT	POINT	CHAINAGE	EASTING	NORTHING	CURVE DATA
70	B.P.	60+000.0	639007.2	7212812.2	
71	P.C.	60+030.2	639004.4	7212782.1	A= 26d31'11"
	P.I.	501.50512	639000.1	7212735.1	R= 200
	C.C.		639203.6	7212763.7	T= 47.1
72	T.P.	60+122.8	639017.2	7212691.2	L= 92.6
73	P.I.	60+175.7	639036.4	7212641.9	
74	P.C.	60+228.3	639052.1	7212591.8	A= 19d58'4"
22000	P.I.		639081.8	7212496.7	R= 565.9
	C.C.	1 100	638512	7212422.6	T= 99.6
75	T.P.	60+425.5	639077.3	7212397.2	L= 197.2
76	T.P.	60+456.1	639076	7212366.6	
77	P.C.	60+491.9	639069.8	7212331.4	A= 17d4'53"
	P.I.		639066.4	7212311.7	R= 133.1
	C.C.		639200.9	7212308.5	T= 20
78	T.P.	60+531.6	639068.9	7212291.8	L= 39.7
79	P.C.	60+561.1	639072.6	7212262.5	A= 10d19'25"
	P.I.		639073.5	7212255.4	R= 80
	C.C.		638993.2	7212252.5	T= 7.2
80	T.P.	60+575.5	639073.1	7212248.2	L= 14.4
81	P.C.	60+642.4	639069.4	7212181.4	A= 17d55'49"
	P.I.	3443434	639067.6	7212149.4	R= 202.8
	C.C.		638866.9	7212192.5	T= 32
82	T.P.	60+705.8	639056.1	7212119.6	L= 63.5
83	P.C.	60+713.7	639053.3	7212112.3	A= 40d16'21"
	P.I.		639017.1	7212018.2	R= 274.8
	C.C.		638796.9	7212211.1	T= 100.8
84	T.P.	60+906.8	638928.7	7211969.9	L= 193.2
85	P.C.	60+934.7	638904.2	7211956.6	A= 13d0'18"
	P.I.	SERVICE CERTAINS	638862.2	7211933.6	R= 420
	C.C.		639105.6	7211588	T= 47.9
86	T.P.	61+030.0	638826.4	7211901.8	L= 95.3
87	P.C.	61+071.7	638795.3	7211874.1	A= 75d14'54"
	P.I.		638687.1	7211777.8	R= 187.9
	C.C.		638670.4	7212014.5	T= 144.8
88	T.P.	61+318.5	638566.4	7211858	L= 246.8
89	P.C.	61+382.2	638513.3	7211893.2	A= 10d21'39"
	P.I.		638506.5	7211897.7	R= 90.1
	C.C.		638563.2	7211968.3	T= 8.2
90	T.P.	61+398.5	638500.6	7211903.4	L= 16.3
91	P.I.	61+439.9	638470.9	7211932.1	
92	P.C.	61+455.4	638458	7211940.7	A= 34d16'33'
	P.I.		638352.8	7212011	R= 410.3
	C.C.		638686	7212281.8	T= 126.5
93	T.P.	61+700.8	638305.5	7212128.3	L= 245.4
94	P.I.	61+741.7	638290.2	7212166.3	
95	E.P.	61+816.4	638254.1	7212231.6	


MEADOWBANK


MINING CORPORATION


MEADOWBANK GOLD PROJECT PROPOSED DIKE LAYOUT PLAN (1 OF 3) **GOOSE ISLAND DIKE**





PROJECT No.		06-1413-081	06-1413-081 FILE No.		0714130047-3000_B_03			
DESIGN	SA	27NOV06	SCALE	AS SHOWN	REV.	В		
CADD	EA	27NOV06						
CHECK	AS	13MAR07	6000-03					
REVIEW	RW	13MAR07						






















































- ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE NOTED.
 ALL ELEVATIONS ARE IN METRES ABOVE SEA LEVEL (MASL), UNLESS OTHERWISE NOTED.
 GRID REFERENCE: NAD 83, UTM ZONE 14

- 4) CONTOUR INFORMATION ON LAND SUPPLIED BY MEADOWBANK MINING CORPORATION.
 5) CONTOURS BELOW LAKE SURFACE ARE BASED ON BATHYMETRIC AND SEISMIC SURVEYS BY
- GOLDER ASSOCIATES LTD., 2006.
 6) LAKE CONTOURS ARE BASED ON SURVEYED LAKE SURFACE ELEVATIONS: 2ND PORTAGE LAKE = 133.1M, 3RD PORTAGE LAKE = 134.1M









NOT FOR CONSTRUCTION

MEADOWBANK MINING CORPORATION

MEADOWBANK GOLD PROJECT PROPOSED SECTIONS (2 OF 2) EAST DIKE & TYPICAL SECTION




PROJECT N	o.	06-1413-081	FILE No.	0714130047-3000_B_29		
DESIGN	SA	27NOV06	SCALE	AS SHOWN	REV.	В
CADD	EA	27NOV06				
CHECK	AS	13MAR07	6000-29			
REVIEW	BW	13MAR07				

0	20	40	60	80	100
		Scale in	Meters		

EA AS BW B 063UL07 ISSUED FOR TENDER - BAYZONE DIKE RE-ALIGNED, WEST ABUTMEN ISSUED FOR TENDER

CADD CHK RVW



O9MAR07 REV DATE DES

1SSUED FOR TENDER - BAYZONE DIKE RE-ALIGNED, WEST ABUTMENT

ISSUED FOR TENDER REVISION DESCRIPTION

- ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE NOTED.
 ALL ELEVATIONS ARE IN METRES ABOVE SEA LEVEL (MASL), UNLESS OTHERWISE NOTED.
 GRID REFERENCE: NAD 83, UTM ZONE 14
- CONTOUR INFORMATION ON LAND SUPPLIED BY MEADOWBANK MINING CORPORATION.
 CONTOURS BELOW LAKE SURFACE ARE BASED ON BATHYMETRIC AND SEISMIC SURVEYS BY
- GOLDER ASSOCIATES LTD., 2006.

 6) LAKE CONTOURS ARE BASED ON SURVEYED LAKE SURFACE ELEVATIONS: 2ND PORTAGE LAKE = 133.1M, 3RD PORTAGE LAKE = 134.1M

 7) SEISMOGRAPH LOCATIONS ARE 1MX1M CONCRETE PADS
- SURVEY MONUMENTS ARE SPACED 25M ALONG CREST CENTRELINE.
 SURVEY CONTROL MONUMENTS SHALL BE CONSTRUCTED ON LAND AS TYPE D GIVEN IN U.S.

ARMY CORPS OF ENGINEERS EM1110-1-1002.

- o T1 : THERMISTOR.
- : SURVEY MONUMENT.
- : SEISMOGRAPH LOCATION.
- : SURVEY CONTROL MONUMENTS.

NOT FOR CONSTRUCTION


MEADOWBANK

MINING CORPORATION

MEADOWBANK GOLD PROJECT DEWATERING DIKE INSTRUMENTATION **PLAN LOCATIONS**



PROJECT No.		06-1413-081	FILE No.	0714130047-3000_B_30			
DESIGN	SA	27NOV06	SCALE	AS SHOWN	REV.	В	
CADD	EA	27NOV06	- Commence of the Commence of				
CHECK	AS	13MAR07	6000-30				
REVIEW	BW	13MAR07	1 "				



09MAR07 REV DATE DES

ISSUED FOR TENDER - BAYZONE DIKE RE-ALIGNED, WEST ABUTMENT

REVISION DESCRIPTION

NOTES:

- 1) ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE NOTED.
- 2) ALL ELEVATIONS ARE IN METRES ABOVE SEA LEVEL (MASL), UNLESS OTHERWISE NOTED.
- GRID REFERENCE: NAD 83, UTM ZONE 14
- 4) CONTOUR INFORMATION ON LAND SUPPLIED BY MEADOWBANK MINING CORPORATION.
- 5) CONTOURS BELOW LAKE SURFACE ARE BASED ON BATHYMETRIC AND SEISMIC SURVEYS BY GOLDER ASSOCIATES LTD., 2006.
- 6) LAKE CONTOURS ARE BASED ON SURVEYED LAKE SURFACE ELEVATIONS: 2ND PORTAGE LAKE = 133.1M, 3RD PORTAGE LAKE = 134.1M
- 7) THERMISTOR STRINGS SHALL BE INSTALLED ALONG SLOPE INCLINOMETER CASING.
 8) THERMISTOR STRINGS IN CUTOFF WALL TO BE DESIGNED AFTER DEPTH TO BEDROCK
- DETERMINED AT INSTRUMENT LOCATION. THERMISTOR BEADS TO BE SPACED AT 0.5m TO 3.0m DEPTH, SPACED AT 1.0m FROM 3.0m TO 5.0m DEPTH AND AT 5.0m SPACING TO MINIMUM OF 3.0m

LEGEND:

●P1 : PIEZOMETER.


OT1 : THERMISTOR.

MEADOWBANK MINING CORPORATION

MEADOWBANK GOLD PROJECT DEWATERING DIKE INSTRUMENTATION **TYPICAL SECTION (1 OF 2)**



PROJECT No.		06-1413-081	FILE No.	0714130047-3000_B_31			
DESIGN	SA	27NOV06	SCALE	AS SHOWN	REV.	В	
CADD	EA	27NOV06					
CHECK	AS	13MAR07	1 6000-31				
NOT/COM	DNA	13MAP07	1 -				



- 2) ALL ELEVATIONS ARE IN METRES ABOVE SEA LEVEL (MASL), UNLESS OTHERWISE NOTED.
- 6) LAKE CONTOURS ARE BASED ON SURVEYED LAKE SURFACE ELEVATIONS: 2ND PORTAGE LAKE =

- 9) THERMISTOR STRINGS IN CUTOFF WALL TO BE DESIGNED AFTER DEPTH TO BEDROCK DETERMINED AT INSTRUMENT LOCATION. THERMISTOR BEADS TO BE SPACED AT 0.5m TO 3.0m DEPTH, SPACED AT 1.0m FROM 3.0m TO 5.0m DEPTH AND AT 5.0m SPACING TO MINIMUM OF 3.0m INTO BEDROCK.

MINING CORPORATION

MEADOWBANK GOLD PROJECT DEWATERING DIKE INSTRUMENTATION **TYPICAL SECTION (2 OF 2)**

PROJECT No.		06-1413-081	FILE No.	0714130047-3000_B_32			
DESIGN	SA	27NOV06	SCALE AS SHOWN		REV.	В	
CADD	EA	27NOV06			850461		
CHECK	BW	13MAR07	6000-32				
REVIEW	TLE	13MAR07					

