

**APPENDIX B19 - DEWATERING DIKE : OPERATION, MAINTENANCE AND SURVEILLANCE
MANUAL, VERSION 3 (SEPT. 2013)**



MEADOWBANK GOLD PROJECT

DEWATERING DIKES

Operation, Maintenance and Surveillance Manual

Prepared by:
Agnico Eagle Mines Limited – Meadowbank Division

Version 3
September 2013

DEWATERING DIKES
OPERATION, MAINTENANCE AND
SURVEILLANCE MANUAL
MEADOWBANK GOLD PROJECT
AGNICO EAGLE MINES LIMITED

This Operation, Maintenance and Surveillance Manual has been prepared by Agnico Eagle Mines Limited and is to be used for the operation, maintenance and surveillance of the Dewatering Dikes at the Meadowbank Gold Project. All Registered Manual Holders are responsible for ensuring that they are using the most recent revision of this document. This Operation, Maintenance and Surveillance Manual, may not be copied in whole or in part without the written consent of Agnico Eagle Mines Limited.

IMPLEMENTATION SCHEDULE

This Plan is immediately implemented.

DISTRIBUTION LIST

AEM - General Manager Meadowbank

AEM- Environment Superintendent

AEM- Mine Operations Superintendent

AEM- Engineering Superintendent

AEM- General Services Manager

AEM- Corporate Environment Director

Golder- Dike Design Engineer

SNC- Dike Design Engineer

DOCUMENT CONTROL

Version	Date (YMD)	Section	Page	Revision
(first revision)	February 2012	All	All	
V2	August 27, 2013	All	All	
V3	September 15, 2013	All	All	Updated items mentioned by MDRB and the Mine Inspector in the Annual Geotechnical Inspection in September 2013

Approved by: _____
Julie Belanger
Engineering Superintendent

Kevin Buck
Environment Superintendent

TABLE OF CONTENTS

DISTRIBUTION LIST	I
DOCUMENT CONTROL	II
LIST OF TABLES.....	V
LIST OF FIGURES.....	VI
LIST OF APPENDICES	VI
SECTION 1 • INTRODUCTION.....	1-1
1.1 Purpose	1-1
1.2 Regulatory Requirements.....	1-1
1.3 Consequences of Failure.....	1-2
1.4 Registered Manual Holders and Revisions	1-2
1.5 Annual Review of Manual.....	1-2
1.6 Reference Documents and Drawings.....	1-3
SECTION 2 • ROLES AND RESPONSIBILITIES.....	2-1
2.1 Responsibilities.....	2-1
2.2 Required Levels of Knowledge.....	2-5
SECTION 3 • DESCRIPTION OF DEWATERING DIKES.....	3-1
3.1 East Dike	3-3
3.1.1 East Dike - Design and Construction.....	3-3
3.1.2 East Dike - Instrumentation.....	3-10
3.1.3 East Dike - Dewatering	3-18
3.1.4 East Dike - Seepage Collection System	3-18
3.1.5 East Dike - Access.....	3-19
3.2 Bay-Goose Dike	3-19
3.2.1 Bay-Goose Dike – Design and Construction	3-20
3.2.2 Bay-Goose Dike – Instrumentation.....	3-28
3.2.3 Bay-Goose Dike - Seepage Collection System	3-38
3.2.4 Bay-Goose Dike - Access	3-38
3.3 South Camp Dike	3-39
3.3.1 South Camp Dike – Design and Construction	3-39
3.3.2 South Camp Dike - Instrumentation.....	3-39
3.3.3 Seepage Collection System.....	3-40
3.3.4 South Camp Dike - Access	3-40

3.4	Vault Dike	3-42
3.4.1	Vault Dike – Design and Construction	3-42
3.4.2	Vault Dike – Dewatering	3-42
3.4.3	Vault Dike - Instrumentation	3-44
3.4.4	Vault Dike - Seepage Collection System	3-45
3.4.5	Vault Dike - Access.....	3-45
SECTION 4 • DEWATERING.....		4-1
4.1	Freeboard	4-1
4.2	Water Management and Quality.....	4-1
4.3	Surveillance and Monitoring Requirements.....	4-2
4.4	Safety and Security	4-2
SECTION 5 • OPERATIONS.....		5-1
5.1	Freeboard	5-1
5.2	Water Management	5-1
5.3	Water Quality	5-2
SECTION 6 • MAINTENANCE PROCEDURES		6-1
6.1	Planned and Un-Planned Maintenance.....	6-1
6.2	Embankment Erosion	6-1
6.3	Seepage Collection System	6-1
6.4	Instrumentation.....	6-2
6.5	Access	6-2
SECTION 7 • SURVEILLANCE		7-1
7.1	Surveillance Requirements.....	7-1
7.2	Surveillance Protocols	7-6
7.3	Responsibilities and Frequency.....	7-6
7.3.1	Dewatering Inspections (Daily and Weekly)	7-7
7.3.2	Daily and Weekly Routine Inspections	7-10
7.3.3	Monthly Routine Inspections.....	7-13
7.3.4	Engineering Inspection	7-13
7.3.5	Dam Safety Review	7-14
SECTION 8 • MONITORING AND INSTRUMENTATION		8-1
8.1	Dewatering – Drawdown Rate and Water Quality	8-1
8.2	Geotechnical Monitoring.....	8-1
8.2.1	Data Collection Protocols and Schedule	8-1
8.2.1.1	Thermistors.....	8-3
8.2.1.2	Survey Monuments and Prisms.....	8-3
8.2.1.3	Slope Inclinator Casings.....	8-3
8.2.1.4	Vibrating Wire Piezometers	8-4

8.2.1.5	Seismographs.....	8-4
8.2.2	Anomalous Instrumentation Data	8-4
8.3	Seepage Monitoring - Operations	8-5
8.3.1	Data Collection Protocols and Schedule	8-5
8.3.2	Anomalous Measurements	8-6
SECTION 9 • REPORTING PROCEDURES AND DATA MANAGEMENT		9-1
9.1	Reporting Protocols	9-1
9.1.1	Inspection Documents	9-1
9.1.2	Instrumentation Measurements	9-1
9.1.3	Emergencies	9-1
9.2	Data Management	9-1
SECTION 10 • DECOMMISSIONING		10-1
10.1	General	10-1
10.2	East Dike Embankments	10-1
10.3	Seepage Collection System	10-1
10.4	Instrumentation and Monitoring	10-1
SECTION 11 • EMERGENCY PREPAREDNESS PLAN		11-1
11.1	Emergency Procedures	11-1
11.1.1	Operation	11-1
11.2	Emergency Details	11-2
11.3	Medical and First Aid Services	11-4
11.4	On Site Equipment and material	11-4
SECTION 12 • EMERGENCY RESPONSE REFERENCE DOCUMENTS		12-1
SECTION 13 • REFERENCES.....		13-1

LIST OF TABLES

Table 1.1	Regulatory Requirements.....	1-1
Table 1.2	Classification of Dams in Terms of Consequences of Failure (CDA 2007)	1-1
Table 1.3	List of Registered OMS Manual Holders	1-2
Table 1.4	Record of Revisions/Addenda	1-2
Table 1.5	Summary of key reference documents for the Dewatering Dikes	1-3
Table 2.1	Responsibilities during Dewatering	2-2
Table 2.2	Responsibilities during Operation.....	2-4
Table 2.3	Recommended Minimum Knowledge and Training Requirements	2-6
Table 3.1	Existing Instrumentation Summary.....	3-11
Table 3.2	Existing Instrumentation Summary.....	3-29

Table 3.3 South Camp Dike Existing Instrumentation Summary	3-40
Table 3.4 Vault Dike Existing Instrumentation Summary	3-44
Table 4.1 Design Minimum Freeboard	4-1
Table 5.1 Freeboard	5-1
Table 5.2 Sump Design Criteria	5-2
Table 7.1 Summary of Consequences and Proposed Monitoring/Action for Rare Events Based on Water Retaining Embankment Failure Modes Identified in ICOLD (1998)	7-2
Table 7.2 Inspection, Monitoring and Review Requirements	7-7
Table 8.1 Geotechnical Instrumentation Monitoring Program	8-2
Table 12.1 Emergency Response Reference Documents	12-1
Table 12.2 Potential Effects or Causes of Failure Mechanisms	12-1
Table 12.3 Threshold Criteria during Operation for East Dike	12-3
Table 12.4 Threshold Criteria during Operation for Bay-Goose Dike	12-4
Table 12.5 Threshold Criteria during Operation for South Camp Dike	12-5
Table 12.6 Threshold Criteria during Operation for Vault Dike	12-6
Table 12.7 Communication Charts for Each Emergency Level	12-7
Table 12.8 Responsibilities of Persons for Each Emergency Level	12-7
Table 12.9 Names and Contact Details	12-8
Table 12.10 Emergency Response Summary for East Dike and Bay-Goose Dike	12-10
Table 12.11 Risk Matrix	12-13
Table 12.12 Risk assessment for East Dike, Bay-Goose Dike, South Camp Dike and Vault Dike	12-14
Table 13.1 References	13-1

LIST OF FIGURES

Figure 1 Organizational Structure	2-1
Figure 2 Site Plan	3-2
Figure 3 East Dike Plan and Profile	3-5
Figure 3A East Dike Plan view Thermistors between Sta. 60+440 to Sta.60+521	3-6
Figure 3B East Dike Profile view Thermistors between Sta. 60+440 to Sta.60+521	3-7
Figure 4 East Dike Typical Section	3-8
Figure 5 East Dike and Access Roads	3-9
Figure 6 Bay-Goose Dike Instrumentation Plan	3-24
Figure 7 Bay-Goose Dike – Profile View of SB and CSB Placement Zones	3-25
Figure 8 Bay-Goose Dike – Instrumentation Profile	3-26
Figure 9 Bay-Goose Dike – Typical Sections	3-27
Figure 10 Plan, cross section and profile of South Camp Dike	3-41
Figure 11 Vault Dike Typical Section	3-43
Figure 12 General Vault Pit area with the access roads	3-46
Figure 13 Earthwork Material and Equipment Location	11-8

LIST OF APPENDICES

- Appendix A: Inspection Forms
- Appendix B: Dike Failure Scenario Appendices from the ERP

SECTION 1 • INTRODUCTION

1.1 PURPOSE

This document includes procedures for the operation, maintenance and surveillance (OMS) of the Dewatering Dikes at the Meadowbank Gold Project, Nunavut, operated by Agnico Eagle Mines Limited (AEM), Meadowbank Division. The Dewatering Dikes are comprised of the following structures: East Dike, Bay-Goose Dike, South Camp Dike, and Vault Dike. The dewatering dikes isolate the open pit mining activities from Second Portage Lake and Third Portage Lake.

The responsibilities of AEM staff have been allocated based on the current management structure. As the management structure changes the OMS Manual should be revised and distributed accordingly.

This OMS Manual refers to the dewatering, operations, and decommissioning phases of the Dewatering Dikes.

1.2 REGULATORY REQUIREMENTS

This manual addresses specific requirements from regulatory agencies and provides procedures to maintain compliance. Regulatory requirements are presented in the documents summarized in Table 1.1.

Table 1.1 Regulatory Requirements

Document	Document Reference No.	Review Date
Territorial Lands Act - Land Lease	Production Lease KVPL08D280	Expires December 27, 2027
Environmental Impact Assessment	NIRB project certificate No. 004	n/a – Only if substantial modifications to original application are to be carried out
Water Licence Type A	Nunavut Water Board Water License 2AM-MEA0815	Expires May 31, 2015

The operating, maintenance, surveillance and emergency procedures recommended by the Canadian Dam Association (CDA) “Dam Safety Guidelines” (CDA 2007) and the Mining Association of Canada (MAC) “Developing an Operation, Maintenance and Surveillance Manual for Tailings and Water Management Facilities” (MAC, 2005) have been incorporated into this manual.

The CDA Dam Safety Guidelines (CDA, 2007) states: “dam operation, maintenance and surveillance shall be provided so that an acceptable level of dam safety is ensured.” This manual contains protocols and information that will assist AEM to operate, maintain, and monitor the Dewatering Dikes in a safe manner and identify early signs of distress. Qualified personnel shall operate, maintain and monitor the structures and adequate records shall be maintained for general and reference purposes.

1.3 CONSEQUENCES OF FAILURE

The Dewatering Dikes consequence of failure classification is based on the guidelines provided in the CDA Dam Safety Guidelines (CDA 2007) and is presented in Table 1.2. The East Dike and Bay-Goose Dike are rated as “High” consequence of failure structures based on the potential for loss of life and “High” economic loss. The South Camp Dike and Vault Dike are rated as a “Significant” consequence of failure structure based on a temporary risk to workers, and classified as “Low” due to economic loss.

No flooding or inundation mapping has been completed. It is assumed that failure of the East Dike could flood the Portage Pit, resulting in associated threat to the safety of mine personnel, equipment, and other workings within the dewatered area. Similarly, it is assumed that failure of the Bay-Goose Dike could flood the Goose Island Pit and Portage Pit, resulting in associated threat to the safety of mine personnel, equipment, and other workings within the dewatered area. Flooding would likely cause cessation of mining operations within one or both pits, either temporarily or permanently. It is assumed that failure of South Camp Dike could not flood the Bay-Goose Pit as the Third Portage Lake water level at South Camp Dike is too low. It is assumed that once the dewatering of Vault Lake will be complete, a failure of Vault Dike could flood Vault Pit resulting in associated threat to the safety of mine personnel, equipment, and other workings within the dewatered area. Flooding would likely cause cessation of mining operations within one or both pits, either temporarily or permanently.

Table 1.2 Classification of Dams in Terms of Consequences of Failure (CDA 2007)

Dam Class	Population at Risk [Note 1]	Incremental losses		
		Loss of Life [Note 2]	Environmental and Cultural Values	Infrastructure and Economics
Low	None	0	Minimal short-term loss No long-term loss	Low economic losses; area contains limited infrastructure or services
Significant	Temporary only	Unspecified	No significant loss or deterioration of fish or wildlife habitat Loss of marginal habitat only Restoration or compensation in kind highly possible	Losses to recreational facilities, seasonal workplaces, and infrequently used transportation routes
High	Permanent	10 or fewer	Significant loss or deterioration of <i>important</i> fish or wildlife habitat Restoration or compensation in kind highly possible	High economic losses affecting infrastructure, public transportation, and commercial facilities
Very High	Permanent	100 or fewer	Significant loss or deterioration of <i>critical</i> fish or wildlife habitat Restoration or compensation in kind possible but impractical	Very high economic losses affecting important infrastructure or services (e.g., <i>highway, industrial facility, storage facilities for dangerous substances</i>)
Extreme	Permanent	More than 100	Major loss of <i>critical</i> fish or wildlife habitat Restoration or compensation in kind impossible	Extreme losses affecting critical infrastructure or services (e.g., <i>hospital, major industrial complex, major storage facilities for dangerous substances</i>)

Note 1. Definitions for population risk:

None – There is no identifiable population at risk, so there is no possibility of loss of life other than through unforeseeable misadventure.

Temporary – People are only temporarily in the dam-breach inundation zone (e.g., seasonal cottage use, passing through on transportation routes, participating in recreational activities).

Permanent – The population at risk is ordinarily located in the dam-breach inundation zone (e.g., as permanent residents); three consequence classes (high, very high, extreme) are proposed to allow for more detailed estimates of potential loss of life (to assist in decision-making if the appropriate analysis is carried out).

Note 2. Implications for loss of life:

Unspecified – The appropriate level of safety required at a dam where people are temporarily at risk depends on the number of people, the exposure time, the nature of their activity, and other conditions. A higher class could be appropriate, depending on the requirements. However, the design flood requirement, for example, might not be higher if the temporary population is not likely to be present during the flood season.

1.4 REGISTERED MANUAL HOLDERS AND REVISIONS

The Engineering Superintendent is responsible for maintaining an up-to-date list of the registered holders of this OMS Manual in Table 1.3.

The Engineering Superintendent is also responsible for the issue of all revisions and addenda to the registered holders of this Manual. Revisions will be made, as and when required, by re-issuing a complete section, table or appendix so that the old section, table or appendix can be removed and replaced. Each registered holder is responsible for placing the revisions and addenda in his or her manual and for recording receipt of the same in Table 1.3.

Each copy of this manual is assigned a unique identification number.

Table 1.3 List of Registered OMS Manual Holders

Position / Name / Address or Location	OMS Manual Copy No.
General Manager Meadowbank / Jean Beliveau, Alexandre Proulx (ass.) / OFFICE	1
Environment Superintendent / Kevin Buck / OFFICE	2
Mine Operations Superintendent /Martin Beausejour, Brock Johnston (ass.) / OFFICE	3
Engineering Superintendent / Julie Belanger / OFFICE	4
Site Services Superintendent / Eric Trudel/ OFFICE	5
Dike Design Engineer / Golder Associates Ltd./ 500 – 4260 Still Creek Drive, Burnaby, BC, V5C 6C6	6
Dike Design Engineer / SNC-Lavalin Inc./ 5500, Boulevard des Galeries, Bureau 200, Quebec, Quebec, G2K 2E2	7
Update as Required	

Table 1.4 Record of Revisions/Addenda

Revision No.	Section	Table	Appendix	Addenda No.	Date of Revision
1	All	All	All	-	February 2012
2	All	All	All	-	August 2013
3	All	All	All	-	September 2013

1.5 ANNUAL REVIEW OF MANUAL

This manual will be reviewed by AEM on at least an annual basis and revised as necessary to accommodate changes in the condition and operation of the facilities. The registered users of the manual are encouraged to provide comments and suggestions for improvement of the manual and the procedures specified in it to the Engineering Superintendent. The comments and suggestions communicated will be considered in the subsequent review.

1.6 REFERENCE DOCUMENTS AND DRAWINGS

The following Table 1.5 is a summary of key reference documents for the Dewatering Dikes. All design and as-built documents can be found in hard copy onsite in the engineering department, as well as in electronic copies on the dikes server.


Table 1.5 Summary of key reference documents for the Dewatering Dikes

Dewatering Dike	Type of Information	Document Number	Document Title
East Dike	Design	Doc. 572	East Dike Design Meadowbank Gold Project (Golder 2008b)
	As-built	Doc. 900	East Dike Construction As-Built Report Meadowbank Gold Project (Golder 2009d)
	Remediation	Doc. 916	Meadowbank East Dike Grouting Response Plan (Golder 2009b)
		Doc. 953	East Dike CPT Investigation Meadowbank Gold Project" (Golder 2010b)
		Doc. 986	East Dike Sinkhole Investigation Program Meadowbank Gold Project (Golder 2010a)
Bay-Goose Dike	Design	Doc. 802	Bay-Goose Dike and South Camp Dike Designs (Golder 2009a)
	As-built	Doc. 1328	Bay Goose Dike Construction As-Built Report Meadowbank Gold Project (Golder 2013)
South Camp Dike	Design	Doc. 802	Bay-Goose Dike and South Camp Dike Designs (Golder 2009a)
	As-built	NA	South Camp Dike Construction Summary Report, Meadowbank Gold Project (AEM 2012)
Vault Dike	Design	610548-2020-4GER-0001	Detailed Engineering of Vault Dike (SNC, 2013a)
	Technical Specifications	610548-2020-4GEF-0001	Construction of Vault Dike – Technical Specifications (SNC, 2013b)
	As-built	NA	Construction Summary Report Vault Dike (AEM, 2013)

SECTION 2 • ROLES AND RESPONSIBILITIES

An organizational chart of the current management structure is shown in Figure 1. This chart shall be updated to reflect changes in management structure, as necessary, such that it is maintained up-to-date.

Figure 1 Organizational Structure



2.1 RESPONSIBILITIES

The responsibilities for each management position during dewatering and during operations of the Dewatering Dikes are shown in Table 2.1 and Table 2.2, respectively. For the purpose of this manual, dewatering is defined as completed, except for Vault Lake which began to be dewatered in June 27, 2013, and operation begins when the downstream toe of the dike is exposed.

Table 2.1 Responsibilities during Dewatering

Position	Responsibilities
Manager of Regulatory Affairs	Liaise with external stakeholders during an emergency event including NIRB, Nunavut Water Board, NGO's, government agencies.
General Manager Meadowbank	Initiate and oversee emergency or contingency protocols during emergency events.
	Liaise/direct/coordinate the Meadowbank Dike Review Board (MDRB).
	Oversight of Mine, Engineering, and Environment Superintendents tasks and responsibilities as laid out in the OMS Manual.
Assistant General Manager	Initiate and oversee emergency or contingency protocols during emergency events, if General Manager is not on site.
	Oversight of Mine, Engineering, and Environment Superintendents tasks and responsibilities as laid out in the OMS Manual.
Mine Superintendent	Maintain access to the Dewatering Dikes, including making road repairs, controlling dust and removing snow. Maintain stockpiles of construction material.
	Carry out field maintenance on the dikes as required, including material placement, electrical and mechanical repairs.
Engineering Superintendent/Principal Geotechnical Engineer	Construction of seepage collection works.
	Carry out inspections of the dikes as required in the OMS Manual.
	Monitor Dewatering Dike instrumentation as required in the OMS Manual.
	Monitor pumping rates for dewatering, upstream and downstream water levels, and freeboard.
	Liaise with Design Engineer during dewatering regarding dike performance, pumping rates, water quality, instrumentation measurements, etc.
	Review geotechnical and environmental monitoring data for compliance with Water License regulations and to evaluate dike performance with respect to design parameters.
	Prepare reports including description of activities on dikes, pumping rates, instrumentation readings, water quality data, dike performance, visual observations, etc. as required in the OMS Manual.
	Determine dewatering pumping schedule based on the water quality monitoring.
	Maintain instrumentation, readout units, data acquisition system and cabins.
	Coordinate work force as required for monitoring and maintenance.

Position	Responsibilities
	Coordinate equipment, labour, materials and maintenance activities required for pumps and pipelines during dewatering.
	Revise and update the OMS Manual to reflect as-built conditions and any other changes.
	Maintain up to date list of registered holders of the OMS Manual.
	Issue all revisions and addenda to registered OMS Manual holders.
	Carry out field operations including pumping.
Environment Superintendent	Monitor water quality.
	Monitor total suspended solids at pump intake.
	Review environmental monitoring data for compliance with Water License and regulations and to evaluate dike performance with respect to design parameters.
	Liaise with external stakeholders including NIRB, Nunavut Water Board, NGO's, government agencies.
Site Services Superintendent	Maintain and service pumps and pipelines for dewatering.
	Coordinate equipment, labour and materials for maintenance during dewatering.
	Carry out field maintenance on material placement, electrical and mechanical repairs.
	Coordinate labour as required for monitoring.
Design Engineer	Communicate with Engineering Superintendent/ Dike Advisor on frequent basis regarding performance of dewatering dikes.
	Review instrumentation package (to be provided by Engineering Superintendent/Dike Advisor) on a frequent basis.
Meadowbank Dike Review Board (MDRB)	Be updated on the performance of the dewatering dikes behaviour during their operation.
Emergency Response Team	Follow the guidance written in the Emergency Response Plan in an emergency situation

Table 2.2 Responsibilities during Operation

Position	Responsibilities
Manager of Regulatory Affairs	Liaise with external stakeholders during an emergency event including NIRB, Nunavut Water Board, NGO's, government agencies.
General Manager Meadowbank	Liaise with external stakeholders including NIRB, Nunavut Water Board, NGO's, government agencies.
	Liaise / coordinate / direct the MDRB.
	Initiate and oversee emergency or contingency protocols during emergency events.
	Oversight of Mine, Engineering, and Environment Superintendents tasks and responsibilities as laid out in the OMS Manual.
	Coordination of mine staff and equipment during an emergency.
Assistant General Manager	Oversight of Mine, Engineering, and Environment Superintendents tasks and responsibilities as laid out in the OMS Manual.
	Coordination of mine staff and equipment during an emergency if General Manager is not on site.
Mine Superintendent	Maintain access to the Dewatering Dikes and seepage collection systems, including making road repairs, controlling dust and removing snow.
	Carry out field maintenance on the dikes as required, including material placement, electrical and mechanical repairs.
Engineering Superintendent/Principal Geotechnical Engineer	Carry out inspections of the dikes, ditches and sumps as required in the OMS Manual.
	Monitor seepage pumping rates.
	Monitor Dewatering Dike instrumentation as required in the OMS Manual.
	Review geotechnical instrumentation and environmental monitoring data to evaluate dike performance with respect to design parameters and for compliance with Water License and regulations.
	Prepare reports including description of activities on dikes, pumping rates, instrumentation readings, water quality data, dike performance, visual observations, etc. as required in the OMS Manual.
	Liaise with Design Engineer regarding dike performance, pumping rates, water quality, instrumentation measurements, etc.
	Maintain instrumentation, readout units, data acquisition system and cabins.
	Coordinate work force as required for monitoring and maintenance.
	Coordinate equipment, labour, materials and maintenance activities required for pumps and pipelines associated with the seepage collection systems and any runoff diversions.
	Revise and update the OMS Manual to reflect as-built conditions of seepage collection system and future modifications.
	Maintain up to date list of registered holders of the OMS Manual.
	Issue all revisions and addenda to the registered OMS Manual holders.
	Liaise with MDRB as required.
	Carry out field operations.
Environment Superintendent	Monitor water quality of seepage and runoff collected in sumps and

Position	Responsibilities
	ditches.
	Review environmental monitoring data for compliance with Water License and regulations and to determine dike performance with respect to design parameters.
	Liaise with external stakeholders including NIRB, Nunavut Water Board, NGO's, government agencies.
Site Services Superintendent	Maintain and service pumps and pipelines for seepage and runoff.
	Coordinate equipment, labour and materials for maintenance during dewatering.
	Carry out field maintenance on material placement, electrical and mechanical repairs
	Coordinate labour as required for monitoring and maintenance.
	Purchase equipment as required.
Design Engineer	Communicate with Engineering Superintendent/ Dike Advisor on a frequent basis regarding performance of dewatering dikes. Frequency to be determined by Engineering Superintendent/ Dike Advisor.
	Review instrumentation package (to be provided by Superintendent/Dike Advisor) on a frequent basis, frequency to be determined by Engineering Superintendent/ Dike Advisor.
	Carry out annual inspection and reporting.
Meadowbank Dike Review Board (MDRB)	Be updated on the performance of the dewatering dikes behaviour during operation.
Emergency Response Team	Follow the guidance written in the Emergency Response Plan in an emergency situation

All site personnel are responsible for informing their Managers of any indications of abnormal situations or conditions that may be observed.

The responsibilities and authorities of each position in the OMS Manual should be updated to reflect any changes to the overall management structure as they occur.

2.2 REQUIRED LEVELS OF KNOWLEDGE

A minimum level of knowledge and training are required for personnel to adequately carry out their responsibilities and to appropriately realize their level of authority. Personnel should understand consequences of non-compliance for their area and have an understanding of emergency procedures. The recommended minimum levels of knowledge for the anticipated positions are as summarized in Table 2.3.

Table 2.3 Recommended Minimum Knowledge and Training Requirements

Position	Recommended Minimum Knowledge and Training
Manager of Regulatory Affairs	Review of the OMS Manual, with an understanding of the operational requirements. Detailed knowledge of emergency response procedures.
General Manager Meadowbank	Detailed understanding of the OMS Manual, with a complete understanding of the design, dewatering and operational requirements, particularly monitoring, inspection and dam safety review requirements.
	Complete understanding of environmental compliance issues and monitoring requirements.
	Understanding of all related technical documents for design and construction.
	Detailed knowledge of emergency response procedures.
Assistant General Manager	Detailed understanding of the OMS Manual, with a complete understanding of the design, dewatering and operational requirements, particularly monitoring, inspection and dam safety review requirements.
	Complete understanding of environmental compliance issues and monitoring requirements.
	Understanding of all related technical documents for design and construction.
	Detailed knowledge of emergency response procedures.
Environment Superintendent	Detailed understanding of the OMS Manual, with a complete understanding of the design, dewatering and operational requirements.
	Detailed and ongoing review of all monitoring, inspections and dam safety reviews.
	Complete understanding of environmental compliance issues and monitoring requirements.
	Knowledge of emergency response procedures.
Mine Operations Superintendent	Basic knowledge of the OMS Manual, with an understanding of the design requirements.
	Detailed knowledge of emergency response procedures.
Engineering Superintendent/Principal Geotechnical Engineer	Detailed understanding of the OMS Manual, with a complete understanding of the design, dewatering and operational requirements.
	Detailed knowledge of monitoring protocols and requirements.
	Detailed and ongoing review of all monitoring, inspections and dam safety reviews.
	Complete understanding of all related technical documents for design, dewatering, operation, risk assessment and emergency response.
	Detailed understanding of all operational elements within the facility and their operational and maintenance requirements.
	Detailed knowledge of emergency response procedures.
Environment Personnel	Knowledge of the OMS Manual, with an understanding of the dewatering and operational requirements set out in this OMS Manual.
	OMS Manual should be reviewed with the Environmental Superintendent.
	Detailed knowledge of environmental monitoring protocols and requirements.

Position	Recommended Minimum Knowledge and Training
	Knowledge of emergency procedures.
Mine Personnel	Knowledge of the OMS Manual, with an understanding of the dewatering and operational requirements set out in this OMS Manual.
	Knowledge of emergency response procedures.
Engineering Personnel	Knowledge of the OMS Manual, with an understanding of the design, dewatering, and operational requirements set out in this OMS Manual.
	Detailed knowledge of monitoring protocols and requirements.
	Knowledge of emergency procedures.
Site Services Superintendent	Basic understanding of the OMS Manual, including the design, dewatering and operational requirements set out in the OMS Manual.
	Detailed knowledge of all operational elements set out in the OMS and required for an event of emergency, such as available materials quantity and locations, equipment inventory and locations and available labour.
	Knowledge of emergency response procedures.
External Personnel (Design Engineer and MDRB)	Varied levels of knowledge and understanding depending on involvement.
	General Manager shall determine levels of knowledge and instruct personnel.
Emergency Response Team	Knowledge of emergency response procedures.

Training of personnel shall be carried out to ensure the minimum levels of knowledge set out in Table 2.3. Training shall be documented for each personnel in a staff database organized and maintained by AEM.

The OMS Manual should be updated to reflect any changes in responsibilities or management structure as they occur.

SECTION 3 • DESCRIPTION OF DEWATERING DIKES

The Meadowbank Gold Project site is located approximately 80 km north of Baker Lake, Nunavut. The gold ore deposits are situated adjacent to and beneath Second Portage Lake, Third Portage Lake and Vault Lake. The mine plan includes the construction and operation of a series of dewatering dikes to isolate the open pit mining activities from the lakes. Figure 2 presents the site plan. The Dewatering Dikes consist of the following structures:

- East Dike;
- Bay-Goose Dike;
- South Camp Dike; and
- Vault Dike.

A description of the physical conditions of the site, as well as a description of the climate, geological and geotechnical conditions can be found in various documents including the design documents for the East Dike and Bay-Goose Dike Doc. 572 Sections 3.0 and 4.0 (Golder 2008b) and Doc. 802 Section 2.0 (Golder 2009a), respectively.

In 2008 the East Dike and West Channel Dikes were constructed to isolate the northwest arm of Second Portage Lake to permit mining of Portage Pit and also to provide an area for the storage of tailings. Dewatering of the northwest arm of Second Portage Lake began in the spring of 2009 and was halted during the summer of 2009. Dewatering recommenced in the fall of 2009. The downstream toe of the East Dike has been exposed continuously since July 2010 although was mostly exposed by July 2009. Dewatering of the basin continued intermittently as other construction and site water was transferred to the basin as part of the operations.


In 2009 the South Camp Dike was constructed. The earthworks component of the Bay-Goose Dike construction occurred over two summer construction seasons. The north portion of the Bay-Goose Dike was constructed in 2009 and the south portion in 2010. Grouting and jet grouting works commenced in 2010 and were completed by mid-July 2011.

Dewatering of the Bay-Goose Basin occurred between July 25 and November 14, 2011 following completion of the Bay-Goose Dike construction and instrumentation installation. In March 2012, the pre-stripping of Goose Pit started and it's now in the operation stage.

The construction of Vault Dike at Meadowbank was conducted from February 2013 to March 2013. Vault Dike is located across a shallow creek which connects Wally Lake and Vault Lake, at the Vault Pit area. Vault Dike is essential to allow the dewatering of Vault Lake and to isolate Vault Pit during mining activities from Wally Lake. The dewatering of Vault Lake has started on June 27th, 2013 and is scheduled to be complete at the end of November 2013.

The following subsections provide additional details for each of the Dewatering Dikes.

Figure 2 Site Plan



3.1 EAST DIKE

The East Dike together with the West Channel Dike isolates the northwest arm of Second Portage Lake. During the operational phase of the mine, the East Dike isolates the Portage Pit from Second Portage Lake. In closure, as the plan will include breaching of the Bay-Goose Dike thereby flooding both Goose and Portage Pits, then the East Dike will separate Third Portage Lake from Second Portage Lake. There are no spillways or water diversion works associated with the East Dike. The East Dike also used to serve as a haul road to connect the North Portage Pit to the ore stockpiles and to the crushing facility within the plant site. The West Channel Dike used to cover a narrow channel and prevent flow from Third Portage Lake to Second Portage Lake. The West Channel Dike together with the East Dike isolated the northwest arm of Second Portage Lake. The West Channel Dike purpose was no longer required and was removed as part of mining operations in the Portage Pit in 2012.

The East Dike was constructed in the summer of 2008 and grouting of the foundation and bedrock occurred in 2008 and during the first quarter of 2009. It is approximately 800 m in length, and was constructed within Second Portage Lake prior to dewatering. The dike consists of a wide rockfill shell, with downstream filters and a soil-bentonite cutoff wall that extends to bedrock. The cutoff wall extends up to 8 m below lake level.

3.1.1 East Dike - Design and Construction

The East Dike design is contained within Doc. 572 (Golder 2008b). A plan view and profile of the constructed dike is presented on Figure 3 and includes the locations of instrumentation installations used for monitoring. A typical cross section through the dike and is shown on Figure 4. Additional as-built information and as-built drawings for the East Dike are provided in Doc. 900 (Golder 2009e).

Dike construction occurred in the following general manner:

Rockfill Embankment:

- A rockfill platform approximately 50 m wide was advanced from the south abutment to the north. The rockfill platform provided construction access and support for the core materials.
- The width of the rockfill platform (embankment) was subsequently increased by placement of additional rockfill on the downstream side, to provide an adequate road width to accommodate two-way haul traffic.

Initial Trench Excavation:

- Rockfill and lakebed soils were excavated from the crest of the rockfill platform to expose bedrock along the cutoff centreline. Loose blocks or slabs from the bedrock surface were removed, as practical.

Backfilling of the Initial Trench:

- A coarse granular filter (150 mm minus) was placed using the bucket of the excavator on the downstream slope of excavation.
- Then the remaining portion of the excavation was backfilled with Core Backfill (19 mm minus) material in the central portion along the cutoff wall centreline and Coarse Filter (150 mm minus) material on the upstream and downstream sides of the Core Backfill. Backfilling of the trench with the Core Backfill and Coarse Filter materials was a simultaneous activity and occurred progressively as the initial trench was the excavation front advanced.
- At the bedrock surface, a minimum of 5 m of Core Backfill material was to be placed.

Compaction of Core Backfill:

- Core Backfill and Coarse Filter were placed to an elevation 2 m above the water level to form a platform from which densification could occur.
- The Core Backfill was densified using multiple passes of dynamic compaction. Craters produced by the dropped weight were backfilled to level the working platform between passes.

Cutoff:

- A 1 m wide trench was excavated through the Core Backfill material and extended to the bedrock surface along the cutoff wall centreline. Bentonite slurry was used to support the trench.
- The trench was backfilled with soil-bentonite.

Grouting:

- Grouting of the bedrock foundation and “contact area” identified as the zone between the base of the cutoff wall and bedrock surface was performed through the centerline of the cutoff wall.

Figure 3 East Dike Plan and Profile




Figure 3A East Dike Plan view Thermistors between Sta. 60+440 to Sta.60+521




Figure 3B East Dike Profile view Thermistors between Sta. 60+440 to Sta.60+521




Figure 4 East Dike Typical Section





Figure 5 East Dike and Access Roads



3.1.2 East Dike - Instrumentation

Instrumentation was installed prior to dewatering to monitor the behaviour of the dike and dike foundation during dewatering and operation. Instrumentation consisted of:

- Single vibrating wire piezometers located downstream of the cutoff wall;
- Arrays of vibrating wire piezometers, installed at various levels, upstream, immediately downstream of the cutoff wall and further downstream;
- Thermistor strings installed through the centreline of the cutoff wall;
- Inclinometers installed through the centreline of the cutoff wall; and
- Survey monuments along the centreline of the cutoff wall.

The monitoring network was expanded through the installation of additional instruments. Table 3.1 summarizes existing instrumentation.

Table 3.1 Existing Instrumentation Summary

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline + is d/s; - is u/s	Elevation (masl)	Details
Vibrating Wire Piezometer Array	60+190	190-P1-A	10	116.7	190-P1 Top of steel casing: El. 136.39
		190-P1-B	10	121.7	
		190-P1-C	10	126.7	
		190-P2-A	2	116.34	190-P2 Top of steel casing: El. 136.54
		190-P2-B	2	121.34	
		190-P2-C	2	126.34	
		190-P3-A	-2	116.63	190-P3 Top of steel casing: El. 136.54
		190-P3-B	-2	121.63	
Vibrating Wire Piezometer Array	60+490	490-P1-A	11	114.12	490-P1 Top of steel casing: El. 136.20
		490-P1-B	11	119.12	
		490-P1-C	11	125.81	
		490-P2-A	3.1	115.07	490-P2 Top of steel casing: El. 136.15
		490-P2-B	3.1	120.07	
		490-P2-C	3.1	126.76	
		490-P3-A	-0.9	114.62	490-P3 Top of steel casing: El. 136.02
		490-P3-B	-0.9	119.62	
Vibrating Wire Piezometer Array	60+700	700-P1-A	9.9	118.81	700-P1 Top of steel casing: El. 136.27
		700-P1-B	9.9	123.81	
		700-P1-C	9.9	130.5	
		700-P2-A	2	118.08	700-P2 Top of steel casing: El. 136.48
		700-P2-B	2	123.08	
		700-P2-C	2	129.77	
		700-P3-A	-1.9	117.93	700-P3 Top of steel casing: El. 136.40
		700-P3-B	-1.9	122.92	

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline + is d/s; - is u/s	Elevation (masl)	Details
Individual Vibrating Wire Piezometers	60+150	150-C	2.1	127.35	Top of steel casing: El. 136.33
	60+200	200-C	2	127.71	Top of steel casing: El. 136.29
	60+240	240-C	2	128.71	Top of steel casing: El. 136.26
	60+400	400-C	2.2	126.76	Top of steel casing: El. 136.27
	60+420	420-C	2	125.32	Top of steel casing: El. 137.10
	60+440	440-C	2	124.66	Top of steel casing: El. 137.14
	60+450	450-C	1.9	127	Top of steel casing: El. 136.22
	60+460	460-C	2	125.15	Top of steel casing: El. 137.60
	60+470	470-C	2	124.76	Top of steel casing: El. 137.43
	60+480	480-C	2	125.44	Top of steel casing: El. 137.65
	60+500	500-C	2	125.78	Top of steel casing: El. 137.34
	60+510	510-C	2	126.06	Top of steel casing: El. 137.10
	60+550	500-C	2	129.85	Top of steel casing: El. 136.24
	60+600	600-C	1.9	128.6	Top of steel casing: El. 136.53
	60+650	650-C	2	128.48	Top of steel casing: El. 136.59
	60+750	750-C	1.5	128.16	Top of steel casing: El. 136.93

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline + is d/s; - is u/s	Elevation (masl)	Details
Thermistor Strings	60+092	TH92	0	136 (1 st Bead)	Beads at Elev. 136, 135.5, 135, 134.5, 134, 133.5, 133, 132, 131, 130, 129, 127, 125, 123, 121 and 119 masl.
	60+185	TH185	0	136 (1 st Bead)	Beads at Elev. 136, 135.5, 135, 134.5, 134, 133.5, 133, 132, 131, 130, 129, 127, 125, 123, 121 and 119 masl.
	60+485	TH485	0	136 (1 st Bead)	Beads at Elev. 136, 135.5, 135, 134.5, 134, 133.5, 133, 132, 131, 130, 129, 127, 125, 123, 121 and 119 masl.
	60+440	P440	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+443	S443	0	136.5 (1 st Bead)	Beads at Elev. 136.50, 136.45, 136.40, 136.35, 136.30, 136.25, 136.20, 136.15, 136.10, 136.05, 136.00, 134.00, 132.00, 130.00, 128.00 and 126.00 masl.
	60+446	P446	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+449	S449	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+452	P452	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+455	S455	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline + is d/s; - is u/s	Elevation (masl)	Details
	60+458	P458	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+461	S461	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+464	P464	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+467	S467	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+479	S479	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+482	P482	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+483	T483	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+486	T486	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+488	P488	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline + is d/s; - is u/s	Elevation (masl)	Details
	60+491	S491	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+494	P494	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+497	S497	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+500	P500	0	136.5 (1 st Bead)	Beads at Elev. 136.50, 136.25, 136.00, 135.00, 134.00, 133.00, 132.00, 131.00, 129.00, 127.00, 125.00, 123.00, 121.00, 119.00, 117.00 and 115.00 masl.
	60+503	S503	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+506	P506	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+509	S509	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+512	P512	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+515	S515	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline + is d/s; - is u/s	Elevation (masl)	Details
	60+518	P518	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+521	S521	0	136 (1 st Bead)	Beads at Elev. 136, 135, 134, 133, 132, 131, 130, 129, 127, 125, 123, 121, 119, 117, 115 and 113 masl.
	60+695	TH695	0	136 (1 st Bead)	Beads at Elev. 136, 135.5, 135, 134.5, 134, 133.5, 133, 132, 131, 130, 129, 127, 125, 123, 121 and 119 masl.
	60+842	TH842	0	136 (1 st Bead)	Beads at Elev. 136, 135.5, 135, 134.5, 134, 133.5, 133, 132, 131, 130, 129, 127, 125, 123, 121 and 119 masl.

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline + is d/s; - is u/s	Elevation (masl)	Details
Inclinometer	60+195	ED-IN-195 (A and B Axis)	0.05	137.6 (Collar Elevation)	Azimuth 51.2 degree Destroyed in 2010
	60+495	ED-IN-495 (A and B Axis)	0.05	137.6 (Collar Elevation)	Azimuth 347.9
	60+705	ED-IN-705 (A and B Axis)	0.09	137.6 (Collar Elevation)	Azimuth 20.4 degree
Initial Crest Survey Monuments		100	0	136.9	Many have been destroyed since installation.
		101		136.8	
		102		136.7	
		103		136.6	
		104		136.9	
		105		136.8	
		106		136.9	
		107		136.7	
		108		136.6	
		109		136.5	
		110		136.6	
		111		136.3	
		112		136.5	
		113		136.7	
		114		136.8	
		115		136.7	
		116		136.8	
		117		136.7	
		118		136.7	

As installation of additional instrumentation occurs to broaden the existing monitoring network or to replace damaged instruments, the summary table and figures shall be updated.

Blast monitoring is carried out using portable blast monitoring seismographs that measure both blast induced velocities and accelerations at the point of monitoring (i.e. crest and/or the toe of the dike).

- Instrumentation locations are shown both in plan and profile on Figure 5.
- Records of all instrument installation details, data sheets, and calibration sheets shall be maintained and stored in a central location, such that they are readily available to AEM personnel and external reviewers.

3.1.3 East Dike - Dewatering

During dewatering of the northwest arm of Second Portage Lake, an apparent leak through the East Dike of up to 0.5 m³/s occurred over several days near Sta. 60+490. The leak then appeared to self heal following drilling works for the additional grouting carried out in this sector. A sinkhole cavity of about 18 m³ in the general vicinity of the leak (Sta. 60+472) also appeared in July 2009. The sinkhole was located immediately upstream of the cutoff wall and extended at least partially through the cutoff wall. A Technical Memorandum entitled “Meadowbank East Dike Grouting Response Plan – Completed Works” (Golder 2009b) provides additional information regarding the remedial grouting work and Golder Doc. No. 961 (Golder, 2009d) “East Dike Sinkhole Summary Report” provides more details about the sinkhole.

Following the appearance of the sinkhole, a cone penetration test (CPT) investigation was conducted, and three diamond drill holes and a surface geophysical survey were advanced in the area to obtain additional information. Based on the CPT results, there appeared to be a zone of coarser grained material (area with lower fines content) in the apparent leak area. The drilling investigation indicated that there may be soil between the base of the cut-off wall and underlying bedrock that was not completely excavated and/or grouted. An additional investigation of the sinkhole and apparent leakage area consisting of the temporary installation of thermistor strings and monitoring of the thermal condition was initially conducted in 2010 and repeated in 2011. Based on the thermal results, it appeared that a pervious zone existed within the cut-off wall and shallow bedrock between approximately Sta. 60+440 and 60+504. In the past, AEM considered potential mitigation options to reduce seepage through the dike and to provide contingency protection for the Portage Pit. Based on the stability of the dike and the seepage rate, remediation or implementation of contingency control measures is not considered necessary. The condition of the dike will continually be monitored and if the condition of the dike is judged to be deteriorating then remediation would be reassessed. Details regarding these investigations are provided in East Dike CPT Investigation Report (Golder, 2010b) and East Dike Sinkhole Investigation Program October-November 2009 (Golder 2010a).

The seepage is currently controlled by a seepage collection system and is not impacting the mining operation. The seepage is regularly monitored and appears to have stabilized and does not have a negative effect on the dike stability.

3.1.4 East Dike - Seepage Collection System

The purpose of the seepage collection system is to:

- Collect and convey seepage and runoff away from the downstream toe area; and
- Allow measurement of seepage through the dike.

The downstream toe of the East Dike was mostly exposed by July 2009 and then entirely by July 2010. Three seepage zones have been identified along the toe of the East Dike at approximately Sta. 60+480, Sta. 60+225 and Sta. 60+550. A temporary rectangular weir was installed in 2009 to monitor the seepage observed at approximately Sta. 60+480. Monitoring of the seepage from this location has occurred during the open water season (approximately mid-July through early October) in 2009 and 2010. During 2010, a temporary v-notch weir was installed to measure a second zone of

seepage exposed near Sta. 60+225 following dewatering. This portion of the dike was not exposed for visual inspection in 2009 due to the downstream water elevation. No monitoring system has been installed in the area around Sta. 60+550. Seepage flows have been measured to be between 7 L/s and 11 L/s at Sta. 60+480 and around 4 L/s at Sta. 60+225 and estimated to be about 1 L/s at Sta. 60+550.

The installation of a seepage collection system downstream of East Dike to capture and pump the seepage water started in September 2011 and was completed in 2012. After the system installation, 3 zones of seepage were identified near the downstream toe. The zones at about Sta. 60+247 and Sta. 60+498 each had a collection sump with pump connected to a year round pumping and piping system.

In 2011, the downstream seepage at Sta. 60+498 had been stable at a rate of about 864 m³/day (10 L/s) with no visual signs of turbidity, which was consistent with rates recorded during previous years. In 2011, the seepage downstream at Sta. 60+247 appeared stable at around 345.6 m³/day (4L/s) with no visual signs of turbidity noted, which was consistent with previous rates. Since the installation of the seepage collection system, all seepage is being captured within the sumps and no sign of additional seepage on the ground surface or downstream in the Portage Pit was observed. No active monitoring of the seepage rate at these locations occurred in 2012 but AEM has been visually inspecting the flow in the sumps and no turbidity was noted. AEM performed a pump test after the installation of the sumps, it was noted that the measured flow were consistent with 2010 and 2011 data. Flow meters have been installed in 2013 at the exit of each pump. The flow is approximately 1000 m³/day.

3.1.5 East Dike - Access

Access to the East Dike is from the north and south abutments, shown on Figure 2 and Figure 5. In 2010, the East Dike was used as a haul road connecting the North Portage Pit to the Plant Site. East Road was built downstream and used to function as haul road to get access from the east to Portage Pit. No haul trucks use the East Dike or East Road anymore during normal operations.

3.2 BAY-GOOSE DIKE

The Bay-Goose Dike together with the South Camp Dike isolates the Bay-Goose Basin from Third Portage Lake, which will permit mining of the Goose Pit and the southern portion of Portage Pit. No spillways or water diversion works are associated with the Bay-Goose Dike. Figure 2 shows the location of Bay-Goose Dike.

The Bay-Goose Dike is approximately 2,200 m in length and was constructed “in the wet”, prior to dewatering. The dike consists of a wide rockfill shell, with downstream filters and a cutoff wall constructed of a mixture of materials dependent on the location along the dike:

- Soil-bentontie (SB);
- Cement soil-bentonite (CSB);
- Jet grouted columns;

- A combination of soil-bentonite and cement soil-bentonite;
- A combination of soil-bentonite and/or cement soil-bentonite and jet grouted columns; and
- With the exception of the south abutment, the cutoff system (including the jet grouted columns) extends to bedrock and is up to 20 m below lake level.

The earthworks component of the Bay-Goose Dike construction occurred over two summer construction seasons. The north portion of the Bay-Goose Dike was constructed in 2009 and the south portion in 2010. Grouting and jet grouting works commenced in 2010 and were completed by mid-July 2011.

Dewatering of the Bay-Goose Basin occurred between July 25 and November 14, 2011 following completion of the Bay-Goose Dike construction and instrumentation installation. In March 2012, the pre-stripping of Goose Pit started and Goose Pit is now under operation stage.

Further details regarding the dike are provided in the following subsections.

3.2.1 Bay-Goose Dike – Design and Construction

The dike design is provided within Doc. 802 (Golder 2009a). A plan view of the dike along with the instrument locations is shown on Figure 6. Figure 7 provides the profile view along the cutoff wall centreline. Figure 8 provides the profile view of instrumentation details. Typical cross sections are shown on Figure 9. As-built drawings of the dike can be found in Golder 2009a.

Dike construction occurred in the following general manner:

Rockfill Platform / Embankment:

- A rockfill platform of varying width (approximately 60 to 90 m) was advanced from the north abutment to Goose Island, between July and September 2009 to an elevation of about 134 m.
- A rockfill causeway about 25 m wide was advanced from Goose Island to the south abutment between February and June 2010 while ice cover existed on Third Portage Lake. Ice was broken and removed, as practical, in front of the advancing rockfill platform.
- Following ice breakup from the lake in July 2010, additional rockfill was placed to widen the causeway to the full design width of the rockfill platform (approximately 55 to 100 m).
- The rockfill platforms surface elevation was about 134 m and was used to provide a working surface for the subsequent construction activities. The rockfill also provides lateral support for the granular core materials.

Initial Trench Excavation:

- Rockfill and lakebed soils were excavated from the rockfill platform surface to bedrock or competent lakebed soils along the cutoff centreline. As much as practical, loose blocks or slabs from the bedrock surface were removed.
- Ice rich soils beneath the cutoff wall were removed with the exception of at the south abutment where beyond Sta. 32+112 some ice-rich soils remain beneath the base of the initial trench excavation and cutoff wall.
- The required bottom width of the excavation varied based on its depth and varied between 8 and 11 m.

Backfilling of the Initial Trench:

North Portion of Dike

- A layer of Core Backfill (19 mm minus) material was placed along the downstream slope of the excavation such that Core Backfill material would be in contact with the lakebed soils.
- Then the remaining portion of the excavation was backfilled with Core Backfill (19 mm minus) material in the central portion along the cutoff wall centerline, with Coarse Filter (150 mm minus) material simultaneously placed on either side of the Core Backfill. Backfilling of the excavated trench occurred progressively as the excavation front advanced.

South Portion of Dike

- In very limited areas along the alignment, a layer of Core Backfill (19 mm minus) material was placed along the downstream slope of the excavation prior to the primary backfilling of the trench.
- The excavation was backfilled with Core Backfill (19 mm minus) material in the central portion along the cutoff wall centerline, with Coarse Filter (150 mm minus) material simultaneously placed on the downstream side of the Core Backfill and a “Fine Rockfill” material placed on the upstream side. Backfilling of the excavated trench occurred progressively as the excavation front advanced.
- In areas to be compacted using the vibratory-densification method, the width of Core Backfill material was required to be 8 m. Therefore, once the initial backfilling had been completed relatively small V-shaped excavations were made at the surface on either side of the initially placed Core Backfill. These excavations were then refilled with Core Backfill material to provide the required 8 m width of Core Backfill.

Compaction of Core Backfill:

- For all of the North Portion of the dike and a majority of the South Portion of the dike, a 2 m layer of Core Backfill, Coarse Filter, and Rockfill was placed to increase the elevation of the platform to provide a working surface for the dynamic compaction.

- The Core Backfill was densified using multiple passes of dynamic compaction. Craters produced by the dropped weight were backfilled to the level of the working platform between passes.
- For the South Portion of the dike, in zones where the initial excavation was not extended to bedrock, termed “partial cutoff” zones, compaction of the Core Backfill material was done using two methods: vibratory-densification and dynamic-compaction. Vibratory-densification of the Core Backfill material was conducted from the initial rockfill platform working surface (134 m). Vibro-densification was utilized to treat the Core Backfill material at the base of the excavation up to an elevation of about 128 m (i.e. 6 m below the water level). Then the 2 m of additional Core Backfill, Coarse Filter, and Rockfill materials were placed to increase the elevation of the platform to about 136 m creating the working surface for the dynamic compaction. The upper portion of the Core Backfill material was then treated using multiple passes of dynamic compaction. Craters produced by the dropped weight were backfilled to the level of the working platform between passes.

Cutoff:

- A 1 m wide trench was excavated through the Core Backfill material and extended to bedrock or competent till surface along the cutoff wall centreline. Bentonite slurry was used to support the trench.
- The trench was backfilled with:
 - Soil-bentonite (SB);
 - Cement Soil-bentonite (CSB); or
 - A combination of SB and CSB.
- Then a capping layer about 0.5 m thick of SB was placed above the trench to an approximate elevation of 136.5 m.

Jet Grouted Wall

- Jet grouting has been used to extend the low permeability element (cutoff wall) of the dike to the bedrock surface. A double jet system was used with a cement water ratio of 1:1 to construct the jet grouted columns. Jet grouting was completed from a working platform elevation of approximately 137 m.
- Jet grouting beneath the cutoff wall to the bedrock surface was conducted in the “partial cutoff” areas where the cutoff wall was not excavated to bedrock. This occurred in Channel 1 (Sta. 32+007 to 32+110), Channel 2 (Sta. 31+820 to 31+928), and Channel 3 (Sta. 31+575 to 31+611). Jet grouted columns were constructed with a centre to centre spacing of 1.2 m with an overlap with the cutoff wall and extended into the bedrock surface. Columns were constructed in two passes, primary columns at a spacing of 2.4 m with secondary columns subsequently constructed between the primary columns.

- Jet grouting was also conducted in two additional areas of the dike where significant silt accumulated at the base of the initial excavation and prevented the cutoff wall from being successfully constructed to bedrock. These two areas the North Channel (Sta. 30+361 to 30+435) and between Channel 1 and Channel 2 (Sta. 31+928 to 32+007). Jet grouted columns were constructed with a centre to centre spacing generally of 1.5 m, with the exception of the portion between Sta. 31+928 and Sta. 31+966.4 where a spacing of 1.2 m was utilized, following a primary and secondary sequence for installation.

Grouting:

- The working platform along the cutoff wall centerline was raised with Coarse Filter material to an elevation of 137 m, from which grouting work was conducted.
- Grouting of the bedrock foundation and “contact area” identified as the zone between the base of the cutoff wall or jet grout columns and bedrock surface was performed through the centerline of the cutoff wall.

Figure 6 Bay-Goose Dike Instrumentation Plan




Figure 7 Bay-Goose Dike – Profile View of SB and CSB Placement Zones




Figure 8 Bay-Goose Dike – Instrumentation Profile





Figure 9 Bay-Goose Dike – Typical Sections



3.2.2 Bay-Goose Dike – Instrumentation

Instrumentation was installed prior to dewatering to monitor the performance of the dike and dike foundation during dewatering and throughout the operational life of the structure.

Instrumentation provides information on the performance of the structure and its foundation and allows comparison with predictions of performance made during the design studies for deformation, seepage and thermal behaviour. Instrumentation may also provide early warnings regarding the development of unexpected pore water pressure responses to dewatering, pit blasting, increasing seepage and increasing deformation.

Several types of instruments have been installed to collect the required information, including the following:

- Single vibrating wire piezometers located downstream of the cutoff wall;
- Arrays of vibrating wire piezometers, installed at various levels, upstream, immediately downstream of the cutoff wall and further downstream;
- Thermistor strings installed through the centreline of the cutoff wall;
- Inclinometers installed through the centreline of the cutoff wall; and
- Survey monuments along the centreline of the cutoff wall.

Table 3.2 summarizes existing instrumentation. The instrumentation locations are shown in plan and section on Figure 6 and Figure 8, respectively.

Table 3.2 Existing Instrumentation Summary

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline (+ is d/s – is u/s)	Elevation (masl)	Details
Vibrating Wire Piezometer Array	30+158	1P1-A	14.43	116.41	1P1 Top of steel casing: El. 137.04 m
		1P1-B	14.43	121.41	
		1P1-C	14.43	127.41	
		1P2-A	1.97	117.05	1P2 Top of steel casing: El. 136.88 m
		1P2-B	1.97	122.05	
		1P2-C	1.97	128.05	
		1P3-A	1.94	117.13	1P3 Top of steel casing: El. 136.53 m
		1P3-B	1.94	122.13	
Vibrating Wire Piezometer Array	30+276.5	2P1-A	14.4	119.25	2P1 Top of steel casing: El. 136.99 m
		2P1-B	14.4	124.25	
		2P1-C	14.4	130.25	
		2P2-A	2.1	119.10	2P2 Top of steel casing: El. 137.52 m
		2P2-B	2.1	124.10	
		2P2-C	2.1	130.10	
		2P3-A	1.93	119.70	2P3 Top of steel casing: El. 137.18 m
		2P3-B	1.93	124.70	
Vibrating Wire Piezometer Array	30+378.5	3P1-A	14.42	113.12	3P1 Top of steel casing: El. 137.24 m
		3P1-B	14.42	118.12	
		3P1-C	14.42	124.12	
		3P2-A	2.03	113.10	3P2 Top of steel casing: El. 138.01 m
		3P2-B	2.03	118.10	
		3P2-C	2.03	124.10	
		3P3-A	2.01	113.58	3P3 Top of steel casing: El. 138.01 m
		3P3-B	2.01	118.58	
Vibrating Wire Piezometer Array	30+453.5	4P1-A	14.44	116.61	4P1 Top of steel casing: El. 137.14 m
		4P1-B	14.44	118.61	
		4P1-C	14.44	124.61	
		4P2-A	2.03	115.13	4P2 Top of steel casing: El. 137.40 m
		4P2-B	2.03	120.13	
		4P2-C	2.03	126.13	
		4P3-A	1.98	115.25	4P3 Top of steel casing: El. 137.68 m
		4P3-B	1.98	120.25	
Vibrating Wire Piezometer Array	30+645.5	5P1-A	14.58	118.00	5P1 Top of steel casing: El. 137.04 m
		5P1-B	14.58	123.00	
		5P1-C	14.58	129.00	
		5P2-A	1.97	117.85	5P2 Top of steel casing: El. 137.03 m
		5P2-B	1.97	122.85	
		5P2-C	1.97	128.85	
		5P3-A	2.09	115.15	5P3 Top of steel casing: El. 137.05 m
		5P3-B	2.09	122.60	
Vibrating Wire Piezometer Array	31+165	23P1-A	14.51	118.49	23P1 Top of steel casing: El. 137.62 m
		23P1-B	14.51	123.49	
		23P1-C	14.51	129.49	
		23P2-A	2.15	116.91	23P2 Top of steel casing: El. 137.86 m
		23P2-B	2.15	121.91	
		23P2-C	2.15	127.91	
		23P3-A	1.92	116.96	23P3 Top of steel casing: El. 136.59 m
		23P3-B	1.92	121.96	

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline (+ is d/s – is u/s)	Elevation (masl)	Details
Vibrating Wire Piezometer Array	31+600	24P1-A1	14.50	111.30	24P1 Top of steel casing: El. 137.45 m
		24P1-A2	14.50	116.30	
		24P1-B1	14.50	121.80	
		24P1-B2	14.50	124.30	
		24P2-A1	2.10	110.15	24P1 Top of steel casing: El. 137.83 m
		24P2-A2	2.10	116.15	
		24P2-B1	2.10	120.65	
		24P2-B2	2.10	123.15	
		24P2-C	2.10	124.65	24P3 Top of steel casing: El. 136.72 m
		24P3-A1	2.20	110.64	
		24P3-A2	2.20	115.64	
		24P3-B1	2.20	121.16	
Vibrating Wire Piezometer Array	31+815	25P1-A1	14.26	117.02	25P1 Top of steel casing: El. 137.45 m
		25P1-A2	14.26	122.02	
		25P1-B1	14.26	127.52	
		25P1-B2	14.26	129.52	
		25P2-A1	1.80	113.82	25P1 Top of steel casing: El. 137.77 m
		25P2-A2	1.80	118.82	
		25P2-B1	1.80	124.32	
		25P2-B2	1.80	126.32	
		25P2-C	1.80	127.32	25P3 Top of steel casing: El. 138.16 m
		25P3-A1	2.13	115.10	
		25P3-A2	2.13	120.10	
		25P3-B1	2.13	123.10	
Vibrating Wire Piezometer Array	31+885	26P1-A1	14.44	104.44	26P1 Top of steel casing: El. 137.27 m
		26P1-A2	14.44	109.44	
		26P1-B1	14.44	114.94	
		26P1-B2	14.44	117.94	
		26P2-A1	1.85	106.77	26P1 Top of steel casing: El. 137.93 m
		26P2-A2	1.85	111.77	
		26P2-B1	1.85	117.27	
		26P2-B2	1.85	120.27	
		26P2-C	1.85	123.27	26P3A Top of steel casing: El. 136.41 m
		26P3-A1	2.10	105.00	
		26P3-A2	2.10	111.36	26P3B Top of steel casing: El. 137.93 m
		26P3-B1	2.10	117.46	
		26P3-B2	2.10	119.86	

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline (+ is d/s – is u/s)	Elevation (masl)	Details
Vibrating Wire Piezometer Array	32+000	27P1-A1	14.45	113.25	27P1 Top of steel casing: El. 137.58 m
		27P1-A2	14.45	118.25	
		27P1-B1	14.45	123.75	
		27P1-B2	14.45	125.75	
		27P2-A1	2.03	112.61	27P1 Top of steel casing: El. 137.64 m
		27P2-A2	2.03	117.61	
		27P2-B1	2.03	123.11	
		27P2-B2	2.03	125.11	
		27P2-C	2.03	126.61	27P3 Top of steel casing: El. 137.71 m
		27P3-A1	1.91	111.72	
		27P3-A2	1.91	116.72	
		27P3-B1	1.91	122.22	
Vibrating Wire Piezometer Array	32+065	28P1-A1	14.40	102.99	28P1 Top of steel casing: El. 136.41 m
		28P1-A2	14.40	107.99	
		28P1-B1	14.40	112.99	
		28P1-B2	14.40	115.99	
		28P2-A1	1.90	105.02	28P1 Top of steel casing: El. 138.13 m
		28P2-A2	1.90	110.02	
		28P2-B1	1.90	115.02	
		28P2-B2	1.90	118.02	
		28P2-C	1.90	124.02	28P3 Top of steel casing: El. 137.89 m
		28P3-A1	1.86	105.91	
		28P3-A2	1.86	110.91	
		28P3-B1	1.86	115.91	
Vibrating Wire Piezometer Array	32+105	29P1-A1	14.44	115.32	29P1 Top of steel casing: El. 136.69 m
		29P1-A2	14.44	120.32	
		29P1-B1	14.44	125.32	
		29P1-B2	14.44	127.32	
		29P2-A1	2.01	114.99	29P1 Top of steel casing: El. 136.62 m
		29P2-A2	2.01	119.99	
		29P2-B1	2.01	124.99	
		29P2-B2	2.01	126.99	
		29P2-C	2.01	129.99	29P3 Top of steel casing: El. 136.80 m
		29P3-A1	2.04	115.91	
		29P3-A2	2.04	120.91	
		29P3-B1	2.04	125.91	
		29P3-B2	2.04	127.91	

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline (+ is d/s – is u/s)	Elevation (masl)	Details
Vibrating Wire Piezometer Individual	30+167	6P2	1.98	127.57	6P2 Top of steel casing: El. 136.86 m
	30+249.5	7P2	2.02	129.85	7P2 Top of steel casing: El. 137.80 m
	30+306.5	8P2	1.98	129.65	8P2 Top of steel casing: El. 137.50 m
	30+440	9P2	1.98	126.73	9P2 Top of steel casing: El. 137.43 m
	30+516.5	10P2	2.00	130.26	10P2 Top of steel casing: El. 137.16 m
	30+684.5	11P2	2.04	130.65	11P2 Top of steel casing: El. 137.15 m
	30+770	12P2	2.1	132.16	12P2 Top of steel casing: El. 137.09 m
	30+804.5	13P2	1.95	132.05	13P2 Top of steel casing: El. 137.19 m
	31+052	14P2	2.04	131.06	14P2 Top of steel casing: El. 137.81 m
	31+220	15P2	2.07	130.73	15P2 Top of steel casing: El. 137.01 m
	31+565	16P2	2.10	131.28	16P2 Top of steel casing: El. 137.65 m
	31+615	17P2	2.10	129.40	17P2 Top of steel casing: El. 137.67 m
	31+700	18P2	1.87	130.53	18P2 Top of steel casing: El. 137.59 m
	31+842	22P2	2.01	116.80	22P2 Top of steel casing: El. 137.98 m
	31+928	19P2	1.99	123.22	19P2 Top of steel casing: El. 137.28 m
	31+990	20P2	2.22	122.44	20P2 Top of steel casing: El. 137.70 m
	32+020	21P2	1.93	121.13	21P2 Top of steel casing: El. 137.94 m
Thermistor Strings	30+134	T1	0	135	Beads at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	30+185	T2	0	135	Beads at Elev. 135, 134, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	30+260	T3	0	130	Beads at Elev. 130, 129.7, 129.4, 129.1, 128.8, 128.5, 128.2, 127.9, 127.6, 127.3, 127, 126.7, 126.4, 126.1, 125.8 and 125.5 masl.

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline (+ is d/s – is u/s)	Elevation (masl)	Details
	30+261.5	T3'	0	136	Beads at Elev. 135.97, 134.97, 133.97, 132.97, 130.97, 128.97, 126.97, 124.97, 122.97, 120.97, 118.97 and 116.97 masl.
	30+272	T4	0	130	Beads at Elev. 130, 129.7, 129.4, 129.1, 128.8, 128.5, 128.2, 127.9, 127.6, 127.3, 127, 126.7, 126.4, 126.1, 125.8 and 125.5 masl.
	30+273.5	T4'	0	136	Beads at Elev. 135.97, 134.97, 133.97, 132.97, 130.97, 128.97, 126.97, 124.97, 122.97, 120.97, 118.97 and 116.97 masl.
	30+288.5	T5	0	130	Beads at Elev. 130, 129.7, 129.4, 129.1, 128.8, 128.5, 128.2, 127.9, 127.6, 127.3, 127, 126.7, 126.4, 126.1, 125.8 and 125.5 masl.
	30+290	T5'	0	136	Beads at Elev. 135.97, 134.97, 133.97, 132.97, 130.97, 128.97, 126.97, 124.97, 122.97, 120.97, 118.97 and 116.97 masl.
	30+330.5	T6	0	135	Beads at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	30+386	T7	0	135	Beads at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	30+417.5	T8	0	135	Beads at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	30+489.5	T9	0	135	Beads at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline (+ is d/s – is u/s)	Elevation (masl)	Details
	30+553.25	T10	0	135	Beads at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	30+621.5	T11	0	135	Beads at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	30+650	T12	0	135	Beads at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	30+713	T13	0	135	Beads at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	30+827	T14	0	135	Beads at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	31+080	T15	0	135	Beads at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	31+134.5	T16	0	135.08	Beads at Elev. 135.08, 134.08, 133.08, 132.08, 131.08, 130.08, 129.08, 128.08, 127.08, 126.08, 125.08, 123.08, 121.08, 119.08, 117.08 and 115.08 masl.
	31+170	T17	0	135	Beads at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	31+352	T18	0	135	Beads at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	31+595	T19	0	135	Beads at Elev. 135, 133.5, 132, 130.5, 129, 127.5, 126, 124.5, 123, 121.5, 120, 118, 116, 114, 111 and 108 masl.

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline (+ is d/s – is u/s)	Elevation (masl)	Details
	31+605	T20	0	135	Beds at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	31+752.5	T21	0	135	Beds at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	31+820	T22	0	135	Beds at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	31+850	T23	0	135	Beds at Elev. 135, 133.5, 132, 130.2, 129, 127.5, 126, 124.5, 123, 121.5, 120, 118, 116, 114, 111 and 108 masl.
	31+880	T24	0	135	Beds at Elev. 135, 133.5, 132, 130.2, 129, 127.5, 126, 124.5, 123, 121.5, 120, 118, 116, 114, 111 and 108 masl.
	31+960	T25	0	135	Beds at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	31+995	T26	0	135	Beds at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	32+030	T27	0	135	Beds at Elev. 135, 133.5, 132, 130.2, 129, 127.5, 126, 124.5, 123, 121.5, 120, 118, 116, 114, 111 and 108 masl.
	32+060	T28	0	135	Beds at Elev. 135, 133.5, 132, 130.2, 129, 127.5, 126, 124.5, 123, 121.5, 120, 118, 116, 114, 111 and 108 masl.
	32+100	T29	0	135	Beds at Elev. 135, 134, 133, 132, 131, 130, 129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
	32+140	T30	0	135	Beds at Elev. 135, 134, 133, 132, 131, 130,

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline (+ is d/s – is u/s)	Elevation (masl)	Details
					129, 128, 127, 126, 125, 123, 121, 119, 117 and 115 masl.
Inclinometer	30+282	1	0	139.8 (collar elevation)	
	30+390	2	0	140.5 (collar elevation)	
	30+640	3	0	139.3 (collar elevation)	
	31+180	4	0	139.5 (collar elevation)	
	31+590	5	0	140.0 (collar elevation)	
	31+815	6	0	139.7 (collar elevation)	
	31+885	7	0	139.3 (collar elevation)	
	32+065	8	0	139.6 (collar elevation)	
Crest survey monuments	30+050	1	0	139.6	
	30+075	2	0	139.5	
	30+100	3	0	139.7	
	30+125	4	0	139.5	
	30+150	5	0	139.4	
	30+175	6	0	139.7	
	30+200	7	0	139.6	
	30+475	8	0	140.3	
	30+500	9	0	140.1	
	30+525	10	0	140.1	
	30+550	11	0	140.0	
	30+575	12	0	139.8	
	30+600	13	0	139.8	
	30+625	14	0	139.6	
	30+650	15	0	139.7	
	30+675	16	0	139.9	
	30+700	17	0	140.1	
	30+725	18	0	140.2	
	30+750	19	0	139.9	

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline (+ is d/s – is u/s)	Elevation (masl)	Details
	30+775	20	0	139.7	
	30+800	21	0	140.0	
	30+825	22	0	139.5	
	30+850	23	0	139.7	
	30+875	24	0	137.0	
	30+900	25	0	139.9	
	30+925	26	0	139.6	
	30+950	27	0	137.0	
	30+975	28	0	139.8	
	31+000	29	0	139.6	
	31+025	30	0	139.6	
	31+050	31	0	139.8	
	31+075	32	0	139.8	
	31+100	33	0	139.8	
	31+125	34	0	139.8	
	31+150	35	0	139.8	
	31+175	36	0	139.7	
	31+200	37	0	139.5	
	31+225	38	0	139.3	
	31+250	39	0	139.4	
	31+275	40	0	139.5	
	31+300	41	0	139.6	
	31+425	42	0	139.4	
	31+450	43	0	139.3	
	31+475	44	0	139.4	
	31+500	45	0	139.6	
	31+525	46	0	139.5	
	31+550	47	0	139.5	
	31+650	48	0	139.6	
	31+675	49	0	139.8	

Instrumentation Type	Station Location	Label / Identification	Offset from Centreline (+ is d/s – is u/s)	Elevation (masl)	Details
	31+700	50	0	139.7	
	31+725	51	0	139.6	
	31+750	52	0	139.6	
	31+775	53	0	139.6	
	32+100	54	0	139.2	
	32+125	55	0	139.9	

3.2.3 Bay-Goose Dike - Seepage Collection System

Four small seepage areas were identified with a total of 9 seepage channels along the dike. The number of active seepage channels vary each year, as some channels stop flowing and others begin to flow. No turbidity has been observed in the seepage. The total flow coming from these seepages is 24.7 m³/day (0.29 L/s). The overall seepage is less than anticipated and is not a concern for now. The area will continue to be monitored to follow the evolution of the seepage in these areas.

Refer to the 2012 Annual Geotechnical Inspection (Golder Associates) for detailed field observations made on the dike. No mitigation measure has been implemented on the dike other than additional geotechnical instrumentation installation and field investigation in certain areas. No seepage collection has been implemented so far as the seepage is not affecting the mine operation or the integrity of the dike. The condition of the dike will continually be monitored and if the condition of the dike is judged to be deteriorating then remediation would be reassessed.

3.2.4 Bay-Goose Dike - Access

Access to the Bay-Goose Dike is from the north and south abutments as shown on Figures 2 and 6. Access to the downstream toe is by foot from the Bay-Goose pit ring road, which is a road that runs around the top circumference of the Bay-Goose pit. The south abutment of the dike is accessible from the main camp, after passing the fuel storage and refuelling station, travelling southward crossing the South Camp Dike. The access road forks, take the access road on the left (east) and continue southward on South Camp Island until reaching the south abutment of the Bay-Goose Dike. The north abutment of the Bay-Goose Dike is accessible from the south abutment of the East Dike.

The Bay-Goose Dike is not intended to be used as a haul road, but merely a structure to dewater the isolated portion and permit open pit mining of the Goose deposit and the southern portion of Portage Pit. Traffic on the dike is restricted to dike and environment personnel only; this measure was taken to protect the dike and the instrumentation.

3.3 SOUTH CAMP DIKE

The South Camp Dike covers a narrow channel within Third Portage Lake and in conjunction with the Bay-Goose Dike isolates the Bay-Goose Basin from Third Portage Lake. No spillways or water diversion works are associated with the South Camp Dike.

The South Camp Dike is located south of the plant site area and is used to connect the mainland to South Camp Island. Figure 2 shows the location of the South Camp Dike. It covers a narrow channel, approximately 60 m in width, where water depths were between 0.5 and 1 m.

The South Camp Dike was primarily constructed between April and June of 2009, prior to ice breakup. During the winter of 2009-2010 additional thermal capping material and rockfill for the haul road was added to the dike. The South Camp Dike has a broad rockfill shell with a bituminous geomembrane liner installed on the upstream side of the shell. The liner was founded on native frozen (permafrost) till material, in a trench approximately 3 to 5 m below the lakebed surface. Compacted granular material mixed with bentonite was placed above the toe of the liner. The haul road is located on the downstream side of the dike.

3.3.1 South Camp Dike – Design and Construction

The South Camp Dike design and as-built drawings are presented within Doc. 802 (Golder 2009a). A plan view and typical section of the as-built dike are shown on Figure 10.

The dike design includes the following components: a rockfill shell, a bituminous geomembrane liner and granular material mixed with bentonite.

3.3.2 South Camp Dike - Instrumentation

Two thermistor strings exist on the upstream side of the South Camp Dike to monitor the thermal behaviour of the foundation soils at the liner key-in trench. Instrumentation is shown in section on Figure 10.

Table 3.3 summarizes existing instrumentation in the South Camp Dike.

Table 3.3 South Camp Dike Existing Instrumentation Summary

Thermistor String	Location		Approx. Offset from Centerline + is d/s; - is u/s	Elevation (masl)	Details
	Northing	Easting			
SD-09-A	7,213,148	638,151	-27 m	133 (1 st bead)	Beads at Elev. 133, 132, 131, 130, 129, 128, 127, 126, 124, 122, 120, 118, 116, 114, 112 and 110 masl
SD-10	7,213,142	638,168	-45 m	132.4 (1 st bead)	Beads at Elev. 132.4, 131.4, 130.4, 129.4, 128.4, 127.4, 126.4, 125.4, 123.4, 121.4, 119.4, 117.4, 115.4, 113.4, 111.4 and 109.4 masl

3.3.3 Seepage Collection System

As of summer 2013 no seepage through the South Camp Dike has been discovered. Seepage through the dike will be visually monitored if discovered. Seepage and runoff from the South Camp Dike will be collected in ditches along the downstream toe and directed to topographic lows if required based on the visual monitoring.

3.3.4 South Camp Dike - Access

Access to the South Camp Dike is from the north and south abutments as shown on Figures 2 and 10. The South Camp Dike connects the mainland to South Camp Island.

SOUTH CAMP DIKE PLAN
SCALE 1:1000

SOUTH CAMP DIKE TYPICAL CROSS SECTION
APPROXIMATE SCALE 1:200

LEGEND

- TOPOGRAPHIC CONTOUR INTERVAL 2M
- TOPOGRAPHIC CONTOUR INTERVAL 10M
- SHORE LINE

NOTES

- 1) TOPOGRAPHIC CONTOUR INTERVAL 2M
- 2) GRID REFERENCE: NAD 83, UTM ZONE 14

REFERENCE

1) DRAINAGE BASIN PROVIDED BY AEM LTD., MEADOWBANK DIVISION IN "MEADOWBANK AUGUST 2010 DMR".

FIGURE 11

3.4 VAULT DIKE

The construction of the Vault Dike at Meadowbank was conducted from February 2013 to March 2013. Vault Dike is located across a shallow creek which connects Wally Lake and Vault Lake, at the Vault Pit area approximately 8 km north of the main Meadowbank site. Vault Dike is essential to allow the dewatering of Vault Lake and to isolate Vault Pit during mining activities from Wally Lake.

Vault Dike is designed and constructed as a zoned rockfill dam with filter zones, an impervious upstream liner consisting of a bituminous membrane, and an upstream key trench made of aggregate mixed with bentonite. The filter zones minimize seepage and internal erosion and facilitate seepage collection. Vault Dike includes a key trench at the base of the upstream side filled with a 0-25 mm fill amended with bentonite surrounding the liner. Coarse and fine filter material was placed on the upstream slope as geomembrane bedding. The bulk part of the dike consists of coarse rockfill material. The embankment crest is at El. 142.4 m and the upstream toe is at approximately El. 139.4 m. The downstream toe is at approximately El. 139.6 m and the bottom of the key trench ranges from El. 135.6m to El. 142.3m, with an average height of El. 137.0m. The upstream and downstream fill slopes of the dam are 1.5H:1V.

The location of the Vault dike is shown on Figure 2. Dewatering of Vault Lake is discharge into Wally lake and begin in June 27, 2013 and is supposed to be ended at the end of October 2013.

3.4.1 Vault Dike – Design and Construction


The Vault Dike design is presented in the report “Detailed Engineering of Vault Dike” (SNC, 2013a). A Vault Dike typical section plan view is included in Figure 11. As-built information and as-built drawings of the Vault Dike are provided in Construction Summary Report Vault Dike (AEM, 2013).

Vault Dike is designed and constructed as a zoned rockfill dam with filter zones, an impervious upstream liner consisting of a bituminous membrane, and an upstream key trench made of aggregate mixed with bentonite. The filter zones minimize seepage and internal erosion and facilitate seepage collection.

3.4.2 Vault Dike – Dewatering

Vault Dike is essential to allow the dewatering of Vault Lake and to isolate Vault Pit during mining activities from Wally Lake. The dewatering of Vault Lake has started on June 27th, 2013 and was supposed to be ended at the end of October 2013. The approximate pool volume to be dewatered is in the order of 2 Mm³. The downstream water levels and the upstream water levels need to be closely monitored during dewatering to preserve the integrity of the dike.

Figure 11 Vault Dike Typical Section



3.4.3 Vault Dike - Instrumentation

Installation of the thermistor strings began on February 26, 2013 and was completed April 14, 2013. Installation of the thermistors was completed by AEM with assistance from the Contractor /TCG and complied with the construction specifications.

TH3 was installed on the downstream side of the dike. TH3 was installed in the deepest channel downstream of the dike. TH5 was installed inclined under the liner on February 26, 2013. TH6, TH7, and TH8 were installed after construction was complete using a Rockmaster drill between April 12, 2013 and April 14, 2013. T6 was installed upstream of the dike in the deepest channel upstream of the liner. TH7 was installed east of the deepest channel in the unf thawed till zone found during construction. TH8 was installed upstream of the dike in the deepest channel outside of the key trench. The locations of the five thermistors at Vault Dike are shown on the as-built drawings in plan view in Figure 11 and their details are shown in Table 3-4. The five (5) thermistor strings were installed to monitor Vault Dike and the thermal behaviour of its foundation. At this point, only one critical section has been identified in the deepest section of the dike.

Table 3.4 Vault Dike Existing Instrumentation Summary

Thermistor String	Location		Elevation (masl)	Details
	Northing	Easting		
VD-TH3	5921.97	3324.066	139.5 (1 st bead)	Beads at Elev. 139.5, 138.5, 137.5, 136.5, 135.5, 134.5, 133.5, 132.5, 131.5, 130.5, 128.5, 126.5, 124.5, 122.5, 120.5, and 118.5 masl
VD-TH5	5945.52	3322.511	141.4 (1 st bead)	Beads at Elev. 141.4, 141.4, 141.4, 141.4, 141.1, 141.0, 140.5, 140.0, 139.5, 139.0, 138.4, 137.9, 137.4, 136.8, 136.4, and 136.1 masl
VD-TH6	5943.00	3322.000	140.5 (1 st bead)	Beads at Elev. 140.5, 139.5, 138.5, 137.5, 136.5, 135.5, 134.5, 133.5, 132.5, 131.5, 130.5, 129.5, 127.5, 125.5, 124, and 121.5 masl
VD-TH7	5946.00	3346.00	140.5 (1 st bead)	Beads at Elev. 140.5, 139.5, 138.5, 137.5, 136.5, 135.5, 134.5, 133.5, 132.5, 131.5, 129.5, 127.5, 125.5, 123.5, 122.0 and 119.5 masl
VD-TH8	5957.00	3322.00	140.5 (1 st bead)	Beads at Elev. 140.5, 139.5, 138.5, 137.5, 136.5, 135.5, 134.5, 133.5, 132.5, 131.5, 129.5, 127.5, 125.5, 123.5, 122.0 and 119.5 masl


3.4.4 Vault Dike - Seepage Collection System

As of summer 2013 no seepage through the Vault Dike has been discovered. Seepage through the dike will be visually monitored if discovered. Seepage and runoff from the Vault Dike will be collected in ditches along the downstream toe and directed to topographic lows if required based on the visual monitoring.

3.4.5 Vault Dike - Access

Two access roads were constructed to the dike footprint – one from Vault Dike Road West and from Vault Dike Road East. Figure 12 presents a map of the general Vault Pit area with the access roads. Vault Dike Road West begins where Vault Road ends at the Vault Waste Dump, runs northeast to pass Dewatering Road A and ends at the northwest end of the dike (Station 0+000). Vault Dike Road East begins at Vault Road between the Tower Pad and the Office Pad, runs northeast to pass Dewatering Road B and Dewatering Road C and ends at the southeast end of the dike (Station 0+350).

Figure 12 General Vault Pit area with the access roads



SECTION 4 • DEWATERING

The Dewatering Dikes isolate the open pit mining activities from the Second Portage Lake, Third Portage Lake, and Wally Lake. The northwest arm of Second Portage Lake was dewatered upon completion of the East Dike and West Channel Dike in 2009.

The Bay-Goose Dike together with the South Camp Dike isolates the Bay-Goose Basin from Third Portage Lake. Dewatering of the Bay-Goose Basin commenced on July 25, 2011 and was completed on November 14 2011. As the operational stage of Goose Pit has started, both dikes are no longer under dewatering conditions. The approximate pool volume dewatered is in the order of 3 Mm³. This is referring to the amount of water removed to expose the majority of the downstream toe of the Bay-Goose Dike.

Vault Dike isolates Vault Pit from Wally Lake. Dewatering of Vault Lake started on June 27th, 2013 and is scheduled to be complete at the end of October 2013. The approximate pool volume to be dewatered is in the order of 2 Mm³. The Vault Dike is presently the only dike that was considered under dewatering condition.

The following outlines the key criteria and constraints that will need to be observed and followed in accordance with the design objectives, concepts, and assumptions for the Dewatering Dikes.

4.1 FREEBOARD

The design criteria for minimum freeboard for the Dewatering Dikes are presented in Table 4.1. The freeboard may change due to fluctuations in Second Portage and Third Portage Lakes or due to settlement in the dikes. Maintenance may be required to restore loss of freeboard due to settlement.

Table 4.1 Design Minimum Freeboard

Structure	Minimum Freeboard	
	Rockfill Structure (Dike Crest) (m)	Low Premeability Element (Cutoff Wall or Liner) (m)
East Dike	3.0	1.0
Bay-Goose Dike	4.0	1.0
South Camp Dike	3.0	1.0
Vault Dike	3.0	1.5

4.2 WATER MANAGEMENT AND QUALITY

Dewatering water from the Vault Lake Basin was pumped and directly discharged to Wally Lake thru a diffuser, or processed through the Water Treatment Plant (WTP) to reduce Total Suspended Solids (TSS). The Nunavut Water Board Water License (No. 2AM-MEA0815) states that the TSS maximum monthly mean value should not exceed 15.0 mg/L and that the short term maximum level is 22.5

mg/L and turbidity maximum monthly mean value should not exceed 15 NTU and the short term maximum level is 30 NTU. The Vault Lake discharge is also considered as an effluent under the Metal Mining Effluent Regulations (MMER) and must meet the criteria of this regulation for arsenic, copper, cyanide, lead, nickel, zinc, TSS and toxicity of trout and daphnia. Under the MMER regulation, the TSS maximum monthly mean value should not exceed 15.0 mg/L and maximum concentration in a grab sample is 30.0 mg/L. In the first stage of the Vault Lake dewatering the WTP was not required because the regulation criteria limit was reached. However, as dewatering proceeds it is anticipated the WTP will need to be used during the latter stages when TSS from bottom sediments could be present.

4.3 SURVEILLANCE AND MONITORING REQUIREMENTS

Surveillance and monitoring requirements are defined in Sections 7 and 8 of this manual.

Pore water pressures in the foundation shall be monitored during dewatering as a predictor of possible slope instability. Both pore water pressures and temperature measurements shall be monitored during dewatering as one method of detecting potential zones of seepage. The quantity of water pumped out during dewatering was monitored with flow meters in addition to monitoring the water level downstream of the Vault Dike, within the Vault Lake Basin.

4.4 SAFETY AND SECURITY

Access to the mine site is controlled by AEM security and public access to the area is restricted.

SECTION 5 • OPERATIONS

The following outlines the key criteria and constraints that will need to be observed and followed to operate the dewatering dikes in accordance with the design objectives, concepts and assumptions.

5.1 FREEBOARD

The design criteria for minimum freeboard for the Dewatering Dikes are presented in Table 5-1. The freeboard may change due to fluctuations in lake levels or due to settlement of the dikes. Maintenance may be required to restore loss of freeboard due to settlement.

Table 5.1 Freeboard

Structure	Freeboard	
	To the Dike Crest (m)	To the Dike Cut-off Wall or Liner (m)
East Dike	3.0	1.0
Bay-Goose Dike	4.0	1.0
South Camp Dike	3.0	1.0
Vault Dike	3.0	1.5

5.2 WATER MANAGEMENT

Water from the seepage collection systems of the Dewatering Dikes is to be pumped to the pit sumps and/or directly to the Tailings Storage Facility or Attenuation Pond. Seepage rates may increase with time as the pits are developed downstream of the dikes. As described in Sections 7 and 8 of the document, seepage rates, volumes and the condition of the seepage water (i.e. turbidity, temperature, etc.) are to be monitored.

Table 5.2 summarizes design criteria for the seepage and runoff flow into the seepage collection sumps. The quantity of seepage through the dike is an estimate based on design analyses and should be periodically reviewed during dewatering and operations.

Table 5.2 Sump Design Criteria

Criteria Type of Storage	Description Temporary
Required Storage Capacity	Seepage from the foundation and embankment plus Average daily 10 year freshet volume
Foundation and Embankment Seepage	Design rate: 300 m ³ /day prior to Portage Pit development (East Dike). However, seepage rates in 2009 and 2010 have been between 860 to 1300 m ³ /day Design rate: 700 m ³ /day prior to Goose Island Pit development (Bay-Goose Dike) However, seepage rates in 2013 have been 24.7 m ³ /day
Average daily 10 year freshet	Average daily 10 yr snowmelt over 14 day melt period
Design Pump Capacity	Sufficient to pump: Foundation and Embankment Seepage plus 10-year annual snow melt in 14 days

Regular monitoring of the seepage volume is required. Sumps size and pump capacity is to be regularly reviewed and upgrades made if deemed necessary by AEM.

5.3 WATER QUALITY

Water quality of the seepage and runoff collected in the sumps and ditches at the toe of the Dewatering Dikes is to be monitored during operations. Daily inspections during dewatering and weekly inspections during operation are required as an indicator of dike performance to note whether seepage water is clear, cloudy or if fine material is present.

SECTION 6 • MAINTENANCE PROCEDURES

Maintenance is important for the safe operation of the Dewatering Dikes. The Engineering Superintendent is responsible for proper and timely maintenance of the Dewatering Dikes embankments, instrumentation, seepage collection system and access.

6.1 PLANNED AND UN-PLANNED MAINTENANCE

Maintenance is divided into planned and un-planned maintenance. Planned maintenance will be scheduled according to manufacturer's requirements for instrumentation and equipment such as pumps. Planned maintenance may be routine, preventative and/or routine inspection observations including low risk / consequence observations.

Un-planned maintenance shall generally derive from routine inspection observations including medium-high risk / consequence observations and / or extreme events including extreme meteorological events, seismic events, etc. where the maintenance requirement is critical and is required immediately.

All planned and un-planned maintenance will be documented in a database organized and maintained by AEM.

6.2 EMBANKMENT EROSION

Erosion of the rockfill embankments is not expected during dewatering or operations. In the event that the upstream face is eroded by wave action or ice scouring then any gullies or depressions that develop are to be filled in with rockfill material and re-sloped.

6.3 SEEPAGE COLLECTION SYSTEM

Seepage is expected to exit the downstream toe of the Dewatering Dikes, in particular at low points along the alignment of the structure. Seepage should be monitored and ditches and sumps maintained to avoid erosion and deterioration of the seepage collection system. Sediments, snow and ice may accumulate in the ditches and sumps during operation. The ditches and sumps will require ongoing cleaning and maintenance.

Pumps located at the seepage collection system sumps will require maintenance based on the manufacturer's specifications. Pump installations are to be winterized to provide year round capacity for pumping, if necessary.

Heat tracing of the pipelines will require maintenance. It is expected that the feeder pipelines to the main pipelines are sloped sufficiently to drain the pipes and not permit ice or sediment accumulation, but this should be confirmed in the field.

6.4 INSTRUMENTATION

All cables, thermistors, inclinometers, piezometers, and survey/displacement monuments must be adequately protected with barriers, signs, and flagging to prevent accidental damage. The instrumentation installed in the Dewatering Dikes is to remain operational until closure of the facility.

Instrumentation will require regular maintenance based on manufacturer's specification. The slope inclinometer casing will require either frequent bailing or filling with a solution of non-toxic antifreeze to prevent freezing and icing.

Calibration sheets and initial instrumentation readings will be included upon replacement of malfunctioning instrumentation; the OMS Manual will be updated accordingly.

6.5 ACCESS

Access roads to the Dewatering Dikes along the crest of the dikes need to be maintained. Access will also be maintained along the seepage collection system and to the sumps at the toe of the East Dike and Bay-Goose Dike. Maintenance activities for access will be conducted.

SECTION 7 • SURVEILLANCE

A program of regular surveillance is required to ensure that the Dewatering Dikes, instrumentation and seepage collection systems are performing adequately and that problems are detected so that the necessary corrective actions can be implemented in a timely manner.

7.1 SURVEILLANCE REQUIREMENTS

Surveillance is required for early detection of possible failure mechanisms. In 1995, the International Commission on Large Dams (ICOLD) released a study summarizing failure mechanisms for world-wide water retaining dam incidents during the 1800s and 1900s. The potential failure mechanisms applicable to the Dewatering Dikes, primarily East Dike and Bay-Goose Dike, based on the ICOLD study are summarized in Table 7-1.

Table 7.1 Summary of Consequences and Proposed Monitoring/Action for Rare Events Based on Water Retaining Embankment Failure Modes Identified in ICOLD (1998)

Failure Mode	Scenario	Consequence	Monitoring/Action
Overtopping	(1) Lake level rise because of restricted outflow e.g. Second Portage outlet (excessive inflow is a far less likely scenario).	Water spilling over the crest. The crest is wide and comprises coarse rockfill. Adequate freeboard is provided by the rockfill crest elevation being 3 m above the lake level and the low permeability element 2 m above. Any rise in lake level is anticipated to be less than the freeboard. Significant damage to the dike is unlikely, based on performance of other rockfill structures subjected to overtopping or flow through events. Mining operations might need to be suspended, but there will be considerable warning time given the design freeboard and the storage volume within the lakes.	Lake levels should be part of weekly safety information provided to mine management. Outflow channels should be inspected weekly during the thaw and ice break-up. If overtopping is likely, a temporary spillway could be constructed and armoured to control and localize flow at shallow dike sections (e.g. abutment).
	(2) Dam crest settles more than 2 m over a distance of approximately 50 m. Not a credible failure mechanism. Observed settlement of the East Dike and Bay-Goose Dike crest during construction was on the order of 0.3 m to 0.5 m. Additional settlement is expected to be smaller in magnitude.	Same as (1).	The situation envisaged in this scenario should develop slowly with crest settlement evident. Monitoring of crest settlement is appropriate, and is included in the surveillance program. Rockfill and till are available from the mining operation can be placed to raise the dike crest, if settlement occurs.

Failure Mode	Scenario	Consequence	Monitoring/Action
Internal Erosion	(3) Dike Section: the low permeability element of the dikes Cutoff wall, jet grout columns, shallow foundation is defective, allowing high water flow through the structure. This defect could potentially erode zones of the dike and lead to loss of material from the dam (piping) increase the seepage, sinkholes in the crest.	<p>The East Dike cutoff wall could progressively loose material, thereby increasing the hydraulic conductivity and resulting in an increased rate/volume of seepage through the dike and development of sinkholes in the dam crest. This is not likely to be a catastrophic failure mode as the rockfill shoulders of the dike will be stable and the filters are founded on or near bedrock. At its worst, this would lead to temporary flooding within the open pit of the mine and a cessation of mining.</p> <p>The Bay-Goose Dike cutoff wall system although similar to East Dike, has potential to lose more material from the dike structure, through piping as in the “deep sections” where jet grouting was conducted, downstream filter material does not extend to bedrock and a higher hydraulic head exists. Internal erosion could lead to increased seepage, sinkhole development, settlement of the crest, and although not probable, loss of containment.</p>	Monitor seepage from downstream face for rate and volume, and for presence of sediment in seepage. Would become evident as localized intensive seepage at the dike toe or beyond. May also see settlement in the cutoff wall or dike crest. Will be most likely in deep water sections with higher gradients. Monitor piezometric and thermistor data for signs of increased flow through the cutoff wall and change in piezometric pressures. Selection of a remediation plan would be based on conditions encountered, but could include the installation of a downstream filter blanket and grouting.
	(4) Foundation: Till is non-uniform with more transmissive zones and zones of erodible material (i.e. silt layers) that may not be self-filtering. It is possible that material loss of the foundation tills and/or through the fractured bedrock with silt infillings could occur and result in high rates of seepage and a loss. Seepage could flow along the transmissive zone beneath the downstream rockfill section and erode the foundation tills at the downstream toe or into the downstream rockfill because of the lack of filtering.	Limited seepage at the toe or into the rockfill would accelerate into a larger flow and could lead to the undermining of the dike if no action was taken. This is a credible catastrophic failure mode if increased seepage is not detected in time.	Monitor seepage flow rates and condition and piezometric and thermistor responses for signs of increased seepage. Monitor dike crest for signs of sinkholes, settlement or slope instability. Remedial actions could comprise of grouting, a reverse filter and rockfill buttress depending on location of the flow and configuration of the foundation. In the worst case, the dewatered areas may be deliberately flooded in a controlled manner, the cutoff repaired, and the areas dewatered.
Seepage within Embankment	(5) Seepage on its own is not a credible failure scenario. The downstream rockfill shell has extremely high flow through capacity. The rockfill zone is both	No credible consequences. May require upgrade of the seepage collection system. May need to suspend mining activities while reducing seepage.	Seepage monitoring program.

Failure Mode	Scenario	Consequence	Monitoring/Action
	large and pervious, so that seepage will not daylight on the downstream face and lead to instability. Any seepage related failures must include internal erosion, see above.		
Seepage within Foundation	(6) Defective construction of cutoff system leading to transfer of unexpectedly high fraction of the reservoir head into the downstream part of the dike foundation, or leading to a piping event as described above (internal erosion).	This failure mechanism has caused embankment failures elsewhere because of pore pressure induced instability. However, at East Dike it is unlikely that it could cause failure of this dike. However, for Bay-Goose Dike this is more of a possibility. The most likely consequence is downstream toe slumping requiring a localized stabilizing berm before the crest roadway could be reinstated.	This mechanism is more likely to arise during dewatering. Monitoring of piezometric heads and thermistor string data.
Internal Conduit Rupture	(7) There are no internal conduits or other structures extending through the dikes.	Not applicable.	Not applicable.
Slope Instability	(8) Normal Operation: The rockfill shoulders of the dikes have high shear strength, making it a conservative design. For slope failure to be a concern, it requires failure in the foundation which would then extend into the overlying dike. Sliding failure is considered unlikely given the low horizontal forces generated by water and ice forces relative to the normal frictional force due to the weight of the dike and the friction angles of foundation materials.	A foundation failure would cause a rotational slip or sliding failure until equilibrium was reached. This mechanism would limit access along the dike until repaired. Failure through the rockfill shoulders will not necessarily compromise the water retaining element of the dikes. Failures which reach the core may cause failure.	This mechanism should develop during construction or dewatering, due to increased loads and associated pore water pressure. Initial stages of failure should be observable as tension cracks in the dike crest. Walk-over inspection of the dike by a trained inspector is an appropriate monitoring strategy. Survey of crest, face, and toe is also appropriate. Stabilizing berms can be placed inside the dike or through water along the upstream shoulder.
	(9) Pit Wall instability that extends towards the dike and causes instability of the dike	If the instability impacted the low permeability element of the dike, then failure of the entire structure and loss of mining operations could occur. This is more likely to be a cause of failure for the Bay-Goose Dike as the offset between the low permeability element and pit crest is much	Slope inclinometer monitoring of the cutoff wall. Pit wall stability monitoring. Depressurization of pit walls. Draining of lakebed soils between pit crest and dike and/or removal of these materials.

Failure Mode	Scenario	Consequence	Monitoring/Action
		less than for East Dike.	Adjustment of mine plan, if necessary.
	(10) Earthquake Induced: Occurrence of an extreme earthquake, much in excess of the current understanding of seismicity of the area.	The extreme earthquake loading for this site is a low magnitude. Settlement of the dike could occur in the event of a large earthquake. Dynamic compaction of the core in the East Dike and Bay-Goose Dike during construction may have subjected the rockfill shells to accelerations equivalent to the expected earthquake loading. This would not be a failure situation. The crest is also erosion resistant for any earthquake induced wave action in the impounded water.	Dike inspection following earthquakes felt on site.
Failure of Cutoff Wall Due to Movement of the Dike	(11) Differential horizontal movement of dike due to water or ice loading, or pit wall failure, or blast vibrations. Creates a breach in the cutoff wall system. Ice and water forces are not credible due to the ratio of frictional forces generated by the self weight of the dike versus ice loads and water pressure. Pit wall failure (see above).	Large inflows through the breach. Dewatered areas would flood requiring suspension of mining activities. Potential for loss of life for workers downstream of the dikes. Excessive vibration from overblasting could potentially damage the CSB and/or jet grout columns resulting in cracks or fissure, however the cement content within these portions of the wall should reduce the erodability of the wall and therefore protect the integrity of the dike, even though seepage rates would increase. It is anticipated that the SB material would deform adequately such that cracks would not be produced.	Prism monitoring for pit wall stability. Blast vibration monitoring on the dikes. Monitoring inclinometers within the cutoff wall.
Unexpected Settlements	(12) Unexpected foundation soils consolidate during dike construction. A significant quantity of clay that was not recognized during foundation excavation would be required to generate settlement required for a water release event. Settlement of the core will be limited.	2 m of settlement would be required to allow water flow through the rockfill and over the settled core. This flow would not cause failure of the rockfill shells. It would also be readily repaired by placing more end-dumped till into the settled zone.	Settlement monitoring of the dikes and visual inspection. Excessive settlements may be remediated by excavating rockfill above the core and placing more till.

Table 7-1 to be updated as necessary during operation

7.2 SURVEILLANCE PROTOCOLS

The surveillance program consists of several types of inspections:

During Dewatering:

- Daily Dewatering Inspection – carried out on an on-going basis by designated qualified mine personnel to assess the performance of the dikes during dewatering. Reporting can be daily if routine, or immediately if conditions warrant;
- Weekly Dewatering Inspection – carried out by designated qualified mine personnel, to assess the performance of the dikes during dewatering with reporting occurring weekly or immediately if conditions warrant; and
- Design Engineer Inspection – upon exposure of the downstream toe to view seepage and review the performance of the dike.

During Operations:

- Weekly Routine Inspection – carried out weekly by designated qualified mine personnel to assess operating of the seepage collection systems including the sumps and performance of the structures;
- Monthly Routine Inspection – carried out monthly by a designated qualified mine personnel to assess operating status of the seepage collection systems including the sumps, and performance of the structures;
- Engineering Inspection – carried out annually by a qualified engineer, during open water period, to verify that the facilities are functioning as intended; and
- Dam Safety Review – carried out by an independent engineer every five years to review all aspects of the design, construction, operation, maintenance, processes and other systems affecting the dam's safety, including the dam safety management system. The review defines and encompasses all components of the "dam system" under evaluation including the dam, foundations, abutments and seepage collection works.

7.3 RESPONSIBILITIES AND FREQUENCY

It is anticipated that the Engineering Superintendent and support personnel and/or the Environment Superintendent and support personnel and/or Mine Superintendent and support personnel will be responsible for the inspections of the Dewatering Dikes, seepage collection systems, instrumentation and access routes during dewatering and operation. The inspections by the Design Engineer and for the Dam Safety Review will be conducted by qualified independent engineers. The inspection, monitoring and review requirements are summarized in Table 7-2 and described in the following sections.

Table 7.2 Inspection, Monitoring and Review Requirements

Party Responsible	Required Inspection, Review or Monitoring	Required Frequency
Design Engineer	Dewatering Inspection	During dewatering once downstream toe is exposed
Engineering Superintendent and Principal Geotechnical Engineer; and/or Environment Superintendent and support personnel; and/or	Daily Dewatering Inspection	Daily and immediately following earthquakes, high intensity rainfall events and other extreme events
	Daily and Weekly Routine Inspection of Dewatering Dikes, seepage collection system, and access.	Weekly and immediately following blasting, large blasts occurring in close proximity to the structures, earthquakes, high intensity rainfall events and other extreme events
	Monitoring of instrumentation (thermistor strings, vibrating wire piezometers, inclinometers, survey prisms and monuments, pump rates, lake water levels)	Varies – see Section 8.0
Engineering Superintendent and Principal Geotechnical Engineer and/or designated qualified mine personnel	Weekly Dewatering Inspection	Weekly and immediately following earthquakes, high intensity rainfall events and other extreme events
	Monthly Routine Inspection of Dewatering Dikes, seepage collection system, and access.	Monthly and immediately following large blasts occurring in close proximity to the dikes, earthquakes, high intensity rainfall events and other extreme events
Qualified Engineer	Engineering inspection of the Dewatering Dikes, drainage works, access and instrumentation.	Annually
Independent Engineer	Dam Safety Review	Once every five years

7.3.1 Dewatering Inspections (Daily and Weekly)

Inspections during dewatering form part of the duties and responsibilities of the Engineering Superintendent, Principal Geotechnical Engineer and support personnel and the Environment Superintendent and support personnel and must be carried out by designated and qualified personnel. It is assumed that Daily Inspections maybe conducted by less knowledgeable staff and weekly inspections by more knowledgeable staff.

Ideally the inspections should be carried out by the same individual or by a small group in order to maintain continuity in the observations. The main operational and structural parameters should be reviewed and verified by the Engineering Superintendent, Principal Geotechnical Engineer and Environment Superintendent. Data collected will be summarized on the respective Dewatering Dike Field Inspection Sheets and stored for easy access and long term record keeping.

The following information should be noted and recorded in the inspection to detect signs of wear, damage or potential loss of structural integrity:

Dike Structure:

- compliance with minimum freeboard requirements:
- crest elevation;
- upstream water elevation; and
- downstream water elevation.

Crest:

- surface cracking; and
- local subsidence.

Upstream face conditions above water line:

- cracking;
- distortion or displacement;
- wave erosion; and
- slope angle.

Downstream face conditions:

- cracking;
- distortion or displacement;
- slumping;
- erosion;
- slope angle;
- seepage quantity and quality (turbidity); and
- wet areas.

Area downstream of dike toe:

- Seepage quantity and quality (turbidity);
- cracking;

- erosion;
- bulging; and
- indications of instability.

Abutments:

- indications of instability;
- erosion at dike – ground surface contact; and
- seepage appearing from abutments.

Barges, Dewatering ramps, and pumps:

- pumping rates and dewatering rate;
- water quality being pumped in regards to turbidity;
- conditions of the holding cables and location of the barge in the dewatering pool;
- presence of ice on the barge due to leaks; and
- general condition of the pumps and the presence of leaks (pumps or piping).

The inspection forms are included in Appendix A.

Photographs should be used to augment the inspection forms. As much as possible, these should be taken from the same vantage points during each inspection so that changes in conditions can be readily identified. Photographs shall be captioned or annotated with a date stamp.

The observations and/or events indicating a trend that are considered “triggers” requiring reference to action items and reporting procedures are outlined in the Emergency Preparedness Plan in Section 11. A summary of triggers for the dewatering inspection are:

- Increasing measurements in total suspended solids at dewatering pump intake or outlet;
- Decrease in the rate of dewatering, when not attributed to a decrease in the pumped volume;
- Instrumentation responses indicating seepage; and
- Increasing measurements in dike displacement such as crest heave/settlement or lateral movements.

7.3.2 Daily and Weekly Routine Inspections

Daily and Weekly Routine Inspections are part of the duties and responsibilities of the Engineering Superintendent, Principal Geotechnical Engineer and their support personnel and the Environment Superintendent and support personnel and must only be carried out by designated and qualified personnel. Ideally the inspections should be carried out by the same individual or small group in order to maintain continuity in the observations. The main operational and structural parameters should be reviewed and verified by the Engineering Superintendent, Principal Geotechnical Engineer and the Environment Superintendent.

Daily Routine Inspections are carried out by the geotechnical technicians as they perform their data readings and other daily duties on the dewatering dikes. Technicians are trained to watch for changes in the condition of the dewatering dikes, and report anything out of the ordinary to the geotechnical engineers so it can be investigated further. Technicians look for any signs of damage to the dikes and monitor seepage conditions daily. Data collected during the Daily Routine Inspections will be summarized on the respective Dewatering Dike Field Inspection Sheets (see Appendix A), and stored in a suitable location for easy accessibility and long-term record keeping.

Weekly Routine Inspections are carried out by the geotechnical engineers and are more detailed than the Daily Routine Inspections. A Weekly Routine Inspection will also occur if a Daily Routine Inspection discovers anything that needs to be investigated further.

The following information should be noted and recorded in the weekly inspection forms to detect signs of wear, damage, or potential loss of structural integrity:

Dike Structure:

- Compliance with minimum freeboard requirements:
- crest elevation; and
- upstream water elevation.

Crest:

- Any indication of cracking or settlement/subsidence;
- Upstream face conditions:
- surface cracking;
- distortion or displacement; and
- wave erosion.

Downstream face conditions:

- cracking;

- distortion or displacement;
- slumping;
- erosion; and
- seepage quantity and quality (turbidity) and wet areas.

Abutments:

- indications of instability;
- erosion at dike – ground surface contact; and
- seepage appearing from abutments (quantity and quality).

Downstream toe of dike:

- seepage quantity and quality (turbidity);
- changes on surface;
- cracking;
- erosion;
- bulging;
- soft wet zones;
- accumulation of fines/silts; and
- ice.

Ditches / Seepage Collection System:

- changes in surface;
- indication of cracking;
- erosion;
- bulging;
- soft wet zones;
- accumulation of fines/silts; and

- ice blockage.

Sumps:

- changes in surface;
- indication of cracking;
- erosion;
- bulging;
- soft wet zones;
- accumulation of fines/silts; and
- ice blockage.

Pumping structures and pipelines:

- leaks; and
- function at capacity.

Seepage:

- rates and location;
- water quality, specifically the presence of fines (turbidity); and
- access.

Other:

- Review of general condition of the access to the Dewatering Dikes, along the Dewatering Dikes crest surface and access to seepage collection system, including sumps and pumping system at the downstream toe;
- Indications of instability (e.g. potholes, slumping or cracks, in the road or path or the cut slopes above them); and
- Accumulations of debris or other materials on the road or paths.

Sample inspection forms are included in Appendix A.

Photographs shall be used to augment the inspection form. As much as possible, these are to be taken from the same vantage points during each inspection so that changes in conditions can be readily identified. Photos should be annotated or captioned and should include a date stamp.

The observations and/or events indicating a trend that are considered “triggers” requiring reference to action items and reporting procedures are outlined in the Emergency Preparedness Plan (see Section 11).

7.3.3 Monthly Routine Inspections

Monthly Routine Inspections form part of the duties and responsibilities of the Engineering Superintendent and Principal Geotechnical Engineer and must only be carried out by designated and qualified personnel. It is assumed that Monthly Routine Inspections will be carried out by more experienced personnel than the Daily/Weekly Routine Inspections. Ideally the monthly inspections should be carried out by the same individual in order to maintain continuity in the observations. The main operational and structural parameters should be reviewed and verified by the Engineering Superintendent, Principal Geotechnical Engineer and the Environment Superintendent. Data collected will be summarized on the respective Dewatering Dike Field Inspection Sheet, and stored for easy accessibility and long term record keeping.

The monthly inspection will require the inspector review the same items as in the weekly inspections described above, with the following additional items:

- Review and comment on results of performance monitoring instrumentation; and
- Review operational performance and confirm that the original design assumptions are still valid.

7.3.4 Engineering Inspection

An annual inspection of each of the Dewatering Dikes should be carried out by a qualified engineer. The objective of the inspection is to carry out a detailed review of the conditions of the facilities and facility operations. This will provide information to be used to revise the operation, maintenance and surveillance programs as necessary and to assist in planning for future operation of the facility.

Each inspection should address the following:

- Review of inspections performed during dewatering;
- Review and comment on results of weekly and monthly inspection reports;
- Review and comment on results of performance monitoring instrumentation;
- Review operational performance criteria and confirm that the original design assumptions are still valid; and
- Review and provide recommendations regarding operation, maintenance and monitoring for the following year.

7.3.5 Dam Safety Review

An independent engineer should carry out a dam safety review of the Dewatering Dikes and associated facilities at five year intervals or after:

- Major modifications to the design or design criteria;
- Discovery of unusual conditions that can endanger the dikes;
- After extreme hydrological or seismic events; and
- Decommissioning.

The high consequence failure rating based on the Dam Safety Guidelines (CDA, 2007) suggests a review every seven years. A five year interval is recommended given that the operational life of the East Dike and Bay-Goose Dike is approximately 9 and 8 years, respectively. The review shall be carried out according to the recommendations laid out in the Dam Safety Guidelines (CDA, 2007).

This review will include, but is not be limited to:

- Review of the dikes classification;
- Site inspection;
- Review of design and construction records;
- Review of monitoring practices and the instrumentation records
- Update of the stability assessment based on the results of the instrumentation readings obtained to that time, construction records and site observations;
- Assessment of the operation of the facilities;
- Review of OMS Manual; and
- Review of emergency plan and response plans.

SECTION 8 • MONITORING AND INSTRUMENTATION

Monitoring of the Dewatering Dikes is carried out for the purpose of:

- Environmental monitoring during dewatering and operation;
- Assessing physical stability of the structure during dewatering and operation;
- Assessing overall performance of the dikes; and
- Aiding in design of future dikes.

Monitoring complements the Surveillance of the Dewatering Dikes and should be taken into account in combination with the routine surveillance described in Section 7.0.

Monitoring is divided into the following aspects:

- Drawdown rate and water quality during dewatering;
- Geotechnical instrumentation including piezometers, thermistors, inclinometers, survey prisms, etc.; and
- Seepage rates and water quality during operation.

8.1 DEWATERING – DRAWDOWN RATE AND WATER QUALITY

The water quality criteria for discharge are listed in Nunavut Water Board Water License 2AM-MEA0815 Part D, item 16 and into the Metal Mining Effluent Regulation. The water quality data collection protocols and schedule are included in the Water Management Plan.

8.2 GEOTECHNICAL MONITORING

The existing geotechnical instrumentation is shown in the as-built drawings for each dewatering dike.

Section 3.0 of this document describes the existing geotechnical instrumentation of the Dewatering Dikes.

8.2.1 Data Collection Protocols and Schedule

Upstream and downstream elevations of Second Portage Lake and Third Portage Lake water and ice levels, if applicable, should always be recorded when piezometer readings are recorded and when the survey prisms and monuments are monitored.

The following sections describe the routine geotechnical monitoring program of permanent instrumentation and are summarized in Table 8.1 below.

Table 8.1 Geotechnical Instrumentation Monitoring Program

Instrumentation	Monitored By	Reported To	Frequency during Dewatering	Frequency during Operations
Piezometers	Manually by Engineering Personnel during dewatering; and Automatically during operations (overseen by Engineering Personnel)	Engineering Superintendent	Daily / every 3 hours	Daily / every 3 hours
Slope Inclinerometer Casings	Manually by Engineering Personnel during dewatering; and Manually during operations (overseen by Engineering Personnel)	Engineering Superintendent	Monthly	Monthly in winter, bi-monthly for the rest of the year
Thermistors	Manually by Engineering Personnel during dewatering; and Automatically during operations (overseen by Engineering Personnel)	Engineering Superintendent	Daily / every 3 hours	Daily / every 3 hours
Surface Monuments and Surface Prisms	Manually by Engineering Personnel during dewatering; and Manually during operations (overseen by Engineering Personnel)	Engineering Superintendent	Not Operational	Bi-Weekly
Seismographs	Manually by Engineering Personnel during dewatering; and Manually during operations (overseen by Engineering Personnel)	Engineering Superintendent	During blasting at the Portage Pit or Goose Island Pit adjacent to the dikes	During blasting at the Portage Pit or Goose Island Pit adjacent to the dikes

The frequency of monitoring will depend, to some degree, on preceding data and on the state of operation. Thus the data is reviewed regularly and the Engineering Superintendent may change the program and amend the OMS Manual as necessary.

Measurements and a review of all instrumentation shall be carried out immediately after significant seismic or climatic events.

An automatic data acquisition system is used to collect data from the piezometers and thermistors. The automatic data acquisition system includes data loggers and instrumentation cabins along the dikes crest. The data collected is downloaded every three hours. Each cabin is supplied with electricity through solar panels and a backup battery.

The equipment for monitoring is maintained by designated mine personnel. Data analysis, review and correction are carried out by the Engineering personnel and reported to the Engineering Superintendent.

8.2.1.1 Thermistors

Data presentation for the thermistors should include:

- temperature vs. time plots (presenting all thermistor beads on each string); and
- temperature vs. depth plots over time.

The plots should indicate the thermistor string reference number and dates of the measurements. Additionally the plots should also indicate air temperature and, if relevant, lithology and both elevations and depths.

8.2.1.2 Survey Monuments and Prisms

The lake elevation is recorded at the same time the survey monuments and prisms are measured. All survey work must be carried out to a minimum precision of 3 mm.

Data presentation for the survey monuments should include:

- total net movement plots (to present total displacement);
- vertical displacement plots; and
- lateral displacement plots parallel and perpendicular to the dike axis.

The plots should indicate the survey monument number, what is considered positive and negative movement (for example, downstream/upstream, heave/settlement) and the dates of the measurements.

8.2.1.3 Slope Inclinator Casings

The vertical and horizontal position of the top of the inclinometer casing will be recorded by surveying when the slope inclinometers readings are taken. All survey work must be carried out to a minimum precision of 3 mm.

Data presentation for the slope inclinometers should include:

- cumulative displacement plots (to view total displacement);
- incremental displacement plots (to present increasing or accelerating movements between readings);
- cumulative displacement at crest versus time; and

- time plots at zones of identified displacement.

The plots should indicate the slope inclinometer number, what is considered positive and negative movement (for example, downstream/upstream, heave/settlement) and the dates of the measurements. Both elevations and depths should be presented together with the lithology.

8.2.1.4 Vibrating Wire Piezometers

Data presentation for the vibrating wire piezometers should include:

- plots of total head as elevation versus time; and
- plots of temperature versus time for piezometers.

The plots should indicate the vibrating wire piezometers number and dates of the measurements. Additionally the plots should also indicate upstream lake elevation or ice level and, if relevant, lithology and both elevations (referred to the mine datum) and depths.

8.2.1.5 Seismographs

Data presentation for the seismographs should include:

- Weekly summary graph showing peak accelerations registered versus the time when they occurred.

The plots should also indicate the seismograph readout identification, date and location.

8.2.2 Anomalous Instrumentation Data

Anomalous instrumentation data includes the following:

Thermistors:

- Increase or decrease in measurements (over two or more readings) that cannot be explained by seasonal temperature variations;

Survey monuments and prisms:

- Accelerating displacement rate of the survey monuments
(x, y, z directions) (over two or more readings);

Inclinometers:

- Cumulative increases in displacement (greater than 3 cm);

Piezometers:

- Increases or decreases in pore water pressure measurements that cannot be explained by seasonal lake level variations; and

Seismographs:

- Vibrations during a blast are not observed.

If anomalous readings are observed, the following actions should be taken:

- Inspect the dike where possible and appropriate;
- Check data, reductions and calculations for accuracy and correctness;
- Re-read to check the reading;
- Check readout equipment to verify that it is functioning correctly;
- Verify calibration;
- If instrument has stopped functioning, notify the Engineering Superintendent immediately. If considered critical, a replacement instrument should be installed;
- If the anomalous reading is confirmed, a detailed review of the effects of the reading should be carried out and design or remedial actions should be implemented if determined necessary by the Engineering Superintendent; and
- Increase monitoring frequency to assess progression of anomaly.

8.3 SEEPAGE MONITORING - OPERATIONS

Seepage and runoff will be collected and conveyed in drainage ditches at the downstream toe of the East Dike and Bay-Goose Dike to sumps located at topographic lows. The rate of seepage and quality of seepage should be monitored during operations.

8.3.1 Data Collection Protocols and Schedule

The rate of seepage and run-off will be monitored indirectly by monitoring and recording pumping rates. The seepage location and elevation along the face should be noted during inspections. The water quality should be monitored daily by visual observations for sediments (turbidity). Visual inspection should document sediment, ice or snow deposits in the ditches and sumps. The data shall be collected by designated mine personnel and reviewed by the Engineering Superintendent. The Engineering Superintendent may change the sampling frequency and amend the OMS Manual as necessary.

8.3.2 Anomalous Measurements

Anomalous measurements of the seepage may occur and include the following:

- Increase or decrease in pump rates that are inconsistent with rainfall or runoff events;
- Sediments present in the seepage water; and
- Changes in seepage location, flow, and quality.

If anomalous readings are observed, the following action should be taken:

- Inspect the seepage collection area;
- Check data, reductions, and calculations for accuracy and correctness;
- Re-read to check the reading;
- Check readout equipment to verify that it is functioning correctly;
- Verify calibration;
- If instrument has stopped functioning, notify the Engineering Superintendent immediately. If considered critical, a replacement instrument should be installed;
- If the anomalous reading is confirmed, a detailed review of the effects of the increased seepage should be carried out and design or remedial actions should be implemented if determined necessary by the Engineering Superintendent; and
- Increase monitoring frequency to assess progression of anomaly.

SECTION 9 • REPORTING PROCEDURES AND DATA MANAGEMENT

9.1 REPORTING PROTOCOLS

9.1.1 Inspection Documents

All inspection documents and reviews shall be reported to the General Manager, Engineering Superintendent and the Environment Superintendent.

9.1.2 Instrumentation Measurements

All geotechnical instrumentation measurements shall be reported to the Engineering Superintendent. Pumping rates during dewatering and operation shall be reported to the Engineering Superintendent.

9.1.3 Emergencies

All documents regarding instrumentation and inspections prior to an emergency and during an emergency shall be provided to all parties involved including the General Manager, Engineering Superintendent, Environment Superintendent, and Design Engineer.

9.2 DATA MANAGEMENT

An electronic library or database, which is easily accessible, shall be set up to catalogue and store inspection documents, maintenance reports and instrumentation measurements. Hard copies shall also be catalogued and stored on site. The following will be stored in the hard copy and electronic format:

Dewatering:

- Daily dewatering inspection report; and
- Instrumentation measurements.

Operations:

- Daily routine operating and structural inspection;
- Monthly routine operating and structural inspection;
- Engineering inspection;
- Dam Safety Review;
- Planned and un-planned maintenance reports; and
- Instrumentation measurements.

SECTION 10 • DECOMMISSIONING

10.1 GENERAL

The decommissioning of the dikes will take place progressively as the Dewatering Dikes are breached and the northwest arm of Second Portage Lake and Bay-Goose Basin are allowed to flood.

The main objectives of the decommissioning are:

- Maintain dike stability;
- Meeting applicable water quality objectives;
- Sequential pit flooding in a controlled manner; and
- Maintain 1 m head difference across the East Dike at closure.

10.2 EAST DIKE EMBANKMENTS

The East Dike will remain intact during the controlled flooding of the Portage Pit and Goose Island Pit areas in order to isolate flooded pit waters from Second Portage Lake. The pit areas are flooded gradually over the course of several years. Once the water levels have stabilized within the flooded pit and water quality is considered acceptable for mixing with neighbouring lakes, parts of the other dewatering dikes will be decommissioned to allow circulation of pit water and lake water.

The East Dike will remain, preserving the 1 m difference in elevation between Third Portage Lake and Second Portage Lake.

10.3 SEEPAGE COLLECTION SYSTEM

The sumps and ditches at the downstream toe of the Dewatering Dikes will be flooded at closure. All pumps, pipe, and equipment shall be removed prior to flooding.

10.4 INSTRUMENTATION AND MONITORING

Long-term inspection shall be carried out to ensure the adequate performance of the post-closure facility.

SECTION 11 • EMERGENCY PREPAREDNESS PLAN

The Dam Safety Guidelines prepared by the Canadian Dam Association (2007) states that “A dam which does not impose an unacceptable risk to people or property, and which meets safety criteria that are acceptable to the government, the engineering profession and the public is a safe dam”.

This guiding principle has been taken into account for the design of the dewatering dike embankments and the emergency procedures.

The East Dike and Bay-Goose Dike are rated as “High Consequence of Failure” (CDA 2007) as discussed in Section 1.3. The South Camp Dike and Vault Dike are rated as a “Significant Consequence of Failure” (CDA 2007) as discussed in Section 1.3.

To respond to possible hazards and emergencies involving the dewatering dikes, emergency response plans have been designed. This section provides a summary of the actions, triggers and measures in the event of an emergency.

In case of an emergency, the documents listed in Table 12.1 shall be referenced. The Emergency Response Plan (ERP) shall also be referenced. The Dike Failure Scenario Appendices from the ERP are included in Appendix B.

11.1 EMERGENCY PROCEDURES

The purpose of the Emergency Preparedness Plan (EPP) is to present a basic procedure for responding to potential failure mechanisms. The procedure identifies various measurable or observable effects or causes of the failure mechanisms and identifies the appropriate people to notify. Potential failure mechanisms are summarized in Table 12.2 with potential measurable and observable causes and effects.

11.1.1 Operation

Table 12.3, 12.4, 12.5 and 12.6 summarizes the triggers for implementing the EPP for each of the dewatering dikes with respect to the potential measurable and observable effects or causes of the various failure mechanisms.

Table 12.7 indicates the chain of communication to follow so persons in charge are notified for different states of emergency.

Table 12.8 indicates the responsibilities of persons for each emergency level in terms of who performs the decision making, mobilization, and action to be taken.

Table 12.9 indicates the names and contact numbers of the persons in charge during an emergency event.

11.2 EMERGENCY DETAILS

In the unlikely event of a catastrophic dike breach that could endanger workers the Code 1 procedure described in Section 11.2.4 would be followed to warn all workers of the situation. Then an evacuation of the affected areas and pits would be carried out and directed by the ERT Team in person and over the emergency channel. In the event of an embankment failure, the following information should be used during the emergency response:

<i>Project Name:</i>	Meadowbank Gold Project
<i>Dike Names:</i>	East Dike, Bay-Goose Dike, South Camp Dike, Vault Dike
<i>Owner's Name:</i>	Agnico Eagle Mines Limited (867) 793-4610
<i>Lake Name:</i>	Second Portage Lake /Third Portage Lake /Wally lake
<i>Site Location:</i>	Latitude: 65°01'07"N Longitude: 96°04'26"W

11.2.1 Access to the Project Site

- 80 km north of the Hamlet of Baker Lake
- Site accessible by all-weather road from Baker Lake.
- Site accessible by aircraft and helicopter.

	Name	Phone Number
Local Charter Company:	Calm Air International Ltd.	Baker Lake : (867) 793-2873
Local Helicopter Company:	Kitikmeot Helicopters Ltd	(867) 983-2544
Charter Aircraft Company:	Propair-Nolinor	(514)631-3000

11.2.2 Emergency Assessment and Risk Assessment

In case of an event, emergency assessment will be done first by AEM Geotechnical Engineering personnel and the Engineering Superintendent on site. Assessment will be done according to the criteria stated in the Table 12.2 and Table 12.3, 12.4, 12.5, 12.6.

11.2.3 Emergency Communication and Actions

In case of an event, after the emergency assessment, the persons involved in the emergency response need to be notified following the chain of command stated in Table 12.7. Contact details of each person are available in Table 12.9.

According to the state of the event, decision and action plan will be taken by the persons notified. Action plan will be defined according to the level of emergency and the cause of the event. Immediate action plan will be taken with material and equipment available on site, as listed in Section 11.4.

Table 12.10 is based on Appendix A of the AEM Emergency Response Plan, which describes the risk of failure for East Dike and Bay-Goose Dike and provides contingency or corrective actions for possible failure mechanisms.

Table 12.12 is the risk assessment for East Dike, Bay-Goose Dike, South Camp Dike and Vault Dike. The ratings for the likelihood and consequence of failure have been included for the risk assessment in Table 12.11. The overall risk rating is the product of the likelihood and consequence ratings. The overall risk rating of the structure for the identified failure mechanism can then be determined. The controls which are in place can potentially reduce the overall risk rating.

11.2.4 Site Emergency Procedure

As specified in the Emergency Response Plan, Ver. 6, Section 4:

In the event of an immediate emergency that is or could impact persons or equipment, the employee will have to follow our emergency procedure:

- Emergency is initiated - by calling **6911** on desk type phones, or calling on two-way radio on **"Working Channel" – Code 1 – Code 1 – Code 1**.
- All communication stops except for those involved with the Emergency – i.e.: First Aid Room attendants, Medics, ERT as required.
- All work stops in First Aid Room / Clinic – and in affected area – depending on seriousness of Emergency – the whole site.
- First Aid Room Attendant / Medic will answer the phone and/or radio.
Note: if the First Aid Room Attendant / Medic do not answer, then Security Guard will answer and/or a Supervisor on radio will answer so that Emergency Response can be initiated.
- **Responder** – will ask where the medic is required.
- **Caller** – will give a brief description of the Emergency – name, location and what is wrong and/or required.
- **Responder** – will confirm location and details of incident and activate the **ERT** team. Security will be notified by responder and a page will be sent out to all **ERT** team members on site. (All **ERT** team members on site now carry pagers).
- The person at the casualty(s) will administer First Aid if trained to do so.
- Incident Commander Center will be immobilized as to ensure that communications, transportation, and effective deployment of **ERT** resources are conducted. It is mandatory that the Official In-Charge be notified immediately.
 - ❖ Transportation will be arranged to meet at the **ERT** hall by the two large doors for medical gear and **ERT** team members.

The **ERT** team (minimum of 6 team members) will assemble as quickly as possible. (Expectation – when the page goes off – all **ERT** team members will make their way expediently to the **ERT** hall.

11.2.5 Communication Equipment Location

Communication equipment can be found at the following locations *(to be updated if required)*:

- 3 phone land lines are located in the main office;
- Base station radios are located in the main office;
- Drills will have either base station radios or handhelds—depending on their distance from camp and will have satellite phones available; and
- Emergency Communication Plans (including emergency contact numbers) are located adjacent to all phones and radios and in each drill.

11.3 MEDICAL AND FIRST AID SERVICES

In case of injury the medic and First Aid station are located in the Service Building. The first aid channel on the radio is 1. The nearest hospital is located in Baker Lake.

Health Center: Baker Lake Health Center Phone #: (867) 793-2816

11.4 ON SITE EQUIPMENT AND MATERIAL

11.4.1 Pumping Equipment

The following is a list of onsite pumping equipment available for use during an emergency event:

Unit Number	Description	Model
61PWA01	Dewatering pump #1	Godwin model HL250M
61PWA02	Dewatering pump #2	Godwin model HL250M
61PWA03	Dewatering pump #3	Godwin model HL250M
61PWA04	Dewatering pump #4	Godwin model HL250M
61PWA05	Dewatering pump #5	Godwin model HL250M
61PWA06	Dewatering pump #6	Godwin model HL250M
61PWA07	Pit Dewatering pump #7	Godwin model CD80M
61PWA08	Pit Dewatering pump #8	Godwin model CD80M
61PWA09	Dike Dewatering pump #9	Godwin model CD100M
61PWA10	Dike Dewatering pump #10	Godwin model CD103M
61PWA11	Dike Dewatering pump #11	Godwin model CD103M
61PWA12	Dike Dewatering pump #12	Godwin model CD103M
61PWA13	Pit Dewatering pump #13	Godwin model HL5MS
61PWA14	Pit Dewatering pump #14	Godwin model HL5MS

Unit Number	Description	Model
61PWA15	Bay-Goose Seepage dewatering pump #9	Godwin model CD103M
61PWA16	Bay-Goose Seepage dewatering pump #10	Godwin model CD103M

Note: To be updated as required

11.4.2 Mobile Equipment

The following are lists of onsite mobile equipment of AEM and FGL available for use during an emergency event:

AEM Mobile Equipment List (to be updated as required)

MODEL	EQUIP. #	MODEL	EQUIP. #	MODEL	EQUIP. #	MODEL	EQUIP. #	MODEL	EQUIP. #
LOADING		LOADER		PICKUP		FROST FIGHTER		TRAILER	
RH 40	BAC01	IT14G (SS)	LOA01	F-350	POK01	IDF-350	HEA01	TANKER	TRL01
345CL	BAC02	420E (SS)	LOA05	F-350 (SS)	POK02	IDF-350	HEA02	LOW BED	TRL04
307	BAC03	999H (SS)	LOA06	F-350	POK03	IDF-350	HEA03	LOW BED	TRL05
345D	BAC05	TC44H (SS)	LOA08	F-350	POK04	IDF-350	HEA04	FUEL TANK	TRL06
385C	BAC06	999H (SS)	LOA09	F-350	POK05	IDF-350	HEA05	FUEL TANK	TRL07
345DL	BAC07	980H (SS)	LOA10	F-350	POK06	IDF-350	HEA06	LOW BOY	TRL08
RH120	BAC10	420E	LOA11	F-350	POK07	IDF-350	HEA07	FIRE PUMP TRAILER	TRL09
RH120	BAC11	TRUCK		F-350	POK08	IDF-350	HEA08	WELDING MACHINE	
RH120	BAC12	T800	TRK01	F-350	POK09	IDF-350	HEA09	400D	SMD01
IT14G	LOA02	KENWORTH	TRK02	F-350	POK10	IDF-350	HEA10	WITH AIR PACK	SMD02
962G	LOA03	KENWORTH	TRK03	F-350	POK11	IDF-350	HEA11	500P W/ AIR	SMD03
962G	LOA04	KENWORTH	TRK04	F-350	POK12	IDF-350	HEA12	WITH AIR PACK	SMD05
980H	LOA12	TRUCK (SS)	TRK05	E-350	POK13	IDF-350	HEA13	RH120 BUCKET	
DOZER		KENWORTH	TRK06	F-350	POK14	IDF-350	HEA14	Bucket 01	
D8T	DOZ01	FRD WATER	TRK07	F-350	POK15	FROST FIGHTER		Bucket 02	
D8T	DOZ02	SEPTIC	TRK08	F-350	POK16	MOBILE TANK		Bucket 03	
D8T	DOZ05	HAB	TRK09	F-350	POK17	GENE		Bucket 04	
D8T	DOZ06	CEMENT	TRK10	F-350	POK18	G5525	SC05	345 BUCKET	
D8T	DOZ07	CEMENT	TRK11	F-250	POK19	S85	SC06	Bucket 01	
834H	DOZ08	Truck	TRK12	F-250	POK20	Z-4525	SC07	Bucket 02	
GRADER		KENWORTH	TRK14	F-250	POK21	Z-4525	SC08	Bucket 03	
16M	GRA03	KENWORTH	TRK15	F-350	POK22	S85	SC011	Bucket 04	
16M	GRA04	TRUCK (SS)	TRK16	F-350	POK23	S85	SC012	385 BUCKET	
HAULING		FUEL	TRK17	F-250	POK24	S125	SC013	Bucket 01	
777F	HTR01	GARBAGE (SS)	TRK18	F-250	POK25	S125	SC014	Bucket 02	
777F	HTR02	FIRE TRUCK	TRK19	F-250 (SS)	POK26	S85	REN07	902 BUCKET	
777F	HTR03	FUEL	TRK21	F-250 (SS)	POK27	Crane		Bucket 01	
777F	HTR04	S.Plow	TRK22	F-250	POK28	120T (SS)	MCR01	Bucket 02	
777F	HTR05	S.Plow	TRK23	F-250	POK29	#0T (SS)	MCR02	Bucket 03	
777F	HTR06	STEAMER	TRK24	F-250 (SS)	POK30	35T (SS)	MCR03	Bucket 04	
777F	HTR07	Fontaine T.	TRK28	F-250	POK31	90T (SS)	MCR04	TRUCK BOX REPAIR	
777F	HTR08	LUB	TRK30	F-250	POK32	25T (SS)	MCR05	TRUCK BOX	BOX01
785B	HTR20	Service	TRK31	F-250	POK33	200T	MCR06	TRUCK BOX	BOX02
785B	HTR21	AIR PLANE FUEL TANKER	TRK32	F-250	POK34	LIGHT TOWER		TRUCK BOX	BOX03
785B	HTR22	LUB	TRK33	F-250	POK35	AL5000	LGT01	TRUCK BOX	BOX04
785D	HTR23	SHOP	TRK34	F-250	POK36	L-20	LGT02	TRUCK BOX	BOX05
785D	HTR24	FUEL	TRK35	F-250	POK37	L-20	LGT03	TRUCK BOX	BOX06
785D	HTR25	S.Plow	TRK36	F-250	POK38	L-20	LGT04	TRUCK BOX	BOX07
785C	HTR26	Service Truck	TRK38	E-350	POK39	L-20	LGT05	TRUCK BOX	BOX08
785C	HTR27	GENSET		F-250	POK40	L-20	LGT06	TRUCK BOX	BOX09
785C	HTR28	XQ2000	GEN01	F-250	POK41	L-20	LGT07	TRUCK BOX	BOX10
785D	HTR29	XQ2000	GEN02	F-250	POK42	L-20	LGT08	TRUCK BOX	BOX11
785D	HTR30	XQ2000	GEN03	F-350	POK43	LTC4	LGT09	TRUCK BOX	BOX12
777B	HTR10	3412	GEN05	F-250	POK44	LTC4	LGT11	TRUCK BOX	BOX13
773E	HTR09	XQ202	GEN06	F-350	POK45	LTC4	LGT12	TRUCK BOX	BOX14
DRILL		XQ202	GEN07	F-250	POK46	LT5000-4MH	LGT18	TRUCK BOX	BOX15
DM45E	RBD01	3508	GEN08	F-250	POK47	MECHANICAL SERVICE TRUCK		TRUCK BOX	BOX16
DM45E	RBD02	C8T	GEN09	F-250	POK48	SERVICE	WMM02	TRUCK BOX	BOX17
DM45E	RBD03	C8T	GEN10	F-250	POK49	MULE		TRUCK BOX	BOX18
DM45E	RBD04	DOHE	GEN11	F-250	POK50	OBSELETE	VSE01	TRUCK BOX	BOX19
CM785	RBD05	DOGO	GEN12	F-250	POK51	Mule	VSE02		
DML	RBD06	D200P	GEN13	F-450 WH	POK52	Mule	VSE03		
DML	RBD07	D100P4S	GEN14	F-250	POK53	Mule	VSE04		
DML	RBD08	D100P15K	GEN15	F-250	POK54	Mule	VSE05		
HAMMER		D25-8	GEN16	F-250	POK55	Mule	VSE06		
V56	HAM01	D25-8S	GEN17	F-250	POK56	Mule	VSE07		
V56	HAM02	D25-8S	GEN18	F-250	POK57	Hubota	VSE08		
BUS		D13-4S	GEN19	F-250	POK58	Hubota	VSE09		
H77 (SS)	BUS01	D13-4S	GEN20	F-250	REN56	Hubota	VSE10		
E-350	BUS02	GA830	GEN21	ATV		Mule	VSE11		
E-350 (SS)	BUS03	GA830	GEN22	ATV02		SKID STEER			
VAN E350	BUS04	D8FAE	GEN23	ATV03		262C	SKD01		
3200S-8 (SS)	BUS05	3412	GEN24	ATV05		753	SKD02		
E-350	BUS06	3412	GEN25	BOAT ENGINE		262C	SKD03		
S30	BUS07	GEH202-2	GEN26	ENG06		SNOW BLOWER			
3800	BUS08	D200P3	GEN27	ENG07		SNOW BLOWER	SSL01		
3800	BUS09	DISKAA	GEN28	COMPACTOR		SNOW BLOWER	SSL02		
SITE SERVICE		DISKAA	GEN29	CPT01		HYSTER HANDLER			
330D	BAC04	GA830	GEN30	CPT02		GTH844	TPA01		
DOZER		GA836	GEN31	EMERGENCY VEHICLE		GTH844	TPA02		
D8R	DOZ03	?	GEN32	SNOWCAT	SN001	HR45 (SS)	TPA03		
D8T	DOZ09	D30-10 (SS)	GEN33	FORK LIFT		PETER	TPA03P		
GRADER		QAS 30	GEN34	HYSTER RH35	FKL02	1096C (SS)	TPA04		
16H	GRA01	QAS 30	GEN35	CAT (WH)	FKL03	SPARE	TPA05		
180H	GRA02	D30-10	GEN36	RJ2	FKL04	JINGERSOLL RAN			
		8081AF001	GEN37	CAT	FKL05	REN15			
		D30-10	GEN38	CAT (SHOP)	FKL06	COMPRESSOR			
		D30-8	GEN39	746DR321T	FKL07	COM01			
				ETDR40TT	FKL08	SULLAIR	COM02		
				HYSTER	FKL09	SULLAIR	COM03		

FGL Mobile Equipment List (to be updated as required)




SHOVELS		
TYPE	UNIT NUMBER	Models
PC 1250	11-0303	Komatsu
385	395	Caterpillar
385	1333	Caterpillar
365	1313	Caterpillar
345	11-0301	Caterpillar
345	393	Caterpillar
GRADER		
TYPE	UNIT NUMBER	OPERATOR NAME
14-M	513	Caterpillar
HAULING TRUCKS		
TYPE	UNIT NUMBER	OPERATOR NAME
773	1516	HTR 773F
773	1517	HTR 773F
773	1518	HTR 773F
773	1519	HTR 773F
773	1520	HTR 773F
773	1535	HTR 773F
773	1536	HTR 773F
740	1522	HTR 740
740	1530	HTR 740
100T	11-1001	TR 100
100T	11-1002	TR 100
100T	11-1003	TR 100
100T	11-1004	TR 100
DOZERS		
TYPE	UNIT NUMBER	OPERATOR NAME
D6	441	Caterpillar
D8T	438	Caterpillar
D8T	443	Caterpillar

11.4.3 Earthwork Material and Equipment

The following map presents the earthwork material, including geomembrane and cement, available on site in case of an emergency.

Figure 13 Earthwork Material and Equipment Location



SECTION 12 • EMERGENCY RESPONSE REFERENCE DOCUMENTS

Table 12.1 Emergency Response Reference Documents

Document	Current Revision
Emergency Response Plan	Updated by AEM. Version 6, August 2013
Emergency Preparedness Plan	In Dewatering Dikes OMS Manual, Version 2, August 2013

Note: To be updated as required

Table 12.2 Potential Effects or Causes of Failure Mechanisms

Failure Mechanism	Potential Measurable and Observable	
	Causes	Effects
Overtopping	(1) Lake level rise. (2) Dam crest settlement	Increase of seepage leading to erosion of downstream foundation soils and associated crest settlement.
Internal Erosion	(1) Loss of cut-off wall/liner at construction defects in cut-off wall/liner, Core Backfill and filter. (2) Loss of bentonite from cut-off wall at defect in construction (3) Loss of till foundation at defect in dike section.	Sinkhole observable at crest Slower lake drawdown during dewatering Increase in seepage pumping rate during operations Increase in pore water pressures downstream of cut-off wall/liner Increase in turbidity / suspended solids of seepage
Seepage Within Embankment	Increase in seepage rate due to cut-off wall/liner failure	Increased seepage water handling. Not likely to compromise stability of dike.
Seepage Within Foundation	Un-observable defects in cut-off/liner construction.	High flow during initial dewatering or shortly thereafter.
Internal Conduit Rupture	Not applicable	Not applicable
Slope Instability	(1) ice or wave forces, or traffic on crest, seepage, weakness of foundation soils (2) Earthquake seismic event or blasting (3) Pit wall failure	Increase in settlement and/or settlement rate Increase in displacement and/or displacement rate of dike toe Cracks along the dike crest Sloughing of the face Bulging of dike toe Disruption of seepage collection ditch

Failure Mechanism	Potential Measurable and Observable	
	Causes	Effects
Failure of Cut-off Wall/Liner Due to Movement of the Dike (Cut-off wall/liner lateral movement)	Differential horizontal movement of dike due to water or ice loading, pit wall stability, excessive dike settlement Seepage.	Large inflows associated with a breach in the dike. Increase in lateral deformation or increase in rate of deformation in slope inclinometer reading Increase in pore water pressure downstream of cut-off wall/liner Increase in pumping rate Dislocation, cracks, settlement localized above or adjacent to cut-off wall/liner
Unexpected settlements	Consolidation of foundation soils or dike fills	Overtopping in extreme case large settlement of cut-off wall/liner.

Table 12.3 Threshold Criteria during Operation for East Dike

		Threshold Criteria During Operation			
		Green Acceptable Situation	Yellow Areas of concern	Orange High Risk Situation	Red Emergency Situation
Criteria	Downstream toe displacement, sloughing or bulging	None visible	Visible displacement or bulging	Toe displacement related to a sloughing slide from near downstream crest to 5 m from centreline Bulging > 1 m in height	Toe displacement related to a sloughing slide reaching 5 m from centreline Bulging greater than 4m in height
	Tension crack along downstream rockfill embankment (more than 3 m from centreline)	Within 7 m of the downstream crest edge and < 0.1 m deep and < 3 m length along the dike	Within 10 m of the downstream crest edge and > 0.1 m and < 1.0 m deep	> 1.0 m deep	> 1.0 m deep
	Tension crack along upstream rockfill embankment (more than 3 m from centreline)	< 0.1 m deep and < 3 m length along the dike	> 0.1 m and < 1.0 m deep	> 1.0 m deep	> 1.0 m deep
	Tension crack within 3 m each side of the cutoff wall at crest (upstream or downstream)	None visible	< 0.1 m deep or < 0.1 m wide	> 0.1 m deep or > 0.1 m wide	> 0.1 m deep or > 0.1 m wide
	Sinkhole on crest	Not visible	> 5 m outside from centreline	Within 5 m from centreline	Within 5 m from centreline
	Cut-off wall lateral cumulative deformation (based on survey monument)	None	<0.05 m	> 0.05 and 0.10 m	> 0.10 m
	Cut-off wall lateral cumulative deformation (based on inclinometer)	None	< 0.05 m	> 0.05 m and < 0.10 m	> 0.10 m
	Lake elevation	< 134.1 masl	> 134.1 and < 134.8 masl	> 134.8 and < 135.6 masl	> 135.6 masl
	Pore water pressure (based on piezometers)	Pore water pressure measurements stable or decreasing.	Increasing trend in pore water pressure downstream of cut-off wall.	Anomalous trends (sharp increase) in pore water pressure downstream of cut-off wall.	Anomalous trends (sharp increase) in pore water pressure downstream of cut-off wall.
	Temperature variation along centreline (based on thermistors and piezometers)	Temperature measurement stable and similar variation at surface from previous years.	Increasing trend in temperature below the active layer	Continuous increasing trend in temperature below the active layer	Continuous increasing trend in temperature below the active layer
	Seepage through dike (excluding Freshet water)	< 3,000 m ³ /day	>3,000 m ³ /day and <6,000 m ³ /day and / or turbidity in the water	> 6,000 m ³ /day and < 20,000 m ³ /day and / or turbidity in the water	> 20,000 m ³ /day <i>Condition where the seepage inflow is rapidly increasing and projected to soon exceed pumping capacity</i>
Action Required		<ul style="list-style-type: none"> Instrumentation monitoring and visual inspection according to frequency set out in OMS manual. Possibility of a mitigation plan to be evaluated by Engineering Department. 	<ul style="list-style-type: none"> Increased instrumentation monitoring frequency, particularly in area of concern. Document location, photograph, survey, and increase inspection and monitoring in area of concern. Identify potential cause Implement engineering review. 	<ul style="list-style-type: none"> Suspend activities on dike crest at area of concern Increased instrumentation monitoring frequency, particularly in area of concern. Document location, photograph, survey, and increase inspection and monitoring in area of concern. Plan and take appropriate mitigation measures with engineering review. (Use as reference contingency measures for different scenarios proposed by AEM (See Table 12-9)). Reassess thresholds and conditions for red category (emergency situation) taking into account the changing conditions presently observed and interactions of various items. 	<ul style="list-style-type: none"> Temporary evacuation of personnel and equipment from pit and suspension of activities. Update planning and take appropriate mitigation with engineering review.
Personnel Notified		Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC, if required).	Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC), Specialized Contractor (if required), Environment Superintendent, Mine Manager, Discuss at MDRB Meeting.	Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC), Specialized Contractor, Environment Superintendent, Mine Manager, Dike Review Board, Mine Inspector, Health and Safety, ERT (Emergency Personnel, if required).	Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC), Specialized Contractor, Environment Superintendent, Mine Manager, Dike Review Board, Mine Inspector, Health and Safety, ERT (Emergency Personnel).

Table 12.4 Threshold Criteria during Operation for Bay-Goose Dike

		Threshold Criteria During Operation			
		Green Acceptable Situation	Yellow Areas of concern	Orange High Risk Situation	Red Emergency Situation
Criteria	Downstream toe displacement, sloughing or bulging	None visible	Visible displacement or bulging	Toe displacement related to a sloughing slide from near downstream crest to 5 m from centreline and bulging > 1 m in height	Toe displacement related to a sloughing slide reaching 5 m from centreline Bulging greater than 4m in height
	Tension crack along downstream rockfill embankment (more than 3 m from centreline)	Within 7 m of the downstream crest edge and < 0.1 m deep and < 3 m length along the dike	Within 10 m of the downstream crest edge and > 0.1 m and < 1.0 m deep	> 1.0 m deep	> 1.0 m deep
	Tension crack along upstream rockfill embankment (more than 3 m from centreline)	< 0.1 m deep and < 3 m length along the dike	> 0.1 m and < 1.0 m deep	> 1.0 m deep	> 1.0 m deep
	Tension crack within 3 m of either side of the cutoff wall at crest	None visible	< 0.1 m deep or < 0.1 m wide	> 0.1 m deep or > 0.1 m wide	> 0.1 m deep or > 0.1 m wide
	Sinkhole on crest	Not visible	> 5 m outside from centreline	Within 5 m from centreline	Within 5 m from centreline
	Cut-off wall lateral cumulative deformation (based on survey monument)	None	<0.05 m	> 0.05 and 0.10 m	> 0.10 m
	Cut-off wall lateral cumulative deformation (based on inclinometer)	None	< 0.05 m	> 0.05 m and < 0.10 m	> 0.10 m
	Lake elevation	< 135.1 masl	> 135.1 and < 135.8 masl	> 135.8 and < 136.1 masl	> 136.1 masl
	Pore water pressure (based on piezometers)	Pore water pressure measurements stable or decreasing.	Increasing trend in pore water pressure downstream of cut-off wall.	Anomalous trends (sharp increase) in pore water pressure downstream of cut-off wall.	Anomalous trends (sharp increase) in pore water pressure downstream of cut-off wall.
	Temperature variation along centreline (based on thermistors and piezometers)	Temperature measurement stable and similar variation at surface from previous years.	Increasing trend in temperature below the active layer	Continuous increasing trend in temperature below the active layer	Continuous increasing trend in temperature below the active layer
	Seepage through dike at toe (excluding Freshet water)	< 300 m ³ /day	>300 m ³ /day and <1,000 m ³ /day and / or turbidity in the water	> 1,000 m ³ /day and < 2,000 m ³ /day and / or turbidity in the water	> 2,000 m ³ /day <i>Seepage inflow is rapidly increasing and projected to soon exceed pumping capacity</i>
	Seepage through dike in North Channel area	< 150 m ³ /day	>150 m ³ /day and <500 m ³ /day and / or turbidity in the water	> 500 m ³ /day and < 1,000 m ³ /day and / or turbidity in the water	> 1,000 m ³ /day <i>Seepage inflow is rapidly increasing and projected to soon exceed pumping capacity</i>
	Seepage through dike in pit (excluding Freshet water, estimated visually)	Slow trickle of water along pit walls, easily handled by regular pit sumps	Steady stream of water along pit walls, easily handled by regular pit sumps	Large quantity of water flowing down the pit walls, cannot be easily handled by regular pit sumps, mining activities are impacted	Water flowing down the walls cannot be handled by regular pit sumps and has markedly increased in flow rate and quantity, mining activities are disrupted.
Action Required		<ul style="list-style-type: none"> Instrumentation monitoring and visual inspection according to frequency set out in OMS manual. Possibility of a mitigation plan to be evaluated by Engineering Department. 	<ul style="list-style-type: none"> Increased instrumentation monitoring frequency, particularly in area of concern. Document location, photograph, survey, and increase inspection and monitoring in area of concern. Identify potential cause Implement engineering review. 	<ul style="list-style-type: none"> Suspend activities on dike crest at area of concern Increased instrumentation monitoring frequency, particularly in area of concern. Document location, photograph, survey, and increase inspection and monitoring in area of concern. Plan and take appropriate mitigation measures with engineering review. (Use as reference contingency measures for different scenarios proposed by AEM (See Table 12-9)). Reassess thresholds and conditions for red category (emergency situation) taking into account the changing conditions presently observed and interactions of various items. 	<ul style="list-style-type: none"> Temporary evacuation of personnel and equipment from pit and suspension of activities. Update planning and take appropriate mitigation with engineering review.
Personnel Notified		Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC, if required).	Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC), Specialized Contractor (if required), Environment Superintendent, Mine Manager, Discuss at MDRB Meeting.	Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC), Specialized Contractor, Environment Superintendent, Mine Manager, Dike Review Board, Mine Inspector, Health and Safety, ERT (Emergency Personnel, if required).	Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC), Specialized Contractor, Environment Superintendent, Mine Manager, Dike Review Board, Mine Inspector, Health and Safety, ERT (Emergency Personnel).

Table 12.5 Threshold Criteria during Operation for South Camp Dike

		Threshold Criteria During Operation			
		Green Acceptable Situation	Yellow Areas of concern	Orange High Risk Situation	Red Emergency Situation
Criteria	Downstream toe displacement, sloughing or bulging	None visible	Visible displacement or bulging	Toe displacement related to a sloughing slide from near downstream crest to 5 m from centreline Bulging > 1 m in height	Toe displacement related to a sloughing slide reaching 5 m from centreline Bulging greater than 4m in height
	Tension crack along downstream rockfill embankment (more than 3 m from centreline)	Within 7 m of the downstream crest edge and < 0.1 m deep and < 3 m length along the dike	Within 10 m of the downstream crest edge and > 0.1 m and < 1.0 m deep	> 1.0 m deep	> 1.0 m deep
	Tension crack along upstream rockfill embankment (more than 3 m from centreline)	< 0.1 m deep and < 3 m length along the dike	> 0.1 m and < 1.0 m deep	> 1.0 m deep	> 1.0 m deep
	Sinkhole on crest	Not visible	> 5 m outside from centreline	Within 5 m from centreline	Within 5 m from centreline
	Lake elevation	< 135.6 masl	> 135.6 and < 136.3 masl	> 136.3 and < 136.6 masl	> 136.6 masl
	Temperature variation within foundation (based on thermistors)	Temperature measurement stable and similar variation at surface from previous years.	Increasing trend in temperature below the active layer	Continuous increasing trend in temperature below the active layer	Continuous increasing trend in temperature below the active layer
	Seepage through dike (excluding Freshet water)	< 300 m ³ /day	>300 m ³ /day and <1,000 m ³ /day and / or turbidity in the water	> 1,000 m ³ /day and < 2,000 m ³ /day and / or turbidity in the water	> 2,000 m ³ /day <i>Condition where the seepage inflow is rapidly increasing and projected to soon exceed pumping capacity</i>
Action Required		<ul style="list-style-type: none">Instrumentation monitoring and visual inspection according to frequency set out in OMS manual.Possibility of a mitigation plan to be evaluated by Engineering Department.	<ul style="list-style-type: none">Increased instrumentation monitoring frequency, particularly in area of concern.Document location, photograph, survey, and increase inspection and monitoring in area of concern.Identify potential causeImplement engineering review.	<ul style="list-style-type: none">Suspend activities on dike crest at area of concernIncreased instrumentation monitoring frequency, particularly in area of concern.Document location, photograph, survey, and increase inspection and monitoring in area of concern.Plan and take appropriate mitigation measures with engineering review.Reassess thresholds and conditions for red category (emergency situation) taking into account the changing conditions presently observed and interactions of various items.	<ul style="list-style-type: none">Temporary evacuation of personnel and equipment from pit and suspension of activities.Update planning and take appropriate mitigation with engineering review.
Personnel Notified		Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC), if required).	Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC), Specialized Contractor (if required), Environment Superintendent, Mine Manager, Discuss at MDRB Meeting.	Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC), Specialized Contractor, Environment Superintendent, Mine Manager, Dike Review Board, Mine Inspector, Health and Safety, ERT (Emergency Personnel, if required).	Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC), Specialized Contractor, Environment Superintendent, Mine Manager, Dike Review Board, Mine Inspector, Health and Safety, ERT (Emergency Personnel).

Table 12.6 Threshold Criteria during Operation for Vault Dike

		Threshold Criteria During Operation			
		Green Acceptable Situation	Yellow Areas of concern	Orange High Risk Situation	Red Emergency Situation
Criteria	Downstream toe displacement, sloughing or bulging	None visible	Visible displacement or bulging	Toe displacement related to a sloughing slide from near downstream crest to 5 m from centreline Bulging > 1 m in height	Toe displacement related to a sloughing slide reaching 5 m from centreline Bulging greater than 4m in height
	Tension crack along downstream rockfill embankment (more than 3 m from centreline)	Within 7 m of the downstream crest edge and < 0.1 m deep and < 3 m length along the dike	Within 10 m of the downstream crest edge and > 0.1 m and < 1.0 m deep	> 1.0 m deep	> 1.0 m deep
	Tension crack along upstream rockfill embankment (more than 3 m from centreline)	< 0.1 m deep and < 3 m length along the dike	> 0.1 m and < 1.0 m deep	> 1.0 m deep	> 1.0 m deep
	Sinkhole on crest	Not visible	> 5 m outside from centreline	Within 5 m from centreline	Within 5 m from centreline
	Lake elevation	< 141.5 masl	> 141.5 and < 142.2 masl	> 142.2 and < 142.5 masl	> 142.5 masl
	Temperature variation within foundation (based on thermistors)	Temperature measurement stable and similar variation at surface from previous years.	Increasing trend in temperature below the active layer	Continuous increasing trend in temperature below the active layer	Continuous increasing trend in temperature below the active layer
	Seepage through dike (excluding Freshet water)	< 300 m ³ /day	>300 m ³ /day and <1,000 m ³ /day and / or turbidity in the water	> 1,000 m ³ /day and < 2,000 m ³ /day and / or turbidity in the water	> 2,000 m ³ /day <i>Condition where the seepage inflow is rapidly increasing and projected to soon exceed pumping capacity</i>
Action Required		<ul style="list-style-type: none">Instrumentation monitoring and visual inspection according to frequency set out in OMS manual.Possibility of a mitigation plan to be evaluated by Engineering Department.	<ul style="list-style-type: none">Increased instrumentation monitoring frequency, particularly in area of concern.Document location, photograph, survey, and increase inspection and monitoring in area of concern.Identify potential causeImplement engineering review.	<ul style="list-style-type: none">Suspend activities on dike crest at area of concernIncreased instrumentation monitoring frequency, particularly in area of concern.Document location, photograph, survey, and increase inspection and monitoring in area of concern.Plan and take appropriate mitigation measures with engineering review.Reassess thresholds and conditions for red category (emergency situation) taking into account the changing conditions presently observed and interactions of various items.	<ul style="list-style-type: none">Temporary evacuation of personnel and equipment from pit and suspension of activities.Update planning and take appropriate mitigation with engineering review.
Personnel Notified		Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC, if required).	Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC), Specialized Contractor (if required), Environment Superintendent, Mine Manager, Discuss at MDRB Meeting.	Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC), Specialized Contractor, Environment Superintendent, Mine Manager, Dike Review Board, Mine Inspector, Health and Safety, ERT (Emergency Personnel, if required).	Principal Geotechnical Engineer, Engineering Superintendent, Engineering Assistant Superintendent, Corporate Environment Director, Designer (Golder or SNC), Specialized Contractor, Environment Superintendent, Mine Manager, Dike Review Board, Mine Inspector, Health and Safety, ERT (Emergency Personnel).

Table 12.7 Communication Charts for Each Emergency Level

Communications are rated to indicate in which order responsible persons should be notified in the case where a person needs to advise more than one person




Table 12.8 Responsibilities of Persons for Each Emergency Level

	Decision Making	Mobilization	Performing the Action to be Taken
Green Acceptable Situation	Principal Geotechnical Engineer	Principal Geotechnical Engineer	Geotechnical Team*
Yellow Areas of Concern	Principal Geotechnical Engineer Engineering Superintendent Engineering Assistant Superintendent Designer (Golder or SNC)	Principal Geotechnical Engineer	Geotechnical Team* Specialized Contractor (if required)
Orange High Risk Situation	Principal Geotechnical Engineer Engineering Superintendent Engineering Assistant Superintendent Designer (Golder or SNC) Corporate Environment Director Dike Review Board Mine Manager Health and Safety (if required)	Principal Geotechnical Engineer Engineering Superintendent Engineering Assistant Superintendent	Geotechnical Team* Specialized Contractor ERT (if required)
Red Emergency Situation	Principal Geotechnical Engineer Engineering Superintendent Engineering Assistant Superintendent Designer (Golder or SNC) Corporate Environment Director Dike Review Board Mine Manager Health and Safety	Principal Geotechnical Engineer Engineering Superintendent Engineering Assistant Superintendent Superintendent Mine Manager Health and Safety	Geotechnical Team* Specialized Contractor ERT

*The Geotechnical Team consists of the Principal Geotechnical Engineer, the Dewatering and Pit Geotechnical Engineer/Geologist, Water Management, and the Geotechnical Technician.

Table 12.9 Names and Contact Details

Internal Emergency Response Contact Information Chart		
Position	Name/Location	24-Hour Contact #
Principal Geotechnical Engineer	Erika Voyer	Ph: 867-793-4610 ext. 6837 cell: 581-982-7107
	Thomas Lepine	Ph: 867-793-4610 ext. 6837 cell: 418-473-8077
Engineering Superintendent	Julie Belanger	Ph: 867-793-4610 ext. 6721 cell: 819-856-1667
Engineering Assistant Superintendent	Stephane Frechette	Ph: 867-793-4610 ext. 6721 cell: 819-856-3152
Corporate Environment Director	Michel Julien	Ph: 416-947-1212 ext. 3738 cell: 514-244-5876
Designer (Golder or SNC)	Golder Burnaby: Dan Walker, Fiona Esford Golder Montreal: Yves Boulianne, Annie Beaulieu	Burnaby Office: 604-296-4200 Montreal Office: 514-383-0990
	SNC: Jean-Francois St-Laurent, Yohan Jalbert, Simon Beaulieu	Quebec City Office: 418-621-9700
Specialized Contractor	SANA (FGL Group)	Onsite Ph: 867-793-4610 ext. 6963 Ph: 418-615-0559
Environment Superintendent	Kevin Buck	Ph: 867-793-4610 ext 6838 Cell: 819-856-1956
Mine Manager	Jean Beliveau	Ph: 867-793-4610 ext. 6901 cell: 819-856-5605
	Alexandre Proulx (asst.)	Ph: 867-793-4610 ext. 6843 cell: 819-860-6389
Dike Review Board	Anthony Rattue Norbert Morgenstern Don Hayley	Anthony.Rattue@snclavalin.com norbertm@ualberta.ca dhayley@eba.ca
Mine Inspector	Martin VanRooy	Martin.vanRooy@wscc.nu.ca_contact1
Health and Safety	Normand Ladouceur	Ph: 867-793-4610 ext. 6720 cell: 819-860-6258
	Yves Levesque (asst.)	Ph: 867-793-4610 ext. 6720 cell: 819-856-9051
ERT (Emergency Personnel)	Emergency response personnel available on site to assist with spill and emergency response activities	Coordinated by the Emergency Measures Counsellor
Incident Commander	André Rouleau	Ph: 867-793-4610 ext. 6809 cell: 819-355-2191 Channel #1
	Normand Ladouceur	Ph: 867-793-4610 ext. 6720 cell: 819-860-6258 Channel #1
Emergency Measures Counsellor	André Rouleau	Ph: 867-793-4610 ext. 6809 cell: 819-355-2191

Health Professionals / Medical Clinic	Medical Clinic 1	Ph: 867-793-4610 ext. 6734
	Medical Clinic 2	Ph: 867-793-4610 ext. 6751
AEM Management Representative	Dominique Girard	Ph: 867-793-4610 ext. 6901 cell: 819-277-4080
Human Resource Superintendent	Krystel Mayrand	Ph: 867-793-4610 ext 6723 cell: 819-856-9556

Table 12.10 Emergency Response Summary for East Dike and Bay-Goose Dike

Concern	Area		Failure Likelihood	Comments/Monitoring	Contingency or Corrective Action
Overtopping and Subsidence	1a	Lake level rise because of restricted outflow from Third Portage or Second Portage Lake (excessive inflow is a far less likely scenario)	Low	Lake levels and crest elevations should be monitored as part of daily safety information provided to mine management. Outflow channels should be inspected during thaw, open water season and during ice break-up.	The crest is wide and comprises coarse rockfill. Significant damage to the dike is not credible, based on performance of other rockfill structures subjected to overtopping or flow through events. Mining operations may need to be suspended, but there will be considerable warning time given the design freeboard and the storage volume within the lakes.
	1b	Dam crest settles more than 2 m	Low	This scenario requires extensive loss of support in the foundation since the rockfill of the dikes is essentially not settlement prone itself after construction and dewatering. For foundation settlement of this magnitude to occur, a piping event must develop or there is unexpected layer of compressible soil in the foundation. A foundation investigation was carried out prior to construction. The situation would develop slowly with crest settlement evident at least several weeks before a run-away event develops. Easily observed cracks should be evident. Monitoring of the crest settlement should be conducted routinely.	The crest is wide and comprises of coarse rockfill. Significant damage to the dike is not credible, based on performance of other rockfill structures subjected to overtopping or flow through events Rockfill and till available from the mining operations can be placed to raise the dike crest. Mining operations may need to be suspended, but there will be considerable warning time given the slow development of the scenario.
	1c	Wave action	Low	Wide beach, large freeboard and wide rock dam crest zone makes this a low concern	If large wave action is observed, can add rip-rap and/or raise dam crest
Internal Erosion	2a	Dike Section: Cut-off wall is defective, allowing high water flow. This defect occurs at a location where the core allows high flows and where the fills are defective; the combination allows erosion of the cut-off and/or the Core Backfill.	Low	The cut-off wall and/or core backfill will develop a progressively increasing void ratio, thereby increasing the rate of water flow through the dike. This is not a catastrophic failure mode as the rockfill will be stable and at its worst would lead to temporary suspension of mining.	Monitor seepage from downstream face for rate of seepage and for presence of sediment in seepage. Will become evident as localized intensive seepage at dike toe and can be repaired. May also see settlement in the core or cut-off wall near the filter. Will be most likely in deepest section. Gradients across the core in shallow water may not be high enough to cause piping.
	2b	Dike Section: Cut-off wall loses bentonite because of improper construction	Low	The cut-off wall will develop progressively increasing voids, thereby increasing the rate of water flow through the dike. This is not a catastrophic failure mode as the rockfill will be stable and at its worst would lead to temporary suspension of mining.	Monitor seepage from downstream face for rate of seepage and for presence of sediment in seepage. Will become evident as localized intensive seepage at dike toe and can be repaired. May also see settlement in the core near the filter. Will be most likely in deepest section. Gradients across the core and cut-off in shallow water may not be high enough to cause piping.
	2c	Foundation till is possibly non-uniform with more transmissive zones and not self-filtering. It is possible that one of these zones may align with defective construction of the cut-off wall allowing high flows. Seepage would lead to erosion of the cut-off into the downstream rockfill. Seepage could also erode the foundation tills at the downstream toe or into the downstream rockfill because of the lack of filtering.	Low	Limited seepage at the toe or into the rockfill would accelerate in to a large inflow, and could lead to the undermining of the dike if no action was taken. This is a credible catastrophic mode if increased seepage is not detected in time. No particular instrumentation is needed as this failure mode will show itself as localized and increasing seepage. It could be detected by walk-over inspection by an experienced engineer or technician.	Remedial action could comprise a reverse filter and rockfill buttress depending on location of the flow and configuration of the foundation, freezing or grouting, if identified in time. In the worst case, the pit may be deliberately flooded in a controlled manner, the cut-off repaired and the pit dewatered. Build additional dike downstream increasing pumping.

Concern	Area		Failure Likelihood	Comments/Monitoring	Contingency or Corrective Action
Seepage	3a	Within the Embankment	Low	Seepage on its own is not a credible failure scenario. The downstream rockfill shell has extremely high flow through capacity. The rockfill zone is both large and pervious, so that seepage will not daylight and lead to instability. Any seepage related failures must include internal erosion.	No credible consequences. May require upgrade of the seepage collection system. May need to suspend mining activities while reducing seepage.
	3b	Within the Foundation	Medium	Defective construction of cut-off leading to transfer of unexpectedly high fraction of the reservoir head into the downstream part of the dike foundation, or leading to a piping event as described in internal erosion(2c). If this mechanism arises it should show itself during initial dewatering or very shortly thereafter.	This failure mechanism has caused embankment failures elsewhere because of straightforward pore water pressure induced instability. However it is unclear that it could cause failure of the dike because of the large width compared to the retained water head. The most likely consequence is downstream toe slumping requiring a localized stabilizing berm before the crest could be reinstated.
Structural - Slope Instability	4a	Normal Operation: Slope Failure	Low	The rockfill shoulders of the dike are wide and have high shear strength, making it a conservative design. Slope failure requires failure in the foundation and which would extend into the overlying dike. Sliding failure is considered unlikely given the low horizontal forces generated by the water and ice relative to the normal frictional force due to the weight of the dikes and the frictional angles of foundational materials. This mechanism should develop during construction or dewatering, due to the increase in load and associated pore water pressure development. Initial stages of failure should be observable as tension cracks in the dike crest. Walk-over inspection of the dike by trained inspector is an appropriate monitoring strategy in addition the instrumentation. Survey of crest face and toe should also be conducted.	A foundation failure would cause a rotational slip or sliding failure until equilibrium was reached. This mechanism would limit access along the dike until repaired. Failure through the rockfill should not necessarily compromise the water retaining function of the dike. Slope failures which reach the core may cause dam failure. Stabilizing berms can be placed at the downstream toe of the dike.
	4b	Earthquake Induced: Slope Failure	Low	Site is located in a low seismic zone. Dam consisting of massive rock zone has a low sensitivity to seismic motion.	In the event a seismic event produced cracks, construction material and equipment will be available for rapid response.
	4c	Erosion; washout, ice scour	Low	Crest – minimum 50 m section, Downstream – large quarry rock face.	Monitor – if any erosion is observed place additional mine rock
Structural – Lateral Movement	5a	Failure of Cut-off Wall	Low	Differential horizontal movement of the dike due to dewatering, water or ice loading or pit wall failure may create a breach in the cut-off wall. Ice and water forces are not credible due to the ratio of frictional forces generated by the self weight of the dike versus ice loads and water pressure. Pit wall failure unlikely based on assessments of pit wall stability. Large inflows through the breach may occur as a consequence if the cut-off wall breached. Pit would flood requiring suspension of mining activities. Potential for loss of life of workers inside dikes. Inclinometer, settlement prism and monument monitoring should be done routinely.	If the pit floods, then repairs to cut-off would be done prior to dewatering.
Subsidence	6	Foundation Soils	Low	Unexpected foundation soils consolidated during dike construction or dewatering. A significant quantity of clay would be required to generate settlement resulting in a water release event. Settlement of the core zone will be limited by dynamic compaction. Prism and monument monitoring should be done routinely.	A 2 m core settlement would be required to allow water to flow through the rockfill and over the settled cut-off. This flow would not cause failure of the rockfill shells. It would also be readily repaired by excavating rockfill above the cut-off wall and placing more till. Soil conditions will be observed during dewatering to accommodate actual conditions.

Concern	Area		Failure Likelihood	Comments/Monitoring	Contingency or Corrective Action
Premature Closure	7	Corporate Bankruptcy or Early Resource Depletion	Low	Bond is provided for this eventuality. Design of rehabilitation is the same as rehabilitation at closure of project.	Pumping will be suspended and the downstream area allowed to flood. The East Dike and Bay-Goose Dike will be monitored to meet closure requirements.
Pump and Pipeline Failure	8	Pumping from Sumps to Process Plant	Medium	Freezing protection is provided by heat tracing and insulation. Pipelines monitored pump pressures at plant and frequent site inspection.	Sump designed for expected seepage capacity. Pumping equipment designed for 1 in 25 year storm events and average freshet. Redundant lines (Minimal interruption to Process Plant operation).

Table 12.11 Risk Matrix

<div><div>Likelihood:</div><div><div></div><div></div><div></div><div></div><div></div></div><div><div></div><div></div><div></div><div></div><div></div></div><div><div></div><div></div><div></div><div></div><div></div></div></div>	Consequence :				
	HIGH		MEDIUM		LOW
	Catastrophic	Major	Significant	Minor	Insignificant
	5	4	3	2	1
Almost Certain	25 (very high risk)	20	15	10	5
Likely	20	16 (high risk)	12	8	4
Possible	15	12	9 (medium risk)	6	3
Unlikely	10	8	6	4 (low risk)	2
Rare	5	4	3	2	1 (very low risk)

Table 12.12 Risk assessment for East Dike, Bay-Goose Dike, South Camp Dike and Vault Dike

Failure Mechanism	Cause	Likelihood Rating	Effect	Consequence Rating	Controls		Overall Risk Rating
					Monitoring	Corrective Action	
Overtopping	Lake level rise because of restricted outflow (e.g., blockage of outlet from Second Portage Lake).	LOW – 2 Temporary ice jam occurring at the outlet is possible for a short duration in the spring. The cutoff wall and liner system provide adequate freeboard above normal lake level.	Water spilling over the crest. Erosion of the dike abutment and / or downstream foundation	LOW - 2 The crest is wide and comprises coarse rockfill. Significant damage to the dike is unlikely based on design.	Routine monitoring of lake levels. Outflow channels should be inspected regularly just before and during the thaw and ice break-up (freshet).	If an obstruction is present, clear blockage at outlet. Develop action plan based on conditions encountered.	4
	Lake level rise because of excessive inflow.	LOW – 2 Due to the large surface area of the lakes, a large volume of water is required to cause a significant increase in the lake elevation. The cutoff wall and liner system provide adequate freeboard above normal lake level.	Water spilling over the crest. Erosion of the dike abutment and / or downstream foundation	LOW - 2 The crest is wide and comprises coarse rockfill. Significant damage to the dike is unlikely based on design.	Routine monitoring of lake levels.	Develop action plan based on conditions encountered.	4
	Settlement of the cutoff wall system. (NOT APPLICABLE TO SOUTH CAMP DIKE OR VAULT DIKE)	MED – 3 The cutoff wall system is founded on or close to bedrock reducing potential for the foundation, and in turn the cutoff wall, to settle. Some settlement of the soil bentonite may be expected. The maximum depth of the soil bentonite cutoff wall is typically such that settlement exceeding the minimum freeboard is unlikely.	Water spilling over the crest. Erosion of the dike abutment and / or downstream foundation.	MED - 3 The crest is wide and comprises coarse rockfill. Significant damage to the dike is unlikely based on design.	Survey of cutoff wall to detect and quantify settlement. Routine monitoring of lake levels.	Till available from the mining operation could be placed above the cutoff wall if significant settlement occurred. (Note – all material over cut-off wall would need to be excavated (i.e. thermal cap, grouting platform))	9
	Settlement of the rockfill embankment over a significant width of the crest.	EAST DIKE BAY-GOOSE DIKE LOW – 2 Adequate rockfill freeboard has been provided such that settlement in excess of the freeboard is not anticipated. Settlement can only occur where lakebed soils were left underneath the rockfill embankment but the majority of the settlement is anticipated to have occurred during construction since additional fill was placed to bring to design elevation. The East Dike has had additional maintenance as it was operated as a haul road.	Potential erosion of upstream filters and cutoff for BG and ED. Potential exposure to wave action (see below in wave action section).	MEDIUM - 3 The hydraulic barrier, cutoff wall system, remains in place. Wave erosion of the cutoff system unlikely due to the presence of surrounding granular material.	Monitoring of Rockfill settlement	Rockfill available from the mining operation can be placed to raise the crest height, if settlement occurs.	6
	Settlement of the rockfill embankment over a significant width of the crest.	SOUTH CAMP DIKE VAULT DIKE LOW – 1 Existing monitoring of the dike within the foundation shows that it remains frozen throughout the year; therefore, thawing of foundation material is unlikely to happen, but in the event it does happen, it will allow settlement of the rockfill.	Potential exposure to wave action (see below in wave action section).	LOW - 2 The hydraulic barrier, liner system, remains in place. Additional water will flow towards the open pit and mining infrastructures.	Routine monitoring of the foundation's temperature.	Develop an action plan to add low hydraulic conductivity barrier if flow is not manageable.	2
	Wave Action	LOW – 2 Adequate freeboard is provided by the rockfill crest elevation. A wide rockfill crest which is erosion resistant reduces potential impact to the cut-off wall/liner.	Water spilling over the crest. Erosion of the dike abutment and / or downstream foundation	LOW - 2 Wave erosion of the cutoff wall system unlikely due to the presence of surrounding granular filter system.	Monitor wave height during storm events or periods of strong winds.	Rockfill can be placed to raise the crest height, if necessary.	4

Failure Mechanism	Cause	Likelihood Rating	Effect	Consequence Rating	Controls		Overall Risk Rating
					Monitoring	Corrective Action	
Internal Erosion (piping)	<p>Erosion of the cutoff wall.</p> <p>If a component of the cutoff wall is defective allowing high water flow through the structure. This defect could potentially erode the cutoff wall.</p> <p>(NOT APPLICABLE TO SOUTH CAMP DIKE OR VAULT DIKE)</p>	<p>MEDIUM HIGH – 4 The soil bentonite has the potential to be eroded under high hydraulic gradients.</p> <p>Although erosion of the downstream foundation soils could potentially occur in association with erosion of the cutoff wall, the width of the rockfill embankment, thickness of soils, and hydraulic head significantly reduce the likelihood of failure.</p> <p>The granular materials within the dike have been designed to be filter compatible reducing the risk for erosion.</p> <p>This mechanism is more likely to occur during dewatering or shortly thereafter.</p> <p>EAST DIKE: As the East Dike has been dewatered since 2010, the likelihood of further deterioration is less.</p> <p>BAY-GOOSE DIKE: The cement content of the cement soil bentonite and jet grout should reduce its potential for erosion.</p> <p>A layer of erodible material (e.g. silt) at the base of the cutoff wall / bedrock contact, was identified and jet grouted to reduce erosion potential. Other areas of erodible material may still exist beneath the cutoff wall.</p> <p>Two areas at Bay-Goose Dike (Sta. 30+230 to 03+350 and Sta. 30+795 to 30+850) have a higher risk for flow through the cutoff wall because the more rigid cement soil bentonite was placed over softer, more deformable soil bentonite. A gap at the interface due to differential settlement or cracking of the cement soil bentonite is possible. The zone between Sta. 30+230 and 30+350 is considered at greater risk.</p> <p>The Bay-Goose design has included a filter blanket downstream of the cutoff wall to reduce internal erosion of the cut-off wall.</p>	<p>Increased seepage, through the dike core evident as localized intensive seepage at the dike toe or beyond.</p> <p>Settlement of the cutoff wall or dike crest, most likely in deep water sections with higher gradients.</p>	<p>MEDIUM HIGH - 4 This is not likely to be a catastrophic failure mode as the filter material and rockfill embankments of the dike will remain stable.</p> <p>Additional seepage would come into the pit as the seepage collection system is not designed for such inflow.</p> <p>Could lead to the undermining of the dike if no action was taken and significant erosion of the foundation soils on the downstream side of the dike occurred. Loss of containment may result.</p> <p>Potential economic loss due to cessation/suspension of mining.</p> <p>BAY-GOOSE DIKE: High seepage leading to erosion is more likely to occur during dewatering when the pit has not been developed. The high seepage rate would delay the start of mining, with financial implication. With no pit development, minimal health and safety risk to personnel are expected.</p>	<p>Monitor seepage flow for rate and volume, and for presence of sediment in seepage (turbidity).</p> <p>Monitor piezometric and thermistor data for signs of increased flow through the cutoff wall and change in piezometric pressures.</p> <p>Monitor dike crest for signs of sinkholes or settlement. Increased seepage, evident as localized flow at the dike toe or beyond, in particular in topographic lows along the dike alignment</p>	<p>Based on conditions encountered, develop an action plan. This could include grouting, compaction grouting, and/or the installation of a downstream filter blanket.</p>	16
	<p>BAY-GOOSE DIKE ONLY:</p> <p>Erosion of the foundation (primarily applies where initial excavation was terminated above bedrock).</p> <p>Seepage flows through / between the jet grout columns, along sand and gravel zones within the till, and through potential erodible material. The foundation tills may be eroded into the downstream rockfill or through fractures in the bedrock.</p>	<p>MEDIUM-4 The potential for gaps within the jet grout columns exist and allow for flow. The cement content of the jet grout columns should reduce the columns potential for erosion.</p> <p>Till is non-uniform with discontinuous layers / lenses of sand and gravel, and erodible material (i.e. silt layers) that may not be self-filtering.</p> <p>For erosion to occur, the seepage through or between the jet grout columns would need to connect with a permeable zone (e.g. zone of sand and gravel) which in turn needs to be in close proximity to a zone of erodible material that can be removed and the seepage forces need to be sufficient to cause the erosion.</p> <p>If this mechanism arises, it should show itself during initial dewatering or very shortly thereafter. May result in slower lake drawdown.</p>	<p>Increased seepage, evident as localized intensive seepage at the dike toe or beyond.</p>	<p>MEDIUM HIGH-4 This is a significant failure mode if increased seepage is not detected in time.</p> <p>Undermining of the dike could lead to overall failure of the structure and flooding within the open pit resulting in cessation of mining and economic loss.</p> <p>Could lead to the undermining of the dike if no action was taken and significant erosion of the foundation soils on the downstream side of the dike occurred. Loss of containment may result.</p>	<p>Monitor seepage flow for rate and volume, and for presence of sediment.</p> <p>Monitor piezometric and thermistor data for signs of increased flow through the foundation and change in piezometric pressures.</p> <p>Monitor dike crest for signs of sinkholes, settlement or slope instability.</p> <p>Monitor inclinometers.</p>	<p>Remedial action could comprise grouting, a reverse filter on downstream and rockfill buttress, depending on location of the flow and configuration of the foundation.</p> <p>In the extreme, the dewatered areas may be deliberately flooded in a controlled manner, the cutoff wall repaired, and then dewatered.</p>	16

Failure Mechanism	Cause	Likelihood Rating	Effect	Consequence Rating	Controls		Overall Risk Rating
					Monitoring	Corrective Action	
	<p>Interconnected open fractures in the bedrock that permit foundation material or cutoff wall material to be lost.</p> <p>(NOT APPLICABLE TO SOUTH CAMP DIKE OR VAULT DIKE)_</p>	<p>MEDIUM – 3 High hydraulic gradients exist at the base of the cutoff wall and potentially within the bedrock, especially along deeper areas of the dike.</p> <p>Grouting was conducted to reduce the permeability of the bedrock and contact zone. There is, however, a potential that bedrock fractures were initially infilled with silt prior grouting. This silt may erode once a hydraulic gradient is imposed and thereby form a pathway for either foundation soil or soil bentonite cutoff wall material to erode.</p> <p>Large setback of dike from pit crest in some parts increases the seepage path thereby reducing the hydraulic gradient imposed.</p> <p>BAY-GOOSE DIKE The cement content of the cement soil bentonite and jet grout reduces potential erodability and was used in the deepest portions of the dike.</p>	Increased seepage, initially evident downstream of the dike or within the pit wall.	<p>HIGH - 5 This is a catastrophic failure mode if increased seepage is not detected in time.</p> <p>Could lead to the undermining of the dike if no action was taken and significant erosion of the foundation soils on the downstream side of the dike occurred. Loss of containment may result.</p> <p>This could lead to flooding within the open pit of the mine and a cessation of mining.</p>	<p>Monitor seepage flow for rate and volume, and for presence of sediment (turbidity).</p> <p>Monitor piezometric and thermistor data for signs of increased flow through the foundation and change in piezometric pressures.</p> <p>Monitor dike crest for signs of sinkholes, settlement or slope instability.</p> <p>Monitor inclinometers.</p>	<p>Grouting of the fractured bedrock. Deep bedrock grouting. In shallower areas, grouting or freezing.</p> <p>Installation of downstream filter blanket, stability berm.</p>	15
	<p>Erosion along instrumentation installed within the cutoff wall system.</p> <p>(NOT APPLICABLE TO SOUTH CAMP DIKE OR VAULT DIKE)</p>	<p>LOW – 1 Preferential flow paths may exist along the edge of vertical instrumentation conduits (thermistors, inclinometers, grout casings) due to inadequate sealing.</p> <p>Preferential seepage path of precipitation and melt water are potential sources of water which can flow down along the edge of the conduits. Erosion caused by precipitation and melt water is very unlikely due to the small volume of water.</p> <p>If this mechanism arises, it should show itself during initial dewatering or very shortly thereafter.</p>	Gradual erosion of the SOIL BENTONITE material adjacent to the instrumentation.	<p>LOW – 2 This is not a catastrophic failure mode as the filter material and rockfill embankments of the dike will remain stable.</p>	<p>Monitor seepage flow for rate and volume, and for presence of sediment.</p> <p>Monitor piezometric and thermistor data for signs of increased flow through the foundation and change in piezometric pressures.</p> <p>Monitor dike crest for signs of sinkholes, settlement or slope instability.</p>	Replacement of the instrumentation and sealing of the annular space.	2
High Seepage rates with no internal erosion	<p>Through the Dike Section (including bedrock contact) :</p> <p>EAST DIKE DIKE: Increase in hydraulic conductivity of the dike's cutoff wall system resulting in high seepage flow through the structure.</p> <p>BAY-GOOSE DIKE: Increase in hydraulic conductivity of the dike's cutoff wall system (cutoff wall and jet grout columns) resulting in high seepage flow through the structure.</p> <p>SOUTH CAMP DIKE AND VAULT DIKE: Punctured or torn liner which will likely increase flow through the structure.</p>	<p>MEDIUM – HIGH– 4 This seepage on its own is not a failure scenario. Seepage-related failures must include internal erosion (see above).</p> <p>Interface between different material exist and could lead to seepage with preferential paths (bedrock contact and for Bay-Goose dike: cement soil bentonite over soil bentonite material and potential gaps between jet grouting columns)</p> <p>If this mechanism arises it should show itself during initial dewatering or very shortly thereafter.</p>	Increased seepage water handling.	<p>MEDIUM -3 May require upgrade of the seepage collection system. May need to suspend mining activities while reducing seepage.</p> <p>The downstream rockfill shell is both large and pervious and has an extremely high flow through capacity.</p> <p>EAST DIKE AND BAY-GOOSE DIKE: The large filter zone combination of core backfill and coarse filter are filter compatible and would maintain the structural integrity of the dike.</p>	<p>Monitor seepage flow for rate and volume, and for presence of sediment (turbidity).</p>	<p>Upgrade seepage collection system and increase pump capacity.</p> <p>Investigate and delineate high permeability zone.</p> <p>Installation of downstream filter blanket, stability berm</p>	12

Failure Mechanism	Cause	Likelihood Rating	Effect	Consequence Rating	Controls		Overall Risk Rating
					Monitoring	Corrective Action	
	Through the bedrock: Fractures in the bedrock results in increased seepage into the pit.	<p>MEDIUM - 3 Seepage on its own is not a failure scenario.</p> <p><u>EAST DIKE AND BAY-GOOSE DIKE:</u> Extensive bedrock grouting within the dike foundation reduces the likelihood for seepage at shallow depths.</p> <p>If this mechanism arises it should show itself as the pit advances with depth.</p> <p><u>SOUTH CAMP DIKE AND VAULT DIKE:</u> Existing monitoring show that foundation material and bedrock beneath the structure is frozen throughout the year.</p>	Increased seepage through the pit wall.	<p>LOW – 1</p> <p>No significant consequences for the dike itself. May require upgrade of the seepage collection system.</p> <p>May result in increased inflows into the pit, and the potential cessation of mining with resulting financial loss.</p>	Monitor seepage flow for rate and volume, and for presence of sediment (turbidity).	<p>Installation of dewatering / depressurization wells to remove water before it reaches the pit.</p> <p>Deep bedrock grouting. In shallower areas, grouting or freezing.</p>	3
Slope Instability (rotational or slip or sliding failure on the upstream and downstream side)	Failure through the dike and/or foundation. Concentrated seepage and elevated pore pressures may result in weakening of the foundation.	<p>LOW -2 The rockfill embankments have high shear strength. For slope failure to be a concern, it requires failure in the foundation which would then extend into the dike.</p> <p>Failure through the rockfill embankments will not necessarily compromise the water retaining element of the dike.</p> <p>Sliding failure is considered unlikely given the low horizontal forces generated by water and ice forces relative to the normal frictional force due to the weight of the dike and the friction angles of foundation materials.</p> <p>Limited available information on soil properties for dike stability analysis.</p> <p>This mechanism should develop during construction or dewatering, due to increase loads and associated pore water pressure.</p>	<p>Sloughing of the face</p> <p>Large seepage / inflow only if instability resulted in loss of the cutoff wall system.</p>	<p>HIGH - 5 If failure were to occur it is likely to be through the lakebed soils affecting the rockfill embankments</p> <p>Failure which reaches the core may cause overall failure of the structure, leading to flooding within the open pit of the mine and a cessation of mining. Potential for loss of life for workers downstream of the dike.</p> <p>Limited access along the dike until repaired.</p>	<p>Initial stages of failure should be observable as tension cracks in the dike crest.</p> <p>Walk-over inspection of the dike by a trained inspector.</p> <p>Monitoring for bulging of dike toe.</p> <p>Survey of the dike crest, face, and toe.</p> <p>Slope inclinometer monitoring of the cutoff wall.</p> <p>Monitor piezometric and thermistor data for signs of increased flow through the foundation and change in piezometric pressures.</p>	<p>Stabilizing berms can be placed upstream and/or downstream of the dike.</p> <p>Installation of downstream filter blanket, buttress</p>	10
	Excessive Vibration Due to blasting within the pit; or due to the occurrence of an extreme earthquake.	<p>LOW -2 The extreme earthquake loading for this site is of low magnitude.</p> <p>The East Dike setback of dike from pit crest reduces the vibration caused by blasting.</p> <p>The Bay-Goose Dike setback of dike from pit crest reduces the vibration caused by blasting.</p> <p>Rockfill structures are designed to resist against wave created by earthquake.</p> <p><u>EAST DIKE AND BAY-GOOSE DIKE:</u></p> <p>Dynamic compaction of the core during construction likely subjected the rockfill shells to accelerations equivalent to the expected earthquake loading and blasting vibration.</p> <p>Excessive vibration is unlikely to cause failure through the rockfill. The vibration may result in increased pore pressures within the foundation soils, weakening the foundation. This may cause failure in the rockfill but is unlikely to extend into the cutoff wall system.</p>	<p>Settlement of the dike could occur in the event of large vibrations.</p> <p>Increase in displacement and/or displacement rate of dike toe</p> <p>Sloughing of the face.</p> <p>Large seepage / inflow only if instability resulted in loss of the cutoff wall system.</p>	<p>MEDIUM - 4 If failure were to occur it is likely to be through the lakebed soils affecting the rockfill shell.</p> <p>Limited access along the dike until repaired.</p> <p>Although unlikely, failure which reaches the core / liner may cause overall failure of the structure, leading to flooding within the open pit of the mine and a cessation of mining. Potential for loss of life for workers downstream of the dikes.</p>	<p>Survey of the dike crest, face, and toe.</p> <p>Dike inspection following larger than anticipated vibrations and earthquakes.</p> <p>Blast vibration monitoring</p> <p>Monitoring for bulging of dike toe.</p> <p>Look for cracks along the dike crest.</p>	<p>In the event the vibration produced cracks, monitor and assess the situation, and develop a remediation plan.</p>	8

Failure Mechanism	Cause	Likelihood Rating	Effect	Consequence Rating	Controls		Overall Risk Rating
					Monitoring	Corrective Action	
	Pit wall instability that extends towards the dike and causes instability of the dike (NOT APPLICABLE TO SOUTH CAMP DIKE AND VAULT DIKE)	EAST DIKE: LOW -2 BAY-GOOSE DIKE: MEDIUM -3 Pit wall failure unlikely based on assessments of pit wall stability and setback. East Dike setback is greater than Bay-Goose Dike setback; therefore, it is viewed that the likelihood rating would be different for each structure. The respect of the setback established from pit crest. East Dike has a large setback from the pit crest, and therefore a low probability that pit instability will affect the dike. The Bay-Goose Dike setback from the pit crest is less than East Dike, and therefore has a higher probability that pit instability will affect the dike.	Increase in displacement and/or displacement rate of dike toe. Large seepage / inflow only if instability resulted in loss of the cutoff wall system.	HIGH-5 If the instability impacted the cutoff wall system of the dike, then failure of the entire structure could result. Cessation /suspension of mining operations would have already occurred due to significant pit wall instability or failure.	Slope inclinometer monitoring of the cutoff wall. Survey of the dike crest and visual inspection. Pit wall stability monitoring. Visual observation related to cracks along the dike crest.	Depressurization of pit walls. Draining of lakebed soils between pit crest and dike and/or removal of these materials. Cut back slopes of pit wall and soils to unload the crest. Adjustment of mine plan, if necessary. Develop action plan to stabilize the instable pit wall area.	EAST DIKE 10
		BAY-GOOSE DIKE 15					
Failure of cutoff wall	BAY-GOOSE DIKE ONLY: Excessive vibration from overblasting or earthquake above design could potentially damage the cement soil bentonite and/or jet grout columns resulting in cracks or fissures.	LOW-2 The vibration may result in increased pore pressures within the foundation soils, weakening the foundation. This may cause failure in the rockfill but is unlikely to extend into the cutoff wall system. Refer to internal erosion as a failure mechanism if cracks lead to internal erosion. It is anticipated that the soil bentonite material would deform such that cracks would not be produced.	Increased seepage water handling.	MEDIUM HIGH-4 May require upgrade of the seepage collection system. May need to suspend mining activities while reducing seepage. The cement content within these portions of the wall should reduce the erodability of the wall and therefore protect the integrity of the dike, even though seepage rates would increase.	Monitor seepage flow for rate and volume, and for presence of sediment (turbidity). Blast vibration monitoring on the dikes. Monitoring inclinometers within the cutoff wall.	Upgrade seepage collection system and increase pump capacity. Develop action plan related to potential grouting in cutoff wall fractured zone.	8
Failure of the liner system	SOUTH CAMP DIKE AND VAULT DIKE ONLY: Settlement of the foundation material	LOW-2 In the unlikely event of thawing of the foundation material beneath the liner, settlement of the dike's foundation material will increase tension in liner, and potentially tear the liner	Increased seepage water handling.	LOW-2 No significant consequences for the dike itself. May require upgrade of the seepage collection system.	Monitor seepage flow for rate and volume. Monitor thermistor data for signs of increased flow through the foundation.	Upgrade seepage collection system and increase pump capacity. Installation of downstream filter blanket, buttress Develop mitigation plan to decrease seepage through the structure	4
Premature Closure	Corporate Bankruptcy or Early Resource Depletion	LOW-2	Pumping will be suspended allowing the downstream area to flood (Note – long term closure plan is for flooding to occur). No or limited monitoring of dikes.	LOW-2 Bond is provided for this eventuality. Design of rehabilitation is the same as rehabilitation at closure of project. Before mining operations could resume any water downstream would need to be pumped out and assessment of performance would need to be done.	Environmental monitoring to ensure closure requirements are met.		4

SECTION 13 • REFERENCES

Table 13.1 References

No.	Title	Document Centre Reference
1	AEM 2012. South Camp Dike Construction Summary Report. March 2012.	
2	AEM 2013. Construction Summary Report Vault Dike. July 29, 2013. Ver. 1.	
3	AMEC (AMEC Earth and Environmental) 2003. Baseline Hydrology Study. December 2003 with January 2004 errata sheets.	
4	AMEC 2005a. Meadowbank Gold Project Hydrologic Monitoring 2004 Draft Data Report. February.	
5	AMEC 2005b. Meadowbank Gold Project Feasibility Study Report. June.	
6	CDA (Canadian Dam Association) 2007. Dam Safety Guidelines.	
7	Golder (Golder Associates Ltd.) 2002. Factual Report on Geotechnical Drilling, Hydrogeological and Geophysical Investigations, Meadowbank Project, Nunavut. July 12. Doc. No. 116	
8	Golder 2003. Summary Report on Spring 2003 Field Geotechnical Studies, Meadowbank Project, Nunavut. September 8. Doc. No. 208	
9	Golder 2007a. Final Report Detailed Design of Dewatering Dikes Meadowbank Gold Project. Final Report. March 13. Doc. No. 342 Ver. 0.	
10	Golder 2007b. Report Addendum Detailed Design of Dewatering Dikes Meadowbank Gold Project. July 12. Doc. No. 492 Ver. 0.	
11	Golder 2008a. 2007 Till Core Material Investigation and Laboratory Testing, Meadowbank Gold Project. Technical Memo. January 25. Doc. No. 538 Ver. 0.	
12	Golder 2008b. East Dike Design Meadowbank Gold Project. Report. October 31 Doc. No. 572 Ver. 0.	
13	Golder 2009a. Bay-Goose Dike and South Camp Dike Designs. Meadowbank Gold Project, Nunavut. February 2. Doc. No. 802 Ver. 0.	
14	Golder 2009b. Meadowbank East Dike Grouting Response Plan - Completed Works. July 14. Doc. No. 916 Ver. 0.	
15	Golder 2009c. 2009 Annual Geotechnical Inspection - Meadowbank Gold Project. November 30. Doc. No. 969 Ver. 0.	
16	Golder 2009d. East Dike Additional Details for Work Carried Out Between Stations 60+452 and 60+500. Meadowbank Gold Project. November, 2009. Doc. No. 961 Ver. 0.	
17	Golder 2009e. East Dike Construction As-Built Report Meadowbank Gold Project, Nunavut. December 15. Doc. No. 900 Ver. 0 Rev. 1.	
18	Golder 2009f. West Channel Dike Construction As-Built Report Meadowbank Gold Project, Nunavut. December 16. Doc. No. 980 Ver. 0.	
19	Golder 2010a. East Dike Sinkhole Investigation Program, October-November 2009, Meadowbank Gold Project. March 5 2010. Doc. No. 986 Ver. 0.	
20	Golder 2010. Draft of South Camp Construction As-built report. No. 1037 Ver. B. Meadowbank Gold Project. 22 April 2010	
21	Golder 2010b. East Dike CPT Investigation - Meadowbank Gold Project, Nunavut. July 22. Doc. No. 953 Ver. 0.	
22	Golder 2010c. 2010 Annual Geotechnical Inspection. Meadowbank Gold Project, Nunavut. December 3. Doc. No. 1216 Ver. 0.	

No.	Title	Document Centre Reference
23	Golder 2011a. Draft of 2011 Annual Geotechnical Inspection. Meadowbank Gold Project, Nunavut. November 21 2011. Doc. No. 1305 Ver. B.	
24	Golder 2013. Bay Goose Dike Construction As-Built Report Meadowbank Gold Project. Meadowbank Gold Project, Nunavut. April 2013. Doc. No. 1328 Ver. 0.	
25	ICOLD (International Congress of Large Dams) 1998. Dam Failures and Statistical Analysis. Bulletin 99.	
26	MAC (Mining Association of Canada) 2005. Developing an Operation, Maintenance and Surveillance Manual for Tailings and Water Management Facilities.	
27	MMC (Meadowbank Mining Corporation) 2008. Emergency Response Plan. October. Rev. 1	
28	SNC 2013a. Detailed Engineering of Vault Dike. Meadowbank Gold Project, Nunavut. January 14. Doc. No. 610548-2020-4GER-0001 Ver. 0.	
29	SNC 2013b. Construction of Vault Dike – Technical Specifications. Meadowbank Gold Project, Nunavut. February 1. Doc. No. 610548-2020-4GEF-0001 Ver. 0.	

Appendix A

Inspection Forms

DETAILED FIELD INSPECTION FORM A
DEWATERING / DIKE INSPECTION REPORT
MEADOWBANK GOLD PROJECT



All parts of this inspection form should be completed. Adverse conditions should be described and location stated. Additional information and relevant photographs should be attached.

Inspecting Officer: _____ Report No.: BG-IR- _____ Inspection Date: _____

DAM/DIKE INFORMATION:

Dam ☐ Dike ☒ _____ Crest Elevation: _____ Third Portage Lake _____
Goose Pit _____

A) CREST / BERM / ROAD SURFACE

	NO	YES
cracking	<input type="checkbox"/>	<input type="checkbox"/>
settlement	<input type="checkbox"/>	<input type="checkbox"/>
erosion	<input type="checkbox"/>	<input type="checkbox"/>
other movement	<input type="checkbox"/>	<input type="checkbox"/>

B) DOWNSTREAM SLOPE AND TOE AREA

	NO	YES
erosion	<input type="checkbox"/>	<input type="checkbox"/>
settlement	<input type="checkbox"/>	<input type="checkbox"/>
Bulging	<input type="checkbox"/>	<input type="checkbox"/>
sloughing	<input type="checkbox"/>	<input type="checkbox"/>
slope protection	<input type="checkbox"/>	<input type="checkbox"/>

Seepage ☐ none ☐ location 1:
rate: ☐ damp ☐ trickle ☐ steady _____ (L/s)
clarity: ☐ clear ☐ muddy _____
sample taken: ☐ yes ☐ no
location 2:
rate: ☐ damp ☐ trickle ☐ steady _____ (L/s)
clarity: ☐ clear ☐ muddy _____
sample taken: ☐ yes ☐ no
type: _____
Sand boils ☐ none ☐ location(s) _____

DETAILED FIELD INSPECTION FORM A
DEWATERING / DIKE INSPECTION REPORT
MEADOWBANK GOLD PROJECT



C) UPSTREAMSLOPE

erosion	<input type="checkbox"/> NO	<input type="checkbox"/> YES	<input type="checkbox"/> wave induced <input type="checkbox"/> surface runoff
		location(s):	
		degree	<input type="checkbox"/> minor <input type="checkbox"/> moderate <input type="checkbox"/> severe
geomembrane	<input type="checkbox"/> N/A	<input type="checkbox"/>	
settlement	<input type="checkbox"/>	<input type="checkbox"/>	
bulging	<input type="checkbox"/>	<input type="checkbox"/>	
sloughing	<input type="checkbox"/>	<input type="checkbox"/>	
slope protection	<input type="checkbox"/>	<input type="checkbox"/>	
sinkholes	<input type="checkbox"/>	<input type="checkbox"/>	
tailings surface	<input type="checkbox"/> N/A	<input type="checkbox"/>	

DAM/DIKE INSTRUMENTATION: *(plot any newly installed instrumentation on relevant plans and cross-sections)*

		<u>Operational</u>	<u>Damaged</u>	<u>Measurement Taken</u>
<input type="checkbox"/> Inclinometers	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Bi-monthly
<input type="checkbox"/> piezometers	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Daily 3hrs interval
<input type="checkbox"/> Thermistors	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Daily 3hrs interval
<input type="checkbox"/> Survey Prisms	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Bi-monthly
<input type="checkbox"/> Thermistors (manual)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Daily and weekly

DETAILED FIELD INSPECTION FORM A
DEWATERING / DIKE INSPECTION REPORT
MEADOWBANK GOLD PROJECT



COMMENTS AND RECOMMENDATIONS:

☐ Action Required: ☐ none ☒ further monitoring ☐ immediate remediation
☐ Plan or Sketch Attached
☒ Photographs (number) See Appendix

Review Officer: _____ Review Agency: _____ Date Reviewed: _____
(DD/MM/YR)

REVIEW COMMENTS: ☒ none

DAILY REPORT DIKE AND GEOTECHNICAL ENGINEERING AGNICO-EAGLE MINES MEADOWBANK PROJECT			
Date: _____		Technician / Engineer: _____	
Weather : Sunny <input type="checkbox"/> Overcast <input type="checkbox"/> Rain <input type="checkbox"/> Snow <input type="checkbox"/> Wind <input type="checkbox"/>		Comments: _____	
Health and Safety: Concern / Incident Y <input type="checkbox"/> N <input type="checkbox"/>			
Comments: _____			
Dewatering Dikes			
<u>BayGoose Dike</u>		Field Visit	Y <input type="checkbox"/> N <input type="checkbox"/> Comment / Observation: _____
Instrumentation	Piezometers (Auto.) <input type="checkbox"/>	Photos	Y <input type="checkbox"/> N <input type="checkbox"/>
	<input type="checkbox"/>		
	Thermistors (Auto.) <input type="checkbox"/>		
	Thermistors (4) (Manual) <input type="checkbox"/>		
	Inclinometer <input type="checkbox"/>	Work Activity	Y <input type="checkbox"/> N <input type="checkbox"/> Description: _____
	Seepage <input type="checkbox"/>		
	USB key (DL9) <input type="checkbox"/>		
<u>East Dike</u>		Field Visit	Y <input type="checkbox"/> N <input type="checkbox"/> Comment / Observation: _____
Instrumentation	Piezometers (Auto.) <input type="checkbox"/>	Photos	Y <input type="checkbox"/> N <input type="checkbox"/>
	<input type="checkbox"/>		
	Thermistors (Auto.) <input type="checkbox"/>		
	Thermistors (Manual) <input type="checkbox"/>	Work Activity	Y <input type="checkbox"/> N <input type="checkbox"/> Description: _____
	Inclinometer <input type="checkbox"/>		
	Survey Prisms <input type="checkbox"/>		
<u>South Camp Dike</u>		Field Visit	Y <input type="checkbox"/> N <input type="checkbox"/> Comment / Observation: _____
Instrumentation	Thermistor (Manual) <input type="checkbox"/>	Photos	Y <input type="checkbox"/> N <input type="checkbox"/>
	<input type="checkbox"/>		
		Work Activity	Y <input type="checkbox"/> N <input type="checkbox"/> Description: _____
<u>Vault Dike</u>		Field Visit	Y <input type="checkbox"/> N <input type="checkbox"/> Comment / Observation: _____
Instrumentation	Thermistors (Manual) <input type="checkbox"/>	Photos	Y <input type="checkbox"/> N <input type="checkbox"/>
	<input type="checkbox"/>		
		Work Activity	Y <input type="checkbox"/> N <input type="checkbox"/> Description: _____
	Vault Lake : Flowmeter <input type="checkbox"/>		
Instrumentation	Piezo. Vpond 11 (Manual) <input type="checkbox"/>		
	<input type="checkbox"/>		
Tailings Facilities System			
<u>Stormwater Dike</u>		Field Visit	Y <input type="checkbox"/> N <input type="checkbox"/> Comment / Observation: _____
		Photos	Y <input type="checkbox"/> N <input type="checkbox"/>
		Work Activity	Y <input type="checkbox"/> N <input type="checkbox"/> Description: _____
<u>Saddle Dam 1</u>		Field Visit	Y <input type="checkbox"/> N <input type="checkbox"/> Comment / Observation: _____
		Photos	Y <input type="checkbox"/> N <input type="checkbox"/>
Instrumentation	Thermistors (Manual) <input type="checkbox"/>		
	<input type="checkbox"/>	Work Activity	Y <input type="checkbox"/> N <input type="checkbox"/> Description: _____
<u>Saddle Dam 2</u>		Field Visit	Y <input type="checkbox"/> N <input type="checkbox"/> Comment / Observation: _____
		Photos	Y <input type="checkbox"/> N <input type="checkbox"/>
Instrumentation	Thermistors (Manual) <input type="checkbox"/>		
	<input type="checkbox"/>	Work Activity	Y <input type="checkbox"/> N <input type="checkbox"/> Description: _____
<u>Coffer Dam - Central Dike</u>		Field Visit	Y <input type="checkbox"/> N <input type="checkbox"/> Comment / Observation: _____
Instrumentation	Piezo. Vpond 8 (Manual) <input type="checkbox"/>	Photos	Y <input type="checkbox"/> N <input type="checkbox"/>
	Piezometers (Manual) <input type="checkbox"/>		
	Thermistor (Manual) <input type="checkbox"/>	Work Activity	Y <input type="checkbox"/> N <input type="checkbox"/> Description: _____
<u>OTHER</u>		Work Activity	Y <input type="checkbox"/> N <input type="checkbox"/> Description: _____
	Reclaim Barge : Flowmeter <input type="checkbox"/>		
Ground Control Inspection - Open Pit			
Review of Ground Control I Y <input type="checkbox"/> N <input type="checkbox"/> Pit Visit Y <input type="checkbox"/> N <input type="checkbox"/> Comment/Observations: _____			
Items to Review (num.): _____			
Items Follow Up in Ground Control Register (after visit) Y <input type="checkbox"/> N <input type="checkbox"/>			

Appendix B

Dike Failure Scenario Appendices from the ERP

Dike Failure Scenarios

1. Dewatering Dikes
 2. Central Dike (removed)
 3. Saddle Dams (removed)
 4. Storm water Dike (removed)
-

Appendix 1

Dewatering Dikes

Dewatering Dike System

The Dewatering Dike System includes the East Dike, Bay Goose Dike, South Camp Dike and Vault Dike as shown on the general mine site plan provided at the beginning of this document. The dike construction for East Dike and Bay Goose Dike involved the dumping of rockfill into water to create the shells of the dikes, excavation through rockfill and lakebed soils to bedrock, placement of granular filter and core materials, dynamic compaction, construction of the cut off wall using slurry supported trench techniques and grouting of the bedrock and contact between the cut off wall and bedrock using cementitious grout. South Camp Dike and Vault Dike both include a bituminous liner and a key trench cut-off to make the structure impermeable. East Dike and Bay Goose Dike have crest widths in excess of 50 m and are not used by haul trucks during normal mine operation. South Camp Dike and Vault Dike have crest widths in excess of 25 m and may be used as haul roads during normal mine operation.

East Dike and Bay Goose Dike are considered high consequence structures, based on Canadian Dam Association (CDA, 2007) Dam Safety Guidelines. South Camp Dike is considered to be a significant consequence structure, based on Canadian Dam Association (CDA, 2007) Dam Safety Guidelines. Vault Dike is considered to be a low consequence structure, based on Canadian Dam Association (CDA, 2007) Dam Safety Guidelines. The dikes are relatively low, wide structures that exceed the minimum design criteria factors-of-safety (FoS) for stability for pre-drawdown conditions, operation conditions with maximum head difference across the dikes, pseudo-static earthquake conditions, and post closure conditions. Consequently, the probability of dike failure is considered to be low provided that the dikes are constructed according to the design. Mitigation against failure of the dikes includes a quality control and quality assurance program during construction, and an ongoing program of dike surveillance and monitoring during operations, as specified in the design.

For information on the consequences and monitoring/action for the various embankment failure modes possible at the Dewatering Dikes see Table 1.1 below.

East Dike

The East Dike was constructed in 2008, with foundation grouting continuing into early 2009. The East Dike has a crest length of 800 m, including abutments, and was constructed in water with a maximum water depth to bedrock at the cut off of 7.2 m. The crest of the East Dike is at elevation 137.1 m and the average lake level along the dike is 133.1 m. The main components of the East Dike include a rockfill shell, a granular core with downstream filter zone, a soil-bentonite cut-off wall through the densified granular core zone to the underlying foundations, and a grout curtain from the base of the cut-off wall into the underlying bedrock.

During operations, the East Dike separates the eastern portion of Second Portage Lake from the Portage Pit and the Tailings Storage Facility behind the Central Dike. Following closure, the East Dike will remain as a permanent structure that will separate Third Portage Lake (El. 134.1 m) from Second Portage Lake (El. 133.1 m) and maintain the existing water elevation difference of 1 metre.

The East Dike is approximately 800 m in length through an average water depth of approximately 2.3 metres, and a maximum water depth to bedrock of about 7.2 m. Crest width is approximately 55 metres. Minimum setback from the Portage Pit (distance between dike toe and pit crest) is greater than 170 metres.

Bay Goose Dike

The Bay Goose Dike together with the South Camp Dike isolates the Bay-Goose Pit from Third Portage Lake. The Bay Goose Dike acts as a permanent structure to allow mining of the Goose Pit and the southern portion of Portage Pit. The main components of the Bay Goose Dike include a rockfill shell, a granular core with downstream filter zone, a soil-bentonite and cement-soil-bentonite cut-off wall through the densified granular core zone to the underlying foundations, a jet grouted wall between the base of the cut-off wall and bedrock where the cutoff wall was not constructed on bedrock, and a grout curtain from the base of the cut-off wall or jet grouted wall into the underlying bedrock.

The Bay Goose Dike is approximately 2,200 m in length, and was constructed in water depths less than 9 metres at the cut off. Crest width varies between approximately 85 and 100 m. Minimum design setback from the Portage and Goose Pit is 70 metres.

South Camp Dike

The South Camp Dike covers a narrow channel within Third Portage Lake and in conjunction with the Bay Goose Dike isolates the Bay Goose Pit from Third Portage Lake.

The South Camp Dike is located south of the plant site area and is used to connect the mainland to South Camp Island. It covers a narrow channel, approximately 60 m in width, where water depths were between 0.5 and 1 m.

The South Camp Dike was primarily constructed between April and June of 2009, prior to ice breakup. During the winter of 2009-2010 additional thermal capping material and rockfill for the haul road was added to the dike. The South Camp Dike has a broad rockfill shell with a bituminous geomembrane liner installed on the upstream side of the shell. The liner was founded on native frozen (permafrost) till material, in a trench approximately 3 to 5 m below the lakebed surface. Compacted granular material mixed with bentonite was placed above the toe of the liner. The haul road is located on the downstream side of the dike. The South Camp Dike is approximately 85 m in length through water depths between 0.5 and 1m. Crest width is approximately 25 metres.

Vault Dike

The construction of the Vault Dike at Meadowbank was conducted from February 2013 to March 2013. Vault Dike is located across a shallow creek which connects Wally Lake and Vault Lake, at the Vault Pit area approximately 8 km north of the main Meadowbank site. Vault Dike is essential to allow the dewatering of Vault Lake and to isolate Vault Pit from Wally Lake during mining activities.

Vault Dike is designed and constructed as a zoned rockfill dam with filter zones, an impervious upstream liner consisting of a bituminous membrane, and an upstream key trench made of aggregate mixed with bentonite. The filter zones minimize seepage and internal erosion and facilitate seepage collection. Vault Dike includes a key trench at the base of the upstream side filled with a 0-25 mm fill amended with bentonite surrounding the liner. Coarse and fine filter material was placed on the upstream slope as geomembrane bedding. The bulk part of the dike consists of coarse rockfill material. The embankment crest is at El. 142.4 m and the upstream toe is at approximately El. 139.4 m. The downstream toe is at approximately El. 139.6 m and the bottom of the key trench ranges from El. 135.6m to El. 142.3m, with an average height of El. 137.0m. The upstream and downstream fill

slopes of the dam are 1.5H: 1V. The Vault Dike is approximately 275 m in length through a maximum water depth of 1 m. The crest width is approximately 25 metres.

Table 1.1: Meadowbank Dewatering Dikes Summary of Consequences and Proposed Monitoring/Action for Rare Events Based on Water Retaining Embankment Failure Modes Identified in ICOLD Study (1995)

Failure Mode	Scenario	Consequence	Monitoring/Action
Overtopping	(1) Lake level rise because of restricted outflow from Third Portage, Second Portage Lake or Wally Lake (excessive inflow is a far less likely scenario).	Water spilling over the crest. The crest is wide and comprises coarse rockfill. Significant damage to the dike is not credible, based on performance of other rockfill structures subjected to overtopping or flow through events. Mining operations might need to be suspended, but there will be considerable warning time given the design freeboard and the storage volume within the lakes.	Lake levels should be part of safety information provided to mine management. Outflow channels should be inspected weekly during thaw, open water season, and during ice break-up. If overtopping is likely, a temporary spillway could be constructed and armoured to control and localize flow at shallow dike sections.
	(2) Dam crest settles more than 2m over a distance of (say) 50m or so. This scenario requires extensive loss of support in the foundation since the rockfill of the dikes is essentially not settlement prone itself. For foundation settlement of this magnitude to occur, a piping event must develop and which in itself might be a failure mode. Or, there would have to be an unexpected layer of compressible soil in the foundation.	Same as (1).	The situation envisaged in this scenario should develop slowly with crest settlement evident at least several weeks before a run-away event develops. Easily observed cracks should be evident. Monitoring of crest settlement is appropriate, and is included in the design. Rockfill and till available from the mining operation can be placed to raise the dike crest.
Internal Erosion	(1) Dike Section: Cut off wall, cut off key trench or bituminous liner is defective, allowing high water flow across the wall. This defect occurs at a deep water location where the core backfill and filters are segregated and permeable; the combination allows erosion of the cut off wall and increasing seepage.	The cut off wall will develop a progressively increasing void ratio, thereby increasing the rate of water flow through the dike. This is not a catastrophic failure mode as the rockfill shoulders of the dike will be stable, and at its worst, would lead to temporary suspension of mining.	Monitor seepage from downstream face for rate of seepage, and for presence of sediment in seepage. Will become evident as localized intensive seepage at dike toe and can be repaired. May also see settlement in the cut off wall. Will be most likely in deep water sections. Gradients across the cut off wall in shallow water are not high enough to cause piping.
	(2) Dike Section: Cut off wall loses bentonite because of improper construction.	Same consequences as erosion because of defect, as above.	Bentonite makes up 2% of the cut off wall fill. Loss of this material will increase the permeability of the cut off wall and increase the rate of seepage.

Failure Mode	Scenario	Consequence	Monitoring/Action
	(3) Foundation: Till is possibly non-uniform with more transmissive zones and not self-filtering. It is possible that one of these zones may align with defective construction of the core backfill and defective construction of the cut off wall allowing high flows. Seepage along the transmissive zone beneath the downstream rockfill section could erode the foundation tills at the downstream toe or flow into the downstream rockfill because of the lack of filtering.	Limited seepage at the toe or into the rockfill would accelerate into a large inflow, and could lead to the undermining of the dike if no action was taken. This is a credible catastrophic failure mode if increased seepage is not detected in time.	No particular instrumentation is needed as this failure mode will show itself as localized and increasing seepage. It could be detected by walk-over inspection by an experienced engineer or technician. Remedial action could comprise a reverse filter and rockfill buttress depending on location of the flow and configuration of the foundation, freezing, or grouting if identified in time. Quality control of cut off is important, and most important for deep water sections. In the worst case, the pit may be deliberately flooded in a controlled manner, the cut off repaired, and the pit dewatered.
Seepage within Embankment	Seepage on its own is not a credible failure scenario. The downstream rockfill shell has extremely high flow through capacity. The rockfill zone is both large and pervious, so that seepage will daylight on the downstream face and lead to instability. Any seepage related failures must include internal erosion, see above.	No credible consequences. May require upgrade of the seepage collection system. May need to suspend mining activities while reducing seepage.	Seepage monitoring program.
Seepage within Foundation	Defective construction of cut off leading to transfer of unexpectedly high fraction of the reservoir head into the downstream part of the dike foundation, or leading to a piping event as above.	This failure mechanism has caused embankment failures elsewhere because of straightforward pore pressure induced instability. However, it is unclear that it could cause failure of the Dewatering Dikes because of their large width compared to the retained water head. The most likely consequence is downstream toe slumping requiring a localized stabilizing berm before the crest roadway could be reinstated.	If this mechanism arises it should show itself during initial dewatering or very shortly thereafter.

Failure Mode	Scenario	Consequence	Monitoring/Action
Internal Conduit Rupture	There are no water off take works or other structures extending through the dikes.	Not applicable.	Not applicable.
Slope Instability	(1) Normal Operation: The rockfill shoulders of the dikes are wide and have high shear strength, making it a conservative design. Slope failure requires failure in the foundation and which would then extend into the overlying dike. Sliding failure is considered unlikely given the low horizontal forces generated by water and ice forces relative to the normal frictional force due to the weight of the dikes and the friction angles of foundation materials	A foundation failure would cause a rotational slip or sliding failure until equilibrium was reached. This mechanism would limit access along the dike until repaired. Failure through the rockfill shoulders will not necessarily compromise the water retaining function of the dikes. Failures which reach the core may cause failure.	This mechanism should develop during construction or dewatering, due to increase in load and associated pore water pressure increase. Initial stages of failure should be observable as tension cracks in the dike crest. Walk-over inspection of the dikes by a trained inspector is an appropriate monitoring strategy. Survey of crest, face, and toe is also appropriate. Stabilizing berms can be placed inside the dikes or through water along the upstream shoulder.
	(2) Earthquake Induced: Occurrence of an extreme earthquake, much in excess of the current understanding of seismicity of the area.	The extreme earthquake loading for this site is a low magnitude. Settlement of the dikes could occur in the event of a large earthquake. Dynamic compaction of the core during construction may have subjected the rockfill shells to accelerations equivalent to the expected earthquake loading. This would not be a failure situation. The crest is also erosion resistant for any earthquake induced wave action in the impounded water.	Dike inspection following earthquakes felt on site.

Failure Mode	Scenario	Consequence	Monitoring/Action
Failure of Cut off Wall or Bituminuous Liner Due to Movement of the Dikes	Differential horizontal movement of dikes due to water or ice loading, or pit wall failure. Creates a breach in the cut off wall, cut off key trench or bituminuous liner. Ice and water forces are not credible due to the ratio of frictional forces generated by the weight of the dike versus ice loads and water pressure. Pit wall failure involving the dike unlikely based on assessments of pit wall stability and setback distance between the pit and the dikes.	Large inflows through the breach. Pit would flood requiring suspension of mining activities. Potential for loss of life for workers inside dikes.	No enhanced monitoring. Prism monitoring program sufficient. If the pit floods, then repairs to cut off or bituminuous liner would be done prior to dewatering.
Unexpected Settlements	Unexpected foundation soils consolidate during dike construction. A significant quantity of clay that was not recognized during foundation excavation would be required to generate settlement required for a water release event. Settlement of the core will be limited by dynamic compaction.	2 m of core settlement would be required to allow water flow through the rockfill and over the settled core. This flow would not cause failure of the rockfill shells. It would also be readily repaired by placing more end-dumped till into the settled zone.	No enhanced monitoring required, as settlement would be apparent from prism monitoring data and visual inspection. Excessive settlements may be remediated by excavating rockfill above the core and placing more till. Soil conditions will be observed during construction, and design revised to accommodate actual conditions.

1.1 Failure Scenario during Operations

The 'worst-case' scenario for failure of the dewatering dikes during operations would involve a movement of the dikes that compromises the integrity of the cut off wall, cut off key trench or bituminous liner. However, the rockfill has a very high flow-through capacity and a high strength and will not move unless the foundation is involved. The water will flow through the upstream rockfill first, then through the core and cut off wall, cut off key trench or bituminous liner, and finally through the downstream rockfill berm. Flow through cracks opening in the foundation may erode the foundation soils and the core. The upstream rockfill will choke the flow to some degree, and flow will decrease once the downstream toe of the dike is inundated and the head difference across the dike begins to reduce.

Although this describes a 'worst-case' scenario, a catastrophic failure of the pit dewatering dike system is not considered a credible failure mode. Elements of the dike design, including the width of the dike section, and the inclusion of filters, in addition to the cut off wall, cut off key trench and bituminous liner make catastrophic failure of the dike highly unlikely. However, for the purposes of this document, the effects of such a failure are described below.

Potential Effect

In the case of East Dike, the worst-case scenario would be associated with the short portion of the dike through the deepest water along the alignment at the centre of the dike. In this area the water depth is as much as 7 m to bedrock at the cut off wall within the dike. This inflow could potentially result in loss of workers caught in flowing water. Breach of the East Dike would be unlikely to trap workers in the pit when access ramps are on the west side, opposite the inflows. Breach of the East Dike would result in cessation of mining, either temporarily or permanently.

Upon completion of the East Dike and dewatering of the northwest arm of Second Portage Lake, there was approximately 17 million m³ (Mm³) of water remaining in Second Portage Lake. If the segment of dike at the deepest portion were suddenly removed, flow from Second Portage Lake into the pit would continue until the elevation of the lake drops by several metres, at which time the current lake bottom would be exposed and would act as a barrier to flow towards the pit. This scenario is the worst in the final year of pit operation when pit volume is the largest. The volume of water associated with this drawdown would be on the order of about 10 Mm³. Some erosion of the till between the pit crest and dike toe would be expected, so the depth of water loss from the lake may be larger, but this would take some time to fully develop.

Inflow to the pit could expose large amounts of shoreline and shoal habitat around the lake. Water flowing into the pit could entrain suspended solids and dissolved constituents from the dike material and pit walls. If necessary, the water could be retained within the pit and diked area and would be amenable to treatment (e.g., particle settling, in-situ amendment) before discharge, should it be required.

The ecological effects of the exposure of shoreline and shoal habitat on fish and fish habitat would be to temporarily eliminate spawning areas and result in reduced water quality from exposure of sediment to wave and wind induced erosion. The effect of this would last approximately one year as inflow from Third Portage Lake to Second Portage Lake averages 10 Mm³ annually (AMEC, 2003). Presuming that the dike breach is repaired, water levels in Second Portage Lake would rise over the

spring and summer to return to pre-breach elevations and would re-fill the lake in the event of a 'worst-case' scenario.

In the case of Bay Goose Dike, the worst-case scenario dike breach that could allow the greatest amount of water inflow would be associated with the southeast segment of the dike through the deepest water along the alignment. In this area, water depth is as much as 20 m deep at the cut off, and the pit could be as deep as 130 m. This inflow could potentially result in loss of workers caught in flowing water. Breach of the Bay Goose Dike would be unlikely to trap workers in the pit when access ramps are on the northwest side, opposite the inflows. Breach of the Bay Goose Dike would result in cessation of mining of the Goose Pit, either temporarily or permanently.

In the unlikely event that such a failure of the Bay Goose Dike were to occur, the rate and volume of water entering the downstream pit would depend on the magnitude of the breach and the length of time to repair the breach. Third Portage Lake has an estimated volume of 446 Mm³ (Golder, 2006). The final volume of Portage Pit (30.0 Mm³) is roughly 6.7% of the volume of the lake, while Goose Pit (14.8 Mm³) is approximately 3.3% of the volume. In the case of a catastrophic breach of the Bay Goose Dike, the estimated Third Portage Lake water level drawdown would be approximately 1.0 m and 0.5 m, respectively assuming that the failure occurs when the pits are completely excavated and a complete filling of the pits. These estimated worst-case scenario changes in water level are comparable to the mean average annual difference between high and low water (0.3 m) on Third Portage Lake.

There would be a small impact to fish and fish habitat in Third Portage Lake in the event of a 0.5 m to 1.0 m drop in water level. Areas used for spawning may be slightly nearer to the ice cover and a small amount of habitat might be vulnerable to freezing. Water quality within the pit would be temporarily impaired from an increase in suspended and dissolved solids, although water quality would return to near background during the first winter as sediment would settle under the ice cover.

In the case of South Camp dike, the worst-case scenario dike breach that could allow the greatest amount of water inflow would be associated with the centre segment of the dike through the deepest water along the alignment. In this area, the water depth is only a maximum of 1 m. This inflow could put the workers at risk at the site on a temporary basis and a potential loss of life between 0 and 10 due to workers caught in flowing water. Breach of South Camp Dike could eventually result in cessation of mining, either temporarily or permanently.

If the segment of dike at the deepest portion were suddenly removed, flow from Third Portage Lake into the pit would continue until the elevation of the lake drew down slightly as South Camp Dike retains a maximum depth of 1 m of water. The impact of a potential failure would likely be limited.

Inflow to the pit could expose a limited amount of shoreline and shoal habitat around the lake. Water flowing into the pit could entrain suspended solids and dissolved constituents from the dike material and pit walls. If necessary, the water could be retained within the pit and diked area and would be amenable to treatment (e.g., particle settling, in-situ amendment) before discharge, should it be required.

The ecological effects of the dike failure will probably have no significant fish or wildlife habitat, affected or deteriorated. Presuming that the dike breach is repaired, water levels in Third Portage Lake would rise over the spring and summer to return to pre-breach elevations and would re-fill the lake in the event of a 'worst-case' scenario.

In the case of Vault dike, the worst-case scenario dike breach that could allow the greatest amount of water inflow would be associated with the centre segment of the dike through the deepest water along the alignment. In this area, the water depth is only a maximum of 1 m. This inflow could put the workers at risk at the site on a temporary basis and a potential loss of life between 0 and 10 due to workers caught in flowing water. Breach of the Vault Dike could eventually result in cessation of mining, either temporarily or permanently.

If the segment of dike at the deepest portion were suddenly removed, flow from Wally Lake into the pit would continue until the elevation of the lake drew down slightly as Vault Dike retains a maximum depth of 1 m of water. The impact of a potential failure would be limited.

Inflow to the pit could expose a limited amount of shoreline and shoal habitat around the lake. Water flowing into the pit could entrain suspended solids and dissolved constituents from the dike material and pit walls. If necessary, the water could be retained within the pit and diked area and would be amenable to treatment (e.g., particle settling, in-situ amendment) before discharge, should it be required.

The ecological effects of the dike failure will probably have no significant fish or wildlife habitat, affected or deteriorated. Presuming that the dike breach is repaired, water levels in Wally Lake would rise over the spring and summer to return to pre-breach elevations and would re-fill the lake in the event of a 'worst-case' scenario.

Mitigation, Management, and Monitoring

A major cut off breach scenario due to pit wall movement, while possible, has a low probability of occurrence in East Dike or Bay Goose Dike. If foundation movement was sufficient to compromise the cut off wall, then the core backfill would act as a semi-permeable element and limit flow. Water would first need to flow through the rockfill shell, the core backfill, the damaged cut off wall, and then through more of the core, filters, and the downstream rockfill. Provided that the downstream filter elements against the rockfill shell are properly constructed, then migration of the core and cut off wall into the rockfill will not occur. Some additional seepage may occur due to failure of the cut off wall; however this would be noted during regular monitoring. Mitigation could be by jet grouting, freezing, or installation of sheet piling through the cut off wall.

The use of appropriately graded filters in the design of dikes and dams is standard engineering practice, and is the key to preventing internal erosion. The dike design includes the use of a two zone filter on the upstream face of the pit side rockfill. During the construction of the dikes a quality control and quality assurance program was undertaken.

Routine visual inspection of the dikes is to be conducted on a regular basis to document any changes in the dikes.

During the operation of the dikes, a series of monitoring instrumentation will be installed, including:

- Thermistors to monitor the thermal regime in the dike and foundations;
 - Slope inclinometers and prisms to monitor deformations within the dikes; and
 - Piezometers to measure pressure and to infer flow through the dikes.
-

Piezometers downstream of the cut off wall would be monitored for pressure changes as the pits are deepened. Increasing pressure would indicate that less head loss is occurring across the seepage cut off, which might indicate that a crack has formed, permeability is increasing, or the pit is experiencing inflows from some other potential flow pathway. The instrumentation will be monitored to identify any potentially problematic areas relating to dike instability. Mitigation measures for seepage and piping could include:

- Additional pressure grouting of bedrock materials;
- De-pressurization wells;
- Construction of a slurry cut off wall within the core just upstream of the suspected seepage area;
- Jet grouting of the core and foundation in the suspected seepage or crack area;
- Construction of a cutter soil mixing (CSM) wall in the suspected crack area;
- Freezing;
- Installation of toe drains; and
- Construction of interceptor ditches within the down-stream overburden materials.
- Allow pit to flood, install new cut off or bituminous liner under no-flow conditions, then dewater and resume mining.

Specific monitoring and mitigation strategies have been developed as part of an Operations Plan (OMS Manual) for the dewatering dikes.

1.2 Failure Scenario during Closure

At end of mine life, once the water quality of the pit lake has been determined to be suitable for release, a portion of the south end of the Bay-Goose Dike will be removed resulting in a hydraulic connection between the Goose/Portage Pit Lake and Third Portage Lake. The East Dike will be the only dike that will remain in service. The elevation of the pit lake will be equal to Third Portage Lake. The elevation difference between the pit lake and Second Portage Lake will be approximately 1 m. Consequently, there will be a low hydraulic gradient from the pit lake towards Second Portage Lake. During the closure and post-closure period, the natural central and east channel outlets that connect Third Portage to Second Portage Lake will continue to carry the entire flow between the two lakes.

Potential Effect

A breach of the East Dike would create an additional outlet and cause water to leave the Portage/Goose pit area and spill into Second Portage Lake at a greater rate, partly at the expense of flow from the central and east channel outlets. This would cause a rise in water level in Second Portage Lake and a reduction in level in Third Portage Lake. The additional water would flow through the channel connecting Second Portage Lake to Tehek Lake until the water elevations in Second and Third Portage lakes equilibrated.

In the event of such a scenario, water would flow from Third Portage Lake, northward through the pit lake area, and then east through a potential East Dike breach and into Second Portage Lake. There is a naturally large outlet capacity via the connecting channel from Second Portage to Tehek Lake. Water residence time in Second Portage Lake during and after mine development is less than one year. Thus, in the event of an East Dike breach, any additional water added to Second Portage Lake would leave the system relatively quickly. Given the flow-through nature of the lake there would be little net change in Second Portage Lake volume or lake elevation as water would easily be absorbed into the much larger Tehek Lake.

Drawdown of Third Portage Lake would be limited, given the large size of the lake (33 km²) and the constriction points within the system that would slow drawdown. Specifically, the magnitude of drawdown in the event of a breach would depend on the magnitude and depth of the breach, time of year (winter ice cover would prevent loss of water), response time, flow rate (i.e., the loss of water depends on the location of the breach and friction through the system), and the outlet capacity of Second Portage Lake. For example, total annual average discharge from Third Portage to Second Portage Lake is approximately 10 Mm³ with a mean annual difference in water level between spring and fall of 0.3 m. Given the large size of Third Portage Lake, a breach resulting in the loss of 10 Mm³ of water, which is equivalent to an entire open water season of runoff through all discharge channels would result in a drawdown of only about 0.3 m. Maximum drawdown would be one metre.

Reductions in water level would therefore be small and have only minor impacts to fish habitat in Third Portage Lake. Adverse impacts to water quality would not be expected given that water quality within Goose/Portage pits is expected to be very high.

Mitigation, Management and Monitoring

Internal erosion of the cut off wall could result in an increase of the rate of water flow through the East Dike. However, this is extremely unlikely due to the low hydraulic gradient across the East Dike (~ 1 m of head difference) and the filter effect of the core backfill. Such a scenario is more likely to occur during the operational phase of the East Dike when the hydraulic gradient across the dike section is much higher, though in the opposite direction. If such a scenario were to occur, it would not be considered a catastrophic failure mode due to the stability of the rockfill shoulders comprising the outside structural elements of the dike.

A breach in the East Dike during closure could be managed by the placement of material to reduce the flow of water and reduce potential erosion of the till core. The hydraulic gradient across the dike at closure is low. The dike could be repaired and hydrologic conditions restored without any danger to the overall stability of the dike, provided annual monitoring is carried out following closure.