



LUDWIG & ASSOCIATES LTD.

Materials and Welding Consulting



LABORATORY
ACCREDITATION
BUREAU

ISO/IEC 17025 ACCREDITED
Certificate Number L2057

LABORATORY TEST REPORT

CUSTOMER: Woodside Fabrications Ltd.
6124 - 39th Avenue
Camrose, Alberta
T4V 3B1

Laboratory Test No.: C07-300.2

Date: March 7, 2007

Attention: Douglas French

PQR Number: WFL-2-1 **Process:** SAW
Material: SA 516 Gr. 60N to SA 516 Gr. 70N (Heat No.: 44410 - 34383)
Thickness: 6.32 mm (0.249 in.)
Thermal Condition: As Welded

NOTCH-TOUGHNESS TEST

TYPE OF TEST: Charpy V-Notch
TEST TEMPERATURE: -48°C (-55°F)

ORIENTATION: Transverse
SPECIMEN SIZE: 10 x 5 mm

Specimen Number	Notch Location	Impact Values Joules (ft.lbs)	
V2.1	Weld Metal within 1/16 in. of root	30.1	(22.2)
V2.2		35.1	(25.9)
V2.3		33.9	(25.0)
V3.1	Gr. 60N - HAZ	32.5	(24.0)
V3.2	Gr. 60N - HAZ	30.1	(22.2)
V3.3	Gr. 60N - HAZ	14.2	(10.5)
W3.1	Gr. 70N - HAZ	28.5	(21.0)
W3.2	Gr. 70N - HAZ	9.5	(7.0)
W3.3	Gr. 70N - HAZ	25.8	(19.0)

We certify the test results in this report and that the specimen(s) were prepared and tested in accordance with the requirements of ASME Section VIII, Div. 1, UG-84 - 2004 edition and latest addenda. The information regarding material identification (i.e. size, thickness, heat number, etc.) has been provided by the customer whose name appears on this report. **Samples associated with this report will be discarded in 45 days.**

Laboratory Test Conducted By: _____


Charles Ugarenko / Steve Rieberger, C.E.T.



LUDWIG & ASSOCIATES LTD.

Materials and Welding Consulting

LABORATORY
ACCREDITATION
BUREAU
ISO/IEC 17025 ACCREDITED
Certificate Number L2057

LABORATORY TEST REPORT

CUSTOMER: Woodside Fabrications Ltd.
6124 - 39th Avenue
Camrose, Alberta
T4V 3B1

Laboratory Test No.: C07-300.2


Date: March 5, 2007

Attention: Douglas French

PQR Number: WFL-2-1 **Process:** SAW
Material: SA 516 Gr. 60N to SA 516 Gr. 70N (Heat No.: 44410 - 34383)
Thickness: 6.32 mm (0.249 in.)
Thermal Condition: As Welded

HARDNESS TEST

TYPE OF TEST: Vickers **LOAD:** 10 kg
INSTRUMENT TYPE: Mitutoyo AVK-C1



SA 516 Gr. 70N

SA 516 Gr. 60N

1) 166 HV	7) 172 HV	13) 214 HV	19) 210 HV	25) 194 HV
2) 192 HV	8) 194 HV	14) 220 HV	20) 222 HV	26) 198 HV
3) 197 HV	9) 178 HV	15) 188 HV	21) 223 HV	27) 212 HV
4) 175 HV	10) 173 HV	16) 192 HV	22) 169 HV	28) 194 HV
5) 162 HV	11) 194 HV	17) 186 HV	23) 188 HV	29) 166 HV
6) 170 HV	12) 203 HV	18) 215 HV	24) 209 HV	

We certify the test results in this report and that the specimen(s) were prepared and tested in accordance with the requirements of ASTM E92 - 82 (Reapproved 2003)^{e2}. The information regarding material identification (i.e. size, thickness, heat number, etc.) has been provided by the customer whose name appears on this report. **Samples associated with this report will be discarded in 45 days.**

Laboratory Test Conducted By: _____

Andrew Vessey / Steve Rieberger, C.E.T.

QM-System: Certification as per ISO 9001

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)

A02 INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004		A10 Advice of dispatch No./ Date of dispatch		A08/ Manufacturer's order/ A03 Certificate No.		Sheet
INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013		558728-23.02.16		411465-004		1/...
MATERIAL TEST REPORT (MTR)						
A05 Established inspecting body		A06 Purchaser		A07.1 No.		
DH		EDMONTON STEEL, EDMON		EDMONTON STEEL, EDMON		
A05 Steel design.		Final receiver		A07.2 No.		
B02/ Steel design.		SA516-60		SA20-S5		
B03 Any suppl. requirements		ASME-III: 2013				
		DIL-HUE-1: R33-2014-04-04				



B01-B99 Description of the product

B14 Item No.	B08 Number of pieces	B09 Thickness	B10 Width INCH	B11 Length	B12 Theoretical mass KG	B04 Product delivery condition	B07.2 Heat No.	B07.1 Rolled plate No./ Test No.	A09 Purchaser article number
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29242-01	EPL-248
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29242-02	SA 516 Gr. 60/70
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29242-03	0.375 in. w.t. plate
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29243-01	HT # 429693 29249-03
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29243-02	Internal PO: E20306
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29243-03	External PO: 210377
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29245-01	Date Received: 29-Jan-19
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29245-02	Recieved by: Jessie Springett
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29245-03	
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29249-01	
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29249-02	
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29249-03	
**	12				26808				
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29255-01	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29255-02	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29255-03	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29256-01	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29256-02	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29256-03	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29263-01	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29263-02	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29263-03	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29264-01	

Springett

A04 Z01Z02/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.



Manufacturer's mark

B. Baldauf

B. BALDAUF
Test House Manager



AG der Dillinger Hüttenwerke
Postfach 1580, D-66748 Dillingen/Saar
Inspection department

Inspector's stamp Date 23.02.16 PP 1

A01

QM-System: Certification as per ISO 9001

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)



A02 INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004 INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013 MATERIAL TEST REPORT (MTR)		A10 Advice of dispatch No./ Date of dispatch 558728-23.02.16	A08/ Manufacturer's order/ A03 Certificate No. 411465-004	Sheet 11/...
A05 Established inspecting body DH		B01 Product HEAVY PLATES		
B02/ Steel design. SA516-60		A07.1 No. ED10682-J1010ER		
B03 Any suppl. requirements		A07.2 No. SA20-S5		
DIL-HUE-1:R33-2014-04-04				

C70-C99 Chemical composition % - Heat analysis

	C70	C	Si	Mn	P	S	N	CU	MO	NI	CR	V	NB	SN	TI
B07.2 Heat															
429474	Y	0,182	0,377	1,17	0,010	0,0009	0,0075	0,028	0,010	0,032	0,033	0,000	0,000	0,001	0,003
429477	Y	0,180	0,375	1,17	0,009	0,0011	0,0070	0,015	0,004	0,025	0,035	0,000	0,000	0,001	0,002
429479	Y	0,173	0,368	1,17	0,010	0,0008	0,0072	0,023	0,012	0,028	0,047	0,001	0,000	0,001	0,003
429480	Y	0,171	0,378	1,19	0,010	0,0006	0,0060	0,019	0,011	0,033	0,041	0,000	0,000	0,001	0,002
429483	Y	0,176	0,381	1,18	0,008	0,0008	0,0082	0,025	0,008	0,026	0,033	0,000	0,000	0,001	0,002
429485	Y	0,183	0,378	1,18	0,009	0,0007	0,0075	0,038	0,006	0,028	0,042	0,000	0,000	0,002	0,003
429601	Y	0,191	0,378	1,19	0,006	0,0008	0,0063	0,014	0,012	0,030	0,029	0,001	0,001	0,001	0,002
429693	Y	0,161	0,384	1,19	0,010	0,0010	0,0068	0,025	0,011	0,024	0,028	0,001	0,001	0,001	0,003
429696	Y	0,154	0,373	1,16	0,009	0,0008	0,0075	0,020	0,006	0,019	0,028	0,001	0,003	0,001	0,002
B07.2 Heat															
429474	Y	0,0003	0,0021	0,032	AL-T										
429477	Y	0,0003	0,0017	0,034	CA										
429479	Y	0,0003	0,0013	0,034											
429480	Y	0,0002	0,0014	0,033											
429483	Y	0,0001	0,0014	0,030											
429485	Y	0,0003	0,0013	0,034											
429601	Y	0,0002	0,0020	0,038											
429693	Y	0,0002	0,0015	0,032											
429696	Y	0,0001	0,0016	0,033											

A04	Z01/Z02/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.	AG der Dillinger Hüttenwerke Postfach 1580, D-66748 Dillingen/Saar Inspection department	Date 23.02.16	pp 1
A01				

QM-System: Certification as per ISO 9001



DILLINGER HÜTTE

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)

A02 INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004		A10 Advice of dispatch No./ Date of dispatch		A08/ Manufacturer's order/ A03 Certificate No.		Sheet	
INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013		558728-23.02.16		411465-004		1/...	
MATERIAL TEST REPORT (MTR)				B01 Product			
A06 Established inspecting body		A06 Purchaser		EDMONTON STEEL, EDMON		A07.1 No. ED10682-J1010ER	
DH		Final receiver		EDMONTON STEEL, EDMON		A07.2 No.	
B02/ Steel design.		SA516-70		SA20-S5			
B03 Any suppl. requirements		ASME-III-A:2013					
		DIL-HUE-1:R33-2014-04-04					



B01-B99 Description of the product

B14 Item No.	B08 Number of pieces	B09 Thickness	B10 Width INCH	B11 Length	B12 Theoretical mass KG	B04 Product delivery condition	B07.2 Heat No.	B07.1 Rolled plate No./ Test No.	A09 Purchaser article number
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29242-01	EPL-248
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29242-02	SA 516 Gr. 60/70
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29242-03	0.375 in. w.t. plate
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29243-01	HT # 429693 29249-03
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29243-02	Internal PO: E20306
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29243-03	External PO: 210377
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29245-01	Date Received: 29-Jan-19
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29245-02	Recieved by: Jessie Springett
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29245-03	
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29249-01	
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29249-02	
01	1	0,3750 x	96,50000 x	480,00000 x	2234	N	429693	29249-03	
**	12				26808				
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29255-01	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29255-02	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29255-03	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29256-01	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29256-02	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29256-03	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29263-01	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29263-02	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29263-03	
02	1	0,3750 x	120,50000 x	480,00000 x	2790	N	429693	29264-01	

Jessie Springett

A04		Z01/Z02/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.		AG der Dillinger Hüttenwerke Postfach 1580, D-66748 Dillingen/Saar Inspection department		A01	
D H Manufacturer's mark		B. BALDAUF Test House Manager		A01		Date 23.02.16	
		Inspector's stamp		Date		PP	

QM-System: Certification as per ISO 9001



DILLINGER HÜTTE

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)

A02 INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004		A10 Advice of dispatch No./ Date of dispatch		A08/ Manufacturer's order/ A03 Certificate No.		Sheet	
INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013		558728-23.02.16		411465-004		11/...	
MATERIAL TEST REPORT (MTR)							
A05 Established inspecting body		A06 Purchaser		A07.1 No.		A07.2 No.	
DH		Final receiver		EDMONTON STEEL, EDMON		EDMONTON STEEL, EDMON	
B02/ Steel design.		SA516-70		SA20-S5			
B03 Any suppl. requirements		ASME-III-A:2013		DIL-HUE-1:R33-2014-04-04			

C70-C99 Chemical composition % - Heat analysis

	C70	C	SI	MN	P	S	N	CU	MO	NI	CR	V	NB	SN	TI
B07.2 Heat															
429474	Y	0,182	0,377	1,17	0,010	0,0009	0,0075	0,028	0,010	0,032	0,033	0,000	0,000	0,001	0,003
429477	Y	0,180	0,375	1,17	0,009	0,0011	0,0070	0,015	0,004	0,025	0,035	0,000	0,000	0,001	0,002
429479	Y	0,173	0,368	1,17	0,010	0,0008	0,0072	0,023	0,012	0,028	0,047	0,001	0,000	0,001	0,003
429480	Y	0,171	0,378	1,19	0,010	0,0006	0,0060	0,019	0,011	0,033	0,041	0,000	0,000	0,001	0,002
429483	Y	0,176	0,381	1,18	0,008	0,0008	0,0082	0,025	0,008	0,026	0,033	0,000	0,000	0,001	0,002
429485	Y	0,183	0,378	1,18	0,009	0,0007	0,0075	0,038	0,006	0,028	0,042	0,000	0,000	0,002	0,003
429601	Y	0,191	0,378	1,19	0,006	0,0008	0,0063	0,014	0,012	0,030	0,029	0,001	0,001	0,001	0,002
429693	Y	0,161	0,384	1,19	0,010	0,0010	0,0068	0,025	0,011	0,024	0,028	0,001	0,001	0,001	0,003
429696	Y	0,154	0,373	1,16	0,009	0,0008	0,0075	0,020	0,006	0,019	0,028	0,001	0,003	0,001	0,002
B07.2 Heat															
429474	Y		CA	AL-T											
429477	Y	0,0003	0,0021	0,032											
429479	Y	0,0003	0,0017	0,034											
429480	Y	0,0002	0,0013	0,034											
429483	Y	0,0001	0,0014	0,033											
429485	Y	0,0001	0,0014	0,030											
429601	Y	0,0003	0,0013	0,034											
429693	Y	0,0002	0,0020	0,038											
429696	Y	0,0002	0,0015	0,032											
429696	Y	0,0001	0,0016	0,033											

A04



Manufacturer's mark

Z01/Z02/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.

B. Baldauf

B. BALDAUF
Test House Manager



AG der Dillinger Hüttenwerke
Postfach 1580, D-66748 Dillingen/Saar
Inspection department

Inspector's stamp

Date 23.02.16

PP 1

A01

QM-System: Certification as per ISO 9001

DILLINGER

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)


A02	INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004		A10	Advice of dispatch No./ Date of dispatch	A08/ Manufacturer's order/ A03 Certificate No.	Sheet
	INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013					
MATERIAL TEST REPORT (MTR)						
A05 Established inspecting body	A06 Purchaser	626272-10.02.18		431792-001	12/...	

B02/ Steel design.	SA516-70	SA20-S5			
B03 Any suppl. requirements	ASME-III-A:2015				
	DIL-HUE-1:R34-2016-08-19				

C70-C99 Chemical composition % - Product analysis

		C01															
B07.2	B07.1																
Heat	Test No.	C	SI	MN	P	S	N	CU	MO	NI	CR	V	NB	SN	TI		
454461	64437	K1 0,167	0,366	1,16	0,011	0,0007	0,0076	0,025	0,006	0,050	0,029	0,001	0,002	0,001	0,002		
454836	27699	K1 0,170	0,368	1,16	0,010	0,0007	0,0061	0,033	0,007	0,027	0,038	0,000	0,001	0,001	0,003		
454836	27706	K1 0,177	0,369	1,16	0,010	0,0006	0,0059	0,033	0,007	0,027	0,038	0,001	0,001	0,001	0,003		
454837	27740	K1 0,166	0,369	1,16	0,009	0,0005	0,0060	0,026	0,005	0,023	0,028	0,001	0,001	0,001	0,002		
454837	27783	K1 0,179	0,373	1,17	0,008	0,0005	0,0060	0,024	0,004	0,022	0,024	0,001	0,001	0,001	0,001		
454840	27789	K1 0,167	0,369	1,17	0,009	0,0004	0,0060	0,023	0,004	0,022	0,023	0,001	0,001	0,000	0,002		
454840	27796	K1 0,164	0,371	1,17	0,009	0,0005	0,0064	0,023	0,004	0,022	0,023	0,001	0,001	0,000	0,002		
454840	27809	K1 0,165	0,365	1,15	0,009	0,0005	0,0054	0,023	0,010	0,024	0,038	0,001	0,001	0,000	0,002		
454843	27952	K1 0,145	0,358	1,14	0,009	0,0004	0,0053	0,023	0,014	0,025	0,045	0,001	0,000	0,000	0,002		

		C01															
B07.2	B07.1																
Heat	Test No.	B	CA	AL-T													
454461	64437	K1 0,0001	0,0013	0,034													
454836	27699	K1 0,0001	0,0018	0,031													
454836	27706	K1 0,0001	0,0019	0,032													
454837	27740	K1 0,0000	0,0015	0,030													
454837	27783	K1 0,0000	0,0014	0,029													
454840	27789	K1 0,0001	0,0011	0,031													
454840	27796	K1 0,0000	0,0011	0,031													
454840	27809	K1 0,0000	0,0012	0,035													
454843	27952	K1 0,0000	0,0011	0,038													

A04	 Manufacturer's mark	Z01Z02/203 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.										AG der Dillinger Hüttenwerke Postfach 1580, D-66748 Dillingen/Saar Inspection department		Date 12.02.18		PP 1	
		 B. BALDAUF Test House Manager										 Inspector's stamp					

QM-System: Certification as per ISO 9001



Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)

A02 INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004 INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013 MATERIAL TEST REPORT (MTR)		A10 Advice of dispatch No./ Date of dispatch 626272-10.02.18	A08/ Manufacturer's order/ A03 Certificate No. 431792-001	Sheet 12/...
A05 Established inspecting body DH		B01 Product HEAVY PLATES		
B02 Steel design. SA516-60		EDMONTON STEEL, EDMON		
B03 Any suppl. requirements DIL-HUE-1:R34-2016-08-19		A07.1 No. ED10722-J1010ER A07.2 No. SA20-S5		

C70-C99 Chemical composition % - Product analysis

B07.2		B07.1		C01																			
Heat	Test No.	C	SI	MN	P	S	N	CU	MO	NI	CR	V	NB	SN	TI								
454461	64437	0,167	0,366	1,16	0,011	0,0007	0,0076	0,025	0,006	0,050	0,029	0,001	0,002	0,001	0,002								
454836	27699	0,170	0,368	1,16	0,010	0,0007	0,0061	0,033	0,007	0,027	0,038	0,000	0,001	0,001	0,003								
454836	27706	0,177	0,369	1,16	0,010	0,0006	0,0059	0,033	0,007	0,027	0,038	0,001	0,001	0,001	0,003								
454837	27740	0,166	0,369	1,16	0,009	0,0005	0,0060	0,026	0,005	0,023	0,028	0,001	0,001	0,001	0,002								
454837	27783	0,179	0,373	1,17	0,008	0,0005	0,0060	0,024	0,004	0,022	0,024	0,001	0,001	0,001	0,001								
454840	27789	0,167	0,369	1,17	0,009	0,0004	0,0060	0,023	0,004	0,022	0,023	0,001	0,001	0,000	0,002								
454840	27796	0,164	0,371	1,17	0,009	0,0005	0,0064	0,023	0,004	0,022	0,023	0,001	0,001	0,000	0,002								
454840	27809	0,165	0,365	1,15	0,009	0,0005	0,0054	0,023	0,010	0,024	0,038	0,001	0,001	0,000	0,002								
454843	27952	0,145	0,358	1,14	0,009	0,0004	0,0053	0,023	0,014	0,025	0,045	0,001	0,000	0,000	0,002								
C01																							
B07.2		B07.1		C01																			
Heat	Test No.	B	CA	AL-T																			
454461	64437	0,0001	0,0013	0,034																			
454836	27699	0,0001	0,0018	0,031																			
454836	27706	0,0001	0,0019	0,032																			
454837	27740	0,0000	0,0015	0,030																			
454837	27783	0,0000	0,0014	0,029																			
454840	27789	0,0001	0,0011	0,031																			
454840	27796	0,0000	0,0011	0,031																			
454840	27809	0,0000	0,0012	0,035																			
454843	27952	0,0000	0,0011	0,038																			

A04	Z01/Z02/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.	AG der Dillinger Hüttenwerke Postfach 1580, D-66748 Dillingen/Saar Inspection department	AG der Dillinger Hüttenwerke Postfach 1580, D-66748 Dillingen/Saar Inspection department	Date 12.02.18	PP 1
A01					

QM-System: Certification as per ISO 9001

DILLINGER

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)

A02 INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004		A10 Advice of dispatch No./ Date of dispatch		A08/ Manufacturer's order/ A03 Certificate No.		Sheet	
INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013		645948-05.08.18		436752-003		4 / ...	
MATERIAL TEST REPORT (MTR)							
A05 Established inspecting body		A06 Purchaser		A07.1 No.		A07.2 No.	
DH		EDMONTON STEEL, EDMON		EDMONTON STEEL, EDMON		EDMONTON STEEL, EDMON	
B02 Steel design.		SA516-60		ED10734-J1010ER		B01 Product	
B03 Any suppl requirements		ASME-III:2017		SA20-S5		HEAVY PLATES	
DIL-HUE-1:R35-2018-02-12							

C94 Heat analysis Carbon equivalent / Alloying restrictions

B07.2	Heat	FO-02=	0,37	FO-51=	0,000	FO-55=	0,08	FO-78=	0,03	FO-91=	7,1
459852		FO-02=	0,39	FO-51=	0,000	FO-55=	0,22	FO-78=	0,06	FO-91=	6,9
460565		FO-02=	0,38	FO-51=	0,001	FO-55=	0,13	FO-78=	0,04	FO-91=	6,8
460566		FO-02=	0,40	FO-51=	0,001	FO-55=	0,21	FO-78=	0,09	FO-91=	6,8

C95 Ladle treatment

ITEM NO.: 01-05

HEAT OF THE INDICATED ITEM: VACUUM DEGASSED / SULPHIDE SHAPE CONTROL

C95 Further information about ladle treatment

ITEM NO.: 01-05

CALCIUM TREATED

C70-C99 Chemical composition % - Product analysis

B07.2	B07.1	Test No.	C	SI	MN	P	S	N	CU	MO	NI	CR	V	NB	SN	TI
459852	56930	K1	0,172	0,365	1,19	0,008	0,0008	0,0059	0,018	0,005	0,026	0,025	0,000	0,000	0,000	0,001
460565	34603	K1	0,169	0,366	1,15	0,004	0,0003	0,0058	0,019	0,040	0,153	0,019	0,000	0,000	0,000	0,001
460565	34606	K1	0,171	0,366	1,16	0,004	0,0004	0,0061	0,018	0,040	0,155	0,018	0,000	0,000	0,000	0,001
460565	34835	K1	0,173	0,365	1,16	0,003	0,0004	0,0061	0,018	0,041	0,159	0,018	0,000	0,000	0,000	0,001
460566	34468	K1	0,177	0,385	1,19	0,009	0,0002	0,0072	0,034	0,010	0,050	0,031	0,001	0,000	0,001	0,004
460567	35011	K1	0,173	0,381	1,18	0,008	0,0002	0,0063	0,054	0,022	0,049	0,066	0,001	0,000	0,003	0,002

A04



Manufacturer's
mark

Z01/202/203 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.

B. Baldauf

B. BALDAUF
Test House Manager

AHB

AG der Dillinger Hüttenwerke
Postfach 1580, D-66748 Dillingen/Saar
Inspection department

Inspector's stamp

Date 06.08.18

PP 1

A01

QM-System: Certification as per ISO 9001

DILLINGER

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)

A02 INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004

INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013

MATERIAL TEST REPORT (MTR)

A05 Established inspecting body

A08 Purchaser

EDMONTON STEEL, EDMON

A07.1 No. ED10734-J1010ER

Final receiver

EDMONTON STEEL, EDMON

A07.2 No.

B02/ Steel design. SA516-60

B03 Any suppl. ASME-III-A:2017

requirements DIL-HUE-1:R35-2018-02-12

SA20-S5

A10 Advice of dispatch No./
Date of dispatch

645948-05.08.18

A08/ Manufacturer's order/
A03 Certificate No.

436752-003

B01 Product

HEAVY PLATES

Sheet

5 / ...

C70-C99 Chemical composition % - Product analysis

B07.2	B07.1	C01	B	CA	AL-T
Heat	Test No.				
459852	56930	K1	0,0001	0,0011	0,030
460565	34603	K1	0,0000	0,0010	0,036
460565	34606	K1	0,0000	0,0011	0,035
460565	34835	K1	0,0000	0,0011	0,034
460566	34468	K1	0,0002	0,0012	0,058
460567	35011	K1	0,0000	0,0016	0,041

C94 Product analysis Carbon equivalent / Alloying restrictions

B07.2	B07.1	C01	FO-02	FO-51	FO-55
Heat	Test No.				
459852	56930	K1	FO-02= 0,38	FO-51= 0,000	FO-55= 0,07
460565	34603	K1	FO-02= 0,38	FO-51= 0,000	FO-55= 0,23
460565	34606	K1	FO-02= 0,39	FO-51= 0,000	FO-55= 0,23
460565	34835	K1	FO-02= 0,39	FO-51= 0,000	FO-55= 0,24
460566	34468	K1	FO-02= 0,39	FO-51= 0,001	FO-55= 0,13
460567	35011	K1	FO-02= 0,39	FO-51= 0,001	FO-55= 0,19

C94 Carbon equivalent formula / Alloying restrictions

FO-02 = $C + (Mn/6) + (Cr+Mo+V)/5 + (Ni+Cu)/15$
FO-51 = V + Nb
FO-55 = Cu+Mo+Ni+Cr
FO-78 = Cr+Mo
FO-91 = Mn/C

A04



Manufacturer's mark

Z01/Z02/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.

B. Baldauf

AHB

AG der Dillinger Hüttenwerke
Postfach 1580, D-66748 Dillingen/Saar
Inspection department

B. BALDAUF
Test House Manager

Inspector's stamp

Date 06.08.18

PP

1

QM-System: Certification as per ISO 9001

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)

A02 INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004
INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013
MATERIAL TEST REPORT (MTR)

DILLINGER

A05 Established inspecting body DH	A08 Purchaser Final receiver	EDMONTON STEEL, EDMON EDMONTON STEEL, EDMON	A07.1 No. ED10734-J1010ER A07.2 No.	A10 Advice of dispatch No./ Date of dispatch 645948-05.08.18	A08/ Manufacturer's order/ A03 Certificate No. 436752-003 B01 Product HEAVY PLATES	Sheet 4 / ...

B02/ Steel design. SA516-70

B03 Any suppl. ASME-III-A:2017

requirements DIL-HUE-1:R35-2018-02-12

SA20-S5

C94 Heat analysis Carbon equivalent / Alloying restrictions

B07.2 Heat	FO-02=	0,37	FO-51=	0,000	FO-55=	0,08	FO-78=	0,03	FO-91=	7,1
459852	FO-02=	0,39	FO-51=	0,000	FO-55=	0,22	FO-78=	0,06	FO-91=	6,9
460565	FO-02=	0,38	FO-51=	0,001	FO-55=	0,13	FO-78=	0,04	FO-91=	6,8
460567	FO-02=	0,40	FO-51=	0,001	FO-55=	0,21	FO-78=	0,09	FO-91=	6,8

C95 Ladle treatment

ITEM NO.: 01-05

HEAT OF THE INDICATED ITEM: VACUUM DEGASSED / SULPHIDE SHAPE CONTROL

C95 Further information about ladle treatment

ITEM NO.: 01-05

CALCIUM TREATED

C70-C99 Chemical composition % - Product analysis

B07.2 Heat	B07.1 Test No.	C	SI	MN	P	S	N	CU	MO	NI	CR	V	NB	SN	TI
459852	56930	K1	0,172	0,365	1,19	0,008	0,0059	0,018	0,005	0,026	0,025	0,000	0,000	0,000	0,001
460565	34603	K1	0,169	0,366	1,15	0,004	0,0058	0,019	0,040	0,153	0,019	0,000	0,000	0,000	0,001
460565	34606	K1	0,171	0,366	1,16	0,004	0,0061	0,018	0,040	0,155	0,018	0,000	0,000	0,000	0,001
460565	34835	K1	0,173	0,365	1,16	0,003	0,0061	0,018	0,041	0,159	0,018	0,000	0,000	0,000	0,001
460566	34468	K1	0,177	0,385	1,19	0,009	0,0072	0,034	0,010	0,050	0,031	0,001	0,000	0,001	0,004
460567	35011	K1	0,173	0,381	1,18	0,008	0,0063	0,054	0,022	0,049	0,066	0,001	0,000	0,003	0,002

A04



Manufacturer's
mark

Z01/Z02/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.



AG der Dillinger Hüttenwerke
Postfach 1580, D-66748 Dillingen/Saar
Inspection department

B. BALDAUF
Test House Manager

Inspector's stamp

Date 06.08.18

pp 1

A01

QM-System: Certification as per ISO 9001

DILLINGER

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)

A02 INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004
INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013
MATERIAL TEST REPORT (MTR)

INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004		A10 Advice of dispatch No./ Date of dispatch 645948-05.08.18	A08/ Manufacturer's order/ A03 Certificate No. 436752-003	Sheet 5 / ...
INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013				
MATERIAL TEST REPORT (MTR)				
A05 Established Inspecting body DIT	A06 Purchaser EDMONTON STEEL, EDMON	A07.1 No. 001072		

B02/ Steel design. SA516-70

B03 Any suppl. ASME-III A:2017

requirements DIL-HUE-1:R35-2018-02-12

SA20-S5

C70-C99 Chemical composition % - Product analysis

B07.2 Heat	B07.1 Test No.	C01			
		B	CA	AL-T	
459852	56930	K1 0,0001	0,0011	0,030	
460565	34603	K1 0,0000	0,0010	0,036	
460565	34606	K1 0,0000	0,0011	0,035	
460565	34835	K1 0,0000	0,0011	0,034	
460566	34468	K1 0,0002	0,0012	0,058	
460567	35011	K1 0,0000	0,0016	0,041	

C94 Product analysis Carbon equivalent / Alloying restrictions

B07.2 Heat	B07.1 Test No.	C01			
		FO-02=	FO-51=	FO-55=	
459852	56930	K1 FO-02= 0,38	FO-51= 0,000	FO-55= 0,07	
460565	34603	K1 FO-02= 0,38	FO-51= 0,000	FO-55= 0,23	
460565	34606	K1 FO-02= 0,39	FO-51= 0,000	FO-55= 0,23	
460565	34835	K1 FO-02= 0,39	FO-51= 0,000	FO-55= 0,24	
460566	34468	K1 FO-02= 0,39	FO-51= 0,001	FO-55= 0,13	
460567	35011	K1 FO-02= 0,39	FO-51= 0,001	FO-55= 0,19	

C94 Carbon equivalent formula / Alloying restrictions

FO-02 = $C + (Mn/6) + (Cr+Mo+V)/5 + (Ni+Cu)/15$

FO-51 = V + NB

FO-55 = CU+MO+NI+CR

FO-78 = CR+MO

FO-91 = MN/C

A04



Manufacturer's
mark

Z01/Z02/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.

B. Baldauf

B. BALDAUF
Test House Manager



AG der Dillinger Hüttenwerke
Postfach 1580, D-66748 Dillingen/Saar
Inspection department

Inspector's stamp

Date 06.08.18

PD 1

A01

WELDING PROCEDURE SPECIFICATION NO.: STS-4 (Rev. 0)

WELDING PROCEDURE QUALIFICATION RECORD NO.(S): STS-4-1 (Rev. 0),
STS-4-2 (Rev. 0),
WFL-4-1 (Rev.1)

QUALIFIED IN ACCORDANCE WITH ASME SECTION IX FOR

Base Metal (Typical): P1 Groups 1 & 2 to P1 Groups 1 & 2
(SA 333 Gr. 6, SA 350 Gr. LF2, SA 420 Gr. WPL6, SA 516 Gr. 70 etc.)
Process(es): SMAW Weld Types: GROOVE & FILLET
Position: ALL POSITIONS Diameter: ALL DIAMETERS
Filler Metal: E6010, E7018-1


BASE METAL CONDITIONS & GROOVE THICKNESS RANGE QUALIFIED:

NOTCH TOUGHNESS APPLICATIONS TO -50 °F AS WELDED

BASE METAL THICKNESS RANGE 0.116 to 1.750 in. inclusive

COMBINED DEPOSITED WELD METAL THICKNESS

ASME IX 1.750 in. maximum
API 650, 620, 12D, 12F 1.750 in. maximum




This WPS was prepared to the requirements of ASME Section IX 2017 and includes some of the additional requirements of the construction codes listed. The application of this WPS is outside the work scope of SGS Canada Inc.

Prepared By: Sara Van Roestel

Signed: 

Date: April 8, 2019

Reviewed By: Keelan Wolfe, C.E.T.

Signed: 

Date: April 8, 2019

(File E19-00104)

QW-482 WELDING PROCEDURE SPECIFICATION (WPS)

Organization Name Storage Tank Solutions Inc.
Welding Procedure Specification No. STS-4 (Rev. 0) Date April 8, 2019
Revision(s) Rev. 0: Essential - Addition of PQR No.'s STS-4-1 (Rev.0) and STS-4-2 (Rev.0).
Updated to current code requirements. WPS No. formerly WFL-4 (Rev.1).
Supporting PQR No.(s) STS-4-1 (Rev. 0), STS-4-2 (Rev. 0), WFL-4-1 (Rev.1)
Welding Process(es) Shielded Metal Arc Welding (SMAW)

JOINTS (QW-402)

Joint Design All ASME groove & fillet, reference construction drawing for joint details.
Where joint details are not specified, refer to figures 1 to 15 attached
Root Opening As per attached typical groove designs, see figures 1 to 15 attached
Backing With or without Retainers With or without

BASE METALS (QW-403)

P-Number P1 Groups 1 & 2 To P-Number P1 Groups 1 & 2
Thickness Range: Groove 0.116 to 1.750 in. inclusive
Fillet 0.116 to 8.00 in. inclusive
Pipe Diameter Ranges: Groove All diameters
Fillet All diameters
Deposited Weld Metal (Per Pass) E6010: 0.188 in. maximum
E7018-1: 0.188 in. maximum

FILLER METALS (QW-404)

	SMAW	SMAW
Specification No. (SFA)	<u>SFA 5.1</u>	<u>SFA 5.1</u>
AWS No. (Class)	<u>E6010</u>	<u>E7018-1</u>
F-No.	<u>F3</u>	<u>F4</u>
A-No.	<u>A1</u>	<u>A1</u>
Diameter	<u>3/32 to 3/16 in. inclusive</u>	<u>3/32 to 1/4 in. inclusive</u>
Deposited Weld Metal Thickness Range:		
Groove	<u>0.188 in. max. (1)</u>	<u>1.750 in. max. (1)</u>
Fillet	<u>All fillet sizes (2)</u>	<u>All fillet sizes</u>
(1)	<u>Combined deposited weld metal thickness shall not exceed 1.750 in.</u>	
(2)	<u>E6010 is restricted to a single pass for fillet weld applications requiring an MDMT less than -20 °F.</u>	

POSITION (QW-405)

Position of Groove All positions Position of Fillet All positions
Weld Progression E6010: Vertical down E7018-1: Vertical down

PREHEAT (QW-406)

Preheat Temperature (Minimum) See attached preheat sheet prior to welding.
Interpass Temperature (Maximum) 500 °F
Preheat Maintenance See attached preheat sheet prior to welding. Preheat maintenance is not required if welding is interrupted or after the completion of welding unless required by the code of construction.

WPS NO. STS-4 (Rev. 0)

POSTWELD HEAT TREATMENT (QW-407)

With or Without Without
 Temperature Range N/A Time Range N/A

ELECTRICAL CHARACTERISTICS (QW-409)

Current Direct Polarity Reverse, electrode positive
 Amps See Table 1 Volts See Table 1
 Maximum Heat Input

Base Metal Thickness Range	E6010 Electrode	E7018-1 Electrode
0.125 - 0.624 in.	29,302 J/in.	36,800 J/in.
0.625 in. and greater	30,191 J/in.	36,800 J/in.

TECHNIQUE (QW-410)

Manual or Automatic Manual
 String or Weave E6010: String E7018-1: String or weave
 Initial & Interpass Cleaning Brushing, chipping or grinding as required
 Method of Back Gouging Air carbon arc, back-grind as required
 Multiple or Single Pass Per Side Multiple
 Peening Not permitted
 Use of Thermal Process N/A
 Travel Speed See Table 1

TABLE 1 - WELDING PARAMETERS

Process	Filler Metal	Diameter in.	Current Type & Polarity	Amperage Range	Voltage Range	Travel Speed i.p.m.
SMAW	E6010	3/32	DCRP	50 - 100	18 - 32	1.8 - 18
SMAW	E6010	1/8	DCRP	60 - 140	19 - 32	2.3 - 20
SMAW	E6010	5/32	DCRP	115 - 250	21 - 32	4.8 - 20
SMAW	E6010	3/16	DCRP	120 - 300	21 - 32	5.1 - 20
SMAW	E7018-1	3/32	DCRP	60 - 110	18 - 26	1.8 - 20
SMAW	E7018-1	1/8	DCRP	90 - 170	19 - 28	2.8 - 20
SMAW	E7018-1	5/32	DCRP	110 - 220	20 - 30	3.6 - 22
SMAW	E7018-1	3/16	DCRP	160 - 320	20 - 30	5.3 - 25
SMAW	E7018-1	7/32	DCRP	240 - 340	20 - 32	7.9 - 25
SMAW	E7018-1	1/4	DCRP	275 - 360	21 - 32	9.5 - 25

Note: Welding parameters shall be adjusted to ensure that the maximum heat input value specified in QW-409 above is not exceeded.
 Heat Input (joules per inch) = (Amperage X Voltage X 60) / Travel Speed (i.p.m.)

TYPICAL JOINT DESIGNS




Figure 1
Single Square Butt




Figure 2
Single Square Butt with Backing Strip




Figure 3
Double Square Butt




Figure 4
Single Vee Butt




Figure 5
Single Vee Butt with Backing Strip




Figure 6
Double Vee Butt




Figure 7
Single U Butt




Figure 8
Single U Butt with Backing Strip




Figure 9
Double U Butt




Figure 10
Single J Butt




Figure 11
Single J Butt with Backing Strip




Figure 12
Double J Butt




Figure 13
Single Bevel Butt




Figure 14
Single Bevel Butt with Backing Strip




Figure 15
Double Bevel Butt

Additional joint designs and internal misalignment on circumferential welds shall be within the dimensional limits stated on the approved construction drawing and/or the engineering design.

PREHEAT**P-No. 1****LARGE, WELDED, LOW-PRESSURE STORAGE TANKS IN ACCORDANCE WITH
API 620 Twelfth Edition**

THICKNESS OF THE THICKER PLATE	MINIMUM PREHEAT TEMPERATURE	
	P1 Group 1	P1 Group 2
0 to 1.25 in.	32 °F	50 °F
Greater than 1.25 in to 1.50 in.	200 °F	200 °F
Greater than 1.50 in.	200 °F	200 °F

- No welding of any kind shall be performed when the surfaces to be welded are wet with rain snow or ice; when rain or snow is falling on such surfaces; or during periods of high winds unless the welder and the work are properly shielded.

- Preheat shall be applied when the metal temperature is below the temperature required by Table 6-2 (summarized above). In that case the base metal shall be heated to at least the temperature indicated within 3 in. of the place where welding is to be started and maintained 3 in. ahead of the arc. Material P-Number and Group Number shall be as designated in ASME IX or in API 630 6.7.2 for materials not listed in ASME IX.

**WELDED TANKS FOR OIL STORAGE IN ACCORDANCE WITH
API 650 Twelfth Edition**

THICKNESS OF THE THICKER PLATE	MINIMUM PREHEAT TEMPERATURE	
	Material Group I, II, III, and IIIA	Material Group IV, IVA, V & VI
0 to 1.25 in.	32 °F	50 °F
Greater than 1.25 in to 1.50 in.	200 °F	200 °F
Greater than 1.50 in.	200 °F	200 °F

- No welding of any kind shall be performed when the surfaces to be welded are wet with rain snow or ice; when rain or snow is falling on such surfaces; or during periods of high winds unless the welder and the work are properly shielded.

- Preheat shall be applied when metal temperature is below the temperature required by table 7-1 (summarized above) for the base metals being joined, and metal shall be heated to at least the temperature indicated within 3 in. of the place where welding is to be started and maintained 3 in. ahead of the arc. Material Groups shall be as designated in Table 4.4

**WELDED STORAGE TANKS IN ACCORDANCE WITH
API 12D Eleventh Edition and API 12F Twelfth Edition**

THICKNESS OF THE THICKER PLATE	MINIMUM PREHEAT TEMPERATURE
0 to 1.25 in.	50 °F
Greater than 1.25 in to 1.50 in.	200 °F
Greater than 1.50 in.	200 °F

- No welding of any kind shall be performed when the surfaces to be welded are wet with rain snow or ice; when rain or snow is falling on such surfaces; or during periods of high winds unless the welder and the work are properly shielded.

- Preheat shall be applied when the metal temperature is below the temperature required by the table above. In that case the base metal shall be heated to at least the temperature indicated within 3 in. of the place where welding is to be started and maintained 3 in. ahead of the arc.

QW-483 PROCEDURE QUALIFICATION RECORD (PQR)

Organization Name Storage Tank Solutions Inc.
Procedure Qualification Record No. STS-4-1 (Rev. 0) Date February 21, 2019
Welding Process(es) Shielded Metal Arc Welding (SMAW)

JOINTS (QW-402)

Joint Design Butt joint, single vee groove, see next page
Root Opening See next page
Backing Without Retainers Without

BASE METALS (QW-403)

Material Specification No. SA 333 to SA 350 Type or Grade Gr. 6 to Gr. LF2
Heat Treat Condition (1) SA 333 Gr. 6: Quenched/Tempered SA 350 Gr. LF2: Normalized
P-No. P1 Group 1 To P-No. P1 Group 2 Thickness 0.232 in.
Heat Number 44391 to A50A8 Carbon Equivalent (2) 0.21 to 0.40
Diameter 6.625 in. O.D.
Other Schedule 40 pipe machined to 0.232 in. wall thickness
Deposited Weld Metal (Per Pass) Did not exceed 0.094 in. for E6010,
and 0.125 in. for E7018-1

- (1) Condition of base metal prior to welding.
(2) Per CSA Z662 Carbon Equivalent formula. See chemical composition of
heat / ladle analysis on attached material test reports.

FILLER METALS (QW-404)

	SMAW	SMAW
Specification No. (SFA)	<u>SFA 5.1</u>	<u>SFA 5.1</u>
AWS No. (Class)	<u>E6010 (3)</u>	<u>E7018-1 (4)</u>
F-No.	<u>F3</u>	<u>F4</u>
A-No.	<u>A1</u>	<u>A1</u>
Diameter	<u>See attached sketch</u>	
Deposited Weld Metal Thickness	<u>0.094 in.</u>	<u>0.138 in.</u>

(3) The Lincoln Electric Company: Fleetweld 5P+
(4) ESAB: OK 55.00

POSITION (QW-405)

Position of Groove 5G
Weld Progression E6010: Vertical down E7018-1: Vertical down

PREHEAT (QW-406)

Preheat Temperature 50 °F Interpass Temp. (Max.) 400 °F
Preheat Maintenance Weld was allowed to cool to ambient temperature in still air after
welding was completed.

POSTWELD HEAT TREATMENT (QW-407)


With or Without Without
Temperature N/A Time N/A

ELECTRICAL CHARACTERISTICS (QW-409)

Current Direct Polarity Reverse, electrode positive
 Amps See below Volts See below
 Heat Input E6010: 29,302 J/in. maximum E7018-1: 36,800 J/in. maximum

TECHNIQUE (QW-410)

Manual or Automatic Manual
 String or Weave E6010: String E7018-1: Weave
 Initial & Interpass Cleaning Brushing, chipping and grinding as required
 Method of Back Gouging Not conducted
 Multiple or Single Pass Per Side E6010: Single E7018-1: Multiple
 Peening Not conducted
 Use of Thermal Process N/A
 Travel Speed See below



Pass	Process	Filler Metal	Diameter in.	Current Type & Polarity	Amperage Range	Voltage Range	Travel Speed i.p.m.
1	SMAW	E6010	1/8	DCEP	74 - 94	24 - 26	4.3
2	SMAW	E7018-1	3/32	DCEP	88 - 92	23 - 25	5.7
3	SMAW	E7018-1	3/32	DCEP	90 - 94	23 - 25	3.6

PQR NO. STS-4-1 (Rev. 0)

CHARPY V-NOTCH IMPACT TEST

Type of Test Charpy V-Notch Orientation Transverse

Governing Specification	Notch Location	Specimen Size in.	Test Temperature °F	Specimen Number	Impact Values ft•lbf
ASME B31.3 - 2016	Weld metal within 1/16 in. of root	0.394 x 0.197	-50	J2.1	28
				J2.2	19
				J2.3	35
ASME B31.3 - 2016	Gr. 6 - HAZ	0.394 x 0.197	-50	J3.1	50
				J3.2	9
				J3.3	39
ASME B31.3 - 2016	Gr. LF2 - HAZ	0.394 x 0.197	-50	J4.1	21
				J4.2	85
				J4.3	98

OTHER TESTS

Vickers Hardness - see attached Laboratory Test Report No.: E19-104.10

Welder's Name Aaron Smedsrud Certificate File No. W-28887
Welder's Name Christopher Jaques Certificate File No. N/A
Tests Conducted By SGS Canada Inc.
Laboratory Test No. E19-104.10

We certify the statements in this record are correct and that the test welds were prepared, welded and tested in accordance with the requirements of Section IX of the ASME Code.

Organization Storage Tank Solutions Inc.

Date January 21, 2021 Print Sebastien Ouellet

Signed 

QW-483 PROCEDURE QUALIFICATION RECORD (PQR)

Organization Name Storage Tank Solutions Inc.
Procedure Qualification Record No. STS-4-2 (Rev.0) Date February 21, 2019
Welding Process(es) Shielded Metal Arc Welding (SMAW)

JOINTS (QW-402)

Joint Design Butt joint, single vee groove, see next page
Root Opening See next page
Backing Without Retainers Without

BASE METALS (QW-403)

Material Specification No. SA 516 Type or Grade Gr. 60/70
Heat Treat Condition (1) SA 516 Gr. 60/70: Normalized
P-No. P1 Groups 1/2 To P-No. P1 Groups 1/2 Thickness 0.875 in.
Heat Number 449291 55060-03 Carbon Equivalent (2) 0.37
Diameter N/A Other Plate product form
Deposited Weld Metal (Per Pass) Did not exceed 0.094 in. for E6010,
and 0.125 in. for E7018-1

- (1) Condition of base metal prior to welding.
(2) Per CSA Z662 Carbon Equivalent formula. See chemical composition of heat analysis on attached material test report

FILLER METALS (QW-404)

	SMAW	SMAW
Specification No. (SFA)	<u>SFA 5.1</u>	<u>SFA 5.1</u>
AWS No. (Class)	<u>E6010 (3)</u>	<u>E7018-1 (4)</u>
F-No.	<u>F3</u>	<u>F4</u>
A-No.	<u>A1</u>	<u>A1</u>
Diameter	<u>See attached sketch</u>	
Deposited Weld Metal Thickness	<u>0.094 in.</u>	<u>0.781 in.</u>
(3)	<u>The Lincoln Electric Company: Fleetweld 5P+</u>	
(4)	<u>ESAB: OK 55.00</u>	

POSITION (QW-405)

Position of Groove 3G
Weld Progression E6010: Vertical down E7018-1: Vertical down

PREHEAT (QW-406)

Preheat Temperature 50 °F Interpass Temp. (Max.) 500 °F
Preheat Maintenance Weld was allowed to cool to ambient temperature in still air after welding was completed.

POSTWELD HEAT TREATMENT (QW-407)

With or Without Without
Temperature N/A Time N/A


PQR NO. STS-4-2 (Rev.0)

ELECTRICAL CHARACTERISTICS (QW-409)

Current	<u>Direct</u>	Polarity	<u>Reverse, electrode positive</u>
Amps	<u>See next page</u>	Volts	<u>See next page</u>
Heat Input	<u>E6010: 30,191 J/in. maximum</u>		<u>E7018-1: 31,543 J/in. maximum</u>

TECHNIQUE (QW-410)

Manual or Automatic	<u>Manual</u>	
String or Weave	<u>E6010: String</u>	<u>E7018-1: Weave</u>
Initial & Interpass Cleaning	<u>Brushing, chipping and grinding as required</u>	
Method of Back Gouging	<u>Not conducted</u>	
Multiple or Single Pass Per Side	<u>E6010: Single</u>	<u>E7018-1: Multiple</u>
Peening	<u>Not conducted</u>	
Use of Thermal Process	<u>N/A</u>	
Travel Speed	<u>See next page</u>	



Pass	Process	Filler Metal	Diameter in.	Current Type & Polarity	Amperage Range	Voltage Range	Travel Speed i.p.m.
1	SMAW	E6010	1/8	DCEP	80 - 84	26 - 28	4.4
2	SMAW	E7018-1	3/32	DCEP	82 - 86	21 - 23	6.7
3	SMAW	E7018-1	3/32	DCEP	84 - 88	21 - 23	6.4
4	SMAW	E7018-1	1/8	DCEP	158 - 162	22 - 24	7.3
5	SMAW	E7018-1	1/8	DCEP	158 - 162	22 - 24	7.0
6	SMAW	E7018-1	1/8	DCEP	158 - 162	22 - 24	9.5
7	SMAW	E7018-1	1/8	DCEP	158 - 162	22 - 24	8.8
8	SMAW	E7018-1	1/8	DCEP	158 - 168	22 - 24	13.3
9	SMAW	E7018-1	1/8	DCEP	158 - 168	22 - 24	16.0
10	SMAW	E7018-1	1/8	DCEP	158 - 168	22 - 24	15.7
11	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	13.3
12	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	14.1
13	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	13.3
14	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	9.2
15	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	12.6
16	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	14.4
17	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	12.6
18	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	11.8
19	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	11.1
20	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	13.6
21	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	12.9
22	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	10.0
23	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	13.1
24	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	12.9
25	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	11.3
26	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	12.6
27	SMAW	E7018-1	1/8	DCEP	158 - 162	21 - 23	14.1

PQR NO. STS-4-2 (Rev.0)

TENSILE TEST (QW-150)

Sample No.	Width in.	Thickness in.	Area sq. in.	Ultimate Load lbf	Ultimate Stress psi	Fracture Type & Location
T1	0.752	0.850	0.639	50,600	79,200	Partial Cup & Cone Parent Metal
T2	0.752	0.870	0.654	51,780	79,200	Partial Cup & Cone Parent Metal

GUIDED BEND TEST (QW-160)

Type & Figure No.	Result	Type & Figure No.	Result
QW-462.2, TSB - S1	Pass	QW-462.2, TSB - S3	Pass
QW-462.2, TSB - S2	Pass	QW-462.2, TSB - S4	Pass

CHARPY V-NOTCH IMPACT TEST

Type of Test Charpy V-Notch Orientation Transverse

Governing Specification	Notch Location	Specimen Size in.	Test Temperature ° F	Specimen Number	Impact Values ft•lbf
ASME B31.3 - 2016	Weld metal within 1/16 in. of root	0.394 x 0.394	-50	K2.1	56
				K2.2	55
				K2.3	18
ASME B31.3 - 2016	HAZ	0.394 x 0.394	-50	K3.1	149
				K3.2	81
				K3.3	61

OTHER TESTS

Vickers Hardness - see attached Laboratory Test Report No.: E19-104.10

Welder's Name Aaron Smedsrud Certificate File No. W-28887
Welder's Name Christopher Jaques Certificate File No. N/A
Tests Conducted By SGS Canada Inc.
Laboratory Test No. E19-104.10

We certify the statements in this record are correct and that the test welds were prepared, welded and tested in accordance with the requirements of Section IX of the ASME Code.

Organization Storage Tank Solutions Inc.

Date January 21, 2021 Print Sebastien Ouellet

Signed 

QW-483 PROCEDURE QUALIFICATION RECORD (PQR)

Company Name Storage Tank Solutions Inc.
Procedure Qualification Record No. WFL-4-1 (Rev.1) Date May 2, 2007
Revision(s) Rev.1 - Essential. Addition of deposited weld metal per pass, update to
manufacturer's certifying statement, and corporate name change, formerly
Woodside Fabricators Ltd. September 7, 2018.
Welding Process(es) SMAW Type(s) Manual

JOINTS (QW-402)

Type Butt joint, single vee groove, see next page

BASE METALS (QW-403)

Material Spec. SA 516 to SA 516 Type or Grade Gr. 60 to Gr.70
P-No. P1 Grp.1 To P-No. P1 Grp.2 Thickness 6.32 mm (0.249 in.)
Diameter N/A Other Plate Product Form m/c to 0.249 in.
Deposited Weld Metal (Per Pass) Did not exceed 0.50 in.

FILLER METALS (QW-404)

Specification No. (SFA)	<u>SFA 5.1</u>	<u>SFA 5.1</u>
AWS No. (Class)	<u>E6010</u>	<u>E7018-1</u>
Filler Metal F-No.	<u>F3</u>	<u>F4</u>
Filler Metal A-No.	<u>A1</u>	<u>A1</u>
Size of Electrode	<u>See attached sketch</u>	
Deposited Weld Metal Thickness	<u>2.39 mm (0.094 in.)</u>	<u>3.94 mm (0.155 in.)</u>

POSITION (QW-405)

Position of Groove 3G
Weld Progression Vertical down

PREHEAT (QW-406)

Preheat Temperature 10°C (50°F) Interpass Temp. (Max.) 232°C (450°F)

POSTWELD HEAT TREATMENT (QW-407)


Temperature N/A Time N/A

ELECTRICAL CHARACTERISTICS (QW-409)

Current	<u>Direct</u>	Polarity	<u>Reverse, electrode positive</u>
Amps	<u>See next page</u>	Volts	<u>See next page</u>
Heat Input	<u>F3: 20,330 J/in. maximum</u>		<u>F4: 20,070 J/in. maximum</u>

TECHNIQUE (QW-410)

String or Weave	<u>Root: String</u>	<u>Remainder: Weave</u>
Travel Speed	<u>See next page</u>	
Multiple or Single Pass Per Side	<u>F3: Single</u>	<u>F4: Multiple</u>



Pass	Process	Filler Metal	Diameter mm (in.)	Current & Polarity	Amperage Range	Voltage Range	Travel Speed mm/min (i.p.m.)
1	SMAW	E6010	3.2 (1/8)	DCRP	85 - 87	24 - 25	158 (6.2)
2	SMAW	E7018-1	3.2 (1/8)	DCRP	140 - 145	21 - 22	233 (9.2)
3	SMAW	E7018-1	3.2 (1/8)	DCRP	140 - 145	21 - 22	282 (11.1)
4	SMAW	E7018-1	3.2 (1/8)	DCRP	140 - 145	21 - 22	275 (10.8)

PQR NO. WFL-4-1 (Rev.1)**TENSILE TEST (QW-150)**

Specimen No.	Width mm (in.)	Thickness mm (in.)	Area Sq. mm (Sq. in.)	Ultimate Load N (lbs.)	Ultimate Stress MPa (psi)	Character & Fracture Location
T1	19.0 (0.748)	4.74 (0.185)	49.5 (0.139)	46 874 (10,500)	524 (76,000)	Partial Cup & Cone Parent Metal (SA 516 Gr.70)
T2	19.0 (0.748)	4.88 (0.192)	92.7 (0.144)	47 904 (10,800)	517 (74,900)	Partial Cup & Cone Weld Metal

GUIDED BEND TEST (QW-160)

Type & Figure No.	Result	Type & Figure No.	Result
QW-462.3a, TRB - R1	Pass	QW-462.3a, TFB - F1	Pass
QW-462.3a, TRB - R2	Pass	QW-462.3a, TFB - F2	Pass

CHARPY IMPACT TOUGHNESS

Type of Test Charpy V Notch Orientation Transverse
 Test Temperature -48° C (-55° F) Specimen Size 10 X 5 mm

Specimen No.	Notch Location	Impact Values J (ft. lbs)
W2.1	Weld Metal	10.8 (8.0)
W2.2	Weld Metal	25.2 (18.6)
W2.3	Weld Metal	30.1 (22.2)
W3.1	P1 Grp.1 - HAZ	15.7 (11.6)
W3.2	P1 Grp.1 - HAZ	77.6 (57.2)
W3.3	P1 Grp.1 - HAZ	93.8 (69.2)
W4.1	P1 Grp.2 - HAZ	55.6 (41.0)
W4.2	P1 Grp.2 - HAZ	64.0 (47.2)
W4.3	P1 Grp.2 - HAZ	38.0 (28.0)

OTHER TESTS

Vickers Hardness - see attached laboratory test report

Welders Name Kyle Maser Certificate File No. N/A
 Tests Conducted By Ludwig & Associates Ltd.
 Laboratory Test No. E07-393.12

We hereby recertify that the statements in this record have been revised in accordance with Paragraph QW-200.2 and that the test welds were prepared, welded and tested in accordance with the requirements of Section IX of the ASME Code.

Manufacturer Storage Tank Solutions Inc.

Date January 21, 2021 Signed 

CHARPY V-NOTCH IMPACT TEST

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6

Laboratory Test No.: E19-104.10
Date: March 15, 2019

Attention: Sebastien Ouellet

PQR No.:	STS-4-1 (Rev.0)	Material Heat No.:	44391 to A50A8
Material:	SA 333 Gr. 6 to SA 350 Gr. LF2		
Material Size:	168 mm (6.625 in.) O.D. x 5.89 mm (0.232 in.) w.t.		
Thermal Condition:	As Welded		

Specimen Size: 10 x 5 mm (0.394 x 0.197 in.)
Orientation: Transverse
Test Temperature: -46 °C (-50 °F)
Governing Spec.: ASME B31.3-2016

Machine: Satec SI-1K3, S/N: 1503
Capacity: 407 J (300 ft-lbf)
Verified Range: 3.4-325J (2.5-240 ft-lbf)
Calibration Date: March 19, 2018

Specimen Number	Notch Location	Impact Values	
		Joules	(ft-lbf)
J2.1	Weld Metal within 1.5mm (1/16") of root	38	(28)
J2.2		26	(19)
J2.3		47	(35)
J3.1	SA 333 Gr. 6 - HAZ	68	(50)
J3.2		12	(9)
J3.3		53	(39)
J4.1	SA 350 Gr. LF2 - HAZ	28	(21)
J4.2		115	(85)
J4.3		133	(98)

Note: Metric values calculated by direct conversion.

Test Conducted By: Tong Zhao (Edmonton)

Certified By:

Eric Dacyk, C.E.T.



This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.

HARDNESS TEST

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6


Laboratory Test No.: E19-104.10
Date: March 15, 2019

Attention: Sebastien Ouellet

PQR No.:	STS-4-1 (Rev.0)	Material Heat No.:	44391 to A50A8
Material:	SA 333 Gr. 6 to SA 350 Gr. LF2		
Material Size:	168 mm (6.625 in.) O.D. x 5.89 mm (0.232 in.) w.t.		
Thermal Condition:	As Welded		

Type of Test: Vickers 10 kg (HV10)
Governing Spec.: ASTM E92 - 17 &
ANSI/NACE MR0175/ISO 15156:2015

Instrument: LECO S/N: 1594
Calibration Date: July 27, 2018



SA 350 Gr. LF2				Weld Metal		SA 333 Gr. 6			
Parent Metal		HAZ				HAZ		Parent Metal	
1	148	3	185	11	194	19	189	27	175
2	156	4	196	12	193	20	157	28	170
		5	190	13	186	21	194		
		6	169	14	182	22	194		
		7	180	15	186	23	185		
		8	182	16	185	24	161		
		9	171	17	163	25	160		
		10	181	18	162	26	170		

Test Conducted By: Tong Zhao (Edmonton)

Certified By: 
Eric Dacyk, C.E.T.



This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.



TENSILE / BEND TEST

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6

Laboratory Test No.: E19-104.11
Date: March 18, 2019

Attention: Sebastien Ouellet

PQR No.:	STS-4-2 (Rev.0)	Material Heat No.:	454840 27789-02
Material:	SA 516 Gr. 60/70		
Material Thickness:	22.2 mm (0.875 in.)		
Thermal Condition:	As Welded		

Governing Spec.: ASME Section IX - 2017

Instrument: Tinius Olsen S/N: 133660

SAMPLE NO.(QW-150)	T1	T2
WIDTH mm (in.)	19.1 (0.752)	19.1 (0.752)
THICKNESS mm (in.)	21.6 (0.850)	22.1 (0.870)
AREA sq. mm (sq. in.)	413 (0.639)	422 (0.654)
ULTIMATE LOAD N (lbf)	225 179 (50,600)	230 525 (51,800)
ULTIMATE STRESS MPa (psi)	546 (79,200)	546 (79,200)
FRACTURE TYPE	Partial Cup & Cone	Partial Cup & Cone
FRACTURE LOCATION	Parent Metal	Parent Metal

Note: Imperial values calculated by direct conversion.

SAMPLE TYPE(QW-462.2)	Side Bend	Side Bend	Side Bend	Side Bend
SAMPLE NO.	S1	S2	S3	S4
RESULTS	Pass	Pass	Pass	Pass

Test Conducted By: Ibrahim Mohamoud (Edmonton)

Certified By:

Eric Dacyk, C.E.T.



This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.

CHARPY V-NOTCH IMPACT TEST

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6

Laboratory Test No.: E19-104.11
Date: March 21, 2019

Attention: Sebastien Ouellet

PQR No.:	STS-4-2 (Rev.0)	Material Heat No.:	454840 27789-02
Material:	SA 516 Gr. 60/70		
Material Thickness:	22.2 mm (0.875 in.)		
Thermal Condition:	As Welded		

Specimen Size: 10 x 10 mm (0.394 x 0.394 in.)
Orientation: Transverse
Test Temperature: -46 °C (-50 °F)
Governing Spec.: ASME B31.3-2016

Machine: Satec SI-1K3, S/N: 1503
Capacity: 407 J (300 ft-lbf)
Verified Range: 3.4-325J (2.5-240 ft-lbf)
Calibration Date: March 19, 2018

Specimen Number	Notch Location	Impact Values	
		Joules	(ft-lbf)
K2.1	Weld Metal within 1.5mm (1/16") of root	76	(56)
K2.2		75	(55)
K2.3		24	(18)
K3.1	HAZ within 1/4 to 1/2t of weld surface	202	(149)
K3.2		110	(81)
K3.3		83	(61)

Note: Metric values calculated by direct conversion.

Test Conducted By: Tong Zhao (Edmonton)

Certified By: 

Eric Dacyk, C.E.T.



This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.

HARDNESS TEST

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6


Laboratory Test No.: E19-104.11
Date: March 12, 2019

Attention: Sebastien Ouellet

PQR No.:	STS-4-2 (Rev.0)	Material Heat No.:	454840 27789-02
Material:	SA 516 Gr. 60/70		
Material Thickness:	22.2 mm (0.875 in.)		
Thermal Condition:	As Welded		

Type of Test: Vickers 10 kg (HV10)
Governing Spec.: ASTM E92 - 17

Instrument: LECO S/N: 1594
Calibration Date: July 27, 2018



Parent Metal		HAZ		Weld Metal		HAZ		Parent Metal	
1	152	3	308	11	206	19	277	27	152
2	148	4	317	12	181	20	255	28	143
		5	263	13	203	21	245		
		6	182	14	192	22	208		
		7	198	15	186	23	194		
		8	185	16	193	24	192		
		9	190	17	173	25	180		
		10	191	18	173	26	194		

Test Conducted By: Ibrahim Mohamoud (Edmonton)

Certified By:


Eric Dacyk, C.E.T.



This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.



LUDWIG & ASSOCIATES LTD.

Materials and Welding Consulting

LABORATORY TEST REPORT

CUSTOMER: Woodside Fabricators Ltd.
6124 - 39th Ave
Camrose, Alberta
T4V 3B1

Laboratory Test No.: E07-393.12
Date: May 7, 2007

Attention: Doug French

PQR No.: WFL-4-1
Material: SA 516 Gr. 60 to SA 516 Gr. 70
Thickness: 6.32 mm (0.249 in.)
Thermal Condition: As Welded

TENSILE TEST QW-150

SAMPLE NUMBER	T1	QW-462.1(a)	T2	QW-462.1(a)
WIDTH mm (in.)	19.0	(0.748)	19.0	(0.748)
THICKNESS mm (in.)	4.71	(0.185)	4.88	(0.192)
AREA sq. mm (sq. in.)	49.5	(0.139)	92.7	(0.144)
ULTIMATE LOAD N (lbs)	46 874	(10,500)	47 904	(10,800)
UTS MPa (psi)	524	(76,000)	517	(74,900)
FRACTURE TYPE	Partial Cup & Cone		Partial Cup & Cone	
FRACTURE LOCATION	Parent Metal (SA 516 Gr. 70)		Weld Metal	

GUIDED-BEND TEST QW-160

SAMPLE WIDTH:	38.1 mm (1.50 in.)	SAMPLE THICKNESS:	6.32 mm (0.249 in.)
PLUNGER SIZE:	22.2 mm (0.875 in.)	YOKE SIZE:	41.1 mm (1.62 in.)
QW-462.3(a)	Face Bend	Face Bend	Root Bend
SAMPLE NUMBER(S)	F1	F2	R1
RESULTS	Pass	Pass	Pass

We certify the test results in this report and that the specimen(s) were prepared and tested in accordance with the requirements of ASME Section IX, 2004 edition and latest addenda. Material information has been provided by the Customer whose name appears on this report.

Samples associated with this report will be discarded in 30 days.

Laboratory Test Conducted By: Natashua Collier, C.E.T.



LUDWIG & ASSOCIATES LTD.

Materials and Welding Consulting

LABORATORY TEST REPORT

CUSTOMER: Woodside Fabricators Ltd.
6124 - 39th Ave
Camrose, Alberta
T4V 3B1

Laboratory Test No.: E07-393.12
Date: May 7, 2007

Attention: Doug French

PQR No.: WFL-4-1
Material: SA 516 Gr. 60 to SA 516 Gr. 70
Thickness: 6.32 mm (0.249 in.)
Thermal Condition: As Welded

NOTCH-TOUGHNESS TEST

TYPE OF TEST: Charpy V-Notch
TEST TEMPERATURE: -48°C (-55°F)

ORIENTATION: Transverse
SPECIMEN SIZE: 10 x 5 mm

Specimen Number	Notch Location	Impact Values	
		Joules	(ft.lbs)
W2.1	Weld Metal within 1/16" of root	10.8	(8.0)
W2.2	Weld Metal within 1/16" of root	25.2	(18.6)
W2.3	Weld Metal within 1/16" of root	30.1	(22.2)
W3.1	Gr. 60 - HAZ	15.7	(11.6)
W3.2	Gr. 60 - HAZ	77.6	(57.2)
W3.3	Gr. 60 - HAZ	93.8	(69.2)
W4.1	Gr. 70 - HAZ	55.6	(41.0)
W4.2	Gr. 70 - HAZ	64.0	(47.2)
W4.3	Gr. 70 - HAZ	38.0	(28.0)

We certify the test results in this report and that the specimen(s) were prepared and tested in accordance with the requirements of ASME Section VIII, Div. I, UG-84 - 2004 edition and latest addenda. Material information has been provided by the Customer whose name appears on this report.

Samples associated with this report will be discarded in 30 days.

Laboratory Test Conducted By: _____

Natashua Collier, C.E.T.



LUDWIG & ASSOCIATES LTD.

Materials and Welding Consulting

LABORATORY TEST REPORT

CUSTOMER: Woodside Fabricators Ltd.
6124 - 39th Ave
Camrose, Alberta
T4V 3B1

Laboratory Test No.: E07-393.12
Date: May 7, 2007

Attention: Doug French


PQR No.: WFL-4-1
Material: SA 516 Gr. 60 to SA 516 Gr. 70
Thickness: 6.32 mm (0.249 in.)
Thermal Condition: As Welded

HARDNESS TEST

TYPE OF TEST: Vickers

LOAD: 10 kg

INSTRUMENT TYPE: Leco V-100-C1



1) 153 HV	7) 181 HV	13) 173 HV	19) 162 HV	25) 171 HV
2) 193 HV	8) 206 HV	14) 188 HV	20) 192 HV	26) 178 HV
3) 210 HV	9) 207 HV	15) 167 HV	21) 185 HV	27) 186 HV
4) 174 HV	10) 161 HV	16) 166 HV	22) 158 HV	28) 167 HV
5) 169 HV	11) 187 HV	17) 168 HV	23) 173 HV	29) 157 HV
6) 164 HV	12) 190 HV	18) 172 HV	24) 185 HV	

We certify the test results in this report and that the specimen(s) were prepared and tested in accordance with the requirements of ASTM E92-82 (Reapproved 2003). Material information has been provided by the Customer whose name appears on this report.

Samples associated with this report will be discarded in 30 days

Laboratory Test Conducted By:

Natashua Collier, C.E.T.



INSPECTION CERTIFICATE

(BS EN 10204 3.1: 2004 - ISO 10474 3.1: 2013)

Page / Página:

1 / 8

S. J. S. S. A. I. C.
Dr. Jorge A. Simón 259
(82) 330 4343 Campana
Buenos Aires, Argentina
(54) 3109 131103 Tel
(54) 3109 131103 Fax

Customer / Cliente: VAN LEEUWEN PIPE & TUBE (CANADA) INC.

Customer's Order Item / Orden Cliente - Item:

45001803-00008

Product Type / Tipo de Producto:

CARBON STEEL FOR LOW TEMPERATURE SERVICE

Number / Número:

853076

Date / Día: July 21, 2017

Manufacturer's Works Order No. / Confirmación de Venta:

51938/08

Surface / Superficie:

INT BARE / EXT VARNISHED

Ends / Extremos:

BEVELLED AT 30 DEG. ASTM

Steel Grade / Grado de acero:

A533 Gr. 61 / A533 Gr. 61

Quantity / Cantidad: 83 Pcs/pz

3157 94 FT

962.54 MTS

Length / Longitud:

11.0/11.8 m

Schedule / Cédula:

940

Dimensions / Dimensiones:

6 5/8 X 0.280 INCH

168.30 X 7.11 MM

TENSILE TEST / ENSAYO DE TENSION

Heat No. Colada No.	Sample No. Muestra No.	Zone Zona	Lot No. Lote No.	Pipe No. Tubo No.	Specimen condition Condición de la probeta		Specimen dimensions Dimensiones de la probeta		Test temp. Temp. ensayo	Y.S.		U.T.S.		Elongation / Alargamiento		Obt.
					St	Typo	Size Tamaño	Area Sectón		Min: 52	Max: 91	Req. 66	Min: 66	Lo 2"	Min.	
44391	2836124	E1	71971	20	B	AM	0.999 x 0.278	0.279	R.T.	57.2	71.1	0.80	50.8	30.8	28.0	36.6
44391	2836125	E2	71971	40	B	AM	0.995 x 0.279	0.279	R.T.	58.1	72.0	0.81	30.8	30.8	28.0	36.7
44391	2836126	E1	71971	60	B	AM	0.999 x 0.283	0.281	R.T.	60.0	73.1	0.82	30.8	30.8	28.0	39.1
44391	2836127	E2	71972	80	B	AM	0.999 x 0.279	0.280	R.T.	62.2	75.9	0.82	30.8	30.8	28.0	40.9
44391	2836129	E2	71973	1	B	AM	1. x 0.276	0.278	R.T.	59.3	73.3	0.81	30.8	30.8	28.0	36.1
44391	2836135	E1	71974	20	B	AM	0.994 x 0.277	0.277	R.T.	56.7	70.5	0.80	30.8	30.8	28.0	38.5
44391	2836139	E2	71974	40	B	AM	0.994 x 0.279	0.278	R.T.	60.3	73.3	0.82	30.8	30.8	28.0	38.5
44391	2836143	E1	71974	60	B	AM	0.999 x 0.279	0.280	R.T.	60.9	73.3	0.82	30.8	30.8	28.0	39.0
44391	2836144	E2	71975	80	B	AM	0.995 x 0.283	0.284	R.T.	59.2	73.4	0.81	30.8	30.8	28.0	38.9
44391	2837409	E1	71971	17	B	AM	0.995 x 0.274	0.274	R.T.	64.2	76.8	0.84	30.8	30.8	28.0	31.6
44391	2837410	E1	71975	85	B	AM	0.993 x 0.265	0.264	R.T.	58.2	73.6	0.79	30.8	30.8	28.0	28.8
44391	2842466	E2	71972	92	B	AM	0.994 x 0.278	0.277	R.T.	58.1	72.2	0.81	30.8	30.8	28.0	34.9
44391	2842467	E1	71973	14	B	AM	0.997 x 0.282	0.282	R.T.	59.2	73.4	0.81	30.8	30.8	28.0	38.6

JF September 18, 2017
SA 333 Gr. 61 / CSA 333 Gr. 61
Sch 40
6.625 00 x 0.280 w.t.
Heat # 44391 E6-20
PO# 186473

As manufactured / Según procesamiento		Location of sample / Ubicación de la muestra		Req. Max: Required maximum / Máximo requerido		U.T.S. Ultimate tensile strength / Resistencia	
B: Body / Cuerpo		Max: Maximum / Máximo		Req: Required / Requerido		Y.S: Yield strength / Fluencia	
F1 / F2: Ends of Sampling / Extremos de Muestra		Min: Minimum / Mínimo		RT: Room temperature / Temperatura ambiente			
L: Longitudinal / Longitudinal		Obt: Obtained / Obtenido		SC: Specimen condition / Condición de la probeta			
Lo: Initial length / Longitud inicial		Ori: Orientation / Orientación		SS: Slip specimen / Muestra rectangular			

This certificate is issued by a computerized system and it is valid with electronic signature. On the original certificate the fluid mark green colored "Tenaris" is stamped. In case the owner of the original certificate would release a copy of it, he must attest its conformity to the original one taking upon himself the responsibility for any unlawful or not allowed use. Any alteration or falsification will be subjected to the law.

Este certificado es emitido por un sistema mediante sistema computarizado y es válido con firma electrónica. El certificado original posee impreso al logo "Tenaris" color verde. En caso de que el poseedor del certificado entregue una copia, deberá garantizar la conformidad con el original haciendo responsable por cualquier uso ilegal o no autorizado. Cualquier alteración y/o falsificación estará sujeta a la ley.



INSPECTION CERTIFICATE

(BS EN 10204 3.1: 2004 - ISO 10474 3.1: 2013)

Number / Número:
853076

Page / Página:
2 / 8

Date / Día: July 21, 2017

Customer / Cliente: VAN LEEUWEN PIPE & TUBE (CANADA) INC.

Customer's Order Item / Orden Cliente - Item:
45001803-00008

Customer's Reference / Ref. del Cliente:
N/A

Product Type / Tipo de Producto:
CARBON STEEL FOR LOW TEMPERATURE SERVICE

Manufacturing Process / Proceso de Manufactura:
SEAMLESS HOT ROLLED

Standard or Specification / Normas o Especificaciones:
ASTM/ASME A533-104 CSA Z245.1-14 CATH-S5+PSP00374+NACE MR0175/103+IPRO LP-006

Dimensions / Dimensiones:
**6 5/8 X 0.280 INCH
168.30 X 7.11 MM**

Length / Longitud:
11.0/11.8 m

Weight / Peso:
**59747 LB
27101 KG**

Quantity / Cantidad: 83 Pcs/pz

Steel Grade / Grado de acero:
116/359 CAT II SS

Surface / Superficie:
INT BARE / EXT VARNISHED

Ends / Extremos:
BEVELLED AT 30 DEG. ASTM

Manufacturer's Works Order No / Confirmación de Venta:
\$1938/08

Siderca S.A.C.
Dr. Jorge A. Simón 240
Buenos Aires, Argentina
(54) 3486 433100 tel
(54) 3486 433105 fax

CHEMICAL COMPOSITION / COMPOSICION QUIMICA

		Composition % / Composición %																														
		X 100														X 1000																
		C	Mn	Si	Cr	Mo	Al sol	Cu	P	Ni	V	Al	Sn	As	Nb	Ti	Pb	Sb	Co	S	Zr	Bi	Ca	B	N	Mg	W	Ce-1	Ce-2	X 100		
II	Max	25	135	50	30	12	--	40	25	400	80	--	--	--	20	110	--	--	100	--	--	--	--	--	10	--	--	--	42	40		
	Min	--	40	10	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--		
P	Max	25	135	50	30	12	--	40	25	400	80	--	--	--	20	110	--	--	100	--	--	--	--	--	10	--	--	--	42	40		
	Min	--	40	10	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--		
Lot N°	44391	8	105	23	9	4	2	16	12	70	4	15	11	1	14	3	1	2	7	9	10	20	12	1	43	7	20	30	21	--		
	2836335	9	105	23	9	4	1	17	12	74	3	16	10	4	14	3	1	3	7	10	20	22	16	2	50	4	20	31	23	--		
Pipe N°	44391	10	105	23	9	4	1	17	12	73	3	15	10	4	16	3	1	3	7	11	20	22	16	2	48	5	20	31	21	--		
	2836326	9	106	24	9	4	2	16	13	69	5	16	10	4	14	2	1	3	7	10	20	22	12	2	45	4	20	31	21	--		
Tubo N°	44391	8	105	23	9	4	1	17	12	70	3	15	10	4	14	3	1	3	7	10	20	22	11	2	41	4	20	31	21	--		
	2837409	9	106	24	9	4	1	17	12	70	3	15	10	4	14	3	1	3	7	10	20	22	12	2	41	4	20	31	21	--		
Lot N°	44391	8	105	23	9	4	1	17	12	73	3	15	10	4	14	3	1	3	7	10	20	22	12	2	41	4	20	31	21	--		
	2836327	9	105	23	9	4	1	17	12	73	3	15	10	4	14	3	1	3	7	10	20	22	12	2	41	4	20	31	21	--		
Pipe N°	44391	8	105	23	9	4	1	17	12	73	3	15	10	4	14	3	1	3	7	10	20	22	12	2	41	4	20	31	21	--		
	2836343	9	105	23	9	4	1	17	12	73	3	15	10	4	14	3	1	3	7	10	20	22	12	2	41	4	20	31	21	--		
Tubo N°	44391	8	105	23	9	4	1	17	12	73	3	15	10	4	14	3	1	3	7	10	20	22	12	2	41	4	20	31	21	--		
	2836344	9	105	23	9	4	1	17	12	73	3	15	10	4	14	3	1	3	7	10	20	22	12	2	41	4	20	31	21	--		
Lot N°	44391	9	105	23	9	4	1	17	12	70	5	16	10	4	14	3	1	2	7	9	9	20	22	12	2	44	4	20	31	21	--	
	2837410	9	105	23	9	4	1	17	12	70	5	16	10	4	14	3	1	2	7	9	9	20	22	12	2	44	4	20	31	21	--	
Pipe N°	44391	9	105	23	9	4	1	17	12	70	5	16	10	4	14	3	1	2	7	9	9	20	22	12	2	44	4	20	31	21	--	
	2836330	10	105	23	9	4	1	16	12	74	4	17	10	4	15	3	1	3	7	10	20	22	17	2	44	4	20	31	21	--		
Tubo N°	44391	16	105	23	9	4	1	17	12	75	3	15	10	4	16	3	1	3	7	9	9	20	22	17	2	44	4	20	32	25	--	
	2836335	16	105	23	9	4	1	17	12	75	3	15	10	4	16	3	1	3	7	9	9	20	22	17	2	44	4	20	32	25	--	

Ce.1: C+(Mn/6)+Si/20+H(Cu/15)+(Ni/20)+(Cr+Mo+V+Nb/5)+
(S*8)
Ce.2: --

Min. Heat / Colada
Max. Heat / Colada
Min. Product / Producto
Max. Product / Producto

This certificate is issued by a computerized system and it is valid with electronic signature. On the original certificate the Tenaris logo and the word "Tenaris" is stamped. In case the owner of the original certificate would release a copy of it, he must attest its conformity to the original one being upon himself the responsibility for any unlawful or not allowed use. Any alteration or modification will be subjected to this law.

Este certificado se emite mediante sistema computarizado y es válido con firma electrónica. El certificado original posee impreso el logo "Tenaris". En caso de que el poseedor del certificado emita una copia, deberá garantizar la conformidad con el original haciéndose responsable por cualquier uso ilegal o indebido. Cualquier alteración o modificación estará sujeta a la ley.

CLIENTE / Customer / Client
 VAN LEEUWEN PIPE AND TUBE - CAN
 2875-64TH AVENUE
 EDMONTON - ALBERTA T6P 1R1
 CANADA
 CAN

CERTIFICADO DE INSPECCION Inspection Certificate - Certificat de Réception

UNE EN 10234-3S / 3.1
 ISO 10474-15 / 3.1

FECHA: 24/05/2018 N.º 195241
 Date: Page: 4

PRODUCTO
 Article - Produit
 FLANGES
 NORMAS APLICABLES
 Requirements - Normes Applicables
 ASME B16.5-17

SU PEDIDO N.º
 Your Order No.
 45001896

DE 10/01/2018
 of - on

MATERIAL CORRESPONDIENTE
 Material Correspondent - Matière
 ASME SA350LF2CL1-2-17, ASTM A350LF2CL1-2-17
 ASME SA105M-17, ASTM A105M-14
 MODE DE FUSION (*)
 Steel Making - Elaboration de l'acier
 E - Elec. Y - Oxígeno básico

NACE MR0175/ISO15156-02/03-15 & NACE MR0103/ISO17495-15
 Clause 7.2.1.4, Annex A.2 and SSC Region 3.
 CSA-Z245.12-17 GR248 CAT II-SS (WN & BLIND FLANGES ONLY)

PARTIDA Item Poste	CANTIDAD Quantity Quantité	DESCRIPCION Description Description	LOTE	OBSERVACIONES Remarks Observations	COLADA N.º Heat No. N.º Coulees	T. Strength Resist Rupt N/mm2	Y. Strength Resist Rupt N/mm2	ELONGATION Allongement Lo-50mm-4d %	RESILIENCIA Impact Test Resilience Joules	CHARPY V 10x10mm MATERIA Average Moyenne °C	DUREZA Hardness Dureté HBW
48 24738	20	WN 4 1500LB XXS RTJ A350LF2	18M18E	NE	A18A8	521	307	32.10	56	58	148 151
54 24625	6	WN 4 600LB XXS RF A350LF2	12A18F	NE	A41A8	513	305	29.70	68	67	148 151
54 24625	19	WN 4 600LB XXS RF A350LF2	29017	NE	B73A7	524	317	28.10	66	66	150 158
56 22171	67	WN 6 150LB STD:40 RF A350LF2	15V806	NE	A50A8	517	309	29.80	50	68	150 151
56 22171	3	WN 6 150LB STD:40 RF A350LF2	29A804	NE	A50A8	519	311	31.20	55	59	149 150
45 24672	5	BLIND 8 800LB RF A350LF2	17A817	NE	A58A8	507	255	28.20	54	50	147 149

COMPOSICION QUIMICA - STEEL MAKER'S LADLE ANALYSIS - ANALYSE CHIMIQUE

C %	Si %	Mn %	P %	S %	Cr %	Ni %	Mo %	Nb %	V %	Cu %	Al %	Ti %	B %	Ceq %
0.190	0.250	0.380	0.009	0.003	0.050	0.080	0.010	0.004	0.006	0.190	0.035	0.002	0.0004	0.39
0.190	0.250	1.060	0.006	0.004	0.050	0.070	0.010	0.003	0.004	0.180	0.031	0.001	0.0002	0.40
0.190	0.190	1.080	0.007	0.005	0.070	0.070	0.012	0.002	0.006	0.220	0.025	0.002	0.0005	0.41
0.190	0.210	1.060	0.011	0.005	0.060	0.080	0.013	0.003	0.010	0.180	0.043	0.001	0.0002	0.39
0.190	0.180	1.050	0.009	0.001	0.100	0.090	0.021	0.004	0.003	0.180	0.040	0.001	0.0005	0.41

(*) OBSERVACIONES
 Remarks
 Observations

N_NORM/LIZED AT 900 C AND ALLOWED TO COOL IN STILL AIR.

SA 350 LF2
 6.625" O.D. x 0.280 w.t.
 WN 150 RF 6 STD
 HT# A50A8
 Internal PO# E20170
 External PO# 203177

Received By: Jessie Springett
 12/09/18



DEPARTAMENTO QUALITY ASSURANCE
 Sector.

- Las dimensiones y la condición superficial se hallaron satisfactorias
- Dimension and surface condition were found acceptable
- Les dimensions et états de surface sont satisfaisants.
- Los materiales citados cumplen las normas aplicables.
- Manufacturing requirements are satisfied.
- Les normes applicables sont respectées.



Jessie Springett

CLIENTE / Customer: Client
VAN LEEUWEN PIPE AND TUBE-CAN
2875-64TH AVENUE
EDMONTON - ALBERTA T6P 1R1
CANADA
CAN

CERTIFICADO DE INSPECCION

Inspection Certificate - Certificat de Réception

UNE EN 10204-06 / 3.1
ISO 9047-15 / 3.1

FECHA: 15/12/2017
Date: 05/02/2018
N.º: 192002
No.: 6
Rev.01

PRODUCTO
Article - Produit

FLANGES

SU PEDIDO N.º
Your Order No.

45001856

DE
of - de

03/11/2017

HOJA: 6
Page: 6

NORMAS APLICABLES
Requirements - Normes Applicables

ASME B16.5-17

MATERIAL CORRESPONDIENTE
Material Correspondent - Matériau

ASME SA350LF2CL1-2-17, ASTM A350LF2CL1-2-17
ASME SA105M-17, ASTM A105M-14

MODO DE FUSION (*)
Steel Melting - Elaboration de l'acier

NACE MR0175/ISO15156-02/03-15 & NACE MR0103/ISO17495-15
Clause 7.2.1.4, Annex A.2 and SSC Region 3.

E = Elec. Y = Origano Básico

CSA-Z245.12-13 GR248 CAT II-SS (WN & BLIND FLANGES ONLY)

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

SECTOR
Département

DEPARTAMENTO
QUALITY ASSURANCE

COMPOSICION QUIMICA - STEEL MAKER'S LADLE ANALYSIS - ANALYSE CHIMIQUE

COLADA N.º Heat No N.º Coulee	C %	Si %	Mn %	P %	S %	Cr %	Ni %	Mo %	Nb %	V %	Cu %	Al %	Ti %	CEq %
43AV7	0.192	0.240	1.020	0.015	0.005	0.096	0.094	0.022	0.001	0.000	0.253	0.035	0.003	0.41
A14A7	0.180	0.190	1.020	0.008	0.004	0.060	0.060	0.009	0.005	0.005	0.120	0.041	0.002	0.38
A48A7	0.190	0.160	1.020	0.009	0.004	0.050	0.070	0.010	0.007	0.007	0.140	0.036	0.001	0.39
A63A7	0.193	0.230	1.030	0.015	0.003	0.100	0.098	0.029	0.001	0.000	0.239	0.041	0.003	0.41
A64A7	0.180	0.240	1.030	0.015	0.005	0.085	0.091	0.024	0.001	0.000	0.205	0.042	0.002	0.39
B47A7	0.200	0.210	1.030	0.012	0.001	0.060	0.050	0.010	0.005	0.005	0.170	0.034	0.002	0.40
B55A7	0.180	0.180	0.990	0.012	0.004	0.060	0.060	0.008	0.003	0.005	0.160	0.030	0.001	0.38
B63A7	0.180	0.230	1.010	0.010	0.003	0.060	0.070	0.010	0.005	0.003	0.180	0.028	0.001	0.38
B73A7	0.190	0.230	0.980	0.009	0.003	0.090	0.080	0.010	0.004	0.005	0.190	0.035	0.002	0.39

(*) OBSERVACIONES:
Remarks
Observations

N, NORMALIZED AT 900 C AND ALLOWED TO COOL IN STILL AIR.

- Las dimensiones y la condición superficial se hallaron satisfactorias.
- Dimension and surface condition were found acceptable.
- Les dimensions et états de surface sont satisfaisants.

- Los materiales citados cumplen las normas aplicables.
- Manufacturing requirements are satisfied.
- Les normes applicables sont respectées.

EL INSPECTOR

Works Inspector - L'inspecteur



ULMA PEBEA S. COOP.

Dpto. de Garantía de calidad

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

Quality Assurance Dept.

QM-System: Certification as per ISO 9001

A02 Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)

INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004

INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013

MATERIAL TEST REPORT (MTR)

DILLINGER

A05 Established inspecting body DH	A06 Purchaser Final receiver	A07.1 No. EDMONTON STEEL, EDMON	A07.2 No. EDMONTON STEEL, EDMON	A10 Advice of dispatch No./ Date of dispatch 611114-07.09.17	A08/ Manufacturer's order/ A03 Certificate No. 427758-001	Sheet 1/...
---------------------------------------	---------------------------------	------------------------------------	------------------------------------	--	---	----------------

B02/ Steel design. SA516-70

B03 Any suppl. ASME-IIA:2015

requirements DIL-HUE-1:R34-2016-08-19

SA20-S5



B01-B99 Description of the product

B14 Item No.	B08 Number of pieces	B09 Thickness	B10 Width	B11 Length	B12 Theoretical mass KG	B04 Product delivery condition	B07.2 Heat No.	B07.1 Rolled plate No./ Test No.	A09 Purchaser article number
01	1	0,5000 x	96,50000 x	480,00000	2979	N	449291	55053-01--	ITEM001
01	1	0,5000 x	96,50000 x	480,00000	2979	N	449291	55053-02	ITEM001
01	1	0,5000 x	96,50000 x	480,00000	2979	N	449291	55053-03	ITEM001
01	1	0,5000 x	96,50000 x	480,00000	2979	N	449291	55054-01	ITEM001
01	1	0,5000 x	96,50000 x	480,00000	2979	N	449291	55054-02	ITEM001
01	1	0,5000 x	96,50000 x	480,00000	2979	N	449291	55054-03	ITEM001
01	1	0,5000 x	96,50000 x	480,00000	2979	N	449291	55056-01	ITEM001
01	1	0,5000 x	96,50000 x	480,00000	2979	N	449291	55056-02	ITEM001
01	1	0,5000 x	96,50000 x	480,00000	2979	N	449291	55056-03	ITEM001
01	1	0,5000 x	96,50000 x	480,00000	2979	N	449291	55060-01	ITEM001
01	1	0,5000 x	96,50000 x	480,00000	2979	N	449291	55060-02	ITEM001
**	12				35748				
**	12				35748				

EPL-243

SA 516 Gr. 60/70

0.50"

HT# 449291 55060 03

PO# 203847

Internal PO# E20207

Received: 26/09/2018

Received by: Jessie Springett

Jessie Springett

B04 Product delivery condition

ITEM NO.: 01

N: HT: 1670 GR.F +36 -27 GR.F

SOAKING TIME TO ATTAIN THE TARGET TEMPERATURE OVER THE WHOLE SECTION: 1-1,75 MIN/MM (25-45 MIN/INCH)

COOLING IN STILL AIR

A04



2012/02/203 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.

B. Baldauf

B. BALDAUF
Test House Manager



AG der Dillinger Hüttenwerke
Postfach 1580, D-66748 Dillingen/Saar
Inspection department

Inspector's stamp

Date 08.09.17

pp 1

QM-System: Certification as per ISO 9001

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)

DILLINGER

A02 INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004		A10 Advice of dispatch No./ Date of dispatch		A08/ Manufacturer's order/ A03 Certificate No.		Sheet
INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013		611114-07.09.17		427758-001		2 / ...
MATERIAL TEST REPORT (MTR)				B07 Product		
A05 Establishing body		A06 Purchaser		EDMONTON STEEL, EDMON		A07.1 No. ED10715-J1010ER
DH		Final receiver		EDMONTON STEEL, EDMON		A07.2 No. SA20-S5
B02/ Steel design.		SA516-70				
B03 Any suppl.		ASME-III-A:2015				
requirements		DIL-HUE-1:R34-2016-08-19				

B06 Marking of the product

ITEM NO.: 01

STEEL DESIGNATION SA516 70 MTLTV SA516 60 MTLTV

HEAT NO. / TRADEMARK / ROLLED PLATE NO. -TEST NO. / INSPECTOR'S STAMP

B07-B99 Further information about the product

ITEM NO.: 01


THICKNESS REDUCTION RATIO $\geq 3,0$ IS FULFILLED - CF. A/SA20(M) PAR. 5.3

C10-C29 Tensile test

B14 Item No.	B07.2 Heat No.	B05 Reference (heat) treatment	C01 C02/ C03 C01	C02/ C03 C01	C10 C11	C12 C13	A % LO=8IN	C14-C15
01	449291	55053	K1 Q	RT	49,9	RM	26	
01	449291	55054	K1 Q	RT	50,0	73,8	24	
01	449291	55056	K1 Q	RT	50,2	73,4	27	
01	449291	55060	K1 Q	RT	50,2	74,0	27	

C30-C39 Hardness test

B14 Item No.	B07.2 Heat No.	B05 Reference (heat) treatment	C01 C02/ C03 C01	C02/ C03 C01	C10 C11	C12 C13	A % LO=8IN	C14-C15
01	449291	55053	K1 Q	RT	49,9	RM	26	
01	449291	55054	K1 Q	RT	50,0	73,8	24	
01	449291	55056	K1 Q	RT	50,2	73,4	27	
01	449291	55060	K1 Q	RT	50,2	74,0	27	



Manufacturer's mark

Z011Z02/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.

B. Baldauf



AG der Dillinger Hüttenwerke
Postfach 1580, D-66748 Dillingen/Saar
Inspection department

B. BALDAUF
Test House Manager

Inspector's stamp Date 08.09.17

pp 1

QM-System: Certification as per ISO 9001

DILLINGER

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)

A02	INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004					A10	Advice of dispatch No./ Date of dispatch	A08/ Manufacturer's order/ A03 Certificate No.	Sheet
	INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013								
	MATERIAL TEST REPORT (MTR)								
A05	Established inspecting body DH	A06 Purchaser Final receiver	EDMONTON STEEL, EDMON	A07.1 No. ED10715-J1010ER		611114-07.09.17	427758-001	B01 Product HEAVY PLATES	3 / ...
B02/	Steel design.	SA516-70							
B03	Any suppl. requirements	ASME-III-A:2015 DIL-HUE-1:R34-2016-08-19							
			SA20-S5						

C40-C49 Impact test

B14	B07.2	B07.1	B05	Reference (heat) treatment		C01	C02/	C03	C41	C40	C44	C45	C42	C43
Item	Heat No.	Roll, plate/ Test No.					C01	Temp. GR.F	Width of test piece	Type of test piece	Testing method	Energy	Individual values AV=FT.LBF	Mean value
01	449291	55053				K1	LV	-51	-51	CHP-V		AV 8	212	193
01	449291	55054				K1	LV	-51	-51	CHP-V		AV 8	131	189
01	449291	55056				K1	LV	-51	-51	CHP-V		AV 8	228	134
01	449291	55060				K1	LV	-51	-51	CHP-V		AV 8	206	198

C70-C99 Chemical composition % - Heat analysis

B07.2	C70	C	SI	MN	P	S	N	CU	MO	NI	CR	V	NB	SN	TI
Heat															
449291	Y	0,161	0,358	1,160	0,010	0,0013	0,0066	0,026	0,005	0,027	0,033	0,000	0,000	0,0009	0,002
B07.2	C70	B	CA	AL-T											
449291	Y	0,0001	0,0021	0,029											

C94 Heat analysis Carbon equivalent / Alloying restrictions

B07.2	Heat	FO-02=	0,37	FO-51=	0,000	FO-55=	0,09	FO-78=	0,04	FO-91=	7,2
449291											

C95 Ladle treatment

ITEM NO.: 01	HEAT OF THE INDICATED ITEM: VACUUM DEGASSED / SULPHIDE SHAPE CONTROL
--------------	--

C95 Further information about ladle treatment

ITEM NO.: 01	CALCIUM TREATED
--------------	-----------------

A04	 Manufacturer's mark	Z01/Z02/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.				A01	
			B. BALDAUF Test House Manager		Inspector's stamp	Date 08.09.17	DD 1
		AG der Dillinger Hüttenwerke Postfach 1580, D-66748 Dillingen/Saar Inspection department					

QM-System: Certification as per ISO 9001

DILLINGER

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)

A02	INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004				A10	Advice of dispatch No./ Date of dispatch	A08/ Manufacturer's order/ A03 Certificate No.	Sheet
	INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013							
	MATERIAL TEST REPORT (MTR)							
A05	Established inspecting body	A06 Purchaser	EDMONTON STEEL, EDMON		A07.1 No.	611114-07.09.17	427758-001	4
	DH	Final receiver	EDMONTON STEEL, EDMON		A07.2 No.			

S02/ Steel design.		SA516-70					
S03 Any suppl. requirements		ASME-IIA:2015					
		DIL-HUB-1:R34-2016-08-19					
			SA20-S5				

C70-C99 Chemical composition % - Product analysis

		C	SI	MIN	P	S	N	CU	MO	NI	CR	V	NB	SN	TI
B07.2	Heat														
	Test No.														
449291	55053	K1	0,160	0,354	1,16	0,010	0,0010	0,0057	0,025	0,003	0,031	0,000	0,000	0,000	0,001
B07.2	Heat														
	Test No.														
449291	55053	K1	0,0000	0,0020	0,029										

C94 Product analysis Carbon equivalent / Alloying restrictions

Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									
Test Results									

C94 Carbon equivalent formula / Alloying restrictions

$$FO-02 = C + (MN/6) + (CR+MO+V) / 5 + (NI+CU) / 15$$

$$FO-51 = V + NB$$

$$FO-55 = CU+MO+NI+CR$$

$$FO-78 = CR+MO$$

$$FO-91 = MN/C$$

D01 Marking and identification, surface appearance, shape and dimensional properties

ITEM NO.: 01

EXAMINATION OF MARKING, SURFACE, SHAPE AND DIMENSIONS: THE RESULTS MEET THE REQUIREMENTS.

SURFACE AS PER ASME-SA20

THICKNESS AS PER ASME-SA20

LENGTH AND WIDTH AS PER ASME-SA20



A04



Z01/Z02/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.

B. Baldauf
B. BALDAUF
Test House Manager



AG der Dillinger Hüttenwerke
Postfach 1580, D-66748 Dillingen/Saar
Inspection department

Inspector's stamp Date 08.09.17

PP 1

A01

JEANTIG

A02 INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004
INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013
MATERIAL TEST REPORT (MTR)

DH	Final receiver	A07.1 No.	EDMONTON STEEL, EDMON	A07.2 No.	EDMONTON STEEL, EDMON	ED10715-J1010ER	B01 Product	HEAVY PLATES
----	----------------	-----------	-----------------------	-----------	-----------------------	-----------------	-------------	--------------

B03 Any suppl. ASME-III-A:2015 SA20-S3

requirements **DIL-HUE-1:R34-2016-08-19**

B01-B09 Description of the structure	21071

Description of the product	
B14	B08
B09	R10
B44	R44

Item No.	Item	Thickness	Width
B11	Length		
B12	Theoretical		
B04	Product delivery		
B07.2	Heat No.		
B07.1	Barrel diameter		
A09	Heat rate		

no.	of pieces	inch	mass g/g	condition	serial no.	rolled plate No./ Test No.	Purchaser article number

01	I	0,5000 x	96,50000 x	480,00000	2979	N	449297	55052.07	TEMP.005
01	I	0,5000 x	96,50000 x	480,00000	2979	N	449297	55052.07	TEMP.005

[illegible]

ITEM	QTY	UNIT	PRICE	TOTAL	ITEM	QTY	UNIT	PRICE	TOTAL
ITEM001	449291				ITEM001	449291			
55053-03					55053-03				
2979 N	480,0000	X			2979 N	480,0000	X		
	96,5000	X				96,5000	X		
	0,5000	X				0,5000	X		
	0,5000	X				0,5000	X		

01	I	0.5000	X	96	50000	X	480	00000	2979	N	449291	55054-01	ITEM001
----	---	--------	---	----	-------	---	-----	-------	------	---	--------	----------	---------

01	1	0,5000 X	96,50000 X	480,00000	2979	N	449291	55054-02	ITEM001
01	1	0,5000 X	96,50000 X	480,00000	2978	N	449291	55054-02	ITEM001

[illegible][illegible][illegible]

ITEM	QTY	UNIT	PRICE	TOTAL	DATE	REMARKS
ITEM001	2979	N	449291	55060-01		
ITEM001	2979	N	449291	55060-01		

01	1	0.5000	X	96.50000	X	480.00000	2878	449291	55060-02	ITEM001
----	---	--------	---	----------	---	-----------	------	--------	----------	---------

12	**	100,00000	2979	N	449291	55060-03	ITEM001
----	----	-----------	------	---	--------	----------	---------

```

12
***
***
***
35748

```

B04 Product delivery condition

ITEM NO.: 01

N: HT: 1670 GR.F +36 -27 GR.F

	SOAKING TIME TO ATTAIN THE TARGET TEMPERATURE OVER THE WHOLE SECTION	1-1	75 MIN/MIN	(25-45 MPa/TARGET)
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				
38				
39				
40				
41				
42				
43				
44				
45				
46				
47				
48				
49				
50				
51				
52				
53				
54				
55				
56				
57				
58				
59				
60				
61				
62				
63				
64				
65				
66				
67				
68				
69				
70				
71				
72				
73				
74				
75				
76				
77				
78				
79				
80				
81				
82				
83				
84				
85				
86				
87				
88				
89				
90				
91				
92				
93				
94				
95				
96				
97				
98				
99				
100				

COOLING IN STILL AIR

104	Z01/202/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance
-----	---

								AG der Dillinger Hüttenwerke	A01
---	---	---	--	---	---	---	---	------------------------------	-----

~~D X H~~

Manufacturer's Inspection department

mark	01.04.2007	Inspector's stamp	Date
mark		Test House Manager	08.09.17

	$\mathcal{I}$	$\mathcal{I}_1$	$\mathcal{I}_2$	$\mathcal{I}_3$
$\mathcal{I}$	1	0	0	0
$\mathcal{I}_1$	0	1	0	0
$\mathcal{I}_2$	0	0	1	0
$\mathcal{I}_3$	0	0	0	1

QM-System: Certification as per ISO 9001

DILLINGER

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)

A02 INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004		A10 Advice of dispatch No./ Date of dispatch		A08/ Manufacturer's order/ A03 Certificate No.		Sheet	
INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013		611114-07.09.17		427758-001		2/...	
MATERIAL TEST REPORT (MTR)							
A05 Established inspecting body DH		A06 Purchaser Final receiver		A07.1 No. ED10715-J1010ER		B01 Product HEAVY PLATES	
B02/ Steel design. SA516-60							
B03 Any suppl. ASME-III-A:2015							
requirements DIL-HUE-1:R34-2016-08-19							

B06 Marking of the product

ITEM NO.: 01

STEEL DESIGNATION SA516 70 MTLTV SA516 60 MTLTV

HEAT NO. / TRADEMARK / ROLLED PLATE NO.-TEST NO. / INSPECTOR'S STAMP

B07-B99 Further information about the product

ITEM NO.: 01

THICKNESS REDUCTION RATIO $\geq 3,0$ IS FULFILLED - CF. A/SA20(M) PAR. 5.3

C10-C29 Tensile test

B14 Item No.	B07.2 Heat No.	B05 Rol.plate/ Test No.	Reference (heat) treatment	C01	C02/ C03 Temp. GR.F	C10 C11 Temp. GR.F	C12	C13	A % L0=8IN	C14-C15
01	449291	55053	K1 Q	RT	RP02	49,9	RM	73,8	26	
01	449291	55054	K1 Q	RT	50,0		73,8	24	27	
01	449291	55056	K1 Q	RT	50,2		73,4	27	27	
01	449291	55060	K1 Q	RT	50,2		74,0	27	27	

C30-C39 Hardness test

B14 Item No.	B07.2 Heat No.	B05 Rol.plate/ Test No.	Reference (heat) treatment	C01	C02/C01	C03 Temp. GR.F	C30 Method of test	C35 Individual values	C32 Mean value
01	449291	55053	K1	O		RT	HBW 10/3000	HB 139	138
01	449291	55054	K1	O		RT	HBW 10/3000	HB 139	137
01	449291	55056	K1	O		RT	HBW 10/3000	HB 139	139
01	449291	55060	K1	O		RT	HBW 10/3000	HB 139	139

A04



Manufacturer's mark

Z01/Z02/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.

B. Baldauf

B. BALDAUF
Test House Manager



AG der Dillinger Hüttenwerke
Postfach 1580, D-66748 Dillingen/Saar
Inspection department

Inspector's stamp Date 08.09.17

PP 1

A01

QM-System: Certification as per ISO 9001

DILLINGER

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dillinger.de/certificate)

A02 INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004 INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013 MATERIAL TEST REPORT (MTR)		A10 Advice of dispatch No./ Date of dispatch 611114-07.09.17	A08/ Manufacturer's order/ A03 Certificate No. 427758-001	Sheet 3/...
---	--	--	---	----------------

A05 Established inspecting body DH	A06 Purchaser EDMONTON STEEL, EDMON	A07.1 No. ED10715-J1010ER
B02/ Steel design. SA516-60	Final receiver EDMONTON STEEL, EDMON	A07.2 No.
B03 Any suppl. ASME-III:2015		
requirements DIL-HUE-1:R34-2016-08-19		SA20-S5

C40-C49 Impact test													
B14 Item No.	B07.2 Heat No.	B07.1 Rol,plate/ TestNo.	B05 Reference (heat) treatment	C01	C02/ C01	C03 Temp. GRF	C41 Width of test piece	C40 Type of test piece	C44 Testing method	C46 Energy	C45	C42 Individual values AV=FT.LBF	C43 Mean value
01	449291	55053		K1	LV	-51		CHP-V			AV 8	212	193
01	449291	55054		K1	LV	-51		CHP-V			AV 8	131	189
01	449291	55056		K1	LV	-51		CHP-V			AV 8	228	134
01	449291	55060		K1	LV	-51		CHP-V			AV 8	206	198
													223
													209

C70-C99 Chemical composition % - Heat analysis															
C70		C	SI	MN	P	S	N	CU	MO	NI	CR	V	NB	SN	TI
B07.2 Heat	449291	Y	0,161	0,358	1,160	0,010	0,0013	0,0066	0,026	0,005	0,027	0,033	0,000	0,0009	0,002
C70		B	CA	AL-T											
B07.2 Heat	449291	Y	0,0001	0,0021	0,029										

C94 Heat analysis Carbon equivalent / Alloying restrictions

C95 Ladle treatment	FO-02=	0,37	FO-51=	0,000	FO-55=	0,09	FO-78=	0,04	FO-91=	7,2
---------------------	--------	------	--------	-------	--------	------	--------	------	--------	-----

ITEM NO.: 01
HEAT OF THE INDICATED ITEM: VACUUM DEGASSED / SULPHIDE SHAPE CONTROL

C95 Further information about ladle treatment

ITEM NO.: 01
CALCIUM TREATED

A04		A01
Z01/Z02/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.		AG der Dillinger Hüttenwerke Postfach 1580, D-66748 Dillingen/Saar Inspection department
B. BALDAUF Test House Manager		Inspector's stamp Date 08.09.17
		PP 1

QM-System: Certification as per ISO 9001

Erläuterungen siehe Rückseite/Explications voir au verso/See reverse for explanations (www.dilling.de/certificate)

DILLINGER

A02 INSPECTION CERTIFICATE 3.1 AS PER EN 10204:2004		A10 Advice of dispatch No./ Date of dispatch		A08/ Manufacturer's order/ A03 Certificate No.		Sheet
INSPECTION CERTIFICATE 3.1 AS PER ISO 10474:2013		611114-07.09.17		427758-001		4
MATERIAL TEST REPORT (MTR)				B01 Product		
A05 Established inspecting body		A06 Purchaser		EDMONTON STEEL, EDMON		
DH		Final receiver		EDMONTON STEEL, EDMON		
B02/ Steel design.		SA516-60		ED10715-J1010ER		
B03 Any suppl.		ASME-IIA:2015		A07.2 No.		
requirements		DIL-HUE-1:R34-2016-08-19		SA20-S5		
HEAVY PLATES						

C70-C99 Chemical composition % - Product analysis

B07.2 Heat	B07.1 Test No.	C01											V	NB	SN	Ti
		C	SI	MN	P	S	N	CU	MO	NI	CR					
449291	55053	K1 0,160	0,354	1,16	0,010	0,0010	0,0057	0,025	0,003	0,027	0,031	0,000	0,000	0,000	0,000	0,001
B07.2	B07.1	C01														
449291	55053	K1 0,0000	0,0020	0,029												

C94 Product analysis Carbon equivalent / Alloying restrictions

B07.2 Heat	B07.1 Test No.	C01											V	NB	SN	Ti
		C	SI	MN	P	S	N	CU	MO	NI	CR					
449291	55053	K1 FO-02=	0,36	FO-51=	0,000	FO-55=	0,09									

C94 Carbon equivalent formula / Alloying restrictions

FO-02 = $C + (MN/6) + (CR+MO+V) / 5 + (NI+CU) / 15$
 FO-51 = $V + NB$
 FO-55 = $CU+MO+NI+CR$
 FO-78 = $CR+MO$
 FO-91 = MN/C

D01 Marking and identification, surface appearance, shape and dimensional properties

ITEM NO.: 01

EXAMINATION OF MARKING, SURFACE, SHAPE AND DIMENSIONS: THE RESULTS MEET THE REQUIREMENTS.
 SURFACE AS PER ASME-SA20
 THICKNESS AS PER ASME-SA20
 LENGTH AND WIDTH AS PER ASME-SA20



A04		Z01/Z02/Z03 We hereby certify, that the above mentioned materials have been delivered in accordance with the terms of order.	B. BALDAUF Test House Manager	B. Balz	AG der Dillinger Hüttenwerke Postfach 1580, D-66748 Dillingen/Saar Inspection department	A01
Manufacturer's mark		Inspector's stamp		Date	08.09.17	PP 1

WELDING PROCEDURE SPECIFICATION NO.: STS-7 (Rev.0)

WELDING PROCEDURE QUALIFICATION RECORD NO.(S): STS-7-1 (Rev.0),
STS-7-3 (Rev.0),
STS-7-4 (Rev.0),
STS-7-5 (Rev.0)

QUALIFIED IN ACCORDANCE WITH ASME SECTION IX FOR

Restricted Applications: SAW WELDING SIMULTANEOUSLY WITH TWO WELDING
HEADS, ONE ON EACH SIDE OF THE JOINT

Base Metal (Typical): P1 Groups 1 & 2 to P1 Groups 1 & 2
(SA 333 Gr. 6, SA 350 Gr. LF2, SA 420 Gr. WPL6, SA 516 Gr. 70 etc.)

Process(es): SAW Weld Types: GROOVE & FILLET

Position: FLAT & HORIZONTAL Diameter: ALL DIAMETERS

Filler Metal: F7A6-EM12K


BASE METAL CONDITIONS & GROOVE THICKNESS RANGE QUALIFIED:

NOTCH TOUGHNESS APPLICATIONS TO -50 °F AS WELDED

BASE METAL THICKNESS RANGE 0.125 to 1.750 in. inclusive

COMBINED DEPOSITED WELD METAL THICKNESS

ASME IX 1.750 in. maximum
API 650, 620, 12D, 12F 1.750 in. maximum



This WPS was prepared to the requirements of ASME Section IX 2017 and includes some of the additional requirements of the construction codes listed. The application of this WPS is outside the work scope of SGS Canada Inc.

Prepared By: Sara Van Roestel

Signed: Sara Van Roestel

Date: July 8, 2019

Reviewed By: Keelan Wolfe, C.E.T.

Signed: Keelan Wolfe

Date: July 8, 2019

(File E19-285)

QW-482 WELDING PROCEDURE SPECIFICATION (WPS)

Organization Name Storage Tank Solutions Inc.
Welding Procedure Specification No. STS-7 (Rev.0) Date July 8, 2019
Supporting PQR No.(s) STS-7-1 (Rev.0), STS-7-3 (Rev.0), STS-7-4 (Rev.0), STS-7-5 (Rev.0)
Welding Process(es) Submerged Arc Welding (SAW)

JOINTS (QW-402)

Joint Design All ASME groove & fillet, reference construction drawing for joint details.
Where joint details are not specified, refer to figures 1 to 15 attached
Root Opening As per attached typical groove designs, see figures 1 to 15 attached
Backing With Retainers With or without

BASE METALS (QW-403)

P-Number P1 Groups 1 & 2 To P-Number P1 Groups 1 & 2
Thickness Range: Groove 0.125 to 1.750 in. inclusive (1)
Fillet 0.125 to 8.00 in. inclusive
Pipe Diameter Ranges: Groove All diameters
Fillet All diameters
Deposited Weld Metal (Per Pass) 0.250 in. maximum
(1) Reference thickness limitations for tests on welds in fabrication or assembly in
ASME B31.3 Table 323.3.1 - Impact Testing Requirements for metals.

FILLER METALS (QW-404)

SAW
Specification No. (SFA) SFA 5.17
Flux / Wire Classification F7A6-EM12K
F-No. F6
A-No. A1
Diameter 5/64 to 3/16 in. inclusive
Supplemental Filler Metal Without
Flux Type Neutral
Flux Designation Lincolnweld 882 (2)
Alloy Elements Without
Alloy Flux Without
Recrushed Slag Without
Deposited Weld Metal Thickness Range:
Groove 1.750 in. max. (3)
Fillet All fillet sizes
(2) Other flux trade names may be used provided they meet an F7A6 classification
(3) Deposited weld metal thickness shall not exceed 1.750 in.

POSITION (QW-405)

Position of Groove Flat & Horizontal Position of Fillet Flat & Horizontal
Weld Progression N/A

PREHEAT (QW-406)

Preheat Temperature (Minimum) See attached preheat sheet prior to welding.
 Interpass Temperature (Maximum) 500 °F
 Preheat Maintenance See attached preheat sheet prior to welding. Preheat maintenance is not required if welding is interrupted or after the completion of welding unless required by the code of construction.

POSTWELD HEAT TREATMENT (QW-407)

With or Without Without
 Temperature Range N/A Time Range N/A

ELECTRICAL CHARACTERISTICS (QW-409)

Current Direct Polarity Reverse, electrode positive
 Amps See Table 1 Volts See Table 1

Maximum Heat Input

Base Metal Thickness Range	SAW Leading head	SAW Trailing Head
0.125 to 0.499 in.	45,300 J/in.	33,887 J/in.
0.500 to 0.624 in.	53,530 J/in.	50,557 J/in.
0.625 in. and greater	65,032 J/in.	46,742 J/in.

TECHNIQUE (QW-410)

Manual or Automatic Machine
 Single or Multiple Electrodes Leading and Trailing Heads - Single
 Electrode Spacing N/A
 String or Weave String
 Initial & Interpass Cleaning Brushing, chipping or grinding as required
 Method of Back Gouging Air carbon arc, back-grind as required
 Oscillation N/A
 Contact Tube to Work Distance 0.500 in. - 1.75 in.
 Multiple or Single Pass Per Side Multiple
 Electrode Spacing N/A
 Peening Not permitted
 Use of Thermal Process N/A
 Travel Speed See Table 1

TABLE 1 - WELDING PARAMETERS

LEADING HEAD							
Process	Filler Metal	Diameter in.	Current Type & Polarity	Amperage Range	Voltage Range	Travel Speed i.p.m.	Wire Feed Speed i.p.m.
SAW	F7A6-EM12K	5/64	DCRP	200 - 500	25 - 32	4.7 - 30	60 - 245
SAW	F7A6-EM12K	3/32	DCRP	250 - 600	25 - 33	5.8 - 32	60 - 245
SAW	F7A6-EM12K	1/8	DCRP	250 - 700	26 - 33	6.0 - 35	45 - 180
SAW	F7A6-EM12K	5/32	DCRP	370 - 800	26 - 34	8.9 - 40	45 - 180
SAW	F7A6-EM12K	3/16	DCRP	500 - 1000	28 - 36	13.0 - 50	30 - 100
TRAILING HEAD							
Process	Filler Metal	Diameter in.	Current Type & Polarity	Amperage Range	Voltage Range	Travel Speed i.p.m.	Wire Feed Speed i.p.m.
SAW	F7A6-EM12K	5/64	DCRP	200 - 500	25 - 32	6.5 - 30	60 - 245
SAW	F7A6-EM12K	3/32	DCRP	250 - 600	25 - 33	8.1 - 32	60 - 245
SAW	F7A6-EM12K	1/8	DCRP	250 - 700	26 - 33	8.4 - 35	45 - 180
SAW	F7A6-EM12K	5/32	DCRP	370 - 800	26 - 34	12.4 - 40	45 - 180
SAW	F7A6-EM12K	3/16	DCRP	500 - 1000	28 - 36	18.0 - 50	30 - 100
Note: Welding parameters shall be adjusted to insure that the maximum heat input value specified in QW-409 above is not exceeded. $\text{Heat Input (joules per inch)} = (\text{Amperage} \times \text{Voltage} \times 60) / \text{Travel Speed (i.p.m.)}$							


TYPICAL JOINT DESIGNS

Figure 1
Single Square Butt




Figure 2
Single Square Butt with Backing Strip




Figure 3
Double Square Butt




Figure 4
Single Vee Butt




Figure 5
Single Vee Butt with Backing Strip




Figure 6
Double Vee Butt




Figure 7
Single U Butt




Figure 8
Single U Butt with Backing Strip




Figure 9
Double U Butt




Figure 10
Single J Butt




Figure 11
Single J Butt with Backing Strip




Figure 12
Double J Butt




Figure 13
Single Bevel Butt




Figure 14
Single Bevel Butt with Backing Strip




Figure 15
Double Bevel Butt

Additional joint designs and internal misalignment on circumferential welds shall be within the dimensional limits stated on the approved construction drawing and/or the engineering design.

PREHEAT
P-No. 1

LARGE, WELDED, LOW-PRESSURE STORAGE TANKS IN ACCORDANCE WITH
API 620 Twelfth Edition, Addendum 1

THICKNESS OF THICKER PLATE	MINIMUM PREHEAT TEMPERATURE	
	P1 Group 1	P1 Group 2
Less than or equal to 1.25 in.	32 °F	50 °F
Greater than 1.25 in to 1.50 in.	50 °F	100 °F
Greater than 1.50 in.	200 °F	200 °F

- No welding of any kind shall be performed when the surfaces to be welded are wet with rain snow or ice; when rain or snow is falling on such surfaces; or during periods of high winds unless the welder and the work are properly shielded.
- Preheat shall be applied when the metal temperature is below the temperature required by Table 6-2 (summarized above). In that case the base metal shall be heated to at least the temperature indicated within 3.0 in. of the place where welding is to be started and maintained 3.0 in. ahead of the arc. Material P-Number and Group Number shall be as designated in ASME IX or in API 630 6.7.2 for materials not listed in ASME IX.

WELDED TANKS FOR OIL STORAGE IN ACCORDANCE WITH
API 650 Twelfth Edition, Addendum 2

THICKNESS OF THICKER PLATE	MINIMUM PREHEAT TEMPERATURE	
	Material Group I, II, III, and IIIA	Material Group IV, IVA, V & VI
Less than or equal to 1.25 in.	32 °F	50 °F
Greater than 1.25 in to 1.50 in.	50 °F	100 °F
Greater than 1.50 in.	200 °F	200 °F

- No welding of any kind shall be performed when the surfaces to be welded are wet with rain, snow or ice; when rain or snow is falling on such surfaces; or during periods of high winds unless the welder and the work are properly shielded.
- Preheat shall be applied when metal temperature is below the temperature required by table 7-1 (summarized above) for the base metals being joined, and metal shall be heated to at least the temperature indicated within 3.0 in. of the place where welding is to be started and maintained 3.0 in. ahead of the arc. Material Groups shall be as designated in Table 4.4

QW-483 PROCEDURE QUALIFICATION RECORD (PQR)

Organization Name Storage Tank Solutions Inc.
Procedure Qualification Record No. STS-7-1 (Rev.0) Date February 22, 2019
Welding Process(es) Submerged Arc Welding (SAW)

JOINTS (QW-402)

Joint Design Butt joint, square groove, see page 2
Root Opening See page 2
Backing Without Retainers Without

BASE METALS (QW-403)

Material Specification No. SA 516 Type or Grade Gr. 60/70
Heat Treat Condition (1) SA 516 Gr. 60/70: Normalized
P-No. P1 Groups 1/2 To P-No. P1 Groups 1/2 Thickness 0.250 in.
Heat Number 429693 29267-03 Carbon Equivalent (2) 0.37
Diameter N/A Other Plate product form m/c to 0.250 in.
Deposited Weld Metal (Per Pass) Did not exceed 0.125 in.
(1) Condition of base metal prior to welding.
(2) Per CSA Z662 Carbon Equivalent formula. See chemical composition of heat analysis on attached material test report

FILLER METALS (QW-404)

SAW
Specification No. (SFA) SFA 5.17
Flux / Wire Classification F7A6-EM12K (3)
F-No. F6
A-No. A1 (4)
Diameter See attached sketch
Supplemental Filler Metal Without
Flux Type Neutral
Flux Designation F7A6
Flux Trade Name Lincolnweld 882
Alloy Elements Without
Alloy Flux Without
Recrushed Slag Without
Deposited Weld Metal Thickness 0.250 in.
(3) The Lincoln Electric Company: Lincolnweld 882M Flux / L-61 Electrode Lot No. 15135168
(4) F7A6-EM12K A-No. established from chemical analysis of SAW weld cap deposit.
See attached Laboratory Test Report No.: E19-104.3

POSITION (QW-405)

Position of Groove 2G Weld Progression N/A

PREHEAT (QW-406)

Preheat Temperature 50 °F Interpass Temp. (Max.) N/A
Preheat Maintenance Weld was allowed to cool to ambient temperature in still air after welding was completed.

PQR NO. STS-7-1 (Rev.0)

POSTWELD HEAT TREATMENT (QW-407)


With or Without Without
 Temperature N/A Time N/A

ELECTRICAL CHARACTERISTICS (QW-409)

Current Direct Polarity Reverse, electrode positive
 Amps See below Volts See below

TECHNIQUE (QW-410)

Manual or Automatic Machine
 Single or Multiple Electrodes Single - Leading and Trailing Head
 Electrode Spacing 2.0 in.
 Multiple or Single Heads Multiple - One on each side of the joint
 Multiple or Single Pass Per Side Multiple
 String or Weave String
 Contact Tube to Work Distance 0.750 in. - 1.00 in.
 Travel Speed See below
 Initial & Interpass Cleaning Brushing, chipping and grinding as required
 Method of Back Gouging Not conducted
 Peening Not conducted
 Oscillation N/A
 Use of Thermal Process N/A



Pass	Process	Filler Metal	Diameter in.	Current Type & Polarity	Amperage Range	Voltage Range	Travel Speed i.p.m.
Leading Head							
1	SAW	F7A6-EM12K	3/32	DCRP	370 - 390	29 - 31	24.0
Trailing Head							
1	SAW	F7A6-EM12K	3/32	DCRP	300 - 310	27 - 29	21.4

PQR NO. STS-7-1 (Rev.0)

TENSILE TEST (QW-150)

Sample No.	Width in.	Thickness in.	Area sq. in.	Ultimate Load lbf	Ultimate Stress psi	Fracture Type & Location
T1	0.752	0.226	0.170	12,900	76,200	Partial Cup & Cone Parent Metal
T2	0.748	0.223	0.167	12,700	75,900	Partial Cup & Cone Parent Metal

GUIDED BEND TEST (QW-160)

Type & Figure No.	Result	Type & Figure No.	Result
QW-462.3a, TRB - R1	Pass	QW-462.3a, TFB - F1	Pass
QW-462.3a, TRB - R2	Pass	QW-462.3a, TFB - F2	Pass

OTHER TESTS

Vickers Hardness - see attached Laboratory Test Report No.: E19-104.1

Chemical Analysis (SAW Cap) - see attached Laboratory Test Report No.: E19-104.3

Welder's Name Matthew MacKenzie & Christopher Jaques
Certificate File No. N/A
Tests Conducted By SGS Canada Inc.
Laboratory Test No. E19-104.1

We certify the statements in this record are correct and that the test welds were prepared, welded and tested in accordance with the requirements of Section IX of the ASME Code.

Organization Storage Tank Solutions Inc.

Date _____ Print _____

Signed _____

QW-483 PROCEDURE QUALIFICATION RECORD (PQR)

Organization Name Storage Tank Solutions Inc.
Procedure Qualification Record No. STS-7-3 (Rev.0) Date February 22, 2019
Welding Process(es) Submerged Arc Welding (SAW)

JOINTS (QW-402)

Joint Design Butt joint, double bevel groove, see page 2
Root Opening See page 2
Backing Without Retainers Without

BASE METALS (QW-403)

Material Specification No. SA 516 Type or Grade Gr. 60/70
Heat Treat Condition (1) SA 516 Gr. 60/70: Normalized
P-No. P1 Groups 1/2 To P-No. P1 Groups 1/2 Thickness 0.875 in.
Heat Number 454840 27789-02 Carbon Equivalent (2) 0.37
Diameter N/A Other Plate product form
Deposited Weld Metal (Per Pass) Did not exceed 0.188 in.
(1) Condition of base metal prior to welding.
(2) Per CSA Z662 Carbon Equivalent formula. See chemical composition of heat analysis on attached material test report

FILLER METALS (QW-404)

SAW
Specification No. (SFA) SFA 5.17
Flux / Wire Classification F7A6-EM12K (3)
F-No. F6
A-No. A1 (4)
Diameter See attached sketch
Supplemental Filler Metal Without
Flux Type Neutral
Flux Designation F7A6
Flux Trade Name Lincolnweld 882
Alloy Elements Without
Alloy Flux Without
Recrushed Slag Without
Deposited Weld Metal Thickness 0.875 in.
(3) The Lincoln Electric Company: Lincolnweld 882M Flux / L-61 Electrode Lot No. 15135168
(4) F7A6-EM12K A-No. established from chemical analysis of SAW weld cap deposit.
See attached Laboratory Test Report No.: E19-104.3

POSITION (QW-405)

Position of Groove 2G Weld Progression N/A

PREHEAT (QW-406)

Preheat Temperature 50 °F Interpass Temp. (Max.) 500 °F
Preheat Maintenance Weld was allowed to cool to ambient temperature in still air after welding was completed.

POSTWELD HEAT TREATMENT (QW-407)


With or Without Without
 Temperature N/A Time N/A

ELECTRICAL CHARACTERISTICS (QW-409)

Current Direct Polarity Reverse, electrode positive
 Amps See next page Volts See next page
 Heat Input Leading head: 65,032 J/in. maximum Trailing Head: 46,742 J/in. maximum

TECHNIQUE (QW-410)

Manual or Automatic Machine
 Single or Multiple Electrodes Single - Leading and Trailing Head
 Electrode Spacing 2.0 in.
 Multiple or Single Heads Multiple - One on each side of the joint
 Multiple or Single Pass Per Side Multiple
 String or Weave String
 Contact Tube to Work Distance 0.750 in. - 1.00 in.
 Travel Speed See below
 Initial & Interpass Cleaning Brushing, chipping and grinding as required
 Method of Back Gouging Not conducted
 Peening Not conducted
 Oscillation N/A
 Use of Thermal Process N/A



Pass	Process	Filler Metal	Diameter in.	Current Type & Polarity	Amperage Range	Voltage Range	Travel Speed i.p.m.
Leading Head							
1	SAW	F7A6-EM12K	3/32	DCRP	370 - 390	30 - 32	17.6
2	SAW	F7A6-EM12K	3/32	DCRP	380 - 400	30 - 32	14.7
3	SAW	F7A6-EM12K	3/32	DCRP	410 - 430	31 - 33	14.1
4	SAW	F7A6-EM12K	3/32	DCRP	405 - 415	30 - 32	14.1
5	SAW	F7A6-EM12K	3/32	DCRP	440 - 450	31 - 33	14.1
6	SAW	F7A6-EM12K	3/32	DCRP	410 - 430	31 - 33	12.4
7	SAW	F7A6-EM12K	3/32	DCRP	400 - 420	31 - 33	15.3
8	SAW	F7A6-EM12K	3/32	DCRP	410 - 430	31 - 33	14.1
Trailing Head							
1	SAW	F7A6-EM12K	3/32	DCRP	350 - 370	27 - 29	17.6
2	SAW	F7A6-EM12K	3/32	DCRP	330 - 340	27 - 29	14.7
3	SAW	F7A6-EM12K	3/32	DCRP	340 - 350	27 - 29	12.4
4	SAW	F7A6-EM12K	3/32	DCRP	310 - 330	27 - 29	15.3
5	SAW	F7A6-EM12K	3/32	DCRP	270 - 280	27 - 29	14.7

PQR NO. STS-7-3 (Rev.0)**TENSILE TEST (QW-150)**

Sample No.	Width in.	Thickness in.	Area sq. in.	Ultimate Load lbf	Ultimate Stress psi	Fracture Type & Location
T1	0.748	0.819	0.613	46,600	76,200	Partial Cup & Cone Weld Metal
T2	0.748	0.819	0.613	47,000	76,700	Partial Cup & Cone Weld Metal

GUIDED BEND TEST (QW-160)

Type & Figure No.	Result	Type & Figure No.	Result
QW-462.2, TSB - S1	Pass	QW-462.2, TSB - S3	Pass
QW-462.2, TSB - S2	Pass	QW-462.2, TSB - S4	Pass

CHARPY V-NOTCH IMPACT TESTType of Test Charpy V-Notch Orientation Transverse

Governing Specification	Notch Location	Specimen Size in.	Test Temperature ° F	Specimen Number	Impact Values ft·lbf
ASME VIII Div.1 - 2017 & ASME B31.3 - 2016	Weld metal within 1/16 in. from weld surface	0.394 x 0.394	-50	C2.1	102
				C2.2	17
				C2.3	75
ASME VIII Div.1 - 2017 & ASME B31.3 - 2016	HAZ within 1/4 to 1/2T of cap side	0.394 x 0.394	-50	C3.1	192
				C3.2	231
				C3.3	61
ASME VIII Div.1 - 2017 & ASME B31.3 - 2016	HAZ within 1/4 to 1/2T of opposite cap side	0.394 x 0.394	-50	C4.1	75
				C4.2	135
				C4.3	170

OTHER TESTSVickers Hardness - see attached Laboratory Test Report No.: E19-104.3Chemical Analysis (SAW Cap) - see attached Laboratory Test Report No.: E19-104.3

Welder's Name Matthew MacKenzie & Christopher Jaques
 Certificate File No. N/A
 Tests Conducted By SGS Canada Inc.
 Laboratory Test No. E19-104.3

We certify the statements in this record are correct and that the test welds were prepared, welded and tested in accordance with the requirements of Section IX of the ASME Code.

Organization Storage Tank Solutions Inc.

Date _____ Print _____

Signed _____

QW-483 PROCEDURE QUALIFICATION RECORD (PQR)

Organization Name Storage Tank Solutions Inc.
Procedure Qualification Record No. STS-7-4 (Rev.0) Date June 11, 2019
Welding Process(es) Submerged Arc Welding (SAW)

JOINTS (QW-402)

Joint Design Butt joint, square groove, see page 2
Root Opening See page 2
Backing Without Retainers Without

BASE METALS (QW-403)

Material Specification No. SA 516 Type or Grade Gr. 60/70
Heat Treat Condition (1) SA 516 Gr. 60/70: Normalized
P-No. P1 Groups 1/2 To P-No. P1 Groups 1/2 Thickness 0.250 in.
Heat Number 429693 29267-03 Carbon Equivalent (2) 0.37
Diameter N/A Other Plate product form m/c to 0.250 in.
Deposited Weld Metal (Per Pass) Did not exceed 0.188 in.
(1) Condition of base metal prior to welding.
(2) Per CSA Z662 Carbon Equivalent formula. See chemical composition of heat analysis on attached material test report

FILLER METALS (QW-404)

SAW
Specification No. (SFA) SFA 5.17
Flux / Wire Classification F7A6-EM12K (3)
F-No. F6
A-No. A1 (4)
Diameter See attached sketch
Supplemental Filler Metal Without
Flux Type Neutral
Flux Designation F7A6
Flux Trade Name Lincolnweld 882
Alloy Elements Without
Alloy Flux Without
Recrushed Slag Without
Deposited Weld Metal Thickness 0.250 in.
(3) The Lincoln Electric Company: Lincolnweld 882M Flux / L-61 Electrode Lot No. 15135168
(4) F7A6-EM12K A-No. established from chemical analysis of SAW weld cap deposit.
See attached Laboratory Test Report No.: E19-104.3

POSITION (QW-405)

Position of Groove 2G Weld Progression N/A

PREHEAT (QW-406)

Preheat Temperature 50 °F Interpass Temp. (Max.) 400 °F
Preheat Maintenance Weld was allowed to cool to ambient temperature in still air after welding was completed.

PQR NO. STS-7-4 (Rev.0)

POSTWELD HEAT TREATMENT (QW-407)


With or Without Without
 Temperature N/A Time N/A

ELECTRICAL CHARACTERISTICS (QW-409)

Current Direct Polarity Reverse, electrode positive
 Amps See below Volts See below
 Heat Input Leading head: 45,300 J/in. maximum Trailing Head: 33,887 J/in. maximum

TECHNIQUE (QW-410)

Manual or Automatic Machine
 Single or Multiple Electrodes Single - Leading and Trailing Head
 Electrode Spacing 3.50 in.
 Multiple or Single Heads Multiple - One on each side of the joint
 Multiple or Single Pass Per Side Multiple
 String or Weave String
 Contact Tube to Work Distance 0.750 in. - 1.00 in.
 Travel Speed See below
 Initial & Interpass Cleaning Brushing, chipping and grinding as required
 Method of Back Gouging Not conducted
 Peening Not conducted
 Oscillation N/A
 Use of Thermal Process N/A



Pass	Process	Filler Metal	Diameter in.	Current Type & Polarity	Amperage Range	Voltage Range	Travel Speed i.p.m.
Leading Head							
1	SAW	F7A6-EM12K	3/32	DCRP	365 - 390	29 - 31	15.0
2	SAW	F7A6-EM12K	3/32	DCRP	370 - 400	27 - 30	16.4
Trailing Head							
1	SAW	F7A6-EM12K	3/32	DCRP	295 - 310	27 - 29	15.0
2	SAW	F7A6-EM12K	3/32	DCRP	310 - 340	27 - 30	16.4

Note: Monitored parameters provided by Storage Tank Solutions Inc.

PQR NO. STS-7-4 (Rev.0)

CHARPY V-NOTCH IMPACT TEST

Type of Test Charpy V-Notch Orientation Transverse

Governing Specification	Notch Location	Specimen Size in.	Test Temperature ° F	Specimen Number	Impact Values ft·lbf
ASME VIII Div.1 - 2017 & ASME B31.3 - 2016	Weld metal within 1/16 in. of root	0.394 x 0.197	-60	A2.1	35
				A2.2	25
				A2.3	20
ASME VIII Div.1 - 2017 & ASME B31.3 - 2016	HAZ @ Middle 1/2t	0.394 x 0.197	-60	A3.1	8
				A3.2	56
				A3.3	7

OTHER TESTS

Vickers Hardness - see attached Laboratory Test Report No.: E19-285.2
Chemical Analysis (SAW Cap) - see attached Laboratory Test Report No.: E19-104.3

Welder's Name Matthew MacKenzie & Christopher Jaques
Certificate File No. N/A
Tests Conducted By SGS Canada Inc.
Laboratory Test No. E19-285.2

We certify the statements in this record are correct and that the test welds were prepared, welded and tested in accordance with the requirements of Section IX of the ASME Code.

Organization Storage Tank Solutions Inc.

Date _____ Print _____

Signed _____

QW-483 PROCEDURE QUALIFICATION RECORD (PQR)

Organization Name Storage Tank Solutions Inc.
Procedure Qualification Record No. STS-7-5 (Rev.0) Date June 11, 2019
Welding Process(es) Submerged Arc Welding (SAW)

JOINTS (QW-402)

Joint Design Butt joint, single bevel groove, see page 2
Root Opening See page 2
Backing Without Retainers Without

BASE METALS (QW-403)

Material Specification No. SA 516 Type or Grade Gr. 60/70
Heat Treat Condition (1) SA 516 Gr. 60/70: Normalized
P-No. P1 Groups 1/2 To P-No. P1 Groups 1/2 Thickness 0.500 in.
Heat Number 459852 56930-01 Carbon Equivalent (2) 0.38
Diameter N/A Other Plate product form
Deposited Weld Metal (Per Pass) Did not exceed 0.188 in.
(1) Condition of base metal prior to welding.
(2) Per CSA Z662 Carbon Equivalent formula. See chemical composition of heat analysis on attached material test report

FILLER METALS (QW-404)

SAW
Specification No. (SFA) SFA 5.17
Flux / Wire Classification F7A6-EM12K (3)
F-No. F6
A-No. A1 (4)
Diameter See attached sketch
Supplemental Filler Metal Without
Flux Type Neutral
Flux Designation F7A6
Flux Trade Name Lincolnweld 882
Alloy Elements Without
Alloy Flux Without
Recrushed Slag Without
Deposited Weld Metal Thickness 0.500 in.
(3) The Lincoln Electric Company: Lincolnweld 882M Flux / L-61 Electrode Lot No. 15135168
(4) F7A6-EM12K A-No. established from chemical analysis of SAW weld cap deposit.
See attached Laboratory Test Report No.: E19-104.3

POSITION (QW-405)

Position of Groove 2G Weld Progression N/A

PREHEAT (QW-406)

Preheat Temperature 50 °F Interpass Temp. (Max.) 500 °F
Preheat Maintenance Weld was allowed to cool to ambient temperature in still air after welding was completed.

PQR NO. STS-7-5 (Rev.0)

POSTWELD HEAT TREATMENT (QW-407)


With or Without Without
 Temperature N/A Time N/A

ELECTRICAL CHARACTERISTICS (QW-409)

Current Direct Polarity Reverse, electrode positive
 Amps See below Volts See below
 Heat Input Leading head: 53,530 J/in. maximum Trailing Head: 50,557 J/in. maximum

TECHNIQUE (QW-410)

Manual or Automatic Machine
 Single or Multiple Electrodes Single - Leading and Trailing Head
 Electrode Spacing 2.50 in.
 Multiple or Single Heads Multiple -- One on each side of the joint
 Multiple or Single Pass Per Side Multiple
 String or Weave String
 Contact Tube to Work Distance 0.750 in. - 1.00 in.
 Travel Speed See below
 Initial & Interpass Cleaning Brushing, chipping and grinding as required
 Method of Back Gouging Not conducted
 Peening Not conducted
 Oscillation N/A
 Use of Thermal Process N/A



Pass	Process	Filler Metal	Diameter in.	Current Type & Polarity	Amperage Range	Voltage Range	Travel Speed i.p.m.
Leading Head							
1	SAW	F7A6-EM12K	3/32	DCRP	350 - 370	27 - 30	11.5
2	SAW	F7A6-EM12K	3/32	DCRP	360 - 380	27 - 30	12.0
3	SAW	F7A6-EM12K	3/32	DCRP	380 - 400	27 - 30	14.2
4	SAW	F7A6-EM12K	3/32	DCRP	390 - 410	27 - 30	14.2
Trailing Head							
1	SAW	F7A6-EM12K	3/32	DCRP	330 - 350	27 - 30	11.5
2	SAW	F7A6-EM12K	3/32	DCRP	340 - 360	27 - 30	12.0
3	SAW	F7A6-EM12K	3/32	DCRP	350 - 370	27 - 30	14.2

Note: Monitored parameters provided by Storage Tank Solutions Inc.

PQR NO. STS-7-5 (Rev.0)

CHARPY V-NOTCH IMPACT TEST

Type of Test Charpy V-Notch Orientation Transverse

Governing Specification	Notch Location	Specimen Size in.	Test Temperature ° F	Specimen Number	Impact Values ft•lbf
ASME VIII Div.1 - 2017 & ASME B31.3 - 2016	Weld metal within 1/16 in. of root	0.394 x 0.394	-50	B2.1	84
				B2.2	51
				B2.3	74
ASME VIII Div.1 - 2017 & ASME B31.3 - 2016	HAZ @ Middle 1/2t	0.394 x 0.394	-50	B3.1	136
				B3.2	131
				B3.3	119

OTHER TESTS

Vickers Hardness - see attached Laboratory Test Report No.: E19-285.2
Chemical Analysis (SAW Cap) - see attached Laboratory Test Report No.: E19-104.3

Welder's Name Matthew MacKenzie & Christopher Jaques
Certificate File No. N/A
Tests Conducted By SGS Canada Inc.
Laboratory Test No. E19-285.2

We certify the statements in this record are correct and that the test welds were prepared, welded and tested in accordance with the requirements of Section IX of the ASME Code.

Organization Storage Tank Solutions Inc.

Date _____ Print _____

Signed _____



TENSILE / BEND TEST

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6

Laboratory Test No.: E19-104.1
Date: March 8, 2019

Attention: Sebastien Ouellet

PQR No.:	STS-7-1 (Rev. 0)	Material Heat No.:	429693 29249-03
Material:	SA 516 Gr. 60/70	Weld Type:	Double Sided
Material Thickness:	6.35 mm (0.250 in.)		
Welding Process:	SAW		
Weld Thickness:	6.35 mm (0.250 in.)		
Thermal Condition:	As Welded		

Governing Spec.: ASME Section IX - 2017

Instrument: Satec S/N: 1308

SAMPLE NO.(QW-150)	T1	T2
WIDTH mm (in.)	19.1 (0.752)	19.0 (0.748)
THICKNESS mm (in.)	5.73 (0.226)	5.66 (0.223)
AREA sq. mm (sq. in.)	109 (0.170)	108 (0.167)
ULTIMATE LOAD N (lbf)	57 518 (12,900)	56 272 (12,700)
ULTIMATE STRESS MPa (psi)	526 (76,200)	523 (75,900)
FRACTURE TYPE	Partial Cup & Cone	Partial Cup & Cone
FRACTURE LOCATION	Parent Metal	Parent Metal


Note: Imperial values calculated by direct conversion.

SAMPLE TYPE(QW-462.3a)	Face Bend	Face Bend	Root Bend	Root Bend
SAMPLE NO.	F1	F2	R1	R2
RESULTS	Pass	Pass	Pass	Pass

Test Conducted By: Ibrahim Mohamoud (Edmonton)

Certified By:

Eric Dacyk, C.E.T.



This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.



HARDNESS TEST

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6


Laboratory Test No.: E19-104.1
Date: March 8, 2019

Attention: Sebastien Ouellet

PQR No.:	STS-7-1 (Rev. 0)	Material Heat No.:	429693 29249-03
Material:	SA 516 Gr. 60/70	Weld Type:	Double Sided
Material Thickness:	6.35 mm (0.250 in.)		
Welding Process:	SAW		
Weld Thickness:	6.35 mm (0.250 in.)		
Thermal Condition:	As Welded		

Type of Test: Vickers 10 kg (HV10)
Governing Spec.: ASTM E92 - 17 &
ANSI/NACE MR0175/ISO 15156:2015

Instrument: Buehler 5112
Calibration Date: July 27, 2018



Parent Metal		HAZ		Weld Metal		HAZ		Parent Metal	
1	154	3	170	11	175	20	167	28	158
2	160	4	197	12	180	21	166	29	160
		5	199	13	173	22	186		
		6	186	14	175	23	214		
		7	195	15	192	24	207		
		8	188	16	193	25	191		
		9	167	17	175	26	179		
		10	182	18	176	27	168		
				19	185				

Test Conducted By: Tong Zhao (Edmonton)

Certified By:

Eric Dacyk, C.E.T.



This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.

Page 1 of 1



TENSILE / BEND TEST

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6

Laboratory Test No.: E19-104.3
Date: March 15, 2019

Attention: Sebastien Ouellet

PQR No.:	STS-7-3 (Rev. 0)	Material Heat No.:	454840 27789-02
Material:	SA 516 Gr. 60/70	Weld Type:	Double Sided
Material Thickness:	22.2 mm (0.875 in.)		
Weld Process:	SAW		
Weld Thickness:	22.2 mm (0.875 in.)		
Thermal Condition:	As Welded		

Governing Spec.: ASME Section IX - 2017

Instrument: Tinius Olsen S/N: 133660

SAMPLE NO.(QW-150)	T1	T2
WIDTH mm (in.)	19.0 (0.748)	19.0 (0.748)
THICKNESS mm (in.)	20.8 (0.819)	20.8 (0.819)
AREA sq. mm (sq. in.)	395 (0.613)	395 (0.613)
ULTIMATE LOAD N (lbf)	207 501 (46,600)	209 027 (47,000)
ULTIMATE STRESS MPa (psi)	525 (76,200)	529 (76,700)
FRACTURE TYPE	Partial Cup & Cone	Partial Cup & Cone
FRACTURE LOCATION	Weld Metal	Weld Metal

Note: Imperial values calculated by direct conversion.

SAMPLE TYPE(QW-462.2)	Side Bend	Side Bend	Side Bend	Side Bend
SAMPLE NO.	S1	S2	S3	S4
RESULTS	Pass	Pass	Pass	Pass

Test Conducted By: Mohamed Botan (Edmonton)

Certified By:

Eric Dacyk, C.E.T.



This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.

Page 1 of 1



CHARPY V-NOTCH IMPACT TEST

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6

Laboratory Test No.: E19-104.3
Date: March 15, 2019

Attention: Sebastien Ouellet


PQR No.:	STS-7-3 (Rev. 0)	Material Heat No.:	454840 27789-02
Material:	SA 516 Gr. 60/70	Weld Type:	Double Sided
Material Thickness:	22.2 mm (0.875 in.)		
Weld Process:	SAW		
Weld Thickness:	22.2 mm (0.875 in.)		
Thermal Condition:	As Welded		

Specimen Size:	10 x 10 mm (0.394 x 0.394 in.)	Machine:	Satec SI-1K3, S/N: 1503
Orientation:	Transverse	Capacity:	407 J (300 ft·lbf)
Test Temperature:	-46 °C (-50 °F)	Verified Range:	3.4-325 J (2.5-240 ft·lbf)
Governing Spec.:	ASME Section VIII, Div. I, UG-84 - 2017 & ASME B31.3-2016	Calibration Date:	March 19, 2018

Specimen Number	Notch Location	Impact Values	
		Joules	(ft·lbf)
C2.1	Weld Metal within 1.5mm (1/16") from weld surface	138	(102)
C2.2		23	(17)
C2.3		102	(75)
C3.1	HAZ within 1/4 to 1/2T of cap side	260	(192)
C3.2		313	(231)
C3.3		83	(61)
C4.1	HAZ within 1/4 to 1/2T of opposite cap side	102	(75)
C4.2		183	(135)
C4.3		230	(170)

Note: Metric values calculated by direct conversion.

Test Conducted By: Tong Zhao (Edmonton)

Certified By: 

Eric Dacyk, C.E.T.



This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.

Page 1 of 1



HARDNESS TEST

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6


Laboratory Test No.: E19-104.3
Date: March 15, 2019

Attention: Sebastien Ouellet

PQR No.:	STS-7-3 (Rev. 0)	Material Heat No.:	454840 27789-02
Material:	SA 516 Gr. 60/70	Weld Type:	Double Sided
Material Thickness:	22.2 mm (0.875 in.)		
Weld Process:	SAW		
Weld Thickness:	22.2 mm (0.875 in.)		
Thermal Condition:	As Welded		


Type of Test: Vickers 10 kg (HV10)
Governing Spec.: ASTM E92 - 17 &
ANSI/NACE MR0175/ISO 15156:2015

Instrument: Buehler 5112
Calibration Date: July 27, 2018



Parent Metal		HAZ		Weld Metal		HAZ		Parent Metal	
1	166	3	162	11	156	20	186	28	157
2	157	4	181	12	152	21	156	29	160
		5	188	13	169	22	205		
		6	155	14	161	23	178		
		7	159	15	163	24	158		
		8	185	16	156	25	208		
		9	174	17	165	26	201		
		10	184	18	147	27	155		
				19	164				

Test Conducted By: Ibrahim Mohamoud (Edmonton)

Certified By: 

Eric Dacyk, C.E.T.



This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.

Page 1 of 1



CHEMICAL ANALYSIS

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6

Laboratory Test No.: E19-104.3
Date: March 13, 2019

Attention: Sebastien Ouellet

PQR No.:	STS-7-3 (Rev. 0)	Material Heat No.:	454840 27789-02
Material:	SA 516 Gr. 60/70	Weld Type:	Double Sided
Material Thickness:	22.2 mm (0.875 in.)		
Weld Process:	SAW		
Weld Thickness:	22.2 mm (0.875 in.)		
Thermal Condition:	As Welded		

Instrument: Shimadzu PDA-7000 Optical Emission Spectrometer
Calibration Date: September 26, 2018
Governing Spec.: ASTM E415-17

% by Weight

Carbon	0.07
Manganese	1.19
Sulphur	0.007
Phosphorus	0.011
Silicon	0.44
Chromium	0.03
Nickel	0.02
Molybdenum	0.01
Copper	0.10
Niobium	<0.01
Vanadium	0.01
Aluminum	0.02
Titanium	<0.01
Boron	<0.0004

Test Conducted By: Kamaldeep Brar (Calgary)

Certified By:


Eric Dacyk, C.E.T.



This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.

Page 1 of 1

SGS Canada Inc. 4027 - 14 Street S.E. Calgary, AB T2G 3K6 t +1 (403) 262-7072 f +1 (403) 266-3169
7925 Davies Road Edmonton, AB T6E 4N1 t +1 (780) 468-3030 f +1 (780) 468-3032

www.sgs.com

Member of the SGS Group (SGS SA)



CHARPY V-NOTCH IMPACT TEST

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6

Laboratory Test No.: E19-00285.1
Date: June 26, 2019

Attention: Sebastien Ouellet

PQR No.:	STS-7-4 (Rev. 0)	Material Heat No.:	429693 29267-03
Material:	SA 516 Gr. 60/70	Weld Type:	Double Sided
Material Thickness:	6.35 mm (0.250 in.)		
Welding Process:	SAW		
Weld Thickness:	6.35 mm (0.250 in.)		
Thermal Condition:	As Welded		


Specimen Size: 10 x 5 mm (0.394 x 0.197 in.)
Orientation: Transverse
Test Temperature: -51 °C (-60 °F)
Governing Spec.: ASME B31.3 – 2016 &
ASME VIII, Div.1, UG-84 - 2017

Machine: Satec SI-1K3, S/N: 1503
Capacity: 407 J (300 ft·lbf)
Verified Range: 3.4-325 J (2.5-240 ft·lbf)
Calibration Date: March 19, 2019

Specimen Number	Notch Location	Impact Values	
		Joules	(ft·lbf)
A2.1	Weld Metal within 1.5mm (1/16") of root	47	(35)
A2.2		34	(25)
A2.3		27	(20)
A3.1	HAZ @ Middle 1/2t	11	(8)
A3.2		76	(56)
A3.3		9	(7)

Note: Metric values calculated by direct conversion.

Test Conducted By: Mohamed Botan (Edmonton)

Certified By: 
Eric Dacyk, C.E.T.

This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.



HARDNESS TEST

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6


Laboratory Test No.: E19-00285.1
Date: June 27, 2019

Attention: Sebastien Ouellet

PQR No.:	STS-7-4 (Rev. 0)	Material Heat No.:	429693 29267-03
Material:	SA 516 Gr. 60/70	Weld Type:	Double Sided
Material Thickness:	6.35 mm (0.250 in.)		
Welding Process:	SAW		
Weld Thickness:	6.35 mm (0.250 in.)		
Thermal Condition:	As Welded		

Type of Test: Vickers 10 kg (HV10)
Governing Spec.: ASTM E92 - 17 & ANSI/NACE MR0175/ISO 15156:2015

Instrument: Buehler 5112
Calibration Date: July 27, 2018



Parent Metal		HAZ		Weld Metal		HAZ		Parent Metal	
1	160	3	167	11	173	20	176	28	154
2	163	4	182	12	163	21	160	29	154
		5	185	13	167	22	170		
		6	167	14	174	23	179		
		7	176	15	163	24	170		
		8	178	16	166	25	202		
		9	169	17	180	26	196		
		10	188	18	175	27	161		
				19	180				

Test Conducted By: Ibrahim Mohamoud (Edmonton)

Certified By:

Eric Dacyk, C.E.T.



This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.



CHARPY V-NOTCH IMPACT TEST

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6

Laboratory Test No.: E19-00285.2
Date: June 26, 2019

Attention: Sebastien Ouellet

PQR No.:	STS-7-5 (Rev. 0)	Material Heat No.:	459852 56930-01
Material:	SA 516 Gr. 60/70	Weld Type:	Double Sided
Material Thickness:	12.7 mm (0.500 in.)		
Welding Process:	SAW		
Weld Thickness:	12.7 mm (0.500 in.)		
Thermal Condition:	As Welded		

Specimen Size: 10 x 10 mm (0.394 x 0.394 in.)
Orientation: Transverse
Test Temperature: -46 °C (-50 °F)
Governing Spec.: ASME B31.3 – 2016 &
ASME Section VIII, Div. I, UG-84 - 2017

Machine: Satec SI-1K3, S/N: 1503
Capacity: 407 J (300 ft·lbf)
Verified Range: 3.4-325 J (2.5-240 ft·lbf)
Calibration Date: March 19, 2019

Specimen Number	Notch Location	Impact Values	
		Joules	(ft·lbf)
B2.1	Weld Metal within 1.5mm (1/16") of root	114	(84)
B2.2		69	(51)
B2.3		100	(74)
B3.1	HAZ @ Middle 1/2t	184	(136)
B3.2		178	(131)
B3.3		161	(119)

Note: Metric values calculated by direct conversion.

Test Conducted By: Mohamed Botan (Edmonton)

Certified By: 
Eric Dacyk, C.E.T.



This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.



HARDNESS TEST

Customer: Storage Tank Solutions Inc.
9 Well Head Street
Devon, Alberta
T9G 1Z6


Laboratory Test No.: E19-00285.2
Date: June 27, 2019

Attention: Sebastien Ouellet

PQR No.:	STS-7-5 (Rev. 0)	Material Heat No.:	459852 56930-01
Material:	SA 516 Gr. 60/70	Weld Type:	Double Sided
Material Thickness:	12.7 mm (0.500 in.)		
Welding Process:	SAW		
Weld Thickness:	12.7 mm (0.500 in.)		
Thermal Condition:	As Welded		

Type of Test: Vickers 10 kg (HV10)
Governing Spec.: ASTM E92 - 17 & ANSI/NACE MR0175/ISO 15156:2015

Instrument: Buehler 5112
Calibration Date: July 27, 2018



Parent Metal		HAZ		Weld Metal		HAZ		Parent Metal	
1	162	3	179	11	198	20	213	28	153
2	159	4	209	12	176	21	182	29	152
		5	224	13	196	22	218		
		6	170	14	189	23	173		
		7	171	15	188	24	178		
		8	224	16	179	25	234		
		9	173	17	188	26	237		
		10	208	18	190	27	192		
				19	179				

Test Conducted By: Ibrahim Mohamoud (Edmonton)

Certified By: 
Eric Dacyk, C.E.T.



This report (or certificate) is issued by the Company under its General Conditions for Inspection and Testing Services (copy available upon request). The issuance of this report (or certificate) does not exonerate buyers or sellers from exercising all their rights and discharging all their liabilities under the Contract of Sale. Stipulations to the contrary are not binding on the Company. The Company's responsibility under this report (or certificate) is limited to proven negligence and will in no case be more than ten times the amount of the fees or commission. Except by special arrangement, samples, if drawn, will not be retained by the Company for more than 30 days. The information stated in this report (or certificate) is derived from the results of inspection or testing procedures carried out in accordance with the instructions of our Client, and/or our assessment of such results on the basis of any technical standards, trade custom or practice, or other circumstances which should in our professional opinion be taken into account.

Page 1 of 1

SECTION 6.0

Weld Consumables



THE LINCOLN ELECTRIC COMPANY

PRODUCT CERTIFICATE

LINCOLNWELD 882 FLUX

The product named above and supplied on the referenced order number is of the same manufacturing process, and material requirements as the material which was used for the tests and calculations, the results of which are shown below. This certificate complies to the requirements of EN 10204, Type 2.2.

- Basicity Index

B.I.* = 1.6

*Calculated using Boniszewski formula shown below

$$B.I. = \frac{0.5 (FeO + MnO) + CaO + MgO + Na_2O + K_2O + CaF_2}{SiO_2 + 0.5 (TiO_2 + ZrO_2 + Al_2O_3)}$$

- Flux Sizing Distribution*

+20 MESH	34% Maximum
-20 +100 MESH	64% Minimum
-100 MESH	2% Maximum


*U.S. sieve number per ASTM E11-04

- Flux Composition (Based on Elemental Values Determined by X-Ray Fluorescence)

Na ₂ O	2%	SiO ₂	16%	MnO	1%
MgO	22%	CaO	1%	FeO	1%
Al ₂ O ₃	24%	ZrO ₂	7%	CaF ₂	24%

- Density (g/cm³): 1.2

- Flux Classification: EN 760 -- S A AS 1

 February 19, 2008
Phillip J. Woodring, Certification Supervisor, Date

Cert No. F882

CERTIFICATE OF CONFORMANCE



Product: **Lincolnweld® L-61®**
Classification: **EM12K**
EM12K
Specification: **AWS A5.17:2019, ASME SFA-5.17**
AWS A5.23:2011, ASME SFA-5.23
Date: **October 28, 2020**

This is to certify that the product named above is of the same classification(s) and design as the material used for the tests reported herein. The material was tested according to the specification(s) indicated and met all requirements. It was manufactured and supplied according to a Quality System Program that meets the requirements of ISO9001 among others as documented on The Lincoln Electric web page (<http://www.lincolnelectric.com/en-us/company/Pages/certifications.aspx>).

Electrode composition (weight %)	EM12K	Electrode
	Requirements	Results
C	0.05 - 0.15	0.12
Mn	0.80 - 1.25	0.97
Si	0.10 - 0.35	0.23
S	0.030 max.	0.007
P	0.030 max.	0.005
Cu (Total)	0.35 max.	0.09

1. This document meets the requirements of AWS A5.01M/A5.01 Schedule F. When a specific lot number is referenced it also meets the requirements of EN10204, type 2.2. It does not meet the requirements of type 3.1.
2. The size(s) of electrode tested is determined by the requirements for this classification. All other sizes manufactured will also meet these requirements.

October 28, 2020

Daniel Gaul, Certification Supervisor

Date

October 28, 2020

Jon Ogborn, Manager, Consumable Compliance

Date

The Lincoln Electric Company
22801 St. Clair Avenue
Cleveland, Ohio 44117-1199

CERTIFICATE OF CONFORMANCE
(APPLIES ONLY TO U.S. PRODUCTS)



Product: **Lincolnweld® L-61®**
Classification: **EM12K**
EM12K
Specification: **AWS A5.17:1997, ASME SFA-5.17**
AWS A5.23:2011, ASME SFA-5.23
Date: **December 18, 2015**

Q1 Lot Number: 16025054

This is to certify that the product named above and supplied on the referenced order number is of the same classification, manufacturing process, and material requirements as the material which was used for the test that was concluded on the date shown, the results of which are shown below. All tests required by the specifications shown for classification were performed at that time and the material tested met all requirements. It was manufactured and supplied according to the Quality System Program of the Lincoln Electric Company, Cleveland, Ohio, U.S.A., which meets the requirements of ISO9001, NCA3800, AWS A5.01, and other specification and Military requirements, as applicable. The Quality System Program has been approved by ASME, ABS, and VdTUV.

Electrode composition (weight %)	EM12K Requirements	Electrode Results
C	0.05 - 0.15	0.11
Mn	0.80 - 1.25	0.98
Si	0.10 - 0.35	0.19
S	0.030 max.	0.011
P	0.030 max.	0.005
Total Cu	0.35 max.	0.09

1. This certificate complies with the requirements of EN 10204, Type 2.2.
2. The electrode size required to be tested for this classification is 5/32 inch. All other sizes manufactured will also meet these requirements.
3. Results below the detection limits of the instrument or lower than the precision required by the specification are reported as zero.


Toronto Cunningham, Certification Supervisor December 18, 2015
Date


Marie Quintana, Director, Consumable December 31, 2015
Compliance Date

CERTIFICATE OF CONFORMANCE



Q1 Lot Number:
15989595

Product: Fleetweld® 5P+™
Classification: E6010
Specification: AWS A5.1:2012, ASME SFA-5.1
Date: October 01, 2018

This is to certify that the product named above is of the same classification(s) and design as the material used for the tests reported herein. The material was tested according to the specification(s) indicated and met all requirements. It was manufactured and supplied according to a Quality System Program that meets the requirements of ISO9001 among others as documented on The Lincoln Electric web page (<http://www.lincolnelectric.com/en-us/company/Pages/certifications.aspx>).

Operating Settings	E6010 Requirements	RESULTS	
Required Size for Classification	Not Specified	5/32" (4.0 mm)	3/16" (4.8 mm)
Current Type/Polarity	DC+	DC+	DC+
Nominal Voltage, V		27	27
Nominal Current, A		140	170
Average Heat Input, kJ/mm (kJ/in)		2.1 (53)	2.5 (63)
Travel Speed, cm/min (in/min)		11 (4.37)	11 (4.41)
Pass/Layers		16/8	16/8
Preheat Temperature, °C (°F)	(225 min.)	105 (225)	105 (225)
Interpass Temperature, °C (°F)	(225 - 350)	150 (300)	150 (300)
Postweld Heat Treatment	As-welded	As-welded	As-welded

Mechanical Properties of Weld Metal

Tensile Strength, MPa (ksi)	(60 min.)	550 (80)	540 (79)
Yield Strength, 0.2% Offset, MPa (ksi)	(48 min.)	440 (63)	440 (63)
Elongation %	22 min.	23	23
Average Impact Energy Joules @ -29 °C (ft-lbs @ -20 °F)	(20 min.)	91 (67) 87,90,97 (64,66,72)	75 (56) 73,74,79 (54,55,58)
Average Hardness, HRB	Info. Only	86	85

Chemical Composition of Weld Metal (weight %)

C	0.20 max.	0.15	0.14
Mn	1.20 max.	0.60	0.60
Si	1.00 max.	0.22	0.19
S	Not Specified	0.008	0.007
P	Not Specified	0.010	0.012
Cr	0.20 max.	0.03	0.03
Ni	0.30 max.	0.02	0.03
Mo	0.30 max.	0.01	0.01
V	0.08 max.	0.00	0.01
Mn+Ni+Cr+Mo+V	Not Specified	0.67	0.67

1. This document meets the requirements of AWS A5.01M/A5.01 Schedule G. When a specific lot number is referenced it also meets the requirements of EN10204, type 2.2. It does not meet the requirements of type 3.1.
2. The electrode sizes required to be tested for this classification are 5/32 inch and 3/16 inch. All other sizes manufactured will also meet these requirements.
3. Fillet Weld Test (positions as required): Met requirements.
4. Radiographic Inspection: Grade 2 - Met requirements.
5. The strength and elongation properties reported here were obtained from tensile specimens artificially aged at 105°C (220°F) for 48 hours.
6. Strength values in SI units are reported to the nearest 10 MPa converted from actual data. Preheat and interpass temperature values in SI units are reported to the nearest 5 degrees.

Toronto Cunningham

October 01, 2018

Toronto Cunningham, Certification Supervisor

Date

Jonathan S. Ogborn

October 01, 2018

Jon Ogborn, Manager, Consumable Compliance

Date

CERTIFICATE OF CONFORMANCE

Q1 Lot Number: 15192360



Product: Fleetweld® 5P+
Classification: E6010
Specification: AWS A5.1:2012, ASME SFA-5.1
Date: June 30, 2016

This is to certify that the product named above is of the same classification(s) and design as the material used for the tests reported herein. The material was tested according to the specification(s) indicated and met all requirements. It was manufactured and supplied according to a Quality System Program that meets the requirements of ISO9001 among others as documented on The Lincoln Electric web page (<http://www.lincolnelectric.com/en-us/company/Pages/certifications.aspx>).

Operating Settings	E6010 Requirements	RESULTS	
Electrode Size		5/32 inch	3/16 inch
Current Type/Polarity	DC+	DC+	DC+
Nominal Voltage, V		25	26
Nominal Current, A		140	170
Average Heat Input, kJ/mm (kJ/in)		2.1 (53)	2.5 (63)
Pass/Layers		18/9	16/8
Preheat Temperature, °C (°F)	(225 min.)	105 (225)	105 (225)
Interpass Temperature, °C (°F)	(225 - 350)	150 (300)	150 (300)
Postweld Heat Treatment	As-welded	As-welded	As-welded

Mechanical properties of weld deposits

Tensile Strength, MPa (ksi)	(60 min.)	550 (79)	490 (71)
Yield Strength, 0.2% Offset, MPa (ksi)	(48 min.)	440 (64)	390 (57)
Elongation %	22 min.	28	29
Average Impact Energy Joules @ -29 °C (ft-lbs @ -20 °F)	(20 min.)	89 (66) 84,91,93 (62,67,68)	93 (69) 84,96,100 (62,71,73)
Average Hardness, HRB	Info. Only	88	82

Chemical composition of weld deposits (weight %)

C	0.20 max.	0.13	0.13
Mn	1.20 max.	0.66	0.52
Si	1.00 max.	0.25	0.15
S	Not Specified	0.007	0.005
P	Not Specified	0.009	0.009
Cr	0.20 max.	0.03	0.03
Ni	0.30 max.	0.04	0.04
Mo	0.30 max.	0.01	0.01
V	0.08 max.	0.01	0.00
Mn+Ni+Cr+Mo+V	Not Specified	0.74	0.60

1. This document meets the requirements of EN10204, type 2.2, when a specific lot or order number is referenced. It does not meet the requirements of type 3.1.
2. The electrode sizes required to be tested for this classification are 5/32 inch and 3/16 inch. All other sizes manufactured will also meet these requirements.
3. Fillet Weld Test (positions as required): Met requirements.
4. Radiographic Inspection: Grade 2 - Met requirements.
5. The strength and elongation properties reported here were obtained from tensile specimens artificially aged at 105°C (220°F) for 48 hours.
6. Strength values in SI units are reported to the nearest 10 MPa converted from actual data. Preheat and interpass temperature values in SI units are reported to the nearest 5 degrees.

Toronto Cunningham

June 30, 2016

Toronto Cunningham, Certification Supervisor

Date

Marie Quintana

June 30, 2016

Marie Quintana, Director, Consumable Compliance

Date

SECTION 7.0

Foudation

QUALITY CONTROL MANUAL

FOUNDATION REPORT

Exhibit 30, Rev 1

TANK TAG NUMBER: TANK 8 WORK ORDER NUMBER: _____
 CUSTOMER: AEM PROJECT: BAKER LAKE
 ITP LINE NUMBER: Tank 8 DATE: 2021-08-06

1.0 TANK PAD ACCEPTANCE GUIDELINES

- 1.1 In acceptance of the Tank Foundation, we acknowledge that the following requirements have been met:
- a) The foundation circumference meets the requirements of API 650 Para 7.5.
 - b) The foundation has been staked to clearly identify the major tank axis (North, South, East, West) and the tank center point
 - c) There is adequate access to the tank erection area to commence erection activities.
- 1.2 Our acceptance of the tank foundation is limited only to the above requirements. Acceptance does not constitute certification of the foundation design and/or construction including but not limited to the following:
- a) Certification of the foundation design including that of the leak detection and cathodic protection system.
 - b) Certification that the foundation has the load bearing capacities required.
 - c) Dimensional accuracy other than that explicitly stated above.
 - d) That the coordinate axis complies with the clients plot plan.
 - e) That soil embedded items have been properly placed according to approved drawings. This will be confirmed during the installation of components associated with the embedded items.
 - f) Certification that the foundation has been properly constructed or is structurally acceptable.
 - g) Certifications that the leak detection and/or cathodic protection systems have been properly installed.

OBSERVATIONS:

Acceptable at time of Inspection.

ACCEPTED BY: Matthew MacKenzie
(NAME & SIGNATURE)
STS QC REPRESENTATIVE

DATE: 2021-08-6

ACCEPTED BY: *[Signature]*
(NAME & SIGNATURE)
CLIENT INSPECTOR

DATE: Sept 4th 21

SECTION 8.0

Floor



STIS STORAGE TANK SOLUTIONS **AS BUILT TAMP**

☐ CHANGE
 ☒ NO CHANGE

NAME: Lindsay C Bolton

SIGNATURE: [Signature]

DATE: August 31, 2021

SCALE 1 / 100



















PLATE OVERLAP WELD DETAIL

Permit Number: 0472

PARTS LIST			
ITEM	QTY	DESCRIPTION	MASS
341M2101	10	RIM ANGLE 76X76X10 [3"X3"X3/8"] SEE DRG 315-M2	125 kg
341M5102	1	CENTRE COLUMN, SEE SHT 5	2741 kg
341M5103	32	INNER RAFTER W250X33 [W10"X22] SEE SHT 2	248 kg
341M5104	64	SHELL CLIP, PLATE 6 THK 152 X 189, SEE DETAIL	1 kg
341M5105	64	OUTER RAFTER W250X33 [W10"X22] SEE SHT 2	295 kg
341M5106	8	INTERMEDIATE GIRDER ASSEMBLY SEE SHT 4	570 kg
341M5107	8	INTERMEDIATE COLUMN ASSEMBLY SEE DETAIL	1285 kg
341M5108	128	GIRDER CONNECTION PLATE 13 [1/2"] THK 279 X 688 SEE DETAIL	10 kg
341M5116	512	BOLT, HEAVY HEX, 5/8" X 2.5" LG	0 kg
341M5117	512	NUT, HEAVY HEX, 5/8" UNC	0 kg
341M5118	1024	WASHER, PLAIN, TYPE A, 5/8"	0 kg
341M5119	320	BOLT, HEAVY HEX, 5/8" X 2" LG	0 kg
341M5120	64	BOLT, HEAVY HEX, 5/8" X 3" LG	0 kg



REVISION HISTORY		DATE
REV	DESCRIPTION	DATE
1	ISSUED FOR REVIEW	3/9/2021
2	ISSUED FOR CONSTRUCTION	6/8/2021



ROOF STRUCTURE LAYOUT		DATE
REV	DESCRIPTION	DATE
1	ISSUED FOR REVIEW	3/9/2021
2	ISSUED FOR CONSTRUCTION	6/8/2021

DETAIL C
SCALE 1/5

SECTION A-A
SCALE 1/200

Permit Number: P471

ROOF STRUCTURE LAYOUT		DATE
REV	DESCRIPTION	DATE
1	ISSUED FOR REVIEW	3/9/2021
2	ISSUED FOR CONSTRUCTION	6/8/2021

ROOF STRUCTURE LAYOUT		DATE
REV	DESCRIPTION	DATE
1	ISSUED FOR REVIEW	3/9/2021
2	ISSUED FOR CONSTRUCTION	6/8/2021

ROOF STRUCTURE LAYOUT		DATE
REV	DESCRIPTION	DATE
1	ISSUED FOR REVIEW	3/9/2021
2	ISSUED FOR CONSTRUCTION	6/8/2021

QUALITY CONTROL MANUAL

VISUAL TEST REPORT

Customer: AGNICO EAGLE

Location: BAKER LAKE

Code Requiring Test: API 650 (section 8.5.2)

Reason for Test: New Construction

A weld shall be acceptable by visual examination if the inspection shows the following.

- There are no crater cracks, other surface cracks or arc strikes in or adjacent to the welded joints.
- Maximum permissible undercut is 0.4 mm (1/64 in.) in depth for vertical butt joints, vertically oriented permanent attachments, attachment welds for nozzles, manholes, flush-type openings, and the inside shell-to-bottom welds. For horizontal butt joints, horizontally oriented permanent attachments, and annular-ring butt joints, the maximum permissible undercut is 0.8 mm (1/32 in.) in depth.
- The frequency of surface porosity in the weld does not exceed one cluster (one or more pores) in any 100 mm (4 in.) of length, and the diameter of each cluster does not exceed 2.5 mm (3/32 in.).
- The reinforcement of the welds on all thicknesses:

Plate Thickness mm (in.)	Maximum Reinforcement Thickness mm (in.)	
	Vertical Joints	Horizontal Joints
≤ 13 (1/2)	2.5 (1/32)	3 (1/8)
> 13 (1/2) to 25 (1)	3 (1/8)	5 (2/16)
> 25 (1)	5 (2/16)	6 (1/4)

Surface Condition (As Welded)

Test Solution: N/A

Test Date(s): 2021-08-18

Tested by: Matthew MacKenzie

Ambient Conditions: 10 Degrees Celcius

Items Tested:

FLOOR WELDS.

Results:

ALL WELDING ACCEPTABLE AT TIME OF INSPECTION.

STS Representative Signature: Matthew MacKenzie Date: 2021-08-18

Client Representative Signature: *Matthew Lee* Date: 23 Sept 21

QUALITY CONTROL MANUAL

Exhibit 14, Rev 1

VACUUM BOX TEST REPORT – FLOOR PLATE WELDS

Customer: AGNICO EAGLE

Location: BAKER LAKE

Equipment Tag No.: TANK 8

Equipment Description:

Code Requiring Test: API 650

Reason for Test: New Construction

(A vacuum box/soap solution test for floor plate weld seams is required for new construction or major alterations, no visible leaks should be observed)

Test Solution: Water / Snoop

Ambient Conditions: 10 Degrees Celcius

Test Date(s): 2021-08-30

Surface Condition: Clean

Tested by: Matthew MacKenzie

Surface Test Temperature: 10 Degrees Celcius

Pressure Gauge:

Items Tested:

Floor plates _____

Results:

No leak detected _____

Acceptable at time of Inspection. _____STS Representative Signature: Matthew MacKenzie Date: 2021-08-30Client Representative Signature: [Signature] Date: 4 Sept 21

SECTION 9.0

Shell to Floor Seams

QUALITY CONTROL MANUAL

VISUAL TEST REPORT

Customer: AGNICO EAGLE

Location: BAKER LAKE

Code Requiring Test: API 650 (section 8.5.2)

Reason for Test: New Construction

A weld shall be acceptable by visual examination if the inspection shows the following.

- There are no crater cracks, other surface cracks or arc strikes in or adjacent to the welded joints.
- Maximum permissible undercut is 0.4 mm (1/64 in.) in depth for vertical butt joints, vertically oriented permanent attachments, attachment welds for nozzles, manholes, flush-type openings, and the inside shell-to-bottom welds. For horizontal butt joints, horizontally oriented permanent attachments, and annular-ring butt joints, the maximum permissible undercut is 0.8 mm (1/32 in.) in depth.
- The frequency of surface porosity in the weld does not exceed one cluster (one or more pores) in any 100 mm (4 in.) of length, and the diameter of each cluster does not exceed 2.5 mm (3/32 in.).
- The reinforcement of the welds on all thicknesses:

Plate Thickness mm (in.)	Maximum Reinforcement Thickness mm (in.)	
	Vertical Joints	Horizontal Joints
≤ 13 (1/2)	2.5 (3/32)	3 (1/8)
> 13 (1/2) to 25 (1)	3 (1/8)	5 (3/16)
> 25 (1)	5 (3/16)	6 (1/4)

Surface Condition (As Welded)

Test Solution: N/A

Test Date(s): 2021-08-23

Tested by: Matthew MacKenzie

Ambient Conditions: 10 Degrees Celcius

Items Tested:

Shell to bottom seam weld.

Results:

No leaks detected at the time of inspection; acceptable to code.

Visual Inspection Acceptable at Time of Inspection

STS Representative Signature: [Signature] Date: 2021-08-23

Client Representative Signature: Mario Marcil Date: 08-29-21

QUALITY CONTROL MANUAL

VISUAL TEST REPORT

Customer: AGNICO EAGLE

Location: BAKER LAKE

Code Requiring Test: API 650 (section 8.5.2)

Reason for Test: New Construction

A weld shall be acceptable by visual examination if the inspection shows the following.

- There are no crater cracks, other surface cracks or arc strikes in or adjacent to the welded joints.
- Maximum permissible undercut is 0.4 mm (1/64 in.) in depth for vertical butt joints, vertically oriented permanent attachments, attachment welds for nozzles, manholes, flush-type openings, and the inside shell-to-bottom welds. For horizontal butt joints, horizontally oriented permanent attachments, and annular-ring butt joints, the maximum permissible undercut is 0.8 mm (1/32 in.) in depth.
- The frequency of surface porosity in the weld does not exceed one cluster (one or more pores) in any 100 mm (4 in.) of length, and the diameter of each cluster does not exceed 2.5 mm (3/32 in.).
- The reinforcement of the welds on all thicknesses:

Plate Thickness mm (in.)	Maximum Reinforcement Thickness mm (in.)	
	Vertical Joints	Horizontal Joints
≤ 13 (1/2)	2.5 (1/2)	3 (1/2)
> 13 (1/2) to 25 (1)	3 (1/2)	5 (2/8)
> 25 (1)	5 (3/16)	6 (1/4)

Surface Condition (As Welded)

Test Solution: N/A

Test Date(s): 2021-08-31

Tested by: Matthew MacKenzie

Ambient Conditions: 10 Degrees Celcius

Items Tested:

SHELL TO FLOOR FINAL PASS.

Results:

ALL WELDING ACCEPTABLE AT TIME OF INSPECTION.

STS Representative Signature: Matthew MacKenzie Date: 2021-08-31

Client Representative Signature: [Signature] Date: Sept 8th 2021

QUALITY CONTROL MANUAL

Exhibit 24, Rev 1

DIESEL TEST REPORT (SHELL TO BOTTOM WELD)

Customer: AGNICO EAGLE

Location: BAKER LAKE

Equipment Tag No.: TK 8

Equipment Type: Above Ground Storage Tank

Equipment Description: Diesel Storage Tank

Code Requiring Test: API 650 (section 7.2.4)

Reason for Test: New Construction

(The initial weld pass inside the shell shall have all slag and non-metals removed from the surface of the weld and then examined for its entire circumference both visually and applying a high Flash-point penetrating oil such as light diesel to the gap between the shell and the bottom, letting stand for at least four hours, and examining the weld for evidence of wicking.)

Surface Condition (As Welded)

Test Solution: Diesel

Test Date(s): 2021-08-23


Tested by: Matthew MacKenzie

Ambient Conditions: 10 Degrees Celcius

Items Tested:

Shell to bottom seam weld, excluding door sheet area.

Results:

No leaks detected at the time of inspection; acceptable to code.STS Representative Signature:  Date: 2021-08-23Client Representative Signature: Mario Marcil Date: 08-29-21

QUALITY CONTROL MANUAL

Exhibit 25, Rev 1

DIESEL TEST REPORT (SHELL)

Customer: AGNICO EAGLE

Location: BAKER LAKE

Equipment Tag No.: TK 8

Equipment Type: Above Ground Storage Tank

Equipment Description: Diesel Storage Tank

Code Requiring Test: API 650 (section 7.3.5)

Reason for Test: New Construction

(The shell shall be tested by painting all of the joints on the inside with a highly penetrating oil and carefully examining the outside of the joints for leakage.)

Surface Condition (As Welded)

Test Solution: Diesel

Test Date(s): 2021-09-05

Tested by: Matthew MacKenzie

Ambient Conditions: 10 Degrees Celcius

Items Tested:

Shell to bottom seam weld at door sheet area.

Results:

No leaks detected at the time of inspection; acceptable to code.

STS Representative Signature: Matthew MacKenzie Date: 2021-09-05


Client Representative Signature:  Date: Sept 8th 2021

Exhibit 26, Rev 1

Revision 1
March 1, 2017

SECTION 10.0

Shell



ST5 SOLUTIONS AS BUILT STAMP

☐ CHANGE ☒ NO CHANGE

NAME: Lindsay C Bolton

SIGNATURE: *[Signature]*


DATE: September 6, 2021

NOTES:
 ONLY COURSE NO. 1 SHELL PLATES REQUIRE SHOP ROLLING
 SHELL PLATES TO BE CHECKED CORNER TO CORNER FOR SQUARENESS
 STEEL PLATES: ASME SA 516 GRADE 70 KILLED FINE GRAIN, NORMALIZED SUPPLIED BY ICL
 STEEL SHAPES: CSA G40.21M 300W SUPPLIED BY TECHFORM

REVISION HISTORY		DATE
REV	DESCRIPTION	DATE
1	ISSUED FOR REVIEW	2/27/2019
2	ISSUED FOR CONSTRUCTION	9/6/2021
DRAWN BY: [Name] CHECKED BY: [Name] DATE: 2/18/2021 TITLE: SHELL PLATES AND RIM ANGLE CUTTING AND ROLLING DETAILS PROJECT: BAKER LAKE WHALE TAIL PROJECT - 10M LITERS - TANK #8: 6170TNK43 SIZE: A1 SCALE: 1/2 SHEET: 1 OF 2		



Tank #8 Baker Lake (AEM)



VERTS (Welder ID)

	IN	OUT
1V1	CPO	CPO
1V2	LMI	LMI
1V3	AKE	AKE
1V4	JNE	JNE
1V5	DGE	DGE
1V6	JNE	JNE
1V7	SFO	SFO
1V8	JNE	JNE
1V9	DGE	DGE
1V10	DGE	DGE

	IN	OUT
2V1	CIA	DGE
2V2	CIA	DGE
2V3	DGE	CPO
2V4	CPO	CPO
2V5	JNE	JNE
2V6	JNE	JNE
2V7	JNE	JNE
2V8	DGE	DGE
2V9	CPO	DGE

	IN	OUT
3V1	DGE	JNE
3V2	DGE	DGE
3V3	JNE	JNE
3V4	JRY	JRY
3V5	JRY	JRY
3V6	CPO	JRY
3V7	DGE	JRY
3V8	DGE	JRY
3V9	JNE	DGE

	IN	OUT
4V1	JNE	JNE
4V2	SFO	SFO
4V3	CPO	CPO
4V4	CPO	CPO
4V5	CPO	CPO
4V6	DGE	JRY
4V7	DGE	JRY
4V8	DGE	JNE
4V9	JNE	JNE

	IN	OUT
5V1	JNE	JNE
5V2	MBO	MBO
5V3	JRY	MBO
5V4	JRY	JRY
5V5	JRY	JRY
5V6	JRY	JRY
5V7	SFO	SFO
5V8	SFO	SFO
5V9	SFO	SFO

HORIZONTAL (Welder ID)

IN	OUT	IN	OUT	IN	OUT	IN	OUT
H1	JRY	CIA	CIA	H2	JRY	H3	CPO
DOOR SHEET	JNE/SFO	JNE/SFO	JNE/SFO				

PLATE IDENTIFICATION

1V1	813P63640	2V1	813S61760	3V1	1600012-01	4V1	1600012-01	5V1	811S00740	20002201
1V2	813P63640	2V2	0605092-05	3V2	1600012-01	4V2	811S00740	5V2	811S00740	20002201
1V3	813P63640	2V3	813S61760	3V3	1600012-01	4V3	811S00740	5V3	811S00740	20002201
1V4	813P63640	2V4	812P33310	3V4	1600012-02	4V4	811S00740	5V4	811S00740	20002201
1V5	813P63640	2V5	812P33310	3V5	1600012-02	4V5	811S00740	5V5	811S00740	20002201
1V6	0605092-03	2V6	812P33310	3V6	1600012-02	4V6	1600012-01	5V6	811S00740	20002201
1V7	0605092-03	2V7	812P33310	3V7	0604883-06	4V7	811S00740	5V7	811S00740	20002201
1V8	0605092-03	2V8	813S61760	3V8	1600012-01	4V8	811S00740	5V8	811S00740	20002201
1V9	823P63640	2V9	812P33310	3V9	1600012-01	4V9	811S00740	5V9	811S00740	20002201

1V1	813P63640	2V1	813S61760	3V1	1600012-01	4V1	1600012-01	5V1	811S00740	20002201
1V2	813P63640	2V2	0605092-05	3V2	1600012-01	4V2	811S00740	5V2	811S00740	20002201
1V3	813P63640	2V3	813S61760	3V3	1600012-01	4V3	811S00740	5V3	811S00740	20002201
1V4	813P63640	2V4	812P33310	3V4	1600012-02	4V4	811S00740	5V4	811S00740	20002201
1V5	813P63640	2V5	812P33310	3V5	1600012-02	4V5	811S00740	5V5	811S00740	20002201
1V6	0605092-03	2V6	812P33310	3V6	1600012-02	4V6	1600012-01	5V6	811S00740	20002201
1V7	0605092-03	2V7	812P33310	3V7	0604883-06	4V7	811S00740	5V7	811S00740	20002201
1V8	0605092-03	2V8	813S61760	3V8	1600012-01	4V8	811S00740	5V8	811S00740	20002201
1V9	823P63640	2V9	812P33310	3V9	1600012-01	4V9	811S00740	5V9	811S00740	20002201

Tank #8 Baker Lake (AEM)



B --> BOTTOM OF THE VERT (0-6")	M ----> MIDDLE OF THE VERT (45"-51")	T ----> TOP OF THE VERT (90"-96")

VERTICAL SEAMS MAPPING UT

STS Representative Signature: <i>[Signature]</i>	Date: <i>Sept 7/21</i>
Client Representative Signature: <i>[Signature]</i>	Date: <i>Sept 8th 2021</i>
NDT Representative Signature: <i>[Signature]</i>	Date: <i>Sept 06/2021</i>
NDT Representative CGSB No: <i>13073</i>	