

CONSTRUCTION SUMMARY REPORT VAULT DIKE

TABLE OF CONTENTS

SECTION 1.0 - INTRODUCTION.....	1
SECTION 2.0 - SCOPE.....	1
SECTION 3.0 - DESIGN AND TECHNICAL SPECIFICATIONS.....	2
3.1 FILL MATERIALS, MEMBRANE, AND THERMISTORS	2
3.1.1 Rockfill (0-1000 mm).....	2
3.1.2 Coarse Filter (0-150 mm).....	2
3.1.3 Fine Filter (0-25 mm)	2
3.1.4 0-25 mm Amended with Bentonite	3
3.1.5 Bituminous Geomembrane	3
3.1.6 Thermistors	4
3.2 ACCESS ROAD AND FOUNDATION PREPARATION	4
3.2.1 Construction Area Access	4
3.2.2 Foundation Surface Preparation.....	4
3.3 FILL PLACEMENT PROCEDURE.....	5
SECTION 4.0 - CONSTRUCTION SCHEDULE	5
SECTION 5.0 - VAULT DIKE CONSTRUCTION ACTIVITIES	5
5.1 ACCESS ROADS	6
5.2 FOUNDATION SURFACE PREPARATION.....	6
5.3 KEY TRENCH DRILLING, BLASTING, EXCAVATION AND GRADING	7
5.4 GRANULAR FILL PREPARATION, LOADING, PLACEMENT, AND COMPACTION	8
5.5 BITUMINOUS GEOMEMBRANE STORAGE, HANDLING, ROLL-OUT, WELDING AND PATCHING CONTROL	10
5.6 COMPLETION OF THE KEY TRENCH AND SLOPES	11
5.6.1 0-25mm amended with bentonite	11
5.6.2 Fine Filter (0-25 mm)	11
5.6.3 Coarse filter (0-150 mm).....	11
5.7 MAIN ROCKFILL (0-1000 MM).....	12
5.8 THERMISTOR STRINGS STORAGE, HANDLING, INSTALLATION, AND MONITORING.....	12
SECTION 6.0 - QC TESTING AND RESULTS.....	12
6.1 FOUNDATION APPROVAL.....	12

6.2	FILL PLACEMENT APPROVAL	13
6.2.1	Coarse Filter (0-150 mm).....	13
6.2.2	Fine Filter (0-25 mm)	13
6.2.3	0-25 mm Amended with Bentonite	13
6.3	BITUMINOUS GEOMEMBRANE APPROVAL	14
6.4	ROCKFILL (0-1000 MM).....	15
6.5	SITE INSPECTION AND PROCEDURE REVIEW.....	15
SECTION 7.0 - FIELD CHANGES AND ADJUSTMENTS DURING CONSTRUCTION		15
7.1	WORKING PLATFORM ENLARGEMENT ON WALLY LAKE SIDE.....	15
7.2	KEY TRENCH DEPTH	15
7.3	TILL IN KEY TRENCH	16
7.4	TYPE OF LINER (TERANAP VERSUS COLETANCHE).....	16
7.5	HORIZONTAL AND VERTICAL GEOMEMBRANE PLACEMENT	17
SECTION 8.0 - OPERATION AND MONITORING		17
SECTION 9.0 - SUMMARY AND CLOSURE.....		17

APPENDICES

APPENDIX A	Vault Dike Typical Section, As-Built Drawings and Table of Quantities
APPENDIX B	Vault Dike Construction Schedule
APPENDIX C	Selected Vault Dike Construction Photos
APPENDIX D	Map of Vault Pit Area
APPENDIX E	QC Results – Geotechnical Testing Records E1. – Fill E2. – Foundation Approval Forms E3. – Geomembrane