

October 17th 2016

Karen Kharatyan Manager of Licensing Nunavut Water Board P.O. Box 119 Gjoa Haven, NU X0B 1J0

Re: Water License 2AM-MEL1631 Part D, Items 1&2 - Submission of Final Design and Construction Drawings for Wesmeg culverts

Mr. Kharatyan,

Agnico Eagle Mines Limited (Agnico Eagle) is developing the Meliadine Project (the Project), a gold mine located approximately 25 km north from Rankin Inlet, and 80 km southwest from Chesterfield Inlet in the Kivalliq Region of Nunavut.

The overall objective of the water management strategy of this project is to develop a practical and feasible site wide water management plan to minimize the potential negative impacts of mining development on the surrounding environment including habitats for fish and wildlife, and to facilitate mine operation and long-term closure and reclamation of the mine site. To attain this objective, culverts are used to control and divert runoff underneath the road.

In accordance with Water License 2AM-MEL1631, Part D, Items 1 and 2, please find enclosed with this letter, a copy of the final design and construction drawings for Wesmeg culverts. Agnico Eagle is planning to start building the above mentioned culverts upon Board's approval.

Should you have any questions regarding this submission, please contact me or Jamie Quesnel.

Regards,

Agnico Eagle Mines Limited - Meliadine Division

Manon Turmel manon.turmel@agnicoeagle.com 819-759-3555 x8025

Environmental Compliance Counselor

Jamie Quesnel jamie.quesnel@agnicoeagle.com 819-759-3700 x 6838

Environmental Superintendent - Nunavut

cc: David Abernethy, Indigenous and Northern Affairs Canada Luis Manzo, Kivallig Inuit Association



DESIGN REPORT FOR WESMEG ROAD CULVERTS MELIADINE PROJECT, NUNAVUT



PRESENTED TO

Agnico Eagle Mines Ltd.

OCTOBER 2016
ISSUED FOR USE
TETRA TECH PROJECT NUMBER: 28920
AGNICO EAGLE DOCUMENT NUMBER: 6515-E-132-005-132-REP-003



TABLE OF CONTENTS

1.0	INTRODUCTION			
	1.1 Site Location and Access			1
	1.2	Existin	g Site Facilities	1
			of Work	
2.0	DES	IGN		2
	2.1	Culvert Design Basis and Water Management Strategy		
		2.1.1	Erosion Control	2
		2.1.2	Culvert Specifications	2
		2.1.3	Figures and Drawings	2
3.0	LIMITATIONS OF REPORT			
4.0	CLO	SURE.		3

APPENDICES

Appendix A Figure 1

Appendix B Construction Drawing 65-695-230-222



1.0 INTRODUCTION

1.1 Site Location and Access

Agnico Eagle Mines Limited (Agnico Eagle) is developing the Meliadine Project (the Project), a gold mine located approximately 25 km north from Rankin Inlet, and 80 km southwest from Chesterfield Inlet in the Kivalliq Region of Nunavut.

The studied area consists of the Meliadine industrial site. More specifically, this study focuses on the 2016 civil construction work zone. The area is accessible from the all-weather gravel road linking the existing exploration camp with Rankin Inlet. The site location is shown in figure 1 in appendix A.

1.2 Existing Site Facilities

Current facilities at the Meliadine Project site include the exploration camp located on the shores of Meliadine Lake, approximately 2.3 km east of the Tiriganiaq deposit. The self-contained camp consists of four wings of new trailers that can accommodate up to 200 people and includes new kitchen facilities, complete with diesel generators. Power for the exploration camp is currently provided by diesel generators. Potable water for the exploration camp is pumped from Meliadine Lake.

An underground portal allowing access to an exploration decline was built at the Tiriganiaq deposit in 2007 and 2008 in order to extract a bulk sample for study purposes. A waste rock and ore storage pad was built during excavation of the decline and a sampling tower was installed for processing the bulk sample. There is a 2 km long road between the Project exploration camp and the portal site. Another underground (UG) bulk sample of 4,600 t of ore was taken from the Tiriganiaq deposit via this portal in 2011. The results confirmed the resource estimation model that has been developed for the two principal zones at Tiriganiaq.

1.3 Scope of Work

Agnico Eagle retained the services of Tetra Tech to carry out the planning and design works associated with the Water and Environment and the Civil Works components of the Project. As part of the scope of work, Agnico Eagle asked Tetra Tech to:

- Conduct a detailed design for the service roads and temporary roads, as part of the 2016 civil work construction schedule including the crossing culverts;
- Produce construction drawings and specifications for the roads and culverts;
- Prepare a design report of the culverts.

This report summarizes the site conditions, design basis and considerations of the Wesmeg road culverts.



2.0 DESIGN

2.1 Culvert Design Basis and Water Management Strategy

The overall objective of the water management strategy of this project is to develop a practical and feasible sitewide water management plan to minimize the potential negative impacts of mining development on the surrounding environment including habitats for fish and wildlife, and to facilitate mine operation and long-term closure and reclamation of the mine site. To attain this objective, culverts are used to control and divert runoff underneath the road.

2.1.1 Erosion Control

To control erosion, rip rap will be installed around the culvert inlet and outlet areas. For an example of a rip rap section, see the typical culvert cross-section presented in appendix B. During the installation of the culverts, if required, silt curtains will be used in the work area to prevent total suspended solids from reaching downstream water bodies.

2.1.2 Culvert Specifications

The culverts that are proposed in this study will be in service for up to 15 years. The standard galvanized, corrugated steel pipe culvert is proposed. It is understood that the haul trucks to be used at the Project site will be CAT AD60 for underground trucks and Komatsu HD465 model or equivalent for open pit trucks. The culvert pipe originally proposed to handle the calculated runoff, were of 600 mm in diameter with a corrugation profile of 68X13 mm and a minimum specified thickness of 1.3 mm. As a safety measure against possible blockage from frost or ice, these culverts are oversized to a diameter of 900 mm. A minimum of 1 m fill cover will be placed over the culverts.

The location of the proposed culverts are shown in appendix A. A typical culvert cross-section is presented in appendix B.

The table below shows the characteristics of each culvert proposed.

Table 1 Culvert specifications

	Culverts		
	West – Service Road to Wesmeg	East – Service Road to Wesmeg	
Number of culverts in group	1	1	
Length of each culvert (m)	17.5	19.2	
Diameter of each culvert (mm)	900	900	

2.1.3 Figures and Drawings

Figure 1 in appendix A presents a general site layout plan. Drawing 65-695-230-222 in appendix B presents the construction details for the Wesmeg road culverts.



3.0 LIMITATIONS OF REPORT

This report and its contents are intended for the sole use of Agnico Eagle Mines Ltd. and their agents. Tetra Tech Inc. (Tetra Tech) does not accept any responsibility for the accuracy of any of the data, the analysis, or the recommendations contained or referenced in the report when the report is used or relied upon by any Party other than Agnico Eagle Mines Ltd., or for any Project other than the proposed development at the subject site. Any such unauthorized use of this report is at the sole risk of the user. Use of this report is subject to the terms and conditions stated in Tetra Tech's Services Agreement.

4.0 CLOSURE

We trust this report meets your present requirements. If you have any questions or comments, please contact the undersigned.

Respectfully submitted, Tetra Tech

> PERMIT TO PRACTICE TETRA TECH INDUSTRIES, INC.

Signature

Date Cold. 10.19

NT/NU Association of Professional Engineers and Geoscientists

Prepared by:

Christopher Morin, Jr. Eng.

Direct Line: 514.257.2427 x3240 Christopher.Morin@tetratech.com

Reviewed by: Josée Alarie, Eng.


J.M.I.F. ALARIE

Direct Line: 514.257.2427 x3323



APPENDIX A Figure 1





P:\28920\DESSIN\CIV-INFRA\DESSINS DE TRAVAIL\AUTDCAD\Sketch\6115-E-132-005-132-REP-003 FIGURE 1.dwg

APPENDIX B

Construction Drawing 65-695-230-222



