




Mary River Project
Attachment 5: Waste Management Plan for
Construction, Operation, and Closure
Appendix 10D-4

2012-01-10	C	Approved for Use Environmental Permit	A. Grzegorzczuk	J. Binns	S. Perry	
2011-12-19	B	Approved for Use	A. Grzegorzczuk	J. Binns	S. Perry	
2011-12-07	A	Approved for Use	A. Grzegorzczuk	J. Binns	S. Perry	
DATE	REV.	STATUS	PREPARED BY	CHECKED BY	APPROVED BY	APPROVED BY
						CLIENT

Rev. No.	Revision	Date	Approved
0	Document issued for approval	June 2010	
1	Updated for Type A Water License	October 2011	
2	Updated for Type A Water License	December 2011	

TABLE OF CONTENTS

	<u>PAGE</u>
SECTION 1: INTRODUCTION	2
1.1 PURPOSE	2
1.2 DEFINITIONS	3
1.3 REGULATORY REQUIREMENTS	4
1.4 RELATIONSHIP TO OTHER MANAGEMENT PLANS	5
1.5 BAFFINLAND'S COMMITMENTS	5
1.6 UPDATE OF THIS MANAGEMENT PLAN	5
SECTION 2: SUSTAINABLE DEVELOPMENT POLICY	6
SECTION 3: TARGETED VEC'S	8
SECTION 4: WASTE MANAGEMENT APPROACH	8
4.1 WASTE IDENTIFICATION	8
4.2 WASTE MANAGEMENT METHODS	9
4.3 WASTE FLOW	15
4.3.1 GENERATION POINTS	15
4.3.2 WASTE COLLECTION	15
4.3.3 TEMPORARY WASTE SORTING AND PROCESSING FACILITIES (DURING CONSTRUCTION PHASE ONLY)	15
4.3.4 PERMANENT WASTE SORTING AND PROCESSING FACILITIES	16
4.4 WASTE HANDLING AND MINIMIZATION BY CATEGORY	18
4.4.1 VEGETATION LESS THAN 80 MM DIAMETER, GRUBBED MATERIAL AND SOIL	18
4.4.2 OTHER SPOILS REMOVED DURING EXCAVATION	18
4.4.3 NONHAZARDOUS WASTE MATERIALS GENERATED DURING CONSTRUCTION OPERATIONS	19
4.4.4 UNSET CONCRETE AND CONCRETE WASH WATER FROM MIXING AND TRANSPORTATION OF CONCRETE	20
4.4.5 CAMP SITE WASTE	20
4.4.6 SEWAGE GENERATED AT THE VARIOUS WORKING LOCATIONS AND AT THE RAIL CAMP SITES	21
4.4.7 HAZARDOUS WASTE	21
4.4.8 OTHER MISCELLANEOUS MATERIALS, OR ITEMS THAT NO LONGER HAVE ECONOMIC VALUE	21
4.4.9 OFFICE PAPER	21
4.5 INCINERATORS	21
4.5.1 PERSONNEL TRAINING PROGRAMS FOR INCINERATOR OPERATION	23
4.5.2 AIR EMISSIONS	23
4.5.3 ASH DISPOSAL	24
4.5.4 MONITORING DURING OPERATION	24

4.6	INERT LANDFILL	25
4.6.1	LANDFILL OPERATION	25
4.6.2	OPERATING PROCEDURE	25
4.6.3	PLACEMENT OF WASTE	26
4.6.4	MONITORING DURING OPERATION	26
4.6.4.1	VOLUME AND WASTE COMPOSITION:	26
4.6.4.2	WATER SAMPLING AND SOIL:	26
4.6.4.3	GROUND TEMPERATURE MONITORING:	26
4.6.4.4	LEACHATE MONITORING:	26
4.6.4.5	INSPECTION AND MAINTENANCE:	26
4.6.5	ANNUAL REPORT	27
4.7	HAZARDOUS WASTE STORAGE AND DISPOSAL	27
4.8	IN-SITE TREATMENT OF HYDROCARBON CONTAMINATED MATERIAL	28
4.9	SHIP WASTE MANAGEMENT	28
4.10	USED TIRES	28
4.11	PROPYLENE GLYCOL	28
4.12	EPP PROCEDURES RELEVANT TO THIS WASTE MANAGEMENT PLAN	29
	SECTION 5: ROLES AND RESPONSIBILITIES	29
5.1	TRAINING PROGRAMS	31
5.2	COMMUNICATION	32
5.3	EXTERNAL COMMUNICATIONS	33
5.4	CONSTRUCTION	33
5.5	OPERATION & CLOSURE	33
	SECTION 6: PERFORMANCE INDICATORS, THRESHOLDS, AND INCIDENT RESPONSE	33
	SECTION 7: MONITORING AND REPORTING REQUIREMENTS	34
7.1	WASTE MONITORING	34
7.1.1	INCINERATOR MONITORING	34
7.1.2	LANDFILL MONITORING	34
7.1.3	HAZARDOUS WASTE MONITORING	35
7.2	OPERATIONS MONITORING	35
7.3	DATA MANAGEMENT	35
7.4	WATER LICENCE REPORTING	36
7.5	STAKEHOLDER REPORTING	36
	SECTION 8: ADAPTIVE STRATEGIES	36
	SECTION 9: QA /QC	36
	SECTION 10: REFERENCES	37

Annex

Annex 1: Block Waste Flow Diagrams

- H337697-7000-07-002-0001 Milne Port Site - Block Flow Diagram for Construction Solid Waste
- H337697-4210-07-002-0001 Mine Site - Block Flow Diagram for Construction/Operation Solid Waste
- H337697-4510-07-002-0001 Steensby Port Site - Block Flow Diagram for Construction/Operation Solid Waste
- H337697-7000-07-002-0003 Ravn River Rail Camp - Block Flow Diagram for Construction Solid Waste
- H337697-7000-07-002-0002 Mid Rail Rail Camp - Block Flow Diagram for Construction Solid Waste
- H337697-7000-07-002-0004 North Cockburn Lake Rail Camp - Block Flow Diagram for Construction Solid Waste
- H337697-7000-07-002-0005 South Cockburn Lake Rail Camp - Block Flow Diagram for Construction Solid Waste

Annex 2: Locations and Layouts of Waste Management Facilities

- H337697-7000-10-014-1001 Milne Inlet Construction Works Site Layout
- H337697-7000-10-014-1002 Mary River Mine Site Construction Works Site Layout
- H337697-7000-10-014-1003 Ravn River Rail Camp Construction Works Site Layout
- H337697-7000-10-014-1004 Mid Rail Camp Construction Works Site Layout
- H337697-7000-10-014-1005 South Cockburn Lake Rail Camp Construction Works Site Layout
- H337697-7000-10-014-1006 Steensby Inlet Construction Works Site Layout
- E337697-0000-10-042-0001 General Arrangement of Typical Landfarm
- E337697-PM406-50-014-0001 Milne Inlet Environmental Waste Management Building Layout
- H337697-7000-10-042-0007 Milne Inlet Environmental Waste Management Facilities
- H337697-4350-10-014-0001 Mine Site Landfill and Landfarm Site Layout
- H337697-4350-10-042-0001 Mine Site Environmental Waste Management Facility
- E337697-PM406-50-014-0002 Mine Site Environmental Waste Management Building Layout
- H337697-4660-10-014-0001 Steensby Inlet Landfill and Landfarm Site Layout
- E337697-PM406-50-014-0003 Steensby Inlet Environmental Waste Management Building Layout
- H337697-4660-10-042-0001 Steensby Inlet Environmental Waste Management Facility

Annex 3: Incinerator Operation Information

1. H377697-PM406: Section 2 - General Description ECO 1TN 1P
2. H377697-PM406: Section 5 - Operating Instructions ECO 1TN 1P
3. H377697-PM406: Section 6 - Maintenance Instructions ECO 1TN 1P

Annex 4: Mary River Project Landfill Operating Manual

Annex 5: Landfarm Operation Information

- Hydrocarbon Impacted Soils Storage and Landfarm Facility Operations Maintenance and Monitoring Plan (EBA, 2010)

Annex 6: Waste Sorting Guidelines

ABBREVIATIONS

Baffinland	: Baffinland Iron Mines Corporation
CCME	: Canadian Council of Ministers of the Environment
EHS	: Environmental, Health and Safety
EIS	: Environmental impact statement
EPCM	: Engineering, Procurement, and Construction Management
EPP	: Environmental Protection Plan
ERCB	: Energy Resources Conservation Board
IIBA	: Inuit Impacts Benefits Agreement
the Project	: Mary River Project
NIRB	: Nunavut Impact Review Board
NWB	: Nunavut Water Board
NWT	: Northwest Territories
QIA	: Qikiqtani Inuit Association
TDG	: Transportation of Dangerous Goods
VEC	: Valued Ecosystem Components
WMP	: Waste Management Plan