


Attachment 8.10

Milne Port Dumper Load Out Tunnel and Indexer Geotechnical Recommendations

(67 Pages)

**Baffinland Iron Mines Corporation
Mary River Expansion Project**

**Geotechnical Recommendations for Dumper Load-out Tunnel and
Indexer**

						
2018-07-30	0	Approved for Use	G Qu	W Hoyle	D Stanger	for R Stefan
Date	Rev.	Status	Prepared By	Checked By	Approved By	Approved By
HATCH						Client

DISCLAIMER

This Report has been prepared by Hatch Ltd. ("Hatch") for the sole and exclusive benefit of Baffinland Iron Mines Corporation (the "Client") for the sole purpose of assisting the Client to identify potential options to increase production from the Mary River mine, and may not be provided to, used or relied upon by any other party without the prior written consent of Hatch.

Any use of this report by the Client is subject to the terms and conditions provided in the ArcelorMittal General Service Agreement, dated November 14, 2014, including the limitations on liability set out therein. Without limiting the foregoing, Hatch explicitly disclaims all responsibility for losses, claims, expenses or damages, if any, suffered by a third party as a result of any reliance on this Report, including for any decisions made or actions made by such a third party and based on this Report ("Claims"), and such third party's use or review of the Report shall constitute its agreement to waive all such Claims and release Hatch in respect thereof.

This report is meant to be read, and sections should not be read or relied upon out of context. While it is believed that the information contained herein is reliable under the conditions and subject to the limitations set forth herein, this Report is based in part on information not within the control of Hatch and Hatch therefore cannot and does not guarantee the accuracy of such information based in whole or in part on information not within the control of Hatch. The comments in it reflect Hatch's professional judgment in light of the information available to it at the time of preparation.

This report contains the expression of the professional opinion of Hatch exercising reasonable care, skill and judgment and based upon information available at the time of preparation. Hatch has conducted this investigation in accordance with the methodology outlined herein. It is important to note that the methods of evaluation employed, while aimed at minimizing the risk of unidentified problems, cannot guarantee their absence. The quality of the information, conclusions and estimates contained herein is consistent with the intended level of accuracy as set out in this report, as well as the circumstances and constraints under which this report was prepared.

Client's Signature:

Name:

Title:

Date:

Table of Contents

1. Introduction.....	1
2. Geotechnical Site Information.....	1
3. Climate Conditions.....	2
4. Load-out Tunnel.....	2
4.1 Design Input / Criteria	2
4.2 Design Parameters	3
4.3 Bearing Capacity.....	3
4.3.1 Scenario (a).....	4
4.3.2 Scenario (b1).....	4
4.3.3 Scenario (b2).....	5
4.4 Settlement.....	5
4.5 Bearing Capacity Summary	6
4.6 Thermal Analyses	6
4.7 Design Considerations and Recommendations	6
4.7.1 General - Rockfill Pad Configuration (base-case)	6
4.7.2 Rockfill Pad Configuration For Tunnel Footing With High Loading Pressure	8
4.7.3 Insulation.....	9
4.7.4 Construction Schedule	9
4.7.5 Excavation /Backfill	9
4.7.6 Foundation Preparation	10
4.7.7 Tunnel Cover (i.e., Backfill) Materials	10
4.7.8 Permanent Cut Slope.....	11
4.7.9 Drainage.....	11
5. Indexer Foundation	12
5.1 Structural Design Input	12
5.2 Bearing Capacity.....	12
5.3 Subgrade Modulus.....	13
5.4 Sliding Friction Angle	13
5.5 Lateral Resistance of Shear Key	13
5.6 Lateral Earth Pressures	14
5.7 Backfill.....	15
5.8 Drainage	15
6. Dumper Foundation	15
6.1 Bearing Capacity.....	15
6.2 Drainage	16
6.3 Backfill.....	16
7. Assumptions and Limitations	16
8. References	18

List of Tables

Table 4-1: Design Parameter Summary	3
Table 4-2: Bearing Capacity Assessment Summary	5
Table A-1: N-factors to be Used in Modelling	2

List of Figures

Figure 1: Typical Cross-section of Load-out Tunnel	3
Figure 2: Typical Rockfill Pad Configuration for Load-out Tunnel	7
Figure 3: Insulation Pad Configuration (Cross Section) for Load-out Tunnel Segment near the Exit	7
Figure 4: Insulation Pad Configuration (Longitudinal Section) for Load-out Tunnel Segment near the Exit	8
Figure 5: Effect of Deformation on Earth Pressure in Cohesionless Material	14
Figure A-1: Mean Monthly Temperatures for Pond Inlet, NU (1981-2010).....	1

List of Appendices

Appendix A 1 Thermal Analyses

Appendix A2 Geotechnical Profile, Load-out Tunnel Configuration and Load Update

Appendix A3 Borehole Logs and Geophysical Survey Data

Appendix B Indexer Slab Drawings

1. Introduction

Hatch has been retained by Baffinland Iron Mines Ltd. (BIM) to design a Bulk Material Handling (BMH) system at the Milne Inlet Port for the Mary River Expansion Project.

The BMH system consists of a rail car dumper (tippler) located at the terminus of the mine-to-port railway, an indexer to push the rail car in the dumper, a loadout tunnel connecting with the dumper, a raw ore stockpile with embedded loadout tunnel, crushing and screening plants, and conveyor systems to transfer materials from the dumper through the crushing and screen plants to a longitudinal bucket-wheel stacker/reclaimer.

This memo provides geotechnical recommendations to support the design of (1) the foundation of the dumper loadout tunnel and (2) the foundation for the indexer mat and the dumper. Guideline and information from literature and engineering practice were used to develop these recommendations, as well as site conditions obtained from the previous investigation program (Hatch, 2017, Rev. 2). The design assumes that the dumper and the load-out tunnel are non-heated structures.

2. Geotechnical Site Information

The locations of the geotechnical site investigation are shown in the borehole layout drawing in Appendix A2, as well as a cross-section with the boreholes within the footprint of the structures. In summary, a total of five boreholes (BH16-M-007, BH16-M-008, and BH17-M008R, BH17-EBC-1 and BH17-EBC-2) were drilled in the vicinity of the dumper and loadout tunnel. BH17-M008R was drilled at the same location but slightly offset from BH16-M-008 to obtain bedrock information. A series of seismic line surveys were also performed to investigate the bedrock depth with calibration using bedrock information encountered in BH16-M-007, BH16-M-008 and BH16-M-008R. Appendix A3 provides the borehole reports and the seismic line survey data, while borehole reports BH17-EBC-1 and BH17-EBC-2 are presented in “draft” version as the investigation / laboratory testing program is still in progress at the time of this report preparation.

The subsurface conditions encountered at the site are highlighted as follows:

- The deposit at the hill crest comprises of a deposit of glacial fluvial sand to sand and gravel overlying till and then bedrock, while down the hill, the deposit consists of silts, silty sands and sands and gravels overlying till sitting on bedrock. A cobble and gravel layer was encountered right above bedrock in BH17-EBC-1 and BH17-EBC-2.
- Ground ice was encountered in borehole BH17-EBC-1. About 6 m of thick ground ice was encountered close to the surface of the native deposit. BH17-EBC-1 is located on the slope near the crest of the hill. A 3 m thick fill was placed to allow the access of the drilling rig. Under a 0.4 m thick surficial native gravel, the ground ice was encountered from el. 48.2 m to el. 42.2 m, with a 0.3 m thick interbedded sand layer from el. 46.5 m to el. 46.2 m. Below this interbedded sequence is a sand layer and a till deposit overlying a cobble and gravel layer and then bedrock. No ground ice was found at the corresponding elevations in the two nearby boreholes located

approximately 30 m north (BH16-M-008) and 40 m south (BH17-EBC-2) of BH17-EBC-1. It is possible that the ground ice found in BH17-EBC-1 formed from a run-off stream.

- The bedrock at the site generally dips from east to west down the hill. The bedrock is granitic gneiss with RQD values varying from 64% to 68% as encountered in BH17-M-008R.

3. Climate Conditions

The site is in a continuous permafrost zone with a mean annual air temperature of about -15°C, as per the mean monthly air temperature data from Pond Inlet, NU (1981-2010) extracted from the Government of Canada website. Climate information was summarized in Hatch Geotechnical Design Basis document (H353004-00000-229-210-0001, 2018). The global warming effect was taken into account according to the Intergovernmental Panel on Climate Change (IPCC) long term climate change studies. A temperature adjustment was applied considering global warming for the period spanning from 2010 to 2039 (see details in Hatch, 2018, H353004-00000-229-210-0001).

4. Load-out Tunnel

4.1 Design Input / Criteria

The load-out tunnel is an approximately 5.5 m high arch with a 7 m+/- wide span. It will be constructed by cut-and-cover method. The thin-plate arch will be founded on two (2) concrete footings. The design is being optimized to shorten the length of the tunnel. The total length of the tunnel is not finalized at the time of preparing this report.

The following provides the load-out tunnel footing information:

- Footing Size: 2.5 m (Width) x 0.8 m (Thickness), Reference drawing 2017-01195-S08, dated on 06/17/2017, by AIL (Atlantic Industries Limited).
- Footing Elevation (The upper side of the concrete footings): el. 39.1 m to 39.5 m (Preliminary Design dated November 2017).
- Footing Bearing Capacity: 500 kPa (SLS) as per a clarification email from AIL, dated on 07/20/2017.
- An updated footing bearing capacity sketch was received on May 2, 2018 noting that the bearing loadings for the footing near the dumper (about 16 m long) are increased to 680 kPa (SLS) and 820 kPa (ULS). The recommendations to address the updated loading pressure are provided in Section 4.7.2.
- Total settlement criteria is 75 mm and differential settlement along transverse direction is 25 mm as per a clarification email from AIL, dated on 07/20/2017.
- tkIS specified the settlement criteria for both the dumper loadout reclaim tunnel and the primary stockpile tunnel on 12/10/2017. The total settlement is less than 20 mm.




Figure 1: Typical Cross-section of Load-out Tunnel

(Reference drawing 2017-01195-S08, dated on 06/17/2017, by AIL)

4.2 Design Parameters

Table 4-1 summarizes the key design parameters used in the calculations.

Table 4-1: Design Parameter Summary

Material	Unit Weight (kN/m ³)	Effective Friction Angle (°)	Deformation Modulus	Frozen Soil Allowable Bearing Capacity (kPa)
Rockfill	20	40	70 MPa	-
Native Sandy Soil (ice content typically less than 20%)	18	32	80 MPa*	380kPa below – 4° C

Note: * Equivalent deformation modulus for long-term deformation. Applicable for low ice content permafrost (less than 20%), which is likely the native foundation soil below the tunnel footing as per the available borehole investigation. The parameters were estimated as per the literature test studies by Tsytoich et al. (1973) and Zhu and Carbee (1984) (see Hatch Geotechnical Design Basis, 2018).

4.3 Bearing Capacity

The native foundation soil is expected between el. 36.8 m and 37.2 m, considering the concrete footing thickness (0.8 m) and the rockfill pad thickness (1.5 m). At this elevation range, the native foundation soil is expected to be silty sand (till) and possible sand and gravel as inferred from the existing borehole investigation data (see Appendix A2).

The allowable bearing capacity of the tunnel foundation is estimated based on the following assumptions:

- A factor of safety of 2.5 is applied to the ultimate bearing capacity to obtain the allowable bearing capacity.
- The foundation bearing capacity was checked for the following scenarios:
 - (a) Bearing capacity of a two-layer foundation system with a top rockfill layer and an underlying native soil layer. The parameters for the rockfill and underlying soil are listed in Table 4-1. A weighted average friction angle for the two-layer foundation is to be calculated as per the recommendation by Bowles (1988).

$$\phi = \frac{d_1\phi_1 + (H - d_1)\phi_2}{H}$$

Where the influence depth $H = 0.5 \times B \times \tan(45 + \phi_1/2)$, where ϕ_1 is the friction angle for the top layer, ϕ_2 for the bottom layer, d_1 is the thickness of the top layer, B is the footing width.

- (b) Bearing capacity of the lower soil. Its bearing capacity was checked for two scenarios: (b1) bearing capacity assuming the permafrost is unbonded (i.e., friction only), and (b2) bearing capacity assuming the permafrost is well bonded (i.e., cohesion only).

Meyerhof's general bearing capacity equation (Das, 2007) was used to calculate the bearing capacity. Meyerhof's equation is (i.e., for zero cohesion):

$$q_u = qN_qF_{qs}F_{qd} + \gamma'BN_yF_{ys}F_{yd} \quad (\text{Equation 1})$$

where q is the surcharge load at the bottom of the foundation, N_q and N_y are bearing capacity factors, B is the foundation width, F_{qs} and F_{rs} are shape factors, and F_{qd} and F_{yd} are depth factors. γ' is the unit weight of soil.

Table 4-2 summarized the analyses results.

4.3.1 Scenario (a)

Using Eqn. 1, the allowable bearing capacity of the two-layer system is 500 kPa, satisfying the required design load (500kPa). The parameters for the rockfill and underlying soil are listed in Table 4-1.

4.3.2 Scenario (b1)

As the foundation soil contains a relatively low water content and may not develop full ice bond among particles, the foundation bearing capacity was checked assuming it would behave as an unbonded (i.e., cohesionless) granular material. The allowable bearing capacity based on the silty sand (shear strength) is 650 kPa, using the 2:1 stress distribution rule.

$$q_{allow} = q_{soil_allowable} \times [(1.5m + B)/B] = 360kPa \times [(1.5m + 2.5m)/2.5m] \approx 650 kPa$$

4.3.3 Scenario (b2)

Assuming the permafrost is well bonded, the allowable bearing capacity for the footing is estimated to be 550 kPa assuming the underlying permafrost can be maintained at a temperature below - 4° C. The 2:1 stress distribution rule was used to estimate the stress on the lower permafrost layer.

$$q_{allow} = 380kPa \times [(1.5m + B)/B] \approx 550 kPa$$

In summary, the 1.5 m thick rockfill pad will satisfy the bearing capacity requirement given that the temperature of underlying permafrost is below -4°C. As shown in the next section, an insulation layer (150 mm Styrofoam HL 100 or equivalent) is required to achieve the temperature requirement.

Table 4-2: Bearing Capacity Assessment Summary

Case	Case Description	Allowable Bearing Capacity (kPa)	Required Bearing Capacity (kPa)
Case A	Rockfill and Soil	500	500
Case B1	Underlying Soil (Friction Strength)	650	500
Case B2	Underlying Soil (Permafrost Bond Strength)	550	500

4.4 Settlement

For the proposed rockfill pad foundation and the SLS load, the load-out tunnel is expected to be less than 70 mm for total settlement and 35 mm for differential settlement in the transverse direction.

- The expected total and differential settlement satisfies the requirement by AIL (Total settlement is less than 75 mm as per a clarification email from AIL, dated on 07/20/2017).
- The expected total settlement of the rockfill pad foundation exceeds the settlement requirement of 20 mm by tkIS on 12/10/2017. Releveling the conveyor in the load-out tunnel may be required. Alternatively, pile foundation can be considered.

The load-out tunnel is to be constructed by cut-and-cover method. Considering the tunnel's opening size (about 5.5 m high and 7 m span), the overall net loads due to the backfill to foundation soil is expected to be low.

The load-out tunnel is expected to be founded on permafrost for the west section near the tunnel exit and on bedrock for its east end (near the tie-in to the dumper). The transition zone from the permafrost soil to bedrock foundation should be graded in a way to minimize the differential settlement of the tunnel footings.

The thaw settlement is excluded in this report as the design includes a rockfill and insulation pad to prevent permafrost thaw during operation. The construction should be carried out in cold seasons to avoid any potential thaw settlement during construction (see Section 4.7 for details).

4.5 Bearing Capacity Summary

In summary, for the for the 2.5 m wide footing with a 1.5 m thick rockfill pad, the bearing capacity for serviceability limit state is 500 kPa with the total settlement less than 75 mm and a differential settlement of 25 mm. The factored bearing capacity in ultimate limit state (Factored ULS) is 630 kPa ($=500\text{kPa} \times 2.5 \times 0.5$) with a geotechnical resistance factor of 0.5.

4.6 Thermal Analyses

Thermal analyses were performed to evaluate the temperature regime in the foundation below the tunnel. Appendix A1 summarizes the methodologies and details of the thermal analyses. Figure A-1 presents the general material and boundary conditions.

- (1) Case with Insulation: In this case, an insulation pad is used in the model to control the temperature at underlying native sand. With the insulation pad, the temperature of the underlying permafrost is about -6°C (see Figure A2 for the temperature contours 2 years after construction and Figure A3 for 20 years after construction in Appendix A1), which satisfies the temperature requirement of -4°C .
- (2) Case Without Insulation: Without insulation, the temperature of the underlying permafrost is about -2°C in the warmest summer (see Figure A4 and Figure A5 in Appendix A1). The permafrost at -2°C will not provide sufficient bearing capacity for the design load.

Based on the thermal modelling, a 150 mm thick insulation pad is required to control the permafrost temperature to ensure the required bearing capacity for the footing.

It is noted that the active zone may temporarily extend to the tunnel base for a short duration in summer (see Figure A6 in Appendix A). Accordingly, the backfill material adjacent to the tunnel must be free-drain granular to allow efficient drainage of any water. The drainage pipe is not recommended as it would be blocked by ice.

4.7 Design Considerations and Recommendations

4.7.1 General - Rockfill Pad Configuration (base-case)

A 1.5 m thick layer of rockfill is required below the loadout tunnel footings to ensure adequate bearing capacity up to 500 kPa.

Figure 2 illustrates the recommended rockfill pad configuration. The rockfill pad consists of mainly coarse rockfill (Type 8 Fill) underlain by a non-woven geotextile placed on the permafrost. The upper surface of the rockfill has a 100mm thick layer of leveling material (Type 9 Fill) underlain by a 150 mm thick transition layer (Type 5 Fill). The insulation pad is placed between the footings with a cushion layer of TY 5.

Near the tunnel exit, the insulation pad should be placed all around the footing and extent to tie-in with the excavation boundary to preserve the underlying permafrost and minimize the water migration, as shown in Figure 3 and Figure 4.

The construction for the rockfill pad shall be carried out in cold seasons to avoid disturbance of the underlying permafrost (see Section 4.7.4 for details).

The permafrost below the foundation may contain ground ice / ice-rich soil, which may lead large creep settlement of the tunnel. If encountered, the ground ice or ice-rich soil must be removed i.e. over-excavated (see Section 4.7.5 for details) and the excavation backfilled with rockfill. A non-woven geotextile separator is required between rockfill and the permafrost. If the ground ice / ice-rich soil is not removed, large post construction settlement will likely occur induced by ground-ice/ ice-rich soil creep.




Figure 2: Typical Rockfill Pad Configuration for Load-out Tunnel

(Over-excavation from the underside of the footing may be required if the ground ice / ice-rich soil is encountered)




Figure 3: Insulation Pad Configuration (Cross Section) for Load-out Tunnel Segment near the Exit

(Applicable for the tunnel section 15 m into backfill or extending to where the external backfill over the tunnel foundation is 5 m thick, whichever is longer. The insulation pad shall be placed all round the footing at the exit including the front side).




Figure 4: Insulation Pad Configuration (Longitudinal Section) for Load-out Tunnel Segment near the Exit

4.7.2 Rockfill Pad Configuration For Tunnel Footing With High Loading Pressure

An updated footing bearing capacity sketch was received on May 2, 2018, as shown in the Sketch 3 in Appendix A2. For the tunnel section (about 16 m long) near the dumper, the loading pressure are 680 kPa (SLS) and 820 kPa (ULS), which are higher than the loading capacity of the base-case rockfill pad configuration. The following provides geotechnical recommendation to address the high loading pressure expected for the tunnel section near the dumper.

The foundation soil below the footing of this section is likely silty sand till with a thickness less than 10 m overlying bedrock as shown in the Sketch 2 in Appendix A2.

The footing of this tunnel section should be founded either on bedrock or on a thicker rockfill pad.

- A **2.5 m** thick rockfill pad below the 2.5 m wide footing will provide a factored ultimate limit state capacity of 850 kPa and a serviceability limit state bearing capacity of 700kPa (SLS) corresponding a settlement less than 70 mm and a differential settlement less than 35 mm. The alternative options are to use a larger-size footing or use pile foundation to reduce the settlement, likely with a higher cost.
- For the bedrock foundation, the recommended bearing capacities are 1.0 MPa for the SLS state corresponding to a settlement less than 25 mm and 1.5 MPa for the Factored ULS state.

4.7.3 *Insulation*

The backfill for the load-out tunnel will serve as insulation for the foundation permafrost. Additionally, the temperature of the permafrost below the tunnel floor is expected to rise during the summer due to the air temperature fluctuations in the tunnel. A styrofoam insulation layer (insulation material) was been designed to control the temperature of the native permafrost, which is required to ensure sufficient bearing capacity as specified in Section 4.1. Accordingly, proper installation of the insulation material is critical to ensure satisfactory performance of the tunnel.

The insulation layer will be placed at the base level of the tunnel with layers placed such that the panels overlap the joints in the underlying layer. It is noted that the insulation material should not be placed directly beneath the footing, due to the insufficient long-term compressive strength of insulation pads (230 kPa for Styrofoam HL 100, with a factor of safety 3 as per product sheet recommendation to avoid long-term creep).

4.7.4 *Construction Schedule*

The excavation and foundation backfill placement for the loadout tunnel should be carried out during the cold seasons (October to April) when the daytime temperatures are below 0°C. Construction during the summer (June to September) will significantly increase the risk of thawing the underlying permafrost, instability of the high side slopes over 10 m, and the cost of the work. As such, the construction for foundation in the summer (June to September) is not recommended.

4.7.5 *Excavation /Backfill*

The contractor should be fully responsible for construction safety. The safe slope gradient for temporary excavations depends on the construction methodology, permafrost material, and the season/temperature during construction. In general, an overall slope gradient of 1.5H:1V should be adequate for the temporary cut into the permafrost with blasting.

The limited geotechnical investigations undertaken for design indicate the presence of random ground ice. As a result, the side slopes for the cut may need to be locally laid back at flatter gradients than 1.5H:1V if ground ice is encountered.

Furthermore, the excavation may need to be deepened to remove ground ice below the rockfill pad. Since the excavation will be done by drill and blast method, this may be difficult to do if the excavation has progressed significantly prior to encountering the ground ice. Accordingly, the contractor should probe the ground with drill rigs prior to executing the excavation to adequately plan and adapt to the presence of ground ice. Sonic drill rigs give the best results. An excavation plan (i.e. depth and slope gradients) should be developed based on the probe hole drilling prior to commencing production drill-and-blast excavation.

During excavation construction, shallow slope sloughing should be expected and a maintenance program should be carried out to maintain the slopes. The contractor will probably need to cover the excavated slope with insulation materials and/or a layer of crushed rock as the excavation is advanced to protect the slopes.

The contractor should remove snow efficiently during the backfill construction.

If the general backfill construction of the load-out tunnel extends to the spring freshet, then run-off will need to be controlled and diverted away from the work area. The introduction of water and warmer temperatures to the base of the excavation will lead to disturbance of the permafrost and contribute to poor performance of the tunnel after construction.

A qualified engineer with arctic construction experience should be on site supervising the construction to ensure QA/QC. After completing the excavation, periodical inspections will be required during construction of the plate-arch tunnel.

4.7.6 Foundation Preparation

Ground ice or ice rich permafrost, if encountered below the foundation base from the probing program, should be completely excavated. Over excavated areas should be backfilled with a 150 mm cushion granular material at the base followed by rockfill.

A qualified geotechnical engineer shall inspect and approve the foundation base prior to backfilling.

4.7.7 Tunnel Cover (i.e., Backfill) Materials

The tunnel cover (i.e., backfill) material will be specified by the tunnel supplier (AIL).

The common fill can be rockfill (run of quarry) or pit-run materials free of ice and snow, as approved by the Engineer.

The backfill material for the rockfill pad are either crusher-run granular fill, rockfill or approved material by the Engineer.

It is critical to properly place and compact the foundation rockfill pad as per the project specifications (Hatch, H353004-00000-221-078-0001, Rev. 1). A test rockfill compaction pad is recommended to verify the compaction achieved at site.

As a minimum the following shall be satisfied:

- a. Rockfill shall be compacted by 5 passes of a 10 ton vibratory roller with vibrations in the range of 1200 to 1500 vpm and the roller speed of about 2 mph (3.2 km/h). One

pass is defined as a full cover the fill area. Alternative compactors such as heavy loaded rubber-tired haul trucks can only be used as per a written approval from the Engineer.

- b. TYPE 5 Fill (crusher-run 32 mm minus material) or TYPE 9 Fill (9 mm minus): the material must be placed in lifts not exceeding 200 mm.
- c. TYPE 8 Fill (crusher-run 150 mm minus): the rockfill must be placed in lifts not exceeding 500 mm. The placement shall avoid segregation and nesting of coarse particles.
- d. TYPE 12 (run-of-mine, typically 600 mm minus): the rockfill must be placed in lift not exceeding 1000 mm, or as approved by the Engineer.

4.7.8 Permanent Cut Slope

Permanent cut slope is required near the tunnel exit.

The overall slope of the permanent cut less than 15 m is recommended to be executed at a gradient of 2.5H:1V or flatter. A benched slope is recommended to better control the erosion (i.e., 5 m high and 2.5 m wide bench with a 2H:1V side slope may be considered). Locally flattening of the slope will be required where ice and very ice-rich soil is encountered.

A thermal protection layer should be placed on the slopes of permanent cuts into native soil and engineered fill. The protection layer should comprise a 1 to 2 m thick layer of rockfill (run of quarry or jaw-run rockfill) or equivalent as approved by the engineer. A toe-berm may be required to protect the toe from causing local slope instability due to potentially softening of the toe during thaw seasons, particularly where ice-rich permafrost is encountered.

4.7.9 Drainage

Proper drainage is an important component to ensure a satisfactory performance of the load-out tunnel.

- (1) Grade the tunnel base downward from the dumper toward the exit. Crown the backfill granular between the tunnel footings.
- (2) Runoff collection and diversion systems should be provided to efficiently direct run off away from the tunnel and slope benches. Grade the ground surface away from the tunnel exit at a 2% minimum gradient.
- (3) For the backfill above the tunnel, it is recommended to cap the tunnel backfill (i.e., the rockfill and crusher run fills specified by AIL) with select thawed native material collected from the excavation. A geotextile separator should be installed between the cap material and the underling coarse rockfills and granular materials. The cap should be sloped and graded such that water does not pond or collect on top of the tunnel. Design the finished grades around the works to minimize the amount of run-off that may enter the area after putting the tunnel into service.

- (4) A sufficient temporary drainage system should be provided during excavation construction, if the construction period extends in above-zero-temperature seasons, to avoid any ponding water in the excavated areas. Drainage ditch, sump and pump should be prepared to efficiently drain the run off or meltwater to avoid any ponding water at the base of the excavation during construction. The ditches with concentrated waterflow and sumps at the base should be lined.

5. Indexer Foundation

5.1 Structural Design Input

The indexer slab is a mat foundation consisting of pre-casted concrete blocks reinforced by post-tensioned cables. Appendix B provides the preliminary design drawings for the indexer.

The preliminary structure design input is summarized below:

- Foundation Size: 8 m wide, 25 m long, and 1 m thick (Preliminary)
- Foundation Shear Key: 1 m wide and 3 m deep (Preliminary).

5.2 Bearing Capacity

The indexer slab is expected to be found on well compacted rockfill. The rockfill below the indexer mat is about 15 m thick to the bedrock.

The factored geotechnical resistance at the ultimate limit state is very high (over 500 kPa) for the mat foundation. Typically, the ultimate limit resistance will not govern the design for mat foundations.

Serviceability Limit State (SLS) geotechnical reaction is 200 kPa corresponding to 25 mm elastic settlement.

The creep-related settlement of the rockfills is likely small in the light of the following conditions:

- (1) The rockfill is laterally confined by the dumper wall and the adjacent soil.
- (2) The rockfill below the active zone is kept frozen.
- (3) The parent rock for the rockfill is granite gneiss with a high to very high strength. The rockfill is to be well compacted.

There are very few studies for the creep settlement of frozen rockfills. A recent case-study for the Doris Dam (10 m high dam on permafrost with rockfill shells and a cut-off core, see Miller and Rykaart 2016) concluded that there is negligible creep settlement at the crest (less than the survey accuracy of 10 mm) 4 years after construction. For unfrozen rockfill, the study by Clements (1984) suggests the range of post-construction long-term settlement of compacted rockfill dams is from 0% to 0.25% of dam height (the dam height in the study ranging from approximate 60 m to 180 m) provided the rockfill is placed in lifts and compacted. It is noted that the settlement observations are based on rockfill dams without lateral confinement and with impacts of water impounding. Sherard and Cooke

(1987) suggested that the half of the rockfill creep occurs during the first 5 years and the other half in 100 years.

As such, the creep settlement of the backfilled rockfill (about 15 m thick) is expected to be in the order of 30 mm for the design life of 20 years. As a result, the indexer should be designed taking into account the elastic and creep settlements.

5.3 Subgrade Modulus

The mat foundation with an 8 m width can be designed base on a modulus of subgrade reaction of 10 MPa/m for compacted rockfill.

5.4 Sliding Friction Angle

For the pre-cast concrete foundation founded on granular or rockfill, the friction angle of 24 degrees (friction coefficient of 0.45) is recommended as per Hatch geotechnical design criteria (Hatch, 2017, H352004-0000-229-078-0001).

5.5 Lateral Resistance of Shear Key

It is understood that a shear key may be used in the mat foundation design to resist the lateral load. The shear key should be designed using a coefficient of lateral earth pressure K from K_0 (0.36) upto $K_p / 5$ (0.9) in order to limit the lateral movement required to mobilize the lateral resistance of the key. A lower factor of safety to K_p can be used if the lateral deflection of the shear key is allowed within the design tolerance level as determined by the structural design engineer.

Figure 5 illustrates the relationship between the deflection and lateral earth pressure coefficient for reference (CFEM,2006).




Figure 5: Effect of Deformation on Earth Pressure in Cohesionless Material

5.6 Lateral Earth Pressures

The lateral earth pressure on the shear key and dumper walls should be calculated as per the following expression, assuming a triangular pressure distribution:

$$p = k (\gamma h + q)$$

where p = the pressure in kPa acting against the wall surface at depth, h , below the finished ground surface

k = lateral earth pressure coefficient;

γ = the bulk unit weight of the retained backfill;

h = depth below the ground surface at which the pressure, p , is to computed; and

q = the value of any adjacent surcharge in kPa which may acting close to the wall (including traffic loads).

The above equation assumes that a non-frost susceptible and free-draining granular backfill adjacent to the dumper's wall, to prevent the frost heave pressure behind the wall.

The physical properties of well compacted rockfill are presented as follows:

Compacted Rockfill

Angle of Internal Friction (ϕ) = 40° (unfactored)

Coefficient of Lateral Earth Pressures:

K_a = 0.22 (unfactored)

K_0 = 0.36 (unfactored)

K_p = 4.6 (unfactored)

Notes:

K_a is the active earth pressure coefficient for a soil loading an unrestrained structure;
and

K_0 is the earth pressure coefficient at rest for a soil loading a restrained structure.

K_p is the earth pressure coefficient a soil loading to a passive failure state.

The dumper structure design shall account for the additional lateral earth pressure caused by the surcharge of the indexer and the lateral load transferred from the indexer to the dumper wall.

5.7 Backfill

The backfill below the mat foundation should be crusher-run, free-drained, and non-frost susceptible rockfills.

A layer of TYPE 5 (32 mm minus), minimum 300 mm thick, should be placed immediately below the indexer foundation as a leveling course.

TYPE 5 (typically 3 m wide) is recommended to be placed adjacent to any vertical concrete/steel structures to serve as a protection layer from direct contact with large-sized rockfills.

The general backfill rockfill should be TYPE 8 (150 mm minus). A geotextile should be used to separate the native soil and the rockfill backfill.

The backfill should be placed and compacted as per Hatch specification and the notes in the construction drawings.

5.8 Drainage

Runoff collection and diversions systems should be provided to efficiently direct run off away from the dumper and the mat foundation.

6. Dumper Foundation

6.1 Bearing Capacity

The dumper should be found directly on bedrock. The bedrock properties below the dumper foundation are expected to be similar to the rock mass encountered in BH 17-008R, BH17-EBC-1 and BH17-EBC-2.

The bearing capacity of sound rock foundation was estimated using the approach recommended by CFEM (2006)

$$q_{allowable} = K_{sp} \times q_{u-core}$$

where q_{u-core} is the unconfined compression strength of the intact rock (i.e., 23.6MPa as per BH 17-008R). The coefficient of K_{sp} is selected as 0.05, as per the bedrock condition.

Serviceability Limit State (SLS) geotechnical reaction is 1 MPa for the bedrock foundation.

The rock surface should be prepared by removing loose or weathered materials for a competent surface. The bedrock foundation condition should be inspected and approved by a qualified geologist or geotechnical engineer prior to foundation construction. The blasting should be designed and performed in a way to minimize over-blasting. A lean concrete slab is recommended to level the blasted surface below the pre-cast concrete structure. If using granular leveling materials as alternative, the differential settlement due to the compression of the granular in depression should be taken into account in the structure design.

6.2 Drainage

Runoff collection, and ground grading should be provided to efficiently direct run off away from the dumper. Temperately drainage during construction should be provided to sufficiently control run-off water from ponding at foundation level.

6.3 Backfill

The backfill below the mat foundation should be crusher-run, free-drained, and non-frost susceptible rockfills.

TYPE 5 (typically 3 m wide) is recommended to be placed adjacent to any vertical concrete/steel structures to serve as a protection layer from direct contacting with large-sized rockfills.

An insulation pad (two layers of Styrofoam HL 100) is recommended to be placed against the wall to keep the permafrost state of the backfill and minimize potential degradation from the freeze/thaw effect.

The general backfill rockfill should be TYPE 8 (150 mm minus). TYPE 12 (run of quarry) may be used where the settlement is not a concern. A geotextile should be used to separate the native soil and the rockfill backfill.

The backfill should be placed and compacted as per Hatch specification and the notes in the construction drawings.

7. Assumptions and Limitations

This report and the engineering described herein is based on five boreholes advanced into the permafrost near the project site. The boreholes indicate the presence of ground ice in the permafrost; the distribution of the ground ice appears to be random. As a result, construction should be coupled with sufficient pre-drilling and probing at major cuts and in

the foundation of major structures to delineate the ground ice to reduce uncertainties. Based on the results of the probing, excavations for the foundations and load out tunnels may need to be adjusted to take into account the presence of ground ice or ice rich soil. The construction approach will need to be observational or adaptive.

Additionally, the recommendations in this report are based on the results of calculations performed using deformation and creep properties for permafrost from the literature. Site specific creep tests have not been performed, and as a result, there is residual risk of applying the engineering parameters from literature to assess the performance of the infrastructure. Hatch has used reasonable judgment and has consulted with experts to develop parameters for the permafrost. During construction, site-specific load tests and creep tests should be conducted on the permafrost to verify design parameters. The tests should consist of in situ plate load tests with temperature monitoring and/or temperature controlled triaxial compression tests on the permafrost, to confirm the strength, deformation and creep parameters used for design. Some adaptation of the design may be required based on these tests.

The design recommendations given in this report are applicable only to the project described in the text and then only if constructed substantially in accordance with the details stated in this report.

8. References

1. Hatch, 2012, "Geotechnical Data Report -Infrastructure" (ref H337697-0000-15-1240004, Rev. C), April 05, 2012.
2. Hatch, 2016, "Geotechnical Criteria for Building Foundations at Milne Inlet", H352004-0000-229-078-0001, Rev. 0, Dec. 15, 2016.
3. Hatch, 2016, "Preliminary Geotechnical Recommendation for Infrastructures at Milne Inlet", H352004-0000-229-230-0002, Rev. 0, Sept. 01, 2016.
4. Hatch, 2017, "2016 Milne Port Geotechnical Investigation Factual Data Report", (ref H352034-1000-229-230-0002), Rev.2.
5. Hatch, 2018, "Hatch Geotechnical Design Basis", H353004-00000-229-210-0001, Rev. A, 2018.
6. Das, Braja, 2007, "Principles of Foundation Engineering", Sixth Edition, Thomson.
7. Andersland, B.A., Ladani, B., 2004, "Frozen Ground Engineering", Second Edition, ASCE, John Wiley and Sons, Inc.
8. Canadian Geotechnical Society, 2006, "Canadian Foundation Engineering Manual", Fourth Edition.
9. Bowles, J.E. "Foundation Analyses And Design" Fourth Edition.
10. Johnston G.H., 1971, "Permafrost Engineering Design and Construction".
11. Tsytoich, N.A., Kronik, Ya.A., Markin, K.F., Aksenov, V.I. Physical and Mechanical Properties of Saline Soils. Proc. 2nd International Conference on Permafrost (1973), Yakutsk, USSR Contributin, U.S. National Academy of Sciences, pp. 238-247.
12. Zhu, Y. and Carbee, D.L., 1984. Uniaxial compressive strength of frozen silt under constant deformation rates. Cold Regions Science and Technology, 9(1), pp.3-15.
13. Clements, R.P. 1984 Post-construction deformation of rockfill dams. Journal of Geotechnical Engineering, 110: 1384-1414.
14. Sherard, J.L. and Cooke, J.B. 1987. Concrete-face rockfill dam I. Assessment. Journal of Geotechnical Engineering, 113: 1096-1112.
15. Miller, M. and Rykaart, M. 2016, Frozen core dam performance : four years post construction. Canadian Dam Association, Halifax.

Appendix A1

Thermal Analyses

Appendix A1

Thermal Analyses

Two-dimensional finite element modelling, with commercially available software (Temp/W), was used to predict the thermal regime for the tunnel foundation.

The air temperature is based on the mean monthly air temperature from Pond Inlet, NU (1981-2010) extracted from the government of Canada website, see Figure A-1.

The global warming effect was taken into account according to the Intergovernmental Panel on Climate Change (IPCC) long term climate change studies. A temperature adjustment was applied considering to global warming for the period spanning from 2010 to 2039 (Hatch 2018).




Figure A-1: Mean Monthly Temperatures for Pond Inlet, NU (1981-2010)

Surface boundary conditions at the site were obtained based on the n-factors which was used to correlate air temperatures to ground surface temperatures during cold seasons (n_f) and thaw seasons (n_t). Values of n_t and n_f used in the analysis were summarized in Table A-1. Typically, n_f is less than 1 considering the impact of snow accumulation/insulation over ground surface during winter while n_t is more than 1 considering the impact of radiation.

Inside the tunnel, the n factor of 1 was used assuming that the ground surface temperature is same as the air temperature. It is noted that in summer the air temperature in the tunnel could be colder than the air temperature outside while in winter, the inside air temperature in the tunnel becomes is likely warmer than the outside air temperature. There is no sufficient data/study to quantify the two opposite effects. As such, this study assumed that the air temperature in tunnel is same.

The available thermistor data from the Mary River site (Hatch, 2012) indicate that ground temperature reaches equilibrium (at -10°C) below 15m depth, thus the bottom boundary was assumed to be 15m below the ground surface, with a constant temperature of -10°C .

The initial temperature of the foundation rockfill is -3°C degree and the other backfill materials are set as 0°C degree.


Table A-1: N-factors to be Used in Modelling

Material	N – factors	
	Freezing (n_f)	Thawing (n_t)
Native Sand	0.7	1.2
Rockfill / Granular Backfill	0.8	1.5
Tunnel Inside Boundary	1	1

The following two cases were analyzed:


- (1) Thermal model of load-out tunnel with 100 mm insulation pad.
- (2) Thermal model of load-out tunnel without insulation.

Color	Name	Unfrozen Thermal Conductivity (J/sec/m/°C)	Frozen Thermal Conductivity (J/sec/m/°C)	Unfrozen Volumetric Heat Capacity (J/m³/°C)	Frozen Volumetric Heat Capacity (J/m³/°C)	Vol W/C (m³/m³)	Initial Temperature (°C)
	Granular Back Fill	3	4.5	3,000,000	2,400,000	0.036	0
	Rockfill Pad	3	4.5	3,000,000	2,400,000	0.036	-3
	Sandy Deposit	2	3	2,600,000	2,600,000	0.255	
	Concrete	1.5	1.5	2,000,000	2,000,000	0.024	-3
	Insulation	0.035	0.035	37,500	37,500	0	-3



Job number		353004		Mary River Expansion Project			BIM	
Ref	Tippler Load-out Tunnel			Thermal Model			Milne Inlet Port	
By	Lk	0	02-Apr-18				FIGURE A1	
Revision		A	02-Apr-18					


File Name: Dumper_LK_updated.gsz
Name: All Sand 150mm insulation
Date: 4/2/2018
Directory: P:\REDLEAF\335458\SPECIALIST_APPS\02 Marry River\08 Dumper\Dumper thermal model\



Job number		353004		Mary River Expansion Project			BIM	
Ref	Tippler Load-out Tunnel			Insulation Temperature Contour In Summer (2 yr after construction)			Milne Inlet Port	
By	Lk	0	02-Apr-18				FIGURE A2	
Revision		A	02-Apr-18					

Fig A2 | 4/2/2018 1:17 PM | P:\REDLEAF\335458\SPECIALIST_APPS\02 Marry River\08 Dumper\Memo\Appendixes\Figure Thermal Model - Dumper v2.xlsx


File Name: Dumper_LK_updated.gsz
Name: All Sand 150mm insulation
Date: 4/2/2018
Directory: P:\REDLEAF\335458\SPECIALIST_APPS\02 Marry River\08 Dumper\Dumper thermal model\



Job number		353004		Mary River Expansion Project			BIM		
Ref	Tippler Load-out Tunnel			Insulation Temperature Contour In Summer (20 yr after construction)			Milne Inlet Port		
By	Lk	0	02-Apr-18						
Revision		A	02-Apr-18						
								FIGURE A3	


Fig A3 | 4/2/2018 1:17 PM | P:\REDLEAF\335458\SPECIALIST_APPS\02 Marry River\08 Dumper\Memo\Appendixes\Figure Thermal Model - Dumper v2.xlsx

File Name: Dumper_LK_updated.gsz
 Name: All Sand No insulation
 Date: 4/2/2018
 Directory: P:\REDLEAF\335458\SPECIALIST_APPS\02 Marry River\08 Dumper\Dumper thermal model\





Job number		353004		Mary River Expansion Project			BIM	
Ref	Tippler Load-out Tunnel			No Insulation Temperature Contour In Summer (2 yr after construction)			Milne Inlet Port	
By	Lk	0	02-Apr-18				FIGURE A4	
Revision		A	02-Apr-18					

File Name: Dumper_LK_updated.gsz
 Name: All Sand No insulation
 Date: 4/2/2018
 Directory: P:\REDLEAF\335458\SPECIALIST_APPS\02 Marry River\08 Dumper\Dumper thermal model\





Job number		353004		Mary River Expansion Project			BIM	
Ref	Tippler Load-out Tunnel			No Insulation Temperature Contour In Summer (20 yr after construction)			Milne Inlet Port	
By	Lk	0	02-Apr-18				FIGURE A5	
Revision		A	02-Apr-18					

File Name: Dumper_LK_updated.gsz
 Name: All Sand 150mm insulation
 Date: 4/2/2018
 Directory: P:\REDLEAF\335458\SPECIALIST_APPS\02 Marry River\08 Dumper\Dumper thermal model\





Job number		353004		Mary River Expansion Project			BIM	
Ref		Tippler Load-out Tunnel		Insulation Temperature Contour In April (20 yr after construction)			Milne Inlet Port	
By	Lk	0	02-Apr-18				FIGURE A6a	
Revision		A	02-Apr-18					

File Name: Dumper_LK_updated.gsz
 Name: All Sand 150mm insulation
 Date: 4/2/2018
 Directory: P:\REDLEAF\335458\SPECIALIST_APPS\02 Marry River\08 Dumper\Dumper thermal model\





Job number		353004		Mary River Expansion Project			BIM	
Ref		Tippler Load-out Tunnel		Insulation Temperature Contour In June (20 yr after construction)			Milne Inlet Port	
By	Lk	0	02-Apr-18				FIGURE A6b	
Revision		A	02-Apr-18					

File Name: Dumper_LK_updated.gsz
 Name: All Sand 150mm insulation
 Date: 4/2/2018
 Directory: P:\REDLEAF\335458\SPECIALIST_APPS\02 Marry River\08 Dumper\Dumper thermal model\





Job number		353004		Mary River Expansion Project			BIM	
Ref		Tippler Load-out Tunnel		Insulation Temperature Contour In July (20 yr after construction)			Milne Inlet Port	
By	Lk	0	02-Apr-18				FIGURE A6c	
Revision		A	02-Apr-18					

File Name: Dumper_LK_updated.gsz
 Name: All Sand 150mm insulation
 Date: 4/2/2018
 Directory: P:\REDLEAF\335458\SPECIALIST_APPS\02 Marry River\08 Dumper\Dumper thermal model\





Job number		353004		Mary River Expansion Project			BIM	
Ref		Tippler Load-out Tunnel		Insulation Temperature Contour In August (20 yr after construction)			Milne Inlet Port	
By	Lk	0	02-Apr-18				FIGURE A6d	
Revision		A	02-Apr-18					

File Name: Dumper_LK_updated.gsz
 Name: All Sand 150mm insulation
 Date: 4/2/2018
 Directory: P:\REDLEAF\335458\SPECIALIST_APPS\02 Marry River\08 Dumper\Dumper thermal model\





Job number		353004		Mary River Expansion Project			BIM	
Ref		Tippler Load-out Tunnel		Insulation Temperature Contour In September (20 yr after construction)			Milne Inlet Port	
By	Lk	0	02-Apr-18				FIGURE A6e	
Revision		A	02-Apr-18					

File Name: Dumper_LK_updated.gsz
 Name: All Sand 150mm insulation
 Date: 4/2/2018
 Directory: P:\REDLEAF\335458\SPECIALIST_APPS\02 Marry River\08 Dumper\Dumper thermal model\





Job number		353004		Mary River Expansion Project			BIM	
Ref		Tippler Load-out Tunnel		Insulation Temperature Contour In October (20 yr after construction)			Milne Inlet Port	
By	Lk	0	02-Apr-18				FIGURE A6f	
Revision		A	02-Apr-18					

File Name: Dumper_LK_updated.gsz
 Name: All Sand 150mm insulation
 Date: 4/2/2018
 Directory: P:\REDLEAF\335458\SPECIALIST_APPS\02 Marry River\08 Dumper\Dumper thermal model\



Job number		353004		Mary River Expansion Project			BIM	
Ref		Tippler Load-out Tunnel		Insulation Temperature Contour In December (20 yr after construction)			Milne Inlet Port	
By	Lk	0	02-Apr-18				FIGURE A6g	
Revision		A	02-Apr-18					

File Name: Dumper_LK_updated.gsz
 Name: All Sand 150mm insulation
 Date: 4/2/2018
 Directory: P:\REDLEAF\335458\SPECIALIST_APPS\02 Marry River\08 Dumper\Dumper thermal model\




Job number		353004		Mary River Expansion Project			BIM	
Ref		Tippler Load-out Tunnel		Insulation Temperature Contour In February (20 yr after construction)			Milne Inlet Port	
By	Lk	0	02-Apr-18				FIGURE A6h	
Revision		A	02-Apr-18					

Appendix A2

Geotechnical Profile, Load-out Tunnel Configuration and Load Update


\\VALE\ENGINEERING\PROJECTS\001195 - SC - RAIL CAR DUMPER CONVEYOR TUNNEL - NO ORDER DRAFTING\2017-01195 (R1) NOT REL
BRIAN HEANEY
Thursday, August 3, 2017 9:46:46 AM

NOTE:
• BALANCED BACKFILL REQUIRED AT BOTH STRUCTURE ENDS.
• ALSO SEE NOTE 7 ON 2017-01195-S08 AND SECTION.




DOWNSLOPE END

UPSLOPE END



Green shows updated and final design length required for the unloader exit tunnel following optimization of the earthworks, therefore structure required can be shortened and extra length included in current variation is to be used for the pedestrian underpass at the mine, Tower EBC to submit a variation for this once the Engineer supplies a general layout.



Section highlighted in yellow to be used for pedestrian underpass at mine to cross under rail line, layout is being prepared to show this crossing at mine for design verification and construction requirements

SECTION - LONGITUDINAL PROFILE THRU ϵ OF STRUCTURE
SCALE: 1:300

Sketch 3

REV NO.	DATE	BY	DESCRIPTION
0	21 JUL 17	BH	ISSUED FOR APPROVAL



Atlantic Industries Limited

CALL TOLL FREE IN NORTH AMERICA 1-877-AIL-PIPE
www.aill.ca www.atlanticindustries.us

BAFFINLAND IRON MINES CORPORATION
RAIL CAR DUMPER CONVEYOR TUNNEL - BAFFIN ISLAND, NU
PLAN VIEW & LONGITUDINAL PROFILE

DESIGNED	MME	19 JUN 17	BRANCH P.O.	CUSTOMER REF.
DES. CHK	KW	21 JUN 17		
DRAWN BY	BH	19 JUN 17	PROJECT NUMBER	2017-01195
DWG. CHK	LM	21 JUN 17		DWG NO. G02
				REV. 0

THIS DRAWING IS THE PROPERTY OF ATLANTIC INDUSTRIES LIMITED (AIL) AND MAY CONTAIN PROPRIETARY INFORMATION. WRITTEN APPROVAL MUST BE GIVEN BY AIL PRIOR TO ANY INFORMATION CONTAINED HEREIN BEING USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT WAS ISSUED. THIS DRAWING SHALL BE RETURNED TO AIL UPON REQUEST. © ATLANTIC INDUSTRIES LIMITED (2016)

Appendix A3

Borehole Logs and Geophysical Survey Data



BOREHOLE REPORT

BH17-EBC-1

Sheet 1 of 4

Client: Baffinland Iron Mines Corporation**Project No.:** H353004**Project:** Mary River Expansion Project**Datum:** NAD 83**Location:** Rail Indexer Foundation**Platform:** Ground**Contractor:** Boart Longyear**Rig Type/ Mounting:** MiniSonic Rig**Date Logged:** 9/19/2017**Driller:** Brent McAndrew**Hole Diameter (mm):** 100 mm**Date Reviewed:** 1/26/2018**Easting:** 503,783.4 m**Northing:** 7,974,920.8 m**Surface Elevation:** 51.59 m**Bottom Elevation:** 29.92 m**Total Depth:** 21.7 m**Logged By:** R.S**Reviewed By:** G.Q

Water	Elevation (m)	Depth (m)	Method	Casing	Graphic Log	Soil Description TYPE; plasticity or particle characteristics (size, grading, shape, roundness), colour, structure, accessory components.	Frozen Soil Description	Recovery Sample Type	Moisture Content Profile 0 50 100							Other Tests
	50.6	1.0				SAND and GRAVEL (FILL): Brown. Material placed to create level drilling platform.	Unfrozen									
	49.6	2.0														
	48.6	3.0				SAND and GRAVEL with Silt: Brown and grey, frozen.	Nbn									
	47.6	4.0				ICE, trace Silt: Grey to white.	ICE									
	46.6	5.0				SAND, trace Silt: Brown, frozen. Ice poor soil.	Nbn									
	45.6	6.0				ICE, trace Silt: White/clear.	ICE									
	44.6	7.0														
	43.6	8.0														
	42.6	9.0														
	41.6	10.0				SAND, trace Silt: Light brown, occasional thin ice lenses. Ice poor soil.	Nbn-Vs									

Notes:



BOREHOLE REPORT

BH17-EBC-1

Sheet 2 of 4

Client: Baffinland Iron Mines Corporation

Project No.: H353004

Project: Mary River Expansion Project

Datum: NAD 83

Location: Rail Indexer Foundation

Platform: Ground

Contractor: Boart Longyear

Rig Type/ Mounting: MiniSonic Rig

Date Logged: 9/19/2017

Driller: Brent McAndrew

Hole Diameter (mm): 100 mm

Date Reviewed: 1/26/2018

Easting: 503,783.4 m

Northing: 7,974,920.8 m

Surface Elevation: 51.59 m

Bottom Elevation: 29.92 m

Total Depth: 21.7 m

Logged By: R.S

Reviewed By: G.Q

Water	Elevation (m)	Depth (m)	Method	Casing	Graphic Log	Soil Description TYPE; plasticity or particle characteristics (size, grading, shape, roundness), colour, structure, accessory components.	Frozen Soil Description	Recovery Sample Type	Moisture Content Profile 0 50 100							Other Tests
	40.6	11.0				SAND and GRAVEL some Silt: Brown. Ice poor soil.	Nbn									
	39.6	12.0														
	38.6	13.0														
	37.6	14.0				COBBLES and BEDROCK: Biege and brown, pulverized cobbles and bedrock, dry powdery, with layers of brown silty sand and gravel, moist. Top of poor quality bedrock, 14.04 m.										
	36.6	15.0				Start of Coring at 14.0m. Continued on Rock Core Log sheet.										
	35.6	16.0														
	34.6	17.0														
	33.6	18.0														
	32.6	19.0														
	31.6	20.0														

Notes:



BOREHOLE LOG

ROCK CORE FORMAT

BH17-EBC-1

Sheet 3 of 4

Client: Baffinland Iron Mines Corporation

Project No.: H353004

Project: Mary River Expansion Project

Datum: NAD 83

Location: Rail Indexer Foundation

Platform: Ground

Contractor: Boart Longyear **Rig Type/ Mounting:** MiniSonic Rig **Bearing:** N/A **Date Logged:** 9/19/2017

Driller: Brent McAndrew **Hole Diameter (mm):** 100 mm **Plunge:** Vertical **Date Checked:** 1/26/2018

Easting: 503,783.4 m

Northing: 7,974,920.8 m

Surface Elevation: 51.59 m

Bottom Elevation: 29.92 m

Total Depth: 21.7 m

Logged By: R.S

Reviewed By: G.Q

Water	Elevation (m)	Depth (m)	Method	Run #/TCR	Graphic Log	Geological Unit	Rock Description	Weathering/ Cementation	Estimated Strength	Is ₍₅₀₎ [UCS] MPa	Defect Spacing					RQD %	Defect Log	Defect Description	
											mm	[100]	60	20	Inclination, type, infill, amount, aperture, planarity, roughness, frequency			Specific	General
	40.6	11.0																	
	39.6	12.0																	
	38.6	13.0																	
	37.6	14.0					Resuming in Rock Core Format 14.0m.												
	36.6	15.0		3 / 96	2 / 100		BEDROCK: Granitic Gneiss, medium to coarse grained, hard to very hard, pinkish-grey colour. Fractures are generally vertical, between 0 to 15 degrees and horizontal, from 70 to 90 degrees.												
	35.6	16.0		4 / 88			Numerous joints and fractures infilled with clayey-silt and fine sand throughout.												
	34.6	17.0		5 / 106															
	33.6	18.0		6 / 99															
	32.6	19.0																	
	31.6	20.0																	

Resuming in Rock Core Format 14.0m.

BEDROCK: Granitic Gneiss, medium to coarse grained, hard to very hard, pinkish-grey colour. Fractures are generally vertical, between 0 to 15 degrees and horizontal, from 70 to 90 degrees.

Numerous joints and fractures infilled with clayey-silt and fine sand throughout.

Dia

75.5

Dia

182.5

Dia

151.7

[184]

Dia

119.6

Cz
70° Jt Pl Sm Silt sn
Cz
80° Jt Pl Sm sn
Cz
10° DI Ir Ro
75° Jt Pl Sm 1 -2 mm clay sn
0° DI Ir Ro
10° DI Ir Ro
Cz
60° Jt Pl Sm 1 -2 mm clay sn
Fz
20° Jt Pl Sm 1 mm clay sn
40° Jt Pl Sm 1 mm clay sn
10° DI Ir Ro
0° DI Ir Ro
70° Jt Pl Sm 1 -2 mm clay sn
60° Jt Pl Sm 1 mm clay cn
90° DI Ir Ro
0° DI Ir Ro
0° DI Ir Ro
0° DI Ir Ro
0° DI Ir Ro
60° Jt Pl Sm 1 mm clay sn
10° Jt Pl Sm sn
Jt
10° Jt Pl Sm 5mm Clay sn
10° Jt Pl Sm Silt sn
10° Jt Pl Sm Silt sn

Notes:

Defect Description Legend

Planarity

PI Planar
Ir Irregular
Cu Curved
Un Undulose
St Stepped

Type

DI Drilling Induced
Jt Joint
Pt Parting on Contact
Sh Shear Seam
Cs Crushed Seam

Sm Seam
Cz Crushed Zone
Fz Fractured Zone
Band Weak Band

Roughness

Ro Rough
Sm Smooth
Po Polished
Sl Slickenside

Infill Amount

cn Clean
sn Stained
vn Veneer
cg Coating



BOREHOLE LOG

ROCK CORE FORMAT

BH17-EBC-1

Sheet 4 of 4

Client: Baffinland Iron Mines Corporation

Project No.: H353004

Project: Mary River Expansion Project

Datum: NAD 83

Location: Rail Indexer Foundation

Platform: Ground

Contractor: Boart Longyear **Rig Type/ Mounting:** MiniSonic Rig **Bearing:** N/A **Date Logged:** 9/19/2017

Driller: Brent McAndrew **Hole Diameter (mm):** 100 mm **Plunge:** Vertical **Date Checked:** 1/26/2018

Easting: 503,783.4 m

Northing: 7,974,920.8 m

Surface Elevation: 51.59 m

Bottom Elevation: 29.92 m

Total Depth: 21.7 m

Logged By: R.S

Reviewed By: G.Q

Water	Elevation (m)	Depth (m)	Method	Run #/TCR	Graphic Log	Geological Unit	Rock Description ROCK TYPE; Grain size, texture and fabric, colour, general defect conditions, minor constituents.	Weathering/ Cementation	Estimated Strength							Is ₍₅₀₎ [UCS] MPa	Defect Spacing mm				RQD %	Defect Log	Defect Description		
									EH	VH	H	M	L	VL	EL		2000	600	200	100			Inclination, type, infill, amount, aperture, planarity, roughness, frequency	Specific	General
	30.6	21.0		7 / 100			BEDROCK: Granitic Gneiss, medium to coarse grained, hard to very hard, pinkish-grey colour. Fractures are generally vertical, between 0 to 15 degrees and horizontal, from 70 to 90 degrees. (Continued)																85° Jt Pl Sm Silt sn 85° Jt Pl Sm Silt sn 85° Jt Pl Sm Silt sn 85° Jt Pl Sm Silt sn 85° Jt Pl Sm 1 mm clay sn 85° Jt Pl Sm Silt sn 85° Jt Pl Sm Silt sn 85° Jt Pl Sm Silt sn 85° Jt Pl Sm Silt sn 85° Jt Pl Sm Silt sn 85° Jt Pl Sm Silt sn 10° Cz Ir Ro Silt		
	29.6	22.0					To Target Depth. Drillhole BH17-EBC-1 terminated at 21.7m.																10° DI Ir Ro Silt 10° DI Ir Ro Silt 10° DI Ir Ro Silt 10° DI Ir Ro Silt		
	28.6	23.0																							
	27.6	24.0																							
	26.6	25.0																							
	25.6	26.0																							
	24.6	27.0																							
	23.6	28.0																							
	22.6	29.0																							
	21.6	30.0																							

Notes:

Planarity		Type		Roughness		Infill Amount	
Defect	PI Planar	DI Drilling Induced	Sm Seam	Ro Rough	cn Clean		
Description	Ir Irregular	Jt Joint	Cz Crushed Zone	Sm Smooth	sn Stained		
Legend	Cu Curved	Pt Parting on Contact	Fz Fractured Zone	Pol Polished	vn Veneer		
	Un Undulose	Sh Shear Seam	Band Weak Band	Sl Slickenside	cg Coating		
	St Stepped	Cs Crushed Seam					



BOREHOLE REPORT

BH17-EBC-2

Sheet 1 of 4

Client: Baffinland Iron Mines Corporation**Project No.:** H353004**Project:** Mary River Expansion Project**Datum:** NAD 83**Location:** Rail Indexer Foundation**Platform:** Ground**Contractor:** Boart Longyear**Rig Type/ Mounting:** MiniSonic Rig**Date Logged:** 9/24/2017**Driller:** Brent McAndrew**Hole Diameter (mm):** 100 mm**Date Reviewed:** 1/26/2018**Easting:** 503,790.9 m**Northing:** 7,974,895.2 m**Surface Elevation:** 54.05 m**Bottom Elevation:** 32.21 m**Total Depth:** 21.8 m**Logged By:** R.S**Reviewed By:** G.Q

Water	Elevation (m)	Depth (m)	Method	Casing	Graphic Log	Soil Description TYPE; plasticity or particle characteristics (size, grading, shape, roundness), colour, structure, accessory components.	Frozen Soil Description	Recovery Sample Type	Moisture Content Profile 0 50 100							Other Tests
	53.1	1.0				SAND and GRAVEL trace Cobbles: Brown, well graded up to 75 mm. Cobbles recovered are partially pulverized to dry, beige rock flour. Ice poor soil.	Unfrozen									
	52.1	2.0				SAND trace Silt: Brown, well graded. Ice poor soil.	Nbn									
	51.1	3.0				SAND trace Silt: Brown, well graded. Ice poor soil.	Nbn									
	50.1	4.0				SAND and GRAVEL trace Silt: Brown, wet, well graded. Ice poor soil.	Nbn Nbn									
	49.1	5.0				GRAVEL with SAND, trace Silt. Brown, well graded. Ice poor soil.										
	48.1	6.0														
	47.1	7.0														
	46.1	8.0														
	45.1	9.0				GRAVEL and SAND with SAND, some Silt: Brown and grey. Recovery by HQ core barrel. Silt and sand content is estimated from wash water recovery.										
	44.1	10.0														

Notes:



BOREHOLE REPORT

BH17-EBC-2

Sheet 2 of 4

Client: Baffinland Iron Mines Corporation**Project No.:** H353004**Project:** Mary River Expansion Project**Datum:** NAD 83**Location:** Rail Indexer Foundation**Platform:** Ground**Contractor:** Boart Longyear**Rig Type/ Mounting:** MiniSonic Rig**Date Logged:** 9/24/2017**Driller:** Brent McAndrew**Hole Diameter (mm):** 100 mm**Date Reviewed:** 1/26/2018**Easting:** 503,790.9 m**Northing:** 7,974,895.2 m**Surface Elevation:** 54.05 m**Bottom Elevation:** 32.21 m**Total Depth:** 21.8 m**Logged By:** R.S**Reviewed By:** G.Q

Water	Elevation (m)	Depth (m)	Method	Casing	Graphic Log	Soil Description TYPE; plasticity or particle characteristics (size, grading, shape, roundness), colour, structure, accessory components.	Frozen Soil Description	Recovery	Sample Type	Moisture Content Profile 0 50 100							Other Tests
	43.1	11.0				GRAVEL and SAND with SAND, some Silt: Brown and grey. Recovery by HQ core barrel. Silt and sand content is estimated from wash water recovery. (Continued)											
	42.1	12.0															
	41.1	13.0															
	40.1	14.0				Start of Coring at 13.3m. Continued on Rock Core Log sheet.											
	39.1	15.0															
	38.1	16.0															
	37.1	17.0															
	36.1	18.0															
	35.1	19.0															
	34.1	20.0															

Notes:



BOREHOLE LOG

ROCK CORE FORMAT

BH17-EBC-2

Sheet 3 of 4

Client: Baffinland Iron Mines Corporation

Project No.: H353004

Project: Mary River Expansion Project

Datum: NAD 83

Location: Rail Indexer Foundation

Platform: Ground

Contractor: Boart Longyear **Rig Type/ Mounting:** MiniSonic Rig **Bearing:** N/A **Date Logged:** 9/24/2017

Driller: Brent McAndrew **Hole Diameter (mm):** 100 mm **Plunge:** Vertical **Date Checked:** 1/26/2018

Easting: 503,790.9 m

Northing: 7,974,895.2 m



Surface Elevation: 54.05 m

Bottom Elevation: 32.21 m

Total Depth: 21.8 m

Logged By: R.S

Reviewed By: G.Q

Water	Elevation (m)	Depth (m)	Method	Run #/TCR	Graphic Log	Geological Unit	Rock Description	Weathering/ Cementation	Estimated Strength	Is ₅₀ [UCS] MPa	Defect Spacing mm	RQD %	Defect Log	Defect Description	
							ROCK TYPE; Grain size, texture and fabric, colour, general defect conditions, minor constituents.							Inclination, type, infill, amount, aperture, planarity, roughness, frequency	Specific
	43.1	11.0													
	42.1	12.0													
	41.1	13.0													
							Resuming in Rock Core Format 13.3m.								
	40.1	14.0		9 / 107			BEDROCK: Granitic Gneiss, medium to coarse grained, hard to very hard, pinkish-grey colour. Fractures are generally vertical, between 0 to 15 degrees and horizontal, from 70 to 90 degrees. Numerous joints and fractures infilled with clayey-silt and fine sand throughout.								
	39.1	15.0		10 / 103											
	38.1	16.0		11 / 130											
	37.1	17.0		12 / 105											
	36.1	18.0		13 / 97						[161.5] 					
	35.1	19.0													
	34.1	20.0													

Notes:

Planarity		Type		Roughness		Infill Amount	
Defect	PI Planar	DI	Drilling Induced	Sm	Seam	cn	Clean
Description	Ir Irregular	Jt	Joint	Cz	Crushed Zone	sn	Stained
Legend	Cu Curved	Pt	Parting on Contact	Fz	Fractured Zone	vn	Veneer
	Un Undulose	Sh	Shear Seam	Band	Weak Band	cg	Coating
	St Stepped	Cs	Crushed Seam				



BOREHOLE LOG

ROCK CORE FORMAT

BH17-EBC-2

Sheet 4 of 4

Client: Baffinland Iron Mines Corporation

Project No.: H353004

Project: Mary River Expansion Project

Datum: NAD 83

Location: Rail Indexer Foundation

Platform: Ground

Contractor: Boart Longyear **Rig Type/ Mounting:** MiniSonic Rig **Bearing:** N/A **Date Logged:** 9/24/2017

Driller: Brent McAndrew **Hole Diameter (mm):** 100 mm **Plunge:** Vertical **Date Checked:** 1/26/2018

Easting: 503,790.9 m

Northing: 7,974,895.2 m


Surface Elevation: 54.05 m

Bottom Elevation: 32.21 m

Total Depth: 21.8 m

Logged By: R.S

Reviewed By: G.Q

Water	Elevation (m)	Depth (m)	Method	Run #/TCR	Graphic Log	Geological Unit	Rock Description	Weathering/ Cementation	Estimated Strength						Is ₍₅₀₎ [UCS] MPa	Defect Spacing mm				RQD %	Defect Log	Defect Description		
							ROCK TYPE; Grain size, texture and fabric, colour, general defect conditions, minor constituents.						EH	VH		H	M	L	VL			EL	2000	600
	33.1	21.0		14 / 100			BEDROCK: Granitic Gneiss, medium to coarse grained, hard to very hard, pinkish-grey colour. Fractures are generally vertical, between 0 to 15 degrees and horizontal, from 70 to 90 degrees. (Continued)														42		85° Jt Pl Sm Silt sn 20° Jt Pl Sm Silt sn 15° Jt Pl Sm Silt sn 30° Jt Pl Sm Silt sn 0° DI Ir Ro 85° Jt Pl Sm Silt sn 0° DI Ir Ro 20° Jt Pl Sm Silt sn 15° Jt Pl Sm Silt sn 25° DI Ir Ro 10° Jt Pl Sm Silt sn Cz 5° Jt Pl Sl vn Cz 0° DI Ir Ro	
	32.1	22.0					To Target Depth. Drillhole BH17-EBC-2 terminated at 21.8m.																0° DI Ir Ro 0° DI Ir Ro 0° DI Ir Ro 0° Jt Pl Ro Silt sn 0° Jt Pl Ro Silt sn 0° Jt Pl Ro Silt sn 0° Jt Pl Ro Silt sn 0° Jt Pl Ro Silt sn 0° DI Ir Ro	
	31.1	23.0																						
	30.1	24.0																						
	29.1	25.0																						
	28.1	26.0																						
	27.1	27.0																						
	26.1	28.0																						
	25.1	29.0																						
	24.1	30.0																						

Notes:

Planarity		Type		Roughness		Infill Amount	
Defect	PI Planar	DI	Drilling Induced	Sm	Seam	cn	Clean
Description	Ir Irregular	Jt	Joint	Cz	Crushed Zone	sn	Stained
Legend	Cu Curved	Pt	Parting on Contact	Fz	Fractured Zone	vn	Veneer
	Un Undulose	Sh	Shear Seam	Band	Weak Band	cg	Coating
	St Stepped	Cs	Crushed Seam				



BOREHOLE REPORT

BH17-M008-R

Sheet 1 of 4

Client: Baffinland Iron Mines Corporation**Project No.:** H353004**Project:** Mary River Expansion Project**Datum:** NAD 83**Location:** Rail Indexer Foundation**Platform:** Ground**Contractor:** Boart Longyear**Rig Type/ Mounting:** MiniSonic Rig**Date Logged:** 9/17/2017**Driller:** Brent McAndrew**Hole Diameter (mm):** 100 mm**Date Reviewed:** 1/26/2018**Easting:** 503,772.0 m**Northing:** 7,974,960.0 m**Surface Elevation:** 52.00 m**Bottom Elevation:** 30.01 m**Total Depth:** 22.0 m**Logged By:** R.S**Reviewed By:** G.Q

Water	Elevation (m)	Depth (m)	Method	Casing	Graphic Log	Soil Description TYPE; plasticity or particle characteristics (size, grading, shape, roundness), colour, structure, accessory components.	Frozen Soil Description	Recovery	Sample Type	Moisture Content Profile 0 50 100							Other Tests
	51.0	1.0				NO SAMPLES TAKEN IN OVERBURDEN. Advanced sonic tube to refusal and began diamond coring bedrock.											
	50.0	2.0															
	49.0	3.0															
	48.0	4.0															
	47.0	5.0															
	46.0	6.0															
	45.0	7.0															
	44.0	8.0															
	43.0	9.0															
	42.0	10.0															

Notes: Redrill of BH16-M008. Elevation is approximate.



BOREHOLE REPORT

BH17-M008-R

Sheet 2 of 4

Client: Baffinland Iron Mines Corporation

Project No.: H353004

Project: Mary River Expansion Project

Datum: NAD 83

Location: Rail Indexer Foundation

Platform: Ground

Contractor: Boart Longyear

Rig Type/ Mounting: MiniSonic Rig

Date Logged: 9/17/2017

Driller: Brent McAndrew

Hole Diameter (mm): 100 mm

Date Reviewed: 1/26/2018

Easting: 503,772.0 m

Northing: 7,974,960.0 m

Surface Elevation: 52.00 m

Bottom Elevation: 30.01 m

Total Depth: 22.0 m

Logged By: R.S

Reviewed By: G.Q

Water	Elevation (m)	Depth (m)	Method	Casing	Graphic Log	Soil Description TYPE; plasticity or particle characteristics (size, grading, shape, roundness), colour, structure, accessory components.	Frozen Soil Description	Recovery	Sample Type	Moisture Content Profile 0 50 100							Other Tests
	41.0	11.0				NO SAMPLES TAKEN IN OVERBURDEN. Advanced sonic tube to refusal and began diamond coring bedrock. (Continued)											
	40.0	12.0															
	39.0	13.0															
	38.0	14.0															
	37.0	15.0															
	36.0	16.0															
	35.0	17.0															
	34.0	18.0				Start of Coring at 17.4m. Continued on Rock Core Log sheet.											
	33.0	19.0															
	32.0	20.0															

Notes: Redrill of BH16-M008. Elevation is approximate.



BOREHOLE LOG

ROCK CORE FORMAT

BH17-M008-R

Sheet 3 of 4

Client: Baffinland Iron Mines Corporation

Project No.: H353004

Project: Mary River Expansion Project

Datum: NAD 83

Location: Rail Indexer Foundation

Platform: Ground

Contractor: Boart Longyear **Rig Type/ Mounting:** MiniSonic Rig **Bearing:** N/A **Date Logged:** 9/17/2017

Driller: Brent McAndrew **Hole Diameter (mm):** 100 mm **Plunge:** Vertical **Date Checked:** 1/26/2018

Easting: 503,772.0 m

Northing: 7,974,960.0 m

Surface Elevation: 52.00 m

Bottom Elevation: 30.01 m

Total Depth: 22.0 m

Logged By: R.S

Reviewed By: G.Q

Water	Elevation (m)	Depth (m)	Method	Run #/TCR	Graphic Log	Geological Unit	Rock Description ROCK TYPE; Grain size, texture and fabric, colour, general defect conditions, minor constituents.	Weathering/ Cementation	Estimated Strength						Is ₍₅₀₎ [UCS] MPa	Defect Spacing mm				RQD %	Defect Log	Defect Description			
									EH	VH	H	M	L	VL		EL	2000	600	200			100	60	20	Inclination, type, infill, amount, aperture, planarity, roughness, frequency
	41.0	11.0																							
	40.0	12.0																							
	39.0	13.0																							
	38.0	14.0																							
	37.0	15.0																							
	36.0	16.0																							
	35.0	17.0																							
	34.0	18.0		1 / 101			Resuming in Rock Core Format 17.4m.																		
	33.0	19.0		2 / 98			BEDROCK: Granitic Gneiss, medium to coarse grained, hard to very hard, pinkish-grey colour. Fractures are generally vertical, between 0 to 15 degrees and horizontal, from 70 to 90 degrees. Numerous joints and fractures infilled with clayey-silt and fine sand throughout.																		
	32.0	20.0																							

Notes: Redrill of BH16-M008. Elevation is approximate.

Planarity		Type		Roughness		Infill Amount	
Defect Description Legend	PI Planar Ir Irregular Cu Curved Un Undulose St Stepped	DI Drilling Induced Jt Joint Pt Parting on Contact Sh Shear Seam Cs Crushed Seam	Sm Seam Cz Crushed Zone Fz Fractured Zone Band Weak Band	Ro Rough Sm Smooth Po Polished Sl Slickenside	cn Clean sn Stained vn Veneer cg Coating		



BOREHOLE LOG

ROCK CORE FORMAT

BH17-M008-R

Sheet 4 of 4

Client: Baffinland Iron Mines Corporation

Project No.: H353004

Project: Mary River Expansion Project

Datum: NAD 83

Location: Rail Indexer Foundation

Platform: Ground

Contractor: Boart Longyear **Rig Type/ Mounting:** MiniSonic Rig **Bearing:** N/A **Date Logged:** 9/17/2017

Driller: Brent McAndrew **Hole Diameter (mm):** 100 mm **Plunge:** Vertical **Date Checked:** 1/26/2018

Easting: 503,772.0 m

Northing: 7,974,960.0 m

Surface Elevation: 52.00 m

Bottom Elevation: 30.01 m

Total Depth: 22.0 m

Logged By: R.S

Reviewed By: G.Q

Water	Elevation (m)	Depth (m)	Method	Run #/TCR	Graphic Log	Geological Unit	Rock Description	Weathering/ Cementation	Estimated Strength	Is ₍₅₀₎ [UCS] MPa	Defect Spacing	RQD %	Defect Log	Defect Description
							ROCK TYPE; Grain size, texture and fabric, colour, general defect conditions, minor constituents.				mm			Inclination, type, infill, amount, aperture, planarity, roughness, frequency

Notes: Redrill of BH16-M008. Elevation is approximate.

Planarity		Type		Roughness		Infill Amount	
Defect Description Legend	PI Planar Ir Irregular Cu Curved Un Undulose St Stepped	DI Drilling Induced Jt Joint Pt Parting on Contact Sh Shear Seam Cs Crushed Seam	Sm Seam Cz Crushed Zone Fz Fractured Zone Band Weak Band	Ro Rough Sm Smooth Po Polished Sl Slickenside	cn Clean sn Stained vn Veneer cg Coating		



Sheet 1 of 3

Platform: Ground

Date Reviewed:2/10/2017

Reviewed By: SH/WH

BAFFINLAND GINT LIBRARY.GLB Log SOIL BOREHOLE RAIL ALIGNMENT ALL WITH ICE LOG REV 3.GPJ <<DrawingFile>> 02/10/2017 17:43

Notes:



BOREHOLE REPORT

BH16-M009

Sheet 1 of 2

Client: Baffinland Iron Mines**Project No.:** H352034**Project:** Mary River Expansion Study Stage 2**Datum:** NAD83**Location:** Milne Port Train Unloading**Platform:** Ground**Contractor:** Boart Longyear**Rig Type/ Mounting:** MiniSonic Rig**Date Logged:** 10/4/2016**Driller:** Samuel Flynn**Hole Diameter (mm):** 96**Date Reviewed:** 2/10/2017**Easting:** 503,904.0 m**Northing:** 7,974,935.0 m**Surface Elevation:** 57.50 m**Bottom Elevation:** 52.32 m**Total Depth:** 5.2 m**Logged By:** MR**Reviewed By:** SH/WH

Water	Elevation (m)	Depth (m)	Method	Casing	Graphic Log	Soil Description TYPE; plasticity or particle characteristics (size, grading, shape, roundness), colour, structure, accessory components.	Moisture Condition	Consistency/ Density	Sample Type	Recovery %	Blows	Field Water Content	Percent Gravel	Percent Sand	Percent Fines	Liquid Limit	Plastic Index	Other Tests
Unobserved due to Permafrost			Vibracore	H-Casing		ORGANICS: Organic soil GRAVELLY SAND: Light brown to grey, angular to subgranular gravel, medium to coarse grained sand SAND and GRAVEL: Grey to light brown, Fine to coarse grained sand, angular to subangular gravel Inferred BOULDERS with SAND: Coarse to fine grained sand Start of Coring at 3.7m. Continued on Rock Core Log sheet.												

Notes:



Sheet 1 of 1

Platform: Ground

Date Reviewed:2/10/2017

Reviewed By: SH/WH

BAFFINLAND GINT LIBRARY.GLB Log SOIL BOREHOLE RAIL ALIGNMENT ALL WITH ICE LOG REV 3.GPJ <DrawingFile>> 02/10/2017 17:43

Notes:



BOREHOLE REPORT

BH16-M011

Sheet 1 of 1

Client: Baffinland Iron Mines**Project No.:** H352034**Project:** Mary River Expansion Study Stage 2**Datum:** NAD83**Location:** Milne Port Crusher**Platform:** Ground**Contractor:** Boart Longyear**Rig Type/ Mounting:** MiniSonic Rig**Date Logged:** 12/4/2016**Driller:** Michael Scott**Hole Diameter (mm):** 96**Date Reviewed:** 2/10/2017**Easting:** 503,339.0 m**Northing:** 7,974,868.0 m**Surface Elevation:** 12.00 m**Bottom Elevation:** -3.20 m**Total Depth:** 15.2 m**Logged By:** MR**Reviewed By:** SH/WH

Water	Elevation (m)	Depth (m)	Method	Casing	Graphic Log	Soil Description TYPE; plasticity or particle characteristics (size, grading, shape, roundness), colour, structure, accessory components.	Moisture Condition	Consistency/ Density	Sample Type	Recovery %	Blows	Moisture Content Profile	Field Water Content	Percent Gravel	Percent Sand	Percent Fines	Liquid Limit	Plastic Index	Other Tests
	10.0	2.0				SILTY SAND: Light brown, moist							16	0	68	32			
	8.0	4.0				SAND and GRAVEL: Light brown, moist, subangular gravel							10						
	6.0	6.0				SILT, trace SAND: Dark grey, moist													
	4.0	8.0	Vibrocoring	H-Casing															
	2.0	10.0																	
	0.0	12.0																	
	-2.0	14.0																	
	-4.0	16.0				To Target Depth. Drillhole BH16-M011 terminated at 15.2m.													
	-6.0	18.0																	
	-8.0	20.0																	

Notes:



BOREHOLE REPORT

BH16-M012

Sheet 1 of 1

Client: Baffinland Iron Mines**Project No.:** H352034**Project:** Mary River Expansion Study Stage 2**Datum:** NAD83**Location:** Milne Port Generator**Platform:** Ground**Contractor:** Boart Longyear**Rig Type/ Mounting:** MiniSonic Rig**Date Logged:** 12/8/2016**Driller:** Michael Scott**Hole Diameter (mm):** 96**Date Reviewed:** 2/10/2017**Easting:** 503,268.0 m**Northing:** 7,974,848.0 m**Surface Elevation:** 12.00 m**Bottom Elevation:** -3.20 m**Total Depth:** 15.2 m**Logged By:** MR**Reviewed By:** SH/WH

Water	Elevation (m)	Depth (m)	Method	Casing	Graphic Log	Soil Description TYPE; plasticity or particle characteristics (size, grading, shape, roundness), colour, structure, accessory components.	Moisture Condition	Consistency/ Density	Sample Type	Recovery %	Blows	Moisture Content Profile	Field Water Content	Percent Gravel	Percent Sand	Percent Fines	Liquid Limit	Plastic Index	Other Tests
						SAND and GRAVEL, some SILT, trace COBBLES: Light brown, rounded							6	39	45	17			
	10.0	2.0				SILT, some SAND: Dark grey							21	0	16	84			
	8.0	4.0																	
	6.0	6.0																	
	4.0	8.0	Vibrocure	H-Casing															
	2.0	10.0																	
	0.0	12.0																	
	-2.0	14.0																	
	-4.0	16.0				To Target Depth. Drillhole BH16-M012 terminated at 15.2m.													
	-6.0	18.0																	
	-8.0	20.0																	

Notes:

BOREHOLE REPORT

BH16-M013

Sheet 1 of 1

Client: Baffinland Iron Mines

Project No.: H352034

Project: Mary River Expansion Study Stage 2

Datum: NAD83

Location: Milne Port Screening

Platform: Ground

Contractor: Boart Longyear

Rig Type/ Mounting: MiniSonic Rig

Date Logged: 12/5/2016

Driller: Michael Scott

Hole Diameter (mm): 96

Date Reviewed:2/10/2017

Easting: 503,140.0 m

Northing: 7,974,820.0 m

Surface Elevation: 11.00 m

Bottom Elevation: -4.20 m

Total Depth: 15.2 m

Logged By: MR

Reviewed By: SH/WH

[illegible]

Notes:



BOREHOLE REPORT

BH16-M014

Sheet 1 of 1

Client: Baffinland Iron Mines**Project No.:** H352034**Project:** Mary River Expansion Study Stage 2**Datum:** NAD83**Location:** Milne Port Tail Pulley**Platform:** Ground**Contractor:** Boart Longyear**Rig Type/ Mounting:** MiniSonic Rig**Date Logged:** 12/5/2016**Driller:** Michael Scott**Hole Diameter (mm):** 96**Date Reviewed:** 2/10/2017**Easting:** 503,052.0 m**Northing:** 7,974,782.0 m**Surface Elevation:** 11.00 m**Bottom Elevation:** -4.20 m**Total Depth:** 15.2 m**Logged By:** MR**Reviewed By:** SH/WH

Water	Elevation (m)	Depth (m)	Method	Casing	Graphic Log	Soil Description TYPE; plasticity or particle characteristics (size, grading, shape, roundness), colour, structure, accessory components.	Moisture Condition	Consistency/ Density	Sample Type	Recovery %	Blows	Moisture Content Profile	Field Water Content	Percent Gravel	Percent Sand	Percent Fines	Liquid Limit	Plastic Index	Other Tests
	9.0	2.0				GRAVELLY SILTY SAND: Grey to brown, angular to subangular gravel							6	22	52	26			
	7.0	4.0				SILTY SAND: Grey							21	0	78	22			
	5.0	6.0																	
	3.0	8.0	Vibrocure	H-Casing		SILT, some SAND: Dark grey, fine grained sand													
	1.0	10.0																	
	-1.0	12.0																	
	-3.0	14.0																	
	-5.0	16.0				To Target Depth. Drillhole BH16-M014 terminated at 15.2m.													
	-7.0	18.0																	
	-9.0	20.0																	

Notes:



BOREHOLE REPORT





BH16-M015

Sheet 1 of 1

Client: Baffinland Iron Mines**Project No.:** H352034**Project:** Mary River Expansion Study Stage 2**Datum:** NAD83**Location:** Milne Port Tail Pulley Alt.**Platform:** Ground**Contractor:** Boart Longyear**Rig Type/ Mounting:** MiniSonic Rig**Date Logged:****Driller:** Michael Scott**Hole Diameter (mm):** 96**Date Reviewed:** 2/10/2017**Eastings:** 503,007.0 m**Northing:** 7,974,799.0 m**Surface Elevation:** 11.00 m**Bottom Elevation:** -4.20 m**Total Depth:** 15.2 m**Logged By:** MR**Reviewed By:** SH/WH

Water	Elevation (m)	Depth (m)	Method	Casing	Graphic Log	Soil Description TYPE; plasticity or particle characteristics (size, grading, shape, roundness), colour, structure, accessory components.	Moisture Condition	Consistency/ Density	Sample Type	Recovery %	Blows	Moisture Content Profile	Field Water Content	Percent Gravel	Percent Sand	Percent Fines	Liquid Limit	Plastic Index	Other Tests
	9.0	2.0				SAND and GRAVEL, trace SILT, trace COBBLES: Light brown to grey, fine to coarse grained sand, rounded gravel							1	32	59	10			
	7.0	4.0				SAND, trace SILT: Light brown, fine to coarse grained sand,							14	15	71	14			
	5.0	6.0				SILT, some SAND: Dark grey to brown													
	3.0	8.0	Vibrocoring	H-Casing															
	1.0	10.0																	
	-1.0	12.0											24						
	-3.0	14.0																	
	-5.0	16.0				To Target Depth. Drillhole BH16-M015 terminated at 15.2m.							27						
	-7.0	18.0																	
	-9.0	20.0																	

Notes:



NOT VALID FOR CONSTRUCTION

1	THE SEISMIC SURVEY WAS EXECUTED BY GEOPHYSICS GPR INTERNATIONAL INC. APRIL 2017	SCEAU PROFESSIONNEL DRAFT PROFESSIONAL SEAL	 GEOPHYSICS GPR INTERNATIONAL INC.	CLIENT	CLIENT
2	COORDINATE SYSTEM: WGS84 UTM ZONE 17W. POSITIONING ACCURACY +/- 2 METRES			HATCH	
3	ELEVATION DATA PROVIDED BY THE CLIENT. DEPTHS ARE RELATIVE TO GROUND SURFACE			PROJET	PROJECT
4	REFER TO FULL REPORT FOR DISCUSSION OF METHODOLOGIES, RESULTS AND LIMITATIONS			BAFFINLAND EXPANSION	
5	BOREHOLE DATA PROVIDED BY THE CLIENT FOR REFERENCE PURPOSES			TITRE	TITLE
6				SEISMIC SURVEY RAILWAY UNLOADING AREA	
No	NOTES				

DESSINÉ PAR DRAWN BY	I.Gusakov, GIT	
VERIFIÉ PAR CHECKED BY		
APPROUVÉ PAR APPROVED BY	M.Situm, P. Geo	
# CONTRAT CONTRACT #	T17001	
ÉCHELLE SCALE	AS SHOWN	# DESSIN DRAWING # T17001-A3-1

Appendix B

Indexer Slab Drawings

1. THIS DRAWING MUST BE READ IN CONJUNCTION WITH THE LATEST REFERENCE DRAWINGS FOR SETTING OUT.
2. ALL DIMENSIONS ARE GIVEN IN MILLIMETRES UNLESS NOTED OTHERWISE.
3. ANY DISCREPANCIES IN DIMENSIONS OR ON THE DRAWING TO BE BROUGHT TO THE ENGINEER'S NOTICE.

4. DESIGN SPECIFICATION: CAN/CSA S6 - 06 INCLUDING SUPPLEMENTS 1, 2 AND 3, UNLESS NOTED OTHERWISE.

5. EARTH PRESSURE: THE FOLLOWING LIMITING ASSUMPTIONS WERE USED FOR THE DESIGN AND THESE DRAWINGS SHALL NOT BE USED WITHOUT APPROPRIATE MODIFICATIONS WHEN ACTUAL SITE CONDITIONS RESULT IN MORE SEVERE LOAD EFFECTS OR LESS EFFECTIVE RESISTANCE.

- UNIT WEIGHT OF SOIL, $\gamma = 20 \text{ kN/m}^3$
- GRANULAR FILL FRICTION ANGLE, $\phi = 40^\circ$
- CO-EFFICIENT OF PASSIVE PRESSURE, $K_p = 4.6$
- ASSUMED ALLOWABLE BEARING PRESSURE $= 200 \text{ kPa}$

6. SUBSOIL DRAINAGE TO CIVIL DETAIL, TO BE PROVIDED

- INSTALL STEEL COLUMNS OFF RAIL, BASEMENT PRECAST BEAMS,
- BACKFILL TO UNDERSIDE OF ANCHOR BEAM LEVEL.
- PLACE ANCHOR BEAM IN POSITION ON SPECIFIED LAYERWORKS.
- CONTINUE BACKFILLING TO UNDERSIDE OF APPROACH SLAB
- PLACE APPROACH SLAB IN POSITION ON SPECIFIED LAYERWORKS. THE PIN CONNECTION POCKETS IN THE APPROACH
- SLAB ARE TO ALIGN WITH THE STEEL COLUMN PINS.
- GROUT APPROACH SLAB POCKETS.
- CONTINUE BACKFILLING TO UNDERSIDE OF INDEXER FOUNDATION.
- PLACE INDEXER FOUNDATION PRECAST PANELS ON SPECIFIED LAYERWORKS.
- ALIGN AND INSTALL DWYDAG BARS AND DEAD MAN ANCHORS.
- GROUT TRANSVERSE SHEAR KEYS.
- DWYDAG BARS TO BE STRESSED TO NOMINAL 20% LOAD IN SPECIFIED SEQUENCE.
- DWYDAG BARS TO BE STRESSED ONLY AFTER MIN. 28 DAY SHEAR KEY GROUT STRENGTH HAS BEEN REACHED.
- INSTALL TRAIN RAILS AND GROUT TRAIN RAILS STUD POCKETS.

- AFTER THE UNDERSIDE OF THE ANCHOR BEAM LEVEL IS REACHED, BACKFILL MUST BE PLACED EVENLY ACROSS THE PLAN EXTENTS OF THE INDEXER FOUNDATION, AND THE BACKFILL SURFACE ELEVATIONS SHALL NOT DIFFER BY MORE THAN 300MM ACROSS THE PLAN EXTENTS OF THE INDEXER FOUNDATION, AT ANY STAGE OF THE OPERATION.
- BACKFILL SHALL BE PLACED IN SUCH A MANNER AS TO AVOID ANY DAMAGE OR MIS-ALIGNMENT OF THE PRECAST CONCRETE PANELS. BACKFILL COMPACTION SHALL BE PERFORMED SUCH THAT EQUIPMENT MOVES PARALLEL TO THE PRECAST PANELS FINAL POSITION.
- ONLY HAND OPERATED POWER TAMPERS AND VIBRATORS SHALL BE USED FOR COMPACTION WITHIN 1000mm OF ANY STRUCTURAL ELEMENT.
- STRUCTURAL STEELWORK
 - ALL STRUCTURAL STEELWORK SHALL CONFORM TO CSA G 40.21 M - 350W AT CATEGORY 3 AND SHALL BE HOT-DIP GALVANISED.
 - ALL CONCRETE ANCHORS TO BE HILTI GALVANISED M20 GRADE 8.8 HAS-E RODS (OR SIMILAR APPROVED) WITH NOMINAL TENSILE STRENGTH = 800 MPa. EMBEDMENT = 170mm MINIMUM. DRILL AND EPOXY WITH HILTI HIT-RE 500SD (OR SIMILAR APPROVED) IN STRICT CONFORMANCE WITH THE MANUFACTURER'S SPECIFICATIONS.
 - ALL WELDING SHALL CONFORM TO THE CURRENT AWS SPECIFICATION D1.5 AND SHALL BE 6 mm CONTINUOUS FILLET WELDS.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ADEQUATE MEANS OF MAINTAINING THE STABILITY OF THE STEEL COLUMNS IN THE CORRECT ALIGNMENT UNTIL THE BACKFILLING AROUND THE COLUMNS IS COMPLETE.

- ALL PANELS ARE TO BE CLEARLY MARKED AS PER THE DRAWINGS IN 50MM LETTERS ON THE BOTTOM EXPOSED FACE WITH AN IDENTIFYING NUMBER AND GRID REFERENCE.
- THE CONTRACTOR IS TO PROVIDE DETAILED DRAWINGS AND REINFORCING SCHEDULES FOR APPROVAL.
- MINIMUM CONCRETE 28 DAY COMPRESSIVE STRENGTH: 40 MPA.
- COVER TO REINFORCING STEEL: 50MM, UNLESS NOTED OTHERWISE.
- ALL REINFORCING STEEL SHALL BE HIGH TENSILE DEFORMED REINFORCING STEEL CONFORMING TO CAN / CSA - G30.18.
- CRACK RESISTANCE BARS SHALL BE HOT-DIP GALVANISED STEEL CONFORMING TO CAN / CSA - G40.21.
- ANY REINFORCING BARS THAT ARE TO BE HOT-DIP GALVANISED SHALL CONFORM TO THE REQUIREMENTS OF CSA G40.21 M GRADE 300W.
- MINIMUM BAR LAP LENGTH = 45 x BAR DIAMETER.
- GROUT FOR PRECAST PANEL TRANSVERSE SHEAR KEYS AND STUD POCKETS, AND APPROACH SLAB POCKETS, SHALL BE SIKADUR LT GROUT (OR SIMILAR APPROVED MAGNESIUM PHOSPHATE BASED FLOWABLE NON-SHRINK GROUT). THE GROUT IS TO BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AND IS TO HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 40 MPA.
- ALL FORMED SURFACES OF THE PRECAST CONCRETE PANELS SHALL HAVE A SMOOTH-RUBBED FINISH.
- AND ALL FORMED FACES SHALL HAVE A SMOOTH-FORM FINISH IN ACCORDANCE WITH CLAUSE 7.7.3: CSA STANDARD A2.31 - 04.
- ALL EXPOSED CONCRETE CORNERS INCLUDING THE STUD POCKETS AND TRANSVERSE SHEAR KEYS, SHALL HAVE A 20mm X 20mm CHAMFER OR FILLET UNLESS NOTED OTHERWISE ON THE DRAWINGS.
- PRECAST CONCRETE PANELS SHALL BE CAST IN A METAL FORM.
- THE MAXIMUM DIMENSIONAL DEVIATION FOR THE PRECAST CONCRETE PANELS FROM THE DIMENSIONS SHOWN ON THE DRAWING SHALL NOT EXCEED THE FOLLOWING:
 - \$ LENGTH (MEASURED PERPENDICULAR TO THE PANEL DIVISIONS) = +/- . ??? 5MM
 - \$ WIDTH (MEASURED PARALLEL TO THE PANEL DIVISIONS) = +/- . ??? 5MM
 - \$ THICKNESS = +/- . ??? 3MM
 - \$ MAXIMUM DIFFERENCE IN PLAN VIEW DIAGONAL DIMENSIONS (SQUARENESS) OF RECTANGULAR PANELS = +/- ??? 10MM.

- ALL SURFACES THAT WILL BE IN CONTACT WITH SIKADUR LT GROUT, SHALL BE INTENTIONALLY ROUGHENED BY HEAVY SANDBLASTING. THIS INCLUDES THE TRANSVERSE PANEL EDGES THAT FORM THE SHEAR KEY, STUD POCKETS AND THE APPROACH SLAB POCKETS.
- ADJUST REINFORCEMENT WHERE REQUIRED TO CLEAR STUD POCKETS, APPROACH SLAB POCKETS, AND LIFTING HOOK ASSEMBLIES.
- GROUTING FOR TRANSVERSE SHEAR KEYS SHALL START FROM THE OUTSIDE END PANELS TOWARDS THE CENTRE PANELS.
- ON THE TOP SURFACE OF THE GROUT IN STUD POCKETS, TRANSVERSE SHEAR KEYS LIFTING HOOK POCKETS SHALL BE FLUSH WITH THE TOP FINISHED SURFACE OF THE PANELS.
- GROUT IN ANY LOCATION SHALL BE TOPPED UP AFTER GROUT HAS SETTLED.
- ALL GROUT SHALL BE PLACED AND CURED ACCORDING TO MANUFACTURER SPECIFICATIONS.

PROVISION FOR LIFTING & HANDLING ARE THE RESPONSIBILITY OF THE CONTRACTOR, WHO SHALL ENSURE THAT THE DESIGN IS ADEQUATE FOR ALL STAGES OF THE ERECTION PROCEDURE.

- IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE LIFTING HOOK LOCATIONS.
- AFTER THE PRECAST CONCRETE PANELS HAVE BEEN ERECTED, LIFTING HOOKS SHALL BE CUT OFF FLUSH WITH THE BOTTOM OF THE POCKET.
- PRECAST PANELS SHALL BE MAINTAINED LEVEL DURING HANDLING AND LIFTING FORCES SHALL BE VERTICAL AT ALL TIMES



DRAWING LIST

HATCH



BAFFINLAND IRON MINES LP
MARY RIVER EXPANSION PROJECT

PORT SITE
RAIL UNLOADER INDEXER
INDEXER FOUNDATION GENERAL
ARRANGEMENT AND NOTES

DRAFTSPERSON	R. PAUL	NR	
DESIGNER	S. HARRYCHUND	NR	
CHECKER	G.HOOPER		
DESIGN COORD.	R. GOOSEN		
RESP. ENG.			
LEAD DISC. ENG.	G.HOOPER		
ENG. MANAGER	N.MASON		
PROJ. MANAGER	S.HEINER		

SCALE	DWG. No.	REV
OR AS NOTED	H353004-40000-231-292-0001-0001	A

		NAME
		SIGNATURE
		ENG REG NUMBER
		REVISION DATE
H35004-00000-220-272-0001-0001	PORT SITE BLOCK PLAN OVERALL LAYOUT	
DRAWING No.	DRAWING TITLE	ORIGINAL DATE
REFERENCE DRAWINGS		REG. PROFESSIONAL

		THIS DRAWING WAS PREPARED FOR THE EXCLUSIVE USE OF BATHINLAND IRON MINES LP ("CLIENT") AND IS ISSUED PURSUANT TO THE AGREEMENT BETWEEN CLIENT AND HATCH LTD. ("HATCH") UNLESS OTHERWISE AGREED IN WRITING WITH CLIENT OR SPECIFIED ON THIS DRAWING. (A) HATCH DOES NOT ACCEPT AND DISCLAIMS ANY AND ALL LIABILITY OR RESPONSIBILITY ARISING FROM ANY USE OF OR RELIANCE ON THIS DRAWING BY ANY THIRD PARTY OR ANY MODIFICATION OR MISUSE OF THIS DRAWING BY CLIENT, AND (B) THIS DRAWING IS CONFIDENTIAL AND ALL INTELLECTUAL PROPERTY RIGHTS EMBODIED OR REFERENCED IN THIS DRAWING REMAIN THE PROPERTY OF HATCH.			
1	CLIENT REVIEW		R.P	S.H	JAN 18
No.	DESCRIPTION		BY	CHK'D	DATE
REVISIONS					



DRAWING APPROVAL STATUS:

OR AS NOTED

DWG. No.

H3530

REV	A	\$USERNAMES	\$TIMES
		\$DATES	\$FILES



NAME			THIS DRAWING WAS PREPARED FOR THE EXCLUSIVE USE OF BAFFINLAND IRON MINES LP (CLIENT) AND IS ISSUED PURSUANT TO THE AGREEMENT BETWEEN CLIENT AND HATCH LTD. (HATCH) UNLESS OTHERWISE AGREED IN WRITING WITH CLIENT OR SPECIFIED ON THIS DRAWING. (A) HATCH DOES NOT ACCEPT AND DISCLAIMS ANY AND ALL LIABILITY OR RESPONSIBILITY ARISING FROM ANY USE OF OR RELIANCE ON THIS DRAWING BY ANY THIRD PARTY OR ANY MODIFICATION OR MISUSE OF THIS DRAWING BY CLIENT, AND (B) THIS DRAWING IS CONFIDENTIAL AND ALL INTELLECTUAL PROPERTY RIGHTS EMBODIED OR REFERENCED IN THIS DRAWING REMAIN THE PROPERTY OF HATCH.			DRAFTSPERSON R. PAUL NR			HATCH			Baffinland		
SIGNATURE						DESIGNER S. HARRYCHUND NR			BAFFINLAND IRON MINES LP			MARY RIVER EXPANSION PROJECT		
ENG REG NUMBER						CHECKER G. HOOPER			PORT SITE			RAIL UNLOADER INDEXER		
REVISION DATE						DESIGN COORD. R. GOOSEN			APPROACH SLAB CONCRETE AND			STRUCTURAL STEELWORK DETAILS SHEET 1		
ORIGINAL DATE			1 CLIENT REVIEW			LEAD DISC. ENG. G. HOOPER			DRAWING APPROVAL STATUS:			SCALE DWG. No. H353004-40000-231-292-0006-0001		
REG. PROFESSIONAL			REVISIONS			ENG. MANAGER N. MASON			ROLE NAME SIGNATURE DATE			OR AS NOTED		
DRAWING No. H35004-40000-231-292-0001-0001			DRAWING TITLE INDEXER FOUNDATION GENERAL ARRANGEMENT AND NOTES			PROJ. MANAGER S. HEINER			SHEET SIZE: A1			SUBSURNAMES \$TIMES		
DRAWING TITLE			DESCRIPTION			R.P. S.H. JAN 18			BY CHK'D DATE			REV A		
REFERENCE DRAWINGS			1											
1			2			3			4			5		
2			3			4			5			6		
3			4			5			6			7		
4			5			6			7			8		