DWG. No. H353004-35000-232-260-0002-0003

BILL OF MATERIALS - BR #15.913

STEEL

ITEM	MARK	UNIT	QTY.	DRAWING No. H353004–35000–232–
14.500m c/c BEARINGS T.P.G. SPAN (SKEWED ENDS)	STSD2	1	7	260–0001–0004
EXPANSION BEARING (PIERS)	A6	1	6	260–0001–0006
EXPANSION BEARING (PIERS)	B6	1	6	260–0001–0006
FIXED BEARING (PIERS)	C6	1	6	260–0001–0006
FIXED BEARING (PIERS)	D6	1	6	260–0001–0006
ANCHOR BOLTS	E6	1	96	260–0001–0006
EXPANSION BEARING (ABUTMENTS)	A13	1	1	260–0001–0013
FIXED BEARING (ABUTMENTS)	B13	1	1	260–0001–0013
FIXED BEARING (ABUTMENTS)	C13	1	1	260–0001–0013
EXPANSION BEARING (ABUTMENTS)	D13	1	1	260–0001–0013
ANCHOR BOLTS	E13	1	16	260–0001–0013
DECK JOINT COVER PLATE (SKEWED)	B8	1	8	260–0001–0008
PRECAST CONCRETE BACKWALL (SKEWED)	A11	1	2	260–0006–0006, –0011
PRECAST CONCRETE BACKWALL (SKEWED)	B11	1	2	260–0006–0006, –0011
STEEL ABUTMENT CAP (SKEWED)	AC2	1	2	260–0006–0007
8–PILE STEEL PIER CAP (SKEWED)	8PPC2	1	4	260–0006–0008
10–PILE STEEL PIER CAP (SKEWED)	10PPC2	1	2	260–0006–0009
WALKWAY				
WALKWAY SUPPORT	A7	1	164	260–0002–0007
HANDRAIL POST	B7	1	164	260–0002–0007
REFUGE BAY POST	B9	1	4	260–0002–0009
REFUGE BAY POST	C9	1	4	260–0002–0009
BACKWALL HANDRAIL	C7	1	4	260–0002–0007
FREE RAIL – 4150mm LONG	D7	1	48	260–0002–0007
FREE RAIL – 2775mm LONG	S7	1	8	260–0002–0007
REFUGE BAY HANDRAIL	A9	1	8	260–0002–0009
HANDRAIL LOOP – 3340mm LONG	E7	1	28	260–0002–0007
GRATING PANEL 613 x 4335mm	G7	1	14	260–0002–0007
GRATING PANEL 613 x 5620mm	W7	1	12	260–0002–0007
GRATING PANEL 613 x 5110mm	T7	1	12	260–0002–0007
GRATING PANEL 613 x 1650mm (REFUGE)	S7	1	2	260–0002–0007
GRATING PANEL 613 x 5075mm (SKEWED)	H7	1	2	260–0002–0007
GRATING PANEL 613 x 6110mm (SKEWED)	K7	1	2	260–0002–0007
HANDRAIL SPLICE	RS1	1	100	260–0002–0007
9.5mm dia. U–BOLT (C/W 4 HEX NUTS & 2 FLAT WASHERS)	M7	1	344	260–0002–0007
FIBRE–OPTIC BRACKET (C/W 12mm dia.x50mm LG. BOLT W/NUT & WASHER)	N7	1	168	260–0002–0007
REFUGE SUPPORT	P7	1	4	260–0002–0007
TYPE 'H–3' SADDLE CLIP C/W M20x70 HEX BOLT & HEX NUT		1	896	
WALKWAY TOE PLATE L 200x200x13x15000	D9	1	14	260–0002–0009

1

1

1

PERMIT TO PRACTICE
HATCH LTD.
Signature
Date
PERMIT NUMBER: P 512
The Association of Professional Engineers, Geologists and Geophysicists of NWT/NU

REGISTERED PROFESSIONAL ENGINEER A.C. MIDDLETON LICENSEE 03/03/2021 NT/NU

APPROVED FOR CONSTRUCTION

THIS DRAWING WAS PREPARED BY HATCH LTD. ("HATCH") FOR THE EXCLUSIVE USE OF BAFFINLAND IRON MINES LP ("CLIENT") AND ITS USE IS SUBJECT TO THE TERMS AND CONDITIONS OF THE CONTRACT BETWEEN HATCH AND THE THE CLIENT, INCLUDING ANY LIMITATIONS ON LIABILITY CONTAINED THEREIN. THIS DRAWING AND ITS CONTENTS REMAIN THE INTELLECTUAL PROPERTY OF HATCH SUBJECT TO CLIENT'S ROYALTY-FREE, IRREVOCABLE, PERPETUAL AND NON-EXCLUSIVE LICENSE TO USE AND REPRODUCE THE DRAWING FOR PURPOSES CONNECTED WITH THE PROJECT, INCLUDING THE CONSTRUCTION, COMPLETION, MAINTENANCE, EXTENSION, REINSTATEMENT AND REPAIR OF THE PROJECT. THIS DRAWING, AND THE INFORMATION CONTAINED HEREIN, SHALL BE TREATED AS CONFIDENTIAL FOR ALL OTHER PURPOSES AND SHALL NOT BE MODIFIED WITHOUT THE WRITTEN CONSENT OF HATCH.

No.	DESCRIPTION	BY	CHK'D	DATE
1	PIER AND ABUTMENT CAPS, BEARINGS, WALKWAY GRATING REVISED			FEB. 23/21
0	ISSUED FOR CONSTRUCTION			MARCH 20/19

REVISIONS

HATCH

ROLE	NAME	SIGNATURE	DATE
DRAFTSPERSON	S HANDY	NR	FEB. 23/21
DESIGNER	J PAEZ/D BENSON	NR	FEB. 23/21
CHECKER	A MIDDLETON		FEB. 23/21
DESIGN COORD.	J BALDWIN		FEB. 23/21
RESP. ENG.	A MIDDLETON		FEB. 23/21
LEAD DISC. ENG.			
AREA LEAD	L NGWENYA		
ENG. MANAGER	F VAN BILJON		FEB. 23/21
AREA MANAGER	F PITTMAN		FEB. 23/21

DRAWING APPROVAL STATUS: APPROVED FOR CONSTRUCTION

Baffinland

BAFFINLAND IRON ORE MINES LP
MARY RIVER EXPANSION PROJECT

RAILWAY
BR #15.913
BILL OF MATERIAL

SCALE: OR AS NOTED
DWG. No.: H353004–35000–232–260–0002–0003
REV: 1

DRAWING No. | DRAWING TITLE
REFERENCE DRAWINGS

REG. PROFESSIONAL

SHEET SIZE: A1

$USERNAME$
$DATE$
$FILE$

DWG. No. H353004-35000-232-260-0003-0003

1 BILL OF MATERIALS - BR #59.400

STEEL

ITEM	MARK	UNIT	QTY.	DRAWING No. H353004–35000–232–
14.500m c/c BEARINGS T.P.G. SPAN (SQUARED ENDS)	STSD1	1	6	260–0001–0001
EXPANSION BEARING (PIERS)	A3	1	5	260–0001–0003
EXPANSION BEARING (PIERS)	B3	1	5	260–0001–0003
FIXED BEARING (PIERS)	C3	1	5	260–0001–0003
FIXED BEARING (PIERS)	D3	1	5	260–0001–0003
ANCHOR BOLTS	E3	1	80	260–0001–0003
EXPANSION BEARING (ABUTMENTS)	A12	1	1	260–0001–0012
EXPANSION BEARING (ABUTMENTS)	B12	1	1	260–0001–0012
FIXED BEARING (ABUTMENTS)	C12	1	1	260–0001–0012
FIXED BEARING (ABUTMENTS)	D12	1	1	260–0001–0012
ANCHOR BOLTS	E12	1	16	260–0001–0012
DECK JOINT COVER PLATE (SQUARED)	A8	1	7	260–0001–0008
PRECAST CONCRETE BACKWALL (SQUARED)	$A1^R$	1	2	260–0006–0001
PRECAST CONCRETE BACKWALL (SQUARED)	$A1^L$	1	2	260–0006–0001
STEEL ABUTMENT CAP (SQUARED)	AC1	1	2	260–0006–0002
8–PILE STEEL PIER CAP (SQUARED)	8PPC1	1	3	260–0006–0003
10–PILE STEEL PIER CAP (SQUARED)	10PPC1	1	2	260–0006–0004
WALKWAY				
WALKWAY SUPPORT	A7	1	140	260–0002–0007
HANDRAIL POST	B7	1	140	260–0002–0007
REFUGE BAY POST	B9	1	4	260–0002–0009
REFUGE BAY POST	C9	1	4	260–0002–0009
BACKWALL HANDRAIL	C7	1	4	260–0002–0007
REFUGE BAY HANDRAIL	A9	1	8	260–0002–0009
FREE RAIL – 4150mm LONG	D7	1	40	260–0002–0007
FREE RAIL – 2775mm LONG	S7	1	8	260–0002–0007
HANDRAIL LOOP – 3340mm LONG	E7	1	24	260–0002–0007
GRATING PANEL 613 x 5480mm	F7	1	4	260–0002–0007
GRATING PANEL 613 x 4335mm	G7	1	12	260–0002–0007
GRATING PANEL 613 x 5365mm	P7	1	20	260–0002–0007
GRATING PANEL 613 x 1650mm (REFUGE)	S7	1	2	260–0002–0007
HANDRAIL SPLICE	RS1	1	80	260–0002–0007
9.5mm dia. U–BOLT (C/W 4 HEX NUTS & 2 FLAT WASHERS)	M7	1	296	260–0002–0007
FIBRE–OPTIC BRACKET (C/W 12mm dia.x50mm LG. BOLT W/NUT & WASHER)	N7	1	144	260–0002–0007
REFUGE SUPPORT	P7	1	4	260–0002–0007
TYPE 'H–3' SADDLE CLIP C/W M20x70 HEX BOLT & HEX NUT		1	784	
WALKWAY TOE PLATE L 200x200x13x15000	D9	1	12	260–0002–0009

1

1

1

PERMIT TO PRACTICE
HATCH LTD.
Signature
Date
PERMIT NUMBER: P 512
The Association of Professional Engineers, Geologists and Geophysicists of NWT/NU

DRAWING No.	DRAWING TITLE
REFERENCE DRAWINGS	

REGISTERED PROFESSIONAL ENGINEER A.C. MIDDLETON LICENSEE 03/03/2021 NT/NU

REG. PROFESSIONAL

APPROVED FOR CONSTRUCTION

THIS DRAWING WAS PREPARED BY HATCH LTD. ("HATCH") FOR THE EXCLUSIVE USE OF BAFFINLAND IRON MINES LP ("CLIENT") AND ITS USE IS SUBJECT TO THE TERMS AND CONDITIONS OF THE CONTRACT BETWEEN HATCH AND THE THE CLIENT, INCLUDING ANY LIMITATIONS ON LIABILITY CONTAINED THEREIN. THIS DRAWING AND ITS CONTENTS REMAIN THE INTELLECTUAL PROPERTY OF HATCH SUBJECT TO CLIENT'S ROYALTY-FREE, IRREVOCABLE, PERPETUAL AND NON-EXCLUSIVE LICENSE TO USE AND REPRODUCE THE DRAWING FOR PURPOSES CONNECTED WITH THE PROJECT, INCLUDING THE CONSTRUCTION, COMPLETION, MAINTENANCE, EXTENSION, REINSTATEMENT AND REPAIR OF THE PROJECT. THIS DRAWING, AND THE INFORMATION CONTAINED HEREIN, SHALL BE TREATED AS CONFIDENTIAL FOR ALL OTHER PURPOSES AND SHALL NOT BE MODIFIED WITHOUT THE WRITTEN CONSENT OF HATCH.

No.	DESCRIPTION	BY	CHK'D	DATE
1	NEW BRIDGE LOCATION/REVISED PIER AND ABUTMENT CAPS – BEARINGS, WALKWAY GRATING REVISED			FEB. 23/21
0	ISSUED FOR CONSTRUCTION			MARCH 20/19

REVISIONS

HATCH

ROLE	NAME	SIGNATURE	DATE
DRAFTSPERSON	S HANDY	NR	FEB. 23/21
DESIGNER	J PAEZ/D BENSON	NR	FEB. 23/21
CHECKER	A MIDDLETON		FEB. 23/21
DESIGN COORD.	J BALDWIN		FEB. 23/21
RESP. ENG.	A MIDDLETON		FEB. 23/21
LEAD DISC. ENG.			
AREA LEAD	L NGWENYA		
ENG. MANAGER	F VAN BILJON		FEB. 23/21
AREA MANAGER	F PITTMAN		FEB. 23/21

DRAWING APPROVAL STATUS: APPROVED FOR CONSTRUCTION

Baffinland

BAFFINLAND IRON ORE MINES LP
MARY RIVER EXPANSION PROJECT

1 RAILWAY
BR #59.400
BILL OF MATERIAL

SCALE	DWG. No.	REV
OR AS NOTED	H353004–35000–232–260–0003–0003	1

SHEET SIZE: A1

$USERNAME$
$DATE$
$FILE$
$TIME$

DWG. No. H353004-35000-232-260-0004-0003

1 BILL OF MATERIALS - BR #82.340

STEEL

ITEM	MARK	UNIT	QTY.	DRAWING No. H353004–35000–232–
14.500m c/c BEARINGS T.P.G. SPAN (SKEWED ENDS)	STSD2	1	4	260–0001–0004
EXPANSION BEARING (PIERS)	A6	1	3	260–0001–0006
EXPANSION BEARING (PIERS)	B6	1	3	260–0001–0006
FIXED BEARING (PIERS)	C6	1	3	260–0001–0006
FIXED BEARING (PIERS)	D6	1	3	260–0001–0006
ANCHOR BOLTS	E6	1	48	260–0001–0006
EXPANSION BEARING (ABUTMENTS)	A13	1	1	260–0001–0013
FIXED BEARING (ABUTMENTS)	B13	1	1	260–0001–0013
FIXED BEARING (ABUTMENTS)	C13	1	1	260–0001–0013
EXPANSION BEARING (ABUTMENTS)	D13	1	1	260–0001–0013
ANCHOR BOLTS	E13	1	16	260–0001–0013
DECK JOINT COVER PLATE (SKEWED)	B8	1	5	260–0001–0008
PRECAST CONCRET BACKWALL (SKEWED)	A11	1	2	260–0006–0006, –0011
PRECAST CONCRET BACKWALL (SKEWED)	B11	1	2	260–0006–0006, –0011
STEEL ABUTMENT CAP (SKEWED)	AC2	1	2	260–0006–0007
8–PILE STEEL PIER CAP (SKEWED)	8PPC2	1	3	260–0006–0008
WALKWAY				
WALKWAY SUPPORT	A7	1	92	260–0002–0007
HANDRAIL POST	B7	1	92	260–0002–0007
REFUGE BAY POST	B9	1	4	260–0002–0009
REFUGE BAY POST	C9	1	4	260–0002–0009
BACKWALL HANDRAIL	C7	1	4	260–0002–0007
REFUGE BAY HANDRAIL	A9	1	8	260–0002–0009
FREE RAIL – 4150mm LONG	D7	1	24	260–0002–0007
FREE RAIL – 2775mm LONG	S7	1	8	260–0002–0007
HANDRAIL LOOP – 3340mm LONG	E7	1	16	260–0002–0007
GRATING PANEL 613 x 4335mm	G7	1	8	260–0002–0007
GRATING PANEL 613 x 5110mm	T7	1	6	260–0002–0007
GRATING PANEL 613 x 5620mm	W7	1	6	260–0002–0007
GRATING PANEL 613 x 1650mm (REFUGE)	S7	1	2	260–0002–0007
GRATING PANEL 613 x 5075mm (SKEWED)	H7	1	2	260–0002–0007
GRATING PANEL 613 x 6110mm (SKEWED)	K7	1	2	260–0002–0007
HANDRAIL SPLICE	RS1	1	56	260–0002–0007
9.5mm dia. U–BOLT (C/W 4 HEX NUTS & 2 FLAT WASHERS)	M7	1	200	260–0002–0007
FIBRE–OPTIC BRACKET (C/W 12mm dia.x50mm LG. BOLT W/NUT & WASHER)	N7	1	96	260–0002–0007
REFUGE SUPPORT	P7	1	4	260–0002–0007
TYPE 'H–3' SADDLE CLIP C/W M20x70 HEX BOLT & HEX NUT		1	512	
WALKWAY TOE PLATE L 200x200x13x15000	D9	1	8	260–0002–0009

PERMIT TO PRACTICE
HATCH LTD.
Signature
Date
PERMIT NUMBER: P 512
The Association of Professional Engineers, Geologists and Geophysicists of NWT/NU

DRAWING No.	DRAWING TITLE
REFERENCE DRAWINGS	

REGISTERED PROFESSIONAL ENGINEER A.C. MIDDLETON LICENSEE 03/23/2021 NT/NU

REG. PROFESSIONAL

APPROVED FOR CONSTRUCTION

THIS DRAWING WAS PREPARED BY HATCH LTD. ("HATCH") FOR THE EXCLUSIVE USE OF BAFFINLAND IRON MINES LP ("CLIENT") AND ITS USE IS SUBJECT TO THE TERMS AND CONDITIONS OF THE CONTRACT BETWEEN HATCH AND THE THE CLIENT, INCLUDING ANY LIMITATIONS ON LIABILITY CONTAINED THEREIN. THIS DRAWING AND ITS CONTENTS REMAIN THE INTELLECTUAL PROPERTY OF HATCH SUBJECT TO CLIENT'S ROYALTY-FREE, IRREVOCABLE, PERPETUAL AND NON-EXCLUSIVE LICENSE TO USE AND REPRODUCE THE DRAWING FOR PURPOSES CONNECTED WITH THE PROJECT, INCLUDING THE CONSTRUCTION, COMPLETION, MAINTENANCE, EXTENSION, REINSTATEMENT AND REPAIR OF THE PROJECT. THIS DRAWING, AND THE INFORMATION CONTAINED HEREIN, SHALL BE TREATED AS CONFIDENTIAL FOR ALL OTHER PURPOSES AND SHALL NOT BE MODIFIED WITHOUT THE WRITTEN CONSENT OF HATCH.

No.	DESCRIPTION	BY	CHK'D	DATE
1	NEW BRIDGE LOCATION, PIER AND ABUTMENT CAPS, BEARINGS, WALKWAY GRATING REVISED			FEB. 23/21
0	ISSUED FOR CONSTRUCTION			MARCH 20/19

REVISIONS

HATCH

ROLE	NAME	SIGNATURE	DATE
DRAFTSPERSON	S HANDY	NR	FEB. 23/21
DESIGNER	J PAEZ/D BENSON	NR	FEB. 23/21
CHECKER	A MIDDLETON		FEB. 23/21
DESIGN COORD.	J BALDWIN		FEB. 23/21
RESP. ENG.	A MIDDLETON		FEB. 23/21
LEAD DISC. ENG.			
AREA LEAD	L NGWENYA		
ENG. MANAGER	F VAN BILJON		FEB. 23/21
AREA MANAGER	F PITTMAN		FEB. 23/21

DRAWING APPROVAL STATUS: APPROVED FOR CONSTRUCTION

Baffinland

BAFFINLAND IRON ORE MINES LP
MARY RIVER EXPANSION PROJECT

RAILWAY
1 BR #82.340
BILL OF MATERIAL

SCALE OR AS NOTED | DWG. No. H353004–35000–232–260–0004–0003 | REV 1

$USERNAME$ $TIME$
$DATE$
$FILE$

SHEET SIZE: A1

DWG. No. H353004-35000-232-260-0005-0004

1 BILL OF MATERIALS - BR #98.534

STEEL

ITEM	MARK	UNIT	QTY.	DRAWING No. H353004–35000–232–
14.500m c/c BEARINGS T.P.G. SPAN (SQUARED ENDS)	STSD1	1	4	260–0001–0001
EXPANSION BEARING	A3	1	3	260–0001–0003
EXPANSION BEARING	B3	1	3	260–0001–0003
FIXED BEARING	C3	1	3	260–0001–0003
FIXED BEARING	D3	1	3	260–0001–0003
ANCHOR BOLTS	E3	1	48	260–0001–0003
EXPANSION BEARING (ABUTMENTS)	A12	1	1	260–0001–0012
EXPANSION BEARING (ABUTMENTS)	B12	1	1	260–0001–0012
FIXED BEARING (ABUTMENTS)	C12	1	1	260–0001–0012
FIXED BEARING (ABUTMENTS)	D12	1	1	260–0001–0012
ANCHOR BOLTS	E12	1	16	260–0001–0012
DECK JOINT COVER PLATE (SQUARED)	A8	1	5	260–0001–0008
PRECAST CONCRETE BACKWALL (SQUARED)	$A1^R$	1	2	260–0006–0001
PRECAST CONCRETE BACKWALL (SQUARED)	$A1^L$	1	2	260–0006–0001
STEEL ABUTMENT CAP (SQUARED)	AC1	1	2	260–0006–0002
8–PILE STEEL PIER CAP (SQUARED)	8PPC1	1	3	260–0006–0003
WALKWAY				
WALKWAY SUPPORT	A7	1	92	260–0002–0007
HANDRAIL POST	B7	1	92	260–0002–0007
REFUGE BAY POST	B9	1	4	260–0002–0009
REFUGE BAY POST	C9	1	4	260–0002–0009
BACKWALL HANDRAIL	C7	1	4	260–0002–0007
REFUGE BAY HANDRAIL	A9	1	8	260–0002–0009
FREE RAIL – 4150mm LONG	D7	1	24	260–0002–0007
FREE RAIL – 2775mm LONG	S7	1	8	260–0002–0007
HANDRAIL LOOP – 3340mm LONG	E7	1	16	260–0002–0007
GRATING PANEL 613 x 5480mm	F7	1	4	260–0002–0007
GRATING PANEL 613 x 4335mm	G7	1	8	260–0002–0007
GRATING PANEL 613 x 5365mm	P7	1	12	260–0002–0007
GRATING PANEL 613 x 1650mm (REFUGE)	S7	1	2	260–0002–0007
HANDRAIL SPLICE	RS1	1	56	260–0002–0007
9.5mm dia. U–BOLT (C/W 4 HEX NUTS & 2 FLAT WASHERS)	M7	1	200	260–0002–0007
FIBRE–OPTIC BRACKET (C/W 12mm dia.x50mm LG. BOLT W/NUT & WASHER)	N7	1	96	260–0002–0007
REFUGE SUPPORT	P7	1	4	260–0002–0007
TYPE 'H–3' SADDLE CLIP C/W M20x70 HEX BOLT & HEX NUT		1	512	
WALKWAY TOE PLATE L 200x200x13x15000	D9	1	8	260–0002–0009

1

1

1

PERMIT TO PRACTICE
HATCH LTD.
Signature
Date
PERMIT NUMBER: P 512
The Association of Professional Engineers, Geologists and Geophysicists of NWT/NU

DRAWING No.	DRAWING TITLE
REFERENCE DRAWINGS	

REGISTERED PROFESSIONAL ENGINEER A.C. MIDDLETON LICENSEE 08/23/2021 NT/NU

REG. PROFESSIONAL

APPROVED FOR CONSTRUCTION

THIS DRAWING WAS PREPARED BY HATCH LTD. ("HATCH") FOR THE EXCLUSIVE USE OF BAFFINLAND IRON MINES LP ("CLIENT") AND ITS USE IS SUBJECT TO THE TERMS AND CONDITIONS OF THE CONTRACT BETWEEN HATCH AND THE THE CLIENT, INCLUDING ANY LIMITATIONS ON LIABILITY CONTAINED THEREIN. THIS DRAWING AND ITS CONTENTS REMAIN THE INTELLECTUAL PROPERTY OF HATCH SUBJECT TO CLIENT'S ROYALTY-FREE, IRREVOCABLE, PERPETUAL AND NON-EXCLUSIVE LICENSE TO USE AND REPRODUCE THE DRAWING FOR PURPOSES CONNECTED WITH THE PROJECT, INCLUDING THE CONSTRUCTION, COMPLETION, MAINTENANCE, EXTENSION, REINSTATEMENT AND REPAIR OF THE PROJECT. THIS DRAWING, AND THE INFORMATION CONTAINED HEREIN, SHALL BE TREATED AS CONFIDENTIAL FOR ALL OTHER PURPOSES AND SHALL NOT BE MODIFIED WITHOUT THE WRITTEN CONSENT OF HATCH.

No.	DESCRIPTION	BY	CHK'D	DATE
1	NEW BRIDGE LOCATION, PIER AND ABUTMENT CAPS, BEARINGS, WALKWAY GRATING REVISED			FEB. 23/21
0	ISSUED FOR CONSTRUCTION			MARCH 20/19

REVISIONS

HATCH

ROLE	NAME	SIGNATURE	DATE
DRAFTSPERSON	S HANDY	NR	FEB. 23/21
DESIGNER	J PAEZ/D BENSON	NR	FEB. 23/21
CHECKER	A MIDDLETON		FEB. 23/21
DESIGN COORD.	J BALDWIN		FEB. 23/21
RESP. ENG.	A MIDDLETON		FEB. 23/21
LEAD DISC. ENG.			
AREA LEAD	L NGWENYA		
ENG. MANAGER	F VAN BILJON		FEB. 23/21
AREA MANAGER	F PITTMAN		FEB. 23/21

DRAWING APPROVAL STATUS: APPROVED FOR CONSTRUCTION

Baffinland

BAFFINLAND IRON ORE MINES LP
MARY RIVER EXPANSION PROJECT

1 RAILWAY BR #98.534 BILL OF MATERIAL

SCALE	DWG. No.	REV
OR AS NOTED	H353004–35000–232–260–0005–0004	1

SHEET SIZE: A1

$USERNAME$ $DATE$ $TIME$