

## Table of Contents

<b>1. Process Conditions .....</b>	<b>3</b>
1.1 General .....	3
1.2 Duty and Operational Requirements .....	3
1.3 Material Characteristics .....	3
1.4 Site Conditions .....	4
<b>2. Design Conditions .....</b>	<b>4</b>
2.1 Average Sewage Generation .....	4
2.2 Peak Flow .....	4
2.3 Treated Sewage Requirements .....	4
<b>3. Technical Requirements .....</b>	<b>4</b>
3.1 Equalization Tank .....	4
3.2 Treated Effluent Tank .....	5
3.3 Odour Control .....	5
<b>4. Performance Requirements .....</b>	<b>5</b>
4.1 Guarantees .....	5
4.2 Warranty .....	5
4.3 Test Methods and Procedures .....	5
<b>5. Pumps, Valves and Piping Requirements .....</b>	<b>6</b>
<b>6. Mechanical Requirements .....</b>	<b>6</b>
<b>7. Electrical Requirements .....</b>	<b>6</b>
<b>8. Instrumentation and Controls Requirements .....</b>	<b>6</b>
<b>9. Structural Requirements .....</b>	<b>7</b>
<b>10. Painting Requirements .....</b>	<b>7</b>
<b>11. Regulations, Standards, and Codes .....</b>	<b>8</b>
<b>12. Health, Safety, Environment and Community Requirements .....</b>	<b>9</b>
<b>13. Assembly and Testing .....</b>	<b>9</b>
13.1 Critical Dimensions .....	9
13.2 Equipment Assembly .....	9
13.3 Pre-Assembly .....	9
13.4 Specific Testing Requirements .....	9
13.5 Control System Components .....	9
<b>14. Shipping, Construction, Commissioning and Operator Training .....</b>	<b>10</b>
14.1 Shipping .....	10
14.2 Construction Supervision, Testing and Commissioning .....	10
14.3 Operator Training .....	10

15. Spare Parts .....	10
16. Quality Assurance .....	10

## **1. Process Conditions**

### **1.1 General**

For design requirements and conditions, refer to the equipment datasheet:

Equipment Data Sheet – Sewage Treatment Plant (Doc. No. H337697-PX701-D460753)

Additional specific requirements are provided below.

Equipment and components shall be the Seller's standard design for the service specified, with readily available replacement parts. No new technology shall be applied to the design of the equipment without examples of operating equipment using the technology in similar design conditions.

### **1.2 Duty and Operational Requirements**

The equipment shall be designed and constructed to operate continuously, 24 hours per day, 365 days per year without excessive maintenance. The design and automation shall consider minimum operating supervision of 2 hours/day. It is however anticipated that a dedicated operator (24/7) will be provided for each site.

The control system shall allow for manual and fully automated operation. Manual operation shall be used only for trouble-shooting, maintenance and repair situations, otherwise, the system shall always be in full automation mode.

All equipment will be of the Supplier's best quality and construction to ensure a minimum equipment design life of 25 years (exceptions to be noted).

The supplier shall supply a sufficient number of modular trains such that the system can produce 100% of the required flow during peak demand. The sewage treatment system shall be equipped with installed redundant spares for all critical components, including pumps, blower and motors. Spares are to be provided such that in the event of equipment failure, barring any pressure vessel or tank failure, the faulty component can be replaced and the system put back into service within hours. During regular maintenance or servicing of the equipment the daily design flow shall still be met. During normal operation all trains are to be in service to treat the feed flow.

### **1.3 Material Characteristics**

The Seller shall fabricate the equipment using only new materials of first grade quality, free from defects impairing strength, durability and appearance.

After the Purchase Order is issued, the Seller shall not substitute materials, without prior written approval from the Owner.

Materials of construction shall be suitable for the specified duty and operating conditions.

Use the lowest material density for volumetric capacity calculations. Use this volume and the highest material density for power calculations.

All materials of construction shall be identified by the Supplier by the current ASTM specification number(s) on the data sheets provided.

Design all equipment components such that corrosion and wear are minimized.

## **1.4 Site Conditions**

Site conditions are identified in Site Conditions Data Sheet (Doc. No. H337696-0000-10-107-0001).

## **2. Design Conditions**

### **2.1 Average Sewage Generation**

The average sewage generation rates shall be based upon a per capita generation rate given in the Design Basis – Sewage Treatment Plant (Doc. No. H337697-1000-10-109-0002) using the camp workforce. The supplier shall clearly identify any operating issues in transitioning from higher flows to lower flows during periods of start-up and shutdown.

### **2.2 Peak Flow**

The peak sewage water requirements shall be estimated using the peaking factors given in the Design Basis – Sewage Treatment Plant (Doc. No. H337697-1000-10-109-0002). The peaking factor estimates the peak hourly flowrate above the average demand. This factor is an estimate that is based upon the total number of people that are served by the sewage treatment system.

### **2.3 Treated Sewage Requirements**

The quality of the sewage treatment plant effluent shall be in accordance with the applicable site discharge limits as given in the Design Basis - Sewage Water Treatment Plant, Document No. H337697-4000-10-109-0002.

## **3. Technical Requirements**

### **3.1 Equalization Tank**

The equalization tank shall be sized to provide a minimum of retention of 24 hours in order to provide peak flow normalization and effective mixing for varying sewage compositions.

### 3.2 Treated Effluent Tank

The effluent tank will have a hydraulic retention of time of 2 days (at minimum). It is intended that the effluent tank will be at a low level during operation such that if sampling indicates that the effluent quality does not meet the applicable criteria further discharge can be prevented for a period in excess of a day to allow this effluent to be mixed, retreated, and retested. In addition this retention volume will allow for a minimal amount of recirculation through the STP using any spare STP capacity. This will improve the quality of the effluent in the tank. The volume is sufficient to allow for periodic sampling and testing of the treated effluent before discharge or reuse.

### 3.3 Odour Control

Odour control systems (i.e. carbon vents) shall be installed as a minimum at the equalization tank but also where deemed necessary by the supplier.

## 4. Performance Requirements

### 4.1 Guarantees

The supplied equipment shall be guaranteed as follows:

**Table 4-1: Guarantees**

Parameter	Guarantee Requirement
Flows	As per Section 2
Effluent Criteria	As per Section 2
Dewatered Sludge Cake TSS	> 30%wt dry solids

### 4.2 Warranty

The Seller shall warrant the equipment's manufacture is free of defects or workmanship for the greater period of 18 months from delivery or 12 months from commissioning. All components deemed to be defective shall be replaced to the Owner at no cost (supply and delivery). Installation or consequential damages costs shall not be the responsibility of the Seller.

In case of assistance delay by the Seller, the Owner reserves the right to perform the necessary maintenance at Seller's full expense.

### 4.3 Test Methods and Procedures

All test method details, timing, sampling protocols and procedures and tolerances shall be developed by the Seller, submitted with the bid package and agreed upon with the Owner before issue of a purchase order.

## 5. Pumps, Valves and Piping Requirements

Refer to standard specifications for Piping Materials Specifications, document number to be confirmed, for materials of construction for piping and valves for details.

## 6. Mechanical Requirements

Standard Mechanical requirements are identified in the Mechanical Design Criteria, XXX-TBD (not published).

All equipment and all components shall be the Seller's standard heavy-duty design and fabrication and shall have been proven effective and reliable under similar operating conditions. No new or unproven design is acceptable.

Not all parts and materials are specified in this specification. For those that are not specified, the Seller shall use their standard parts and materials, which will be subject to the approval of the Owner.

The Seller shall notify the Owner if any specific requested component is unsuitable for the required service and present alternatives, along with the technical justifications.

## 7. Electrical Requirements

Electrical design shall comply with the following:

- H337967-S260050 – Electrical Requirements for Packaged Equipment.

All electrical panels, transformers, lighting panel, MCCs, including starters, circuit breakers, and VFDs shall be provided by the Seller.

All lighting system, and power outlets, shall be included by the Seller.

All wiring, cabling conduits, and cable trays to be included by the Seller.

## 8. Instrumentation and Controls Requirements

Instrumentation and controls design shall comply with the following:

- Instrumentation Requirements for Packaged Equipment, H337967-S250050.

The local control system for the water treatment plant shall be supplied by the seller.

The Owner shall approve all exceptions or deviations from these requirements.

## 9. Structural Requirements

Structural design shall comply with the following:

- Structural Design Criteria – Doc. No. H337697-0000-35-109-0001.

The container and water tanks shall be designed for seismic and wind conditions in accordance with local codes, API and IBC.

Container and water tanks shall be anchored.

All equipment, including piping and electrical equipment, shall be secured by base plates, supports, or other means, to withstand seismic or wind loads.

The Seller shall supply certified design data showing dimensions, loadings, locations and sizes of all steel members which will allow others to design concrete foundations, inserts, and anchor bolts to receive Seller's equipment.

All stairs, ladders, platforms and walkways shall be supplied by the Supplier.

## 10. Painting Requirements

All exterior metallic surfaces shall be primed and painted / coated with a suitable polyurethane, or epoxy product capable of withstanding the noted site conditions, especially temperature variations without cracking chipping or peeling.

All interior carbon steel surfaces shall be primed and painted / coated or lined, with a suitable polyurethane, or epoxy product, and shall be in accordance with NSF61.

Painting shall not be required for parts of equipment that are manufactured of or coated with corrosion resistant materials that are machine finished or normally left unpainted.

Machine finished parts that are not manufactured of corrosion resistant materials and are not painted, shall be given a heavy coat of rust-inhibiting compound that can be easily removed at installation by the use of solvents and hand wiping.

## 11. Regulations, Standards, and Codes

The International System (SI) will be used for all design calculations and on all drawings.

The equipment shall comply with the latest version of all appropriate regulations, standards and codes, including, but not limited to, those listed below:

**Table 13-1: Applicable Regulations, Standards and Codes**

Number / Acronym	Title
AWWA	American Water Works Association
IBC	International Building Codes
Nunavut Waters and Nunavut Surface Rights Tribunal Act, SC 2002, c 10	
Northwest Territories Water Act	
Northwest Territories Water Regulations (SOR/93-303)	
Canadian Fisheries Act	
Canadian Environmental Protection Act (1999)	
CCME Water Quality Guidelines for the Protection of Aquatic Life	
Ontario Guidelines for Sewage Works 2008	
CCME Guidelines for Compost Quality	
Canadian Guidelines for Domestic Reclaimed Water for Use in Toilet and Urinal Flushing	
NSF	National Sanitation Foundation
OSHA	Occupational Safety and Health Administration



## **12. Health, Safety, Environment and Community Requirements**

Protection designed for the valid codes and standards shall be installed in order to avoid operator injury. Minimum required protection as follows:

- Operation point protection.
- Moving parts protection.
- Power transmission and gyratory parts protection.
- Hot spots protection.
- Dust emission protection.
- Tools protection.
- Collision detection system (between machines).
- Fire protection and detection system.

## **13. Assembly and Testing**

### **13.1 Critical Dimensions**

All critical dimensions shall be checked prior to shipment. All ancillaries shall be assembled and all motions tested in accordance with manufacturers standard procedures. Prior to disassembly all components shall be match marked, where practical, for ease of field assembly. The Seller shall describe the extent of field assembly required.

### **13.2 Equipment Assembly**

All equipment shall be shipped assembled to the maximum extent possible consistent with shipping limitations indicated below. The Owner shall be consulted prior to the shipment of large components.

### **13.3 Pre-Assembly**

All pre-piped and pre-assembled lube oil and hydraulic oil systems shall be tested for their output pressures and motions to the maximum extent possible.

### **13.4 Specific Testing Requirements**

Tanks to be hydrostatically tested, or other approved equivalent.

### **13.5 Control System Components**

At the Owner's option, Seller-furnished control systems components shall be subject to Owner-witnessed Factory Acceptance Test (FAT) in accordance with test procedures that shall be submitted by the Seller and reviewed by the Owner. All input / output signals and control functions shall be simulated. If required, the Seller-furnished components may be subject to integration testing with the main project PCS system.

The Seller shall submit a Site Acceptance Test procedure that will be subject to the Owner's review and permission to proceed. Items such as proper equipment grounding, powering up, checking for correct software installed, etc. shall be included in the procedure.

Wherever possible instruments shall be pre-wired and pre-installed to controller.

## **14. Shipping, Construction, Commissioning and Operator Training**

### **14.1 Shipping**

The equipment will be shipped to an assembly site in the largest feasible sections that allow transportation by gravel road. Protective coatings and coverings shall be applied to ensure that the equipment is not damaged during shipment. The Seller shall provide match-marking of all parts to facilitate field assembly and shall provide shipping dimensions and weights of all components and assemblies.

### **14.2 Construction Supervision, Testing and Commissioning**

The Seller shall make available qualified personnel to advise and assist with on-site supervision of construction and assist with testing and commissioning. The Seller's expense policy shall be outlined in the bid document. The Owner, and / or his representative and any Authorities having jurisdiction over the equipment shall witness all tests.

### **14.3 Operator Training**

If requested, the Seller shall train operators and supervisors in the operation of the supplied equipment. Such training shall include:

- Training lectures and lecture notes.
- On-the-job training during commissioning and plant operation.

The Seller will supply rates and terms for such training.

## **15. Spare Parts**

The Seller shall supply lists of recommended spare parts.

## **16. Quality Assurance**

The Seller shall prepare a quality assurance and inspection/ test plan and submit for Owner's approval. No changes to the plan will be allowed during implementation without prior consent from the Owner. Refer to Section S01 43 00 – Quality Management for the requirements of this plan.

**END OF SECTION**