



June 21, 2017

Sean Joseph  
Senior Technical Advisor, NWB  
P.O. Box 119  
Gjoa Haven, NU X0B 1J0

**RE: Milne Port Accommodations Camp Pad and Proposed Surface Water Diversion  
System (Modification Request)  
Water Licence 2AM-MRY1325 – Amend. No. 1**

On June 9, 2017, Baffinland Iron Mines Corporation (Baffinland) received an Inspector's Direction from Indigenous and Northern Affairs Canada (INAC) following an inspection conducted by INAC of the Mary River Project from May 29 to June 1, 2017. The Inspector's Direction documented a stop work order issued to Baffinland for an accommodations camp pad that had been constructed during May 2017 at Milne Port in a location that impeded the flow of an intermittent drainage path(s). On June 14, 2017 Baffinland responded to the Inspector's Direction notifying INAC and other agencies of Baffinland's planned corrective actions to remedy the situation and intention to submit proper documentation, as required by Part D, Item 2 and Part G of Baffinland's Type "A" Water Licence 2AM-MRY1325 Amendment 1 (Type "A" Water Licence), to the Nunavut Water Board (NWB) by June 16, 2017.

In accordance with Part D, Item 2 and Part G of Baffinland's Type "A" Water Licence, the purpose of this letter is to submit a Request for Modification for the proposed surface water diversion system required to redirect surface water from the impeded drainage path(s) around the pad, as shown in Attachments 1 and 2.

It is Baffinland's intention to use the new accommodation camp pad to eventually upgrade the existing accommodations at Milne Port, replacing the existing soft wall camp and increasing accommodations infrastructure in order to support the increased camp populations required for full production (4.2Mt per annum). However, it should be noted that Baffinland is not requesting approval for the future accommodations upgrades in this submission. A subsequent Request for Modification will be made prior to the construction of the camp facilities.

Both the constructed accommodations camp pad and the proposed surface water diversion system are within the Project's Development Area (PDA) and are consistent with approved activities outlined in the Project Certificate (Project Certificate 005 – Amend. 1) issued for the Mary River Project by the Nunavut Impact Review Board (NIRB).

The requested modification is described below and is consistent with the requirements of Part G of the Type "A" Water License.

a. Description of Facilities and/or Works to be Constructed

Baffinland has developed a new accommodations camp pad at Milne Port. The new accommodations camp pad is approximately 280m x 120m in size. The constructed accommodations camp pad is located south of the existing Milne Port Ore Stockpile Pad and west of the Tote Road (near Km 1). The proposed surface water diversion system will follow along the pad's southern perimeter and direct flow from the impeded drainage path(s) to the natural drainages west of the accommodations camp pad, as shown in Attachments 1 and 2.

Attachment 1 shows the constructed accommodations camp pad in relation to the Milne Port general layout. As shown in Attachment 2, the sub-grade of the accommodations camp pad was constructed using Type 12 (Run of Quarry <200mm) coarse material and capped with Type 5 (<32mm crushed) crushed granular surface material. Attachment 2 also shows the proposed diversion system and design details, including the associated hydrology and hydraulic design calculations. Attachment 3 details the construction methodology for the proposed diversion system in order to minimize potential environmental effects during construction. The exact dimensions of the proposed diversion system will be field fit during construction based on field observations of the impeded drainages path(s). The completed pad and diversion system will be documented in as-built drawings for the construction.

b. Proposed Location of the Structure

The constructed accommodations pad is located south of the existing Milne Port Ore Stockpile Pad and west of the Tote Road (near Km 1). The proposed surface water diversion system will follow along the pad's southern perimeter and direct flow to the natural drainages west of the accommodations camp pad, as shown in Attachments 1 and 2.

c. Identification of any Potential Impacts to the Receiving Environment

The impeded drainage path(s) are not classified as fish habitat and therefore the proposed diversion system will not cause harmful alteration, disruption or destruction of fish habitat. The main concern Baffinland foresees is sedimentation from the construction of the proposed diversion system. To prevent the release of sediment into the receiving environment during construction, Baffinland will employ a combination of sediment and erosion control measures (check dams, rip-rap, silt fences, etc.) to address sedimentation concerns, as outlined in Baffinland's Environmental Protection Plan (BAF-PH1-830-P16-0008 – Rev. 1) and Surface Water and Aquatic Ecosystems Management Plan (BAF-PH1-830-P16-0026 - Rev. 4).

d. Monitoring

During construction, daily environmental monitoring will be performed including before, during and after photographs of construction activities. Surface water runoff will be managed as outlined in Baffinland's Surface Water and Aquatic Ecosystems Management Plan (BAF-PH1-830-P16-0026 - Rev. 4). Baffinland will conduct daily water quality monitoring of surface water drainage originating from the construction area. Water quality impacts of construction activities on nearby water bodies will be assessed using water quality discharge criteria established under Baffinland's Type "A" Water Licence. Additional monitoring stations may be established, if required.

e. Schedule for Construction

Construction of the accommodations camp pad was completed in May 2017. Construction of the proposed surface water diversion system is planned to start as soon as the Request for Modification approval has been received from the NWB.

f. Drawings of Engineered Structures

Hatch Ltd. (Hatch) was retained to design and provide issued-for-construction drawings for the constructed accommodations camp pad and proposed surface water diversion system. The issued-for-construction (IFC) drawings are provided in Attachment 2 of this letter.

g. Proposed Sediment and Erosion Control Measures

Baffinland will employ a combination of sediment and erosion control measures (check dams, rip-rap, silt fences, etc.), as outlined in Baffinland's Environmental Protection Plan (BAF-PH1-830-P16-0008 – Rev. 1) and Surface Water and Aquatic Ecosystems Management Plan (BAF-PH1-

830-P16-0026 - Rev. 4), to address and manage sedimentation concerns during construction. No sediment or erosion control measures are expected to be required once construction of the diversion system has been completed.

We trust that this information meets the requirements under Part D, Item 2 and Part G under Baffinland's Type "A" Water Licence and look forward to the NWB's response. Please do not hesitate to contact the undersigned or Andrew Vermeer should you have any questions or comments.

Regards,



Wayne McPhee,  
Director Sustainable Development

Attachments:

Attachment 1: Milne Port – New Camp Pad

Attachment 2: Milne Port – Camp Pad Natural Stream Diversion – Hydrology & Hydraulic Calculations  
(includes engineering/design drawings)

Attachment 3: Construction Methodology – Camp Pad Water Diversion System

cc. Matt Weaver, Laura Taylor, Andrew Vermeer, William Bowden, Todd Burlingame, Sylvain Proulx  
(Baffinland)  
Manager of Licensing, David Hohnstein (NWB)  
Justin Hack, Jonathan Mesher (INAC)  
Stephen Williamson Bathory (Qikiqtani Inuit Association)

**Attachment 1**

**Milne Port – New Camp Pad**



## **Attachment 2**

**Milne Port – Camp Pad Natural Stream Diversion – Hydrology & Hydraulic Calculations  
(includes Engineering/Design Drawings)**

Project Memo

H-353004

21 June 2017

To: Matt Weaver

From: A Grobbelaar

cc: Tyler Bruce

## Baffinland Iron Mines LP Mary River Project



### Milne Port - Camp Pad Natural Stream Diversion- Hydrology & Hydraulic Calculations

#### 1. Introduction

The accommodation camp pad intersects a minor seasonal stream. In order to maintain continuation of the stream, it has to be diverted around the camp pad. (See below camp pad location and streams identified)




Figure 1: Accommodation Camp Pad Diversion


If you disagree with any information contained herein, please advise immediately.

H353004-2100-240-030-001, Rev. 0

Page 1



The catchment area for the seasonal stream is depicted below:



**Figure 2: Seasonal Stream Catchment**

A suitable sized culvert under the existing quarry access road will have to be installed in order to reduce the catchment size for the seasonal stream to 0.25km<sup>2</sup>. Details, including elevations near the quarry access road, will need to be confirmed by onsite survey prior to finalizing culvert design and associated geotechnical engineering.

## 1.1 Design Calculations

### 1.1.1 *Diversion Channel Catchment Runoff Calculation*

In order to design the stream diversion, the expected storm water flow needs to be calculated (For the diversion design, Hatch used a 1:100 year return period storm in line with the previously approved design philosophy for external streams & stream diversions).

Rainfall intensities were obtained from a previous phase approved report by Hatch titled "Civil Design Criteria" – H-349000-1000-10-122-001 (Rev 1). In the report reference is made to the Knight Piesold calculated rainfall intensities for various return periods – See table 1-1 below:

**Table 1-1: Rainfall Intensities for Various Return Periods**

Duration	2 yrs	5 yrs	10 yrs	15 yrs	20 yrs	25 yrs	50 yrs	100 yrs	200 yrs
5 min	9.5	12.0	14.0	15.1	15.9	16.5	18.3	20.1	22.0
10 min	7.2	9.0	10.5	11.3	11.9	12.4	13.7	15.1	16.5
15 min	6.0	7.5	8.7	9.4	9.9	10.3	11.4	12.6	13.7
30 min	5.0	6.3	7.3	7.9	8.3	8.6	9.5	10.5	11.4
1 hr	4.0	5.2	6.1	6.6	7.0	7.3	8.1	9.0	9.9
2 hr	3.0	3.9	4.6	5.0	5.2	5.5	6.1	6.8	7.4
6 hr	2.0	2.7	3.3	3.6	3.9	4.0	4.6	5.1	5.7
12 hr	1.3	1.8	2.2	2.4	2.6	2.7	3.1	3.4	3.8
24 hr	1.0	1.4	1.7	1.9	2.0	2.1	2.4	2.7	3.0

The catchment area is 0.25km<sup>2</sup>.

The Table 1-2 below indicates the calculation to determine the peak runoff from the 1:100 storm event:

**Table 1-2: Peak Flow Calculation**

$Q = 0.28 C I A$		$T_c = 0.06628(L^{0.77}/S^{0.385})$		Unit	
Q= 0.78	m <sup>3</sup> /s	Tc= 0.25		hr	15.1 min
C= 0.9		L= 1.177		km	
I= 12.6	mm/hr	S= 0.04317		m/m	
A= 0.25	km <sup>2</sup>				

The diversion channel was sized based on a peak catchment flow of **0.78m<sup>3</sup>/s** for the 1:100year return period storm.

## 1.1.2 Diversion Channel Hydraulic Calculation

Based on the previous phase approved report by Hatch titled "Civil Design Criteria" – H-349000-1000-10-122-001 (Rev 1), the channel properties were compiled. The side slopes of 2H:1V was used together with the rip rap and the Manning flow friction factor (n) value of 0.04 applied. Using the Flow Master software by Bentley Systems Inc, the flow depth was determined using the natural ground level slope along the accommodations camp pad. A minimum slope of 1:500 was applied where the natural ground was flatter.

Hatch Drawings No H353004-4000-228-272-0001-0001 & H353004-4000-228-271-0001-0001 indicates the layout of the diversion channel and longitudinal profile respectively (see attached).

The seasonal minor stream is re-directed into the diversion channel through a long radius intercept channel, transitioning from the natural stream shape into the trapezoidal channel. This detail is apparent in the drawings referenced above. Some dimensional data will have to be determined on site and adjusted after consultation with the Engineer.

At the south east corner of the pad where the diversion channel turns through 90 degrees, the channel was sized and detailed to contain the specific energy calculated for the stream flow, thus ensuring that no spillage will occur during the storm event.

A general freeboard of 300 mm was applied throughout the channel design.

At the discharge end of the channel, a hydraulic flow dispersion structure is detailed to allow the energy of the  $0.78^3/s$  flow to dissipate and not cause any erosion damage. The actual invert level of the natural water body that the diversion channel will drain into shall be confirmed on site and conveyed to the Engineer. This invert level cannot be above the diversion channel invert so as not to allow any capacity reduction of the channel. The Engineer must be consulted in the event that the invert of the natural water body is higher than the diversion channel to allow for adjustment in the details to be constructed.

In order to obtain the flow properties for the channel at various sections (change in gradient) the software by DEVOTECH was used. The EPA storm water management model - version 5.1 (build 5.1.006) calculates the flow properties at set sections and generates the long sections data as reflected on the drawing.



A Grobbelaar

AG:AG

Attachment(s)/Enclosure:

- Diversion Channel hydraulic calculation – Attachment 1
- Diversion Channel steady uniform flow calculation- Attachment 2
- H353004-4000-228-272-0001-0001- Attachment 3
- H353004-4000-228-271-0001-0001- Attachment 4

# Attachment 1:

## Diversion Channel Hydraulic Calculation

### Project Description

Friction Method                      Manning Formula  
Solve For                                Bottom Width

### Input Data

Roughness Coefficient	0.040
Channel Slope	0.20 %
Normal Depth	0.40 m
Left Side Slope	2.00 m/m (H:V)
Right Side Slope	2.00 m/m (H:V)
Discharge	0.78 m³/s

### Results

Bottom Width	2.95 m
Flow Area	1.50 m²
Wetted Perimeter	4.74 m
Hydraulic Radius	0.32 m
Top Width	4.55 m
Critical Depth	0.18 m
Critical Slope	0.02947 m/m
Velocity	0.52 m/s
Velocity Head	0.01 m
Specific Energy	0.41 m
Froude Number	0.29
Flow Type	Subcritical

## Attachment 2: Diversion Channel Steady Uniform Flow Calculation

PA STORM WATER MANAGEMENT MODEL - VERSION 5.1 (Build 5.1.006)

About: File generated by iDAS (www.devotech.co.za)

\*\*\*\*\*  
NOTE: The summary statistics displayed in this report are based on results found at every computational time step, not just on results from each reporting time step.  
\*\*\*\*\*

### \*\*\*\*\* Analysis Options \*\*\*\*\*

Flow Units ..... CMS  
Process Models:  
Rainfall/Runoff ..... NO  
RDII ..... NO  
Snowmelt ..... NO  
Groundwater ..... NO  
Flow Routing ..... YES  
Ponding Allowed ..... NO  
Water Quality ..... NO  
Flow Routing Method ..... STEADY  
Starting Date ..... JUN-08-2017 00:00:00  
Ending Date ..... JUN-09-2017 00:00:00  
Antecedent Dry Days ..... 0.0  
Report Time Step ..... 00:01:00  
Routing Time Step ..... 10.00 sec

*****	Volume	Volume
Flow Routing Continuity	hectare-m	10^6 ltr
*****	-----	-----
Dry Weather Inflow .....	0.000	0.000
Wet Weather Inflow .....	0.000	0.000
Groundwater Inflow .....	0.000	0.000
RDII Inflow .....	0.000	0.000
External Inflow .....	6.739	67.389
External Outflow .....	6.739	67.389
Internal Outflow .....	0.000	0.000
Evaporation Loss .....	0.000	0.000
Seepage Loss .....	0.000	0.000
Initial Stored Volume ....	0.000	0.000
Final Stored Volume .....	0.000	0.000
Continuity Error (%) .....	0.000	

### \*\*\*\*\* Highest Flow Instability Indexes \*\*\*\*\*

All links are stable.

### \*\*\*\*\* Routing Time Step Summary \*\*\*\*\*

Minimum Time Step : 10.00 sec  
Average Time Step : 10.00 sec  
Maximum Time Step : 10.00 sec  
Percent in Steady State : 0.00  
Average Iterations per Step : 1.00  
Percent Not Converging : 0.00

\*\*\*\*\*

## Node Depth Summary

\*\*\*\*\*

Node	Type	Average Depth	Maximum Depth	Maximum HGL	Time of Max Occurrence
		Meters	Meters	Meters	days hr:min
CN1	JUNCTION	0.40	0.40	13.68	0 00:00
CN4	JUNCTION	0.40	0.40	13.62	0 00:00
CN5	JUNCTION	0.39	0.39	13.06	0 00:00
CN6	JUNCTION	0.39	0.39	12.91	0 00:00
CN7	JUNCTION	0.20	0.20	11.76	0 00:00
CN8	JUNCTION	0.19	0.19	11.43	0 00:00
CN9	JUNCTION	0.31	0.31	10.94	0 00:00
CN10	JUNCTION	0.40	0.40	10.85	0 00:00
CN11	JUNCTION	0.40	0.40	10.78	0 00:00
CN12	JUNCTION	0.52	0.52	10.82	0 00:00
CN13	JUNCTION	0.52	0.52	10.82	0 00:00
CN14	JUNCTION	0.40	0.40	10.64	0 00:00
CN15	JUNCTION	0.40	0.40	10.63	0 00:00
MH70	OUTFALL	0.39	0.39	10.62	0 00:00

\*\*\*\*\*

## Node Inflow Summary

\*\*\*\*\*

Node	Type	Maximum		Time of Max Occurrence	Lateral Inflow Volume	Total Inflow Volume	Flow	
		Lateral Inflow	Total Inflow				Balance	Error
		CMS	CMS		10^6 ltr	10^6 ltr	Percent	
CN1	JUNCTION	0.780	0.780	0 00:00	67.4	67.4	0.000	
CN4	JUNCTION	0.000	0.780	0 00:00	0	67.4	0.000	
CN5	JUNCTION	0.000	0.780	0 00:00	0	67.4	0.000	
CN6	JUNCTION	0.000	0.780	0 00:00	0	67.4	0.000	
CN7	JUNCTION	0.000	0.780	0 00:00	0	67.4	0.000	
CN8	JUNCTION	0.000	0.780	0 00:00	0	67.4	0.000	
CN9	JUNCTION	0.000	0.780	0 00:00	0	67.4	0.000	
CN10	JUNCTION	0.000	0.780	0 00:00	0	67.4	0.000	
CN11	JUNCTION	0.000	0.780	0 00:00	0	67.4	0.000	
CN12	JUNCTION	0.000	0.780	0 00:00	0	67.4	0.000	
CN13	JUNCTION	0.000	0.780	0 00:00	0	67.4	0.000	
CN14	JUNCTION	0.000	0.780	0 00:00	0	67.4	0.000	
CN15	JUNCTION	0.000	0.780	0 00:00	0	67.4	0.000	
MH70	OUTFALL	0.000	0.780	0 00:00	0	67.4	0.000	

\*\*\*\*\*

## Node Surge Summary

\*\*\*\*\*

No nodes were surcharged.

\*\*\*\*\*

## Node Flooding Summary

\*\*\*\*\*

No nodes were flooded.

\*\*\*\*\*

## Outfall Loading Summary

\*\*\*\*\*

Flow Freq	Avg Flow	Max Flow	Total Volume
--------------	-------------	-------------	-----------------



Outfall Node	Pcnt	CMS	CMS	10^6 ltr
MH70	100.00	0.780	0.780	67.389
System	100.00	0.780	0.780	67.389

\*\*\*\*\*

## Link Flow Summary

\*\*\*\*\*

Link	Type	Maximum [Flow]	Time of Max Occurrence CMS days hr:min	Maximum [Veloc] m/sec	Maximum Full Flow	Max/ Full Depth
CH21	CONDUIT	0.780	0 00:00	0.37	0.57	0.74
CH24	CONDUIT	0.780	0 00:00	0.52	0.35	0.56
CH1	CONDUIT	0.780	0 00:00	0.51	0.36	0.57
CH17	CONDUIT	0.780	0 00:00	1.24	0.10	0.27
CH11	CONDUIT	0.780	0 00:00	1.20	0.10	0.27
CH8	CONDUIT	0.780	0 00:00	1.35	0.08	0.25
CH9	CONDUIT	0.780	0 00:00	0.52	0.35	0.56
CH10	CONDUIT	0.780	0 00:00	1.17	0.11	0.28
CH18	CONDUIT	0.780	0 00:00	0.68	0.24	0.45
CH19	CONDUIT	0.780	0 00:00	0.52	0.36	0.57
CH20	CONDUIT	0.780	0 00:00	0.52	0.36	0.57
CH22	CONDUIT	0.780	0 00:00	0.52	0.35	0.56
CH23	CONDUIT	0.780	0 00:00	0.51	0.36	0.57

\*\*\*\*\*

## Conduit Surge Summary

\*\*\*\*\*

No conduits were surcharged.


Analysis begun on: Tue Jun 20 16:00:38 2017

Analysis ended on: Tue Jun 20 16:00:38 2017

Total elapsed time: < 1 sec

## **Attachment 3**





THIS DRAWING

KEY PLAN

NTS

ACCOMMODATION CAMP PAD COORDINATES		
POINT	EASTING	NORTHING
T1	503408.977	7975209.046
T4	503326.171	7975279.119
T5	503373.873	7975264.133
T6	503423.018	7975187.011
T7	503356.128	7974974.084
T8	503337.047	7974980.078
T9	503241.644	7975010.049

FOR CONSTRUCTION

NOTES:

- LIDAR SURVEY PROVIDED BY PHOTOSAT (2016)
- COORDINATE GRID IS SHOWN IN UTM (NAD83) ZONE 17 AND IS IN METERS.
- ALL DIMENSIONS ARE IN METERS
- CONTOURS ARE IN METERS. CONTOUR INTERVAL IS 2m.
- MODIFY EXISTING CULVERT OR CONSTRUCT A NEW CULVERT AT THE QUARRY ROAD TO ENSURE POSITIVE DRAINAGE (FLOW FROM SOUTH TO NORTH) THROUGH CULVERT.

LEGEND:

- MINOR SEASONAL STREAMS
- WATER BODY
- CATCHMENT AREA
- LIDAR GROUND CONTOUR
- FLOW DIRECTION

0 50 100 150 200 250  
SCALE IN METERS

LAYOUT  
SCALE 1:5000

THIS DRAWING WAS PREPARED FOR THE EXCLUSIVE USE OF [NAME OF CLIENT] ("CLIENT") AND IS ISSUED PURSUANT TO THE RELEVANT AGREEMENT BETWEEN CLIENT AND HATCH LTD ("HATCH"). UNLESS OTHERWISE AGREED IN WRITING WITH CLIENT OR SPECIFIED ON THIS DRAWING, HATCH DOES NOT ACCEPT AND ISSUES ANY AND ALL LIABILITY OR RESPONSIBILITY ARISING FROM ANY USE OF OR RELIANCE ON THIS DRAWING BY ANY THIRD PARTY OR ANY MODIFICATION OR MISUSE OF THIS DRAWING BY CLIENT, AND ITS THIS DRAWING IS CONFIDENTIAL AND ALL INTELLECTUAL PROPERTY RIGHTS EMBODIED OR REFERENCED IN THIS DRAWING REMAIN THE PROPERTY OF HATCH.

**HATCH**

DRAFTSPERSON	F HUGO	NR	20/06/2017
DESIGNER	F HUGO	NR	20/06/2017
CHECKER	S HALL		20/06/2017
DESIGN COORD	R GOOSEN		20/06/2017
RESP. ENG.	A GROBBELAAR		20/06/2017
LEAD DISC. ENG.	A GROBBELAAR		20/06/2017
AREA MANAGER	T BRUCE		20/06/2017
PROJ. MANAGER	S HEINER		20/06/2017

**Baffinland**

BAFFINLAND IRON MINES LP  
MARY RIVER PROJECT

MILNE PORT  
CAMP PAD NATURAL STREAM DIVERSION  
LAYOUT

0	APPROVED FOR CONSTRUCTION	FH	SRH	20/06/2017	CLIENT	ROLE	NAME	SIGNATURE	DATE	SCALE 1:5,000 OR AS NOTED	DWG. No. H353004-40000-228-272-0001-0001	REV 0
---	---------------------------	----	-----	------------	--------	------	------	-----------	------	---------------------------------	---	----------

1	2	3	4	5	6	7	8	
REFERENCE DRAWINGS		REG. PROFESSIONAL	REVISIONS		DRAWING APPROVAL STATUS: Approved for Construction			SHEET SIZE: D

## **Attachment 4**







**Attachment 3**

**Construction Methodology – Camp Pad Water Diversion System**

**(H353004-40000-400-050-0001)**

## Plan

# Construction Methodology - Camp Pad Water Diversion System

						
2017-06-16	0	Approved for Use	T Bruce	L Langlois	S Heiner	M Weaver
DATE	REV.	STATUS	PREPARED BY	CHECKED BY	APPROVED BY	APPROVED BY
						Employer

## 1. Overview

A diversion channel is required to divert a seasonal stream that runs through the accommodations camp pad at Milne Port that was constructed in May 2017. The seasonal stream flows briefly in the spring freshet and during significant rain events. Due to the timing and criticality of this diversion, a sequential plan must be in place and followed to ensure impacts to the downstream receiving environment are minimized.

## 2. Design

The diversion which has been designed to pick up the flows, divert and discharge into the natural drainages west of the constructed accommodations camp pad, run along the southern perimeter of the pad and has a cut throughout several hundred meters which reaches a depth of 1.0 meters at its deepest. This cut must be performed in to maintain flow while eliminating any ponding water.

## 3. Construction Methodology

The accommodation camp pad has previously been constructed and remains in place. Although flows for the remainder of this year will only occur during any significant rain events, the diversion must be fully constructed as soon as possible in the event flows do occur.

The diversion shall be constructed starting at the downstream end and progressing to the upstream to eliminate the possibility of encountering flows during construction. The sequence of construction shall be as follows:

1. Create a sump upstream of the diversion consisting of an excavated hole armored with rip rap to prevent erosion.
2. Setup of a pump with an intake in the sump and discharge hose running to a determined discharge location that flows to the natural drainages west of the pad.
3. Install a dam which does not allow water to travel downstream of the sump to the proposed construction area and downstream drainages. It should be noted that above pumping setup will only be used if flows are encountered during construction.
4. Complete all excavation for the full alignment of the diversion. Note that frozen conditions will be encountered in areas of cut deeper than 300 mm. To achieve the cuts an iterative process will be taken involving cutting to maximum depth allowed by local frozen conditions, allowing the frozen ground to thaw over 5-7 days and then revisiting the area until design depths have been achieved.
5. Place geotextile and rip rap on all areas of new diversion system to mitigate erosion and scouring from flow.



6. Upon completion of all ditching and placement of geotextile and rip rap, the diversion system will be complete and the upstream sump, dam and pumping setup will be removed to allow for flow through the diversion system.