

Design Report of Mammoth Dike

Detailed Engineering of Water Management and Geotechnical Infrastructures

Agnico Eagle Mines Limited - Meadowbank Division



Mining & Metallurgy

22 | 10 | 2018

Report > Client ref. AEM # 6118-E-132-002-TCR-015 > Original > Rev. 01
Internal ref. 651298-5000-40ER-0001

Quebec, October 22, 2018

Mr. Frédérick Bolduc
Mr. Alexandre Lavallée
Agnico Eagle Mines Limited
Meadowbank Division
Baker Lake, Nunavut, Canada
X0C 0A0

Subject: Design Report of Mammoth Dike
Detailed Engineering of Water Management and Geotechnical Infrastructures
AEM File AEM # 6118-E-132-002-TCR-015
SNC File: 651298-5000-40ER-0001_01

Dear Sirs,

We are pleased to submit the final version of the report on the detailed design of Mammoth Dike, which is one of the key components of the water management infrastructures required during open pit mining of the Whale Tail deposit.

Do not hesitate to communicate with the undersigned should you have further questions regarding the content of this report.

Truly yours,

SNC LAVALIN INC.

Yohan Jalbert, Eng.
Project Manager
Mining and Metallurgy

YJ/ml



List of Revisions

Revision				Revised pages	Remarks
#	Prep.	App.	Date		
PA	M. D.-J.		2018-08-07		Issued for internal review
PB	M. D.-J. / G. H.	YJ	2018-09-17	All	Issued for AEM review
00	M.D.J/G.H	YJ	2018-10-16	All	Issued for use
01	G.H	YJ	2018-10-22	All	Appendices excluded

Notice to Reader

This document contains the expression of the professional opinion of SNC-Lavalin Inc. (“SNC-Lavalin”) as to the matters set out herein, using its professional judgment and reasonable care. It is to be read in the context of the agreement dated October 4th, 2017 (the “Agreement”) between SNC-Lavalin and Agnico Eagle Mines (the “Client”) and the methodology, procedures and techniques used, SNC-Lavalin’s assumptions, and the circumstances and constraints under which its mandate was performed. This document is written solely for the purpose stated in the Agreement, and for the sole and exclusive benefit of the Client, whose remedies are limited to those set out in the Agreement. This document is meant to be read as a whole, and sections or parts thereof should thus not be read or relied upon out of context.

SNC-Lavalin has, in preparing estimates, as the case may be, followed accepted methodology and procedures, and exercised due care consistent with the intended level of accuracy, using its professional judgment and reasonable care, and is thus of the opinion that there is a high probability that actual values will be consistent with the estimate(s). Unless expressly stated otherwise, assumptions, data and information supplied by, or gathered from other sources (including the Client, other consultants, testing laboratories and equipment suppliers, etc.) upon which SNC-Lavalin’s opinion as set out herein are based have not been verified by SNC-Lavalin; SNC-Lavalin makes no representation as to its accuracy and disclaims all liability with respect thereto.

To the extent permitted by law, SNC-Lavalin disclaims any liability to the Client and to third parties in respect of the publication, reference, quoting, or distribution of this report or any of its contents to and reliance thereon by any third party.

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report

Table of Content

	Page
1.0 INTRODUCTION.....	4
1.1 Context	4
1.2 Structure of the Report.....	6
2.0 GUIDELINES AND STANDARDS.....	6
3.0 AVAILABLE GEOTECHNICAL INFORMATION	6
4.0 MAMMOTH DIKE DESIGN BASIS AND CRITERIA.....	7
4.1 Design Basis	7
4.2 Dam Classification and Safety Criteria	8
4.3 Mammoth Dike Operational Criteria.....	9
5.0 HYDROLOGY	9
5.1 Available Data	9
5.1.1 Hydrometeorological Data.....	9
5.1.2 Hydrometric Data.....	9
6.0 MAMMOTH DIKE DESIGN OUTLINE	10
6.1 Design Flood Level	10
6.2 Seepage Performance	10
6.3 Stability Performance	10
6.4 Dike Composition	11
7.0 ENVIRONMENTAL CONCERNS.....	11
8.0 CONSTRUCTION	11
9.0 INSTRUMENTATION AND MONITORING PLAN	12
10.0 ESTIMATED QUANTITIES	12
11.0 CLOSURE	12
12.0 CONCLUSIONS	13
13.0 PERSONNEL	14
14.0 REFERENCES.....	15

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report

List of Tables

Table 4-1: Dam Classification Criteria for the Mammoth Dike.....	8
Table 4-2: Design Criteria for the Mammoth Dike	9
Table 6-1: Results of Stability Analyses.....	10
Table 10-1: Quantity estimation for the construction of Mammoth Dike	12

List of Figures

Figure 1-1: Whale Tail Pit locations	4
Figure 1-2: Mammoth Dike.....	5
Figure 3-1: Locations of geotechnical and air track holes and thermistor station at Mammoth Dike	7

List of Appendices

- Appendix A: Mammoth Dike Technical Specifications
- Appendix B: Thermal Analyses of Mammoth Dike
- Appendix C: Stability Analyses of Mammoth Dike

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report

1.0 INTRODUCTION

1.1 Context

Agnico Eagle Mines Limited, Meadowbank Division (“Agnico Eagle”) is developing the Whale Tail Pit, a satellite deposit on the Whale Tail property, as a continuation of current mine operations and milling at the Meadowbank Mine. The Whale Tail property is a 408 km² site located on Inuit Owned Land, approximately 150 km north of the Hamlet of Baker Lake and approximately 50 km northwest of the Meadowbank Mine in the Kivalliq region of Nunavut (Figure 1-1). The property was acquired by Agnico Eagle in April 2013.





Figure 1-1: Whale Tail Pit locations

The Meadowbank Mine is an approved mining operation and Agnico Eagle will extend the life of the mine by constructing and operating the Whale Tail Pit. Mammoth Dike is designed to prevent flooding of the Whale Tail Pit in the event that the Mammoth lake level rises. The dike, discussed in the sections to follow, is a structure which will be dismantled or breached at the end of ore extraction from the Whale Tail Pit and once the closure conditions satisfied and monitoring completed.

This report presents the detailed design of Mammoth Dike in accordance with Type A Water Licence 2AM-WTP1826.

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report



PROJECT COMPONENTS (PHASE I)

Dike or cofferdam

Modified waterbody

Collection ditch

Diversion ditch

Open pit

Storage facility

Industrial area

Road

HYDROGRAPHY

Watercourse

Lake

Modified watershed

AMARUQ GOLD MINING PROJECT

Detailed Engineering of Water Management and Geotechnical Infrastructure

Mine Layout Watersheds – Phase 1

Sources:
Topography, PhotoSat, 2015
Project components : March 2018

Project: 651298
File: snc651298_004_fx_Mammoth_181016.mxd

0200400

1:20 000

UTM projection, Zone 14, NAD83 (CSRS)

October 16, 2018

Figure 1-2

S:\INTC\MineAmaruq\651298 Detailed Eng WM-Geotech\product\004-MammothDike\snc651298_004_fx_Mammoth_181016.mxd

1.2 Structure of the Report

This report presents all of the available site specific geotechnical and topographic information, together with our interpretation of the factual data and the results of the thermal and stability analyses carried out for Mammoth Dike. For the design of Mammoth Dike, SNC-Lavalin has drawn on its experience and lessons learned during the detailed engineering of the Whale Tail Dike (WTD) which included a more detailed geotechnical investigation and stability, seepage, thaw settlement, thermal and stress analyses.

For completeness in presentation, the report includes the technical specifications for Mammoth Dike (SNC-Lavalin, 2018f) in Appendix A, together with the construction drawings. Therefore, when a drawing is mentioned in the report, the reader shall consult the technical specifications.

2.0 GUIDELINES AND STANDARDS

The design of Mammoth Dike has used the latest Dam Safety Guidelines produced by the Canadian Dam Association (CDA) with respect to dam classification and the American Society for Testing and Materials (ASTM) for the geotechnical components of the work. The Technical Specifications included in Appendix A (SNC-Lavalin, 2018f), provide a list of the ASTM and other construction material standards relevant to the Mammoth Dike, and hence are not repeated herein.

3.0 AVAILABLE GEOTECHNICAL INFORMATION

The subsurface condition of the Mammoth Dike foundation described next is based on three geotechnical boreholes close to the axis of either the dike or the key trench on the upstream side as shown on Drawing 651298-5000-4GEF-0003, carried out in spring 2018 (Series AMQMD-01). However, the bedrock profile shown in the longitudinal section of the dike is based on a large number of mine boreholes drilled within the footprint of the dike. The overburden consists of a surficial layer of gravel, cobbles and boulders underlain by glacial till followed by bedrock. The above drawing also shows five (5) destructives boreholes with the Tamrock drill rig put down in fall 2017 on the upstream side of the dike (Series L1611) to have an order of magnitude of the overburden thickness. The thicknesses of the upper gravel cobbles and-boulder layer, the glacial till and the overall overburden vary in rounded figures from/to: 0.8/2.7 m, 1.1/1.70 m and 2.0/3.9 m respectively.

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report




Figure 3-1: Locations of geotechnical and air track holes and thermistor station at Mammoth Dike

4.0 MAMMOTH DIKE DESIGN BASIS AND CRITERIA

4.1 Design Basis

The following elements were considered during the design of the Mammoth Dike:

- > The dike will be constructed in 2018 or early 2019;
- > The dike will be dismantled or breached at closure;
- > The dike will be constructed with rock fill incorporating a seepage barrier on its upstream slope;
- > The seepage barrier consists of a sheet of bituminous geomembrane (BGM) on the upstream slope anchored at the toe in a layer of Fine Filter Amended with Bentonite (FFAB).
- > Based on the available geotechnical information, the dike will be founded mainly on the surficial overburden composed of gravel, cobbles and boulders. For the installation of the FFAB component of the seepage barrier along the upstream toe of the dike, a key trench will be excavated in the overburden until the bottom reaches glacial till or bedrock.

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report

- › The hydrologic/hydraulic and seismic design criteria are provided in Section 4.2;
- › Mammoth Dike has sufficient width to be used for a one way traffic by a 150-Ton¹ trucks, however if required the width can be enlarged in the downstream direction to accommodate a two-way traffic by such vehicles.

4.2 Dam Classification and Safety Criteria

Table 4-1 provides the classification of Mammoth Dike in terms of consequence of failure, based on the system proposed by the Canadian Dam Association (CDA, 2007/13) as determined in (SNC-Lavalin, 2018d). It is seen that Mammoth Dike falls into a 'High' consequence class.

For the 'High' consequence class the minimum design flood and seismic loading are as follows:

1. Table 4-2 provides the in-flow design flood criterion as well as the resulting flood level and minimum dike crest elevation;
2. For the seismic stability, the required minimum annual exceedance probability (APE) of the earthquake is 1/2475.

Table 4-1: Dam Classification Criteria for the Mammoth Dike

Risk Type	Dam Class	Commentaries	Reference
Population	High	Workers in the mine pit downstream of the dike are considered as permanent population of at risk of 10 or fewer loss of lives.	Dam Safety Guidelines (CDA, 2007, rev 2013)
Economy	Low	No infrastructure downstream of the dike	Dam Safety Guidelines (CDA, 2007, rev 2013)
Environment	Significant	No significant loss or deterioration of fish or wildlife habitat Loss of marginal habitat only Restoration or compensation in kind highly possible	Dam Safety Guidelines (CDA, 2007, rev 2013)
Summary: High			

¹ Nominal payload in imperial (US) units

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report

Table 4-2: Design Criteria for the Mammoth Dike

Use	Water Type	Classification (CDA, 2007/13)	Inflow Design Flood	Water Level (m)		Crest Elevation (m)
				Normal	Design Flood	
Runoff storage	natural runoff	High	1/3 (1,000-PMF)	Low or no water	153.5	155.0

Mammoth dike will be inspected routinely for seepage on the downstream side as well as for differential movements especially during the thawing season. In addition, the thermistor strings that will be installed in the dike embankment.

5.0 HYDROLOGY

5.1 Available Data

Available hydrometeorological and hydrometric data are:

- › Hydrometeorological data from Environment and Climate Change Canada, Baker Lake A station, located approximately 124 km southeast of the Whale Tail pit, and covering the period from 1946 to 2017. These data include total precipitation, rainfall, snowfall and snow on ground;
- › Water level and streamflow measurements carried out at different locations on watersheds near the project site during June to September of years 2015 and 2016 (Golder Associates Ltd, 2017);
- › Flow measurements were made in streams. However, the stream beds were covered with boulders, making the data less reliable.

5.1.1 Hydrometeorological Data

Data from Baker Lake A meteorological station is available for the period 1946-October 2017. However, Years 1946-1949, 1973, 1993, and 2015 have several missing records and consequently were excluded from the data set used for the analyses. The missing data from other years (1950-1972, 1974-1992, and 1994-2014) were filled using the average values from available years for the same day and month. The resulting rainfall, snowfall, daily and total precipitation data series cover 66 full years over the period 1950-2017 (1973 and 1993 data not used). The average annual precipitation, over the period 1950-2017, is 250 mm including, 145 mm of rainfall and 105 mm (water equivalent) of snow. This data is assumed to be representative of the conditions at the Whale Tail Pit.

5.1.2 Hydrometric Data

The Whale Tail Pit is located on a watershed with an extensive network of lakes and interconnecting streams, with a lake to land ratio of approximately 20%. During two summers, in 2015 and 2016, several discharge and water level measurements were made by (Golder Associates Ltd, 2017) both manually and with automated hydrometric stations. One of the automated stations was located at Whale Tail Lake outlet.

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report

6.0 MAMMOTH DIKE DESIGN OUTLINE

6.1 Design Flood Level

Mammoth Dike is designed to last the life of the Whale Tail Pit and the transition to the closure, after which it will be dismantled or breached. The dike is required to prevent flooding of the mine pit up to the design flood elevation 153.5 m as indicated in Table 4-2.

6.2 Seepage Performance

Seepage analyses have not been carried out for the following reasons:

- › The thermal analyses (see Appendix B) have shown that the FFAB component of the seepage barrier is expected to stay in the frozen state;
- › Most of the year, the upstream side of the dike will stay almost dry;
- › The seepage barrier will be instrumented with thermistor strings to monitor the thermal regime of the FFAB layer and along the bituminous geomembrane. The frozen state of the FFAB will be monitored closely by frequent thermistor string readings;
- › If seepage is observed along the downstream toe of the dike, the water from Mammoth Lake will be collected by a ditch/sump system along the downstream side of the dike and pumped back to the lake or depending on the rate and quality, may be pumped to the attenuation pond prior to be treated.

6.3 Stability Performance

The stability of Mammoth Dike has been verified under static and earthquake loadings, the latter simulated by pseudo-static analyses. The results of the stability analyses which were submitted in a technical memorandum (SNC-Lavalin, 2018h) are included in Appendix C. The following Table 6-1 provides the calculated factors of safety together with the minimum required by CDA.

Table 6-1: Results of Stability Analyses

Analysis	FS obtained	FS required	Figure
Static Loading – Downstream Slope	1.58	1.50	1
Pseudo-Static Loading – Downstream Slope – 1/2500 AEP	1.52	1.20 -1.30	2
Static loading – Upstream Slope	Local: 2.6 Global: 4.73	1.50	3
Pseudo-Static Loading – 1/2500 AEPs	Local: 2.39 Global: 3.91	1.0	4

The results of the analyses show that:

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report

1. It is the downstream slope that is critical but still has factors safety in excess of the required minimum under both static and seismic loadings;
2. The difference between the static and pseudo-static FS's is negligible on account of the low seismicity of the site.

6.4 Dike Composition

Mammoth Dike will be composed of hard and non-acid generating rock, with the upstream slope to be lined with BGM embedded in the fine filter zone on the slope, and in a layer of FFAB at its toe. The fine filter is in turn separated from the rock fill by a transition zone referred to on the design drawings as coarse filter. The BGM and the FFAB layer are designed to retain water without spillage in the event that the Mammoth lake level rises up to a maximum design flood noted in Section 6.1. The gradation limits of the fine and coarse filters satisfy filter rules as noted in the Whale Tail Dike design report (SNC-Lavalin, 2018g), provided that care is taken to minimize segregation during their handling and placement.

The Technical Specifications of Mammoth Dike (SNC-Lavalin, 2018f) included in Appendix A provides the fill gradations as well as the requirements for the BGM and the sodium bentonite, which will be used to construct the FFAB.

Foundation preparation at the Mammoth Dike, will involve mainly the removal of snow, ice and boulders in the key trench area. Where bedrock is exposed at the bottom of the key trench along the FFAB alignment, it must be carefully inspected for cracks, joints and soil infills. Following the inspection, the soil infills must be cleaned and the cracks and joints treated with the appropriate sealing product to be selected during construction but before placing the FFAB.

7.0 ENVIRONMENTAL CONCERNS

During the construction of Mammoth Dike construction, excavated materials will be managed in conformity with the environmental policy of Agnico Eagle. Runoff from the construction area will be collected during construction and transferred to the Attenuation Pond for treatment.

8.0 CONSTRUCTION

The construction of Mammoth Dike is planned to start in the in fall 2018 and will be completed before the end of the winter 2019.

Careful scheduling of key trench excavation and FFAB construction is crucial to respect the above time frame as well as for the optimal performance of the dike. The rock fill zone shall be constructed ahead of key trench excavation to the extent necessary be used as a working platform and access.

The Mammoth Dike plan, profile and selected sections are shown on Drawings 651298-5000-4GDD-0004 and 651298-5000-4GDD-0005 in Appendix A.

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report

9.0 INSTRUMENTATION AND MONITORING PLAN

Mammoth Dike will be instrumented with thermistor strings in order to monitor the thermal regime of the dike and in particular the FFAB. A minimum of three (3) thermistor strings needs to be installed within the dike foundation and in the FFAB. The specific location of thermistor strings will be selected to suit conditions encountered during foundation approval.

If required, other thermistor strings could be installed vertically to monitor the thermal regime within the dike and its foundation after the commissioning of Mammoth Dike.

10.0 ESTIMATED QUANTITIES

The quantities of materials required for the construction of Mammoth Dike are presented in Table 10-1. These quantities were generated from the 3D model developed for the design based on the topographic map of the area provided by Agnico-Eagle and SNC-Lavalin's assumptions that post construction settlement of the foundation to be negligible.

Table 10-1: Quantity estimation for the construction of Mammoth Dike

ITEM	UNIT	QUANTITY (see note)
Site clearing - dike footprint	ha	1.0
Trench excavation	m ³	11,300
Rockfill (including safety berm)	m ³	23,500
Coarse filter	m ³	1,900
Fine filter	m ³	1,550
BGM	m ²	2,500
FFAB	m ³	650
Note: the material quantities tabulated above are rounded figures and include a contingency of 20% for all earthworks and 40% for the BGM.		

11.0 CLOSURE

Mammoth Dike will be dismantled or breached after the end of mining in the Whale Tail Pit.

A closure plan, not discussed in this report, has been developed to maximize the re-use of the materials removed.

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report

12.0 CONCLUSIONS

1. The design of Mammoth Dike was completed to the detailed engineering level in accordance with codes and standards used by the profession.
2. According to the CDA (2007/13), Mammoth Dike classifies as a high consequence structure. As the result it has been designed to safely store the design flood and resist the earthquake loading indicated in Section 6.1.
3. Careful scheduling is required for the construction of the FFAB due to the presence of a surficial layer of gravel, cobbles and boulders and water level at or above the natural ground surface.

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report


13.0 PERSONNEL

This report has been prepared by Mr. Getahun Haile, M.A.Sc, P.Eng, with contributions by Mr. Mathieu Durand –Jezequel, M.A.Sc., P.Eng and revised by Mr. Yohan Jalbert, P.Eng.

We trust that this report is to your satisfaction. Should you have any question, please do not hesitate on contacting me.

SNC LAVALIN INC.

Prepared by:



Getahun Haile, M.A.Sc, P. Eng.
Senior Geotechnical Specialist
Mining & Metallurgy

Verified by:

Yohan Jalbert, P. Eng.
Geotechnical Expert
Mining & Metallurgy

YJ/bsp

t:\proj\651298 detailed eng wm-geotech amaruq\40_ingénierie\40er_rapports\task 6 - MAMMOTH dike\detailed design\pb\651298-6000-40er-0001_pb MAMMOTH dike detailed design.docx

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report

14.0 REFERENCES

CDA (2007). Dam Safety Guidelines (Revised in 2013)

Golder Associates Ltd. (2017). *2016 Hydrology Baseline Report*. Report Number: Doc 088-1656381 Ver 1, January 2017.

SNC-Lavalin. (2018a). *Thermal analysis at Whale Tail Dike*. Report No. 651298-2100-4GER-0001_00, June 2018.

SNC-Lavalin. (2018b). *2018 Geotechnical Investigation*. 651298-4000-4GER-0001_PB, June 2018.

SNC-Lavalin. (2018c). *Thermal Analysis at Mammoth Dike*. 651298-5000-4GER-0001_PA, April 2018.

SNC-Lavalin. (2018d). *Design Criteria - Basins and Pumps*. 651298-8000-40EC-0001_00, April 2018.

SNC-Lavalin. (2018e). *Water Management Infrastructures*. 651298-8000-4HER-0001-PB (DRAFT to be issued), July 2018.

SNC-Lavalin. (2018f). *Technical specifications for WRSF Dike*. 651298-6000-40EF-0001_PB, July 26th 2018.

SNC-Lavalin. (2018g). *Design Report of Whale Tail Dike*. 651298-2700-4GER-0001_01, May 2018.

SNC-Lavalin (2018h). Technical Memorandum No. 65

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report

Appendix A

Technical Specifications

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report

Appendix B

Thermal Analyses of Mammoth Dike

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report

Appendix C

Stability Analyses of Mammoth Dike

Detailed Engineering of Water Management and Geotechnical Infrastructures - for Whale Tail Pit		Original -V.01
2018-10-22	AEM # 6118-E-132-002-TCR-015 SNC # 651298-5000-40ER-0001	Technical Report



5500, boulevard des Galeries, bureau 200
Québec (Québec) G2K 2E2
418-621-5500 - 418-621-8887

