

 <b>SNC • LAVALIN</b>	<b>TECHNICAL SPECIFICATION</b> Construction of the Waste Rock Storage Facility Dike	Prepared by: G. Haile Reviewed by: Y. Jalbert		
		Rev.	Date	Page
	AEM # 6118-E-132-002-SPT-003 SNC-Lavalin # 651298-6000-4GEF-0001	00	August 17, 2018	27

## APPENDIX 2

### Bituminous Geomembrane (BGM) Specifications

## PRODUCT DATA SHEET

### COLETANCHE ES 2



#### DESCRIPTION

COLETANCHE ES 2 is an SBS elastomeric modified bituminous geomembrane.

#### USE

Moderate level of mechanical resistance, for use an environmental protection and groundworks waterproofing, in particular :

- To cover landfill,
- Hydraulic ponds,
- Containment of Industrial liquid wastes,
- Canals ,
- Contaminated land.

Product use must be validated by Axter

#### APPLICATION METHOD

Torched

#### STORAGE

Rolls must not be stored directly on the ground. They must be laid supported on concrete blocks, trestles or timber beams) min 35 cm height, placed under the mandrel ends.

#### COMPOSITION

(indicative)

Reinforcement (g/m <sup>2</sup> ) :	Glass mat	50
Reinforcement (g/m <sup>2</sup> ) :	Non-woven geotextile	250
Binder (g/m <sup>2</sup> ) :	Elastomeric SBS	4300
Surface finish (g/m <sup>2</sup> ) :	Sand	200
Under surface finish (g/m <sup>2</sup> ) :	Polyester antiroot film	15

#### CHARACTERISTICS

CHARACTERISTICS					VALUES	Tolerance	
			STANDARD	UNITS		Min	Max
Dimensions	Length		-	m	79	≥	
	Width			m	5.01	≥	
Thickness (on finished product)			ASTM D 5199	mm	4.00	3.80	4.40
Surface mass			ASTM D 3776	kg/m²	4.85	4.50	5.20
Resistance to tearing	Longitudinal		ASTM D 4073	N	825	619	
	Cross direction				700	525	
Tensile properties : maximum tensile strength	Longitudinal		ASTM D 7275	kN/m	27	20.3	
	Cross direction				24	18	
Tensile properties : elongation	Longitudinal			%	60	48	
	Cross direction				60	48	
Tensile properties : maximum tensile strength	Longitudinal		ASTM D 4595	kN/m	25	19	
	Cross direction				21	16	
Tensile properties : elongation	Longitudinal			%	80	60	
	Cross direction				80	60	
Static Puncture			ASTM D 4833	N	530	477	
Flexibility at low temperature	Surface		ASTM D 5147	°C	-20		
	Under surface				-20		
Water permeability (liquid tightness)			ASTM E 96	m/s	6.10 <sup>-14</sup>		
Gas permeability (gas tightness)			ASTM D 1434-82	m3/(m².j.atm)	< 2.3.10 <sup>-14</sup>		

NOTE: AXTER COLETANCHE INC. may modify the composition and/or utilisation of its products without prior notice. Consequently orders will be filled according to the latest specification.

The manufacturer reserves the right to modify, at any time, the characteristics of its products.



 <b>SNC • LAVALIN</b>	<b>TECHNICAL SPECIFICATION</b> Construction of the Waste Rock Storage Facility Dike	Prepared by: G. Haile Reviewed by: Y. Jalbert		
		Rev.	Date	Page
	AEM # 6118-E-132-002-SPT-003 SNC-Lavalin # 651298-6000-4GEF-0001	00	August 17, 2018	28

## APPENDIX 3

### WRSF Dike– QC/QA Program

 <b>SNC • LAVALIN</b>	<b>TECHNICAL SPECIFICATION</b> Construction of the Waste Rock Storage Facility Dike	Prepared by: G. Haile Reviewed by: Y. Jalbert		
		Rev.	Date	Page
	AEM # 6118-E-132-002-SPT-003 SNC-Lavalin # 651298-6000-4GEF-0001	00	August 17, 2018	29

		QA Inspectors			QC Representatives			
Item	Material	Task	Frequency	Form to be fill	Task	Frequency	Form to be filled	Owner Representative – Coordinator
Survey	All placed material limits	Visual assessment for grade limits	Periodically	Daily report	Ensure that the surveyors use the latest information, bench marks and other datum and have a good understanding of the Project and meet requirements	Continuously	Daily report	Coordinate and compile information
Respect of the gradation limit	Rockfill	Visual assessment	Periodically	Daily report	Visual inspection	Continuously	Daily report	Evaluation of PAG / NPAG <sup>5</sup> material. Coordination to change the borrow source if required, adjust the exploitation by sorting out boulders with the Agnico Eagle operator, etc.
Respect of the gradation limit	Coarse Filter	Visual assessment	Periodically	Daily report	Visual inspection	Continuously	Daily report	Modify the source or the method of crushing and/or processing
Respect of the gradation limit	Fine filter BGM bedding and cover	Visual inspection Review QC data and procedure	Periodically as requested	Daily report	Visual inspection and testing <ul style="list-style-type: none"><li>- Sampling</li><li>- Grain Size distribution</li></ul>	Daily	Daily report	Collect and assess the QC results. Adapt the screening if required
Respect of the gradation limit	Fine Filter amended with bentonite	Ensure that mixing location and procedures are respected. Review QC data and procedure	Periodically As requested	Daily report	<ul style="list-style-type: none"><li>- Sampling for external lab:</li><li>- Grain Size distribution</li><li>- Saturated hydraulic conductivity (see note)</li><li>- Standard Proctor (see note)</li><li>- Sand Cone (see note)</li></ul>	Daily 1 / 300 m³ 1 / 300 m³ 1 / 300 m³	Daily report	
Storage	Bentonite and BGM <sup>6</sup>	Visual inspection	Once	Daily report	Visual inspection	Once	Daily report	Ensures that the storage in conformity with the manufacturer's specifications
Foundation approval (footprint)	Snow / Ice / Boulder removal	Visual inspection	Periodically prior to filling of footprint	Daily report / QA / QC approval form	Visual inspection to detect any unsuitable material and coordination with Contractor to ensure specifications are met Manage the clearing limits with the surveyor	Continuously	Daily report / QA / QC approval form	Collect, review and compile completed QC/QA forms
Foundation approval (Key trench)	Bedrock / Ice poor Till	Visual inspection for foundation approval and verify the excavation limit with the surveyor	Periodically prior to fill placement	Daily report / QA / QC approval form	Visual inspection to detect soil and rock fragments in bedrock cracks and/or joints. Coordination with the Contractor to remove the above undesirable materials. Verify the excavation limits with the surveyor	Continuously	Daily report / QA / QC approval form	Collect, review and compile completed QC/QA original forms
Foundation treatment (key trench)	Slush grout	Visual assessment	Periodically	Daily report / QA / QC approbation form	Visual inspection of each lift – ensure specifications are met.	Periodically	Daily report / QA / QC approval form	Collect, review and compile completed QC/QA original forms
Placement of material	All materials	Visual assessment	Periodically	Daily report / QA / QC approbation form	Visual inspection of each lift – ensure specifications are met.	Periodically	Daily report / QA / QC approval form	Collect, review and compile completed QC/QA original forms
Compaction of material	All materials	Visual inspection – procedures meet the specification	Periodically	Daily report	Visual inspection / manage the procedures with the Contractor, counting the number of passes	Continuously	Daily report	Collect, review and compile completed QC/QA original forms Collect and compile original form
Membrane installation	BGM	Visual assessment and may request additional testing	Periodically	Daily report	Visual inspection Destructive Tests (DT) Vacuum	Continuously 2 / day (1/1000 m min) 2 / day (30 m seam length)	Contractor QC report	Collect, review and compile completed QC/QA original forms;

1 PAG/NGAG = potential acid generating/non potential acid generating

Note: Because of the limited quantity of the FFAB (<1400 m³), the required QC tests do not exceed about four (4) tests per test type.

6 BGM = Bituminous geomembrane

 <b>SNC • LAVALIN</b>	<b>TECHNICAL SPECIFICATION</b> Construction of the Waste Rock Storage Facility Dike	Prepared by: G. Haile Reviewed by: Y. Jalbert		
		Rev.	Date	Page
	AEM # 6118-E-132-002-SPT-003 SNC-Lavalin # 651298-6000-4GEF-0001	00	August 17, 2018	30

## APPENDIX 4

### Bituminous Geomembrane (BGM) QC/QA Plan

 <b>SNC • LAVALIN</b>	<b>TECHNICAL SPECIFICATION</b> <b>Construction of the Waste Rock Storage Facility Dike</b>	Prepared by: G. Haile Reviewed by: Y. Jalbert		
		Rev.	Date	Page
	AEM # 6118-E-132-002-SPT-003 SNC-Lavalin # 651298-6000-4GEF-0001	00	August 17, 2018	31

**Table A: Schedule of QC Testing by Contractor**

Type of test	In-Situ or Sample Extraction	Testing Standard	Frequency of testing	Specified Value
Tensile Shear Strength of BGM Seams	Sample Extraction	D7056	1 per 1000 m of seam length	15 kN <sup>3</sup> m (min)
Vacuum Box Testing	In-situ	ASTM D5641	1 per 30 m of seam length	No defects permitted
Ultrasonic T of Seams	In-situ	ASTM D7006	1 per 300 m of seam length	No defects permitted
Visual	In-situ		Along entire seam	No defects permitted

**Table B: Schedule of QA Testing by QA Inspector**

Type of test	Testing Type and Standard	Frequency of testing	Specified Value
Oversee vacuum box test	In-Situ	1 every 10 QC tests	pass
Oversee vacuum box test	In-Situ	1 every 5 QC tests	pass
Thickness	ASTM D5199	1 per 1000 m of seam length	3.8 mm (min)
Density	ASTM D792	1 per 1000 m of seam length	1268 g/cm <sup>3</sup>
Tensile Shear Strength of Seams	ASTM D7056	1 for every 5 QC tests	15 kN/m (min)
Tensile Strength of BGM Liner material	ASTM D4595-86	1 per 2000 m of seam length	26.8 kN <sup>3</sup> m longitudinal and 16.2 kN/m transverse

 <b>SNC • LAVALIN</b>	<b>TECHNICAL SPECIFICATION</b> Construction of the Waste Rock Storage Facility Dike	Prepared by: G. Haile Reviewed by: Y. Jalbert		
		Rev.	Date	Page
	AEM # 6118-E-132-002-SPT-003 SNC-Lavalin # 651298-6000-4GEF-0001	00	August 17, 2018	32

## APPENDIX 5

### Approval form

Document number \_\_\_\_\_

Visit date	Time (Start/End)	Project No.	Prepared by
			Agnico Eagle
Project		Client	
SNC-Lavalin			
Consultant		Contractor	

Weather : ☐ Sunny ☐ Cloudy ☐ Rain ☐ Storm ☐ Snow ☐ Glaze

Wind : ☐ None gusts ☐ Light ☐ Moderate ☐ Strong, Temperature : \_\_\_\_\_ °C

Comments : \_\_\_\_\_

Appendix : ☐ Yes ☐ No Pictures ☐ Yes ☐ No Inspection report or other : \_\_\_\_\_

**ACTIVITIES PERFORMED BY SNC-LAVALIN (indicate if test forms were used)**


**SITE GUIDELINES (guidelines, memos, modification proposals, etc.)**

No	Subject	Given to



### SPECIFIC ELEMENTS VERIFIED

Elements	Location	Scope and comments

### SAFE AND SAFETY REMARKS

---



---



---



---

Issued by :

\_\_\_\_\_

Signature

\_\_\_\_\_

Date

Verified by :

\_\_\_\_\_

Signature

\_\_\_\_\_

Date

### SKETCH

**PROJECT :** \_\_\_\_\_

**PROJECT #:** \_\_\_\_\_

**DATE:** \_\_\_\_\_

**DOCUMENT #:** \_\_\_\_\_

**TIME:** \_\_\_\_\_

(YYYYMMDD-DS/NS-01) DS/NS = Day/Night shift

(24 hour clock)

**APPROVAL FOR :**

- ☐ Foundation approval (footprint)
- ☐ Foundation approval (key trench)
- ☐ Fill placement: \_\_\_\_\_
- ☐ CB cutoff wall approval
- ☐ Other: \_\_\_\_\_

<u>LOCATION</u>		<u>PREVIOUS APPROVALS</u>	
<b>Station</b>	_____	<b>Station:</b>	_____
<b>Inclination:</b>	_____	<b>Details:</b>	_____
<b>ELEVATION</b>	_____		
:	<input type="checkbox"/> varies _____ m		

**COMPLIANCE WITH TECHNICAL SPECIFICATIONS:**

(Add additional items if needed)

	<u>VERIFICATIONS DONE BY:</u>				
	<u>QA</u>		<u>QC</u>		<u>N/A</u>
	<u>Y</u>	<u>N</u>	<u>Y</u>	<u>N</u>	
1. Lines and grades					
2. Free of ice/snow/water					
3. Cleaning of trench and/or pile bottom					
4. Gradation (visual)					
5. Placement (lift thickness, segregation, etc.)					
6. Compaction					
7. Foundation on bedrock					
8. Key-in depth into bedrock					
9. Water quality					
10. CB slurry viscosity and density					
11. Elevation of CB Piles					
12. Primary piles strength (Minimum of 50 kPa UCS)					
13. Keying between primary and secondary					
14. Cracks on top of cutoff wall					

	QA		QC		N/A
	Y	N	Y	N	
15. CB mix/slurry tested (UCS, permeability, and pinhole tests)					
16. As built survey completed					
17.					
18.					
19.					
20.					
21.					
22.					
23.					
24.					
25.					

# **DETAILS**

(Refer to list above for item #)

		<b><u>APPROVED BY:</u></b>			
ITEM		QA		QC	
		Y	N	Y	N

**APPROVED BY:**

**NAME**

**SIGNATURE**

**DATE**

QA REPRESENTATIVE

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

QC REPRESENTATIVE

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

OWNER'S REPRESENTATIVE

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_






SNC • LAVALIN

# B | Technical Note on Thermal Analysis of WRSF Dike





 <b>SNC • LAVALIN</b>	<b>TECHNICAL NOTE</b> <b>Thermal Analyses at the WRSF Dike</b>	Prepared by: M. Durand-Jézéquel Reviewed by: G. Haile		
		Rev.	Date	Page
	AEM # 6118-E-132-002-TCR-013 SNC # 651298-6000-4GER-0001	00	August 8, 2018	i

**Title of document:**

## **THERMAL ANALYSES AT THE WRSF DIKE**

**Client:**

**AGNICO EAGLE MINES LTD.**

**Project:**

**AMARUQ WATER MANAGEMENT INFRASTRUCTURE DETAILED ENGINEERING**

*Prepared by:* Mathieu Durand-Jézéquel, Jr. Eng., M. Sc.


*GH for M.D.J.*

*Reviewed by:* G. Haile, P.Eng., M. Sc. A.

*G. Haile*

*Approved by:* Yohan Jalbert, Eng.

*Y. Jalbert*

 <b>SNC • LAVALIN</b>	<b>TECHNICAL NOTE</b> <b>Thermal Analyses at the WRSF Dike</b>	Prepared by: M. Durand-Jézéquel Reviewed by: G. Haile		
		Rev.	Date	Page
	AEM # 6118-E-132-002-TCR-013 SNC # 651298-6000-4GER-0001	00	August 8, 2018	ii

### REVISION INDEX

Revision				Pages Revised	Remarks
#	Prep.	App.	Date		
PA	M. D.-J.		2018-06-13		Issued for internal review
PB	M. D.-J. / G. H.	Y. J.	2018-07-31	All	Issued for Client's comments
00	M. D.-J.	Y. J.	2018-08-13	All	Final version

### NOTICE TO READER

This document contains the expression of the professional opinion of SNC-Lavalin Inc. ("SNC-Lavalin") as to the matters set out herein, using its professional judgment and reasonable care. It is to be read in the context of the agreement dated October 4<sup>th</sup>, 2017 (the "Agreement") between SNC-Lavalin and Agnico Eagle Mines Limited (the "Client") and the methodology, procedures and techniques used, SNC-Lavalin's assumptions, and the circumstances and constraints under which its mandate was performed. This document is written solely for the purpose stated in the Agreement, and for the sole and exclusive benefit of the Client, whose remedies are limited to those set out in the Agreement. This document is meant to be read as a whole, and sections or parts thereof should thus not be read or relied upon out of context.

SNC-Lavalin has, in preparing estimates, as the case may be, followed accepted methodology and procedures, and exercised due care consistent with the intended level of accuracy, using its professional judgment and reasonable care, and is thus of the opinion that there is a high probability that actual values will be consistent with the estimate(s). Unless expressly stated otherwise, assumptions, data and information supplied by, or gathered from other sources (including the Client, other consultants, testing laboratories and equipment suppliers, etc.) upon which SNC-Lavalin's opinion as set out herein are based have not been verified by SNC-Lavalin; SNC-Lavalin makes no representation as to its accuracy and disclaims all liability with respect thereto.

To the extent permitted by law, SNC-Lavalin disclaims any liability to the Client and to third parties in respect of the publication, reference, quoting, or distribution of this report or any of its contents to and reliance thereon by any third party.