CUMBERLAND RESOURCES LTD.



The document revision number is indicated below. Please replace all revised pages of this document and destroy the superseded copies. PROJECT: **MEADOWBANK GOLD PROJECT** NO: SP-GAL-02 REV 0 **PROJECT NO:** 06-1413-009 TITLE: **MEADOWBANK FUEL TANK FARM** REV DATE ISSUED-**ISSUED FOR** No. **ORIGIN** OUT IN PAGES/SECTIONS INITIAL Construction WJP 28Apr06 New Issue X Revised Sheets Only Attached Entire Document Re-issued FINAL DOCUMENT APPROVAL **CUMBERLAND APPROVAL GOLDER APPROVAL** Project Manager Project Manager Date: Date: **Engineering Manager** Engineering Lead Date: Date: Discipline Area Lead Date: Originator Date:

graded so that spillage that may occur will be conveyed toward the fuel tank farm facility to be contained there.

4.0 CLOSING REMARKS

Additional information and data relating to any or all of the geotechnical investigations at the site are available on request.

Yours very truly,

GOLDERASSOCIATES LTD.

William J. Purdy, P. Eng. Associate, Mining Group

Carrieron Clayton, M. Eng., P. Geo.

Associate, Mining Group

Nunavut Water Board

JUL 19 2006

Public Registry

WJP\CJC\aaf

N:\FINAL\2006\1413\06-1413\009\LET - 0501_06 - WATER LICENSE AMENDMENT APPLICATION COVER LETTER.DOC

7.0 CONCLUSIONS

The geotechnical comments and recommendations provided in this report are intended as design input for use by AMEC in their design and feasibility assessment of the project infrastructure. It is understood that further design input will be required for the detailed design and subsequent stages.

Currently, it is recommended that additional investigation and geotechnical assessment should be conducted to refine the infrastructure design, namely for the revised tank farm location and air strip alignment, in the next stage of the work.

We trust the information contained in the above report meets your requirements at this time. Please feel free to contact us if you need more detailed information on any of the information presented in the report.

GOLDER ASSOCIATES LTD.

W.J. Purdy, P.Eng.

Senior Geofechnica Engineer

Terry L. Eldridge, P.Eng.

Principal

WJP/TLE/vee/dmb 03-1413-427/4400

N:\FINAL\2003\1413\03-1413-427\REP 0104 2005 FINAL INFRASTRUCTURE GEOTECH REPORT MARCH 2004.DOC

ス
m
~
T
_
➢
Z

	I	٥
,		ő ő
Couls in Kilomatare	l	200
	ł	300
	-	8
	L	500

KPILE ORGANIC MATERIALS	0
ARATION	0
	0
S	0
ONSTRUCTION	0
RUCTION	0
MENT CONTROL ORING PONDS	0
	0

PROJECT

CUMBERLAND RESOURCES LTD.

TITLE SHEET MEADOWBANK FUEL TANK FARM

PROJECT NO.

ACTIVITY NO.

PROJECT MGR.
PACKAGE CODE

PROJECT PHASE

SCALE

DSN.

BY/CJC

DD/MMM/YY 28APR06 28APR06

Associates

CLIENT PROJECT MGR.

ENGINEERING MGR.


APPROVED FOR CONSTRUCTION


ĦF


THIS DRAWING IS THE PROPERTY OF GOLDER ASSOCIATES LTD.
AND IS NOT TO BE LOANED OR REPRODUCED IN ANY WAY
WITHOUT THE PERMISSION OF GOLDER ASSOCIATES LTD.


STAMP/SEAL


06-1413-009	061413009_SK-200	SK-200
RAWING NO.		REV.
3000-C-200		0











PROJECT

CUMBERLAND RESOURCES LTD.

SCALE

DSN.

둦튛묮

28 APR 06 28 APR 06 DD/MMM/YY PROJECT PHASE

CLIENT PROJECT MGR.

ENGINEERING MGR.

PROJECT MGR.

MEADOWBANK FUEL TANK FARM TANK FARM BACKFILL DETAILS APPROVED FOR CONSTRUCTION


TILLE


PROJECT NO.

ACTIVITY NO.

PACKAGE CODE

0)5	3000-C-205
REV.		DRAWING NO.
SK-21	061413009_SK-212	06-1413-009





3000-C-208 REV.	Associates	00/MMM/YY 28 APR 06 28 APR 06	DSN. WJP DRN. JK	SCALE AS SHOWN	THIS DRAWING IS THE PROPERTY OF GOLDER ASSOCIATES LTD. AND IS NOT TO BE LOANED OR REPRODUCED IN ANY WAY WITHOUT THE PERMISSION OF GOLDER ASSOCIATES LTD.
06-1413-009 FILE No. 061413009_S				PROJECT PHASE	STAMP/SEAL
MEADOWBANK FUEL TANK FARM	MEADO	PACKAGE CODE	ACTIVITY NO.	PROJECT NO.	REGISTER W. PURPOY OF THE PROPERTY OF THE PROP
DISPENSING STATION SECTIONS AND DETAILS	TITLE DISPENSING S	1	Ď.	AF	SO TOPESON
IBERLAND	CUM			·	
2) GRANULAR FILL PROVIDED FROM CRUSHING AND SCREENING OPERATIONS AT MINE SITE QUARRY. 3) LIMIT OF HDPE LINER FROM DISPENSING STATION TO BE TERMINATED 0.5m BEYOND THE CREST OF ANCHOR TRENCH ON TOP OF CONTAINMENT BERM AND EXTRUSION WELDED TO CONTAINMENT BERM HDPE. 4) HDPE LINER SYSTEM BENEATH DISPENSING STATION RUNS FULL LENGTH OF STATION AND DRAPES OVER HDPE OF TANK FARM BERM.	2) GRANULA OPERATIK 3) LIMIT OF I TERMINAT TOP OF C CONTAINN 4) HDPE LINE LENGTH C BERM.				
GEOTECHNICAL ENGINEER TO INSPECT AND APPROVE EXPOSED BEDROCK SUBGRADE SURFACE PRIOR TO PLACEMENT OF GRANULAR FILL MATERIALS.	1) GEOTECH BEDROCH GRANULA				ANNOWANT WILLIAM.
	NOTES		k		