


PROGRESSIVE PLACEMENT OF ROCKFILL COVER DURING LANDFILL OPERATION



- 1) EXCAVATION SOIL TO BEDROCK OR 2.1m DEPTH, WHICHEVER IS LESS AND REPLACE WITH 100mm MINUS GRAVEL HAVING LESS THAN 5% PASSING THE USS NO.100 SIEVE.
- 2) TEMPORARY BERM MATERIAL SHALL BE ROCKFILL.
- 3) ACTIVE AREA WITH EXPOSED WASTE MATERIAL SHALL BE MAXIMUM 15m LONG BY 24m WIDE AREA.

TITLE	LANDFILL DETAILED DESIGN LANDFILL #1 CROSS SECTIONS
-------	--



PROJECT No.	06-1413-009	FILE No.	06-1413-009-FILE-1
DESIGN BY	15AUG07	SCALE	AS SHOWN
CADD BY	15AUG07	REV.	...
CHECK			
REVIEW			

FIGURE 3

FIGURE 3