

Havaap Naunaitkutaa:

Arctic Copper Corp-kut upalungaijaqtut hanaqilutik mikijumik pinahuarutikhamik ikuutarnirmik utirutikhanik uataanit Coppermine River-mi imaqtut 40km hivuraanit Kugluktumi naunaijailutik maniliurutikhanik ihuaqtumik akiliqhivikhanik. Tamna ilihairutikhaq piniatqut taima 1000nik miitaanik taima 10nik ikuutaqaqtunik hivulliuyunik havaktauyukharnik ayuiqhautikharnik. Una halikaaptakkut ikajuqtauniaqtut tamaat ikuutarnikkut aulapkaidjutainnun, ilaujullu ikuutarnikkut ingutaarutit ubluq tamaatlu havaktiit aallanguqtiruttainnik. Tingmitikhat nayuqtauniaqtut Kugluktumi taimaaqtittilutik ihariagiyaayunik maniqami aullaaqtitivikhanik. Tamna havaaqhaq aulaniaqtut 2nik 3nik havainirnik aulaniaqtunlu upin'ngaarmi auyanguliqtuniluuniit 2025mi. Tahapkuat Havakvit munakgiyaulimaitun talvuuna ikaakninik tuktunik auladjutikharnik nurrarviingitlu. Tamna ikuutarniq ikhivaniaqtut 8"x8"x12' timbers iliyauniaqtut nunami taima ikikliyumiqtitiyaangat ayungnautikharnik nunap qangani. Imarmik iliuraqtauniaqtut hanianit najugainit imaaluuniit mikijunit tahiit. Ikuutaqtut imaq utirutait iliugaqtauniaqtut qataquuit iliugagiangani nunap uvalu ikuutaqlugit avguiviit taimaali imaq atuqtauffaagiangani aulahimaaqtumik ikuutagiangani. Drill qitqani agyaqtauniaqtut Kugluktumun angmaqtiriangani, ihivriutaayaangani tutqumavingnunlu. Arctic Copper Corp unalu/imaaluuniit ikuutaqujijit nanminirijaujut qiniqhianiaqtut havaktikhamingnik ilanganik havaktimingnik nunamingni havaktikhainnik Kugluktumi. Tamna ikuutarniq aulaniaqtut talvuuna nanminiaqtunik ACB 8,9, unalu ACSD 4nik uuktuqtunik.

Project Description:

Arctic Copper Corp plans to conduct a small program of core drilling on its claims west of the Coppermine River approximately 40km southwest of Kugluktuk to evaluate its potential to host economically viable copper deposits. The program would consist of approximately 1000 metres in approx. 10 holes in its first phase of drilling. This will be helicopter supported for the entire drill operation, including drill moves and daily crew change. The crew will be housed in Kugluktuk thereby eliminating the need for a field camp. The job will take approximately 2-3 weeks and will take place in early spring or late summer of 2023. The Company will not operate during the sensitive periods of caribou migration and calving. The drill will sit on 8"x8"x12' timbers placed on the tundra so as to minimize the disturbance of the tundra surface. Water will be sourced from nearby streams or small lakes. Drill water return will be fed into tanks to settle out the sediment and drill cuttings so that the water can be re-used for continued drilling. Drill core will be transported to Kugluktuk for logging, sampling and storage. Arctic Copper Corp and/or the drilling company will be looking to hire part of its crew from the local labour pool in Kugluktuk. The drilling will take place primarily on the company's ACB 8,9 and ACSD 4 claims.