

McGregor Lake Campsite Abandonment & Restoration Plan

Prepared for

5050 Nunavut Limited
507-700 West Pender Street
Vancouver, BC. V6C 1G8

Prepared by

Franz Environmental Inc.
308-1080 Mainland Street
Vancouver, BC V6B 2T4

Revised by

Phu Van Bui
Project Manager
5050 Nunavut Limited

March 31, 2010

McGregor Lake Campsite Abandonment & Restoration Plan

Table of Contents

1.	Introduction	1
1.1	Expected Environmental Impacts of Campsite and Exploration Activities	2
2.	Camp & Exploration Operations	2
2.1	Campsite	2
2.2	Fuel Storage	4
2.3	Campsite Sewage Disposal	4
2.4	Solid Waste	4
2.5	Waste Oil	4
2.6	Hazardous Waste	5
2.7	Drill Holes	5
2.8	Drill Cores and Sumps	5
2.9	Bulky Items/Scrap Metal	5
2.10	Water Intake	5
2.11	Helicopter Landing Pad	6
2.12	Generator	6
3.	Final Abandonment & Restoration	6
3.1	Time Frame	6
3.2	Camp	6
3.3	Fuel storage and re-fuelling areas	6
3.4	Grey-water Sump	6
3.5	Solid Wastes	7
3.6	Waste Oil	7
3.7	Hazardous Waste	7
3.8	Drill Sites, Sumps and Cuttings	7
3.9	Bulky Items	7
3.10	Water Intake	7
3.11	Helicopter Landing Pad	7
3.12	Generators	7

List of Appendices

Appendix A	Contact List
Appendix B	Material Safety Data Sheets (MSDS)
Appendix C	Spill Report Form
Appendix D	Uranium Exploration Plan
Appendix E	Nunavut Waste Generator Number
Appendix F	Daily Wildlife Log
Appendix G	Figures
	1-1 Site Location Map
	1-2 Exploration Area
	1-3 Camp Layout

List of Tables

2-1	Campsite Structures to be Left On-Site in a Short Term Temporary Closure (Less than One Year)	3
2-2	Campsite Equipment to be Left On-Site in a Short Term Temporary Closure (Less than One Year)	3

1. Introduction

5050 Nunavut Limited (5050 Nunavut) was incorporated under the laws of Nunavut and presently holds 64 mineral claims comprising 53,734.30 hectares and two Inuit Owned Land parcels comprising of 19,711.70 hectares surrounding All Night Lake and McGregor Lake.

These claims are located between 70 and 100 kilometres south of Kugluktuk, Nunavut (Figure 1-2). The exploration program is at grass root stage and is considered to be low impact. It includes regional and detailed geological mapping, prospecting and sampling, airborne and ground based geophysical surveys and drilling.

5050 Nunavut is a wholly owned subsidiary of MIE Metals Corporation (MIE Metals) and has its corporate office at:

*Suite 507, 700 West Pender Street
Vancouver, B.C. V6C 1G8
Tel: (604) 681-4001
Fax: (604) 681-4022*

The principals in both companies are:

- Gordon Addie, President of 5050 Nunavut Limited and MIE Metals Corporation*

5050 Nunavut Limited (5050 Nunavut), presently holds a Kitikmeot Inuit Association (KIA) Land Use License KTL306C016 permitting a camp (with airstrip), staking & prospecting, exploration (geophys-grd/air) drilling and bulk fuel storage at McGregor Lake to support exploration activities associated with Ni-Cu-PGE and uranium exploration. The License is valid until *July 20, 2011*. This *original* license was issued to establish a new camp at Iceberg Creek along the southwest shore of McGregor Lake.

As an alternative to setting up a new camp, the Kitikmeot Inuit Association (KIA) required 5050 Nunavut use an abandoned exploration camp along the north shore of McGregor Lake that was established and operated by Inco Limited in the 1950's and 1960's (Figure 1-1). Figure 1-2 shows the location of the campsite as well as the proposed drill targets.

This Abandonment and Restoration Plan was originally provided as part of the amendment and renewal of KTL306C016 to expand 5050 Nunavut's drilling program to 10,000m and the use/expansion of the McGregor Lake Campsite to accommodate 25-30 personnel. Figure 1-3 presents the proposed camp layout.

This Spill and Contingency Plan is in support of any activities conducted by 5050 Nunavut and shall be in effect when approval is obtained by the appropriate authorizing agencies, and is subject to revisions as may be necessitated by future programs.

1.1 Expected Environmental Impacts of Campsite and Exploration Activities

Little environmental impact is anticipated from the use of the existing McGregor Lake Campsite. The proposed camp area was chosen because it will avoid any additional surface disturbance in the area. To further reduce any possible impact to vegetation, the exploration programs will run from March to October with seasonal shutdown periods during May and June during ice break-up. The campsite and exploration activities will be shutdown from October to March. During the winter shut-down, the camp will either be winterized or, if warranted, one or two people will remain on site as caretakers and to watch the camp.

2. CAMP & EXPLORATION OPERATIONS

The following details maintenance that is completed on a continuing basis throughout the land use operation, seasonal closures, and temporary shutdowns.

2.1 Campsite

The camp will be maintained in a tidy and orderly fashion. Upon arriving at the camp, all staff will be trained in camp rules such as the Spill Contingency Plan, camp operations, and waste management.

In the case of short term temporary shutdown (less than a year), all portable wooden structures (survival shacks, generator shacks, etc.) will be stored in the campsite area and all portable equipment will be stored in sheds and locked up. The kitchen will be inspected and all food will be removed to decrease the potential for attracting animals. The kitchen, dry and insulated tents will be closed and battened down. All garbage will be incinerated or removed to an approved municipal discharge site in Yellowknife or Kugluktuk.

Final inspections of all areas of the site will be conducted prior to the commencement of work and at the end of the camp's operational period to ensure these sites have been reclaimed as much as possible to its previous condition. Soil samples and pictures before and after the project will be collected to ensure proper records are kept.

Tables 2-1 and 2-2 show the building and equipment inventory to be left on site in a temporary closure.

Table 2-1
Campsite Structures to be Left On-Site in a Short Term
Temporary Closure (Less than One Year)

Structure Type	New or Existing Structure	Approximate Dimensions	Number
Core Shack	New	20ft x 30ft	1
Geologist's Office w/ existing core shack	Existing	34ft x 20ft	1
Drill Foreman Office	Existing	14ft x 16ft	1
Kitchen	Existing	30ft x 16ft	1
First Aid	Existing	14ft x 16ft	1
Generator Room	Existing	10ft x 10ft	1
Dry	Existing	34ft x 20ft	1
Sleeper (insulated tent accommodation)	Existing	16ft x 20ft	6
Sleeper (insulated tent accommodation)	New	14ft x 16ft	5
Outhouse	Existing	9ft x 9ft	1
Pacto Toilets	New	9ft x 9ft	2

Table 2-2
Campsite Equipment to be Left On-Site in a Short Term
Temporary Closure (Less than One Year)

Equipment Type	Number	Size/Ground/Pressure	Use
Caterpillar D6M with Low-ground pressure tracks (LGP)	1	15, 000kg/4.71 psi	Site maintenance & ice airstrip construction
Sled	1	2 ,300kg/5cm ground indent	Site maintenance & ice airstrip construction
Bobcat	1		Site maintenance & ice airstrip construction
Snowmobiles	15	Various/minimal	Transportation
Hydracore 2000 diamond drill	2	Maximum depth of 800m with BTW	Drilling

2.2 Fuel Storage

All fuel storage and handling is guided by the procedures set out in the Spill and Contingency Plan. Empty drums used during the exploration program will be regularly rotated out of camp by fixed wing aircraft in order to be re-filled and then returned to camp during annual pre-exploration resupply programs. Any empty drums that are deemed not fit to hold fuel are back hauled to Kugluktuk and/or Yellowknife and disposed of at approved facilities.

2.3 Campsite Sewage Disposal

Pacto toilet systems will be used at the campsite. These toilets require no electricity, water, or sewage system. A flush foil system is used to encapsulate the waste which is then incinerated daily. In the case of temporary shutdown, all encapsulated waste bags will be removed and incinerated prior to shutting down the camp.

2.4 Solid Waste

All camp and kitchen wastes will be incinerated daily in the camp incinerator. Any waste that cannot be incinerated will be stored in barrels and shipped to Kugluktuk and/or Yellowknife for disposal. In the case of temporary shutdown, all waste will either be incinerated or removed.

There will be a comprehensive waste segregation strategy designed to reduce and control the volumes of wastes produced. This strategy includes the separation of non-food waste items suitable for storage and subsequent transport to Kugluktuk and/or Yellowknife for disposal or recycling.

A dual chamber, forced-air incinerator will be operated to ensure complete combustion of wastes. Appropriate training will be provided to all personnel working with and in the vicinity of the incinerator.

The following solid waste will be separated for transport to Kugluktuk and/or Yellowknife for disposal and recycling (i.e. not to be incinerated):

- *Waste wood treated with preservatives such as creosote, pentachlorophenol*
- *Heavy metal solutions should not be burned*
- *Plastics*
- *Electrical wire*
- *Asbestos and building demolition wastes (except clean wood)*
- *Other solid wastes that may be deemed hazardous*

2.5 Waste Oil

Waste oil volumes from the camp and related activities will be incinerated or used for heating purposes. In the case of temporary shutdown, all waste oil will be incinerated.

2.6 Hazardous Waste

Hazardous waste will be separated for transport to Kugluktuk and/or Yellowknife for disposal and recycling. Heavy metal solutions and other waste that is suspected to produce dioxins and furans when burned will be excluded from incineration.

Waste oil volumes from the camp and related activities will be less than 0.04 cubic metres per week. Waste oil will be incinerated or used for heating purposes.

Uranium may be encountered in the drill cores for Bear Valley Project only. 5050 Nunavut currently holds Nunavut Waste Generator # NUG 100022 (attached in the appendices). All such waste will be documented and transported from the Project Area for proper disposal. The same individual in charge of documenting the hazardous wastes will have completed a course in the Transportation of Dangerous Goods specifically designed to train geologists in the safe transport of nuclear substances.

For the long term storage of drill core, radiation levels will be reduced to less than 1.0 μSv measured at 1.0 meter from the surface and in no instance will the level be allowed to exceed 2.5 μSv . In practice, it is anticipated that major uranium intersections will be transported to the Saskatchewan Research Council for testing and storage at their nuclear materials storage facility. Please refer to the attached Uranium Exploration Plan.

2.7 Drill Holes

All drill sites are cleaned and maintained on a daily basis. Waste materials, garbage and any empty drums or propane cylinders are routinely returned to camp for incineration or removal to Kugluktuk and/or Yellowknife. Upon completion of an individual drill hole the drill rig and supplies are moved to a new site and the drill set up is cleaned of any debris and the area returned, as close as possible, to a pre disturbed state. In the case of temporary shutdown, all drill sites will be cleaned.

2.8 Drill Cores and Sumps

All drill cores are collected and will be stored within the drill-core area of the camp. Water used during the drilling will be disposed of in natural depressions or sumps, at least 100m from the high water mark of any water body.

2.9 Bulky Items/Scrap Metal

Scrap metal in the form of drill rods will be removed to Kugluktuk and/or Yellowknife on a regular schedule to avoid excessive stockpiling.

2.10 Water Intake

The water intake will be located on McGregor Lake using a 'hose & float system' which will suspend the intake pipe on the water surface with the intake located on the float. The intake end of the pipe will be equipped with a screen to avoid fish entrapment. The screen size will be determined following the calculations outlined in DFO's Freshwater Intake End-of-Pipe Fish Screen Guidelines. In the case of temporary shutdown, the water intake pump will be shut off.

2.11 Helicopter Landing Pad

The helicopter landing pad will be regularly inspected to ensure there is no debris around the area. A drip pan and spill kit is located at the landing pad to be used while re-fuelling the helicopter. In the case of temporary shutdown, all debris will be cleared from around the helicopter pad.

2.12 Generator

The generators will receive regular maintenance. The generator shack will be equipped with a drip pan, spill kit, and absorbent matting should there be a spill of gas while filling the generator. In the case of temporary shutdown, the generators will be turned off, and the shack will be closed and locked.

3. FINAL ABANDONMENT AND RESTORATION

The final abandonment and restoration plan provided below includes the time frame, discussion about the camp, discussion regarding fuel storage and re-fuelling areas, grey water disposal, solid waste disposal, waste oil and hazardous wastes disposal, bulky items. In addition, the section discusses abandonment and restoration at drill sites, the water intake system, the helicopter landing pad and generators.

3.1 Time Frame

Projects are still in exploration stage therefore it is not feasible at this time to subscribe to a definitive schedule for the conclusion of this land use operation. Once the projects are terminated or campsite relocation becomes necessary, 5050 Nunavut the following procedures will be followed to allow for proper abandonment and restoration of the project area.

3.2 Camp

When the camp is no longer required all structures erected by 5050 Nunavut, temporary buildings, machinery, equipment, materials, fuel drums, storage containers, and any other items used in connection with the camp will either be burned or removed from the site. The disturbed areas will be stabilized and restored as close as possible to a pre-disturbed state. The buildings existing prior to 5050 Nunavut occupying the campsite will remain in place.

3.3 Fuel storage and re-fuelling areas

Upon closure all fuel drums will be removed and the non-reusable drums will go to the Kugluktuk and/or Yellowknife land fill. The containment system will either be removed or re-contoured, and the area around the secondary containment for fuel storage will be sampled for hydrocarbon contamination. If there is any hydrocarbon contamination resulting from 5050 Nunavut activities the contaminated materials will be removed, the area will be stabilized and restored as close as possible to a pre-disturbed state.

3.4 Grey-water Sump

At time of closure all camp sumps will be backfilled, re-contoured, stabilized, and restored as close as possible to a pre-disturbed state.

3.5 Solid Wastes

At the time of closure most wastes will be incinerated. Any waste that cannot be incinerated will be placed in barrels and removed to the Kugluktuk and/or Yellowknife landfill. At time of closure the incinerator will be removed along with any barrels of garbage. The soil under and around the incinerator will be sampled for metals and hydrocarbon contamination. If there are any metals and/or hydrocarbon contamination resulting from 5050 Nunavut activities the contaminated materials will be removed, the area will be stabilized and restored as close as possible to a pre-disturbed state.

3.6 Waste Oil

All waste oil will be incinerated.

3.7 Hazardous Waste

There will be no hazardous materials on the project site.

3.8 Drill Sites, Sumps and Cuttings

For final restoration of all drill sites, excess cuttings will be put into sumps, and sumps will be back filled. Sumps will be restored as close as possible to a pre-disturbed state. Drill casing, timbers, fuel and fuel berms, will be removed along with all other drilling equipment.

3.9 Bulky Items

Scrap metal in the form of drill rods and bulky items will be removed from site. All drilling scrap will be removed from the project site as backhaul on supply flights.

3.10 Water Intake

Upon closure the water intake pipe, float and pump will be removed, and backhauled with other equipment headed for Kugluktuk and/or Yellowknife.

3.11 Helicopter Landing Pad

Upon closure all debris around the helicopter landing area will be removed. As this is a designated refuelling area it will be sampled for hydrocarbon contamination. If there is any hydrocarbon contamination resulting from 5050 Nunavut activities the contaminated materials will be removed. The area will be stabilized and restored as close as possible to a pre-disturbed state.

3.12 Generators

Upon closure the generator shacks will be removed from the site. The area around shack will be sampled for hydrocarbon contamination. If there is any hydrocarbon contamination resulting from 5050 Nunavut activities the contaminated materials will be removed, the area will be stabilized and restored as close as possible to a pre-disturbed state.

McGregor Lake Campsite Abandonment & Restoration Plan

ADDENDIX A Contact List








Contact Telephone Numbers	Telephone	Facsimile
Emergency Spill Hotline	(867) 920-8130	(867) 873-6924
<i>INAC Water Resources Officer, Melissa Joy</i>	<i>(867) 982-4302</i>	
<i>INAC Resource Management Officer, Baba Pederson</i>	<i>(867) 982-4306</i>	
<i>INAC Manager of Field Operations, Peter Kusugak</i>	<i>(867) 975-4644</i>	
<i>Environment Canada 24-Hour Emergency Pager</i>	<i>(867) 766-3737</i>	
<i>5050 Nunavut / MIE Metals Corp. – Vancouver Office</i>	<i>(604) 681-4001</i>	<i>(604) 681-4022</i>
<i>Camp Manager, John McLean</i>	<i>(867) 873-8666</i>	
<i>Project Manager, Phu Van Bui</i>	<i>(778) 233-3221</i>	<i>(604) 681-4022</i>
<i>President, Gordon Addie</i>	<i>(604) 512-0145</i>	<i>(604) 681-4022</i>
Workers Compensation Board	(867) 669-4409	(867) 873-0262
RCMP – Kugluktuk	(867) 982-1111	
Kitikmeot Inuit Association – Kugluktuk	(867) 982-3310	(867) 982-3311
Ministry of Environment – Rankin Inlet	(867) 645-8083	(867) 645-8085
Environment Canada Iqaluit	(867) 975-4464	
Department of Environment, Nunavut	(867) 975-7700	
Department of Fisheries and Oceans	(867) 645-2871	
Nunavut Impact Review Board	(867) 983-2593	
Nunavut Water Board	(867) 360-6338	(867) 360-6369
Franz Environmental Inc.	(604) 632-9941	(604) 632-9942
Diamond Drill: Major Drilling – Nunavut/NWT Cory Redwood	(867) 873-3358	
Kikiak Construction – Kugluktuk, Nunavut	(867) 982-4713	
Air Tindi – Yellowknife, NWT	(888) 545-6794	
Adlair Aviation – Yellowknife, NWT	(867) 873-5161	
Air Thelon – Yellowknife, NWT	(867) 920-7110	
Arctic Air – Yellowknife, NWT	(867) 873-1210	
Arctic Sunwest Charters – Yellowknife, NWT	(867) 873-4464	
Buffalo Airways – Yellowknife, NWT	(867) 873-6112	
Remote Helicopters – Slave Lake, Alberta	(780) 849-2222	
1984 Enterprises Inc, Vancouver, BC,	(604) 736-8142	

McGregor Lake Campsite Abandonment & Restoration Plan

APPENDIX B
MSDS



Material Safety Data Sheet

WHMIS (Pictograms)	WHMIS (Classification)	Protective Clothing	TDG (pictograms)
 	B-3, D-2B	   	

Section 1. Chemical Product and Company Identification

Product Name	DIESEL FUEL	Code	W104, W293 SAP: 120, 121, 122, 287
Synonym	Diesel 50, Diesel 50 LS, #1 Diesel, #1 Diesel LS, Diesel LC, Seasonal Diesel, Seasonal Diesel LS, Diesel AA, Domestic Marine Diesel, International marine Diesel, Seasonal Diesel Locomotive, Domestic Marine diesel LS, diesel -20°C (LS), LSD, Low Sulphur Diesel, dyed diesel, marked diesel, coloured diesel, Naval Distillate, Ultra Low Sulphur Diesel, ULS Diesel, Mining Diesel, Mining Diesel Special, Mining Diesel Special LS, High Flash Mining Diesel, Furnace Oil, Stove Oil.	Validated on	2/6/2004.
Manufacturer	PETRO-CANADA P.O. Box 2844 Calgary, Alberta T2P 3E3	In case of Emergency	Petro-Canada: 403-296-3000 Canutec Transportation: 613-996-6666 Poison Control Centre: Consult local telephone directory for emergency number(s).
Material Uses	Diesel fuels are distillate fuels suitable for use in high and medium speed internal combustion engines of the compression ignition type. Mining Diesel has a higher flash point requirement, for safe use in underground mines.		

Section 2. Composition and Information on Ingredients

			Exposure Limits (ACGIH)		
Name	CAS #	% (V/V)	TLV-TWA(8 h)	STEL	CEILING
1) Diesel oil.	68334-30-5	>99.9	100 mg/m ³ (as total hydrocarbons) *	Not established	Not established
2) Proprietary additives.	Not available	<0.1	Not established	Not established	Not established
Aromatic content is 50% maximum (benzene: nil). Sulphur content is 0-0.50%.					
Manufacturer Recommendation	* Avoid prolonged or repeated skin contact to diesel fuels which can lead to dermal irritation and may be associated with an increased risk of skin cancer.				
Other Exposure Limits	Consult local, state, provincial or territory authorities for acceptable exposure limits.				

Section 3. Hazards Identification.

Potential Health Effects	Combustible liquid. Exercise caution when handling this material. Contact with this product may cause skin and eye irritation. Prolonged or repeated contact may cause skin irritation, defatting, drying and dermatitis. Inhalation of this product may cause respiratory tract irritation and Central Nervous System (CNS) Depression, symptoms of which may include; weakness, dizziness, slurred speech, drowsiness, unconsciousness and in cases of severe overexposure; coma and death. Ingestion of this product may cause gastro-intestinal irritation. Aspiration of this product may result in severe irritation or burns to the respiratory tract. For more information refer to Section 11 of this MSDS.
---------------------------------	--

Section 4. First Aid Measures

Eye Contact	IMMEDIATELY flush eyes with running water for at least 15 minutes, keeping eyelids open. Seek medical attention.
Skin Contact	Remove contaminated clothing - launder before reuse. Wash gently and thoroughly the contaminated skin with running water and non-abrasive soap. Seek medical attention.
Inhalation	Evacuate the victim to a safe area as soon as possible. If the victim is not breathing, perform artificial respiration. Allow the victim to rest in a well ventilated area. Seek medical attention.
Ingestion	DO NOT induce vomiting because of danger of aspirating liquid into lungs. Seek medical attention.
Note to Physician	Not available

Section 5. Fire-fighting Measures

Flammability	Class II - combustible liquid (NFPA).	Flammable Limits	LOWER: 0.7%, UPPER: 6% (NFPA)
Flash Points	Diesel Fuel: Closed Cup: >40°C (>104°F) Marine Diesel Fuel: Closed Cup: >60°C (>140°F) Mining Diesel: Closed Cup: 52°C (126°F)	Auto-Ignition Temperature	225°C (437°F)
Fire Hazards in Presence of Various Substances	Flammable in presence of open flames, sparks, or heat. Vapours are heavier than air and may travel considerable distance to sources of ignition and flash back. This product can accumulate static charge and ignite. May accumulate in confined spaces.	Explosion Hazards in Presence of Various Substances	Containers may explode in heat of fire. Do not cut, weld, heat, drill or pressurize empty container. Vapour explosion hazard indoors, outdoors or in sewers. Runoff to sewer may create fire or explosion hazard.
Products of Combustion	Carbon oxides (CO, CO ₂), nitrogen oxides (NO _x), sulphur oxides (SO _x), sulphur compounds (H ₂ S), water vapour (H ₂ O), smoke and irritating vapours as products of incomplete combustion. See Section 11 (Other Considerations) for information regarding the toxicity of the combustion products.		
Fire Fighting Media and Instructions	<p>NAERG96, GUIDE 128, Flammable liquids (Non-polar/Water-immiscible). CAUTION: This product has a moderate flash point above 40°C: Use of water spray when fighting fire may be inefficient.</p> <p>If tank, rail car or tank truck is involved in a fire, ISOLATE for 800 meters (1/2 mile) in all directions; also consider initial evacuation for 800 meters (1/2 mile) in all directions.</p> <p>SMALL FIRES: Dry chemical, CO₂, water spray or regular foam. LARGE FIRES: Water spray, fog or regular foam. Do not use straight streams. Move containers from fire area if you can do it without risk. Fires Involving Tanks or Car/Trailer Loads: Fight fire from maximum distance or use unmanned hose holders or monitor nozzles.</p> <p>Cool containers with flooding quantities of water until well after fire is out. Withdraw immediately in case of rising sound from venting devices or any discolouration of tank. ALWAYS stay away from the ends of tanks. For massive fire, use unmanned hose holders or monitor nozzles; if this is impossible withdraw from area and let fire burn. Wear positive pressure self-contained breathing apparatus (SCBA). Structural firefighters' protective clothing will only provide limited protection.</p>		

Section 6. Accidental Release Measures

Material Release or Spill	Consult current National Emergency Response Guide Book (NAERG) for appropriate spill measures if necessary. IN THE EVENT OF A LARGE SPILL CONSIDER THE FOLLOWING CONTROL MEASURES: Extinguish all ignition sources. Stop leak if safe to do so. Ventilate area. Dike spilled material. Use appropriate inert absorbent material to absorb spilled product. Collect used absorbent for later disposal. Avoid contact with spilled material. Avoid breathing vapours or mists of material. Avoid contaminating sewers, streams, rivers and other water courses with spilled material. Evacuate non-essential personnel. Ensure clean-up personnel wear appropriate personal protective equipment. Ground and bond all equipment used to clean up the spilled material, as it may be a static accumulator. Notify appropriate authorities immediately.
----------------------------------	---

Section 7. Handling and Storage

Handling	COMBUSTIBLE MATERIAL. Handle with care. Avoid contact with any sources of ignition, flames, heat, and sparks. Avoid skin contact. Avoid eye contact. Avoid inhalation of product vapours or mists. Empty containers may contain product residue. Do not pressurize, cut, heat, or weld empty containers. Do not reuse containers without commercial cleaning and/or reconditioning. Personnel who handle this material should practice good personal hygiene during and after handling to help prevent accidental ingestion of this product. Properly dispose of contaminated leather articles including shoes that cannot be decontaminated. Avoid confined spaces and areas with poor ventilation. Ensure all equipment is grounded/bonded. Wear proper personal protective equipment (See Section 8).
Storage	Store away from heat and sources of ignition. Store in dry, cool, well-ventilated area. Store away from incompatible and reactive materials (See section 5 and 10). Ensure the storage containers are grounded/bonded.

Section 8. Exposure Controls/Personal Protection

Engineering Controls	For normal application, special ventilation is not necessary. If user's operations generate vapours or mist, use ventilation to keep exposure to airborne contaminants below the exposure limit. Make-up air should always be supplied to balance air removed by exhaust ventilation. Ensure that eyewash station and safety shower are close to work-station.
Personal Protection	<i>The selection of personal protective equipment varies, depending upon conditions of use.</i>
Eyes	Eye protection (i.e., safety glasses, safety goggles and/or face shield) should be determined based on conditions of use. If product is used in an application where splashing may occur, the use of safety goggles and/or a face shield should be considered.
Body	Wear appropriate clothing to prevent skin contact. As a minimum long sleeves and trousers should be worn.
Respiratory	Where concentrations in air may exceed the occupational exposure limits given in Section 2 (and those applicable to your area) and where engineering, work practices or other means of exposure reduction are not adequate, NIOSH approved respirators may be necessary to prevent overexposure by inhalation.
Hands	Wear appropriate chemically protective gloves. When handling hot product ensure gloves are heat resistant and insulated.
Feet	Wear appropriate footwear to prevent product from coming in contact with feet and skin.

Section 9. Physical and Chemical Properties

Physical State and Appearance	Bright oily liquid.	Viscosity	1.3 - 4.1 cSt @ 40°C (104°F)
Colour	Clear to yellow / brown (may be dyed for taxation purposes).	Pour Point	Variable, -50°C to 0°C (-58°F to -32°F)
Odour	Petroleum oil like.	Softening Point	Not applicable.
Odour Threshold	Not available	Dropping Point	Not applicable.
Boiling Point	150 - 371°C (302-700°F)	Penetration	Not applicable.
Density	0.80 - 0.85 kg/L @ 15°C (59°F)	Oil / Water Dist. Coefficient	Not available
Vapour Density	4.5 (Air = 1)	Ionicity (in water)	Not applicable.
Vapour Pressure	Not available	Dispersion Properties	Not available
Volatility	Semivolatile to volatile.	Solubility	Insoluble in cold water, soluble in non-polar hydrocarbon solvents.

Section 10. Stability and Reactivity

Corrosivity	Not available		
Stability	The product is stable under normal handling and storage conditions.	Hazardous Polymerization	Will not occur under normal working conditions.
Incompatible Substances / Conditions to Avoid	Reactive with oxidizing agents and acids.	Decomposition Products	May release COx, NOx, SOx, H2S, H2O, smoke and irritating vapours when heated to decomposition.

Section 11. Toxicological Information



Routes of Entry	Skin contact, eye contact, inhalation, and ingestion.
Acute Lethality	Acute oral toxicity (LD50): 7500 mg/kg (rat).
Chronic or Other Toxic Effects	
Dermal Route:	This product contains a component (at >= 1%) that can cause skin irritation. Therefore, this product is considered to be a skin irritant. Prolonged or repeated contact may defat and dry skin, and cause dermatitis. (See Other Considerations)
Inhalation Route:	Inhalation of this product may cause respiratory tract irritation. Inhalation of this product may cause Central Nervous System (CNS) Depression, symptoms of which may include; weakness, dizziness, slurred speech, drowsiness, unconsciousness and in cases of severe overexposure; coma and death.
Oral Route:	Ingestion of this product may cause gastro-intestinal irritation. Aspiration of this product may result in severe irritation or burns to the respiratory tract. Ingestion of this product may cause Central Nervous System (CNS) Depression, symptoms of which may include; weakness, dizziness, slurred speech, drowsiness, unconsciousness and in cases of severe overexposure; coma and death.
Eye Irritation/Inflammation:	This product contains a component (at >= 1%) that can cause eye irritation. Therefore, this product is considered to be an eye irritant.
Immunotoxicity:	Not available
Skin Sensitization:	Contact with this product is not expected to cause skin sensitization, based upon the available data and the known hazards of the components.
Respiratory Tract Sensitization:	Contact with this product is not expected to cause respiratory tract sensitization, based upon the available data and the known hazards of the components.
Mutagenic:	This product is not known to contain any components at >= 0.1% that have been shown to cause mutagenicity. Therefore, based upon the available data and the known hazards of the components, this product is not expected to be a mutagen.
Reproductive Toxicity:	This product is not known to contain any components at >= 0.1% that have been shown to cause reproductive toxicity. Therefore, based upon the available data and the known hazards of the components, this product is not expected to be a reproductive toxin.
Teratogenicity/Embryotoxicity:	This product is not known to contain any components at >= 0.1% that have been shown to cause teratogenicity and/or embryotoxicity. Therefore, based upon the available data and the known hazards of the components, this product is not expected to be a teratogen/embryotoxin.
Carcinogenicity (ACGIH):	ACGIH A3: animal carcinogen. [Diesel oil] (See Other Considerations)
Carcinogenicity (IARC):	This product is not known to contain any chemicals at reportable quantities that are listed as Group 1, 2A, or 2B carcinogens by IARC.
Carcinogenicity (NTP):	This product is not known to contain any chemicals at reportable quantities that are listed as carcinogens by NTP.
Carcinogenicity (IRIS):	This product is not known to contain any chemicals at reportable quantities that are listed as carcinogens by IRIS.

DIESEL FUEL		Page Number: 4
Carcinogenicity (OSHA):	This product is not known to contain any chemicals at reportable quantities that are listed as carcinogens by OSHA.	
Other Considerations	<p>Avoid prolonged or repeated skin contact to diesel fuels which can lead to dermal irritation and may be associated with an increased risk of skin cancer.</p> <p>Diesel engine exhaust particulate is probably carcinogenic to humans (IARC Group 2A).</p>	

Section 12. Ecological Information			
Environmental Fate	Not available	Persistence/Bioaccumulation Potential	Not available
BOD5 and COD	Not available	Products of Biodegradation	Not available
Additional Remarks	No additional remark.		

Section 13. Disposal Considerations	
Waste Disposal	Spent/ used/ waste product may meet the requirements of a hazardous waste. Consult your local or regional authorities. Ensure that waste management processes are in compliance with government requirements and local disposal regulations.

Section 14. Transport Information			
TDG Classification	DIESEL FUEL, 3, UN1202, PGIII (CL-TDG)	Special Provisions for Transport	See Transportation of Dangerous Goods Regulations.

Section 15. Regulatory Information														
Other Regulations		This product is acceptable for use under the provisions of WHMIS-CPR. All components of this formulation are listed on the CEPA-DSL (Domestic Substances List). All components of this formulation are listed on the US EPA-TSCA Inventory. All components of this product are on the European Inventory of Existing Commercial Chemical Substances (EINECS). This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all of the information required by the CPR. Please contact Product Safety for more information.												
DSD/DPD (Europe)		Not evaluated.	HCS (U.S.A.) CLASS: Irritating substance. CLASS: Target organ effects. CLASS: Combustible liquid having a flash point between 37.8°C (100°F) and 93.3°C (200°F).											
ADR (Europe) (Pictograms)		NOT EVALUATED FOR EUROPEAN TRANSPORT NON ÉVALUÉ POUR LE TRANSPORT EUROPÉEN.	DOT (U.S.A) (Pictograms) 											
HMIS (U.S.A.)		<table><tr><td>Health Hazard</td><td>2*</td></tr><tr><td>Fire Hazard</td><td>2</td></tr><tr><td>Reactivity</td><td>0</td></tr><tr><td>Personal Protection</td><td>H</td></tr></table>	Health Hazard	2*	Fire Hazard	2	Reactivity	0	Personal Protection	H	NFPA (U.S.A.) Health  Fire Hazard Reactivity Specific hazard			Rating 0 Insignificant 1 Slight 2 Moderate 3 High 4 Extreme
Health Hazard	2*													
Fire Hazard	2													
Reactivity	0													
Personal Protection	H													

Section 16. Other Information	
References	Available upon request. * Marque de commerce de Petro-Canada - Trademark
Glossary	<div> ACGIH - American Conference of Governmental Industrial Hygienists ADR - Agreement on Dangerous goods by Road (Europe) ASTM - American Society for Testing and Materials (BOD5 - Biological Oxygen Demand in 5 days CAN/CGA B149.2 Propane Installation Code CAS - Chemical Abstract Services CEPA - Canadian Environmental Protection Act CERCLA - Comprehensive Environmental Response, Compensation and Liability Act CFR - Code of Federal Regulations CHIP - Chemicals Hazard Information and Packaging Approved Supply List COD5 - Chemical Oxygen Demand in 5 days CPR - Controlled Products Regulations DOT - Department of Transport DSCL - Dangerous Substances Classification and Labeling (Europe) </div> <div> IRIS - Integrated Risk Information System LD50/LC50 - Lethal Dose/Concentration kill 50% LDLo/LCLo - Lowest Published Lethal Dose/Concentration NAERG'96 - North American Emergency Response Guide Book (1996) NFPA - National Fire Prevention Association NIOSH - National Institute for Occupational Safety & Health NPRI - National Pollutant Release Inventory NSNR - New Substances Notification Regulations (Canada) NTP - National Toxicology Program OSHA - Occupational Safety & Health Administration PEL - Permissible Exposure Limit RCRA - Resource Conservation and Recovery Act SARA - Superfund Amendments and Reorganization Act SD - Single Dose STEL - Short Term Exposure Limit (15 minutes) </div>
Continued on Next Page	Internet: www.petro-canada.ca/msds Available in French

DSD/DPD - Dangerous Substances or Dangerous Preparations Directives (Europe)
DSL - Domestic Substance List
EEC/EU - European Economic Community/European Union
EINECS - European Inventory of Existing Commercial Chemical Substances
EPCRA - Emergency Planning and Community Right to Know Act
FDA - Food and Drug Administration
FIFRA - Federal Insecticide, Fungicide and Rodenticide Act
HCS - Hazardous Communication System
HMIS - Hazardous Material Information System
IARC - International Agency for Research on Cancer

TDG - Transportation Dangerous Goods (Canada)
TDLo/TCLo - Lowest Published Toxic Dose/Concentration
TLm - Median Tolerance Limit
TLV-TWA - Threshold Limit Value-Time Weighted Average
TSCA - Toxic Substances Control Act
USEPA - United States Environmental Protection Agency
USP - United States Pharmacopoeia
WHMIS - Workplace Hazardous Material Information System

For Copy of MSDS

Internet: www.petro-canada.ca/msds

Western Canada, Ontario & Central Canada, telephone: 1-800-668-0220; fax: 1-800-837-1228

Quebec & Eastern Canada, telephone: 514-640-8308; fax: 514-640-8385

For Product Safety Information: (905) 804-4752








Prepared by Product Safety - JDW on 2/6/2004.

Data entry by Product Safety - JDW.

To the best of our knowledge, the information contained herein is accurate. However, neither the above named supplier nor any of its subsidiaries assumes any liability whatsoever for the accuracy or completeness of the information contained herein. Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist.



Material Safety Data Sheet

WHMIS (Pictograms)	WHMIS (Classification)	Protective Clothing	TDG (pictograms)
 	B-2, D-2A, D-2B	   	

Section 1. Chemical Product and Company Identification

Product Name	GASOLINE, UNLEADED	Code	W102E
Synonym	Regular, Unleaded Gasoline (US Grade), Mid-Grade, Plus, Super, WinterGas, SummerGas, Supreme, SuperClean WinterGas, RegularClean, PlusClean, Premium, marked or dyed gasoline, Super Premium (94 RO)	Validated on	6/9/2004.
Manufacturer	PETRO-CANADA P.O. Box 2844 Calgary, Alberta T2P 3E3	In case of Emergency	Petro-Canada: 403-296-3000 Canutec Transportation: 613-996-6666 Poison Control Centre: Consult local telephone directory for emergency number(s).
Material Uses	Unleaded gasoline is used in spark ignition engines including motor vehicles, inboard and outboard boat engines, small engines such as chain saws and lawn mowers, and recreational vehicles.		

Section 2. Composition and Information on Ingredients

			<i>Exposure Limits (ACGIH)</i>		
Name	CAS #	% (V/V)	TLV-TWA(8 h)	STEL	CEILING
Gasoline	8006-61-9	85-100	300 ppm (890 mg/m ³)	500 ppm (1480 mg/m ³)	Not established
Methyl tert-butyl ether	1634-04-4	0-15	40 ppm (144mg/m ³)	Not established	Not established
Note: Petro-Canada does not use MTBE in the manufacturing of its gasoline, however MTBE can be introduced from time to time through the use of external gasoline blendstocks.					
Manufacturer Recommendation	Not applicable				
Other Exposure Limits	Consult local, state, provincial or territory authorities for acceptable exposure limits.				

Section 3. Hazards Identification.

Potential Health Effects	Possible cancer hazard. Inhalation of vapours can be irritating to respiratory tract and cause CNS depression with symptoms of nausea, headaches, vomiting, dizziness, fatigue, light-headedness, reduced coordination, unconsciousness and possibly death. Skin and eye contact can cause irritation. Toxic if ingested. For more information, refer to Section 11.
---------------------------------	--

Section 4. First Aid Measures

Eye Contact	IMMEDIATELY flush eyes with running water for at least 15 minutes, keeping eyelids open. Seek medical attention if irritation persists.
Skin Contact	Remove contaminated clothing - launder before reuse. Wash gently and thoroughly the contaminated skin with running water and non-abrasive soap. Seek medical attention.
Inhalation	Evacuate the victim to a safe area as soon as possible. If the victim is not breathing, perform artificial respiration. Allow the victim to rest in a well ventilated area. Seek medical attention.
Ingestion	DO NOT induce vomiting because of danger of aspirating liquid into lungs. Seek medical attention.
Note to Physician	Not available

Section 5. Fire-fighting Measures

Flammability	Flammable liquid (NFPA).	Flammable Limits	Lower: 1.3%; Upper: 7.6% (NFPA).
Flash Points	Closed Cup: -50 to -38°C (-58 to -36°F), ASTM D56 Standard Test Method for Flash Point by Tag Closed Tester.	Auto-Ignition Temperature	257°C (495°F) (NFPA).
Fire Hazards in Presence of Various Substances	Extremely flammable in presence of open flames, sparks, and heat. Vapours are heavier than air and may travel considerable distance to sources of ignition and flash back. Rapid escape of vapour may generate static charge causing ignition.	Explosion Hazards in Presence of Various Substances	Do not cut, weld, heat, drill or pressurize empty container. Containers may explode in heat of fire. Vapours may form explosive mixtures with air.
Products of Combustion	Carbon oxides (CO, CO ₂), nitrogen oxides (NO _x), polynuclear aromatic hydrocarbons, phenols, smoke and irritating vapours as products of incomplete combustion.		
Fire Fighting Media and Instructions	NAERG96, GUIDE 128, flammable/combustible liquid (non-polar/water-immiscible). CAUTION: This product has a very low flash point, use of water spray when fighting fire may be inefficient. SMALL FIRE: Use DRY chemicals, CO ₂ , water spray or foam. LARGE FIRE: Use water spray, fog or foam. DO NOT use water jet. If tank, rail car or tank truck is involved in a fire, ISOLATE for 1600 meters (1 mile) in all directions; also, consider initial evacuation for 1600 meters (1 mile) in all directions. DO NOT extinguish a leaking gas flame unless leak can be stopped. Shut off fuel to fire if it is possible to do so without hazard. If this is impossible, withdraw from area and let fire burn out under controlled conditions. Withdraw immediately in case of rising sound from venting safety device or any discolouration of tank due to fire. Cool containing vessels with water spray in order to prevent pressure build-up, autoignition or explosion. Avoid flushing spilled material into sewers, streams or other bodies of water. Self-contained breathing apparatus (SCBA) will be required if approaching the fire from downwind, or to enter enclosed areas or buildings.		

Section 6. Accidental Release Measures

Material Release or Spill	NAERG96, GUIDE 128, flammable/combustible liquid (non-polar/water-immiscible). Evacuate in a downwind direction for at least 300 meters (1000 feet). ELIMINATE ALL IGNITION SOURCES. Ventilate closed spaces before entering. By forced ventilation, maintain concentration of vapour below the range of explosive mixture. Avoid contact, fully-encapsulating, vapour-protective clothing should be worn for spills and leaks with no fire. Stop leak if without risk. Use vapour suppressing foam or water spray to reduce vapours; it may reduce vapour, but it may not prevent ignition in closed spaces; isolate area until vapour has dispersed. Contain spill. Absorb with inert absorbents such as dry clay, or diatomaceous earth, or recover using electrically grounded explosion-proof pumps. Avoid inhaling dust of diatomaceous earth for it may contain silica (very fine particle size), making this a potential respiratory hazard. Place used absorbent in closed metal containers for later disposal or burn absorbent in a suitable combustion chamber. DO NOT FLUSH TO SEWERS, STREAMS OR OTHER BODIES OF WATER. Check with applicable jurisdiction for specific disposal requirements of spilled material and empty containers. Notify the appropriate authorities immediately.
----------------------------------	---

Section 7. Handling and Storage

Handling	Keep away from heat, spark and other sources of ignition. Empty container may contain flammable/explosive residues or vapours. DO NOT reuse empty containers without commercial cleaning or reconditioning. Ground/bond line and equipment during pumping or transfer to avoid accumulation of static charge. DO NOT USE AS CLEANING FLUID OR SIPHON BY MOUTH. Wear proper protective equipment. Avoid inhalation and contact with skin or eyes. Practice good personal hygiene. Wash hands after handling and before eating. Launder work clothes frequently. Discard saturated leather goods.
Storage	Store in cool, dry, isolated, well-ventilated area, and away from direct sunlight, sources of ignition and incompatibles. Flammable materials should be stored in a separate safety storage cabinet or room. Ground all equipment containing material.

Section 8. Exposure Controls/Personal Protection

Engineering Controls	For normal application, special ventilation is not necessary. If user's operations generate vapours or mist, use ventilation to keep exposure to airborne contaminants below the exposure limit. Make-up air should always be supplied to balance air removed by exhaust ventilation. Ensure that eyewash station and safety shower are close to work-station.
Personal Protection - The selection of personal protective equipment varies, depending upon conditions of use.	
Eyes	Eye protection (i.e., safety glasses, safety goggles and/or face shield) should be determined based on conditions of use. If product is used in an application where splashing may occur, the use of safety goggles and/or a face shield should be considered.
Body	Wear appropriate clothing to prevent skin contact. As a minimum long sleeves and trousers should be worn.

Respiratory Where concentrations in air may exceed the occupational exposure limits given in Section 2 (and those applicable to your area) and where engineering, work practices or other means of exposure reduction are not adequate, NIOSH approved respirators may be necessary to prevent overexposure by inhalation.

Hands Wear appropriate chemically protective gloves. When handling hot product ensure gloves are heat resistant and insulated.

Feet Wear appropriate footwear to prevent product from coming in contact with feet and skin.

Section 9. Physical and Chemical Properties

Physical State and Appearance	Clear liquid.	Viscosity	Not available
Colour	Clear to slightly yellow, undyed liquid. May be dyed red for taxation purposes.	Pour Point	Not applicable.
Odour	Gasoline. MTBE has a terpene-like odour.	Softening Point	Not applicable.
Odour Threshold	Less than 1 ppm.	Dropping Point	Not applicable.
Boiling Point	25 to 220°C (77 to 428°F) Initial boiling point by ASTM D86 Standard Test Method.	Penetration	Not applicable.
Density	0.7 kg/L @ 15°C (59°F).	Oil / Water Dist. Coefficient	Not available
Vapour Density	3 to 4 (Air = 1) (NFPA).	Ionicity (in water)	Insoluble in water.
Vapour Pressure	<107 kPa @ 37.8°C (100°F)	Dispersion Properties	Not available
Volatility	Volatile.	Solubility	Hydrocarbon components virtually insoluble in water. Soluble in alcohol, ether, chloroform, and benzene. Dissolves fats, oils and natural resins.

Section 10. Stability and Reactivity

Corrosivity	Non corrosive.		
Stability	The product is stable under normal handling and storage conditions.	Hazardous Polymerization	Will not occur under normal working conditions.
Incompatible Substances / Conditions to Avoid	Reactive with oxidizing agents, acids.	Decomposition Products	May release COx, NOx, phenols, polynuclear aromatic hydrocarbons, smoke and irritating vapours when heated to decomposition.

Section 11. Toxicological Information

Routes of Entry	Skin contact, eye contact, inhalation, and ingestion.
Acute Lethality	Gasoline: Acute oral toxicity (LD50): 13 600 mg/kg (rat). Acute dermal toxicity (LD50): >5000 mg/kg (rabbit). Acute inhalation toxicity (LC50): >300 000 mg/m ³ /4h (rat). MTBE: Acute oral toxicity (LD50): 29630 mg/kg (rat). Acute dermal toxicity (LD50): >6800 mg/kg (rabbit). Acute inhalation toxicity (LC50): 23 576 ppm/4h (rat).
Chronic or Other Toxic Effects	
Dermal Route:	This product can cause skin irritation. Prolonged or repeated contact with skin may cause dermatitis.
Inhalation Route:	Inhalation of vapours can be irritating to respiratory tract and cause CNS depression with symptoms of nausea, headaches, vomiting, dizziness, fatigue, light-headedness, reduced coordination, unconsciousness and possibly death.
Oral Route:	Swallowing or vomiting of the liquid may result in aspiration into the lungs. Can cause CNS depression. (See Inhalation Route for symptoms).
Eye Irritation/Inflammation:	Can cause irritation to the eyes.
Immunotoxicity:	Not available

Skin Sensitization:	This product is not expected to be a skin sensitizer, based on the available data and the known hazards of the components.
Respiratory Tract Sensitization:	This product is not expected to be a respiratory tract sensitizer, based on the available data and the known hazards of the components.
Mutagenic:	This product is not considered to be a mutagen, based on the available data and the known hazards of the components.
Reproductive Toxicity:	This product is not considered to be a reproductive hazard, based on the available data and the known hazards of the components.
Teratogenicity/Embryotoxicity:	This product is not considered to be a teratogen or an embryotoxin, based on the available data and the known hazards of the components.
Carcinogenicity (ACGIH):	ACGIH A3: animal carcinogen. [Gasoline, MTBE]
Carcinogenicity (IARC):	IARC Group 2B: possibly carcinogenic to humans. [Gasoline]
Carcinogenicity (NTP):	This product is not known to contain any chemicals at reportable quantities that are listed as carcinogens by NTP.
Carcinogenicity (IRIS):	Not available
Carcinogenicity (OSHA):	This product is not known to contain any chemicals at reportable quantities that are listed as carcinogens by OSHA.
Other Considerations	Unleaded gasoline caused kidney effects in male rats and liver effects in female mice.

Section 12. Ecological Information

Environmental Fate	Not available	Persistence/Bioaccumulation Potential	Not available
BOD5 and COD	Not available	Products of Biodegradation	Not available
Additional Remarks	Not available		


Section 13. Disposal Considerations

Waste Disposal	Preferred waste management priorities are: (1) recycle or reprocess; (2) incineration with energy recovery; (3) disposal at licensed waste disposal facility. Ensure that disposal or reprocessing is in compliance with government requirements and local disposal regulations. Consult your local or regional authorities.
-----------------------	--

Section 14. Transport Information

TDG Classification	GASOLINE, 3, UN1203, PGII (CL-TDG)	Special Provisions for Transport	See Transportation of Dangerous Goods Regulations.
---------------------------	------------------------------------	---	--

Section 15. Regulatory Information

Other Regulations		CEPA: This product is acceptable for use under the provisions of WHMIS-CPR. All components of this formulation are listed on the CEPA-DSL (Domestic Substances List). EPA: All components of this formulation are listed on the US EPA-TSCA Inventory.															
		This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all of the information required by the CPR. Please contact Product Safety for more information.															
DSD/DPD (Europe)		Not evaluated.		HCS (U.S.A.)	CLASS: Contains material which may cause cancer. CLASS: Flammable liquid having a flash point lower than 37.8°C (100°F). CLASS: Irritating substance. CLASS: Target organ effects.												
ADR (Europe) (Pictograms)		NOT EVALUATED FOR EUROPEAN TRANSPORT NON ÉVALUÉ POUR LE TRANSPORT EUROPÉEN.		DOT (U.S.A) (Pictograms)													
HMIS (U.S.A.)		<table><tr><td>Health Hazard</td><td>(2*)</td></tr><tr><td>Fire Hazard</td><td>(4)</td></tr><tr><td>Reactivity</td><td>(0)</td></tr></table>		Health Hazard	(2*)	Fire Hazard	(4)	Reactivity	(0)	NFPA (U.S.A.)	<table><tr><td rowspan="2">Health</td><td>4</td><td rowspan="2">Fire Hazard Reactivity</td></tr><tr><td>2</td><td>0</td></tr></table>	Health	4	Fire Hazard Reactivity	2	0	Rating 0 Insignificant 1 Slight 2 Moderate
Health Hazard	(2*)																
Fire Hazard	(4)																
Reactivity	(0)																
Health	4	Fire Hazard Reactivity															
	2		0														

Personal Protection

(H)

Specific hazard

3 High

4 Extreme

Section 16. Other Information**References**

Available upon request.

* Marque de commerce de Petro-Canada - Trademark

Glossary

ACGIH - American Conference of Governmental Industrial Hygienists
 ADR - Agreement on Dangerous goods by Road (Europe)
 ASTM - American Society for Testing and Materials
 BOD5 - Biological Oxygen Demand in 5 days
 CAN/CGA B149.2 Propane Installation Code
 CAS - Chemical Abstract Services
 CEPA - Canadian Environmental Protection Act
 CERCLA - Comprehensive Environmental Response, Compensation and Liability Act
 CFR - Code of Federal Regulations
 CHIP - Chemicals Hazard Information and Packaging Approved Supply List
 COD5 - Chemical Oxygen Demand in 5 days
 CPR - Controlled Products Regulations
 DOT - Department of Transport
 DSCl - Dangerous Substances Classification and Labeling (Europe)
 DSD/DPD - Dangerous Substances or Dangerous Preparations Directives (Europe)
 DSL - Domestic Substance List
 EEC/EU - European Economic Community/European Union
 EINECS - European Inventory of Existing Commercial Chemical Substances
 EPCRA - Emergency Planning and Community Right to Know Act
 FDA - Food and Drug Administration
 FIFRA - Federal Insecticide, Fungicide and Rodenticide Act
 HCS - Hazardous Communication System
 HMIS - Hazardous Material Information System
 IARC - International Agency for Research on Cancer

IRIS - Integrated Risk Information System
 LD50/LC50 - Lethal Dose/Concentration kill 50%
 LDLo/LCLo - Lowest Published Lethal Dose/Concentration
 NAERG'96 - North American Emergency Response Guide Book (1996)
 NFPA - National Fire Prevention Association
 NIOSH - National Institute for Occupational Safety & Health
 NPRI - National Pollutant Release Inventory
 NSNR - New Substances Notification Regulations (Canada)
 NTP - National Toxicology Program
 OSHA - Occupational Safety & Health Administration
 PEL - Permissible Exposure Limit
 RCRA - Resource Conservation and Recovery Act
 SARA - Superfund Amendments and Reorganization Act
 SD - Single Dose
 STEL - Short Term Exposure Limit (15 minutes)
 TDG - Transportation Dangerous Goods (Canada)
 TDLo/TCLo - Lowest Published Toxic Dose/Concentration
 TLM - Median Tolerance Limit
 TLV-TWA - Threshold Limit Value-Time Weighted Average
 TSCA - Toxic Substances Control Act
 USEPA - United States Environmental Protection Agency
 USP - United States Pharmacopoeia
 WHMIS - Workplace Hazardous Material Information System

For Copy of MSDS**Fuels & Solvents:**

Western Canada, telephone: 403-296-4158; fax: 403-296-6551

Ontario & Central Canada, telephone: 1-800-668-0220; fax: 1-800-837-1228

Quebec & Eastern Canada, telephone: 514-640-8308; fax: 514-640-8385

For Product Safety Information: (905) 804-4752








Prepared by Product Safety - JDW on 6/9/2004.

Data entry by Product Safety - RS.

To the best of our knowledge, the information contained herein is accurate. However, neither the above named supplier nor any of its subsidiaries assumes any liability whatsoever for the accuracy or completeness of the information contained herein. Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist.



Material Safety Data Sheet

WHMIS (Pictograms)	WHMIS (Classification)	Protective Clothing	TDG (pictograms)
 	B-2, D-2A, D-2B	   	

Section 1. Chemical Product and Company Identification

Product Name	JET B AVIATION TURBINE FUEL	Code	W219 SAP: 150, 151, 152
Synonym	Jet B; Jet B DI; JP-4; Jet F-40; NATO F-40; Turbine Fuel, Aviation, Wide Cut Type (CAN/CGSB-3.22).	Validated on	12/3/2001.
Manufacturer	PETRO-CANADA P.O. Box 2844 Calgary, Alberta T2P 3E3	In case of Emergency	Petro-Canada: 403-296-3000 Canutec Transportation: 613-996-6666 Poison Control Centre: Consult local telephone directory for emergency number(s).
Material Uses	Used as aviation turbine fuel. May contain a fuel system icing inhibitor.		

Section 2. Composition and Information on Ingredients

			Exposure Limits (ACGIH)		
Name	CAS #	% (V/V)	TLV-TWA(8 h)	STEL	CEILING
1) Complex mixture of petroleum hydrocarbons (C6-C14).	64741-41-9	>99	Not established	Not established	Not established
2) Benzene	71-43-2	<0.5	0.5 ppm	2.5 ppm	Not established
3) Fuel System Icing Inhibitor (FSII) (if added*): Diethylene Glycol Monomethyl Ether	111-77-3	≤0.15	Not established	Not established	Not established
4) Anti-static, antioxidant and metal deactivator additives.	Not applicable	<0.1	Not applicable	Not applicable	Not applicable
* Please note that Jet B DI, JP-4, Jet F-40 and NATO F-40 all contain Fuel System Icing Inhibitor (FSII).					
Manufacturer Recommendation	Not applicable				
Other Exposure Limits	Consult local, state, provincial or territory authorities for acceptable exposure limits.				

Section 3. Hazards Identification.

Potential Health Effects	Skin and eye contact can cause irritation. Inhalation of vapours can cause irritation of the respiratory tract and CNS depression with symptoms of nausea, headaches, vomiting, dizziness, fatigue, light-headedness, reduced coordination, unconsciousness and possibly death. Aspiration into the lungs may produce potentially fatal chemical pneumonitis (fluid in the lungs), severe lung damage, or respiratory failure. This product contains a cancer causing agent. For more information, refer to Section 11.
---------------------------------	---

Section 4. First Aid Measures

Eye Contact	IMMEDIATELY flush eyes with running water for at least 15 minutes, keeping eyelids open. Seek medical attention.
Skin Contact	Remove contaminated clothing - launder before reuse. Wash gently and thoroughly the contaminated skin with running water and non-abrasive soap. Seek medical attention.
Inhalation	Evacuate the victim to a safe area as soon as possible. If the victim is not breathing, perform artificial respiration. Allow the victim to rest in a well ventilated area. Seek medical attention.
Ingestion	DO NOT induce vomiting because of danger of aspirating liquid into lungs. Seek medical attention.
Note to Physician	Not available

Section 5. Fire-fighting Measures

Flammability	Flammable liquid (NFPA).	Flammable Limits	LOWER: 1.3% UPPER: 8% (NFPA)
Flash Points	CLOSED CUP: -31°C (-24°F) (NFPA)	Auto-Ignition Temperature	240°C (464°F) (NFPA)
Fire Hazards in Presence of Various Substances	Flammable in presence of open flames, sparks, and heat. Vapours are heavier than air and may travel considerable distance to sources of ignition and flash back. This product can accumulate static charge and ignite. May accumulate in confined spaces.	Explosion Hazards in Presence of Various Substances	Do not cut, weld, heat, drill or pressurize empty container. Containers may explode in heat of fire.
Products of Combustion	Carbon oxides (CO, CO ₂), nitrogen oxides (NO _x), sulphur oxides (SO _x), aldehydes, ketones, smoke and irritating vapours as products of incomplete combustion.		

**Fire Fighting
Media and
Instructions**

NAERG96, GUIDE 128, Flammable liquids (Non-polar/Water-immiscible).

CAUTION: This product has a very low flash point: Use of water spray when fighting fire may be inefficient.

If tank, rail car or tank truck is involved in a fire, ISOLATE for 800 meters (1/2 mile) in all directions; also consider initial evacuation for 800 meters (1/2 mile) in all directions.

SMALL FIRES: Dry chemical, CO₂, water spray or regular foam.

LARGE FIRES: Water spray, fog or regular foam. Do not use straight streams. Move containers from fire area if you can do it without risk.

Fires Involving Tanks or Car/Trailer Loads: Fight fire from maximum distance or use unmanned hose holders or monitor nozzles.

Cool containers with flooding quantities of water until well after fire is out. Withdraw immediately in case of rising sound from venting devices or any discolouration of tank. ALWAYS stay away from the ends of tanks. For massive fire, use unmanned hose holders or monitor nozzles; if this is impossible withdraw from area and let fire burn. Wear positive pressure self-contained breathing apparatus (SCBA). Structural firefighters' protective clothing will only provide limited protection.

Section 6. Accidental Release Measures**Material Release
or Spill**

NAERG96, GUIDE 128, Flammable Liquids (Non-polar/ Water-immiscible). ELIMINATE ALL IGNITION SOURCES. Avoid contact. Stop leak if without risk. Contain spill. Absorb with inert absorbents, dry clay, or diatomaceous earth. Avoid inhaling dust of diatomaceous earth for it may contain silica in very fine particle size, making this a potential respiratory hazard. Place used absorbent in closed metal containers for later disposal or burn absorbent in a suitable combustion chamber. DO NOT FLUSH TO SEWERS, STREAMS OR OTHER BODIES OF WATER. Check with applicable jurisdiction for specific disposal requirements of spilled material and empty containers. Notify the appropriate authorities immediately.

Section 7. Handling and Storage**Handling**

Keep away from heat. Keep away from sources of ignition. Empty containers pose a fire risk. DO NOT reuse empty containers without commercial cleaning or reconditioning. Ground/bond line and equipment during pumping or transfer to avoid accumulation of static charge. DO NOT ingest. Do not breathe gas/vapour/spray. In case of insufficient ventilation, wear suitable respiratory equipment. If ingested, seek medical advice immediately. Avoid contact with skin and eyes. Practice good personal hygiene. Wash hands after handling and before eating. Launder work clothes frequently. Discard saturated leather goods.

Storage

Store in tightly closed containers in cool, dry, isolated, well-ventilated area, and away from incompatibles. Ground all equipment containing material. Keep away from direct sunlight.

Section 8. Exposure Controls/Personal Protection**Engineering Controls**

For normal application, special ventilation is not necessary. If user's operations generate vapours or mist, use ventilation to keep exposure to airborne contaminants below the exposure limit. Make-up air should always be supplied to balance air removed by exhaust ventilation. Ensure that eyewash station and safety shower are close to work-station.

Personal Protection - *The selection of personal protective equipment varies, depending upon conditions of use.*

Eyes Eye protection (i.e., safety glasses, safety goggles and/or face shield) should be determined based on conditions of use. If product is used in an application where splashing may occur, the use of safety goggles and/or a face shield should be considered.

Body Wear appropriate clothing to prevent skin contact. As a minimum long sleeves and trousers should be worn.

Respiratory Where concentrations in air may exceed the occupational exposure limits given in Section 2 (and those applicable to your area) and where engineering, work practices or other means of exposure reduction are not adequate, NIOSH approved respirators may be necessary to prevent overexposure by inhalation.

Hands Wear appropriate chemically protective gloves. When handling hot product ensure gloves are heat resistant and insulated.

Feet Wear appropriate footwear to prevent product from coming in contact with feet and skin.

Section 9. Physical and Chemical Properties

Physical State and Appearance	Clear liquid.	Viscosity	Not available (similar to gasoline)
Colour	Clear and colourless.	Pour Point	Freezing Point: <-51°C (<-60°F) for Jet B/Jet B DI; <-58°C (<-72°F) for Jet Fuel F-40.
Odour	Gasoline like.	Softening Point	Not applicable.
Odour Threshold	Not available	Dropping Point	Not applicable.
Boiling Point	50 to 270°C (122 to 518°F)	Penetration	Not applicable.
Density	0.75 to 0.80 kg/L @ 15°C (59°F).	Oil / Water Dist. Coefficient	Not available
Vapour Density	3.5 (Air = 1)	Ionicity (in water)	Not available
Vapour Pressure	21 kPa (158 mmHg) @ 37.8°C (100°F).	Dispersion Properties	Not available
Volatility	Volatile.	Solubility	Insoluble in water. Partially miscible in some alcohols. Miscible in other petroleum solvents.

Section 10. Stability and Reactivity

Corrosivity	Not available		
Stability	The product is stable under normal handling and storage conditions.	Hazardous Polymerization	Will not occur under normal working conditions.
Incompatible Substances / Conditions to Avoid	Reactive with oxidizing agents and acids.	Decomposition Products	May release COx, NOx, SOx, aldehydes, ketones, smoke and irritating vapours when heated to decomposition.

Section 11. Toxicological Information

Routes of Entry	Skin contact, eye contact, inhalation and ingestion.		
Acute Lethality	<p>Based on toxicity of similar product. Acute oral toxicity (LD50): >20000 mg/kg (rat). Acute dermal toxicity (LD50): >5000 mg/kg (rabbit). Acute inhalation toxicity (LC50): >5000 mg/m³/4h (rat).</p> <p>Benzene Acute oral toxicity (LD50): 930 mg/kg (rat). Acute dermal toxicity (LD50): >9400 mg/kg (rabbit). Acute inhalation toxicity (LC50): 13200 ppm/4h (rat).</p> <p>Diethylene Glycol Monomethyl Ether Acute oral toxicity (LD50): 4140-5180 mg/kg (rat). Acute dermal toxicity (LD50): >2000 mg/kg (rabbit). Acute inhalation toxicity (LC50): >50000 mg/m³/4h (rat).</p>		
Chronic or Other Toxic Effects			
Dermal Route:	Skin contact can cause irritation.		
Inhalation Route:	Inhalation of vapours can cause irritation of the respiratory tract and CNS depression with symptoms of nausea, headaches, vomiting, dizziness, fatigue, light-headedness, reduced coordination, unconsciousness and possibly death.		
Oral Route:	Aspiration into the lungs may produce potentially fatal chemical pneumonitis (fluid in the lungs), severe lung damage, or respiratory failure.		
Eye Irritation/Inflammation:	Eye contact can cause irritation.		
Immunotoxicity:	Not available		
Skin Sensitization:	This product is not expected to be a skin sensitizer, based on the available data and the known hazards of the components.		
Respiratory Tract Sensitization:	This product is not expected to be a respiratory tract sensitizer, based on the available data and the known hazards of the components.		
Mutagenic:	Benzene is tumorigenic by RTECS criteria.		
Reproductive Toxicity:	This product is not expected to be a reproductive hazard, based on the available data and the known hazards of the components.		
Teratogenicity/Embryotoxicity:	Fetotoxicity, embryotoxicity and/or teratogenicity have been observed in rats or rabbits following oral or dermal administration, in the absence of maternal toxicity. [Diethylene Glycol Monomethyl Ether]		
Carcinogenicity (ACGIH):	ACGIH A1: confirmed human carcinogen. [Benzene]		
Carcinogenicity (IARC):	IARC Group 1: carcinogenic to Humans. [Benzene]		
Carcinogenicity (NTP):	NTP Group 1: known to be a carcinogen. [Benzene]		
Carcinogenicity (IRIS):	Not available		
Carcinogenicity (OSHA):	Benzene is an OSHA known carcinogen.		
Other Considerations	No additional remark.		

Section 12. Ecological Information

Environmental Fate	Not available	Persistence/ Bioaccumulation Potential	Not available
BOD5 and COD	Not available	Products of Biodegradation	Not available
Additional Remarks	No additional remark.		



Section 13. Disposal Considerations

Waste Disposal	Preferred waste management priorities are: (1) recycle or reprocess; (2) incineration with energy recovery; (3) disposal at licensed waste disposal facility. Ensure that disposal or reprocessing is in compliance with government requirements and local disposal regulations. Consult your local or regional authorities.
-----------------------	--

Section 14. Transport Information

TDG Classification	Currently: Fuel, aviation, turbine engine, 3, UN1863, PGII As of August 15, 2002: FUEL, AVIATION, TURBINE ENGINE, 3, UN1863, PGII	Special Provisions for Transport	Not applicable.
---------------------------	--	---	-----------------

Section 15. Regulatory Information

Other Regulations		This product is acceptable for use under the provisions of WHMIS-CPR. All components of this formulation are listed on the CEPA-DSL (Domestic Substances List).											
		All components of this formulation are listed on the US EPA-TSCA Inventory.											
		All components of this product are on the European Inventory of Existing Commercial Chemical Substances (EINECS).											
		This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all of the information required by the CPR.											
		Please contact Product Safety for more information.											
DSD/DPD (Europe)		Not evaluated.		HCS (U.S.A.) CLASS: Contains material which may cause cancer. CLASS: Flammable liquid having a flash point lower than 37.8°C (100°F). CLASS: Toxic. CLASS: Irritating substance. CLASS: Target organ effects.									
ADR (Europe) (Pictograms)		NOT EVALUATED FOR EUROPEAN TRANSPORT NON ÉVALUÉ POUR LE TRANSPORT EUROPÉEN.		DOT (U.S.A) (Pictograms) 									
HMIS (U.S.A.)		<table border="1"><tr><td>Health Hazard</td><td>2*</td></tr><tr><td>Fire Hazard</td><td>3</td></tr><tr><td>Reactivity</td><td>0</td></tr><tr><td>Personal Protection</td><td>H</td></tr></table>		Health Hazard	2*	Fire Hazard	3	Reactivity	0	Personal Protection	H	NFPA (U.S.A.) Health  Fire Hazard Reactivity Specific hazard	
Health Hazard	2*												
Fire Hazard	3												
Reactivity	0												
Personal Protection	H												
				Rating 0 Insignificant 1 Slight 2 Moderate 3 High 4 Extreme									

Section 16. Other Information

References	<p>Available upon request.</p> <p>* Marque de commerce de Petro-Canada - Trademark</p>		
Glossary	<div style="display: flex;"> <div style="flex: 1;"> <p>ACGIH - American Conference of Governmental Industrial Hygienists</p> <p>ADR - Agreement on Dangerous goods by Road (Europe)</p> <p>ASTM - American Society for Testing and Materials (</p> <p>BOD5 - Biological Oxygen Demand in 5 days</p> <p>CAN/CGA B149.2 Propane Installation Code</p> <p>CAS - Chemical Abstract Services</p> <p>CEPA - Canadian Environmental Protection Act</p> <p>CERCLA - Comprehensive Environmental Response, Compensation and Liability Act</p> <p>CFR - Code of Federal Regulations</p> <p>CHIP - Chemicals Hazard Information and Packaging Approved Supply List</p> <p>COD5 - Chemical Oxygen Demand in 5 days</p> <p>CPR - Controlled Products Regulations</p> <p>DOT - Department of Transport</p> <p>DSCL - Dangerous Substances Classification and Labeling (Europe)</p> <p>DSD/DPD - Dangerous Substances or Dangerous Preparations Directives (Europe)</p> <p>DSL - Domestic Substance List</p> <p>EEC/EU - European Economic Community/European Union</p> <p>EINECS - European Inventory of Existing Commercial Chemical Substances</p> <p>EPCRA - Emergency Planning and Community Right to Know Act</p> <p>FDA - Food and Drug Administration</p> <p>FIFRA - Federal Insecticide, Fungicide and Rodenticide Act</p> <p>HCS - Hazardous Communication System</p> <p>HMIS - Hazardous Material Information System</p> <p>IARC - International Agency for Research on Cancer</p> </div> <div style="flex: 1;"> <p>IRIS - Integrated Risk Information System</p> <p>LD50/LC50 - Lethal Dose/Concentration kill 50%</p> <p>LDLo/LCLo - Lowest Published Lethal Dose/Concentration</p> <p>NAERG'96 - North American Emergency Response Guide Book (1996)</p> <p>NFPA - National Fire Prevention Association</p> <p>NIOSH - National Institute for Occupational Safety & Health</p> <p>NPRI - National Pollutant Release Inventory</p> <p>NSNR - New Substances Notification Regulations (Canada)</p> <p>NTP - National Toxicology Program</p> <p>OSHA - Occupational Safety & Health Administration</p> <p>PEL - Permissible Exposure Limit</p> <p>RCRA - Resource Conservation and Recovery Act</p> <p>SARA - Superfund Amendments and Reorganization Act</p> <p>SD - Single Dose</p> <p>STEL - Short Term Exposure Limit (15 minutes)</p> <p>TDG - Transportation Dangerous Goods (Canada)</p> <p>TDLo/TCLo - Lowest Published Toxic Dose/Concentration</p> <p>TLm - Median Tolerance Limit</p> <p>TLV-TWA - Threshold Limit Value-Time Weighted Average</p> <p>TSCA - Toxic Substances Control Act</p> <p>USEPA - United States Environmental Protection Agency</p> <p>USP - United States Pharmacopoeia</p> <p>WHMIS - Workplace Hazardous Material Information System</p> </div> </div>		
For Copy of MSDS	Prepared by Product Safety - TAR on 12/3/2001.		

Western Canada, telephone: 403-296-4158; fax: 403-296-6551
Ontario & Central Canada, telephone: 1-800-668-0220; fax: 1-800-837-1228
Quebec & Eastern Canada, telephone: 514-640-8308; fax: 514-640-8385




Data entry by Product Safety - JDW.

For Product Safety Information: (905) 804-4752

To the best of our knowledge, the information contained herein is accurate. However, neither the above named supplier nor any of its subsidiaries assumes any liability whatsoever for the accuracy or completeness of the information contained herein. Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist.



Material Safety Data Sheet

WHMIS (Pictograms)	WHMIS (Classification)	Protective Clothing	TDG (pictograms)
	Not controlled		

Section 1. Chemical Product and Company Identification

Product Name	PETRO-CANADA SUPREME 5W-30, 10W-30, 10W-40, 20W-50 MOTOR OIL	Code	410-344, MOSP53 410-341, MOSP13 410-342, MOSP14 410-343, MOSP25
Synonym	Not available.	Validated on	8/31/2004.
Manufacturer	PETRO-CANADA P.O. Box 2844 Calgary, Alberta T2P 3E3	In case of Emergency	Petro-Canada: 403-296-3000 Canutec Transportation: 613-996-6666 Poison Control Centre: Consult local telephone directory for emergency number(s).
Material Uses	Supreme is designed for the lubrication of all gasoline, propane and CNG engines where the manufacturer recommends the use of API SM quality oils. SAE 5W-30 and 10W-30 grades also meet the requirements of ILSAC GF-4.		

Section 2. Composition and Information on Ingredients

			<i>Exposure Limits (ACGIH)</i>		
Name	CAS #	% (W/W)	TLV-TWA(8 h)	STEL	CEILING
Mixture of severely hydrotreated and hydrocracked base oil (petroleum) and other proprietary, non-hazardous additives.	Mixture	100	5 mg/m ³ (oil mist)	10 mg/m ³ (oil mist)	Not established
Manufacturer Recommendation	Not applicable				
Other Exposure Limits	Consult local, state, provincial or territory authorities for acceptable exposure limits.				

Section 3. Hazards Identification.

Potential Health Effects	Prolonged or repeated contact may cause skin irritation, defatting, drying and dermatitis. Not expected to cause more than slight skin or eye irritation. With its relatively low vapour pressure, this product is not expected to be inhaled in any appreciable quantity at ambient conditions. If heated to high temperatures or subjected to mechanical actions which produce vapours or mists, inhalation may cause respiratory tract irritation. Ingestion may produce a laxative effect. For more information refer to Section 11 of this MSDS.
---------------------------------	---

Section 4. First Aid Measures

Eye Contact	IMMEDIATELY flush eyes with running water for at least 15 minutes, keeping eyelids open. Seek medical attention.
Skin Contact	Remove contaminated clothing - launder before reuse. Wash gently and thoroughly the contaminated skin with running water and non-abrasive soap. Seek medical attention.
Inhalation	Evacuate the victim to a safe area as soon as possible. If the victim is not breathing, perform artificial respiration. Allow the victim to rest in a well ventilated area. Seek medical attention.
Ingestion	DO NOT induce vomiting because of danger of aspirating liquid into lungs. Seek medical attention.
Note to Physician	Not available

Section 5. Fire-fighting Measures

Flammability	May be combustible at high temperature.	Flammable Limits	Not available.
Flash Points	OPEN CUP: 223°C (433.4°F) (Cleveland)	Auto-Ignition Temperature	Not available
Fire Hazards in Presence of Various Substances	Low fire hazard. This material must be heated before ignition will occur.	Explosion Hazards in Presence of Various Substances	Do not cut, weld, heat, drill or pressurize empty container. Containers may explode in heat of fire.

Products of Combustion	Carbon oxides (CO, CO ₂), nitrogen oxides (NO _x), sulphur oxides (SO _x), calcium oxides (CaO _x), phosphorus compounds (PO _x), zinc oxides, boron oxides and molybdenum, smoke and irritating vapours as products of incomplete combustion.
Fire Fighting Media and Instructions	NAERG96, GUIDE 171, Substances (low to moderate hazard). If tank, rail car or tank truck is involved in a fire, ISOLATE for 800 meters (0.5 mile) in all directions; also, consider initial evacuation for 800 meters (0.5 mile) in all directions. Shut off fuel to fire if it is possible to do so without hazard. If this is impossible, withdraw from area and let fire burn out under controlled conditions. Withdraw immediately in case of rising sound from venting safety device or any discolouration of tank due to fire. Cool containing vessels with water spray in order to prevent pressure build-up, autoignition or explosion. SMALL FIRE: use DRY chemicals, foam, water spray or CO ₂ . LARGE FIRE: use water spray, fog or foam. For small outdoor fires, portable fire extinguishers may be used, and self contained breathing apparatus (SCBA) may not be required. For all indoor fires and any significant outdoor fires, SCBA is required. Respiratory and eye protection are required for fire fighting personnel.

Section 6. Accidental Release Measures

Material Release or Spill	Consult current National Emergency Response Guide Book (NAERG) for appropriate spill measures if necessary. Extinguish all ignition sources. Stop leak if safe to do so. Dike spilled material. Use appropriate inert absorbent material to absorb spilled product. Collect used absorbent for later disposal. Avoid contact with spilled material. Avoid contaminating sewers, streams, rivers and other water courses with spilled material. Notify appropriate authorities immediately.
----------------------------------	--

Section 7. Handling and Storage

Handling	Avoid contact with any sources of ignition, flames, heat, and sparks. Avoid skin contact. Avoid eye contact. Avoid inhalation of product vapours or mists. Empty containers may contain product residue. Do not pressurize, cut, heat, or weld empty containers. Do not reuse containers without commercial cleaning and/or reconditioning. Personnel who handle this material should practice good personal hygiene during and after handling to help prevent accidental ingestion of this product. Properly dispose of contaminated leather articles including shoes that cannot be decontaminated.
Storage	Store away from incompatible and reactive materials (See section 5 and 10). Keep container tightly closed. Store in dry, cool, well-ventilated area.

Section 8. Exposure Controls/Personal Protection

Engineering Controls	For normal application, special ventilation is not necessary. If user's operations generate vapours or mist, use ventilation to keep exposure to airborne contaminants below the exposure limit. Make-up air should always be supplied to balance air removed by exhaust ventilation. Ensure that eyewash station and safety shower are close to work-station.
Personal Protection - The selection of personal protective equipment varies, depending upon conditions of use.	
Eyes	Eye protection (i.e., safety glasses, safety goggles and/or face shield) should be determined based on conditions of use. If product is used in an application where splashing may occur, the use of safety goggles and/or a face shield should be considered.
Body	Wear appropriate clothing to prevent skin contact. As a minimum long sleeves and trousers should be worn.
Respiratory	Where concentrations in air may exceed the occupational exposure limits given in Section 2 (and those applicable to your area) and where engineering, work practices or other means of exposure reduction are not adequate, NIOSH approved respirators may be necessary to prevent overexposure by inhalation.
Hands	Wear appropriate chemically protective gloves. When handling hot product ensure gloves are heat resistant and insulated.
Feet	Wear appropriate footwear to prevent product from coming in contact with feet and skin.

Section 9. Physical and Chemical Properties

Physical State and Appearance	Viscous liquid.	Viscosity	5W-30: 62.3 cSt @ 40°C (104°F), 10.6 cSt @ 100°C (212°F). VI=160 10W-30: 67.4 cSt @ 40°C (104°F), 10.5 cSt @ 100°C (212°F). VI=143 10W-40: 97.2 cSt @ 40°C (104°F), 14.1 cSt @ 100°C (212°F). VI=143 20W-50: 170 cSt @ 40°C (104°F), 19.0 cSt @ 100°C (212°F). VI=127
Colour	Light amber.	Pour Point	5W-30: -36°C (-33°F) 10W-30: -36°C (-33°F) 10W-40: -30°C (-22°F) 20W-50: -24°C (-11°F)
Odour	Mild petroleum oil like.	Softening Point	Not applicable.
Odour Threshold	Not available.	Dropping Point	Not applicable.
Boiling Point	Not available.	Penetration	Not applicable.

Density	0.8566 - 0.8775 kg/L @ 15°C (59°F).	Oil / Water Dist. Coefficient	Not available.
Vapour Density	Not available.	Ionicity (in water)	Not available
Vapour Pressure	Negligible at ambient temperature and pressure.	Dispersion Properties	Not available
Volatility	Non-volatile	Solubility	Insoluble in water.

Section 10. Stability and Reactivity

Corrosivity	Copper corrosion, 3h, 121°C (ASTM D0130): 1a		
Stability	The product is stable under normal handling and storage conditions.	Hazardous Polymerization	Will not occur under normal working conditions.
Incompatible Substances / Conditions to Avoid	Reactive with oxidizing agents and acids.	Decomposition Products	May release CO _x , H ₂ S, methacrylate monomers, alkyl mercaptans, smoke and irritating vapours when heated to decomposition.

Section 11. Toxicological Information

Routes of Entry	Skin contact, eye contact, inhalation, and ingestion.		
Acute Lethality	<p>Acute toxicity information is not available for the product as a whole, therefore, data for some of the ingredients is provided below:</p> <p>Acute oral toxicity (LD50): >5000 mg/kg (rat).</p> <p>Acute dermal toxicity (LD50): >2000 mg/kg (rabbit).</p> <p>Acute inhalation toxicity (LC50): >2500 mg/m³/4h (rat).</p>		
Chronic or Other Toxic Effects			
Dermal Route:	Prolonged or repeated contact may defat and dry skin, and cause dermatitis. Short-term exposure is expected to cause only slight irritation, if any.		
Inhalation Route:	With its relatively low vapour pressure, this product is not expected be inhaled in any appreciable quantity at ambient conditions. If heated to high temperatures or subjected to mechanical actions which produce vapours or mists, inhalation may cause respiratory tract irritation.		
Oral Route:	Ingestion of this product may lead to aspiration of the liquid, especially if vomiting occurs. This may result in chemical pneumonitis (inflammation of the lungs) and/or pulmonary edema (an accumulation of fluid in the lungs). May produce a laxative effect.		
Eye Irritation/Inflammation:	Short-term exposure is expected to cause only slight irritation, if any.		
Immunotoxicity:	Not available.		
Skin Sensitization:	Contact with this product is not expected to cause skin sensitization, based upon the available data and the known hazards of the components.		
Respiratory Tract Sensitization:	Contact with this product is not expected to cause respiratory tract sensitization, based upon the available data and the known hazards of the components.		
Mutagenic:	This product is not known to contain any components at >= 0.1% that have been shown to cause mutagenicity. Therefore, based upon the available data and the known hazards of the components, this product is not expected to be a mutagen.		
Reproductive Toxicity:	This product is not known to contain any components at >= 0.1% that have been shown to cause reproductive toxicity. Therefore, based upon the available data and the known hazards of the components, this product is not expected to be a reproductive toxin.		
Teratogenicity/Embryotoxicity:	This product is not known to contain any components at >= 0.1% that have been shown to cause teratogenicity and/or embryotoxicity. Therefore, based upon the available data and the known hazards of the components, this product is not expected to be a teratogen/embryotoxin.		
Carcinogenicity (ACGIH):	This product is not known to contain any chemicals at reportable quantities that are listed as Group A1 or A2 carcinogens by ACGIH.		
Carcinogenicity (IARC):	This product is not known to contain any chemicals at reportable quantities that are listed as Group 1, 2A, or 2B carcinogens by IARC.		
Carcinogenicity (NTP):	This product is not known to contain any chemicals at reportable quantities that are listed as carcinogens by NTP.		
Carcinogenicity (IRIS):	This product is not known to contain any chemicals at reportable quantities that are listed as carcinogens by IRIS.		
Carcinogenicity (OSHA):	This product is not known to contain any chemicals at reportable quantities that are listed as carcinogens by OSHA.		
Other Considerations	No additional remark.		

Section 12. Ecological Information

Environmental Fate	Not available	Persistence/Bioaccumulation Potential	Not available
BOD5 and COD	Not available.	Products of Biodegradation	Not available.
Additional Remarks	No additional remark.		



Section 13. Disposal Considerations

Waste Disposal	Spent/ used/ waste product may meet the requirements of a hazardous waste. Consult your local or regional authorities. Ensure that waste management processes are in compliance with government requirements and local disposal regulations.
-----------------------	--

Section 14. Transport Information

TDG Classification	Not a hazardous material for transport according to the TDG Regulations. (Canada)	Special Provisions for Transport	Not applicable.
---------------------------	---	---	-----------------

Section 15. Regulatory Information

Other Regulations		This product is acceptable for use under the provisions of WHMIS-CPR. All components of this formulation are listed on the CEPA-DSL (Domestic Substances List).												
		All components of this formulation are listed on the US EPA-TSCA Inventory.												
		All components of this product are on the European Inventory of Existing Commercial Chemical Substances (EINECS).												
		This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all of the information required by the CPR.												
		Please contact Product Safety for more information.												
DSD/DPD (Europe)		Not evaluated.		HCS (U.S.A.)	Does not meet the definitions of a health or physical hazard according to the OSHA - Hazard Communication Standard. (United States)									
ADR (Europe) (Pictograms)		NOT EVALUATED FOR EUROPEAN TRANSPORT NON ÉVALUÉ POUR LE TRANSPORT EUROPÉEN.		DOT (U.S.A) (Pictograms)										
HMIS (U.S.A.)		<table><tr><td>Health Hazard</td><td>1</td></tr><tr><td>Fire Hazard</td><td>1</td></tr><tr><td>Reactivity</td><td>0</td></tr><tr><td>Personal Protection</td><td>B</td></tr></table>		Health Hazard	1	Fire Hazard	1	Reactivity	0	Personal Protection	B	NFPA (U.S.A.) Health  Fire Hazard Reactivity Specific hazard		Rating 0 Insignificant 1 Slight 2 Moderate 3 High 4 Extreme
Health Hazard	1													
Fire Hazard	1													
Reactivity	0													
Personal Protection	B													

Section 16. Other Information

References	<p>Available upon request.</p> <p>* Marque de commerce de Petro-Canada - Trademark</p>
-------------------	--

Glossary

ACGIH - American Conference of Governmental Industrial Hygienists	IRIS - Integrated Risk Information System
ADR - Agreement on Dangerous goods by Road (Europe)	LD50/LC50 - Lethal Dose/Concentration kill 50%
ASTM - American Society for Testing and Materials	LDLo/LCLo - Lowest Published Lethal Dose/Concentration
BOD5 - Biological Oxygen Demand in 5 days	NAERG'96 - North American Emergency Response Guide Book (1996)
CAN/CGA B149.2 Propane Installation Code	NFPA - National Fire Prevention Association
CAS - Chemical Abstract Services	NIOSH - National Institute for Occupational Safety & Health
CEPA - Canadian Environmental Protection Act	NPRI - National Pollutant Release Inventory
CERCLA - Comprehensive Environmental Response, Compensation and Liability Act	NSNR - New Substances Notification Regulations (Canada)
CFR - Code of Federal Regulations	NTP - National Toxicology Program
CHIP - Chemicals Hazard Information and Packaging Approved Supply List	OSHA - Occupational Safety & Health Administration
COD5 - Chemical Oxygen Demand in 5 days	PEL - Permissible Exposure Limit
CPR - Controlled Products Regulations	RCRA - Resource Conservation and Recovery Act
DOT - Department of Transport	SARA - Superfund Amendments and Reorganization Act
DSDL - Dangerous Substances Classification and Labeling (Europe)	SD - Single Dose
DSD/DPD - Dangerous Substances or Dangerous Preparations	STEL - Short Term Exposure Limit (15 minutes)
	TDG - Transportation Dangerous Goods (Canada)
	TDLo/TCLo - Lowest Published Toxic Dose/Concentration

Directives (Europe)
DSL - Domestic Substance List
EEC/EU - European Economic Community/European Union
EINECS - European Inventory of Existing Commercial Chemical Substances
EPCRA - Emergency Planning and Community Right to Know Act
FDA - Food and Drug Administration
FIFRA - Federal Insecticide, Fungicide and Rodenticide Act
HCS - Hazard Communication Standard
HMIS - Hazardous Material Information System
IARC - International Agency for Research on Cancer

TLM - Median Tolerance Limit
TLV-TWA - Threshold Limit Value-Time Weighted Average
TSCA - Toxic Substances Control Act
USEPA - United States Environmental Protection Agency
USP - United States Pharmacopoeia
WHMIS - Workplace Hazardous Material Information System

For Copy of MSDS

The Canadian Controlled Products Regulations (CPR) (Under the Hazardous Products Act, part of the WHMIS legislation) only apply to WHMIS Controlled (i.e., hazardous) products. Therefore, the CPR and the 3-year update rule specified therein do not apply to WHMIS Non-Controlled products. Although this is true, customarily Petro-Canada reviews and updates Non-Controlled product MSDS if a customer requests such an update. These Non-Controlled product updates are given a lower priority than Controlled products but are handled as soon as practicable. If you would like to verify if the MSDS you have is the most current, or you require any further information, please contact:

Internet: www.petro-canada.ca

Lubricants:

Western Canada, telephone: 1-800-661-1199; fax: (780) 464-9564

Ontario & Central Canada, telephone: 1-800-268-5850 and (905) 822-4222; fax: 1-800-201-6285


Quebec & Eastern Canada, telephone: 1-800-576-1686; fax: 800-201-6285

For Product Safety Information: (905) 804-4752

Prepared by Product Safety - TLM on 8/31/2004.

Data entry by Product Safety - RS.

To the best of our knowledge, the information contained herein is accurate. However, neither the above named supplier nor any of its subsidiaries assumes any liability whatsoever for the accuracy or completeness of the information contained herein. Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist.



Poly-Drill Drilling Systems

1824 - 104 Avenue, S.W.
Calgary, Alberta, Canada T2W-OA8
(403) 259-5112 FAX (403) 255-7185
email: polydril@telus.net
www.poly-drill.com

poly-drill.com



MATERIAL SAFETY DATA SHEET/FICHE SIGNALÉTIQUE

1. PRODUCT IDENTIFICATION

PRODUCT TRADE NAME(S): Poly Drill O.B.X.

WHMIS CLASSIFICATION: Non-regulated

TDG Classification: Non dangerous goods

DATE: November 17, 2004

A liquid polymer containing guar gum, mineral oil, vegetable oil, acrylamide copolymer and a surfactant: Evaluation of the ingredient(s) has found no ingredient(s) hazardous as per WHMIS regulations.

2. PHYSICAL DATA

Boiling Point: Not available

Specific Gravity: 0.9 g/cm

Solubility in Water: disperses in water(forms viscous, slippery solution).

pH: 3.8 (1% concentration)

Density (g/ml): Not available

Physical State: Liquid

Appearance and Odor: Brown. Odor slight.

3. FIRE AND EXPLOSION DATA

Flash Point (method used): (PMCC) greater than 100 C.

Conditions of flammability: Very low risk.

Hazardous combustion products: None known.

Upper and Lower flammable limits: Not available.

Extinguishing media: Carbon dioxide, dry chemicals, foam, in preference to water spray

4. REACTIVITY

Chemical stability: Stable under normal conditions.

Hazardous Polymerization: Will not occur.

Incompatible substances: Avoid strong oxidants such as liquid chlorine, concentrated oxygen, sodium or calcium hypo chloride.

Hazardous decomposition products: None known

5. HEALTH HAZARD DATA

TOXICITY RATING: Practically non-harmful.

Routes of Exposure and Effects:

SKIN: Slight irritant: prolonged contact may cause skin irritation or dermatitis in some individuals

EYE: No effects of exposure expected with the exception of possible irritation.

INHALATION: Due to low volatility of mineral distillates a small inhalation hazard exists.

INGESTION: can cause nausea, vomiting, cramps, diarrhea
Chronic exposure limits: None
Sensitization of product: Not suspected to be a sensitizer.
Teratogenicity: Not available.
Mutagenicity: Not available.
Carcinogenicity: None of the components of this product are listed as carcinogens by IARC and ACGIH

6. EMERGENCY AND FIRST AID PROCEDURES

SKIN: Wash exposed area with soap and water. Remove contaminated clothing. Launder contaminated clothing before re-use. If irritation or abnormalities persist, call a physician.

EYE: Immediately flush eyes with water for 15 minutes, lifting upper and lower lids occasionally. Get medical attention.

INHALATION: Remove to fresh air. If breathing becomes difficult, give oxygen and call a physician.

INGESTION: Do not induce vomiting: Call a physician immediately or poison control center. Never give anything by mouth to an unconscious person. Seek medical advice.

8. INDUSTRIAL HYGIENE CONTROL MEASURES

Respiratory Protection: None normally required.

Ventilation: If mist and/or vapors are present, use air purifying respirator or self-contained breathing apparatus, but this is rarely required.

Eye Protection: Safety glasses, if personally preferred

Gloves: Generally not necessary. Personal preference.

7. HANDLING AND USE PRECTIONS

Storage requirements: keep container closed when no in use. Store in a cool dry location away from oxidizing and reducing agents.

Waste Disposal: product should be disposed of in accordance with applicable local, Provincial and Federal regulations.

Steps must be taken if product is released or spilled: clean spill areas thoroughly to avoid hazardous slippery conditions.

8. TOXICOLOGICAL PROPERTIES

G50 Microtox Analysis prepared by HydroQual Laboratories, Calgary, AB--97/6/26 Test#970978:

Test Description	EC20	EC50	Pass/Fail
MTX	>91	>91	PASS

9. DEPARTMENT OF TRANSPORTATION INFORMATION

PROPER SHIPPING NAME/HAZARD CLASS MAY VARY BY PACKAGING, PROPERTIES, AND MODE OF TRANSPORTATION. TYPICAL PROPER SHIPPING NAMES FOR THIS PRODUCT ARE:

ALL TRANSPORTATION MODES: PRODUCT IS NOT REGULATED DURING TRANSPORTATION


Shipping Name: Liquid Drilling Additive

Hazard Class: Not hazardous

Hazardous Substances: None
Cautionary Labeling: None required

10. OTHER INFORMATION

This information contained herein is given in good faith, but no warranty, expressed or implied is made



Poly-Drill Drilling Systems

1824 - 104 Avenue, S.W.
Calgary, Alberta, Canada T2W-OA8
(403) 259-5112 FAX (403) 255-7185
email: polydril@telus.net
www.poly-drill.com

poly-drill.com



MATERIAL SAFETY DATA SHEET/FICHE SIGNALÉTIQUE

1. PRODUCT IDENTIFICATION

PRODUCT TRADE NAME: Poly-Drill 133-X
PRODUCT DESCRIPTION: LIQUID ANIONIC POLYMER
CHEMICAL DESCRIPTION: Polymer, Surfactant(s), Water, Hydrocarbon solvent
UPDATED: March 15, 2004

NFPA704M/HMIS RATING

HEALTH: 0/1	FLAMMABILITY: 1/1	REACTIVITY: 0/0	OTHER:
0=Insignificant	1=Slight 2=Moderate	3=High	4=Extreme

2. COMPOSITION

A liquid polymer: Evaluation of the ingredient(s) has found no ingredient(s) hazardous as per WHMIS regulations. None of the substances in this product are hazardous.

3. PHYSICAL DATA

Flash Point: >100°C (PMCC)
Specific Gravity (@ 25°C.): 1.08
Solubility in Water: Emulsifiable
pH: 8.1 (1.0% solution)
Freeze Point: -10 °C (14 Degrees F)
Density (g/ml): 1.08 at 25 °C
Physical State: Liquid
Appearance: Blue liquid
Odor: Hydrocarbon

Note: These physical properties are typical values for this product.

4. FIRE AND EXPLOSION DATA

INCOMPATIBILITY: Avoid contact with strong oxidizers (eg. Chlorine, peroxides, chromates, nitric acid, perchlorates, concentrated oxygen, permanganates) which can generate heat, fires, explosions and the release of toxic fumes.

THERMAL DECOMPOSITION PRODUCTS: In the event of combustion CO, oxides of carbon (COx), oxides of nitrogen (NOx) may be formed. Do not breathe smoke or fumes. Wear suitable protective equipment.

5. FIRE FIGHTING MEASURES

FLASH POINT: >100°C (PMCC)

EXTINGUISHING MEDIA: Based on the NFPA guide, use dry chemical, foam, carbon dioxide or other extinguishing agent suitable for Class B fires. Use water to cool containers exposed to fire. For larger fires, use water spray or fog, thoroughly drenching the burning material.

UNSUITABLE EXTINGUISHING MEDIA:
Do not use water unless flooding amounts are available.

UNUSUAL FIRE AND EXPLOSION HAZARD: May evolve oxides of nitrogen (NOx) under fire conditions.

6. HEALTH HAZARD DATA

EMERGENCY OVERVIEW:

CAUTION: May cause irritation to skin and eyes. Avoid contact with skin, eyes and clothing. Do not take internally.

Empty containers may contain residual product. Do not reuse container unless properly reconditioned.

PRIMARY ROUTE(S) OF EXPOSURE: Eye & Skin

EYE CONTACT: Can cause mild to moderate irritation

SKIN CONTACT: Can cause mild, short-lasting irritation

SYMPTOMS OF EXPOSURE: A review of available data does not identify any symptoms from exposure not previously mentioned.

AGGRAVATION OF EXISTING CONDITIONS: A review of available data does not identify any worsening of existing conditions.

7. EMERGENCY AND FIRST AID PROCEDURES

SKIN: Wash exposed area with soap and water. If irritation or abnormalities persist, call a physician.

EYE: Immediately flush eyes with water for 15 minutes, if irritation or abnormalities persist, call a physician.

INHALATION: Remove to fresh air. If breathing becomes difficult, give oxygen and call a physician.

INGESTION: Do not induce vomiting: Call a physician immediately.

CAUTION: If unconscious, having trouble breathing or in convulsions, do not induce vomiting or give water. Call for medical assistance immediately.

8. HANDLING, ACCIDENTAL RELEASE MEASURES & DISPOSAL CONSIDERATIONS

Storage: Keep container tightly closed when not in use.

DISPOSAL:

In Ontario, the waste class under Regulation 347 is: 233L

SMALL SPILLS:

Soak up spill with absorbent material. Place residues in a suitable, covered, properly labeled container. Wash affected area.

LARGE SPILLS:

Contain liquid using absorbent material, by digging trenches or by dyking. Reclaim into recovery or salvage drums or tank truck for proper disposal. Contact approved waste hauler for disposal of contaminated recovered material. Dispose of material in compliance with regulations indicated.

Dispose of wastes in an approved incinerator or waste treatment/disposal site, in accordance with all applicable regulations. Do not dispose of wastes in local sewer or with normal garbage.

ENVIRONMENTAL PRECAUTIONS

This product should NOT be directly discharged into lakes, ponds, streams, waterways or public water supplies.

As a non-hazardous liquid waste, it should be solidified with stabilizing agents (such as sand, fly ash, or cement) so that no free liquid remains before disposal to an industrial waste landfill. A non-hazardous liquid waste can also be incinerated in accordance with local, state, provincial and federal regulations.

9. INDUSTRIAL HYGIENE CONTROL MEASURES

OCCUPATIONAL EXPOSURE LIMITS:

This product does not contain any substance that has an established exposure limit.

Respiratory Protection: None normally required.

For large spills, entry into large tanks, vessels or enclosed small spaces with inadequate ventilation, a positive pressure, self-contained breathing apparatus is recommended.

Ventilation: General ventilation is recommended.

Eye Protection: Safety glasses, if personally preferred

Gloves: Generally not necessary. Personal preference. Examples of impermeable gloves available on the market are neoprene, nitrile, PVC, natural rubber, viton, and butyl (compatibility studies have not been performed).

If clothing is contaminated, remove clothing and thoroughly wash the affected area. Launder contaminated clothing before reuse.

10. TOXICOLOGICAL PROPERTIES

SENSITIZATION:

This product is not expected to be a sensitizer.

A "LC50-96" Pass/Fail Bioassay test. This test determines the lethality of a fluid on young aquatic organisms. The fluid fails if 50% or more of the animals are dead after 96 hours in the fluid.

96 hour static acute LC50 to Rainbow Trout = Greater than 1,000 mg/L

96 hour no observed effect concentration = 125 mg/L based on no mortality or abnormal effects

96 hour static acute LC50 to Sheepshead Minnow = Greater than 1,000 mg/L

96 hour no observed effect concentration = 1,000 mg/L (highest concentration tested) based on no mortality or abnormal effects.

96 hour static acute LC50 to Mysid Shrimp = 400 mg/L

96 hour no observed effect concentration = 180 mg/L based on no mortality or abnormal effects.

96 hour static acute LC50 to Daphnia Magna - 400 mg/L

96 hour no observed effect concentration = 56 mg/L (lowest concentration tested) based on no mortality or abnormal effects.

Microtoxicity

The Microtox bioassay has been established as the reference test for mud additive toxicity testing.

Test Method: Luminescent Bacteria, IC50@ 15 min

Reference: Appendix 1: Microtox Bioassay Procedure, Drilling Waste Management, Guide G50. 1993. Alberta Energy and Utilities Board, Calgary, AB, Canada.

Sample: Poly Drill 1330, sample #97324-1 for test #970723, 97/05/09 by D. Lintott

Preparation: Sample was diluted to 2 g/L, which formed thick, slightly cloudy liquid. The sample was then centrifuged for 1 hour.

Test Results:

SAMPLE	TREATMENT	%CTL	IC20%	IC50	RESULT
97324-1	None	N/A	14 (9-22)	>91	PASS

The following results are for a 1% aqueous solution of product.

CARCINOGENICITY:

None of the substances in this product are listed as carcinogens by the International Agency for Research on Cancer (IARC), the National Toxicology Program (NTP) or the American Conference of Government Industrial Hygienists (ACGIH).

HUMAN HAZARD CHARACTERIZATION:

Based on our Hazard Characterization, the potential human hazard is: LOW

ENVIRONMENTAL HAZARD AND EXPOSURE CHARACTERIZATION:

Based on our Hazard Characterization, the potential environmental hazard is: LOW.

11. DEPARTMENT OF TRANSPORTATION INFORMATION

PROPER SHIPPING NAME/HAZARD CLASS MAY VARY BY PACKAGING, PROPERTIES, AND MODE OF TRANSPORTATION. TYPICAL PROPER SHIPPING NAMES FOR THIS PRODUCT ARE:

ALL TRANSPORTATION MODES: PRODUCT IS NOT REGULATED DURING TRANSPORTATION

Shipping Name: Liquid Drilling Additive

Hazard Class: Not hazardous

Cautionary Labeling: None required

14. OTHER INFORMATION

This information contained herein is given in good faith, but no warranty, expressed or implied is made

SECTION 1 – PRODUCT INFORMATION

Product Name: Propane
Trade Name: LPG (Liquified Petroleum Gas), LP-Gas
Chemical Formula: C₃H₈

WHMIS CLASSIFICATION
 Class A - Compressed Gas
 Class B, Division 1 - Flammable Gas

Supplier: Superior Propane Inc.
 1111 - 49th Avenue N.E.
 Calgary, AB T2E 8V2
Business: (403) 730-7500

Local Market
Emergency Number: _____
 (Non Medical)

Application and Use: Propane is commonly used as a fuel for heating, cooking, automobiles, forklift trucks, crop drying and welding and cutting operations. Propane is used in industry as a refrigerant, solvent and as a chemical feedstock.

SECTION 2 – HAZARDOUS INGREDIENTS

COMPONENTS	CAS NO.	% Volume (v/v)	LD50
Propane	74 -98-6	90% - 99%	Not Applicable
Propylene	115 -07-1	0% - 5%	Not Applicable
Ethane	74 -84-0	0% - 5%	Not Applicable
Butane and heavier hydro carbons	106 -97-8	0% - 2.5%	Not Applicable

Occupational Exposure Limit:

Based upon animal test data, the acute toxicity of this product is expected to be inhalation: 4 hour LC50 = 280,000 ppm (Rat).

Note: Composition is typical for HD-5 Propane per The Canadian General Standard Board CGSB 3.14 National Standard of Canada. Exact composition will vary from shipment to shipment.

SECTION 3 – CHEMICAL AND PHYSICAL DATA

Form: Liquid and vapour while stored under pressure.
Boiling Point: -42°C @ 1 atm.
Freezing Point: -188°C
Evaporation Rate: Rapid (Gas at normal ambient conditions).
Vapour Pressure: 1435 kPa (maximum) @ 37.8°C
Vapour Density: 1.52 (Air = 1)
Coefficient of Water/Oil Distribution: Not available.
pH: Not available.

Solubility in water: Slight, 6.1% by volume @ 17.8°C

Specific Gravity: 0.51 (water = 1)

Appearance/Odour: Colourless liquid and vapour while stored under pressure. Colourless and odourless gas in natural state at any concentration. Commercial propane has an odourant added, ethyl mercaptan, which has an odour similar to boiling cabbage.*

Odour Threshold: 4800 ppm

* With proper handling, transportation and storage, adding a chemical odourant such as eth-merc has proven to be a very effective warning device, but all odourants have certain limitations. The effectiveness of the odourant may be diminished by a person's sense of smell, by competing odours and by oxidation which may cause a potentially dangerous situation.

SECTION 4 – FIRE OR EXPLOSION HAZARD

Flash Point: -103.4°C
Method: Closed cup.
Flammable Limits: Lower 2.4%, Upper 9.5%
Auto Ignition Temperature: 432°C
Products Evolved Due To Heat Or Combustion: Carbon monoxide can be produced when primary air and secondary air are deficient while combustion is taking place.
Fire and Explosive Hazards: Explosive air-vapour mixtures may form if allowed to leak to atmosphere.
Sensitivity To Impact: No.
Sensitivity To Static Discharge: Yes.

Fire Extinguishing Precautions: Use water spray to cool exposed cylinders or tanks. Do not extinguish fire unless the source of the escaping gas that is fueling the fire can be turned off. Fire can be extinguished with carbon dioxide and/or dry chemical (BC). Container metal shells require cooling with water to prevent flame impingement and the weakening of metal. If sufficient water is not available to protect the container shell from weakening, the area will be required to be evacuated. If gas has not ignited, liquid or vapour may be dispersed by water spray or flooding.

Special Fire Fighting Equipment: Protective clothing, hose monitors, fog nozzles, self-contained breathing apparatus.

SECTION 5 – REACTIVITY DATA

Stability: Stable.
Conditions To Avoid: Keep separate from oxidizing agents. Gas explodes spontaneously when mixed with chloride dioxide.
Incompatibility: Remove sources of ignition and observe distance requirements for storage tanks from combustible material, drains and openings to building.

Hazardous Decomposition Products: Deficient primary and secondary air can produce carbon monoxide.

Hazardous Polymerization: Will not occur.

SECTION 6 – TOXICOLOGICAL PROPERTIES OF MATERIAL

ROUTES OF ENTRY:

Inhalation: Simple asphyxiant. No effect at concentrations of 10,000 ppm (peak exposures). Higher concentrations may cause central nervous system disorder and/or damage. Lack of oxygen may cause dizziness, loss of coordination, weakness, fatigue, euphoria, mental confusion, blurred vision, convulsions, breathing failure, coma and death. Breathing high vapour concentrations (saturated vapours) for a few minutes may be fatal. Saturated vapours may be encountered in confined spaces and/or under conditions of poor ventilation. Avoid breathing vapours or mist.

Skin and Eye Contact: Exposure to vapourizing liquid may cause frostbite (cold burns) and permanent eye damage.

Ingestion: Not considered to be a hazard.

Acute Exposure: The acute toxicity of this product is expected to be inhalation: 4 hour LC50=280,000ppm (Rat).

Chronic Exposure: There are no reported effects from long term low level exposure.

Sensitization to Product: Skin–unknown, Respiratory–unknown.

Occupational Exposure Limits: American Conference of Governmental Industrial Hygienists (ACGIH) lists as a simple asphyxiant. ACGIH TLV: 1000 ppm.

Carcinogenicity, Reproductive Toxicity, Teratogenicity, Mutagenicity: No effects reported.

SECTION 7 – PREVENTIVE MEASURES

Eyes: Safety glasses, are recommended when transferring product.

Skin: Insulated gloves required if contact with liquid or liquid cooled equipment is expected. Wear gloves and long sleeves when transferring product.

Inhalation: Where concentration in air would reduce the oxygen level below 18% air or exceed occupational exposure limits in section 6, self-contained breathing apparatus is required.

Ventilation: Explosion proof ventilation equipment required in confined spaces.

SECTION 8 – EMERGENCY AND FIRST AID PROCEDURES

FIRST AID:

Eyes: Should eye contact with liquid occur, flush eyes with lukewarm water for 15 minutes. Obtain immediate medical care.

Skin: In case of “Cold Burn” from contact with liquid, immediately place affected area in lukewarm water and keep at this temperature until circulation returns. If fingers or hands are frostbitten, have the victim hold his hand next to his body such as under the armpit. Obtain immediate medical care.

Ingestion: None considered necessary.

Inhalation: Remove person to fresh air. If breathing is difficult or has stopped, administer artificial respiration. Obtain immediate medical care.

SPILL OR LEAK:

Eliminate leak if possible.

Eliminate source of ignition.

Ensure cylinder is upright.

Disperse vapours with hose streams using fog nozzles. Monitor low areas as propane is heavier than air and can settle into low areas. Remain upwind of leak. Keep people away. Prevent vapour and/or liquid from entering into sewers, basements or confined areas.

SECTION 9 – TRANSPORTATION, HANDLING AND STORAGE

- Transport and store cylinders and tanks secured in an upright position in a ventilated space away from ignition sources (so the pressure relief valve is in contact with the vapour space of the cylinder or tank).
- Cylinders that are not in use must have the valves in the closed position and be equipped with a protective cap or guard.
- Do not store with oxidizing agents, oxygen, or chlorine cylinders.

- Empty cylinders and tanks may contain product residue. Do not pressurize, cut, heat or weld empty containers.
- Transport, handle and store according to applicable federal and provincial codes and regulations.

Transportation of Dangerous Goods (TDG)

- TDG Classification: Flammable Gas 2.1
- TDG Shipping Name: Liquefied Petroleum Gas (Propane)
- TDG Special Provisions: 56, 90, 102
- PIN Number: UN1075

SECTION 10 – PREPARATION

Superior Propane Inc., Regulations & Safety Department. (403) 730-7500 Date prepared: November 2001.
Supersedes: September 1999.

The information contained herein is believed to be accurate. It is provided independently of any sale of the product. It is not intended to constitute performance information concerning the product. No express warranty, implied warranty of merchantability or fitness for a particular purpose is made with respect to the product information contained herein.

McGregor Lake Campsite Abandonment & Restoration Plan

APPENDIX C
NT-NU Spill Report Form



NT-NU SPILL REPORT

OIL, GASOLINE, CHEMICALS AND OTHER HAZARDOUS MATERIALS

EMAIL: spills@gov.nt.ca

REPORT LINE USE ONLY

REPORT LINE USE ONLY					
N	RECEIVED AT SPILL LINE BY	POSITION	EMPLOYER	LOCATION CALLED	REPORT LINE NUMBER
		STATION OPERATOR		YELLOWKNIFE, NT	(867) 920-8130
LEAD AGENCY <input type="checkbox"/> EC <input type="checkbox"/> CCG <input type="checkbox"/> GNWT <input type="checkbox"/> GN <input type="checkbox"/> ILA <input type="checkbox"/> INAC <input type="checkbox"/> NEB <input type="checkbox"/> TC			SIGNIFICANCE <input type="checkbox"/> MINOR <input type="checkbox"/> MAJOR <input type="checkbox"/> UNKNOWN		FILE STATUS <input type="checkbox"/> OPEN <input type="checkbox"/> CLOSED
AGENCY		CONTACT NAME	CONTACT TIME	REMARKS	
LEAD AGENCY					
FIRST SUPPORT AGENCY					
SECOND SUPPORT AGENCY					
THIRD SUPPORT AGENCY					

McGregor Lake Campsite Abandonment & Restoration Plan

APPENDIX D Uranium Exploration Plan

Introduction

5050 Nunavut Limited ("the Company"), a wholly owned subsidiary of MIE Metals Corporation, was incorporated under the laws of Nunavut and presently holds Nunavut Water Board License No. 2BE-MCG0810 with expiry date of July 19, 2010. The Company's Land ownership comprises of 64 mineral claims totaling 53,734.30 hectares and two Inuit Owned Land parcels totaling of 19,711.70 hectares surrounding All Night Lake and McGregor Lake. Claims are located between 70 and 100 kilometres south of Kugluktuk and are situated over a north-south trending layered mafic to ultramafic intrusive body called the Muskox Intrusion that geologically hosts nickel, copper and platinum group elements (Ni-Cu-PGE) as well as uranium within the adjacent sedimentary basin. Exploration efforts by the Company since 2005 have targeted both Ni-Cu-PGE and uranium mineralization in the following areas:

1. McGregor Lake south – for Ni-Cu-PGE
2. All Night Lake Area – for uranium
3. Tabb lake Area – for uranium

In 2007, 5050 Nunavut Limited was approved for an exploration camp located at Iceberg Creek on the southern shores of McGregor Lake. Upon written request by the Kitikmeot Inuit Association, the camp was relocated to a pre-existing camp on the northern shores of McGregor Lake, established and operated by Inco Limited in the early 1950's and 1960's. Subsequently the camp was referbished and expanded to accommodate 30 persons.

A 10,000 meters of NQ diamond drilling program began in 2007. To date, only four NQ diamond drill holes totaling 2,858 m was completed on claim M1 and one diamond drill hole totaling 266 meters was completed on claim DM72. 5050 Nunavut Limited intends to complete the remaining 6,876 meters of NQ diamond drilling, including planned diamond drilling surrounding All Night Lake in search of uranium.

Locations of proposed boreholes in the Tabb Lake area are shown on Figure 2, of which initially four or five boreholes will be drilled with a depth range of 200-250m. If required, 2 boreholes will be drilled on the adjacent joint venture claims with UNOR Inc. Locations of proposed boreholes for All Night Lake

area are shown on Figure 3, of which initially six or seven boreholes will be drilled with a depth range of 150 to 200 m.

Uranium Exploration Plan

The following uranium exploration plan is submitted to address the environmental and water issues related to uranium exploratory drilling. As required by Part F of our License, this plan is based on the Mineral Exploration Guidelines for Saskatchewan, 2005.

Drilling Operations

1. The uranium exploration drill program will start in the first week of July and no ice drilling will be carried out.
2. Core Drilling (NQ size) will be carried out using a Boyles 37 drill rig supplied and operated by Major Drilling Group International Inc.
3. Approximate location of boreholes is provided on Figure 2 (Tabb Lake area) and Figure 3 (All Night Lake area) attached with this plan.
4. No borehole will be located within 100 m of a water body or water course.
5. No clearing is involved in drill site preparation.
6. The drill site footprint will not exceed an area of 20m by 20m and minimum distance of 100 m will be kept between the drill site footprint and the nearest water body.
7. A minimum distance of 100 m will be maintained between the drill site area and any water body in the vicinity.
8. The drill rig will be leveled using timbers and no soil stripping is involved in the drill site preparation.
9. Where possible, all efforts will be used to prevent drill mud, return water, and cuttings (sludge) from running uncontrolled from the drill site or to within 100 m of a water body or water course. If required, appropriate erosion control methods will be implemented.
10. Where possible, biodegradable mud and non-toxic drill additives are being used for the copper nickel, PGE drill program, and will also be used for uranium program.
11. Drill mud solids or cuttings with uranium concentration greater than 0.05 percent will be collected and disposed of down the drill hole and sealed.

12. Any drill hole that encounters mineralization with a uranium content greater than 1.0% over a length >1 meter, and with a meter-percent concentration >5.0, will be sealed by grouting over the entire length of the mineralization zone and not less than 10 meters above or below each mineralization zone.
13. All artesian drill holes will be reported to NWB within 30 days of its discovery.
14. All artesian drill holes will be sealed to prevent discharge to the environment.

Core Storage

1. Core storage areas will be located a minimum of 100 meters from the high waterline of all the water bodies in the vicinity.
2. All core will be stored in standard core boxes and each box will be identified with weatherproof labels.
3. 5050 Nunavut Limited will be responsible for all core drilled and if the property is sold or reassigned the new operator will be responsible for all core.
4. Gamma levels in the core storage area, measured at 1 meter from surface of the storage area will be reduced to 1.0 μSv and in no instance will the level be allowed to exceed 2.5 μSv . Instruments that measure radiation in counts per second will be converted to μSv according to the specification of that instrument.

Reclamation

5050 Nunavut Limited recognizes that reclamation is an integral part of exploration and has developed a plan to return the disturbed areas to an acceptable natural and productive state. The key element of the plan is minimizing impacts and avoiding surface disturbances which will help in reducing reclamation requirements and costs for the program.

1. Reclamation of each drill site will be carried out by removing all infrastructures, facilities, and waste from each drill site.
2. The drill rig will be leveled using timbers and no soil stripping is involved in the drill site preparation.
3. In a location where there is a reasonable chance of erosion, appropriate erosion control methods like soil stabilization through berms, water and mud collection sumps, recirculation of drill fluids, and placing slash material will be implemented.

4. 5050 Nunavut Limited will ensure that the aforementioned measures and all other measures mentioned in its Water License are implemented to the satisfaction of Nunavut Water Board.

If there are questions or concerns regarding 5050 Nunavut Limited's Uranium Exploration Plan, please contact the Company's representative at the contact information below. Thank you.

Phu Van Bui, Project Geologist

Tel: 604-681-4001 ext. 111

pvanbui@miemetals.com.

Head Office

5050 Nunavut Limited & MIE Metals Corporation

Suite 507 – 700 West Pender Street


Vancouver, British Columbia

Canada V6C 1G8

Tel: 604-681-4001

Fax: 604-681-4022

5050 Nunavut Ltd



LEGEND

- McGregor Camp Site
- 2007 DDH Location
- Claim boundary
- River
- Elevation Contour [m]
- Lake



FIGURE 1

MAP DATE: 2010-04-13


SURIFICAL TOPOGRAPHY

2007 DRILL PROGRAM


MCGREGOR LAKE AREA

NUNAVUT


Scale 1:50 000



Universal Transverse Mercator Projection
North American Datum 1983



5050 Nunavut Ltd



LEGEND

- Claim boundary
- Proposed Uranium Drillholes
- River
- Elevation Contour [m]
- Lake



FIGURE 2

MAP DATE: 2010-04-12


SURIFICAL TOPOGRAPHY

2007 DRILL PROGRAM

BEAR VALLEY AREA


NUNAVUT

Scale 1:20 000



Universal Transverse Mercator Projection
North American Datum 1983

5050 Nunavut Ltd



LEGEND

- Claim boundary
- IOL Kitikmoet Surface Rights
- Proposed DDH Uranium
- ~ River
- ~ Elevation Contour [m]
- ~ Lake



FIGURE 3



MAP DATE: 2010-04-13

SURFICIAL TOPOGRAPHY

PROPOSED BOREHOLE LOCATION

ALL NIGHT LAKE

NUNAVUT



McGregor Lake Campsite Abandonment & Restoration Plan

APPENDIX E
Nunavut Waste Generation Number

**Government of Nunavut
Department of Environment
Environmental Protection Division**

Request for Territorial Identification Number

Hazardous Waste Generator # NUG 100022

Please complete this questionnaire, as accurately as possible, by providing the information requested below. This information is to be submitted –preferably in electronic format –to: Manager, Pollution Control, Box 1000, Stn. 1360, Iqaluit, NU. X0A0H0. e-mail: reno@gov.nu.ca.

The purpose of this questionnaire is to ensure that the Department of Environment is able to track the movement of hazardous waste in Nunavut and further, is assured that the agency/firm/company/individual in possession of, offering for transport, or receiving hazardous waste, is able to manage that waste in a manner which complies with current environmental acts, regulations, guidelines and standards of practice. **Please refer to the attached *Environmental Guideline for the General Management of Hazardous Waste* for additional details.**

Generator numbers will not be issued until the questionnaire has been completed to the satisfaction of the Department of Environment. For those companies who have already been issued with Generator Numbers, you are required to fill out this questionnaire and return it to the Department of Environment as soon as possible.

1. Company name:

5050 Nunavut Limited (subsidiary of MIE Metals Corporation)

2. Mailing address:

Suite 507 – 700 West Pender Street, Vancouver, British Columbia, V6C 1G8
Phone: 604-681-4001, Fax: 604-681-4022

3. Site location:

McGregor Lake (Map Sheet No. 86J, 86O, 86N)
Inuit Land Parcel No. CO 52, 53, 60, 61, & 62
Lat. 115° 15' 44" W Long. 66° 51' 30" N

4. Company contact (include title):

Phu Van Bui, Project Manager
Phone: 604-681-4001 ext. 111, Fax: 604-681-4022
Email: pvanbui@miemetals.com

5. Company official (include title):

Gordon Addie, President
Phone: 604-681-4001 ext. 109, Fax: 604-681-4022
Email: gaddie@miemetals.com

6. Type of business:

Mineral Exploration and Mining

7. Type of Waste Generated.

- Provide name and description of each site from which waste is intended to be removed:
McGregor Lake camp and various borehole locations in the area.
- Provide a description of the waste, proper shipping name, TDGR Product Identification Number and where applicable, the process resulting in the production of the waste.
The following hazardous waste is expected form the drilling and camping exploration activities:
 - Waste oil, greases (Class 3.1 TDG)
 - Antifreeze (Class 9.1 TDG)
 - Calcium or sodium chloride salt (Class 9.1 TDG)
 - Lead acid batteries (Class 8 TDG)
 - Cleaners (Class 9.1 TDG)
 - There is a chance of encountering uranium in the drill cores (Class 7 TDG) for which Canadian Nuclear Safety Commission will be consulted and “Canadian Guidelines for the Management of Naturally Occurring Radioactive Materials (NORM)” will be used as guiding document. For the long term storage of drill core, radiation level will be maintained as per NORM. In practice it is anticipated that the major uranium intersections will be transported to the Saskatchewan Research Council (SRC) Geoanalytical laboratories for testing and storage at their nuclear materials storage facility. The transportation of samples will be carried out as per NORM Guidelines.
- Is this a one time only generation or will your company be generating hazardous waste on a regular basis? If so, how often and what types of waste do you anticipate generating?
The exploration work period of operation will be: March – May (spring break up), June-September (fall freeze-up) and October – November. The above listed waste will be generated three to four times in a year.

8. Emergency Response/Management:

- Do you have a spill/emergency plan for accidents involving the hazardous material under your control? If so, please provide a copy (preferably electronic) to DOE.

Yes, this plan will be part of our camp permitting. The copy will be provided before start of the camp.

- If not, is your company prepared to manage emergencies involving this material? How?
- Is the management of the hazardous waste in your possession being undertaken by a third party?

No.

- If yes, please provide the name of that firm as well as a company contact name, phone number and address. Briefly describe that firm's experience in managing hazardous waste.

9. Intended carrier (if applying for a number in general anticipation of shipping hazardous waste at an unspecified time, please provide this information at a later date):

This information will be provided later, the number is being applied in general anticipation of shipping hazardous waste at an unspecified time.

- Please include full name, company location, address, contact person and number, provincial/territorial ID number and mode ⁽⁵⁾ of transport (ship, rail, road, air).
- Is the carrier capable of managing this hazardous material in the event of a spill or other emergency?
- Is this carrier a recognized and reputable firm capable of managing the hazardous material being consigned to them?
- For how long has this carrier been in business?

10. Intended Receiver (if applying for a number in general anticipation of shipping hazardous waste at an unspecified time, please provide this information at a later date):

This information will be provided later, the number is being applied in general anticipation of shipping hazardous waste at an unspecified time.

- Please include full name of company, location, address, contact person, telephone number, e-mail address and Provincial/Territorial ID number.
- Is this receiver a recognized and reputable firm capable of managing the hazardous material being consigned to them?
- For how long has this receiver been in business?

McGregor Lake Campsite Abandonment & Restoration Plan



APPENDIX F
Daily Wildlife Log


505 Nunavut Limited., McGregor Lake Campsite

Location from camp: North, East, South, West


McGregor Lake Campsite Abandonment & Restoration Plan

APPENDIX G **Figures**



Title:		SITE LOCATION	
Project:		CAMPSITE PERMIT RENEWAL AND AMENDMENT	
Client:		5050 NUNAVUT LTD.	
 FRANZ ENVIRONMENTAL INC. CONSULTING • ENGINEERING • TECHNOLOGIES		Date:	DECEMBER 2007
		FIGURE 1-1	

5050 Nunavut Ltd



LEGEND

- Proposed DH Location
- ◆ McGregor Camp Site
- ▭ IOL Agreements
- ▭ Claim boundary
- ▭ IOL Kitikmoet Surface Rights
- ~ River
- ~ Elevation Contour [m]
- ~ Lake



FIGURE 1-2

MAP DATE: 2010-04-12

SURIFICAL TOPOGRAPHY

PROPOSED EXPLORATION AREA

MCGREGOR LAKE & ALL NIGHT LAKE

NUNAVUT

