

Hornby Bay Exploration Limited Abandonment and Restoration Plan

Upon completion of the exploration of the Mouse Lake project, the following procedures will be implemented to ensure the proper abandonment and reclamation of the area. The plan will be revised annually based on the exploration results.

A and R Procedures to be Implemented

1. Greywater sumps and toilet pits will be treated with lime and covered with twelve inches of native soil.
2. All remaining garbage will be incinerated in a burn barrel.
3. All wood (tent floors, frames, etc) will be removed from the site to an approved landfill or will be burned on site in a burn barrel. Non-combustible items will be removed from the ashes and hauled to an approved landfill. The ashes will then be buried.
4. Any remaining fuel drums and machinery will be transported to Yellowknife.
5. A check will be made to ensure that all drill sumps have been backfilled and that there is no remaining garbage at the site.
6. Any docks or other temporary infrastructure will be removed from the site.

The above procedures have been put in place to ensure that once Hornby Bay Exploration has ceased operations, there will have been minimal impact to the environment.