

---

201-1250 HOMER STREET, VANCOUVER, BRITISH COLUMBIA, CANADA V6B 1C6  
TELEPHONE: (604) 408-8880 FAX: (604) 408-8881  
[www.peregrinediamonds.com](http://www.peregrinediamonds.com)

**Abandonment and Restoration Plan  
Nanuq North Project**

**Kivalliq Region, Nunavut  
Peregrine Diamonds Ltd.**

**August 18, 2015**

**Nanuq North Project  
Abandonment and Restoration Program  
August 18, 2015**

---

**Background as of August 18, 2015**

The exploration camp (Latitude 65°23'45.65"N Longitude 91°13'8.40"W) authorized in June 2009 has yet to be established. There are no buildings, tent frames or tents at this location.

There are no fuel caches located on the Nanuq North Project Area.

The last drilling on the Nanuq North Project occurred on August 2, 2011. All drill materials were removed upon the completion of drilling.

When facilities are established or additional exploration work undertaken the following Abandonment and Restoration Program will apply.

**CAMP LOCATION**

The Nanuq North camp is located on unnamed 1:50,000 scale National Topographic Map 56G-06. The coordinates for the camp are as follows:

**Latitude:** 65° 23' 45.65"

**Longitude:** -91° 13' 8.40"

This location is approximately 300 kilometers at heading 7.45 degrees (north-northeast) of the Kivalliq Regional Centre of Rankin Inlet.

**CAMP - SEASONAL SHUTDOWN**

**Buildings and Contents**

Buildings and Contents will be dismantled and the canvas tents will be removed from site for dryings and storage. Wood structures (generator and pacto toilet shacks) and wood doors will be kept secured. Wooden bed frames will be turned upside down and secured to the wooded floors for over winter storage. The generator will be removed form site for servicing and storage

## **Water System**

Pumps and Hoses will be drained and dismantled. Pumps and Hoses will be removed from the site for servicing and storage.

## **Fuel Storage**

All fuel caches will be removed and drums will be located at the camp. An inventory and inspection of all fuel drums will be completed and empty fuel drums will be removed from site. Partially full fuel drums will be kept to a minimum and placed on an angle to ensure that snow and water do not enter the drum and no leakage from the drum occurs. Fuel drums will be stored on their sides.

## **Domestic Chemicals**

No domestic chemicals (cleaners etc.) will be stored on site over winter. All chemicals including cleaning products will be removed from site for storage and/or disposal.

## **Waste**

All combustible waste will be incinerated. Non-combustible waste will be packaged and flown out to an appropriate disposal facility.

Domestic Grey Water sump will be inspected and covered securely for the winter. Stakes will be placed around the sump so that it is easily identifiable when the camp is opened up again each year.

Sewage will be contained in portable toilets. Bags containing waste will be incinerated and the ashes removed from the site.

## **CAMP – FINAL ABANDONMENT AND RESTORATION**

### **Buildings and Contents**

All buildings will be dismantled and removed. All wooden structures, including floors, will either be burned or removed.

### **Equipment**

All equipment, including pumps, will be dismantled and removed from the project area.

## **Fuel Caches and Chemical Storage**

All fuel drums will be removed. All areas where there have been fuel caches will be thoroughly inspected. Any contamination will be cleaned up as well as any debris removed. If there are instances of contaminated soil will be handled as per the Spill Contingency Plan.

## **Sumps**

The grey water sump will be inspected to ensure there is no leaching or run-off. It will be back-filled and leveled as required.

## **DRILLS SITES – SEASONAL AND FINAL**

The drill site will be dismantled into its main components as per the drill contractor's procedures, packaged and secured along with equipment and rods. The drill will be flown out by the drilling contractor or as the contract describes.

All drill sites will be inspected for soil contamination. Any remaining waste will be taken to camp to be burned if possible or to be flown out to an approved disposal location. Natural depressions used as sumps will be inspected.

Drill sites will be subject to progressive reclamation. As much as possible drill sites will be restored immediately after the drill has been moved to the next site.

## **CONTAMINATION CLEAN-UP**

No contamination is anticipated however should this occur any contamination will be treated as per the Nanuq North Spill Contingency Plan.