

February 7, 2022
Richard Dwyer
Manager of Licensing
Nunavut Water Board
P.O Box 119 Gjoa Haven, X0B1J0

Re: Notification of Construction within 3AM-GRA1631

Dear Mr. Dwyer,

Please find issued for construction (IFC) drawings for your consideration for work to be completed on the utilidor system, with substantial completion estimated as September 30, 2022, licensed under 3AM-GRA1631. As this modification is consistent with the terms of the licence, please take this letter and ICF drawings as notification, under part F, section 2 of the licence. The following major work items are included in the IFC drawings attached with this email.

Johnston Cove Lift Station:

- 1. Replacement of 2 Submersible Pumps with Centrifugal Pumps.
- 2. Replacement of Boilers and Generator
- 3. Replacement of 2 Access Vaults beside JC lift station and 1 additional Access Vault
- 4. Watermain 250 mm pre-insulated HDPE 95 m.
- 5. Sanitary Sewer 300mm pre-insulated HDPE 175 m.
- 6. New Fuel tank 8500 litre with concrete slab.

Nuvuk Trunk Line:

- 1. 2 Additional Access Vaults
- 2. Sanitary Sewer 300mm pre-insulated HDPE 152 meter

Please feel free to contact me with any questions.

Regards,

Sarah Collins P.Eng

A/Manager Municipal Planning

Community and Government Services

Government of Nunavut