



EXP SERVICES INC. 2013-06-27 14:00:00

EXP SERVICES INC. 2013-06-27 14:00:00

EXP SERVICES INC. 2013-06-27 14:00:00



System Tag : Generator Rm Cooling

System sequences of Generator Room Cooling

- 1.1 ON generator start, OAD to minimum position for combustion air. Modulate MAD and OAD to maintain space temperature. Set point selected on PLC 1 (mechanical system P.L.C).
- 1.2 After generator shut off, continue operation of dampers for a minimum of 10 minutes. Operations to be similar to 1.1 except dampers to never close more than 50%.
- 1.3 When the generator is off and RMaxxSPT (generator room) is greater than 30 ° C, enable operation of dampers until space temperature lowers below 30 ° Celsius.

System Tag : HW system

System sequences of Hot Water system

- 1.1 Hot water system temperature lower than 50 °Celsius for more than 60 min when circulators enabled, CPI alarm lamp on (heating system fail), auto dialer "call" and outside strobe on.
- 1.2 Circulators to operate lead / standby. Pumps to alternate on total run time duty cycles. Pumps to switch roles after 168-hrs operation.
- 1.3 Circulators continue operations for 30 minutes after heating system switch turned to off position. Time to cool down the system.
- 1.4 When circulators operation proven, pump status P21s or P22S, enable boiler temperature controllers to cycle burners. Burners to cycle to maintain set point (controller built-in furnace)
- 1.5 Hot water pump P1/2 status by P1S/P2S In event of pump failure auto change to standby pump and Signal alarm, CPI alarm lamp on.
- 1.6 TCH to provide boiler high limit protection. In event of high limit set point, burner disabled, manual reset (built in boiler)
- 1.7 LWCO to provide boiler low water protection. In event of low water level, burner disabled, manual reset (built-in boiler)
- 1.8 In event of panel failure Hot Water pumps on and boilers enabled. In event of power failure heating System auto reset
- 1.9 Boilers to low fire when OAT (outside air temperature) above 0 degree Celsius for more then 15 minutes. To high fire when colder.


System Tag : BLBG Trouble

Ref. Description

System sequences of building Troubles

- 1.1 When space temp at FLRTEMP below 5 degree C signal auto dialer and exterior strobe.
- 1.2 When space humidity at FLRHUMID above 80%RH signal auto dialer and exterior strobe

GENERATOR ROOM COOLING, HOT WATER SYSTEM AND BUILDING TROUBLE P & ID



NOTE:

1. THESE SCHEMATICS ARE FROM THE ORIGINAL CONTRACT. REFER TO MECHANICAL SEQUENCE OF OPERATION AND DRAWING FOR ADDITIONAL EQUIPMENT AND OPERATION.

TYPICAL MAGNETIC STARTER CONTROL SCHEMATIC

No.	Issue	Date
1	60% REVIEW SUBMISSION	2013-MAR-8
2	ISSUED FIR TENDER	2013-APR-10
3	RELEASED FOR CONSTRUCTION	2013-JUN-27



No.	Revision	Ckd. By	Date

PERMIT OF PRACTICE
EXP SERVICES INC.
Signature *[Signature]*
Date 2013/JUN/27
PERMIT NUMBER: P483
NT/NU Association of Professional
Engineers and Geoscientists.

RELEASED FOR CONSTRUCTION

	Const. North
	Drawn By: TAW
	Dwg. Standards Ckd. By: PD
	Designed By: DEB
Date Printed	Dwg. Design Ckd. By: JFP

exp Services Inc.
t: +1.613.688.1899 | f: +1.613.225.7330
2650 Queensview Drive, Unit 100
Ottawa, ON K2B 8H6
CANADA
www.exp.com



• BUILDINGS • EARTH & ENVIRONMENT • ENERGY •
• INDUSTRIAL • INFRASTRUCTURE • SUSTAINABILITY •

Project Title WASTE WATER TREATMENT PLANT UPGRADE PANGNIRTUNG, NU		
Dwg. Title GENERATOR, HOT WATER, AND BUILDING P & ID AND TYPICAL STARTER CONTROL SCHEMATIC		
Project No.	OTT-00204430-A0	
Dwg. No.	E2635-1	Rev. No. 0
Scale	NOT TO SCALE This drawing is not to be scaled	