



- **Hamlet of Cape Dorset**

## **Quality Assurance / Quality Control Plan**

**Project Name**

Water Licence Compliance – Hamlet of Cape Dorset

**Type of Document**

Final

**Project Number**

OTT-00209248-A0

**Prepared By:** Robert Renaud, M.Sc., P.Geo.

**Reviewed By:** Chris Kimmerly, M.Sc., P.Geo. (ON)

**exp** Services Inc.  
100-2650 Queensview Drive  
Ottawa, ON K2B 7H6  
Canada

**Date Submitted**

August 13, 2013

This page intentionally left blank

# Hamlet of Cape Dorset

## Quality Assurance / Quality Control Plan

**Type of Document:**  
Final

**Project Name:**  
Water Licence Compliance – Hamlet of Cape Dorset


**Project Number:**  
OTT-00209248-A0

**Prepared By:**  
exp  
100-2650 Queensview Drive  
Ottawa, ON K2B 8H6  
Canada  
T: 613 688-1899  
F: 613 225-7337  
www.exp.com



---

Robert Renaud, M.Sc., P.Geo.  
Senior Geoscientist



---

Chris Kimmerly, M.Sc., P.Geo. (ON)  
Manager & Senior Geoscientist

**Date Submitted:**  
August 13, 2013

This page intentionally left blank

## Table of Contents

<b>1</b>	<b>Introduction .....</b>	<b>1</b>
1.1	Background .....	1
1.2	Monitoring and Regulatory Requirement Program .....	2
1.3	Objectives.....	2
1.4	Scope of Work.....	2
1.5	Definitions.....	2
<b>2</b>	<b>Field Sampling.....</b>	<b>3</b>
2.1	Sampling Procedures .....	3
2.2	Sampling Collection.....	3
2.2.1	Locations .....	3
2.2.2	Sampling Equipment .....	6
2.2.3	Sampling Methods.....	6
2.3	Sample Handling .....	8
2.4	Quality Assurance and Quality Control Program.....	8
<b>3</b>	<b>Laboratory Analysis.....</b>	<b>9</b>
3.1	Laboratory Accreditation .....	9
3.2	Method Detection Limits.....	9
<b>4</b>	<b>Reporting Requirements .....</b>	<b>10</b>
4.1	General Submissions .....	10
<b>5</b>	<b>References.....</b>	<b>11</b>

## Appendices

Appendix A: Figures

Appendix B: Hamlet of Cape Dorset's Water Licence

Appendix C: Environmental Monitoring Program Checklist, Summary of Sample Bottle Requirements

Appendix D: Completed Example of Chain of Custody Documentation

Appendix E: Environmental Monitoring Program Schedule

Appendix F: Subcontract Laboratory Accreditation & Supporting Documentation

This page intentionally left blank

# 1 Introduction

The purpose of this document is to provide guidance to ensure that environmental monitoring program samples collected in the field are done so with a high degree of quality, in order to ensure that they accurately reflect the physical and chemical nature of the matrix being tested.

## 1.1 Background

The Hamlet of Cape Dorset (Hamlet) is located on Dorset Island in the Hudson Strait (Figure 1, Appendix A).

The water supply for the Hamlet is Tee Lake located approximately 1 km south of the Hamlet. Water is conveyed to the truck fill station through a 1.3 km transmission main. Water is drawn into the pump house at Tee Lake via a single inclined shaft intake. The pump house contains heating equipment, provided to avoid freeze of the transmission water main linking the pump house and water treatment plant. The truck fill station is located adjacent to the Hamlet and is comprised of a truck fill station and water storage tank. This facility provides water treatment through chlorination, equipment for truck loading and freeze prevention for the water storage tank.

The 2001 Sewage Disposal Facility is comprised of a 3-tier series of lagoons and decant structures designed to contain sewage. The facility is located approximately 730 metres to the west of the community. It is located along a natural valley directly to the south east of the 2001 Sewage Disposal Facility and the solid waste facility. Sewage is disposed of at cell #1 and during the summer months naturally decants into cell #2, followed by cell #3, finally discharging to the environment from the outlet structure of sewage lagoon #3. During the winter months, when the decant and outlet structures are frozen, water is pumped from one sewage lagoon cell to the subsequent cell on an as required basis. Due to capacity issues, this sewage treatment facility sewage must be decanted during the winter months as the facility does not provide sufficient over winter storage to meet the requirements of the Hamlet.

The 2007 Sewage Disposal Facility is a single-cell sewage lagoon built in 2007. It was built in a natural valley between two hills. It was created through the construction of the main berm on the western limits of the sewage lagoon and a berm on the northeast corner, which is the location of the truck discharge point. The sewage treatment facility incorporates a natural wetlands located to the west of the facility, including Pee Lake, a wetlands and the rocky drop off referred to as the waterfalls in the water licence. There is a gravel access road traversing both sides of the rocky hills connecting and providing access to the lower berm. The sewage lagoon has never been commissioned due to concerns of leaking through the main berm.

The Emergency Sewage Disposal Facility is located approximately 500 m west of the town site along the access route to the solid waste site and the 2001 Sewage Disposal Facility. The facility is the old sewage lagoon and is currently maintained for use during adverse wind conditions, at which time the sewage discharge point for the 2001 Sewage Disposal Facility is non operational due to health and safety concerns for the operators.

The Solid Waste Disposal site is located approximately 700 m to the west of the Hamlet, adjacent to the 2001 Sewage Disposal Facility. A bulk metal waste dump is located along to the road to the 2001 Sewage Disposal Facility. It is approximately 300 m west of the town.

The Nunavut Water Board (NWB) issued a Class B Water Licence (3BM-CAP0810) to the Hamlet on March 7, 2008. The water licence governs water use and waste disposal within the Hamlet. A copy of the Water Licence is provided in Appendix B.

## 1.2 Monitoring and Regulatory Requirement Program

Condition 20 of Part H of the water licence issued to the Hamlet requires that the Hamlet submit to the NWB for approval, a Quality Assurance / Quality Control (QA/QC) Plan prepared in accordance with *“Quality Assurance (QA) and Quality Control (QC) Guidelines for use by Class “B” Licensees in Collecting Representative Water Samples in the Field and for Submission of a QA/QC Plan”* (Department of Indian and Northern Affairs Canada, July 1996), herein referred to as “The Guidelines”.

## 1.3 Objectives

The objectives of this QA/QC plan are to: i) to ensure the reliability of the data collected during monitoring activities at the locations specified in the Hamlet’s water licence, and ii) satisfy the requirement of the water licence.

## 1.4 Scope of Work

This QA/QC Plan covers the environmental monitoring undertaken at the Hamlet’s truck fill station, solid waste disposal site, 2001 Sewage Disposal Facility, Emergency Sewage Disposal Facility, and 2007 Sewage Disposal Facility (Figures 2 and 3).

## 1.5 Definitions

The following definitions that are relevant to this plan include:

**Quality Assurance** is a system that ensures that quality control procedures are correctly performed and documented.

**Quality Control** refers to the established procedures observed both in the field and in the laboratory, designed to ensure that the resulting end data meet intended quality objectives.

**Trip Blank** is a sample of clean water that was prepared by the analytical laboratory and shipped to the sample site in the cooler along with the empty sample bottles. This trip blank sample remains unopened and is transported back to the laboratory with the monitoring program samples. The trip blanks is analyzed by the laboratory along with the monitoring program samples. The purpose of the trip blank is the assess contamination introduced during shipping and field handling procedures.

**CALA** refers to the Canadian Association for Laboratory Accreditation, formally known as the Canadian Association for Environmental Analytical Laboratories (CAEAL).

**Chain of Custody Documentation** refers to the documentation that accompanies samples sent to an analytical laboratory. It is a legal document which ensures that the sample taken at a specific site is the same sample received in the laboratory. It also provides information on the sample condition and integrity as received by the laboratory.



## 2 Field Sampling

### 2.1 Sampling Procedures

All sampling, sample preservation and analyses is to be conducted in accordance with methods described in the current edition of *Standard Methods for the Examination of Water and Wastewater* (American Public Health Association, American Water Works Association, and Water Environment Federation, most current edition).

To obtain meaningful results from the analyses, the following six factors are of particular importance:

- Sample collection as per schedule and location.
- Correct usage of container/sample bottle for parameter being tested.
- Correct labelling of sample bottles and filling out record/field sheet.
- Correct procedure for field sampling.
- Proper and timely shipment of samples to the laboratory.
- Timely delivery of samples to the laboratory from the air cargo facility.

### 2.2 Sampling Collection

Refer to the *Environmental Monitoring Program Checklist*, found in Appendix C for specific details on the sampling locations, equipment and sampling methods.

#### 2.2.1 Locations

The water licence issued to the Hamlet (3BM-CAP0810) by the NWB specifies twenty-four monitoring stations across the licensed facilities.

- Station CAP-1 is a raw water supply (from Tee Lake) volume monitoring location.
- Station CAP-2 is a run-off sampling location from the Solid Waste Disposal Facility.
- Station CAP-3 is a wastewater influent sampling location at the active (at the time of sampling) Wastewater Facility.
- Station CAP-4 is an effluent discharge sampling location from the 2001 Sewage Disposal Facility.
- Station CAP-5 is an effluent discharge sampling location from the Emergency Sewage Disposal Facility.
- Station CAP-6 is an effluent discharge sampling location from the 2007 Sewage Disposal Facility, at the Final Point of Control.
- Station CAP-7 is a wastewater influent sampling location to P-Lake.
- Station CAP-8 is a sampling location in the centre of P-Lake.
- Station CAP-9 is a sampling location midway between the centre of P-Lake (CAP-8) and the effluent discharge of P-Lake (CAP-10).

- Station CAP-10 is an effluent discharge sampling location from P-Lake (if flow is negligible a sample from the immediate upstream area within P-Lake shall be obtained).
- Station CAP-11 is an effluent discharge sampling location from the Wetland area.
- Station CAP-12 is a sampling location located at the top of the waterfall on the Wetland Pathway.
- Station CAP-13 is a sampling location located midway down the waterfall on the Wetland Pathway.
- Station CAP-14 is a sampling location located at the bottom of the cliff (Final Discharge Point).
- Station CAP-15 a Control Point sampling location (small lake) located between the Lagoon and Tee Lake.
- Station CAP-16 is a monitoring well located up gradient of the 2007 Sewage Disposal Facility.
- Station CAP-17 is Monitoring Well No. 1, located down gradient of the 2007 Sewage Disposal Facility.
- Station CAP-18 is Monitoring Well No. 2, located down gradient of the 2007 Sewage Disposal Facility.
- Station CAP-19 is a monitoring well located up gradient of the Solid Waste Disposal Facility.
- Station CAP-20 is a monitoring well located down gradient of the Solid Waste Disposal Facility.
- Stations CAP-21 to CAP-24 are thermistor stations.

The following table includes the geographic coordinates for the eight monitoring stations described above.

**Table 1 –Geographic Coordinates for the Monitoring Stations for NWB Licence 3BM-CAP0810**

Monitoring Station	Latitude	Longitude
CAP-1	N 64° 13' 30.4"	W 76° 32' 53.2"
CAP-2	Not located	Not located
CAP-3	N 64° 13' 40.8"	W 76° 34' 29.5"
CAP-4	N 64° 13' 44.9"	W 76° 34' 42.4"
CAP-5	N 64° 13' 49.3"	W 76° 34' 23.7"
CAP-6	Not located	Not located
CAP-7	Not located	Not located
CAP-8	Not located	Not located
CAP-9	Not located	Not located
CAP-10	Not located	Not located
CAP-11	Not located	Not located
CAP-12	Not located	Not located
CAP-13	Not located	Not located
CAP-14	Not located	Not located
CAP-15	Not located	Not located
CAP-16	N 64° 13' 17.2"	W 76° 33' 45.5"
CAP-17	N 64° 13' 12.2"	W 76° 33' 59.8"
CAP-18	N 64° 13' 14.2"	W 76° 34' 00.2"
CAP-19	N 64° 13' 47.5"	W 76° 33' 53.8"
CAP-20	N 64° 13' 59.4"	W 76° 34' 06.5"
CAP-21	N 64° 13' 17"	W 76° 33' 45.5"
CAP-22	N 64° 13' 14.3"	W 76° 33' 58.4"
CAP-23	N 64° 13' 13.5"	W 76° 33' 57.8"
CAP-24	N 64° 13' 12.2"	W 76° 33' 57.3"

## 2.2.2 Sampling Equipment

Dedicated latex or nitrile gloves (i.e., one pair per sample) are to be used during sample handling. Dedicated sampling equipment such as sampling poles (see photo below for an example) are to be cleaned with soap and water after each sample is collected to prevent cross-contamination.



Environmental monitoring samples collected for analysis of selected chemical parameters are to be placed directly into new pre-cleaned, laboratory-supplied sample bottles. All monitoring samples are to be placed in clean coolers for transportation to the subcontract laboratory. The samples are transported/submitted under Chain of Custody documentation. Included on a Chain of Custody form is the client information, the sample information, the analyses requested, the relevant regulations, the turnaround time for the analytical results, comments, and temperature of the samples at the time they arrived in the laboratory. An example of a completed Chain of Custody form is included in Appendix D.

## 2.2.3 Sampling Methods

Please see Appendix E for the Environmental Monitoring Program Schedule. As a general recommendation, please refrain from using insect repellent, disinfection hand gel or other chemical products before and during sample collection. Also, please refrain from smoking during sample collection.

### 2.2.3.1 Wastewater Sampling

Wastewater influent samples are collected from the active sewage disposal facility (Station CAP-3) beginning one week prior to the proposed discharge date, once at the beginning of the discharge and weekly thereafter until the cessation of discharge. Wastewater influent samples are collected from the lagoon by immersing the sample bottle into the lagoon neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with influent wastewater and the sample bottle is raised neck first to prevent sample spillage.

Effluent discharge samples are collected from the 2001 Sewage Disposal Facility (Station CAP-4), following the same schedule and methodology described above for Station CAP-3.

Effluent discharge samples are collected from the Emergency Sewage Disposal Facility (Station CAP-5), following the same schedule and methodology described above for Station CAP-3.

Effluent discharge samples are collected from the Final Point of Control at the 2007 Sewage Disposal Facility (Station CAP-6), following the same schedule and methodology described above for Station CAP-3.

Wastewater influent samples are collected from P-Lake (Station CAP-7), following the same schedule and methodology described above for Station CAP-3.

Wastewater samples are collected from the centre of P-Lake (Station CAP-8), following the same schedule and methodology described above for Station CAP-3.

Wastewater samples are collected from a location (Station CAP-9) midway between the centre of P-Lake (Station CAP-8) and the effluent discharge of P Lake (Station CAP-10). These samples are collected following the same schedule and methodology described above for Station CAP-3.

Wastewater effluent discharge samples are collected from P-Lake (Station CAP-10). If flow is negligible, then the samples are collected from a location located immediately upstream within P-Lake. These samples are collected following the same schedule and methodology described above for Station CAP-3.

Wastewater effluent discharge samples are collected from the Wetland area (Station CAP-11), following the same schedule and methodology described above for Station CAP-3.

Wastewater effluent discharge samples are collected from the top of the waterfall on the Wetland Pathway (Station CAP-12), following the same schedule and methodology described above for Station CAP-3.

Wastewater effluent discharge samples are collected from midway down the waterfall on the Wetland Pathway (Station CAP-13), following the same schedule and methodology described above for Station CAP-3.

Wastewater effluent discharge samples are collected from the Final Discharge Point, located at the bottom of the cliff (Station CAP-14), following the same schedule and methodology described above for Station CAP-3.

Wastewater effluent discharge samples are collected from a Control Point (Station CAP-15) sampling location (small lake) located between the Lagoon and Tee Lake, following the same schedule and methodology described above for Station CAP-3.

#### 2.2.3.2 Landfill Runoff Sampling

Landfill runoff is collected once monthly during periods of observed flow from Station CAP-2. Runoff samples are collected from the receiving water body by immersing the sample bottle into the runoff stream neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with runoff and the sample bottle is raised neck first to prevent sample spillage.

#### 2.2.3.3 Groundwater Sampling

Groundwater samples are collected from a monitoring well located up gradient of the 2007 Sewage Disposal Facility (Station CAP-16), as well as from Monitoring Well No. 1 (Station CAP-17) and Monitoring Well No. 2 (Station CAP-18), located down gradient of the 2007 Sewage Disposal Facility. Groundwater samples are collected once annually in the summer, prior to commencing discharge from the 2007 Sewage Disposal Facility, giving due consideration to adequate ground thaw and obtaining representative groundwater samples. Groundwater samples should be collected using dedicated sampling tubing with Waterra™ foot valves (or bailers). Well purging should not be undertaken due to the potential limited availability of groundwater in the monitoring wells. Instead, samples should be collected of all available groundwater present in the monitoring wells.

Groundwater samples are collected from a monitoring well located up gradient of the Solid Waste Disposal Facility (Station CAP-19), as well as from a monitoring well located down gradient of the Solid Waste Disposal Facility (Station CAP-20). Groundwater samples are collected once annually in the summer, giving due consideration to adequate ground thaw and obtaining representative groundwater samples. Groundwater samples should be collected in the same manner as described above (i.e., for Stations CAP-16 to CAP-18).

## 2.3 Sample Handling

All water samples are to be collected in laboratory-supplied containers with the proper preservative, where applicable. A complete list of parameter handling and preservatives can be found in Appendix C.

All sample containers are to be tightly sealed and properly labelled with the sample ID, date and time of sample collection, location of sample collection and parameters to be analyzed. The outside of the bottles are to be cleaned with soap and water after sampling and dried off prior to placing the samples in the cooler. The samples are to be stored on ice in a cooler until delivery to the laboratory. A chain of custody form is to be filled out completely and is used to track the samples and placed in the cooler with the samples, in a ziplock bag. Keep the last page of the Chain of Custody and give it to the Hamlet Foreman for their records.

The following checks are generally performed by the laboratory upon receipt:

- Verification of the integrity and condition of all sample coolers.
- Verification of the integrity and condition of all sample containers.
- Checks for leakage, cracked or broken closures or containers, evidence of grossly contaminated container exteriors or shipping cooler interiors, and obvious odours, etc.
- Verification of receipt of complete documentation for each container.
- Verification that sample identification numbers on sample transmittal forms corresponds to sample identification numbers on the sample containers.
- Verifications that holding times were met and samples were kept cool during transit.

## 2.4 Quality Assurance and Quality Control Program

Cross contamination is a common source of error in sampling procedures. QC samples help identify when and how contamination might occur. There are various types of QC samples. For the purposes of the Hamlet's environmental monitoring, **exp** recommends the use of trip blanks.

**It is essential to request a trip blank sample to be prepared when placing the bottle order with the contract laboratory.**

## 3 Laboratory Analysis

### 3.1 Laboratory Accreditation

As indicated in the Guidelines, the Hamlet should use an analytical laboratory accredited by the Canadian Association for Laboratory Accreditation (CALA); formally known as the Canadian Association for Environmental Analytical Laboratories (CAEAL) for the monitoring program for NWB Licence 3BM-CAP0810. Appendix F includes a copy of the laboratory's CALA accreditation certificate and a list of the parameters for which they are certified.

### 3.2 Method Detection Limits

The method detection limits (MDLs) are provided on the contract laboratory's Certificates of Analysis.

## 4 Reporting Requirements

### 4.1 General Submissions

As a condition of NWB Licence 3BM-CAP0810 (Appendix B), the Hamlet is required to submit an Annual Report to the NWB, no later than March 31<sup>st</sup> of the year following the calendar year reported. Among other requirements, the annual report is required to include tabular summaries of all analytical data generated under the Monitoring Program (compared to the Maximum Average Concentrations – provided in Part D of the NWB Licence 3BM-CAP0810 – where applicable).



## 5 References

*Quality Assurance (QA) and Quality Control (QC) Guidelines for use by Class "B" Licensees in Collecting Representative Water Samples in the Field and for Submission of a QA/QC Plan*, Department of Indian and Northern Affairs Canada, July 1996.

*Standard Methods for the Examination of Water and Wastewater*, American Public Health Association, American Water Works Association, and Water Environment Federation, 22nd Edition, 2012.

This page intentionally left blank

## **Appendix A: Figures**

This page intentionally left blank



exp Services Inc.

t: +1.613.688.1899 | f: +1.613.225.7330  
2650 Queensview Drive, Unit 100  
Ottawa, ON K2B 8H6  
Canada

[www.exp.com](http://www.exp.com)

• BUILDINGS • EARTH & ENVIRONMENT • ENERGY •  
• INDUSTRIAL • INFRASTRUCTURE • SUSTAINABILITY •

scale	NTS	CLIENT:	CAPE DORSET, NUNAVUT	project no.	OTT-00209248-A0
date	27/05/13	TITLE:	LOCATION PLAN	FIG 01	
drawn by	M.KELLEY				





exp Services Inc.


t: +1.613.688.1899 | f: +1.613.225.7330  
2650 Queensview Drive, Unit 100  
Ottawa, ON K2B 8H6  
Canada

www.exp.com

• BUILDINGS • EARTH & ENVIRONMENT • ENERGY •  
• INDUSTRIAL • INFRASTRUCTURE • SUSTAINABILITY •

scale NTS	CLIENT: CAPE DORSET, NUNAVUT	project no. OTT-00209248-A0
date 27/05/13	TITLE: MONITORING STATION LOCATIONS	FIG 02
drawn by M.KELLEY		





**exp Services Inc.**

t: +1.613.688.1899 | f: +1.613.225.7330  
2650 Queensview Drive, Unit 100  
Ottawa, ON K2B 8H6  
Canada

[www.exp.com](http://www.exp.com)

• BUILDINGS • EARTH & ENVIRONMENT • ENERGY •  
• INDUSTRIAL • INFRASTRUCTURE • SUSTAINABILITY •

scale <b>NTS</b>	CLIENT: <b>CAPE DORSET</b>	project no. <b>OTT-00209248-A0</b>
date <b>27/05/13</b>	TITLE: <b>MONITORING STATION LOCATIONS</b>	<b>FIG 03</b>
drawn by <b>M.KELLEY</b>		

This page intentionally left blank



## **Appendix B:** **Hamlet of Cape Dorset's Water Licence**

This page intentionally left blank

Ministre des Affaires indiennes et  
du Nord canadien et interlocuteur fédéral  
auprès des Métis et des Indiens non inscrits



Minister of Indian Affairs and  
Northern Development and Federal Interlocutor  
for Métis and Non-Status Indians

Ottawa, Canada K1A 0H4

APR 21 2008

Mr. Thomas Kabloona  
Interim Chair  
Nunavut Water Board  
PO Box 119  
GJOA HAVEN NU X0B 1J0

Nunavut Water  
Board

APR 21 2008

Public Registry

Dear Mr. Kabloona:

This is in response to your letter of March 7, 2008, regarding water licence number 3BM-CAP0810 for the Hamlet of Cape Dorset, Nunavut, and the Nunavut Water Board's reasons for decision. I would like to thank the Nunavut Water Board for its work in the development of this licence.

I recognize the challenges faced by both the Nunavut Water Board and the joint proponents, the Government of Nunavut and the Hamlet of Cape Dorset, in finalizing the application for this licence, in the preparation for the public hearings, and in the drafting of this water licence. Moreover, I recognize the importance of improving Cape Dorset's sewage treatment infrastructure.

With this letter, I am approving water licence number 3BM-CAP0810 for the Hamlet of Cape Dorset. However, I would like to make some observations regarding two aspects of the water licence. In making this approval I have assumed that water licence number 3BM-CAP0810 renews then amends Cape Dorset's previous water licence number 3BM-CAP0207 which has expired. Indian and Northern Affairs Canada's enforcement activities will be based on this understanding. Additionally, conditions of licence number 3BM-CAP0810 (section 25.ii) could be interpreted to require departmental inspectors to evaluate the proponent's work in confirming the geotechnical assumptions made in the design of the wastewater facility for Cape Dorset. The limits of the Department's role in fulfilling such a condition would be to confirm whether the validation work required by the water licence is being conducted. Any evaluations of whether the project's design assumptions were accurate would be the role of the proponent.

.../2

Canada

Again, I thank the Nunavut Water Board for its efforts and energies in the development of the Hamlet of Cape Dorset water licence.

Sincerely,

A handwritten signature in cursive script, appearing to read "Chuck Strahl". The signature is written in dark ink on a white background.

Chuck Strahl

Encl:

c.c.: The Honourable Levinia Brown, MLA  
His Worship Fred Schell



**WATER LICENCE NO: 3BM-CAP0810**

## **TABLE OF CONTENTS**

<b>LICENCE 3BM-CAP0810 .....</b>	<b>1</b>
<b>PART A: SCOPE AND DEFINITIONS.....</b>	<b>1</b>
<b>PART B: GENERAL CONDITIONS.....</b>	<b>4</b>
<b>PART C: CONDITIONS APPLYING TO WATER USE .....</b>	<b>7</b>
<b>PART D: CONDITIONS APPLYING TO WASTE DISPOSAL.....</b>	<b>7</b>
<b>PART E: CONDITIONS APPLYING TO MODIFICATION AND CONSTRUCTION.....</b>	<b>9</b>
<b>PART F: CONDITIONS APPLYING TO OPERATION AND MAINTENANCE</b>	<b>10</b>
<b>PART G: CONDITIONS APPLYING TO ABANDONMENT AND RESTORATION .....</b>	<b>12</b>
<b>PART H: CONDITIONS APPLYING TO THE MONITORING PROGRAM.....</b>	<b>13</b>
<b>SCHEDULE 1.....</b>	<b>19</b>
<b>SCHEDULE 2.....</b>	<b>21</b>

## ANNEX B

### LICENCE 3BM-CAP0810

Pursuant to the *Nunavut Waters and Nunavut Surface Rights Tribunal Act* and the *Agreement Between the Inuit of the Nunavut Settlement Area and Her Majesty the Queen in Right of Canada*, the Nunavut Water Board, hereinafter referred to as the Board, hereby grants to

#### HAMLET OF CAPE DORSET

(Licensee)

of P.O. BOX 30, CAPE DORSET, NUNAVUT X0A 0C0  
(Mailing Address)

hereinafter called the Licensee, the right to alter, divert or otherwise use water for a period subject to restrictions and conditions contained within this licence:

Licence Number 3BM-CAP0810

Water Management Area NUNAVUT 05

Location CAPE DORSET, NUNAVUT  
Latitude 64°14'N and Longitude 76°32'W

Purpose WATER USE AND WASTE DISPOSAL

Description MUNICIPAL UNDERTAKINGS

Quantity of Water Not to Exceed 70,000 CUBIC METRES ANNUALLY

Date of Licence MARCH 7, 2008

Expiry Date of Licence MARCH 1, 2010



Thomas Kabloona,  
Nunavut Water Board  
A/Chair

APPROVED  
BY:



Minister of Indian and  
Northern Affairs  
Canada

DATE LICENCE APPROVED:

APR 21 2008

## **PART A: SCOPE, DEFINITIONS AND ENFORCEMENT**

### **1. Scope**

- a. This Licence allows for the use of water and the disposal of waste for municipal undertakings at the Hamlet of Cape Dorset, Nunavut (Latitude 64°14'N and Longitude 76°32'W);
- b. This Licence is issued subject to the conditions contained herein with respect to the taking of water and the depositing of waste of any type in any waters or in any place under any conditions where such waste or any other waste that results from the deposits of such waste may enter any waters. Whenever new Regulations are made or existing Regulations are amended by the Governor in Council under the *Nunavut Waters and Nunavut Surface Rights Tribunal Act*, or other statutes imposing more stringent conditions relating to the quantity or type of waste that may be so deposited or under which any such waste may be so deposited, this Licence shall be deemed, upon promulgation of such Regulations, to be subject to such requirements; and
- c. Compliance with the terms and conditions of this Licence does not absolve the Licensee from responsibility for compliance with the requirements of all applicable Federal, Territorial and Municipal legislation.

### **2. Definitions**

**“Act”** means the *Nunavut Waters and Nunavut Surface Rights Tribunal Act*;

**“Amendment”** means a change to original terms and conditions of this licence requiring correction, addition or deletion of specific terms and conditions of the licence; modifications inconsistent with the terms of the set terms and conditions of the Licence;

**“Analyst”** means an Analyst designated by the Minister under Section 85 (1) of the *Act*;

**“Appurtenant undertaking”** means an undertaking in relation to which a use of waters or a deposit of waste is permitted by a licence issued by the Board;

**“Average Concentration”** means the arithmetic mean of the last four consecutive analytical results for contained in composite or grab samples collected from the Waste Disposal Facility’s final discharge point;



**“Average Concentration For Faecal Coliforms”** means the geometric mean of the last four consecutive analytical results for faecal coliforms contained in composite or grab samples collected from the Waste Disposal Facility’s final discharge point;

**“Board”** means the Nunavut Water Board established under the *Nunavut Land Claims Agreement*;

**“Chief Administrative Officer”** means the Executive Director of the Nunavut Water Board;

**“Composite Sample”** means a water or wastewater sample made up of four (4) samples taken at regular periods over a 24 hour period;

**“Effluent”** means treated or untreated liquid waste material that is discharged into the environment from a structure such as a settling pond or a treatment plant;

**“Engineer”** means a professional engineer registered to practice in Nunavut in accordance with the *Engineering, Geological and Geophysical Act (Nunavut)* S.N.W.T. 1998, c.38, s.5;

**“Final Discharge Point”** means the discharge location point where the effluent from the 2007 Sewage Disposal Facilities enters fish habitat or fish bearing waters;

**“Final Point of Control”** means the discharge location at the 2007 Sewage Disposal Facilities August 27, 2007 submission prepared by Dillon Consulting including ten appendices, to be confirmed by an Inspector;

**“Freeboard”** means the vertical distance between water line and crest on a dam or dyke’s upstream slope;

**“Geotechnical Engineer”** means a professional engineer registered with the Association of Professional Engineers, Geologist and Geophysicists of Nunavut and whose principal field of specialization with the engineering properties of earth materials in dealing with man-made structures and earthworks that will be built on a site. These can include shallow and deep foundations, retaining walls, dams, and embankments;

**“Grab Sample”** means a single water or wastewater sample taken at a time and place representative of the total discharge;

**“Greywater”** means all liquid wastes from showers, baths, sinks, kitchens and domestic washing facilities, but does not include toilet wastes;

**“Inspector”** means an Inspector designated by the Minister under Section 85 (1) of the

Act;

**“Licensee”** means the holder of this Licence;

**“Modification”** means an alteration to a physical work that introduces new structure or eliminates an existing structure and does not alter the purpose or function of the work, but does not include an expansion, and changes to the operating system that are consistent with the terms of this Licence and do not require amendment;

**“Monitoring Program”** means a monitoring program established to collect data on surface water and groundwater quality to assess impacts to the freshwater aquatic environment of an appurtenant undertaking;

**“Nunavut Land Claims Agreement”** (NLCA) means the *“Agreement Between the Inuit of the Nunavut Settlement Area and Her Majesty the Queen in right of Canada”*, including its preamble and schedules, and any amendments to that agreement made pursuant to it;

**“Sewage”** means all toilet wastes and greywater;

**“Sewage Disposal Facilities”** includes the facilities licensed in 2001, 2004 and 2007;

**“Emergency Sewage Disposal Facility”** comprises the area designed to contain and treat sewage as described in the Water Licence Amendment Application filed by the Applicant on August 16, 2004, and illustrated on the “Cape Dorset Sewage Lagoon Rehabilitation Site Plan (August 2004)”

**“2001 Sewage Disposal Facilities”** comprises the Three Tier Lagoon which comprises the area and engineered lagoon and decant structures designed to contain sewage as described in the Application for Water Licence filed by the Applicant on April 19, 2001;

**“2007 Sewage Disposal Facilities”** comprises the engineered lagoon and decant structures constructed in 2007 and illustrated in the Record Drawings No.’s 100 and 101 of Project N-05-4319-3000 prepared by Dillon Consulting and submitted November 13, 2007;

**“Solid Waste Disposal Facilities”** comprises the area and associated structures designed to contain solid waste (landfill site) as described in the Application for Water Licence filed by the Applicant on April 19, 2001;

**“Toilet Wastes”** means all human excreta and associated products, but does not include greywater;

**“Waste”** means, as defined in S.4 of the *Act*, any substance that, by itself or in combination with other substances found in water, would have the effect of altering the quality of any water to which the substance is added to an extent that is detrimental to its use by people or by any animal, fish or plant, or any water that would have that effect because of the quantity or concentration of the substances contained in it or because it has been treated or changed, by heat or other means;

**“Waste Disposal Facilities”** means all facilities designated for the disposal of waste, and includes the 2001, 2004 and 2007 Sewage Disposal Facilities, Solid Waste Disposal Facilities, and Bagged Toilet Waste Disposal Facilities, as described in the Application for Water Licence filed by the Applicant on April 19, 2001 and subsequently in the application dated July 7, 2005;

**“Water Supply Facilities”** comprises the area and associated intake infrastructure at Tee Lake, as described in the Application for Water Licence filed by the Applicant on April 19, 2001;

### **3. Enforcement**

- i. Failure to comply with this Licence will be a violation of the *Act*, subjecting the Licensee to the enforcement measures and the penalties provided for in the *Act*;
- ii. All inspection and enforcement services regarding this Licence will be provided by Inspectors appointed under the *Act*; and
- iii. For the purpose of enforcing this Licence and with respect to the use of water and deposit or discharge of waste by the Licensee, Inspectors appointed under the *Act*, hold all powers, privileges and protections that are conferred upon them by the *Act* or by other applicable law.
- iv. The Licensee shall, in relation to any application to renew or amend the Licence, have in place a Plan for Compliance approved by the Board in writing, to achieve full compliance with the conditions of this Licence, or a Plan for Compliance must be submitted at the time of Application, in order for the Application to be deemed complete.

## **PART B: GENERAL CONDITIONS**

1. The Licensee shall file an Annual Report with the Board not later than March 31st of the year following the calendar year reported which shall contain the following information:

- i. tabular summaries of all data generated under the Monitoring Program;
  - ii. the monthly and annual quantities in cubic metres of fresh water obtained from all sources;
  - iii. the monthly and annual quantities in cubic metres of each and all waste discharged;
  - iv. a summary of modifications and/or major maintenance work carried out on the Water Supply and Waste Disposal Facilities, including all associated structures and facilities;
  - v. a list of unauthorized discharges and summary of follow-up action taken;
  - vi. a summary of any abandonment and restoration work completed during the year and an outline of any work anticipated for the following year;
  - vii. a summary of any studies, reports and plans (i.e. Operations and Maintenance, Abandonment and Restoration, QA/QC) requested by the Board that relate to water use and waste disposal or reclamation, and a brief description of any future studies planned; and
  - viii. any other details on water use or waste disposal requested by the Board by November 1st of the year being reported.
2. The Licensee shall comply with the Monitoring Program described in this Licence, and any amendments to the Monitoring Program as may be made from time to time, pursuant to the conditions of this Licence.
3. The Monitoring Program and compliance dates specified in the Licence may be modified at the discretion of the Board.
4. Meters, devices or other such methods used for measuring the volumes of water used and waste discharged shall be installed, operated and maintained by the Licensee.
5. The Licensee shall, within ninety (90) days after the first visit by the Inspector following issuance of this Licence, post the necessary signs, to identify the stations of the Monitoring Program. All signage postings shall be in the Official Languages of Nunavut.
6. The Licensee shall submit to the Board, for approval in writing, within the lesser of ninety (90) days or the filing of any application in relation to the Licence, a Plan for Compliance that clearly demonstrates the ways and means the Licensee will undertake to achieve full compliance with the conditions of this Licence.
7. The Licensee shall, for all Plans submitted under this Licence, include a proposed timetable for implementation. Plans submitted, cannot be undertaken without subsequent written Board approval and direction. The Board may alter or modify a Plan if necessary to achieve the legislative objectives and will notify the Licensee in writing of acceptance, rejection or alteration of the Plan.

8. Every Plan to be carried out pursuant to the terms and conditions of this Licence shall become a part of this Licence, and any additional terms and condition imposed upon approval of a Plan by the Board become part of this Licence. All terms and conditions of the Licence should be contemplated in the development of a Plan where appropriate.
9. The Licensee shall immediately report to the 24-Hour Spill Report Line (867-920-8130) any spills of Waste, which are reported to, or observed by the Licensee, within the municipal boundaries or in the areas of the Water Supply or Waste Disposal Facilities.
10. The Licensee shall ensure a copy of this Licence is maintained at the municipal office at all times. Any communication with respect to this Licence shall be made in writing to the attention of:

**Manager of Licensing:**

Nunavut Water Board  
P.O. Box 119  
Gjoa Haven, NU X0B 1J0  
Telephone: (867) 360-6338  
Fax: (867) 360-6369  
Email: [licensing@nunavutwaterboard.org](mailto:licensing@nunavutwaterboard.org)

**Inspector Contact:**

Water Resources Officer  
Nunavut District, Nunavut Region  
P.O. Box 100  
Iqaluit, NU X0A 0H0  
Telephone: (867) 975-4295  
Fax: (867) 979-6445

**Analyst Contact:**

Taiga Laboratories  
Department of Indian and Northern Affairs  
4601 – 52 Avenue, P.O. Box 1500  
Yellowknife, NT X1A 2R3  
Telephone: (867) 669-2781  
Fax: (867) 669-2718

11. The Licensee shall submit one paper copy and one electronic copy of all reports, studies, and plans to the Board. Reports or studies submitted to the Board by the Licensee shall include a detailed executive summary in Inuktitut.
12. The Licensee shall ensure that any document(s) or correspondence submitted by the

Licensee to the Board, is received by the Board and maintain on file a copy of the acknowledgment of receipt issued by the Manager of Licensing.

13. This Licence is not assignable except as provided in Section 44 of the Act.

#### **PART C: CONDITIONS APPLYING TO WATER USE**

1. The Licensee shall obtain all fresh water from the Tee Lake using the Water Supply Facilities or as otherwise approved by the Board in writing.
2. The annual quantity of water used for all purposes shall not exceed 70,000 cubic metres.
3. The Licensee shall equip all water intake hoses with a screen of an appropriate mesh size to ensure that fish are not entrained and shall withdraw water at a rate such that fish do not become impinged on the screen.
4. The Licensee shall not remove any material from below the ordinary high water mark of any water body unless otherwise approved by the Board in writing.
5. The Licensee shall not cause erosion to the banks of any body of water and shall provide necessary controls to prevent such erosion.
6. Sediment and erosion control measures shall be implemented prior to and maintained during the operation to prevent entry of sediment into water.

#### **PART D: CONDITIONS APPLYING TO WASTE DISPOSAL**

1. Licensee shall locate areas designated for waste disposal at a minimum distance of thirty (30) metres from the ordinary high water mark of any water body such that the quality, quantity or flow of water is not impaired, unless otherwise approved by the Board in writing.
2. Subject to the conditions in the Licence regarding commissioning, the Licensee shall direct all Sewage to the 2007 Sewage Disposal Facilities or as otherwise approved by the Board in writing.
3. The Licensee shall provide notice to an Inspector at least ten (10) days prior to initiating any decant of the 2001 and 2007 Sewage Disposal Facilities.
4. All Effluent discharge from the 2001 Sewage Disposal Facility at Monitoring Program Station CAP-3 and the Emergency Sewage Disposal Facility at Monitoring Program

Station CAP-4, shall meet the following effluent quality limits:

<b>Parameter</b>	<b>Maximum Average Concentration</b>
BOD <sub>5</sub>	120 mg/L
Total Suspended Solids	180 mg/L
Faecal Coliforms	$1 \times 10^4$ CFU/100mL
Oil and grease	No visible sheen
pH	between 6 and 9

5. All Effluent discharged from the 2007 Sewage Disposal Facilities at Monitoring Program Station CAP-5 shall meet the following effluent quality limits:

<b>Parameter</b>	<b>Maximum Average Concentration</b>
BOD <sub>5</sub>	80 mg/L
Total Suspended Solids	100 mg/L
Faecal Coliforms	$1 \times 10^4$ CFU/100mL
Oil and grease	No visible sheen
pH	between 6 and 9

6. The Licensee shall maintain at all times, a freeboard of at least 1.0 metre, or as recommended by a qualified Geotechnical Engineer with notice in writing provided to the Board, for all dams, dykes or other structures intended to contain, withhold, divert or retain water or wastes.
7. The Sewage Disposal Facilities shall be maintained and operated in such a manner as to prevent structural failure.
8. All Effluent discharged from the 2007 Sewage Disposal Facility at the Final Discharge Point at Monitoring Station CAP-14 and effluent discharge from Monitoring Stations CAP-3 and CAP-4 prior to the point of entry at the ocean, shall be demonstrated to be non-acutely toxic under the following tests to be conducted once annually, approximately mid-way through the discharge period:
- Acute lethality to Rainbow Trout, *Oncorhynchus mykiss* (as per Environment Canada's Environmental Protection Series Biological Test Method EPS/1/RM/13); or

- ii. Acute lethality to the crustacean, *Daphnia magna* (as per Environment Canada's Environmental Protection Series Biological Test Method EPS/1/RM/14).
- 9. The Licensee shall dispose of and contain all solid wastes at the Solid Waste Disposal Facilities or as otherwise approved by the Board in writing.
- 10. The Licensee shall implement appropriate erosion and diversion control methods, to minimize surface water intrusion and leachate generation at the Solid Waste Storage Facility.
- 11. The Licensee shall segregate and securely store all hazardous materials and/or hazardous waste within the Solid Waste Disposal Facility in a manner as to prevent the deposit of deleterious substances into any water.

#### **PART E: CONDITIONS APPLYING TO MODIFICATION AND CONSTRUCTION**

- 1. The Licensee shall submit to the Board, for approval in writing, design drawings stamped by a qualified engineer registered in Nunavut prior to the construction of any dams, dykes or structures intended to contain, withhold, divert or retain water or wastes.
- 2. The Licensee may, without written approval from the Board, carry out modifications to the Water Supply and Waste Disposal Facilities provided that such modifications are consistent with the terms of this Licence and the following requirements are met:
  - i. the Licensee has notified the Board in writing of such proposed modifications at least sixty (60) days prior to beginning the modifications;
  - ii. these modifications do not place the Licensee in contravention of the Licence or the Act;
  - iii. the Board has not, during the sixty (60) days following notification of the proposed modifications, informed the Licensee that review of the proposal will require more than sixty (60) days; and
  - iv. the Board has not rejected the proposed modifications.
- 3. Modifications for which all of the conditions referred to in Part E, Item 2, have not been met may be carried out only with written approval from the Board.
- 4. The Licensee shall provide as-built plans and drawings of the Modifications referred to in this Part within ninety (90) days of completion of the Modification. These plans and



drawings shall be stamped by an Engineer.

5. The Licensee shall, within sixty (60) days of issuance of this Licence, provide a summary report along with revised stamped as-built plans and record drawings of the 2007 Sewage Disposal Facility, to reflect the clarifications and omissions identified through the Licence application review and detailed in the attached Schedule 1.
6. All activities shall be conducted in such a way as to minimize impacts on surface drainage and the Licensee shall immediately undertake corrective measures to restore natural surface drainage in the event of any impacts on surface drainage
7. The Licensee shall ensure that sediment and erosion control measures are implemented prior to and maintained during the operation to prevent the release of sediment and minimize erosion during construction activities.
8. The Licensee shall designate an area for the deposition of excavated and stockpiled materials that is at least thirty (30) metres above the ordinary high water mark of any water body and in such a manner as to prevent sediment from entering any surrounding water body.
9. The Licensee shall ensure that both (a) fill material used in construction, and (b) that the ground to be constructed upon, are free of contaminants. If contaminated soils are identified, notification shall be made in the Licensee's annual report. All contaminated soils shall be treated and disposed of in accordance with Part F, Item 2, or as otherwise approved by the Board in writing.

#### **PART F: CONDITIONS APPLYING TO OPERATION AND MAINTENANCE**

1. The Licensee shall submit to the Board, for approval in writing, within ninety (90) days of issuance of the Licence and prior to commissioning of the 2007 Sewage Disposal Facilities, a revised *Operation and Maintenance Manual, Sewage Treatment System, Hamlet of Cape Dorset, November 7, 2007*. The revision shall include the requirements of Schedule 2.
2. The Licensee shall submit to the Board, for approval in writing, within ninety (90) days of issuance of the Licence, an Operation and Maintenance Manual for the Water Supply Facilities and the Solid Waste Disposal Facilities prepared in accordance with the *"Guidelines for Preparing an Operation and Maintenance Manual for Sewage and Solid Waste Disposal Facilities"*, October 1996. The Plan shall include a specific section addressing waste management and the proper diversion and segregation of wastes, the storage, transport and disposal of hazardous wastes materials.

3. The Licensee shall implement the Manuals specified in Part F, Items 1 and 2, following approval in writing by the Board.
4. The Licensee shall provide notification in writing to the Board, in accordance with Part E, Item 2, of changes to the approved Operation and Maintenance Plan under Part F, Item 1, with respect to the wastewater storage and decanting operations and procedures. For any potential significant impact of such change to the geothermal regime within and under the berms or lagoon floor, notice shall be accompanied by the Geotechnical Engineer's supporting documentation and further geotechnical analysis.
5. An inspection of all engineered facilities related to the management of water and waste shall be carried out annually in July, by a Geotechnical Engineer in accordance with the Canadian Dam Association, Dam Safety Guidelines, November 2007, where applicable. This inspection shall include the access road alignment with respect to water resources and the diversion and passage of water through culverts. The engineer's report shall be submitted to the Board within sixty (60) days of the inspection, including a covering letter from the Licensee outlining an implementation plan addressing each of the Engineer's recommendations.
6. The Licensee shall perform a visual operations inspection of all engineered facilities related to the management of water and waste on a weekly basis or more frequently as requested by an Inspector, to assess the general operating conditions and integrity of the containment structures. The records of these inspections are to be maintained and made available to an Inspector upon request during the Licence term.
7. The Licensee shall review the Manual(s) referred to in this Part if there are changes in operation and/or technology and modify the Manual(s) accordingly. Revisions to the Board approved Manual(s) are to be submitted in the form of an Addendum to be included with the Annual Report under Part B, Item 1.
8. If, during the period of this Licence, an unauthorized discharge of waste occurs, or if such a discharge is foreseeable, the Licensee shall:
  - i. employ the appropriate contingency plan as provided for in the Operation and Maintenance Manual;
  - ii. report the incident immediately via the 24-Hour Spill Reporting Line at (867) 920-8130 and to the Inspector at (867) 975-4295; and
  - iii. submit to the Inspector, a detailed report on each occurrence, no later than thirty (30) days after initially reporting the event, that provides the necessary information on the location (including the GPS coordinates), initial response action, remediation/clean-up, status of response (ongoing, complete), proposed disposal options for dealing with contaminated materials and preventative measures to be implemented.

**PART G: CONDITIONS APPLYING TO ABANDONMENT, RESTORATION AND CLOSURE**

1. The Licensee shall submit to the Board, for approval in writing, within ninety (90) days of issuance of the Licence, a detailed Final Abandonment and Restoration Plan for the 2001 Sewage Disposal Facility and the Emergency Sewage Disposal Facility. The Plan should incorporate, where applicable, the appropriate sections as described in Part G, Item 2.
2. The Licensee shall submit to the Board, for approval in writing, within six (6) months of issuance of this Licence, a preliminary or conceptual Abandonment and Restoration Plan for the Hamlet of Cape Dorset, Water and Waste Disposal Facilities and all associated structures not covered under Part G, Item 1, with end objectives to return the site to pre-use conditions. The Plan shall include the following (where applicable):
  - i. water intake facilities;
  - ii. the water treatment and waste disposal sites and facilities;
  - iii. petroleum and chemical storage areas;
  - iv. any site affected by waste spills;
  - v. leachate prevention;
  - vi. an implementation and completion schedule;
  - vii. maps delineating all disturbed areas, and site facilities;
  - viii. consideration of altered drainage patterns;
  - ix. type and source of cover materials;
  - x. future area use;
  - xi. hazardous wastes; and
  - xii. a proposal identifying measures by which restoration costs will be financed by the Licensee upon abandonment.
3. The Licensee shall submit to the Board, for approval in writing, six (6) months prior to the planned decommissioning of any licensed facility and the construction of new facilities to replace existing ones, a Final Abandonment and Restoration Plan for the facilities being decommissioned.
4. The Licensee shall implement the Plan(s) specified in Part G, Item 1 and 3, following approval in writing by the Board.
5. The Licensee shall review the Plan(s) referred to in this Part if there are changes in operation and/or technology and modify the Plan accordingly. Revisions to the Board approved Plan(s) are to be submitted in the form of an Addendum to be included with the Annual Report under Part B, Item 1.

6. The Licensee shall carry out progressive reclamation of any components of the project no longer required for the Licensee's operations.
7. The Licensee shall complete the restoration work within the time schedule specified in the Plan, or as subsequently revised and approved by the Board.
8. The Licensee shall complete all restoration work prior to the expiry of this Licence.

**PART H: CONDITIONS APPLYING TO THE MONITORING PROGRAM**

1. The Licensee shall maintain Monitoring Program Stations at the following locations:

<b>Monitoring Program Station Number</b>	<b>Description</b>	<b>Status</b>
CAP-1	Raw Water supply prior to treatment	Active (Volume)
CAP-2	Runoff from the Solid Waste Disposal Facilities	Active
CAP-3	Influent of Wastewater to Wastewater Facilities (active at the time of sampling)	New
CAP-4	Effluent Discharge from the 2001 Sewage Disposal Facilities	Active (including volume)
CAP-5	Effluent discharge from the Emergency Sewage Disposal Facilities	Active (including volume)
CAP-6	Effluent discharge from the 2007 Sewage Disposal Facilities – Final Point of Control	Active (including volume)
CAP-7	Point of influent of wastewater to P-Lake	New
CAP-8	Centre of P-Lake	New
CAP-9	Location midway between the Centre of P-Lake (Station 8) and the effluent discharge of P-Lake	New

Monitoring Program Station Number	Description	Status
CAP-10	Effluent discharge from P-Lake; note, if flow is negligible a sample from the immediate upstream area within P-Lake shall be obtained	New
CAP-11	Effluent discharge from Wetland area	New
CAP-12	Wetland Pathway at the top of the waterfall	New
CAP-13	Wetland Pathway at mid-way down waterfall	New
CAP-14	Wetland Pathway at bottom of cliff – Final Discharge Point	
CAP-15	Control point using a small lake located between the Lagoon and Tee Lake	New
CAP-16	Monitoring well located up gradient of the 2007 Sewage Disposal Facility	New
CAP-17	Monitoring Well No.1 located down gradient of the 2007 Sewage Disposal Facility	New
CAP-18	Monitoring Well No.2 located down gradient of the 2007 Sewage Disposal Facility	New
CAP-19	Monitoring well located up gradient of the Solid Waste Disposal Facilities	New
CAP-20	Monitoring well located down gradient of the Solid Waste Disposal Facilities	New
CAP-21	Thermistor stations	Proposed with final description to be provided
CAP-22	As above	
CAP-23	As above	
CAP-24	As above	

2. The Licensee shall sample at Monitoring Program Stations CAP-3 through CAP-15 inclusive, one week prior to the proposed discharge date, once at the beginning of discharge and weekly thereafter until cessation of discharge. Samples shall be analyzed for the following parameters:

Biochemical Oxygen Demand (BOD<sub>5</sub>)

Carbonaceous Biochemical Oxygen Demand (CBOD<sub>5</sub>)

Total Suspended Solids

pH

Conductivity

Oil and Grease (visual)

Fecal Coliforms

Nitrate-Nitrite

Total Phosphorus

Magnesium

Sodium

Chloride

Total Hardness

Ammonia Nitrogen

Total Phenols

Calcium

Potassium

Sulphate

Total Alkalinity

Total Trace Metals as determined by a standard ICP Scan (to include at a minimum, the following elements: Al, Sb, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Li, Mn, Mo, Ni, Se, Sn, Sr, Tl, Ti, U, V, Zn),

Total Arsenic

Total Mercury

Total Organic Carbon (TOC)

3. If the discharge at Station CAP-4, CAP-5 or CAP-6 has been suspended for more than 48 hours and subsequently restarted, the sampling sequence described in Part H, Item 2 of the Monitoring Program shall be repeated for these Stations.
4. The Licensee shall sample monthly at Monitoring Program Station CAP-2 during periods of observed flow. Samples shall be analyzed for the following parameters:

BOD <sub>5</sub>	Fecal Coliforms
pH	Conductivity
Total	Suspended Solids
Nitrate-Nitrite	Ammonia Nitrogen
Total Phenols	Oil and Grease
Total Hardness	Total Alkalinity
Magnesium	Calcium
Sodium	Potassium
Total Arsenic	Sulphate
Total Copper	Total Cadmium
Total Iron	Total Chromium
Total Mercury	Total Lead
	Total Nickel

5. The Licensee shall report all results of non-acute toxicity testing as required under Part D, Item 8 within the Annual Report as per Part B, Item 1.
6. The Licensee shall install thermistors for the purpose of validating assumptions made in the geothermal analyses for the 2007 Sewage Disposal Facilities as recommended by the Geotechnical Engineer of record and agreed upon by the Licensee, subject to a minimum of three 20 to 25 metre deep thermistors installed in crest of the west berm and at least one thermistor of that depth in the east berm.
7. The results of thermistor monitoring required under Part II, Item 6, shall be submitted to the Board for approval in writing, prior to commissioning of the 2007 Sewage Disposal Facility. The results shall include an Engineer's Report, validating the assumptions of the geothermal analysis through adequate monitoring of the thermal regime for the East and West Berms and downstream foundations
8. The Licensee shall not commission the 2007 Sewage Disposal Facility until the requirements of Part H, Item 6 and Item 7 have been completed and approved.
9. The Licensee shall, within ninety (90) days of issuance of this Licence, provide a Temperature Monitoring Program and Implementation Plan for ongoing collection of ground temperatures within each berm structure and foundation of the 2007 Sewage Disposal Facility through the installation of thermistors. This Plan shall take into consideration the following:
  - i. Locations of thermistors, to be incorporated into the Monitoring Station Table under Part H, Item 1;
  - ii. Appropriate thermistor configuration, overall depth and spacing of bead locations to provide the level of data collection that will capture any extreme variations in temperature and provide the information needed to validate the assumptions made in the geothermal analysis.
  - iii. The frequency of temperature readings shall be such to allow the determination of the maximum freeze and thaw of the berm and underlying native materials and provide adequate data for thermal modeling of the berms.
  - iv. This frequency may be reviewed and adjusted upon collection of adequate data and as recommended by the Geotechnical Engineer in order to assess the berms through thermal modeling and provide an assessment with respect to berm stability and potential seepage.
  - v. This information is to be reported along with the results of the annual geotechnical inspection as required under Part F, Item 6.
  - vi. An implementation schedule that will allow collection of data for confirmation of core-trench freeze-back.

10. The Licensee shall implement the Plan specified in Part II, Item 9 following approval by the Board in writing.
11. The Licensee shall review the Plan(s) referred to in this Part if there are changes in operation and/or technology and modify the Plan accordingly. Revisions to the Board approved Plan(s) are to be submitted in the form of an Addendum to be included with the Annual Report under Part B, Item 1.
12. The Licensee shall install groundwater monitoring wells at the 2007 Sewage Disposal Facility to obtain at least one monitoring season of data prior to the expiry of the Licence. At least one groundwater monitoring well shall be located upstream of the 2007 Sewage Disposal Facility for background data collection, at least one groundwater monitoring well shall be located downstream of the landfill and at least one groundwater monitoring well shall be located downstream of the metals dump.
13. The Licensee shall sample at Monitoring Program Stations CAP-16, CAP-17 and CAP-18 once annually in the summer, prior to commencing discharge from the 2007 Sewage Disposal Facility, giving due consideration to adequate ground thaw and obtaining a representative groundwater sample. Samples shall be analyzed for parameters identified in Part H, Item 4.
14. The Licensee shall install groundwater monitoring at the Solid Waste Disposal Facilities wells to obtain at least one monitoring season of data prior to the expiry of the Licence, At least one groundwater monitoring well shall be located upstream of the Solid Waste Disposal Facilities for background data collection and at least one groundwater monitoring well shall be located downstream of the Solid Waste Disposal Facilities .
15. The Licensee shall sample at Monitoring Program Stations CAP-19 and CAP-20 once annually in the summer season, giving due consideration to adequate ground thaw and obtaining a representative groundwater sample. Samples shall be analyzed for parameters identified in Part H, Item 4.
16. The Licensee shall measure and record in cubic metres, the monthly and annual quantities of water pumped for all purposes at Monitoring Program Station CAP-1.
17. The Licensee shall measure and record in cubic metres (a) the monthly and annual quantities of raw sewage offloaded from trucks and the number of days of use for the 2001 Sewage Disposal Facility and the Emergency Sewage Disposal Facility, and (b) the monthly and annual quantities of raw sewage offloaded from trucks at the 2007 Sewage Disposal Facility.
18. The Licensee shall measure and record the annual quantities of sewage solids removed from the Sewage Disposal Facilities.



19. The Licensee shall conduct additional sampling and analysis as may be requested by an Inspector.
20. The Licensee shall revise the "Guidelines for Wastewater Sampling, October 27, 2007" and submit to the Board for approval by an Analyst in writing a Quality Assurance/Quality Control (QA/QC) Plan for the Hamlet of Cape Dorset, within ninety (90) days of issuance of this Licence. The Plan shall use as a guide the document "*Quality Assurance and Quality Control Guidelines for use by Class "B" Licensees in Collection of Representative Water Samples in the Field, and for Submission of a QA/QC Plan, July 1996*". The Plan shall address the use of field blanks, replicate sampling and certified reference material in order to assess accuracy, precision and field contamination.
21. The Licensee shall implement the Plan referred to in Part H, Item 20 following approval in writing by the Analyst.
22. All sampling, sample preservation and analyses shall be conducted in accordance with methods prescribed in the current edition of *Standard Methods for the Examination of Water and Wastewater*, or by such other methods approved by the Board.
23. All analyses shall be performed in a Canadian Association of Environmental Analytical Laboratories (CAEAL) Certified Laboratory, or as otherwise approved by an Analyst.
24. The Licensee shall include all of the data and information required by the "Monitoring Program" in the Licensee's Annual Report, as required *per* Part B, Item 1 or as otherwise requested by an Inspector.
25. Her Majesty in the right of Canada shall:
  - i. Monitor the Licensee's installation of thermistors and notify the Board when the installation of thermistors is complete and in compliance with Part H, Item 6;
  - ii. Monitor the Licensee's validation of the assumptions of the geothermal analysis through adequate monitoring of the thermal regime for the East and West Berms and downstream foundations under Part H, Item 7, and notify the Board when satisfied the assumptions of the geothermal analysis have been validated; and
  - iii. Monitor the 2007 Waste Disposal Facility and notify the Board immediately if the Project is commissioned prior to the completion of i. and ii., or in contravention of any other condition of the Licence.

## **SCHEDULE 1      CONDITIONS APPLYING TO MODIFICATIONS AND CONSTRUCTION**

### **List of drawing deficiencies identified by BGC for revision and submission.**

Please refer to Technical Memorandum "Cape Dorset Sewage lagoon-Review of Final Submissions, January 8, 2008", or the final intervention memo dated January 8, 2008 for further clarification.

The record set of drawings fails to include a signature block for AMEC. It was noted that the original design drawings issued by Dillon in the December 21, 2006 design report, revision 5, marked "Issued for Construction" included a signature block "Reviewed by AMEC" on Drawing 111, which is the equivalent of Drawing 112 of the Record Drawings

1.      At a minimum, AMEC is to provide a signature block for the following drawings:
  - Drawing 101- shows location of test pits carried out for geotechnical investigations.
  - Drawing 109- shows longitudinal geological sections along cut-off trench.
  - Drawing 110- shows typical earthworks sections for the access road and berm.
  - Drawing 112- shows lagoon berm sections
2.      The as-built drawings must identify the areas where field changes were made from the original design drawings, preferably in the form of a revision bubble and a brief note in the revisions section of the title block.

### **List of Drawing alterations and request for rationale for the change.**

Record drawing 100 - the alignment of the access roads between the East and West Berms, on the north and south sides of the lagoon was changed from the original design. The road berms were originally designed to deflect runoff from entering the lagoon.

3.      Explanation is required as to the rationale for changing the alignment of the road berms and how the as-built berm details in the drawing prevents runoff from entering the lagoon.

Record Drawing 109 - there is up to 1m of unfrozen fill used to level the ground surface under both the East and West berms. This leveling course of material has not been shown as a separate zone in the berm sections presented in Record Drawing 112.

4.      A description for record drawing 112 is required of the material used including grain size gradation curve.

Record Drawing 109 shows that the berm contours at the north end of the West Berm have been modified from the original design drawings. Crest widened from 4m to 25m to accommodate what appears to be a vehicle turnaround on the downstream side of the berm.

5. Additional as-built cross-sections of this area are to be provided along with geothermal analysis that there is sufficient fill thickness over the abutment to ensure that the GCL tie-in to the cut-off trench remains frozen.

Record Drawing 110 shows typical road sections. On July 30, 2007, the GN CGS provided a revised ditch detail for the road

6. This revised ditch detail is requested as part of the as-built drawing details for Drawing 110
7. Additional information is requested providing further details as to how seepage through the active zone under the berm will be prevented.

The Hamlet of Cape Dorset noted a problem during the October 1, 2007 Technical Meeting/Pre-Hearing, with seepage into the lagoon through the active zone with the as-constructed detail. Record Drawing 112 indicates that the material used to backfill the cut-off trench is a "Sand", the same material as used for the berm.

8. Further clarification is requested on how the issue of seepage is being resolved.

In the original Design Drawing 111, Detail 4 showed the liner embedment longitudinal section in the abutments. This Detail was absent from Record Drawing 112. The cut-off trench must extend sufficient distance into the abutment so that any "end-run" seepage through the active zone is prevented. It is not clear from the as-built information if the extent of the cut-off trench satisfies this criterion.

9. Therefore the as-built liner embedment details for the abutment areas of the East and West Berms are therefore requested to be included for Record Drawing 112.

In Record Drawing 112, the crest detail of the emergency overflow weir section was changed. This change notice was transmitted to the contractor by Dillon on July 21, 2007. The as-built detail shows the geo-web and the GCL in one layer, with no granular or other material between the two. Dillon initiated this modification to address a previous concern raised by BGC that water could seep under the GCL in the emergency spillway and potentially lift the liner. It is still not clear how the above modification prevents this problem from occurring.

10. Design change rationale is requested that provides an explanation as to the change from the original drawing, change to meet BGC's concern and then further change to what appears to be potentially inadequate construction.

## **SCHEDULE 2            CONDITIONS APPLYING TO MONITORING AND                                  MAINTENANCE**

A revised *Operation and Maintenance Manual, Sewage Treatment System, Hamlet of Cape Dorset, November 7, 2007* shall include the following requirements:

- i. Expansion of Section 3.4.5 to include terms and conditions for the disposal of sludge as provided for in the Draft Guidelines for Discharge of Domestic Wastewater in Nunavut, 2000;
- ii. Section 3.4.6 should include a description of the installation of thermistors required under Part H, Item 6, including the number, locations and depths of thermistor beads used to monitor the berms, and a description of the method and frequency of monitoring requirements;
- iii. Section 3.4.6 should include a description of the installation of monitoring wells required under Part H, Item 7, including the number, locations and depths of thermistor beads used to monitor the berms, and a description of the method and frequency of monitoring requirements;
- iv. Description of the details of any repairs, upgrades and maintenance required for the use of part or all of the 2001 Sewage Disposal Facility or Emergency Sewage Disposal Facility;
- v. Include a contingency plan for the operation of the 2007 Sewage Disposal Facility during periods where accessibility to the facility is limited and alternative measures are required for the handling of sewage. This may include operation and maintenance of any older facility or portion of, that would be retained as the contingency;
- vi. Provision for the monitoring of effluent discharges from the 2001 Sewage Disposal Facility and the Emergency Sewage Disposal Facility;
- vii. Inspection program for the 2001 Sewage Disposal Facility, the Emergency Sewage Disposal Facility and 2007 Sewage Disposal Facility, detailing the frequency and inspection requirements by the operator(s) of the facility;
- viii. Appendix C of the O&M Manual to include forms to document the recommendations and follow up work required as a result of the annual geotechnical inspection.
- ix. Section 4 – Spill Contingency Plan be revised to comprehensively address specific recommendations provided during the review process by GN DoE as follows:
  - a. The date the contingency plan was prepared.
  - b. The name and address of the person in charge, management or control. This is an on-site person responsible for managing the facility. This person would be initially responsible for clean-up activities.
  - c. The name and address of the owner if different from the person in charge. This is the person ultimately responsible for the facility, usually the owner.
  - d. The name, job title and 24 hour telephone number for the persons responsible for activating the contingency plan. This ensures the employee discovering the spill can activate a response and provides a 24 hour point of contact for the authority

- investigating the spill.
- e. A description of the facility including the location, size and storage capacity. This is important if persons are unfamiliar with the facility or area. The description could include a map and/or diagrams.
- f. A site map that is intended to illustrate the facilities relationship to other areas that may be affected by the spill. The map should be to scale and be large enough to include the location of your facility, nearby buildings or facilities, roads, culverts, drainage patterns, and any nearby bodies of water.
- g. The steps to be taken to report, contain, and clean up and dispose of a contaminant in the case of a spill.
  - 1. Reporting: Notification of all parties involved. This can include internal and external reporting procedures as well as a copy of the spill report;
  - 2. Clean up: Removal of the contaminant from the environment, a detailed of actual containment and clean up techniques. (2 steps: contain and remediate; be aware of fire);
  - 3. Disposal: Is the treatment of the contaminant such that it is no longer a threat to the environment. Plans may include location of disposal sites approved to accept wastes, means of storage prior to disposal and other approvals required. (Waste Manifest document).
- h. The means by which the contingency plan is activated. This should outline internal company procedures to activate appropriate response equipment and personnel.
- i. A description of the training provided to employees to respond to a spill. A sound training program is necessary when dealing with an emergency situation.
- j. An inventory and the location of response and clean up equipment available to implement the plan. This includes your equipment as well as any to be used by another person responding to the spill on your behalf.
- k. SPILL KIT (FUEL)The kit can include but not limited to the following: shovel, pick-axe, drums, booms, absorbent pad/sheet, disposable protective gloves/coveralls, sorbent and containment materials, and disposal bags.
- l. A list of local contractors or clean up specialists who may be called upon to assist in responding to spills. A list of emergency numbers such as fire, ambulance and police.
- x. Section 4 – describe the measures to be implemented for a spill during the collection and transportation of wastewater. This spill response is to be expanded to include spill scenarios resulting from the leakage or failure of a containment structure for the Sewage Disposal Facilities; and
- xi. Appendix B to include specific reference to monitoring stations and required frequency of sampling and the analyses required by the Licence.



P.O. Box 119  
GJOA HAVEN, NU X0B 1J0  
TEL: (867) 360-6338  
FAX: (867) 360-6369

ᓄᓇᓂᓪ ᐃᓕᓕᓂᓪ ᑲᑎᓕᓂᓪ  
NUNAVUT IMALIRIYIN KATIMAYINGI  
NUNAVUT WATER BOARD  
OFFICE DES EAUX DU NUNAVUT

---

File No: 3BM-CAP0810

March 7, 2008

Honorable Chuck Strahl, P.C., M.P.  
Minister of Indian Affairs & Northern Development  
and Federal Interlocutor for Metis and Non-Status Indians  
21<sup>st</sup> Floor, 10 Wellington  
Gatineau, Quebec K1A 0H4

*By Courier, Email and Regular Mail*

**Subject:       Licence 3BM-CAP0810 – Cape Dorset, Nunavut**

Dear Minister:

Please find enclosed an amended Licence 3BM-CAP0810 duly issued by the Nunavut Water Board (NWB).

The amendment to this Licence authorizes the Hamlet of Cape Dorset, to dispose of waste in relation the disposal, treatment and discharge of sewage effluent for municipal operations at Cape Dorset. This Type B Licence is being sent to you for your approval in accordance with Section 56(1) of the *Nunavut Waters and Nunavut Surface Rights Tribunal Act* (Act) as the Board determined pursuant to subsection 51(2) of the Act that it is in the public interest to hold a public hearing on the amendment application.

As set out in the Board's Reasons for Decision, attached for your information, this decision was particularly difficult for the Board. The Board has concluded that the current sewage lagoon system has failed. At the same time, construction of the new sewage lagoon was completed prior to the Public Hearing. The new sewage lagoon appears to have been built without environmental assessment, and certainly without this Board's regulatory review and approval.

Without the benefit of environmental assessment or regulatory direction, the evidence supports that the new sewage lagoon, has been built in a location with unfavourable geological characteristics; the integrity of the design is seriously questioned by technical reviewers; and the facility has not been constructed in accordance with construction drawings, omitting design elements essential to mitigating the design risks (i.e. thermistors installations). Furthermore, the new lagoon is accessible only by

a road that the Board believes is likely to prove unusable during winter months, forcing continued reliance on the existing lagoon.

While the new lagoon system poses serious risks, the Board is satisfied that with appropriate conditions these risks can be mitigated. Moreover, this is likely the only mechanism for the Hamlet to come into compliance with the Act and the terms of the Licence. Accordingly, the Board has decided that the optimum benefit for the residents of Nunavut is derived from a decision to issue the amendment to the Licence.

The Board's decision relies heavily on the need for mitigating risks posed by the new lagoon system and has set out corresponding conditions in the amended Licence, including specified responsibilities of the Her Majesty in right of Canada pursuant to 70(2) of the Act. The Board believes these conditions are essential to achieving optimum benefit for the residents of Nunavut and asks that the Minister approve this Licence only if INAC inspectors are committed to comply with the responsibilities specified in the Licence and pursuant to the Act.

Through the conditions set out in the Licence, the Board will carefully monitor the Hamlet's efforts to come into compliance with the Licence. If at any point the Board determines that future failure to comply with key conditions set out in the Licence such that the balance of the benefit to the residents of Nunavut changes, the Board is prepared to exercise its authority pursuant to clause 43(1)(c)(iii) of the Act to recommend cancellation of the licence if the Board determines it is in the public interest to do so.

If your office wishes to receive a full Records of Proceedings please contact our head office. The Licence is in your hands to be considered in accordance with section 56 of the *Nunavut Waters and Nunavut Surface Rights Tribunal Act*.

Please contact the undersigned in writing should you have any questions regarding this matter.

Sincerely,



Thomas Kabloona  
A/Chair

Attachment: Licence No: 3BM-CAP0810 and Decision

c.c. Cape Dorset Distribution List  
NWB Public Registry



**WATER LICENCE NO: 3BM-CAP0810**



# TABLE OF CONTENTS

<b>LICENCE 3BM-CAP0810 .....</b>	<b>1</b>
<b>PART A: SCOPE AND DEFINITIONS .....</b>	<b>1</b>
<b>PART B: GENERAL CONDITIONS .....</b>	<b>4</b>
<b>PART C: CONDITIONS APPLYING TO WATER USE .....</b>	<b>7</b>
<b>PART D: CONDITIONS APPLYING TO WASTE DISPOSAL.....</b>	<b>7</b>
<b>PART E: CONDITIONS APPLYING TO MODIFICATION AND CONSTRUCTION.....</b>	<b>9</b>
<b>PART F: CONDITIONS APPLYING TO OPERATION AND MAINTENANCE</b>	<b>10</b>
<b>PART G: CONDITIONS APPLYING TO ABANDONMENT AND RESTORATION.....</b>	<b>12</b>
<b>PART H: CONDITIONS APPLYING TO THE MONITORING PROGRAM.....</b>	<b>13</b>
<b>SCHEDULE 1.....</b>	<b>19</b>
<b>SCHEDULE 2.....</b>	<b>21</b>

**LICENCE 3BM-CAP0810**

Pursuant to the *Nunavut Waters and Nunavut Surface Rights Tribunal Act* and the *Agreement Between the Inuit of the Nunavut Settlement Area and Her Majesty the Queen in Right of Canada*, the Nunavut Water Board, hereinafter referred to as the Board, hereby grants to

**HAMLET OF CAPE DORSET**

\_\_\_\_\_  
(Licensee)

of

**P.O. BOX 30, CAPE DORSET, NUNAVUT X0A 0C0**  
\_\_\_\_\_  
(Mailing Address)

hereinafter called the Licensee, the right to alter, divert or otherwise use water for a period subject to restrictions and conditions contained within this licence:

Licence Number **3BM-CAP0810**  
\_\_\_\_\_

Water Management Area **NUNAVUT 05**  
\_\_\_\_\_

Location **CAPE DORSET, NUNAVUT**  
**Latitude 64°14'N and Longitude 76°32'W**  
\_\_\_\_\_

Purpose **WATER USE AND WASTE DISPOSAL**  
\_\_\_\_\_

Description **MUNICIPAL UNDERTAKINGS**  
\_\_\_\_\_

Quantity of Water Not to Exceed **70,000 CUBIC METRES ANNUALLY**  
\_\_\_\_\_

Date of Licence **MARCH 7, 2008**  
\_\_\_\_\_

Expiry Date of Licence **MARCH 1, 2010**  
\_\_\_\_\_



\_\_\_\_\_  
**Thomas Kabloona,**  
**Nunavut Water Board**  
**A/Chair**

**APPROVED**  
**BY:**

\_\_\_\_\_  
**Minister of Indian and**  
**Northern Affairs**  
**Canada**

**DATE LICENCE APPROVED:** \_\_\_\_\_

## **PART A: SCOPE, DEFINITIONS AND ENFORCEMENT**

### **1. Scope**

- a. This Licence allows for the use of water and the disposal of waste for municipal undertakings at the Hamlet of Cape Dorset, Nunavut (Latitude 64°14'N and Longitude 76°32'W);
- b. This Licence is issued subject to the conditions contained herein with respect to the taking of water and the depositing of waste of any type in any waters or in any place under any conditions where such waste or any other waste that results from the deposits of such waste may enter any waters. Whenever new Regulations are made or existing Regulations are amended by the Governor in Council under the *Nunavut Waters and Nunavut Surface Rights Tribunal Act*, or other statutes imposing more stringent conditions relating to the quantity or type of waste that may be so deposited or under which any such waste may be so deposited, this Licence shall be deemed, upon promulgation of such Regulations, to be subject to such requirements; and
- c. Compliance with the terms and conditions of this Licence does not absolve the Licensee from responsibility for compliance with the requirements of all applicable Federal, Territorial and Municipal legislation.

### **2. Definitions**

“**Act**” means the *Nunavut Waters and Nunavut Surface Rights Tribunal Act*;

“**Amendment**” means a change to original terms and conditions of this licence requiring correction, addition or deletion of specific terms and conditions of the licence; modifications inconsistent with the terms of the set terms and conditions of the Licence;

“**Analyst**” means an Analyst designated by the Minister under Section 85 (1) of the *Act*;

“**Appurtenant undertaking**” means an undertaking in relation to which a use of waters or a deposit of waste is permitted by a licence issued by the Board;

“**Average Concentration**” means the arithmetic mean of the last four consecutive analytical results for contained in composite or grab samples collected from the Waste Disposal Facility’s final discharge point;

**“Average Concentration For Faecal Coliforms”** means the geometric mean of the last four consecutive analytical results for faecal coliforms contained in composite or grab samples collected from the Waste Disposal Facility’s final discharge point;

**“Board”** means the Nunavut Water Board established under the *Nunavut Land Claims Agreement*;

**“Chief Administrative Officer”** means the Executive Director of the Nunavut Water Board;

**“Composite Sample”** means a water or wastewater sample made up of four (4) samples taken at regular periods over a 24 hour period;

**“Effluent”** means treated or untreated liquid waste material that is discharged into the environment from a structure such as a settling pond or a treatment plant;

**“Engineer”** means a professional engineer registered to practice in Nunavut in accordance with the *Engineering, Geological and Geophysical Act (Nunavut)* S.N.W.T. 1998, c.38, s.5;

**“Final Discharge Point”** means the discharge location point where the effluent from the 2007 Sewage Disposal Facilities enters fish habitat or fish bearing waters;

**“Final Point of Control”** means the discharge location at the 2007 Sewage Disposal Facilities August 27, 2007 submission prepared by Dillon Consulting including ten appendices, to be confirmed by an Inspector;

**“Freeboard”** means the vertical distance between water line and crest on a dam or dyke’s upstream slope;

**“Geotechnical Engineer”** means a professional engineer registered with the Association of Professional Engineers, Geologist and Geophysicists of Nunavut and whose principal field of specialization with the engineering properties of earth materials in dealing with man-made structures and earthworks that will be built on a site. These can include shallow and deep foundations, retaining walls, dams, and embankments;

**“Grab Sample”** means a single water or wastewater sample taken at a time and place representative of the total discharge;

**“Greywater”** means all liquid wastes from showers, baths, sinks, kitchens and domestic washing facilities, but does not include toilet wastes;

**“Inspector”** means an Inspector designated by the Minister under Section 85 (1) of the

Act;

**“Licensee”** means the holder of this Licence;

**“Modification”** means an alteration to a physical work that introduces new structure or eliminates an existing structure and does not alter the purpose or function of the work, but does not include an expansion, and changes to the operating system that are consistent with the terms of this Licence and do not require amendment;

**“Monitoring Program”** means a monitoring program established to collect data on surface water and groundwater quality to assess impacts to the freshwater aquatic environment of an appurtenant undertaking;

**“Nunavut Land Claims Agreement”** (NLCA) means the *“Agreement Between the Inuit of the Nunavut Settlement Area and Her Majesty the Queen in right of Canada”*, including its preamble and schedules, and any amendments to that agreement made pursuant to it;

**“Sewage”** means all toilet wastes and greywater;

**“Sewage Disposal Facilities”** includes the facilities licensed in 2001, 2004 and 2007;

**“Emergency Sewage Disposal Facility”** comprises the area designed to contain and treat sewage as described in the Water License Amendment Application filed by the Applicant on August 16, 2004, and illustrated on the “Cape Dorset Sewage Lagoon Rehabilitation Site Plan (August 2004)”

**“2001 Sewage Disposal Facilities”** comprises the Three Tier Lagoon which comprises the area and engineered lagoon and decant structures designed to contain sewage as described in the Application for Water Licence filed by the Applicant on April 19, 2001;

**“2007 Sewage Disposal Facilities”** comprises the engineered lagoon and decant structures constructed in 2007 and illustrated in the Record Drawings No.’s 100 and 101 of Project N-05-4319-3000 prepared by Dillon Consulting and submitted November 13, 2007;

**“Solid Waste Disposal Facilities”** comprises the area and associated structures designed to contain solid waste (landfill site) as described in the Application for Water Licence filed by the Applicant on April 19, 2001;

**“Toilet Wastes”** means all human excreta and associated products, but does not include greywater;

**“Waste”** means, as defined in S.4 of the *Act*, any substance that, by itself or in combination with other substances found in water, would have the effect of altering the quality of any water to which the substance is added to an extent that is detrimental to its use by people or by any animal, fish or plant, or any water that would have that effect because of the quantity or concentration of the substances contained in it or because it has been treated or changed, by heat or other means;

**“Waste Disposal Facilities”** means all facilities designated for the disposal of waste, and includes the 2001, 2004 and 2007 Sewage Disposal Facilities, Solid Waste Disposal Facilities, and Bagged Toilet Waste Disposal Facilities, as described in the Application for Water Licence filed by the Applicant on April 19, 2001 and subsequently in the application dated July 7, 2005;

**“Water Supply Facilities”** comprises the area and associated intake infrastructure at Tee Lake, as described in the Application for Water Licence filed by the Applicant on April 19, 2001;

### **3. Enforcement**

- i. Failure to comply with this Licence will be a violation of the *Act*, subjecting the Licensee to the enforcement measures and the penalties provided for in the *Act*;
- ii. All inspection and enforcement services regarding this Licence will be provided by Inspectors appointed under the *Act*; and
- iii. For the purpose of enforcing this Licence and with respect to the use of water and deposit or discharge of waste by the Licensee, Inspectors appointed under the *Act*, hold all powers, privileges and protections that are conferred upon them by the *Act* or by other applicable law.
- iv. The Licensee shall, in relation to any application to renew or amend the Licence, have in place a Plan for Compliance approved by the Board in writing, to achieve full compliance with the conditions of this Licence, or a Plan for Compliance must be submitted at the time of Application, in order for the Application to be deemed complete.

## **PART B: GENERAL CONDITIONS**

1. The Licensee shall file an Annual Report with the Board not later than March 31st of the year following the calendar year reported which shall contain the following information:

- i. tabular summaries of all data generated under the Monitoring Program;
  - ii. the monthly and annual quantities in cubic metres of fresh water obtained from all sources;
  - iii. the monthly and annual quantities in cubic metres of each and all waste discharged;
  - iv. a summary of modifications and/or major maintenance work carried out on the Water Supply and Waste Disposal Facilities, including all associated structures and facilities;
  - v. a list of unauthorized discharges and summary of follow-up action taken;
  - vi. a summary of any abandonment and restoration work completed during the year and an outline of any work anticipated for the following year;
  - vii. a summary of any studies, reports and plans (i.e. Operations and Maintenance, Abandonment and Restoration, QA/QC) requested by the Board that relate to water use and waste disposal or reclamation, and a brief description of any future studies planned; and
  - viii. any other details on water use or waste disposal requested by the Board by November 1st of the year being reported.
2. The Licensee shall comply with the Monitoring Program described in this Licence, and any amendments to the Monitoring Program as may be made from time to time, pursuant to the conditions of this Licence.
3. The Monitoring Program and compliance dates specified in the Licence may be modified at the discretion of the Board.
4. Meters, devices or other such methods used for measuring the volumes of water used and waste discharged shall be installed, operated and maintained by the Licensee.
5. The Licensee shall, within ninety (90) days after the first visit by the Inspector following issuance of this Licence, post the necessary signs, to identify the stations of the Monitoring Program. All signage postings shall be in the Official Languages of Nunavut.
6. The Licensee shall submit to the Board, for approval in writing, within the lesser of ninety (90) days or the filing of any application in relation to the Licence, a Plan for Compliance that clearly demonstrates the ways and means the Licensee will undertake to achieve full compliance with the conditions of this Licence.
7. The Licensee shall, for all Plans submitted under this Licence, include a proposed timetable for implementation. Plans submitted, cannot be undertaken without subsequent written Board approval and direction. The Board may alter or modify a Plan if necessary to achieve the legislative objectives and will notify the Licensee in writing of acceptance, rejection or alteration of the Plan.

8. Every Plan to be carried out pursuant to the terms and conditions of this Licence shall become a part of this Licence, and any additional terms and condition imposed upon approval of a Plan by the Board become part of this Licence. All terms and conditions of the Licence should be contemplated in the development of a Plan where appropriate.
9. The Licensee shall immediately report to the 24-Hour Spill Report Line (867-920-8130) any spills of Waste, which are reported to, or observed by the Licensee, within the municipal boundaries or in the areas of the Water Supply or Waste Disposal Facilities.
10. The Licensee shall ensure a copy of this Licence is maintained at the municipal office at all times. Any communication with respect to this Licence shall be made in writing to the attention of:

**Manager of Licensing:**

Nunavut Water Board  
P.O. Box 119  
Gjoa Haven, NU X0B 1J0  
Telephone: (867) 360-6338  
Fax: (867) 360-6369  
Email: [licensing@nunavutwaterboard.org](mailto:licensing@nunavutwaterboard.org)

**Inspector Contact:**

Water Resources Officer  
Nunavut District, Nunavut Region  
P.O. Box 100  
Iqaluit, NU X0A 0H0  
Telephone: (867) 975-4295  
Fax: (867) 979-6445

**Analyst Contact:**

Taiga Laboratories  
Department of Indian and Northern Affairs  
4601 – 52 Avenue, P.O. Box 1500  
Yellowknife, NT X1A 2R3  
Telephone: (867) 669-2781  
Fax: (867) 669-2718

11. The Licensee shall submit one paper copy and one electronic copy of all reports, studies, and plans to the Board. Reports or studies submitted to the Board by the Licensee shall include a detailed executive summary in Inuktitut.
12. The Licensee shall ensure that any document(s) or correspondence submitted by the



Licensee to the Board, is received by the Board and maintain on file a copy of the acknowledgment of receipt issued by the Manager of Licensing.

13. This Licence is not assignable except as provided in Section 44 of the Act.

#### **PART C: CONDITIONS APPLYING TO WATER USE**

1. The Licensee shall obtain all fresh water from the Tee Lake using the Water Supply Facilities or as otherwise approved by the Board in writing.
2. The annual quantity of water used for all purposes shall not exceed 70,000 cubic metres.
3. The Licensee shall equip all water intake hoses with a screen of an appropriate mesh size to ensure that fish are not entrained and shall withdraw water at a rate such that fish do not become impinged on the screen.
4. The Licensee shall not remove any material from below the ordinary high water mark of any water body unless otherwise approved by the Board in writing.
5. The Licensee shall not cause erosion to the banks of any body of water and shall provide necessary controls to prevent such erosion.
6. Sediment and erosion control measures shall be implemented prior to and maintained during the operation to prevent entry of sediment into water.

#### **PART D: CONDITIONS APPLYING TO WASTE DISPOSAL**

1. Licensee shall locate areas designated for waste disposal at a minimum distance of thirty (30) metres from the ordinary high water mark of any water body such that the quality, quantity or flow of water is not impaired, unless otherwise approved by the Board in writing.
2. Subject to the conditions in the Licence regarding commissioning, the Licensee shall direct all Sewage to the 2007 Sewage Disposal Facilities or as otherwise approved by the Board in writing.
3. The Licensee shall provide notice to an Inspector at least ten (10) days prior to initiating any decant of the 2001 and 2007 Sewage Disposal Facilities.
4. All Effluent discharge from the 2001 Sewage Disposal Facility at Monitoring Program Station CAP-3 and the Emergency Sewage Disposal Facility at Monitoring Program

Station CAP-4, shall meet the following effluent quality limits:

<b>Parameter</b>	<b>Maximum Average Concentration</b>
BOD <sub>5</sub>	120 mg/L
Total Suspended Solids	180 mg/L
Faecal Coliforms	1 x 10 <sup>4</sup> CFU/100mL
Oil and grease	No visible sheen
pH	between 6 and 9

5. All Effluent discharged from the 2007 Sewage Disposal Facilities at Monitoring Program Station CAP-5 shall meet the following effluent quality limits:

<b>Parameter</b>	<b>Maximum Average Concentration</b>
BOD <sub>5</sub>	80 mg/L
Total Suspended Solids	100 mg/L
Faecal Coliforms	1 x 10 <sup>4</sup> CFU/100mL
Oil and grease	No visible sheen
pH	between 6 and 9

6. The Licensee shall maintain at all times, a freeboard of at least 1.0 metre, or as recommended by a qualified Geotechnical Engineer with notice in writing provided to the Board, for all dams, dykes or other structures intended to contain, withhold, divert or retain water or wastes.
7. The Sewage Disposal Facilities shall be maintained and operated in such a manner as to prevent structural failure.
8. All Effluent discharged from the 2007 Sewage Disposal Facility at the Final Discharge Point at Monitoring Station CAP-14 and effluent discharge from Monitoring Stations CAP-3 and CAP-4 prior to the point of entry at the ocean, shall be demonstrated to be non-acutely toxic under the following tests to be conducted once annually, approximately mid-way through the discharge period:
- Acute lethality to Rainbow Trout, *Oncorhynchus mykiss* (as per Environment Canada's Environmental Protection Series Biological Test Method EPS/1/RM/13); or

- ii. Acute lethality to the crustacean, *Daphnia magna* (as per Environment Canada's Environmental Protection Series Biological Test Method EPS/1/RM/14).
- 9. The Licensee shall dispose of and contain all solid wastes at the Solid Waste Disposal Facilities or as otherwise approved by the Board in writing.
- 10. The Licensee shall implement appropriate erosion and diversion control methods, to minimize surface water intrusion and leachate generation at the Solid Waste Storage Facility.
- 11. The Licensee shall segregate and securely store all hazardous materials and/or hazardous waste within the Solid Waste Disposal Facility in a manner as to prevent the deposit of deleterious substances into any water.

#### **PART E: CONDITIONS APPLYING TO MODIFICATION AND CONSTRUCTION**

- 1. The Licensee shall submit to the Board, for approval in writing, design drawings stamped by a qualified engineer registered in Nunavut prior to the construction of any dams, dykes or structures intended to contain, withhold, divert or retain water or wastes.
- 2. The Licensee may, without written approval from the Board, carry out modifications to the Water Supply and Waste Disposal Facilities provided that such modifications are consistent with the terms of this Licence and the following requirements are met:
  - i. the Licensee has notified the Board in writing of such proposed modifications at least sixty (60) days prior to beginning the modifications;
  - ii. these modifications do not place the Licensee in contravention of the Licence or the Act;
  - iii. the Board has not, during the sixty (60) days following notification of the proposed modifications, informed the Licensee that review of the proposal will require more than sixty (60) days; and
  - iv. the Board has not rejected the proposed modifications.
- 3. Modifications for which all of the conditions referred to in Part E, Item 2, have not been met may be carried out only with written approval from the Board.
- 4. The Licensee shall provide as-built plans and drawings of the Modifications referred to in this Part within ninety (90) days of completion of the Modification. These plans and

drawings shall be stamped by an Engineer.

5. The Licensee shall, within sixty (60) days of issuance of this Licence, provide a summary report along with revised stamped as-built plans and record drawings of the 2007 Sewage Disposal Facility, to reflect the clarifications and omissions identified through the Licence application review and detailed in the attached Schedule 1.
6. All activities shall be conducted in such a way as to minimize impacts on surface drainage and the Licensee shall immediately undertake corrective measures to restore natural surface drainage in the event of any impacts on surface drainage
7. The Licensee shall ensure that sediment and erosion control measures are implemented prior to and maintained during the operation to prevent the release of sediment and minimize erosion during construction activities.
8. The Licensee shall designate an area for the deposition of excavated and stockpiled materials that is at least thirty (30) metres above the ordinary high water mark of any water body and in such a manner as to prevent sediment from entering any surrounding water body.
9. The Licensee shall ensure that both (a) fill material used in construction, and (b) that the ground to be constructed upon, are free of contaminants. If contaminated soils are identified, notification shall be made in the Licensee's annual report. All contaminated soils shall be treated and disposed of in accordance with Part F, Item 2, or as otherwise approved by the Board in writing.

#### **PART F: CONDITIONS APPLYING TO OPERATION AND MAINTENANCE**

1. The Licensee shall submit to the Board, for approval in writing, within ninety (90) days of issuance of the Licence and prior to commissioning of the 2007 Sewage Disposal Facilities, a revised *Operation and Maintenance Manual, Sewage Treatment System, Hamlet of Cape Dorset, November 7, 2007*. The revision shall include the requirements of Schedule 2.
2. The Licensee shall submit to the Board, for approval in writing, within ninety (90) days of issuance of the Licence, an Operation and Maintenance Manual for the Water Supply Facilities and the Solid Waste Disposal Facilities prepared in accordance with the "*Guidelines for Preparing an Operation and Maintenance Manual for Sewage and Solid Waste Disposal Facilities*", October 1996. The Plan shall include a specific section addressing waste management and the proper diversion and segregation of wastes, the storage, transport and disposal of hazardous wastes materials.

3. The Licensee shall implement the Manuals specified in Part F, Items 1 and 2, following approval in writing by the Board.
4. The Licensee shall provide notification in writing to the Board, in accordance with Part E, Item 2, of changes to the approved Operation and Maintenance Plan under Part F, Item 1, with respect to the wastewater storage and decanting operations and procedures. For any potential significant impact of such change to the geothermal regime within and under the berms or lagoon floor, notice shall be accompanied by the Geotechnical Engineer's supporting documentation and further geotechnical analysis.
5. An inspection of all engineered facilities related to the management of water and waste shall be carried out annually in July, by a Geotechnical Engineer in accordance with the Canadian Dam Association, Dam Safety Guidelines, November 2007, where applicable. This inspection shall include the access road alignment with respect to water resources and the diversion and passage of water through culverts. The engineer's report shall be submitted to the Board within sixty (60) days of the inspection, including a covering letter from the Licensee outlining an implementation plan addressing each of the Engineer's recommendations.
6. The Licensee shall perform a visual operations inspection of all engineered facilities related to the management of water and waste on a weekly basis or more frequently as requested by an Inspector, to assess the general operating conditions and integrity of the containment structures. The records of these inspections are to be maintained and made available to an Inspector upon request during the Licence term.
7. The Licensee shall review the Manual(s) referred to in this Part if there are changes in operation and/or technology and modify the Manual(s) accordingly. Revisions to the Board approved Manual(s) are to be submitted in the form of an Addendum to be included with the Annual Report under Part B, Item 1.
8. If, during the period of this Licence, an unauthorized discharge of waste occurs, or if such a discharge is foreseeable, the Licensee shall:
  - i. employ the appropriate contingency plan as provided for in the Operation and Maintenance Manual;
  - ii. report the incident immediately via the 24-Hour Spill Reporting Line at (867) 920-8130 and to the Inspector at (867) 975-4295; and
  - iii. submit to the Inspector, a detailed report on each occurrence, no later than thirty (30) days after initially reporting the event, that provides the necessary information on the location (including the GPS coordinates), initial response action, remediation/clean-up, status of response (ongoing, complete), proposed disposal options for dealing with contaminated materials and preventative measures to be implemented.

**PART G: CONDITIONS APPLYING TO ABANDONMENT, RESTORATION AND CLOSURE**

1. The Licensee shall submit to the Board, for approval in writing, within ninety (90) days of issuance of the Licence, a detailed Final Abandonment and Restoration Plan for the 2001 Sewage Disposal Facility and the Emergency Sewage Disposal Facility. The Plan should incorporate, where applicable, the appropriate sections as described in Part G, Item 2.
2. The Licensee shall submit to the Board, for approval in writing, within six (6) months of issuance of this Licence, a preliminary or conceptual Abandonment and Restoration Plan for the Hamlet of Cape Dorset, Water and Waste Disposal Facilities and all associated structures not covered under Part G, Item 1, with end objectives to return the site to pre-use conditions. The Plan shall include the following (where applicable):
  - i. water intake facilities;
  - ii. the water treatment and waste disposal sites and facilities;
  - iii. petroleum and chemical storage areas;
  - iv. any site affected by waste spills;
  - v. leachate prevention;
  - vi. an implementation and completion schedule;
  - vii. maps delineating all disturbed areas, and site facilities;
  - viii. consideration of altered drainage patterns;
  - ix. type and source of cover materials;
  - x. future area use;
  - xi. hazardous wastes; and
  - xii. a proposal identifying measures by which restoration costs will be financed by the Licensee upon abandonment.
3. The Licensee shall submit to the Board, for approval in writing, six (6) months prior to the planned decommissioning of any licensed facility and the construction of new facilities to replace existing ones, a Final Abandonment and Restoration Plan for the facilities being decommissioned.
4. The Licensee shall implement the Plan(s) specified in Part G, Item 1 and 3, following approval in writing by the Board.
5. The Licensee shall review the Plan(s) referred to in this Part if there are changes in operation and/or technology and modify the Plan accordingly. Revisions to the Board approved Plan(s) are to be submitted in the form of an Addendum to be included with the Annual Report under Part B, Item 1.

6. The Licensee shall carry out progressive reclamation of any components of the project no longer required for the Licensee's operations.
7. The Licensee shall complete the restoration work within the time schedule specified in the Plan, or as subsequently revised and approved by the Board.
8. The Licensee shall complete all restoration work prior to the expiry of this Licence.

#### **PART H: CONDITIONS APPLYING TO THE MONITORING PROGRAM**

1. The Licensee shall maintain Monitoring Program Stations at the following locations:

<b>Monitoring Program Station Number</b>	<b>Description</b>	<b>Status</b>
CAP-1	Raw Water supply prior to treatment	Active (Volume)
CAP-2	Runoff from the Solid Waste Disposal Facilities	Active
CAP-3	Influent of Wastewater to Wastewater Facilities (active at the time of sampling)	New
CAP-4	Effluent Discharge from the 2001 Sewage Disposal Facilities	Active (including volume)
CAP-5	Effluent discharge from the Emergency Sewage Disposal Facilities	Active (including volume)
CAP-6	Effluent discharge from the 2007 Sewage Disposal Facilities – Final Point of Control	Active (including volume)
CAP-7	Point of influent of wastewater to P-Lake	New
CAP-8	Centre of P-Lake	New
CAP-9	Location midway between the Centre of P-Lake (Station 8) and the effluent discharge of P-Lake	New

<b>Monitoring Program Station Number</b>	<b>Description</b>	<b>Status</b>
CAP-10	Effluent discharge from P-Lake; note, if flow is negligible a sample from the immediate upstream area within P-Lake shall be obtained	New
CAP-11	Effluent discharge from Wetland area	New
CAP-12	Wetland Pathway at the top of the waterfall	New
CAP-13	Wetland Pathway at mid-way down waterfall	New
CAP-14	Wetland Pathway at bottom of cliff – Final Discharge Point	
CAP-15	Control point using a small lake located between the Lagoon and Tee Lake	New
CAP-16	Monitoring well located up gradient of the 2007 Sewage Disposal Facility	New
CAP-17	Monitoring Well No.1 located down gradient of the 2007 Sewage Disposal Facility	New
CAP-18	Monitoring Well No.2 located down gradient of the 2007 Sewage Disposal Facility	New
CAP-19	Monitoring well located up gradient of the Solid Waste Disposal Facilities	New
CAP-20	Monitoring well located down gradient of the Solid Waste Disposal Facilities	New
CAP-21	Thermistor stations	Proposed with final description to be provided
CAP-22	As above	
CAP-23	As above	
CAP-24	As above	

2. The Licensee shall sample at Monitoring Program Stations CAP-3 through CAP-15 inclusive, one week prior to the proposed discharge date, once at the beginning of discharge and weekly thereafter until cessation of discharge. Samples shall be analyzed for the following parameters:

Biochemical Oxygen Demand (BOD<sub>5</sub>)



Carbonaceous Biochemical Oxygen Demand (CBOD<sub>5</sub>)  
 Total Suspended Solids  
 pH  
 Conductivity  
 Oil and Grease (visual)

Fecal Coliforms	
Nitrate-Nitrite	Ammonia Nitrogen
Total Phosphorus	Total Phenols
Magnesium	Calcium
Sodium	Potassium
Chloride	Sulphate
Total Hardness	Total Alkalinity

Total Trace Metals as determined by a standard ICP Scan (to include at a minimum, the following elements: Al, Sb, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Li, Mn, Mo, Ni, Se, Sn, Sr, Tl, Ti, U, V, Zn),

Total Arsenic  
 Total Mercury  
 Total Organic Carbon (TOC)

3. If the discharge at Station CAP-4, CAP-5 or CAP-6 has been suspended for more than 48 hours and subsequently restarted, the sampling sequence described in Part H, Item 2 of the Monitoring Program shall be repeated for these Stations.
4. The Licensee shall sample monthly at Monitoring Program Station CAP-2 during periods of observed flow. Samples shall be analyzed for the following parameters:

BOD <sub>5</sub>	Fecal Coliforms
pH	Conductivity
Total	Suspended Solids
Nitrate-Nitrite	Ammonia Nitrogen
Total Phenols	Oil and Grease
Total Hardness	Total Alkalinity
Magnesium	Calcium
Sodium	Potassium
Total Arsenic	Sulphate
Total Copper	Total Cadmium
Total Iron	Total Chromium
Total Mercury	Total Lead
	Total Nickel

5. The Licensee shall report all results of non-acute toxicity testing as required under Part D, Item 8 within the Annual Report as per Part B, Item 1.
6. The Licensee shall install thermistors for the purpose of validating assumptions made in the geothermal analyses for the 2007 Sewage Disposal Facilities as recommended by the Geotechnical Engineer of record and agreed upon by the Licensee, subject to a minimum of three 20 to 25 metre deep thermistors installed in crest of the west berm and at least one thermistor of that depth in the east berm.
7. The results of thermistor monitoring required under Part H, Item 6, shall be submitted to the Board for approval in writing, prior to commissioning of the 2007 Sewage Disposal Facility. The results shall include an Engineer's Report, validating the assumptions of the geothermal analysis through adequate monitoring of the thermal regime for the East and West Berms and downstream foundations
8. The Licensee shall not commission the 2007 Sewage Disposal Facility until the requirements of Part H, Item 6 and Item 7 have been completed and approved.
9. The Licensee shall, within ninety (90) days of issuance of this Licence, provide a Temperature Monitoring Program and Implementation Plan for ongoing collection of ground temperatures within each berm structure and foundation of the 2007 Sewage Disposal Facility through the installation of thermistors. This Plan shall take into consideration the following:
  - i. Locations of thermistors, to be incorporated into the Monitoring Station Table under Part H, Item 1;
  - ii. Appropriate thermistor configuration, overall depth and spacing of bead locations to provide the level of data collection that will capture any extreme variations in temperature and provide the information needed to validate the assumptions made in the geothermal analysis.
  - iii. The frequency of temperature readings shall be such to allow the determination of the maximum freeze and thaw of the berm and underlying native materials and provide adequate data for thermal modeling of the berms.
  - iv. This frequency may be reviewed and adjusted upon collection of adequate data and as recommended by the Geotechnical Engineer in order to assess the berms through thermal modeling and provide an assessment with respect to berm stability and potential seepage.
  - v. This information is to be reported along with the results of the annual geotechnical inspection as required under Part F, Item 6.
  - vi. An implementation schedule that will allow collection of data for confirmation of core-trench freeze-back.

10. The Licensee shall implement the Plan specified in Part H, Item 9 following approval by the Board in writing.
11. The Licensee shall review the Plan(s) referred to in this Part if there are changes in operation and/or technology and modify the Plan accordingly. Revisions to the Board approved Plan(s) are to be submitted in the form of an Addendum to be included with the Annual Report under Part B, Item 1.
12. The Licensee shall install groundwater monitoring wells at the 2007 Sewage Disposal Facility to obtain at least one monitoring season of data prior to the expiry of the Licence. At least one groundwater monitoring well shall be located upstream of the 2007 Sewage Disposal Facility for background data collection, at least one groundwater monitoring well shall be located downstream of the landfill and at least one groundwater monitoring well shall be located downstream of the metals dump.
13. The Licensee shall sample at Monitoring Program Stations CAP-16, CAP-17 and CAP-18 once annually in the summer, prior to commencing discharge from the 2007 Sewage Disposal Facility, giving due consideration to adequate ground thaw and obtaining a representative groundwater sample. Samples shall be analyzed for parameters identified in Part H, Item 4.
14. The Licensee shall install groundwater monitoring at the Solid Waste Disposal Facilities wells to obtain at least one monitoring season of data prior to the expiry of the Licence, At lease one groundwater monitoring well shall be located upstream of the Solid Waste Disposal Facilities for background data collection and at least one groundwater monitoring well shall be located downstream of the Solid Waste Disposal Facilities .
15. The Licensee shall sample at Monitoring Program Stations CAP-19 and CAP-20 once annually in the summer season, giving due consideration to adequate ground thaw and obtaining a representative groundwater sample. Samples shall be analyzed for parameters identified in Part H, Item 4.
16. The Licensee shall measure and record in cubic metres, the monthly and annual quantities of water pumped for all purposes at Monitoring Program Station CAP-1.
17. The Licensee shall measure and record in cubic metres (a) the monthly and annual quantities of raw sewage offloaded from trucks and the number of days of use for the 2001 Sewage Disposal Facility and the Emergency Sewage Disposal Facility, and (b) the monthly and annual quantities of raw sewage offloaded from trucks at the 2007 Sewage Disposal Facility.
18. The Licensee shall measure and record the annual quantities of sewage solids removed from the Sewage Disposal Facilities.

19. The Licensee shall conduct additional sampling and analysis as may be requested by an Inspector.
20. The Licensee shall revise the “Guidelines for Wastewater Sampling, October 27, 2007” and submit to the Board for approval by an Analyst in writing a Quality Assurance/Quality Control (QA/QC) Plan for the Hamlet of Cape Dorset, within ninety (90) days of issuance of this Licence. The Plan shall use as a guide the document “*Quality Assurance and Quality Control Guidelines for use by Class “B” Licensees in Collection of Representative Water Samples in the Field, and for Submission of a QA/QC Plan, July 1996*”. The Plan shall address the use of field blanks, replicate sampling and certified reference material in order to assess accuracy, precision and field contamination.
21. The Licensee shall implement the Plan referred to in Part H, Item 20 following approval in writing by the Analyst.
22. All sampling, sample preservation and analyses shall be conducted in accordance with methods prescribed in the current edition of *Standard Methods for the Examination of Water and Wastewater*, or by such other methods approved by the Board.
23. All analyses shall be performed in a Canadian Association of Environmental Analytical Laboratories (CAEAL) Certified Laboratory, or as otherwise approved by an Analyst.
24. The Licensee shall include all of the data and information required by the “Monitoring Program” in the Licensee's Annual Report, as required *per* Part B, Item 1 or as otherwise requested by an Inspector.
25. Her Majesty in the right of Canada shall:
  - i. Monitor the Licensee’s installation of thermistors and notify the Board when the installation of thermistors is complete and in compliance with Part H, Item 6;
  - ii. Monitor the Licensee’s validation of the assumptions of the geothermal analysis through adequate monitoring of the thermal regime for the East and West Berms and downstream foundations under Part H, Item 7, and notify the Board when satisfied the assumptions of the geothermal analysis have been validated; and
  - iii. Monitor the 2007 Waste Disposal Facility and notify the Board immediately if the Project is commissioned prior to the completion of i. and ii., or in contravention of any other condition of the Licence.

## **SCHEDULE 1            CONDITIONS APPLYING TO MODIFICATIONS AND CONSTRUCTION**

### **List of drawing deficiencies identified by BGC for revision and submission.**

Please refer to Technical Memorandum “Cape Dorset Sewage lagoon-Review of Final Submissions, January 8, 2008”, or the final intervention memo dated January 8, 2008 for further clarification.

The record set of drawings fails to include a signature block for AMEC. It was noted that the original design drawings issued by Dillon in the December 21, 2006 design report, revision 5, marked “Issued for Construction” included a signature block “Reviewed by AMEC” on Drawing 111, which is the equivalent of Drawing 112 of the Record Drawings

1.     At a minimum, AMEC is to provide a signature block for the following drawings:
  - Drawing 101- shows location of test pits carried out for geotechnical investigations.
  - Drawing 109- shows longitudinal geological sections along cut-off trench.
  - Drawing 110- shows typical earthworks sections for the access road and berm.
  - Drawing 112- shows lagoon berm sections
2.     The as-built drawings must identify the areas where field changes were made from the original design drawings, preferably in the form of a revision bubble and a brief note in the revisions section of the title block.

### **List of Drawing alterations and request for rationale for the change.**

Record drawing 100 – the alignment of the access roads between the East and West Berms, on the north and south sides of the lagoon was changed from the original design. The road berms were originally designed to deflect runoff from entering the lagoon.

3.     Explanation is required as to the rationale for changing the alignment of the road berms and how the as-built berm details in the drawing prevents runoff from entering the lagoon.

Record Drawing 109 – there is up to 1m of unfrozen fill used to level the ground surface under both the East and West berms. This leveling course of material has not been shown as a separate zone in the berm sections presented in Record Drawing 112.

4.     A description for record drawing 112 is required of the material used including grain size gradation curve.

Record Drawing 109 – shows that the berm contours at the north end of the West Berm have been modified from the original design drawings. Crest widened from 4m to 25m to accommodate what appears to be a vehicle turnaround on the downstream side of the berm.

5. Additional as-built cross-sections of this area are to be provided along with geothermal analysis that there is sufficient fill thickness over the abutment to ensure that the GCL tie-in to the cut-off trench remains frozen.

Record Drawing 110 shows typical road sections. On July 30, 2007, the GN CGS provided a revised ditch detail for the road

6. This revised ditch detail is requested as part of the as-built drawing details for Drawing 110
7. Additional information is requested providing further details as to how seepage through the active zone under the berm will be prevented.

The Hamlet of Cape Dorset noted a problem during the October 1, 2007 Technical Meeting/Pre-Hearing, with seepage into the lagoon through the active zone with the as-constructed detail. Record Drawing 112 indicates that the material used to backfill the cut-off trench is a “Sand”, the same material as used for the berm.

8. Further clarification is requested on how the issue of seepage is being resolved.

In the original Design Drawing 111, Detail 4 showed the liner embedment longitudinal section in the abutments. This Detail was absent from Record Drawing 112. The cut-off trench must extend sufficient distance into the abutment so that any “end-run” seepage through the active zone is prevented. It is not clear from the as-built information if the extent of the cut-off trench satisfies this criterion.

9. Therefore the as-built liner embedment details for the abutment areas of the East and West Berms are therefore requested to be included for Record Drawing 112.

In Record Drawing 112, the crest detail of the emergency overflow weir section was changed. This change notice was transmitted to the contractor by Dillon on July 21, 2007. The as-built detail shows the geo-web and the GCL in one layer, with no granular or other material between the two. Dillon initiated this modification to address a previous concern raised by BGC that water could seep under the GCL in the emergency spillway and potentially lift the liner. It is still not clear how the above modification prevents this problem from occurring.

10. Design change rationale is requested that provides an explanation as to the change from the original drawing, change to meet BGC’s concern and then further change to what appears to be potentially inadequate construction.

## **SCHEDULE 2            CONDITIONS APPLYING TO MONITORING AND MAINTENANCE**

A revised *Operation and Maintenance Manual, Sewage Treatment System, Hamlet of Cape Dorset, November 7, 2007* shall include the following requirements:

- i. Expansion of Section 3.4.5 to include terms and conditions for the disposal of sludge as provided for in the Draft Guidelines for Discharge of Domestic Wastewater in Nunavut, 2000;
- ii. Section 3.4.6 should include a description of the installation of thermistors required under Part H, Item 6, including the number, locations and depths of thermistor beads used to monitor the berms, and a description of the method and frequency of monitoring requirements;
- iii. Section 3.4.6 should include a description of the installation of monitoring wells required under Part H, Item 7, including the number, locations and depths of thermistor beads used to monitor the berms, and a description of the method and frequency of monitoring requirements
- iv. Description of the details of any repairs, upgrades and maintenance required for the use of part or all of the 2001 Sewage Disposal Facility or Emergency Sewage Disposal Facility;
- v. Include a contingency plan for the operation of the 2007 Sewage Disposal Facility during periods where accessibility to the facility is limited and alternative measures are required for the handling of sewage. This may include operation and maintenance of any older facility or portion of, that would be retained as the contingency;
- vi. Provision for the monitoring of effluent discharges from the 2001 Sewage Disposal Facility and the Emergency Sewage Disposal Facility;
- vii. Inspection program for the 2001 Sewage Disposal Facility, the Emergency Sewage Disposal Facility and 2007 Sewage Disposal Facility, detailing the frequency and inspection requirements by the operator(s) of the facility;
- viii. Appendix C of the O&M Manual to include forms to document the recommendations and follow up work required as a result of the annual geotechnical inspection.
- ix. Section 4 – Spill Contingency Plan be revised to comprehensively address specific recommendations provided during the review process by GN DoE as follows:
  - a. The date the contingency plan was prepared.
  - b. The name and address of the person in charge, management or control. This is an on-site person responsible for managing the facility. This person would be initially responsible for clean-up activities.
  - c. The name and address of the owner if different from the person in charge. This is the person ultimately responsible for the facility, usually the owner.
  - d. The name, job title and 24 hour telephone number for the persons responsible for activating the contingency plan. This ensures the employee discovering the spill can activate a response and provides a 24 hour point of contact for the authority

- investigating the spill.
- e. A description of the facility including the location, size and storage capacity. This is important if persons are unfamiliar with the facility or area. The description could include a map and/or diagrams.
- f. A site map that is intended to illustrate the facilities relationship to other areas that may be affected by the spill. The map should be to scale and be large enough to include the location of your facility, nearby buildings or facilities, roads, culverts, drainage patterns, and any nearby bodies of water.
- g. The steps to be taken to report, contain, and clean up and dispose of a contaminant in the case of a spill.
  - 1. Reporting: Notification of all parties involved. This can include internal and external reporting procedures as well as a copy of the spill report;
  - 2. Clean up: Removal of the contaminant from the environment, a detailed of actual containment and clean up techniques. (2 steps: contain and remediate; be aware of fire);
  - 3. Disposal: Is the treatment of the contaminant such that it is no longer a threat to the environment. Plans may include location of disposal sites approved to accept wastes, means of storage prior to disposal and other approvals required. (Waste Manifest document).
- h. The means by which the contingency plan is activated. This should outline internal company procedures to activate appropriate response equipment and personnel.
- i. A description of the training provided to employees to respond to a spill. A sound training program is necessary when dealing with an emergency situation.
- j. An inventory and the location of response and clean up equipment available to implement the plan. This includes your equipment as well as any to be used by another person responding to the spill on your behalf.
- k. SPILL KIT (FUEL)/The kit can include but not limited to the following: shovel, pick-axe, drums, booms, absorbent pad/sheet, disposable protective gloves/coveralls, sorbent and containment materials, and disposal bags.
- l. A list of local contractors or clean up specialists who may be called upon to assist in responding to spills. A list of emergency numbers such as fire, ambulance and police.
- x. Section 4 – describe the measures to be implemented for a spill during the collection and transportation of wastewater. This spill response is to be expanded to include spill scenarios resulting from the leakage or failure of a containment structure for the Sewage Disposal Facilities; and
- xi. Appendix B to include specific reference to monitoring stations and required frequency of sampling and the analyses required by the Licence.



## **Appendix C: Environmental Monitoring Program Checklist, Summary of Sample Bottle Requirements**

This page intentionally left blank

# HAMLET OF CAPE DORSET

## ENVIRONMENTAL MONITORING PROGRAM CHECKLIST

### PRE-SAMPLING ACTIVITIES

<b>Bottle Order</b>	At least two weeks before upcoming environmental sampling (see Environmental Monitoring Program Schedule in Appendix E), send a request to the contract laboratory for the appropriate sample sets (bottles) for the required sampling test groups (see Conditions 2 & 4 of Part H of Nunavut Water Board Licence 3BM-CAP0810)	<input type="checkbox"/>
<b>Personal Protective Equipment</b>	Ensure that the required personal protective equipment (PPE), such as latex gloves, is on hand before commencing the environmental monitoring program.	<input type="checkbox"/>
<b>Bottle Shipment</b>	Ensure that the bottle shipment has arrived from the contract laboratory in time for the sampling program and verify the integrity of all sampling containers. Report any missing or broken bottles to the contract laboratory as soon as possible, so that replacement bottles may be shipped.	<input type="checkbox"/>
<b>Sampling Location Inspections</b>	Perform an initial inspection of all routinely-monitored sampling locations before the commencement of the monitoring program. Make note of any equipment damage or conditions that may prevent the collection of the environmental monitoring program samples.	<input type="checkbox"/>

### GENERAL SAMPLING INSTRUCTIONS

<b>Prevention of Cross-Contamination</b>	Ensure that any laboratory provided sampling instructions are strictly followed. Latex or nitrile gloves should be worn during sampling and should be replaced with fresh gloves after all sample containers are filled at each sampling location. Dedicated sampling equipment such as sampling poles should be cleaned with soap and water after each sample is collected to prevent cross-contamination. As a general recommendation, please refrain from using insect repellent, disinfection hand gel or other chemical products before and during sample collection. Also, please refrain from smoking during sample collection.	<input type="checkbox"/>
<b>Sample Care (including Packing of Cooler)</b>	All sample containers should be tightly sealed and properly labelled with the sample ID, date and time of sample collection, location of sample collection and parameters to be analyzed. The outside of the bottles should be cleaned with soap and water and dried prior to placing the samples in the cooler. The samples should be stored on ice in a cooler until delivery to the laboratory. A chain of custody form should be filled out completely and be used to track the samples and placed in the cooler with the samples, in a ziplock bag. Keep the last page of the Chain of Custody and give it to the Hamlet Foreman for their records.	<input type="checkbox"/>

### RAW WATER SUPPLY

<b>Sampling Station CAP-1</b>	Station CAP-1 (see Figure 2) is a raw water supply (from Tee Lake) volume monitoring location. The water licence does not require the collection of any water samples from this location. Measure and record (in m <sup>3</sup> ) the monthly and annual quantities of water pumped from Station CAP-1.	<input type="checkbox"/>
-------------------------------	---	--------------------------

### SOLID WASTE DISPOSAL FACILITIES

<b>Sampling Station CAP-2</b>	Landfill runoff is collected once monthly during periods of observed flow (see Schedule in Appendix E for timing and list of parameters to be sampled). Runoff samples are collected from the receiving water body (see Figure 2) by immersing the sample bottle into the runoff stream neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with runoff and the sample bottle is raised neck first to prevent sample spillage.	<input type="checkbox"/>
<b>Sampling Station CAP-19</b>	A groundwater sample is collected from a monitoring well located up gradient of the Solid Waste Disposal Facility (see Figure 2) once annually in the summer (see Schedule in Appendix E for timing and list of parameters to be sampled), giving due consideration to adequate ground thaw and obtaining a representative groundwater sample. The groundwater sample should be collected using dedicated sampling tubing with a Waterra™ foot valve (or bailer). Well purging should not be undertaken due to the potential limited availability of groundwater in the monitoring well. Instead, a sample should be collected of all available groundwater present in the monitoring well.	<input type="checkbox"/>
<b>Sampling Station CAP-20</b>	A groundwater sample is collected from a monitoring well located down gradient of the Solid Waste Disposal Facility (see Figure 2) once annually in the summer (see Schedule in Appendix E for timing and list of parameters to be sampled), giving due consideration to adequate ground thaw and	<input type="checkbox"/>

	obtaining a representative groundwater sample. The groundwater sample should be collected using dedicated sampling tubing with a Waterra™ foot valve (or bailer). Well purging should not be undertaken due to the potential limited availability of groundwater in the monitoring well. Instead, a sample should be collected of all available groundwater present in the monitoring well.	
<b>ACTIVE SEWAGE DISPOSAL FACILITY</b>		
<b>Sampling Station CAP-3</b>	Wastewater influent samples are collected from the active sewage disposal facility (see Figure 2) beginning one week prior to the proposed discharge date, once at the beginning of the discharge and weekly thereafter until the cessation of discharge (see Schedule in Appendix E for timing and list of parameters to be sampled). Wastewater influent samples are collected from the lagoon by immersing the sample bottle into the lagoon neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with influent wastewater and the sample bottle is raised neck first to prevent sample spillage.	<input type="checkbox"/>
<b>2001 SEWAGE DISPOSAL FACILITIES</b>		
<b>Sampling Station CAP-4</b>	Effluent discharge samples are collected from the 2001 Sewage Disposal Facility (see Figure 2), beginning one week prior to the proposed discharge date, once at the beginning of the discharge and weekly thereafter until the cessation of discharge (see Schedule in Appendix E for timing and list of parameters to be sampled). Wastewater effluent samples are collected from the receiving water body by immersing the sample bottle into the effluent stream neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with effluent wastewater and the sample bottle is raised neck first to prevent sample spillage.	<input type="checkbox"/>
<b>EMERGENCY SEWAGE DISPOSAL FACILITIES</b>		
<b>Sampling Station CAP-5</b>	Effluent discharge samples are collected from the Emergency Sewage Disposal Facility (see Figure 2), beginning one week prior to the proposed discharge date, once at the beginning of the discharge and weekly thereafter until the cessation of discharge (see Schedule in Appendix E for timing and list of parameters to be sampled). Wastewater effluent samples are collected from the receiving water body by immersing the sample bottle into the effluent stream neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with effluent wastewater and the sample bottle is raised neck first to prevent sample spillage.	<input type="checkbox"/>
<b>2007 SEWAGE DISPOSAL FACILITIES</b>		
<b>Sampling Station CAP-6</b>	Effluent discharge samples are collected from the Final Point of Control at the 2007 Sewage Disposal Facility (see Figure 3), beginning one week prior to the proposed discharge date, once at the beginning of the discharge and weekly thereafter until the cessation of discharge (see Schedule in Appendix E for timing and list of parameters to be sampled). Wastewater effluent samples are collected from the receiving water body by immersing the sample bottle into the effluent stream neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with effluent wastewater and the sample bottle is raised neck first to prevent sample spillage.	<input type="checkbox"/>
<b>Sampling Station CAP-7</b>	Wastewater influent samples are collected from P-Lake (see Figure 3), beginning one week prior to the proposed discharge date, once at the beginning of the discharge and weekly thereafter until the cessation of discharge (see Schedule in Appendix E for timing and list of parameters to be sampled). Wastewater influent samples are collected from P-Lake by immersing the sample bottle into P-Lake neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with influent wastewater and the sample bottle is raised neck first to prevent sample spillage.	<input type="checkbox"/>
<b>Sampling Station CAP-8</b>	Wastewater samples are collected from the centre of P-Lake (see Figure 3), beginning one week prior to the proposed discharge date, once at the beginning of the discharge and weekly thereafter until the cessation of discharge (see Schedule in Appendix E for timing and list of parameters to be sampled). Wastewater samples are collected from P-Lake by immersing the sample bottle into P-Lake neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with wastewater and the sample bottle is raised neck first to prevent sample spillage.	<input type="checkbox"/>
<b>Sampling Station CAP-9</b>	Wastewater samples are collected from a location midway between the centre of P-Lake (Station CAP-8) and the effluent discharge of P Lake (Station CAP-10), beginning one week prior to the proposed discharge date, once at the beginning of the discharge and weekly thereafter until the cessation of discharge (see Schedule in Appendix E for timing and list of parameters to be sampled). Wastewater samples are collected from P-Lake (see Figure 3) by immersing the sample bottle into P-	<input type="checkbox"/>

	Lake neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with wastewater and the sample bottle is raised neck first to prevent sample spillage.	
<b>Sampling Station CAP-10</b>	Wastewater effluent discharge samples are collected from P-Lake (see Figure 3). If flow is negligible, then the samples are collected from a location located immediately upstream within P-Lake. These samples are collected beginning one week prior to the proposed discharge date, once at the beginning of the discharge and weekly thereafter until the cessation of discharge (see Schedule in Appendix E for timing and list of parameters to be sampled). Wastewater effluent samples are collected from the receiving water body by immersing the sample bottle into water body neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with effluent wastewater and the sample bottle is raised neck first to prevent sample spillage.	<input type="checkbox"/>
<b>Sampling Station CAP-11</b>	Wastewater effluent discharge samples are collected from the Wetland area (see Figure 3) beginning one week prior to the proposed discharge date, once at the beginning of the discharge and weekly thereafter until the cessation of discharge (see Schedule in Appendix E for timing and list of parameters to be sampled). Wastewater effluent samples are collected from the wetland by immersing the sample bottle into the wetland neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with effluent wastewater and the sample bottle is raised neck first to prevent sample spillage.	<input type="checkbox"/>
<b>Sampling Station CAP-12</b>	Wastewater effluent discharge samples are collected from the top of the waterfall on the Wetland Pathway (see Figure 3) beginning one week prior to the proposed discharge date, once at the beginning of the discharge and weekly thereafter until the cessation of discharge (see Schedule in Appendix E for timing and list of parameters to be sampled). Wastewater effluent discharge samples are collected from the waterfall by immersing the sample bottle into the waterfall neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with effluent discharge wastewater and the sample bottle is raised neck first to prevent sample spillage.	<input type="checkbox"/>
<b>Sampling Station CAP-13</b>	Wastewater effluent discharge samples are collected from midway down the waterfall on the Wetland Pathway (see Figure 3) beginning one week prior to the proposed discharge date, once at the beginning of the discharge and weekly thereafter until the cessation of discharge (see Schedule in Appendix E for timing and list of parameters to be sampled). Wastewater effluent discharge samples are collected from the waterfall by immersing the sample bottle into the waterfall neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with effluent discharge wastewater and the sample bottle is raised neck first to prevent sample spillage.	<input type="checkbox"/>
<b>Sampling Station CAP-14</b>	Wastewater effluent discharge samples are collected from the Final Discharge Point (see Figure 3), located at the bottom of the cliff, beginning one week prior to the proposed discharge date, once at the beginning of the discharge and weekly thereafter until the cessation of discharge (see Schedule in Appendix E for timing and list of parameters to be sampled). Wastewater effluent discharge samples are collected from the water body by immersing the sample bottle into the water body neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with effluent discharge wastewater and the sample bottle is raised neck first to prevent sample spillage.	<input type="checkbox"/>
<b>Sampling Station CAP-15</b>	Wastewater effluent discharge samples are collected from a Control Point sampling location (small lake) located between the Lagoon and Tee Lake (see Figure 3), beginning one week prior to the proposed discharge date, once at the beginning of the discharge and weekly thereafter until the cessation of discharge (see Schedule in Appendix E for timing and list of parameters to be sampled). Wastewater effluent discharge samples are collected from the lake by immersing the sample bottle into the lake neck first to a depth of 5 to 10 cm (if possible). The sampling container is filled with effluent discharge wastewater and the sample bottle is raised neck first to prevent sample spillage.	<input type="checkbox"/>
<b>Sampling Station CAP-16</b>	A groundwater sample is collected from a monitoring well located up gradient of the 2007 Sewage Disposal Facility (see Figure 3) once annually in the summer, prior to commencing discharge from the 2007 Sewage Disposal Facility, giving due consideration to adequate ground thaw and obtaining a representative groundwater sample (see Schedule in Appendix E for timing and list of parameters to be sampled). The groundwater sample should be collected using dedicated sampling tubing with a Waterra™ foot valve (or bailer). Well purging should not be undertaken due to the potential limited availability of groundwater in the monitoring well. Instead, a sample should be collected of all available groundwater present in the monitoring well.	<input type="checkbox"/>
<b>Sampling Station CAP-17</b>	A groundwater sample is collected from Monitoring Well No.1 located down gradient of the 2007 Sewage Disposal Facility (see Figure 3) once annually in the summer, prior to commencing	<input type="checkbox"/>

	discharge from the 2007 Sewage Disposal Facility, giving due consideration to adequate ground thaw and obtaining a representative groundwater sample (see Schedule in Appendix E for timing and list of parameters to be sampled). The groundwater sample should be collected using dedicated sampling tubing with a Waterra™ foot valve (or bailer). Well purging should not be undertaken due to the potential limited availability of groundwater in the monitoring well. Instead, a sample should be collected of all available groundwater present in the monitoring well.	
<b>Sampling Station CAP-18</b>	A groundwater sample is collected from Monitoring Well No.2 located down gradient of the 2007 Sewage Disposal Facility (see Figure 3) once annually in the summer, prior to commencing discharge from the 2007 Sewage Disposal Facility, giving due consideration to adequate ground thaw and obtaining a representative groundwater sample (see Schedule in Appendix E for timing and list of parameters to be sampled). The groundwater sample should be collected using dedicated sampling tubing with a Waterra™ foot valve (or bailer). Well purging should not be undertaken due to the potential limited availability of groundwater in the monitoring well. Instead, a sample should be collected of all available groundwater present in the monitoring well.	<input type="checkbox"/>
<b>POST-SAMPLING ACTIVITIES</b>		
<b>Sample Shipment</b>	See <b>Sample Care</b> section for sampling handling and cooler packing instructions. Ensure all samples are shipped to the contract laboratory immediately after the completion of the environmental monitoring event to ensure that the hold times are respected for the various parameters. Follow-up with the contract laboratory on the day after the samples were shipped to ensure that the samples were collected from the air cargo facility and received by the contract laboratory for analysis.	<input type="checkbox"/>
<b>Analytical Results</b>	Ensure that the analytical results for the environmental monitoring program samples are received within the specified turn-around time. Follow-up with the contract laboratory if the results are not provided as expected to ensure timely reporting to the Nunavut Water Board (as required by Water Licence 3BM-CAP0810).	<input type="checkbox"/>

Checklist Performed By:

\_\_\_\_\_  
Name\_\_\_\_\_  
Signature\_\_\_\_\_  
Date

**Sample Bottle Requirements for Parameters Listed in Conditions 2 & 4 of Part H of  
Nunavut Water Board Licence No. 3BM-CAP0810**

<b>Parameter</b>	<b>Recommended Sample Container</b>	<b>Preservative</b>	<b>Hold Time</b>
Alkalinity	250 mL plastic	None	14 days
Anions (Br, Cl, F, NO <sub>3</sub> , NO <sub>2</sub> , PO <sub>4</sub> , SO <sub>4</sub> )	250 mL plastic	None	5/28 Days
Biochemical Oxygen Demand (BOD <sub>5</sub> )	500 mL plastic	None	4 days
Carbonaceous Biochemical Oxygen Demand (CBOD <sub>5</sub> )	500 mL plastic	None	4 days
Carbon, Total Organic (TOC)	250 mL plastic	H <sub>2</sub> SO <sub>4</sub> (pH < 2)	10 days
Conductivity	250 mL plastic	None	28 days
Dissolved ICPMS, ICP Metals	250 mL plastic	None - if not field filtering	60 days
Total ICPMS, ICP Metals - NOT FILTERED	250 mL plastic	HNO <sub>3</sub> (pH < 2)	30 days
Nitrogen - Ammonia ( NH <sub>3</sub> - N ) / Total Kjeldahl Nitrogen ( TKN )	250 mL plastic	H <sub>2</sub> SO <sub>4</sub> (pH < 2)	10 days
Phenolics - Total	120 mL amber glass	H <sub>2</sub> SO <sub>4</sub> (pH < 2)	30 days
Solids - ( TS, TSS, TDS )	500 mL plastic	None	7 days
Microbiological (incl. faecal coliforms)	300 mL plastic - Sterilized	Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub>	48 hours
Total Hardness	500 mL plastic	None	28 days

This page intentionally left blank



## **Appendix D: Completed Example of Chain of Custody Documentation**

This page intentionally left blank

Turnaround Time Requested	
Rush 24 Hr	<input type="checkbox"/> 100% Surcharge
Rush 48 Hr	<input type="checkbox"/> 50% Surcharge
Rush 72 Hr	<input type="checkbox"/> 25% Surcharge
5-7 Day	<input checked="" type="checkbox"/> Standard

[illegible]

This page intentionally left blank

## **Appendix E:** **Environmental Monitoring Program Schedule**

This page intentionally left blank

Cape Dorset Monitoring Program Schedule  
Nunavut Water Board Licence No. 38M-CAP0810

Monitoring Station ID	Location Description	Month												Annual
		January	February	March	April	May	June	July	August	September	October	November	December	
CAP-1	Raw water supply from Tee Lake	V	V	V	V	V	V	V	V	V	V	V	V	V
CAP-2	Runoff from Solid Waste Disposal Facilities					LR <sup>1</sup>	LR <sup>1</sup>	LR <sup>1</sup>	LR <sup>1</sup>	LR <sup>1</sup>				
CAP-3	Influent of Wastewater to Wastewater Facilities (active at the time of sampling)					WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>				
CAP-4	Effluent discharge from the 2001 Sewage Disposal Facilities	V	V	V	V	V, WW <sup>2</sup>	V, WW <sup>2</sup>	V, WW <sup>2</sup>	V, WW <sup>2</sup>	V, WW <sup>2</sup>	V	V	V	V
CAP-5	Effluent discharge from the Emergency Sewage Disposal Facilities	V	V	V	V	V, WW <sup>2</sup>	V, WW <sup>2</sup>	V, WW <sup>2</sup>	V, WW <sup>2</sup>	V, WW <sup>2</sup>	V	V	V	V
CAP-6	Effluent discharge from the 2007 Sewage Disposal Facilities - Final Point of Control	V	V	V	V	V, WW <sup>2</sup>	V, WW <sup>2</sup>	V, WW <sup>2</sup>	V, WW <sup>2</sup>	V, WW <sup>2</sup>	V	V	V	V
CAP-7	Point of influent of wastewater to P-Lake					WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>				
CAP-8	Centre of P-Lake					WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>				
CAP-9	Location midway between the Centre of P-Lake (Station 8) and the effluent discharge of P-Lake					WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>				
	Effluent discharge from P-Lake (note: if flow is negligible a sample from the immediate upstream area within P-Lake shall be obtained)					WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>				
CAP-10						WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>				
CAP-11	Effluent discharge from Wetland Area					WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>				
	Wetland Pathway at the top of the waterfall					WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>				
CAP-12						WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>				
	Wetland Pathway at mid-way down waterfall					WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>				
CAP-13						WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>				
	Wetland Pathway at bottom of cliff - Final Discharge Point					WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>				
CAP-14						WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>				
CAP-15	Control point using a small lake located between the Lagoon and Tee Lake					WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>	WW <sup>2</sup>				
CAP-16	Monitoring well located up gradient of the 2007 Sewage Disposal Facility								GW <sup>3</sup>					
	Monitoring Well No. 1 located down gradient of the 2007 Sewage Disposal Facility								GW <sup>3</sup>					
CAP-17									GW <sup>3</sup>					
	Monitoring Well No. 2 located down gradient of the 2007 Sewage Disposal Facility								GW <sup>3</sup>					
CAP-18									GW <sup>3</sup>					
	Monitoring well located up gradient of the Solid Waste Disposal Facilities								GW <sup>3</sup>					
CAP-19									GW <sup>3</sup>					

Cape Dorset Monitoring Program Schedule  
Nunavut Water Board Licence No. 38M-CAP0810

Monitoring Station ID	Location Description	January	February	March	April	May	June	July	August	September	October	November	December	Annual
	Monitoring well located down gradient of the Solid Waste Disposal Facilities								GW <sup>3</sup>					
CAP-20														
CAP-21	Thermistor Station													
CAP-22	Thermistor Station													
CAP-23	Thermistor Station													
CAP-24	Thermistor Station													
Test Groups														
V	Volume (m <sup>3</sup> )													
LR	Landfill Runoff	(Biochemical Oxygen Demand (BOD <sub>5</sub> ), pH, Total Suspended Solids (TSS), nitrate-nitrite, total phenols, total hardness, magnesium, sodium, total arsenic, total copper, total iron, total mercury, faecal coliforms, conductivity, ammonia nitrogen, oil & grease (visual), total alkalinity, calcium, potassium, sulphate, total cadmium, total chromium, total lead, total nickel)												
WW	Wastewater Effluent	(Biochemical Oxygen Demand (BOD <sub>5</sub> ), Carbonaceous Biochemical Oxygen Demand (CBOD <sub>5</sub> ), Total Suspended Solids (TSS), pH, conductivity, oil & grease (visual), faecal coliforms, nitrate-nitrite, total phosphorus, magnesium, sodium, chloride, total hardness, ammonia nitrogen, total phenols, calcium, potassium, sulphate, total alkalinity, total trace metals (including Al, Sb, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Li, Mn, Mo, Ni, Se, Sn, Sr, Ti, U, V, Zn), total arsenic, total mercury, Total Organic Carbon (TOC))												
GW	Groundwater	(Biochemical Oxygen Demand (BOD <sub>5</sub> ), pH, Total Suspended Solids (TSS), nitrate-nitrite, total phenols, total hardness, magnesium, sodium, total arsenic, total copper, total iron, total mercury, faecal coliforms, conductivity, ammonia nitrogen, oil & grease (visual), total alkalinity, calcium, potassium, sulphate, total cadmium, total chromium, total lead, total nickel)												

- <sup>1</sup> Sample monthly during periods of observed flow.
- <sup>2</sup> TBD by operational staff - samples to be collected one week prior to proposed discharge date, once at the beginning of discharge and weekly thereafter until cessation of discharge.
- <sup>3</sup> Once annually in the summer, given due consideration to adequate ground thaw and obtaining a representative groundwater sample.



## **Appendix F: Subcontract Laboratory Accreditation & Supporting Documentation**

This page intentionally left blank



# CALA

Canadian Association for  
Laboratory Accreditation Inc.

## CALA Directory of Laboratories

---

**Membership Number:** 2644

**Laboratory Name:** Caduceon Environmental Laboratories (Ottawa)

**Parent Institution:** Caduceon Enterprises Inc.

**Address:** 2378 Holly Lane Ottawa ON K1V 7P1

**Contact:** Mr. Greg Clarkin

**Phone:** (613) 526-0123

**Fax:** (613) 526-1244

**Email:** gclarkin@caduceonlabs.com

---

**Standard:** Conforms with requirements of ISO/IEC 17025

**Clients Served:**

**Revised On:** May 9, 2013

**Valid To:** October 25, 2015

---

### Scope of Accreditation

#### Air (Inorganic)

Metals - Air Filter (012)

D-ICP-02; modified from APHA 3120 B

ICP - DIGESTION

Cadmium

Chromium

Cobalt

Copper

Iron

Lead

Manganese

Molybdenum

Nickel

Zinc

#### Air (Inorganic)

Total Suspended Particulates - Air Filter (018)

A-TSP-01; modified from MOEE E3288A

GRAVIMETRIC

Total Suspended Particulates

#### Dustfall

Total/Insoluble Dustfall - Dustfall (020)

A-DF-01; modified from MOEE DF-E3043A

FILTRATION - GRAVIMETRIC

Insoluble Dustfall

Total Dustfall

† "OSDWA" indicates the appendix is used for the analysis of Ontario drinking water samples, which is subject to the rules and related regulations under the Ontario "Safe Drinking Water Act" (2002).

The list of tests and measurement capabilities for which a laboratory is accredited can change at any time due to circumstances such as scope extensions, voluntary withdrawal of tests by the laboratory and suspension. Scopes are published by the CALA via the Internet at [http://www.cala.ca/cala\\_directories.html](http://www.cala.ca/cala_directories.html)

**Fluoride Candles**

Fluoride - Candles (019)

A-FISE-01; modified from MOEE FSIE-1983D

DIGESTION - ISE

Fluoride

**Oil (Organic)**

Polychlorinated Biphenyls (PCB) - Oil (040)

C-PCB-01; modified from EPA 8081

GC/ECD - EXTRACTION

Aroclor 1242

Aroclor 1248

Aroclor 1254

Aroclor 1260

**Solids (Inorganic)**

Anions - Soils, Biosolids (069)

A-IC-01; modified from APHA 4110 C

ION CHROMATOGRAPHY - EXTRACTION

Chloride

Nitrate

Nitrite

Sulphate

**Solids (Inorganic)**

Boron (Hot Water Soluble) - Soil (098)

D-ICP-02; MOE-LaSB E3470

ICP/AES - EXTRACTION

Boron

**Solids (Inorganic)**

Conductivity - Soil, Sediments (099)

A-CONDO-03; SM 2510 B & MOE-LaSB E 3138

CONDUCTIVITY METER - EXTRACTION

Conductivity

**Solids (Inorganic)**

Extractable Anions - Leachate (090)

A-IC-01; modified from EPA 1311, APHA 4110-C

ION CHROMATOGRAPHY - TCLP

Nitrate

Nitrite

**Solids (Inorganic)**

Extractable Metals - Leachate (091)

D-ICP-01; modified from EPA 1311/APHA 3120 B

ICP/AES - TCLP

Arsenic

Barium

Beryllium

Boron

Cadmium

Chromium

Lead

Nickel

Silver

Zinc

† "OSDWA" indicates the appendix is used for the analysis of Ontario drinking water samples, which is subject to the rules and related regulations under the Ontario "Safe Drinking Water Act" (2002).

The list of tests and measurement capabilities for which a laboratory is accredited can change at any time due to circumstances such as scope extensions, voluntary withdrawal of tests by the laboratory and suspension. Scopes are published by the CALA via the Internet at [http://www.cala.ca/cala\\_directories.html](http://www.cala.ca/cala_directories.html)

**Solids (Inorganic)**

Extractable Metals - Leachate (092)

D-ICPMS-01; modified from EPA 1311/EPA 200.8

ICP/MS - TCLP

Antimony

Arsenic

Selenium

Uranium

**Solids (Inorganic)**

Extractable Metals - Leachate (093)

D-HG-02; modified from EPA 1311/SM 3112 B

COLD VAPOUR AA - TCLP

Mercury

**Solids (Inorganic)**

Flash Point - Soil, Solid Waste (096)

C-FPCC-01; modified FROM ASTM D93-10

CLOSED CUP FLASH POINT TESTER

Flashpoint

**Solids (Inorganic)**

Hexavalent Chromium - Soil (094)

D-CRVI-02; modified from EPA 3060A EPA 7196 A

COLORIMETRIC - MANUAL

Chromium (VI)

**Solids (Inorganic)**

Mercury - Soil, Solid Biosolids (017)

D-HG-01; modified from EPA 7471A

COLD VAPOUR AA - DIGESTION

Mercury

**Solids (Inorganic)**

Metals - Soil, Solid Biosolids (015)

D-ICP-02; modified from EPA 6010

ICP/OES - DIGESTION

Aluminum

Antimony

Arsenic

Barium

Beryllium

Boron

Cadmium

Calcium

Chromium

Cobalt

Copper

Iron

Lead

Magnesium

Manganese

Molybdenum

Nickel

Potassium

Silver

Sodium

Strontium

† "OSDWA" indicates the appendix is used for the analysis of Ontario drinking water samples, which is subject to the rules and related regulations under the Ontario "Safe Drinking Water Act" (2002).

The list of tests and measurement capabilities for which a laboratory is accredited can change at any time due to circumstances such as scope extensions, voluntary withdrawal of tests by the laboratory and suspension. Scopes are published by the CALA via the Internet at [http://www.cala.ca/cala\\_directories.html](http://www.cala.ca/cala_directories.html)

Tin  
Titanium  
Tungsten  
Vanadium  
Zinc

**Solids (Inorganic)**

pH - Soil, Sediment, Solid Sludge (100)  
A-pH-03; SM 4500 H & MOE-LaSB E3137  
pH METER - EXTRACTION  
pH

**Solids (Inorganic)**

Total Metals - Soils, Biosolids (070)  
D-ICPMS-01; modified from EPA 6020  
ICP/MS - DIGESTION  
Antimony  
Arsenic  
Selenium  
Silver  
Thallium  
Uranium

**Solids (Organic)**

Extractable Volatile Organic Compounds (VOC) - Leachate (089)  
C-VOC-01; modified from EPA SW-846 METHOD 1311, 5030/8260  
GC/MS - PURGE AND TRAP - TCLP  
1,1-Dichloroethylene  
1,2-Dichlorobenzene  
1,2-Dichloroethane  
1,4-Dichlorobenzene  
Benzene  
Carbon tetrachloride  
Chlorobenzene  
Chloroform  
Dichloromethane  
Methyl ethyl ketone  
Tetrachloroethylene  
Trichloroethylene  
Vinyl chloride

**Solids (Organic)**

Petroleum Hydrocarbons (PHC) - Soil (075)  
C-PHCS-01; modified from CCME CWS REF. METHOD & MOE E3398  
GC/FID - EXTRACTION  
F2: C10-C16  
F3: C16-C34  
F4: C34-C50

**Solids (Organic)**

Petroleum Hydrocarbons (PHC) - Soil (097)  
C-PHCS-01; modified from CCME CWS REF. METHOD & MOE E3398  
GRAVIMETRIC  
F4: Gravimetric

† "OSDWA" indicates the appendix is used for the analysis of Ontario drinking water samples, which is subject to the rules and related regulations under the Ontario "Safe Drinking Water Act" (2002).

The list of tests and measurement capabilities for which a laboratory is accredited can change at any time due to circumstances such as scope extensions, voluntary withdrawal of tests by the laboratory and suspension. Scopes are published by the CALA via the Internet at [http://www.cala.ca/cala\\_directories.html](http://www.cala.ca/cala_directories.html)

**Solids (Organic)**

Polychlorinated Biphenyls (PCB) - Soil (053)

C-PCB-02; modified from EPA 8000/8081

GC/ECD - EXTRACTION

Aroclor 1242

Aroclor 1248

Aroclor 1254

Aroclor 1260

**Solids (Organic)**

Volatile Organic Compounds (VOC) - Soil (063)

C-VOC-02; modified from EPA 8260

GC/MS - PURGE AND TRAP

1,1 - Dichloropropene

1,1-Dichloroethane

1,1-dichloroethylene

1,1,1-Trichloroethane

1,1,1,2 - Tetrachloroethane

1,1,2-Trichloroethane

1,1,2,2-Tetrachloroethane

1,2 - Dibromo - 3 - chloropropane

1,2-dichlorobenzene

1,2-dichloroethane

1,2-Dichloropropane

1,2,3 - Trichlorobenzene

1,2,3 - Trichloropropane

1,2,4 - Trichlorobenzene

1,2,4 - Trimethylbenzene

1,3 - Dichloropropane

1,3-Dichlorobenzene

1,3,5 -Trimethylbenzene

1,4-dichlorobenzene

2 - Chlorotoluene

2 - Hexanone (MBK)

2,2 - Dichloropropane

4 - Chlorotoluene

Acetone (2-Propanone)

Benzene

Bromobenzene

Bromodichloromethane

Bromoform

Bromomethane

Carbon Tetrachloride

Chlorobenzene

Chlorodibromomethane

Chloroethane

Chloroform

Chloromethane

cis-1,2-Dichloroethylene

cis-1,3-Dichloropropene

Dibromomethane

Dichlorodifluoromethane

Dichloromethane

Ethylbenzene

† "OSDWA" indicates the appendix is used for the analysis of Ontario drinking water samples, which is subject to the rules and related regulations under the Ontario "Safe Drinking Water Act" (2002).

The list of tests and measurement capabilities for which a laboratory is accredited can change at any time due to circumstances such as scope extensions, voluntary withdrawal of tests by the laboratory and suspension. Scopes are published by the CALA via the Internet at [http://www.cala.ca/cala\\_directories.html](http://www.cala.ca/cala_directories.html)

Ethylene Dibromide  
 Hexachlorobutadiene  
 Hexane  
 Isopropylbenzene  
 Isopropyltoluene  
 m/p-xylene  
 Methyl Ethyl Ketone  
 Methyl isobutyl Ketone  
 Methyl t-butyl ether  
 n - Butylbenzene  
 Naphthalene  
 o-xylene  
 Propylbenzene  
 sec - Butylbenzene  
 Styrene  
 tert - Butylbenzene  
 Tetrachloroethylene  
 Toluene  
 trans-1,2-Dichloroethylene  
 trans-1,3-Dichloropropene  
 Trichloroethylene  
 Trichlorofluoromethane  
 Vinyl Chloride

**Solids (Organic)**

Volatile Petroleum Hydrocarbons (VPH) - Soil (073)  
 C-GRO-01; modified from CCME CWS REF. METHOD & MOE E3398  
 GC/FID - PURGE AND TRAP  
 F1: C6-C10

**Water (Inorganic)**

Alkalinity - Water (088)  
 A-ALK-03; modified from APHA 2320 B  
 AUTO TITRIMETRIC  
 Alkalinity (pH 4.5)

OSDWA †

**Water (Inorganic)**

Ammonia - Water, Wastewater, Liquid Biosolids (055)  
 A-NH3-01; modified from MOEE RNDNP-E3364, SDNP-E3366  
 AUTO COLOR  
 Ammonia  
 Ammonia - Nitrogen

OSDWA †

**Water (Inorganic)**

Ammonia - Water, Wastewater, Liquid Biosolids (103)  
 A-NH3-01; modified from MOEE RNDNP-E3364, SDNP-E3366  
 COLORIMETRIC - DISCRETE  
 Ammonia

**Water (Inorganic)**

Anions - Water, Wastewater, Liquid Biosolids (002)  
 A-IC-01; modified from APHA 4110 C  
 ION CHROMATOGRAPHY  
 Bromide  
 Chloride  
 Fluoride  
 Nitrate  
 Nitrite

OSDWA †

† "OSDWA" indicates the appendix is used for the analysis of Ontario drinking water samples, which is subject to the rules and related regulations under the Ontario "Safe Drinking Water Act" (2002).

The list of tests and measurement capabilities for which a laboratory is accredited can change at any time due to circumstances such as scope extensions, voluntary withdrawal of tests by the laboratory and suspension. Scopes are published by the CALA via the Internet at [http://www.cala.ca/cala\\_directories.html](http://www.cala.ca/cala_directories.html)



Sulfate	
<b>Water (Inorganic)</b>	OSDWA †
Biochemical Oxygen Demand (BOD) - Water (008)	
C-BOD-01; modified from APHA 5210 B	
D.O. METER	
BOD (5 day)	
CBOD (5 day)	
<b>Water (Inorganic)</b>	OSDWA †
Carbon - Water (054)	
C-OC-01; modified from APHA 5310C, EPA 415.1	
IR-UV-PERSULFATE	
Organic Carbon	
<b>Water (Inorganic)</b>	OSDWA †
Chemical Oxygen Demand (COD) - Water (083)	
C-COD-01; modified from APHA 5220 D	
COLORIMETRIC	
COD	
<b>Water (Inorganic)</b>	OSDWA †
Colour - Water (027)	
A-COL-01; modified from APHA 2120 C	
SPECTROPHOTOMETRIC	
True Colour	
<b>Water (Inorganic)</b>	OSDWA †
Conductivity - Water (003)	
A-COND-01; modified from APHA 2510 B	
CONDUCTIVITY METER	
Conductivity (25°C)	
<b>Water (Inorganic)</b>	OSDWA †
Conductivity - Water (087)	
A-COND-02; modified from APHA 2510 B	
AUTO CONDUCTIVITY METER	
Conductivity (25°C)	
<b>Water (Inorganic)</b>	OSDWA †
Dissolved and Extractable Metals - Water (004)	
D-ICP-01; modified from APHA 3120 B	
ICP	
Aluminum	
Barium	
Beryllium	
Bismuth	
Boron	
Cadmium	
Calcium	
Chromium	
Cobalt	
Copper	
Iron	
Lead	
Lithium	
Magnesium	
Manganese	
Molybdenum	

† "OSDWA" indicates the appendix is used for the analysis of Ontario drinking water samples, which is subject to the rules and related regulations under the Ontario "Safe Drinking Water Act" (2002).

The list of tests and measurement capabilities for which a laboratory is accredited can change at any time due to circumstances such as scope extensions, voluntary withdrawal of tests by the laboratory and suspension. Scopes are published by the CALA via the Internet at [http://www.cala.ca/cala\\_directories.html](http://www.cala.ca/cala_directories.html)

Nickel  
Potassium  
Silicon  
Silver  
Sodium  
Strontium  
Tin  
Titanium  
Tungsten  
Vanadium  
Yttrium  
Zinc  
Zirconium

**Water (Inorganic)**

Dissolved Metals - Water (049)  
D-ICPMS-01; modified from EPA 200.8

OSDWA †

ICP/MS  
Antimony  
Arsenic  
Barium  
Beryllium  
Cadmium  
Chromium  
Cobalt  
Copper  
Lead  
Molybdenum  
Selenium  
Silver  
Thallium  
Uranium  
Vanadium

**Water (Inorganic)**

Hexavalent Chromium - Water (095)  
D-CRVI-01; modified from MOE - HEXCR-E3056  
COLORIMETRIC - MANUAL  
Chromium (VI)

**Water (Inorganic)**

Mercury - Water, Wastewater (025)  
D-HG-02; modified from APHA 3112 B  
COLD VAPOUR AA - DIGESTION  
Mercury

OSDWA †

**Water (Inorganic)**

Nitrate + Nitrite - Water (102)  
A-NO23-01; modified from SM 4500-NO3-F  
COLORIMETRIC - DISCRETE ANALYZER  
Nitrate plus Nitrite

**Water (Inorganic)**

Nitrite - Water (101)  
A-NO2-01; modified from SM 4500-NO2-B  
COLORIMETRIC - DISCRETE ANALYZER  
Nitrite

† "OSDWA" indicates the appendix is used for the analysis of Ontario drinking water samples, which is subject to the rules and related regulations under the Ontario "Safe Drinking Water Act" (2002).

The list of tests and measurement capabilities for which a laboratory is accredited can change at any time due to circumstances such as scope extensions, voluntary withdrawal of tests by the laboratory and suspension. Scopes are published by the CALA via the Internet at [http://www.cala.ca/cala\\_directories.html](http://www.cala.ca/cala_directories.html)

<b>Water (Inorganic)</b> Nitrogen - Water, Wastewater, Liquid Biosolids (033) A-TKN-01; modified from MOEE RTNP-E3367 AUTO COLOR - DIGESTION Total Kjeldahl Nitrogen	OSDWA †
<b>Water (Inorganic)</b> Orthophosphate - Water (104) A-PO4-01; modified from MOEE RNDNP-E3364, SDNP-E3366 COLORIMETRIC - DISCRETE Phosphate	
<b>Water (Inorganic)</b> pH - Water (005) A-pH-01; modified from APHA 4500 H pH METER pH	OSDWA †
<b>Water (Inorganic)</b> pH - Water (086) A-pH-02; modified from APHA 4500H+ B AUTO - pH METER pH	OSDWA †
<b>Water (Inorganic)</b> Phenols - Water (056) C-PHEN-01; modified from MOE ROPHEN-E3179 AUTO, 4-AAP Total Phenolics	OSDWA †
<b>Water (Inorganic)</b> Phosphate - Water (058) A-PO4-01; modified from MOEE RNDNP-E3364, SDNP-E3366 AUTO COLOR Phosphate	OSDWA †
<b>Water (Inorganic)</b> Total Metals - Water, Wastewater, Liquid Biosolids (067) D-ICP-01; modified from APHA 3120 B ICP/AES - DIGESTION Aluminum Antimony Arsenic Barium Beryllium Bismuth Boron Cadmium Calcium Chromium Cobalt Copper Iron Lead Lithium Magnesium Manganese Molybdenum	

† "OSDWA" indicates the appendix is used for the analysis of Ontario drinking water samples, which is subject to the rules and related regulations under the Ontario "Safe Drinking Water Act" (2002).

The list of tests and measurement capabilities for which a laboratory is accredited can change at any time due to circumstances such as scope extensions, voluntary withdrawal of tests by the laboratory and suspension. Scopes are published by the CALA via the Internet at [http://www.cala.ca/cala\\_directories.html](http://www.cala.ca/cala_directories.html)

Nickel  
Potassium  
Silver  
Sodium  
Strontium  
Tin  
Titanium  
Tungsten  
Vanadium  
Yttrium  
Zinc  
Zirconium

**Water (Inorganic)**

Total Metals - Water, Wastewater, Liquid Biosolids (071)

D-ICPMS-01; modified from EPA 6020

ICP/MS - DIGESTION

Antimony  
Arsenic  
Barium  
Beryllium  
Cadmium  
Chromium  
Cobalt  
Copper  
Lead  
Molybdenum  
Selenium  
Silver  
Vanadium

**Water (Inorganic)**

Total Phosphorus - Water, Wastewater, Liquid Biosolids (057)

A-TP-01; modified from MOEE RTNP-E3367

AUTO COLOR - DIGESTION

Total Phosphorus

OSDWA †

**Water (Inorganic)**

Total Suspended Solids (TSS) - Water (009)

A-TSS-01; modified from APHA 2540 D

GRAVIMETRIC

Total Suspended Solids

OSDWA †

**Water (Inorganic)**

Turbidity - Water (026)

A-TURB-01; modified from APHA 2130 B

NEPHELOMETRY

Turbidity

OSDWA †

**Water (Microbiology)**

Coliforms - Water (050)

B-ECTC-01; modified from MICROMFDC-E3407

MEMBRANE FILTRATION (DC)

Background Bacteria  
Escherichia coli (E. coli)  
Total Coliforms

OSDWA †

† "OSDWA" indicates the appendix is used for the analysis of Ontario drinking water samples, which is subject to the rules and related regulations under the Ontario "Safe Drinking Water Act" (2002).

The list of tests and measurement capabilities for which a laboratory is accredited can change at any time due to circumstances such as scope extensions, voluntary withdrawal of tests by the laboratory and suspension. Scopes are published by the CALA via the Internet at [http://www.cala.ca/cala\\_directories.html](http://www.cala.ca/cala_directories.html)

<b>Water (Microbiology)</b> Escherichia coli (E. coli) - Water (010) B-MFEC-01; modified from MFMICRO-E3371 MEMBRANE FILTRATION (EC) Escherichia coli (E. coli)	OSDWA †
<b>Water (Microbiology)</b> Fecal (Thermotolerant) Coliforms - Water (065) B-MFFC-01; modified from MFMICRO-E3371 MEMBRANE FILTRATION (mFC) Fecal (Thermotolerant) Coliforms	OSDWA †
<b>Water (Microbiology)</b> Heterotrophic Plate Count (HPC) - Water (021) B-HPC-01; modified from APHA 9215 C SPREAD PLATE Heterotrophic Plate Count (HPC)	OSDWA †
<b>Water (Microbiology)</b> Total Coliforms - Water (066) B-MFTC-01; modified from MFMICRO-E3371 MEMBRANE FILTRATION (mENDO) Background Counts Total Coliforms	OSDWA †
<b>Water (Organic)</b> Glycols - Water (085) C-GLYCOL-01; modified from EPA 8015 B DIRECT INJECTION GC-FID Diethylene Glycol Ethylene Glycol Propylene Glycol	OSDWA †
<b>Water (Organic)</b> Petroleum Hydrocarbons (PHC) - Water (072) C-GRO-01; modified from MOE E3421 GC/FID - PURGE AND TRAP F1: C6-C10	OSDWA †
<b>Water (Organic)</b> Petroleum Hydrocarbons (PHC) - Water (074) C-PHCW-02; modified from MOE E3421 GC/FID - EXTRACTION F2: C10-C16 F3: C16-C34 F4: C34-C50	OSDWA †
<b>Water (Organic)</b> Volatile Organic Compounds (VOC) - Water (041) C-VOC-01; modified from EPA 8260 and 5030 GC/MS - PURGE AND TRAP 1,1-Dichloroethane 1,1-dichloroethylene 1,1-Dichloropropene 1,1,1-Trichloroethane 1,1,1,2-Tetrachloroethane 1,1,2-Trichloroethane 1,1,2,2-Tetrachloroethane 1,2-Dibromo-3-chloropropane	OSDWA †

† "OSDWA" indicates the appendix is used for the analysis of Ontario drinking water samples, which is subject to the rules and related regulations under the Ontario "Safe Drinking Water Act" (2002).

The list of tests and measurement capabilities for which a laboratory is accredited can change at any time due to circumstances such as scope extensions, voluntary withdrawal of tests by the laboratory and suspension. Scopes are published by the CALA via the Internet at [http://www.cala.ca/cala\\_directories.html](http://www.cala.ca/cala_directories.html)

1,2-dichlorobenzene  
 1,2-dichloroethane  
 1,2-Dichloropropane  
 1,2,3-Trichlorobenzene  
 1,2,3-Trichloropropane  
 1,2,4-Trichlorobenzene  
 1,2,4-Trimethylbenzene  
 1,3-Dichlorobenzene  
 1,3-Dichloropropane  
 1,3,5-Trimethylbenzene  
 1,4-dichlorobenzene  
 2-Chlorotoluene  
 2-Hexanone (MBK)  
 2,2-Dichloropropane  
 4-Chlorotoluene  
 4-Isopropyl Toluene  
 Acetone (2-Propanone)  
 Benzene  
 Bromobenzene  
 Bromodichloromethane  
 Bromoform  
 Bromomethane  
 Carbon Tetrachloride  
 Chlorobenzene  
 Chlorodibromomethane  
 Chloroform  
 Chloromethane  
 cis-1,2-Dichloroethylene  
 cis-1,3-Dichloropropene  
 Dibromomethane  
 Dichlorodifluoromethane  
 Dichloromethane  
 Ethylbenzene  
 Ethylene Dibromide  
 Hexachlorobutadiene  
 Hexane  
 Isopropyl Benzene  
 m/p-xylene  
 Methyl Ethyl Ketone  
 Methyl isobutyl Ketone  
 Methyl t-butyl ether  
 n-Butylbenzene  
 n-Propylbenzene  
 Naphthalene  
 o-xylene  
 Sec-Butylbenzene  
 Styrene  
 tert-Butylbenzene  
 Tetrachloroethylene  
 Toluene  
 trans-1,2-Dichloroethylene  
 trans-1,3-Dichloropropene  
 Trichloroethylene

† "OSDWA" indicates the appendix is used for the analysis of Ontario drinking water samples, which is subject to the rules and related regulations under the Ontario "Safe Drinking Water Act" (2002).

The list of tests and measurement capabilities for which a laboratory is accredited can change at any time due to circumstances such as scope extensions, voluntary withdrawal of tests by the laboratory and suspension. Scopes are published by the CALA via the Internet at [http://www.cala.ca/cala\\_directories.html](http://www.cala.ca/cala_directories.html)

Trichlorofluoromethane  
Vinyl Chloride

† "OSDWA" indicates the appendix is used for the analysis of Ontario drinking water samples, which is subject to the rules and related regulations under the Ontario "Safe Drinking Water Act" (2002).

The list of tests and measurement capabilities for which a laboratory is accredited can change at any time due to circumstances such as scope extensions, voluntary withdrawal of tests by the laboratory and suspension. Scopes are published by the CALA via the Internet at [http://www.cala.ca/cala\\_directories.html](http://www.cala.ca/cala_directories.html)