



ᓄᓇᓕᓂ ᓄᓇᓄᓂᓂ ᓄᓇᓂᓂᓂᓂᓂ
Nunalingni Kavamatkunillu Pivikhaqautikkut
Department of Community Government Services
Ministère des Services communautaires et gouvernementaux

Richard Dwyer
Licensing Administrator
Nunavut Water Board
P.O. Box 119, Gjoa Haven,
NU X0B 1J0
Phone: (867) 360-6338, Ext. 26
Fax: (867) 360-6369
E-mail: licensing@nunavutwaterboard.org

December 09, 2009

Sub: O&M manual of the Municipality of Clyde River Truck Fill Station

Dear Mr. Dwyer,

I am sending the O&M manual of Clyde River Water Truckfill station electronically and also a hard copy total 145 pages including this cover letter as mentioned in your e-mail on December 8, 2009. This was prepared in 1998. I understand that the document was previously submitted by NWT to Water Board at that time. The facility has not been upgraded since then.

We trust that this will satisfy the requirements to renew the Water license for the Municipality of Clyde River for the period of five years. I will appreciate if you keep me in loop of the approval process.

Thanks.

Bhabesh Roy, M.A.Sc., P.Eng.
Municipal Planning Engineer
Community & Government Services
Baffin Region, Government of Nunavut
P.O.Box 379, Pond Inlet, X0A 0S0
Ph-867 899 7314
Fax-867 899 7328
E-mail: broy@gov.nu.ca

Copy to : Patricio Fuentes, Regional Projects Manager, GN-CGS, Baffin Region
Johnathan Palluq, Assistant Regional Director, GN-CGS, Baffin Region
Timoon Toonoo, Regional Director, GN-CGS, Baffin Region
Bill Buckle, SAO, Hamlet of Clyde River

P.O. Box 379, Government of Nunavut, Pond Inlet
☎ (867) 899-7301 📠 (867) 899-7330

Appendix-1.0

Introduction

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

OPERATIONS AND MAINTENANCE MANUAL

VOLUME 1 OF 2

Prepared for:

Government of Northwest Territories
Department of Public Works and Services
Bag 1000
Iqaluit, NT
X0A 0H0

Prepared by:

Dillon Consulting Limited
#201, 5102 - 51 Street
Yellowknife, NT.
X1A 1S7

Department of Public Works and Services Project No. 4-001-659
Dillon Project No. 96-3817

June 22, 1998



Appendix-2.0

Index

2.0 **TABLE OF CONTENTS**

	<u>Page No.</u>
1.0 INTRODUCTION	
1.1 Project Title	1.1
1.2 Revision Data	1.1
1.3 Changes After Commissioning	1.2
1.4 Project Representatives	1.2
3.0 DESIGN DATA	
3.1 Design Concept Brief	3.1
4.0 SCHEMATICS AND FUNCTIONAL DATA	
4.1 General	4.1
5.0 COMPONENT DATA	
5.1 General	5.1
6.0 OPERATING PROCEDURES	
6.1 General	6.1
6.2 Start-up Procedures	6.1
6.2.1 Start-up from Utility Power	6.1
6.3 Normal Operating Procedures	6.2
6.3.1 Truckfilling Procedure	6.2
6.3.2 Chlorination Process	6.4
6.3.3 Intake Screen Backwashing	6.11
6.3.4 Heat Trace System	6.11
6.3.5 Heating System	6.16
6.4 Special Procedures	6.17
6.4.1 Truckfill Pump Removal	6.17
6.5 Trouble Shooting Procedures	6.19
6.5.1 Alarm System	6.19
7.0 MAINTENANCE PROCEDURES	
7.1 General	7.1
7.2 Maintenance Logs	7.2
8.0 TESTING AND CERTIFICATION DATA	
8.1 General	8.1

...continued

2
5

TABLE OF CONTENTS (Cont'd)

	<u>Page No.</u>
9.0 MANUFACTURER'S DATA AND SERVICE INFORMATION	
9.1 Pipes, Pipe Support, Valves, Intake Screen, and Fittings	9.1
9.2 Pumps	9.1
9.3 Meters and Gauges	9.1
9.4 Water Treatment	9.1
9.5 Heating System	9.1
9.6 Electrical Panels and Associated Items	9.2
9.7 Uninterruptible Power System	9.2
9.8 Control Panel, Remote Control, and Associated Items	9.2
9.9 Alarm Items	9.2
9.10 Luminaires	9.2
9.11 Heat Trace System	9.3
9.12 Laboratory and Safety Equipment	9.3
9.13 Miscellaneous Items	9.3

LIST OF TABLES

	<u>Page No.</u>
Table 4.1 Water Treatment System	4.3
Table 4.2 Power Distribution System	4.6
Table 4.3 Controls and Alarms	4.8
Table 4.4 Heat Trace System	4.11
Table 5.1 Components, Manufactures, and Suppliers	5.2
Table 7.1 Maintenance Tasks by Equipment	7.4
Table 7.2 Maintenance Tasks by Schedule	7.1
Table 7.3 Spare Parts and Miscellaneous Equipment	7.10

LIST OF FIGURES

	<u>Page No.</u>
Figure 4.1 Water Treatment System	4.2
Figure 4.2 Power Distribution System	4.5
Figure 4.3 Controls and Alarms	4.7
Figure 4.4 Intake Casing, Intake Pipe and Cables	4.9
Figure 4.5 Heat Trace System	4.10

LIST OF DRAWINGS

<u>Drawing No.</u>	<u>Page No.</u>
101 COVER SHEET	A1
102 TRUCKFILL STATION SITE PLAN AND PROFILE	A2
103 STEEL SKID FOUNDATION AND STRUCTURAL DETAIL	A3
201 ARCHITECTURE ELEVATION	A4
202 TRUCKFILL STATION LAYOUT, WALL AND ROOF DETAILS	A5
301 PROCESS, MECHANICAL PLAN AND EQUIPMENT SCHEDULE ..	A6
401 MECHANICAL ELEVATION, ANCHOR AND DETAILS	A7
402 INTAKE DETAILS	A8
501 ELECTRICAL SINGLE LINE, PLAN, ELEVATION, AND DETAILS ...	A9
502 ELECTRICAL CONTROLS, WEST ELEVATION, AND PANELS ...	A10

Appendix-3.0

Background Design Data

3.0 DESIGN DATA

3.1 General

This section contains the predesign report entitled "Truckfill Stations - Arctic Bay & Clyde River, NWT Predesign Report" as originally published. The page numbering, figure numbers, table numbers, headers, footers, and appendices are independent of this manual's organization.

Truckfill Stations - Arctic Bay & Clyde River, NWT *Predesign Report*

November 19, 1996

Truckfill Stations

Arctic Bay & Clyde River, NWT

Government of the Northwest Territories
Department of Public Works & Services

96-3817-01-01

Submitted by

**Dillon Consulting
Limited**

December 18, 1996



Public Works and Services
Government of Northwest Territories
Project Management
P.O. Bag 1000
Iqaluit, NWT
XOA OHO

5102
51st Street,
Suite 201,
Yellowknife, N.T.,
Canada
X1A 1S7
Telephone
(403) 920-4555
Fax
(403) 873-3328

Attention: David Parker, P. Eng
Project Officer

Arctic Bay and Clyde River
Truck Fill Stations, NWT

Dear Mr. Parker;


Enclosed, please find three copies of the final version of the predesign report for the above project. As requested we have forwarded a copy of this report to the NWT and Nunavut Water Boards for their review and comment. This report has been revised to the comments we received from you recently.

The design of the truck fill stations is proceeding based on the information contained in the document. We anticipate the design will be completed early in the new year. We trust that you find this final report to your satisfaction.

Yours sincerely

Dillon Consulting Limited

Gary Strong, P.Eng.
Project Manager



cc:
GS:gs
96-3817/158/draft let

Dillon Consulting
Limited

13

TABLE OF CONTENTS

	<u>Page No.</u>
1.0 INTRODUCTION	1
2.0 SYSTEM DESIGN STANDARDS	3
2.1 Design Criteria	3
2.2 Design Standards	3
2.3 Design Parameters	4
2.4 Cost Analysis	5
3.0 WATER QUANTITY REQUIREMENTS	6
3.1 Water Quality and Water Treatment	9
3.1.1 Arctic Bay	9
3.1.2 Clyde River	11
3.1.3 Disinfection	11
4.0 TRUCKFILL STATION	16
4.1 Building Foundation	16
4.2 Truckfill Controls and Metering	16
4.3 Conveyance Piping	17
4.4 Power Supply	20
4.5 Freeze Protection	24
4.6 Monitoring and Alarms	25
4.7 Building Construction	26
4.8 Building Layout	27
4.9 Site Layout	30
4.10 Spares and Ancillary Components	35
5.0 SUMMARY AND IMPLEMENTATION	38

TABLE OF CONTENTS (Cont'd)

LIST OF FIGURES

	<u>Page No.</u>
Figure 3.1 - Population Projections, Arctic Bay	7
Figure 3.2 - Population Projections, Clyde River	8
Figure 3.3 - Arctic Bay Water Samples	10
Figure 3.4 - Clyde River Water Samples	12
Figure 4.1 - Truckfill Pump Selection - Arctic Bay	18
Figure 4.2 - Truckfill Pump Selection - Clyde River	19
Figure 4.3 - Process Schematic	21
Figure 4.4 - Clyde River Building Layout	28
Figure 4.5 - Arctic Bay Building Layout	29
Figure 4.6 - Clyde River Site Plan	31
Figure 4.7 - Clyde River Intake Profile	32
Figure 4.8 - Arctic Bay Site Plan	33
Figure 4.9 - Arctic Bay Intake Profile	34

APPENDICES

APPENDIX A - Geotechnical Report Arctic Bay

APPENDIX B - Geotechnical Report Clyde River

APPENDIX C - Cost Estimate Data

APPENDIX D - Sample Calculations

1.0 INTRODUCTION

General

The Government of the Northwest Territories (GNWT) identified the installation of truckfill stations in the communities of Arctic Bay and Clyde River as priorities in the 1997/98 fiscal period. The implementation of these initiatives was combined by the Department of Public Works and Services (PW&S) into one project. The facilities will have many similar components in the design and construction, and it was determined by PW&S that there will be economies in scale in the completion of these projects as one design assignment. In October of 1996, Dillon Consulting Limited was retained to complete the engineering services related to this assignment.

Background

Planning studies for the water supply systems in Arctic Bay and Clyde River were completed by Dillon in 1995. These planning studies identified the conceptual water supply system for each community. The water supply systems, as set out in the planning studies, and stated in the project terms of reference, are as follows:

"The new facility shall accommodate the following design characteristics:

It is assumed that power to the site will be provided by on site power generation, however the consultant is to investigate the construction of a power line to the site and provide a cost analysis for both alternatives.

Pumphouse / Truckfill Building

- *Truckfill pumps (1 duty, 1 standby).*
- *In-line chlorination through the truckfill line.*
- *Insulated and heat traced overhead truckfill arm, with water totalizer meter.*
- *Building heating and light.*
- *System controls / monitoring.*
- *Spares for the critical components subject to breakdown.*

- *One year supply of consumable (ie. chlorine)*
- *Adequate storage space for chlorine chemicals, space should be secure.*
- *On site power source for the station to be diesel motor / generator sets (1 duty) and are to be low RPM units.*
- *Heat trace (1 duty, 1 standby) c/w heat trace monitoring capability.*
- *Bench / cupboard for storage.*
- *Eyewash station.*
- *Exterior Fuel Tank.*
- *Interior day tank c/w (1 duty, 1 standby) fuel transfer pumps.*
- *Metal skid foundation for portability.*
- *Truckfill intake to be, single intake with screen and intake protection.*
- *Insulated and heat traced intake pipe at minimum length."*

Report Approach

This design concept brief will develop the planning concepts for the water supply system to a design level of detail. Where alternative approaches are possible, these will be discussed, and cost estimates developed. Recommendations for each of the component systems will be made. The report will deal with each of the community water supply systems individually. Where components can be maintained through both facilities to reduce costs, this will be identified.

2.0 SYSTEM DESIGN STANDARDS

2.1 Design Criteria

The design criteria for this project will be completed in accordance with the parameters set out by the GNWT, "Water and Sewage Facilities Capital Programs" and as modified by the terms of reference. These are as follows:

Facility	Design Horizon	Design Economic Life	Design Expected Life
Building	20	20	40
Pumps	10	20	20
Pipelines	20	20	30

Where the:

- Design horizon is the period used to establish capacity requirements for a facility.
- Design economic life is the period used in the economic analysis to establish the present value (or equivalent capital cost) of a facility.
- Design expected life is the practical maximum expected life of a facility assuming no premature failure, destruction or obsolescence.

2.2 Design Standards

The following is a list of the design standards to be used in the development of the water supply system. These are derived from the GNWT "General Terms of Reference for Water and Sanitation" (GTR), and the "National Building Code" (NBC), and "Capital Standards Criteria, September 1993," MACA.

Water Consumption Rates		Reference
Domestic	90 litres per capita per day	MACA
Commercial	$0.00023 \times \text{population}$	MACA
Total Consumption per Capita	$90 \times (1.0 + 0.00023 \times \text{pop.})$	MACA
Fire Demand	910 litres per minute for 60 minute duration	MACA & Fire Marshal
Discount Rates	4%, 8% and 12%	MACA

Environmental Conditions		
	Arctic Bay	Clyde River
Design Minimum Temp.	-43°C	-41°C
Degree Days (18°C)	11693	11006
Snow Load	1.9 kPa	3.2 kPa
SS	0.1 kPa	0.2 kPa
SR		
Wind Pressures	0.5 kPa	0.8 kPa

2.3 Design Parameters

The project terms of reference identified the following as design parameters for the facilities.

- *"Facilities must be simple to operate and maintain by local forces with limited equipment, and parts and materials which are available locally.*
- *Reliability of the facility is extremely important.*
- *The facility must be efficient and cost effective.*
- *The truckfill supply shall have a minimum pumping capacity of 1000 L/min.*
- *All equipment and pipes must be self draining after each use cycle, where practical. When self draining of any major component cannot practically be accommodated, some other means of frost protection should be incorporated.*
- *All major components must be capable of recovering from a frozen condition, in an operable state, if there is any possibility of freezing.*
- *Provisions of spares for all equipment is required, particularly components that have bulbs, fuses, relays, timers, etc.*
- *The first year supply of consumable, such as calcium hypochlorite, must be a requirement of the construction contract.*
- *Provision for standby power generation at the truckfill station is in accordance with GNWT's Municipal and Community Affairs Guidelines.*
- *The electrical drawings are to be provided to an industrial electrical standard and all drawings must have adequate detail to ensure that they are easily understood by*

local and northern contractors.

- *If the truckfill station is constructed at some location other than the site, the building is to be mounted on skids should relocation be required.*
- *Fuel storage at the truckfill station must provide for spill containment.*
- *Water supplied from the truckfill station must be metered.*
- *A copy of the design must be submitted to the NWT Water Board, for review.*
- *Provision for an alarm system which indicates loss of power and low building temperature, is required."*

2.4 Cost Analysis

Throughout this document, there are cost analysis of various options. The analysis have been carried out as outlined in the GTR as described below:

Capital Cost

Cost of construction for the facility

Annual Operation and Maintenance Costs

The cost of operation, which may include manpower, energy requirements, fuel, general maintenance (light bulbs, paint), and equipment replacement.

Life Cycle Costs

The calculation of the total facility cost over a 20-Year period. This includes the capital, operations and maintenance costs. The life cycle value is shown as a present value which is calculated at a discount rate of 4%, 8% and 12%.

3.0 WATER QUANTITY REQUIREMENTS

The water supply system for the communities is to meet the 20-Year demand. The program implementation schedule and fiscal budgets set out by the GNWT indicate that the construction of the facility will be completed in 1997 and therefore, Year 0 of the facility is 1997. In the planning study completed by Dillon, Year 0 was set at 1998. The water consumption data from the planning study has been brought forth into this document, and updated to reflect the change in the design horizon.


The following illustrates the historical population and water consumption data for the communities.

ARCTIC BAY		
Year	Population	Water Consumption (lcd)
1976	387	N/A
1978	414	34
1986	480	50
1994	592	73.9

CLYDE RIVER			
Year	Population	Growth Rate of Population	Water Consumption (lcd)
1974	350	4.6%	N/A
1979	439	4.5%	20.6
1981	443	1.2%	N/A
1986	471	3.7%	N/A
1989	500	2.0%	49.2
1991	565	2.4%	49.9
1993	592	1.5%	48.0
1994	601	1.5%	N/A


The Bureau of Statistics for the Northwest Territories provides population projections for all communities in the NWT with a population in excess of 100 people. **Figure 3.1** shows the population growth and annual water consumption for the community of Arctic Bay and **Figure 3.2** for Clyde River. Based on the values presented in this table, the 20-Year design population and consumption for Arctic Bay are 973 people and 39,100 m³ respectively, and for Clyde River are 1,076 people and 44,100 m³.

Design Year	Year	Population	Consumption		
			Litres per Capita	Daily (litres)	Annual (cubic metres)
0	1997	628	103.0	64,700	23,600
1	1998	637	103.2	65,700	24,000
2	1999	651	103.5	67,400	24,600
3	2000	666	103.8	69,100	25,200
4	2001	682	104.1	71,000	25,900
5	2002	698	104.4	72,900	26,600
6	2003	714	104.8	74,800	27,300
7	2004	730	105.1	76,700	28,000
8	2005	747	105.5	78,800	28,800
9	2006	763	105.8	80,700	29,500
10	2007	780	106.1	82,800	30,200
11	2008	797	106.5	84,900	31,000
12	2009	815	106.9	87,100	31,800
13	2010	833	107.2	89,300	32,600
14	2011	852	107.6	91,700	33,500
15	2012	871	108.0	94,100	34,300
16	2013	890	108.4	96,500	35,200
17	2014	910	108.8	99,000	36,100
18	2015	931	109.3	101,800	37,200
19	2016	952	109.7	104,400	38,100
20	2017	973	110.1	107,100	39,100



**Figure 3.1 Population Projections, Arctic Bay
Predesign Report, Arctic Bay & Clyde River Truck Fill Station, NWT**

Design Year	Year	Population	Consumption		
			Litres per Capita	Daily (litres)	Annual (cubic metres)
0	1997	655	103.6	67,900	24,800
1	1998	672	103.9	69,800	25,500
2	1999	688	104.2	71,700	26,200
3	2000	706	104.6	73,800	26,900
4	2001	723	105.0	75,900	27,700
5	2002	742	105.4	78,200	28,500
6	2003	760	105.7	80,300	29,300
7	2004	779	106.1	82,700	30,200
8	2005	799	106.5	85,100	31,100
9	2006	819	107.0	87,600	32,000
10	2007	840	107.4	90,200	32,900
11	2008	861	107.8	92,800	33,900
12	2009	882	108.3	95,500	34,900
13	2010	905	108.7	98,400	35,900
14	2011	927	109.2	101,200	36,900
15	2012	951	109.7	104,300	38,100
16	2013	975	110.2	107,400	39,200
17	2014	999	110.7	110,600	40,400
18	2015	1,024	111.2	113,900	41,600
19	2016	1,050	111.7	117,300	42,800
20	2017	1,076	112.3	120,800	44,100



**Figure 3.2 Population Projections, Clyde River
Predesign Report, Arctic Bay & Clyde River Truck Fill Station, NWT**

3.1 Water Quality and Water Treatment

3.1.1 Arctic Bay

The long term water supply for Arctic Bay has been identified as Marcil Lake. The community has indicated that they accept this water source, and that they find the water aesthetically acceptable.

Water quality testing has been completed on this water source by various parties, including Dillon during the previous planning assignment. **Figure 3.3** summarizes the water sample data completed on Marcil Lake in previous studies.

Parameters tested were selected to provide indicators of the water quality of the raw water source. The test results indicate that there is not a particular area of concern with the water source. The water quality meets the requirements of the Guidelines for Canadian Drinking Water Quality (1996) (GCDWQ) for all parameters except turbidity. The guidelines require an average level of turbidity below the level of 1.0 NTU (Nephelometric Turbidity Units). However, the guidelines allow the average level of turbidity to be less than 5.0 NTU if it can be shown that disinfection is not affected by the higher level of turbidity.

The water data indicates that turbidity ranged from 1 to 15 NTU with an average of 6.2 over the test samples. The historic use of the water source by the community with no reported problems of water related disease attributed to the raw water source, suggests that the presence of the slightly elevated levels of turbidity do not affect the disinfection of the water. The number of data sets available is limited, and the data doesn't provide a clear understanding of the temporal water characteristics.

In discussions with MACA it was decided that the truckfill station is to be designed to allow for the addition of filtration to remove the turbidity in the future. This addition will be made if the operation of the facility and the results of the sampling program indicate that the turbidity levels are problematic.

Monitoring of the raw water source should be done as part of the operation of the facility. The parameters to be tested for should include the major ions and turbidity. Monthly testing should be completed of the raw water supply to develop a more extensive data base to allow for future treatment assessment. Parameters to be tested for are to include; balance, bicarbonate, chloride, carbonate, conductance, fluoride, hardness, calcium, iron, potassium, magnesium, manganese, sodium, sulphate, nitrate, nitrite, pH, total alkalinity, TDS, and turbidity.

3.1.2 Clyde River

Historic water sampling has been completed on the selected water source from 1983 to date. **Figure 3.4** illustrates the sample collection and analysis completed. The 1994 samples were collected from various depths. The results of the samples indicated that the water is of good quality with no major areas of concern.

Turbidity levels are slightly elevated, the average is 3.0 NTU, which is within the guidelines.

Two samples indicate that the pH is below the aesthetic guidelines. The community has not raised concerns with the taste of the water, however, should continued sampling indicate that the water is consistently below the guideline, remedial treatment is to be considered. Treatment would consist of the addition of Soda Ash (NaCO_3) to the water. This can be completed automatically or manually. Due to fluctuations in the pH, monthly testing of the water for pH, and pH control manually is recommended. A supply of Soda Ash, and a hach pH Kit will be included in the design. The design of the facility will not address this issue.

There has been concerns expressed by MACA and/or the community with respect to late spring water quality. In other communities, water quality deteriorates over the winter due to a decrease in the level of dissolved oxygen. Sampling to date indicates that this will not be a concern at Clyde River. However, if in future a concern is raised, the small lake can be aerated using a compressor and a hose to convey air to the intake screen. This system is in place elsewhere in the NWT (Rankin Inlet). No provision in the design of the facility is required to address this future installation.

3.1.3 Disinfection

The GCDWQ require that the disinfection process for raw water also have a residual disinfection component. This is achieved through the use of chlorination. A typical residual chlorination level is 1 part per million (ppm). Many communities in the NWT find the taste of chlorine unpleasing, and residual levels are often set at 0.5 ppm. Several chemicals are available for disinfection of domestic water supplies. These include:

- Gaseous Chlorine
- Sodium hypochlorite (liquid)
- Calcium hypochlorite (solid)

Date Sampled :		Aug 26/83	Mar 13/84	Oct 24/84	Sept 10/85	Dec 1/87	Aug 18/82	July 26/84					GCDWQ GUIDELINES		Aesthetic Objectives (Max. Conc.)	
Sample Depth (m):		0	0	0	0	0	0	2.0	4.0	6.0	8.0	10.0	12.0	Maximum Acceptable Concentrations	Interim Maximum Acceptable Concentrations	
PARAMETER		NOTES														
Ammonia		0.0010	0.0010					0.0250	0.0090	0.0030	0.0030	0.0110	0.0005	0.05	0.025	
Arsenic		<0.05	0.0013				<0.0002						0.0003	0.005		
Cadmium		<0.10	0.50	0.20	1.20	1.70	<1.0	0.67	0.62	0.62	0.59	0.62	0.62			
Calcium		2.00	4.50	3.80	3.20	4.10	3.90	2.42	2.34	2.30	2.29	2.31	2.28			250
Chloride		0.0080	0.0045				0.0030							0.05		
Chromium		<5.0	<5.0	10.0	15.0	10.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0			15
Color (TCU)	2	18.0	36.0	29.0	28.9	46.1	22.5	23.2	22.5	22.3	22.2	22.6	22.3			
Conductivity (µmho/cm)							0.003									
Copper		0.0555	0.0400	0.2300	0.2300	0.0200	0.0055									1.0
Iron			0.0057				<0.001							0.01		0.3
Lead		0.53	0.80	0.60	0.20	0.80	0.60	0.50	0.50	0.50	0.50	0.50	0.60			
Magnesium				0.006	0.005	<0.01										0.05
Manganese		0.00010	0.00006					0.00022	0.00002			0.00030		0.001		
Nickel			0.001				0.001									
Ortho Phosphate	3	6.50	6.60	6.90	7.43	6.90	6.76	<0.002	0.002	0.002	0.002	0.002	0.002			
pH (unitless)		0.35	0.70	0.70	0.60	0.60	0.50	0.61	0.41	0.41	0.41	0.42	0.42			6.5-8.5
Potassium		1.80	3.60	2.70	3.60	2.70	2.50	2.13	1.90	1.92	1.89	1.91	1.90			200
Silica		<1.0	1.5	2.0	2.0	<1.0	<2.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0			500
Sulphate		<5	<5				<3	<3	<3	<3	<3	<3	<3			
Suspended Solids		3.1	5.8	8.2	8.4	7.5	4.0	3.1	3.1	3.1	3.0	3.1	3.0			
Total Alkalinity	4	2.36	4.50	3.00	3.80	4.20	5.00	17.0	<10.0	13.0	10.0	10.0	11.0			500
Total Dissolved Solids								3.70	3.60	3.60	3.50	3.60	4.00	500.00		100
Total Hardness								<0.008	<0.008							
Total Kjeldahl N	5		0.050		0.050		<0.04	<0.008	<0.008	0.011	0.011	0.038	0.012	45.0		
Total Nitrates	6		0.005	0.003	0.003	<0.05	<0.05			0.011	0.011	0.038	0.012	3.2		
Total Nitrites	3							<0.002	0.008	0.007	0.005	0.010	0.008			
Total Phosphorus		1.6	0.6	8.0	8.5	8.5	1.0	2.3	2.3	2.3	2.3	2.3	2.3	1		5
Turbidity (NTU)		0.0440	0.0052				0.0010									
Zinc																

Notes

All Results are expressed in mg/L, unless indicated in brackets ().

Blank cells indicate that the sample was not tested for that parameter.

Shaded cells indicate that the sample exceeds the GCDWQ guidelines for the indicated parameter.

1. Sample was too acidic for alkalinity titration.

2. TCU - True Color Units

3. Ortho Phosphate, and Total Phosphorus are stated in terms of mg/L of P (phosphorus)

4. Total Hardness, and Total Alkalinity are stated in terms of mg/L of CaCO₃ (calcium carbonate)

5. Total Kjeldahl N is stated in terms of mg/L of N (Nitrogen)

6. Equivalent to 10.0 mg/L nitrate as nitrogen, where nitrate and nitrite are determined separately. Levels of nitrite should not exceed 3.2 mg/L

7. NTU - Neophelometric Turbidity Units

**Figure 3.4 Clyde River Water Samples
Arctic Bay & Clyde River Truck Fill Stations, NWT**

Public Works and Services
Dillon Consulting Limited

Gaseous chlorine requires storage in a separate room that is monitored for chlorine gas emissions. Safety equipment and training is necessary to comply with the Occupational Health and Safety Regulations when chlorine gas is used. The transport of gaseous chlorine is regulated by the Transportation of Dangerous Goods (TDG) and it cannot be transported by passenger airplane. For these reasons, the use of gaseous chlorine is not recommended for small facilities such as the Arctic Bay or Clyde River Truckfill Stations.

Sodium hypochlorite is shipped and stored as a liquid. The liquid is subject to freezing, and is to be stored in a heated room (above -10°C). Sodium hypochlorite used in water treatment is similar to house hold bleach. It is available at 12% available chlorine, whereas bleach is 6% available chlorine. Sodium hypochlorite loses its concentration with time. After 90 days the level of available chlorine drops slowly and may reach a level similar to bleach after 6 months. If the 12% available sodium hypochlorite is diluted to 2% available, the shelf life is significantly extended. The operation of the disinfection system using sodium hypochlorite is relatively simple. The liquid is used directly without mixing. An injection pump is used to inject the liquid into the water as it flows through the truckfill arm.

Calcium hypochlorite is shipped and stored as a powder. There is no concern with freeze protection, and heated storage is not required. Calcium hypochlorite has 65% available chlorine by weight. The powder is mixed with water to make a solution that can be used in the disinfection process. Typically the solution is mixed at a concentration similar to that of sodium hypochlorite (2% available chlorine is typical). The disinfection system for calcium hypochlorite requires a mixing tank, a solution tank, and an injection pump.

Both calcium and sodium hypochlorite are commonly used for disinfection in small facilities. The use of calcium hypochlorite is more common in the NWT. The issues to be addressed in the selection of a disinfectant are; the cost of the optional system; the relative ease of use; and the risk of failure.

Cost of System

Sodium hypochlorite, as a liquid, requires a greater volume of disinfectant to be shipped to site than calcium hypochlorite. Based on 12% available chlorine for sodium hypochlorite and 65% available for calcium hypochlorite the required shipping weight of disinfectant and volume to be shipped to site are as follows:

Disinfectant	Year 0 (1997)	Year 20 (2018)
Calcium Hypochlorite	37 Kg	60 Kg
Sodium Hypochlorite	200 L (200 Kg)	325 L (325 Kg)

The supply and transportation costs associated with each chemicals.

Disinfectant	Supply (Year 0)	Transportation (Year 0)	Life Cycle
Calcium Hypochlorite	\$270	\$20	\$2,850
Sodium Hypochlorite	\$160	\$77	\$2,350

The above is based on using the sealift for all transportation.

Operation

The mechanical and control systems for either disinfectant is similar. The difference is that calcium hypochlorite requires a mixing and solution tank. Typically these are 30 to 60 litre tanks each. They require a floor area of 1.5 m² for the tanks. The mixing tank is elevated to allow it to gravity feed into the solution tank. The sodium hypochlorite does not require any additional tanks as it is transported in its own 22 litre container. The tanks and additional space required for the calcium hypochlorite system increases the capital cost of the facility.

The mixing process requires approximately 1 hour of operation time every 2 weeks for the calcium system. Less than 10 minutes per month will be required for the sodium system.

Risk of Failure

As the two systems are mechanically and electrically the same, the risk of failure for these systems are also similar. There is an additional risk associated with the sodium hypochlorite when there is a power failure. The liquid could freeze during an extended power loss. With the calcium system, the mixed disinfectant will also freeze, however, the remaining powdered calcium hypochlorite will not be damaged.

Summary

The use of sodium hypochlorite is operatively more simplistic and user friendly. The difference in supply and transportation costs for these chemicals is negligible. The sodium hypochlorite has a risk of freezing in the event of a power outage. Should this occur, standard household bleach from the local Northern Store can be used as a substitute until additional sodium hypochlorite is flown in. To assess the risk, it is assumed that each year 50% of the sodium hypochlorite is flown to site.

Item	Sodium Hypochlorite	Calcium Hypochlorite
Supply Cost (Year 1)	\$ 77.00	\$ 170.00
Transportation Cost (Year 1)	\$ 421.00 * 400	\$ 7.00
Operations Time (Year 1)	\$ 40.00	\$ 520.00
Total Annual Cost (Year 1)	\$ 1,015.00	\$ 1,140.00
Capital Cost	\$ 800.00	\$ 920.00
Life Cycle Cost	\$ 12,000.00	\$ 16,000.00

The above analysis indicates that sodium hypochlorite is the more economical system for disinfection. The detailed cost calculation is Appended.

* The transportation cost for sodium hypochlorite in this annalysis is based on 50% of the required volume being transported by air to the community.

The Department of Municipal and Community Affairs selected the use of the calcium hypochlorite for disinfection in these facilities.

4.0 TRUCKFILL STATION

The truckfill station will have the following major components:

1. Building Foundation
2. Truckfill controls and metering
3. Conveyance Pipes
4. Power Supply
5. Freeze Protection
6. Monitoring and Alarms
7. Building Construction
8. Building Layout
9. Site Access
10. Spares and Ancillary Components

The following section will describe these components for each facility.

4.1 Building Foundation

The geotechnical reports completed by Agra Earth and Environmental for the facility locations are included in the appendix. Recommendations for the foundation from these reports are for steel skid mounted building and a granular pad foundation. The granular pads are to be a minimum of 1.0 m in depth.

4.2 Truckfill Controls and Metering

The truckfill control has been established in accordance with the Government of the Northwest Territories standard for similar facilities in other small communities. The truckfill control system will have the following components:

- Truckfill control with one customer key lock. This will have an individual flow accumulator to record cumulative flows. The control will be on the truckfill arm, with a start/stop and resume button. The fill volume for each fill cycle will be variable, however, it will be pre-selected from within the building.
- Building flow totalizer to indicate total volume of water delivered by the truckfill station.
- Flow rate indicator.
- Flow sensor installed in the truckfill pipe to control individual and building flow

accumulations.

- Control device for chlorine feed pump.
- Flow switch to interlock with the pump and chlorine pump to avoid damage to the equipment or excessive chlorine injection into an empty line.
- All measurements for the metering are to be in SI units (litres).

The accumulators, flow indicator, and miscellaneous control devices will be located in a main control panel inside the pumphouse. All flow sensor equipment will be by Signet.

4.3 Conveyance Piping

The process piping is required to deliver 1,000 l/min of treated water to the truckfill discharge point. The pump curves for this system have been developed and are shown in **Figure 4.1 and 4.2**. The flow requirements can be met with a 7.5 h.p. pump and a minimum 100 mm discharge line. This is based on the available prime power supply 120 VAC single phase power. The pump will require an inclined shaft casing of 300 mm.

The process piping will consist of the following:

- Off-take pumps and 100 mm HDPE piping DR17, contained within a 300 mm HDPE DR17, insulated with 50 mm of rigid foam and heat traced, incline shaft conduit. The in-take piping will enter the truckfill station and terminate with a flange connection just inside the truckfill station wall.
- The in-take pipe line will be weighted using pre cost concrete weights.
- The in-take will have large diameter (300 to 1,000 mm) riprap installed over the pipeline to protect against mechanical ice damage.
- Galvanized 100 mm Schedule 40 steel piping with Victaulic system connections from the intake to the truckfill discharge point.
- Chlorine injection diffuser, located on the galvanized steel piping within the building.
- Pipeline drain line, that drains the line into the outer casing of the off-take line, after each fill cycle.




Figure 4.1 Truck Fill Pump Selection- Arctic Bay
Predesign Report, Arctic Bay and Clyde River Truck Fill Stations, N.W.T.
 Public Works and Services
 Dillon Consulting limited

32




Figure 4.1 Truck Fill Pump Selection- Clyde River
Predesign Report, Arctic Bay and Clyde River Truck Fill Stations, N.W.T.
 Public Works and Services
 Dillon Consulting limited

- Flow switch to activate the chlorine pump.
- Flow sensor for the truckfill control system.

A schematic of the process piping is shown in **Figure 4.3**.

4.4 Power Supply

Prime Power

Prime power can be obtained from either:


- Northwest Territories Power Corporation's power plant, or
- An on-site electric generator.

Typically, the use of grid power generated by the Power Corporation is the source of prime power. However, the new facilities are not directly adjacent to the community, and a new power line is required to service the truckfill station. Based on estimates received from the Power Corporation, the cost to install the new lines will be approximately:

Clyde River	700 m	=	\$ 95,000
Arctic Bay	9000 m	=	\$ 900,000

The installation of on-site power generation will require:

- A building or space within the truckfill building to house the generator.
- A generator sized to meet the power requirements of the truckfill station.
- Controls, monitoring and alarms for the power supply system.



 DILLON CONSULTING	PROJECT ARCTIC BAY AND CLYDE RIVER TRUCKFILL STATIONS, NWT	PROJECT NUMBER 96-3817
	PROCESS PROCESS SCHEMATIC	REV. OF SCHEMATIC 4.3

35

The estimated steady-state power requirements of the truckfill station are:

	Power (kW)
• Truckfill Pump	6.0
• Building Heat	0.5
• Heat Trace	1.0
• Lighting	1.0
• Chemical Feed Pumps	0.1
TOTAL	9 kW

This results in a minimal generation requirement of 9 kW. Start-up power for the truckfill pump is not included, but will be approximately 2 kW more for total of 11 kW.

The on-site generator is assumed to run continuously for the 20-Year design horizon. The estimated daily power requirements are 36 kW/h in winter. The capital and life cycle costs of these options are as follows:

Prime Power System	Capital Cost	Operation Cost	Annual Maintenance Cost	Life Cycle Cost		
				4%	8%	12%
Arctic Bay						
Power Line	900,000	2,700	0	937,000	925,000	920,000
On-site Generator	150,000	30,000	6,000	640,000	510,000	420,000
Clyde River						
Power Line	95,000	2,700	0	133,000	122,000	116,000
On-site Generator	150,000	30,000	6,000	640,000	510,000	420,000

The use of an on-site generator at Arctic Bay is significantly more economical and, therefore, recommended over the use of a power line. The generator system will consist of:

- A 9 kW generator and diesel engine.
- Fuel storage for 30 days of operation (calculated to be 792 l, and a 1,120 l tank will be used which will supply 42 days of fuel supply).
- Fuel supply and return line.
- Engine and room ventilation and cooling

The use of a power line is significantly more economical at Clyde River and is, therefore, recommended for prime power.

Standby Power

Clyde River

Two methods of standby power for Clyde River are possible:

- Standby diesel electric generator
- Uninterruptible power supply (UPS) by battery bank.

The requirements for standby power is to supply emergency power for fire fighting protection during a power outage. The fire protection requirements are 60 minutes of water supply at 910 l/min. Based on the pump power consumption, a UPS must supply 6 kW/hr of stored power at a peak load of 8 kW.

A UPS can be supplied to meet this requirement. A Best Ferups EBP9F - 2.5 KVA has been identified for this analysis. The UPS system requires a space of 0.7 m² in the pumphouse. No maintenance is required for this system.

The standby diesel would be similar to the system required by a prime power generator. This system would require:

- A 3.0 m x 4.0 m addition to the pumphouse,
- Switch gear, monitoring and controls,
- Ventilation, duct work and cooling system,
- Fuel storage, fuel storage containment and fuel oil piping,
- UPS supply for initial start-up.

Monthly and annual maintenance is required to ensure the diesel will operate properly when it is required.

A cost analysis of the two options is as follows:

Standby Power System	Capital Cost	Operation	Annual Maintenance Cost	Life Cycle Cost		
				4%	8%	12%
Diesel Electric Power	150,000	2,000	6,000	250,000	230,000	210,000
UPS	30,000	1,000	0	44,000	49,000	38,000

The use of a UPS system for Clyde River is significantly more economical and is recommended for this facility.

4.5 Freeze Protection

To protect the water supply system from failure due to freezing, three freeze protection systems are required:

1. Truckfill building heating.
2. In- take casing freeze protection.
3. Truckfill arm.

Truckfill Building

Heating load calculations for the truckfill building are based upon 38 mm x 140 mm wood frame wall construction, vapour barrier, air barrier, and sheathing, with climatic factors of 8,101 degree C days and -45°C January design temperature. Based on these factors, a 4 m x 4 m x 3 m high truckfill building will require 3.2 kW of heat for peak load and an annual requirement of 9,400 kWh. The costs of electricity and diesel fuel for the GNWT in the communities are \$0.70/kWh and \$0.68/l respectively. The table below shows the estimated costs of heating systems using electric heat or a diesel furnace. For comparison, a heating value of 10 kWh/l was used for diesel.

Freeze Protection System	Capital Cost	Annual Power/Fuel Cost	Annual Maintenance Cost	Life Cycle Cost		
				4%	8%	12%
Diesel Furnace or Unit Heater	3,000	300	5,000	75,000	55,000	42,000
Electric Unit Heater	1,500	3,100	0	46,000	32,000	25,000

The life cycle cost for electric heat is lower than for a diesel furnace. Also, electric heating is much more convenient and the maintenance is minimal. Additionally, electric heating will not require fuel to be stored at the truckfill building, greatly reducing the risk of fire. We recommend the use of an electric unit heater.

In-take Casing and In-take Pipe

The in-take casing and in-take pipe must be protected from freezing. This will be accomplished by electric heat trace cable installed in conduit, located outside the in-take pipe. The cable will be 15 W/m self-limiting, heat trace cable, chosen with the assistance of the manufacturer, such that it will not damage the HDPE pipe. Two lengths of cable will be installed. The second cable will also provide backup in case of failure of the first cable. Automatic controls will be used. The cable will be removable.

Truckfill Arm

A method must be used to protect the truckfill pipe from freezing and to recover the pipe if it freezes. Various methods have been used in past designs, including insulation and heat trace cable. A key to successfully avoiding freezing of the truckfill pipe is to ensure that it drains quickly and completely after use. The truckfill pipe will be installed with a 5% or greater slope back into the pumphouse, and an automatic draining mechanism at the intake. The pipe will be bare steel and not insulated or heat traced. Freezing of the pipe is unlikely, due to the draining system. In the unlikely event that the pipe freezes, a propane tiger torch will be supplied to thaw the pipe.

4.6 Monitoring and Alarms

The truckfill building will have the following monitoring and control system. The system will have two (2) levels of alarms: major and minor. Major alarms will cause an alarm light, and will cause a horn to sound at the pumphouse. Major alarms will activate an auto dialler system that will call the facility operator. At Clyde River this will use the main UPS System, and a land line to the normal phone system. At Arctic Bay the UPS will be included in the auto dialler system, and a remote transmitter system will be used. Minor alarms will only

sound an internal horn and flash a light. The alarms for this system are set as follows:

- Major
 - High building temperature alarm
 - UPS failure with power on (Clyde River)
 - Power Off/UPS at less than 1 hour storage (Clyde River)
 - Power off/Generator failure (Arctic Bay)
 - Low fuel level 2 (Arctic Bay)
- Minor
 - Truckfill pump failure
 - Power Off/UPS On
 - Building temperature low
 - Low fuel level 1 (Arctic Bay)

4.7 Building Construction

There are two types of building construction available for this facility, namely:

- Wood frame, on-site construction.
- Pre-engineered, prefabricated construction, that is built off-site.

The wood frame building would be constructed to the standard for truckfill stations used by the Government of the Northwest Territories Standard as follows:

- Wall construction consisting of 38 mm x 150 mm with 150 mm of fibreglass batt insulation.
- Walls with vapour barrier on the inside and air barrier on the outside of the wall studs.
- Walls with plywood sheathing on the outside face and 50 mm of rigid foam insulation.
- The interior of the walls sheathed with dry wall, plywood, and clad with metal siding. (The interior plywood is for convenient equipment installation.)
- Roofing provided by a pre-manufactured truss, or rafter system.

The pre-manufactured building would be constructed to provide the equivalent insulation value as the wood frame building. Several companies produce these structures (Baily, Brytex, Butler), and each have a slightly different building design. Typically these buildings have an insulation value of R-32.

The use of on-site construction will typically add \$40,000 to \$50,000 to the total facility cost. The increase in cost is a result of the required accommodations, flights and additional man hours on-site for down time. The local involvement created by on-site construction will be approximately 10 man days, or the equivalent of \$2,000 in wages the economic benefit to the community is not justified and off-site construction is recommended.

On previous projects, the GNWT has had success with pre-manufactured buildings (Cold Stream). This building type will be used in the final design.

4.8 Building Layout


A summary of the requirements for the special allowance for the building is shown below:

- In-take piping and truckfill discharge piping, including allowance for intake pump removal.
- Chlorination system with chlorine pump and injection point.
- Work bench for water testing.
- Control panels, electrical panels.
- UPS System. (Clyde River only)
- Truckfill control box.
- Seasonal fill line through pumphouse.
- Storage of chemicals and spare parts.
- Diesel electric generator, and fuel supply system. (Arctic Bay only)

Future expansion for, and special allocation are to be made for:

- Fluoridation equipment and storage of chemical.
- Filtration equipment. (Arctic Bay only)

Figure 4.4 and 4.5 shows the building layouts providing for the above in each facility.



30/21 96 BASE NAME: 3817
 10/11 95 L. THEO. 3817

FILE

1-411



ARCTIC BAY AND CLYDE RIVER
 TRUCKFILL STATIONS, NWT

DILLON
 CONSULTING

96-3817

4.4

OCT 96

42

RELIEF AIR DUCT AND
CONTROL DAMPER

GENERATOR EXHAUST

DIESEL SUPPLY FROM
MAIN TANK

VENT FROM DAY TANK

MAKE UP AIR HOOD
AND DUCT

300 HDPE DR17 OFFTAKE

HOSE HANGAR

CHLORINE FEED PUMP

CHLORINE MIX TANK

CHLORINE FEED
TANK

CHLORINE FEED
TUBE INJECTOR


EYE WASH
STATION

STORAGE CABINET

INFRA RED
HEATER

FLOW SENSOR

WORK BENCHES



SCALE 1:50

ARCTIC BAY AND CLYDE RIVER
TRUCKFILL STATIONS, NWT

ARCTIC BAY
BUILDING LAYOUT

96-3817

NOV 96

4.5



DILLON
CONSULTING

43


4.9 Site Layout

The access road can be constructed from available granular soil materials. The roadway and granular pad will consist of:

- 8.0 m wide travelling surface to meet Municipal & Community Affairs standard.
- 1,000 mm depth of granular sub base compacted in place.
- 100 mm of granular base.
- Ditching along both sides of the road to remove run-off water, and culverts.


The site and road drainage is important to remove snow melt and run-off water away from the water source area. The truck pad is designed to allow the trucks to turn around without backing up. The granular pads will be well compacted to prevent erosion.

Figure 4.6 through 4.9 show the site layout for the Clyde River and Arctic Bay truckfill facilities.



 DILLON CONSULTING	ARCTIC BAY AND CLYDE RIVER TRUCKFILL STATIONS, NWT	OCT 96	96-3817
	CLYDE RIVER SITE PLAN	1:1000	4.6

107
45




Time (min)	$10^3 \Delta T / \text{K}$	$10^3 \Delta T / \text{K}$	$10^3 \Delta T / \text{K}$
0	0	0	0
10	1.5	1.5	1.5
20	3.0	3.0	3.0
30	4.5	4.5	4.5
40	6.0	6.0	6.0
50	7.5	7.5	7.5
60	9.0	9.0	9.0
70	10.5	10.5	10.5
80	12.0	12.0	12.0
90	13.5	13.5	13.5
100	15.0	15.0	15.0

DILLON
CONSULTING

4.7


OCT 96



 DILLON CONSULTING	ARCTIC BAY AND CLYDE RIVER TRUCKFILL STATIONS, NWT	NOV 96	96-3817
	ARCTIC BAY SITE PLAN	1:1000	4.8 <i>109</i>

NEW INTAKE
PIPE
WATER SURFACE
(JULY 94)
EXISTING PROFILE

NEW PUMPHOUSE
NEW BERM
TO FACILITATE
DESIGN GRADE



SCALE 1500

FILE NAME: 13-02-96 0451 DATE: 3/96
PROJECT: 13-02-96 0451 3817/ABR 604 DWE



DILLON
CONSULTING

48

DATE

ARCTIC BAY AND CLYDE RIVER
TRUCKFILL STATIONS, NWT

PROJECT

ARCTIC BAY
INTAKE PROFILE

PROJECT NUMBER

96-3817

PROJECT TITLE

4.9

DATE

NOV 96

4.10 Spares and Ancillary Components

The following is a list of spares, replacement parts, and ancillary components that will be included.

Spare Components	Parts
In-take Pump	• 1 complete submersible pump complete with power cable.
Calcium Hypochlorite Feed System	• 3 replacement part kits for chemical pump. • 1 chlorine flow switch. • 1 chemical feed pump. • Nylon tubing.
Eyewash	• 1 spare container of solution.
Lighting - exterior	• 2 spare lamps each type.
Distribution Panel	• 2 breakers of each size and type.
Terminal Blocks	• 1 set of blocks for each size and type installed including end caps, end plates, cross connectors and tear-off markers.
Fuses	• Unless noted elsewhere, 12 spares for each type required in facility.
Motor Starters	• 6 of each type of pilot light and over load heaters. • 1 of each type of coil and contact.
Control Devices	• 1 of each type of push button pilot light and lens. • 1 spare rotational water flow paddle wheel. • 1 spare flow display/totalizer. • 1 spare flow switch.
Alarm Panel	• 1 alarm annunciator.
6 of each Fuses or Mini-breaker	• 2 of each relay and timer. • 1 of each relay and timer base.
Generator (Arctic Bay Only)	• Fuel filters (12) • Oil filters (12) • Oil 30 @ 4L • Belts • Air filters (18)
K Valves	• 1 spare of each type of valve.
Thermostats	• 1 spare of each type of thermostat.
Heat Trace	• Spare controller • Spare thermostat
Miscellaneous	• Damper motors • Fan motors • Timers

Miscellaneous Equipment

1. Fire Extinguisher: One (1) Ansul A20E, Class ABC, UL listed, 9 kg capacity, external nitrogen cartridge Foray powder with wall mounting brackets. Mount on wall near exterior door.

2. Dustmasks: Fisher 11-875-54 disposable masks supply three(3) packs of 50 masks each.
3. Face Shield: One (1) Fisher 11-409-5, optically clear 1.5 mm polycarbonate shield with adjustable head band.
4. Gloves: Twelve(12) Fisher 11-394-30, large, extra long, heavyweight rubber gloves, 19 mm by 380 mm length.
5. Apron: One (1) Fisher 01-357 double coated abrasion resistant, rubberized cloth apron.
6. Fush Broom: One (1) Dustbane 403089, 600 mm wide, horse hair and synthetic bristle broom with handle.
7. Mop: One (1) Dustbane 481127, Syntex Flat size #20 with handle.
8. Mop Bucket and Wringer: One (1) Dustbane No. 2024X, 27 L, round, with Cam Squeezer Wringer.
9. Dust Pan: One (1) Dustbane No. 8 Hooded 300 mm.
10. Garbage Can: One (1) 100 L, galvanized, with cover.
11. Floor Cleaner: Dustbane No. 501379 Liquid cleaner, one (1) 20 L container.
12. Lighting: Two (2) fluorescent tubes and One (1) low temperature ballasts.
13. Storage Cabinet:
 - 1 Combination shelving/wardrobe unit.
 - 2 Two (2) doors.
 - 3 Four (4) half shelves.
 - 4 Pre-finished in grey.
 - 5 Standard of Acceptance: Par Equipment Ltd. Model No. 4273

14. Work Benches: (Supply one (1), 1200 mm x 760 mm x 825 mm high, heavy duty construction steel table, no shelves.
15. Cabinet Table: 610 mm x 610 mm x 860 mm high, 50 mm lip on three sides of top, locking cabinet door.
16. Stepstool: 400 mm diameter, treaded top, expanded step, one piece construction, anti-skid bottom with retractable castes.
17. Hand Winch: 1500 lbs. hand winch, 5,1:1 gear ratio.
18. Hach Kit Dr 100 c/w 1 year supply of consumables (100 pillows)
19. Hach pH Kit (Clyde River) c/w 1 year supply of consumables.

5.0 SUMMARY AND IMPLEMENTATION

Arctic Bay

The truckfill facility at Arctic Bay will consist of:

- A skid mounted building constructed on a 1.0 m thick well compacted granular pad.
- An intake pipeline constructed of a 300 mm HDPE casing pipe with 50 mm of insulation and protected with riprap.
- A intake screen, 6 kw pump, and 100 mm conveyance piping.
- Prime power will be by on site 11 kw diesel electric generator. On site fuel storage will be a 1,100 l tank mounted on the building skids.
- Freeze protection of the intakes will be by 2 self-limiting heat trace cables.
- The building will be constructed off site and be a cold stream building. Electric unit heaters will provide freeze protection.
- Disinfection will be by injection of calcium hypochlorite.
- The truckfill control will be from the truckfill arm, with one customer key.
- The alarm in the system will consist of:
 - Major
 - High building temperature
 - Generator failure
 - Low fuel level 2
 - Minor
 - Truckfill pump failure
 - Building low temperature
 - Low fuel level 1

Major alarms will be annunciated on site, and to the plant operator by auto dialler.

The estimated cost of construction for this facility is \$550,000.00 GST and engineering not included. This estimate is based on the actual cost of construction for Lake Harbour, which is of similar construction.

The project is to go to tender in January 1997, with construction completed by November 1997.

Clyde River

The truckfill facility at Clyde River will consist of:

- A skid mounted building constructed on a 1.0 m thick well compacted granular pad.
- An intake pipeline constructed of a 300 mm HDPE casing pipe with 50 mm of insulation and protected with riprap.
- A intake screen, 6 kw pump, and 100 mm conveyance piping.
- Prime power will be by Grid power from NWTPC.
- Standby power will be by UPS system.
- Freeze protection of the intakes will be by 2 self-limiting heat trace cables.
- The building will be constructed off site and be of wood construction. Electric unit heaters will provide freeze protection.
- Disinfection will be by injection of calcium hypochlorite. Soda Ash will be supplied for possible pH control.
- The truckfill control will be from the truckfill arm, with one customer key.
- The alarm in the system will consist of
 - Major
 - High building temperature alarms
 - UPS failure with power on power off / UPS with less than 1 hour
 - Minor
 - Truckfill pump failure
 - Building low temperature
 - Power off / UPS on

Major alarms will be annunciated on site, and to the plant operator by auto dialler.

The estimated cost of construction for this facility is \$380,000.00 GST and engineering not included. The power line to the facility is estimated to cost \$95,000. This estimate is based on the annual cost of construction for Trout Lake, which is of similar construction. The estimate has been adjusted to the community location. The project is to go to tender in January 1997, with construction completed by November 1997.

APPENDIX B

GEOTECHNICAL REPORT CLYDE RIVER

December 21, 1994

File No. YX00388

M. M. Dillon Limited
201-5102 51 Street
Yellowknife, N.W.T.
X1A 1S7

Attention: Mr. Gary Strong, P.Eng.
Manager

Dear Sir:

Re: Report on Geotechnical Conditions
Water Supply Improvements, Clyde River, N.W.T.
MMD Reference 94-2214, MMD-GNWT Ref. SC320524

This letter summarizes the results of a geotechnical investigation undertaken by AGRA Earth & Environmental Limited (AGRA E&E) at the site of the proposed Water Supply Improvements and Truckfill Station in Clyde River, N.W.T.

1.0 TERMS OF REFERENCE

The Terms of Reference for the investigation, as outlined in AGRA E&E's proposal to M. M. Dillon of June 7, 1994 were to include:

- review available geotechnical information and examine aerial photographs;
- conduct a field investigation consisting of test pits (with locally contracted equipment) in order to identify the soil and bedrock conditions at the proposed truckfill sites and turn around areas;
- provide recommendations for the design and construction of the foundation for the pumphouse/truckfill station, water intake line, and armour rock/rip rap, and any site improvements, if required; and,

- provide comments as to the availability of suitable granular sources in the community.

2.0 PROJECT BACKGROUND

The hamlet of Clyde River receives its potable water from a lake which is approximately 1.6 kilometres northwest of the community. The lake has been chosen to fulfill the potable water supply needs of the community for the next 20 years. As such, a single, all-weather truckfill/pumphouse facility is required.

The truckfill station is understood to comprise the following:

- a pumphouse building of wooden construction with dimensions that are approximately 3.5m x 7.5m; it will be heated to +10°C;
- 300mm nominal diameter HDPE intake pipe will extend from the pumphouse to a depth in the order of 2 metres (design ice thickness); and,
- the intake line will be equipped with a heat trace line to reduce the potential for freezing; it will also be covered with 50mm of rigid foam insulation.

3.0 FIELD INVESTIGATION

The field investigation was conducted under the direct supervision of Mr. James Anklewich, P.Eng., of AGRA E&E's Yellowknife Office. Mr. Gary Strong, P.Eng., of M. M. Dillon's (MMD) Yellowknife Office was also present during the field investigation. The field program, which was conducted on July 26, 1994, included a visual reconnaissance of the site, excavation of test pits in the vicinity of the proposed pumphouse/truckfill station, and inspections of potential granular borrow sources.

The field program also included assisting MMD during the topographic and bathometric surveys, the results of which are reported by M. M. Dillon separately.

3.0 SITE CONDITIONS

3.1 WINTER FILL LOCATION

3.1.1 Site Description

The winter fill site, which is situated furthest to the west, is accessed from the Arctic Bay-Nanisivik Road by an all-weather, narrow road over a distance of about 600 metres. Based on visual observations, the road was constructed by dozing local gravel materials from the slopes of an adjacent ridge on to the native tundra terrain which prevails along the lake shore at the winter fill location. The thickness of the road embankment was estimated to be in the order of 1 to 1.5 metres. The surface of the road is rutted extensively suggesting that the granular materials were not compacted during construction and that possible soft, unfrozen native soils exist beneath the fill.

In the winter time, the trucks must travel beyond the end of this road on the frozen tundra and ice for a distance of approximately 45 metres to the fill point on Marcil Lake. When thawing conditions exist, truck access to the fill point over the tundra and ice is not possible.

At the time of the field reconnaissance, the water level in the lake appeared to be raised (from winter levels) such that the truck fill location and the possible area for the proposed pumphouse was flooded. The ground surface of the possible pumphouse location is about 2 metres below the top of the access road. The adjacent tundra terrain above the water level in the lake was observed to be soft and spongy.

As noted above, the winter fill site and the access road lie adjacent to an elevated ridge, the height of which is in excess of 25 metres above the level of the road. The slopes of the ridge are inclined at about 2H:1V and are underlain by coarse gravel beneath a thin cover of lichen and moss. On some slopes, the organic cover was stripped. The materials comprising the ridge are likely similar to that observed on an exposed portion of the ridge near the end of the existing access road (sand and gravel).

A substantial quantity of cobble and boulder sized rocks, some as large as 600mm diameter, have accumulated along a stretch of the shoreline in the vicinity of the proposed water intake line at the winter truckfill site. These rocks were piled along the lake shoreline to a height of 1 to 1.5 metres above the water level in the lake on that date (July 21/94). It is conceivable that the rocks piled against the shoreline were deposited by ice movements resulting from wave action and frost processes.

3.1.2 Subsurface Conditions

A single test pit was excavated near the end of the access road using a front end loader contracted from Enokseot Holdings of Arctic Bay. The soils observed at the test pit location generally consisted of a nominal 300mm thick cover of sandy, gravel fill underlain by a sand with a high silt content and scattered gravel sizes up to 150mm. Based on the relative ease of excavation by a loader, the gravel fill is considered to be loose. Organic soil inclusions were observed in the upper portions of the native soil. The native brown sand was observed to be saturated and in a loose state. Due to the fines content, the sand displayed a low plasticity.

Movement of the front end loader on the tundra immediately beyond the access road was difficult as it soon became bogged down in the saturated organic and sandy soils. Manoeuvring became increasingly difficult as the excavation proceeded, indicating that the native sand is somewhat sensitive to disturbance.

Groundwater seepage into the excavation was noted. After a period of several minutes, approximately 150mm of water was recorded. Frozen ground was encountered at a depth of 1 metre; however, the depth to frozen ground may be deeper in the immediate vicinity of the lake shoreline. The excavation was terminated at this depth and immediately backfilled.

3.2 SUMMER FILL LOCATION

3.2.1 Site Description

The summer fill location is located approximately 1 km east along the lake shore from the winter fill location. It is located some 150 metres away from the main road and is accessed by a sloping all-weather road. A turn-around pad is available for the trucks at the fill location. The existing summer fill location is not used during the winter due to the greater distance.

Drainage down the access road is poorly defined with the surface runoff flowing over the road in a random fashion. Several runoff gulleys have been created near the shoulders of the road.

Marcil Creek provides drainage of the uplands to the north and drains into Marcil Lake in the immediately vicinity of the fill location. Within approximately 100 to 150 metres upstream from the point of discharge at the lake shore, the river is braided with numerous wide and shallow channels. The soils in the vicinity of the point of discharge at the lake shore are generally rounded, gravel and cobble sizes with an abundance of particles exceeding 200mm to 300mm (boulders) in average diameter. The ground surface in this area is strewn with many such cobbles and boulders. Similar sizes of granular materials were noted in the water in the immediate vicinity of the shoreline.

At the time of the field reconnaissance (July 21/94), a considerable number of ice blocks were shoved on to the shoreline from the lake. At one location, which was situated approximately 30 metres southwest of the proposed fill location, the ice was pushed some 3 to 5 metres on to the shore. These blocks of ice were not observed the previous day, suggesting that the lake ice is relatively mobile during the breakup season.

3.2.2 Subsurface Conditions

Two test pits were excavated in the immediate vicinity of the proposed pumphouse location and turn-around pad. The soils encountered at these two test pit locations comprise a sandy gravel with a trace to little silt (less than 20 percent passing 0.075mm/#200 sieve screen). Cobble-sized materials (greater than 100mm diameter) were frequently noted in the test pits. The soils were moist to wet near the surface, but became saturated at a depth of approximately 500mm. Excavating beyond this depth was difficult as caving conditions prevailed in response to the groundwater seepage. Frozen ground was observed at a depth of 1 metre; however, the depth to frozen ground may be deeper in the immediate vicinity of the lake shoreline. The excavations were terminated at this depth and the test pits were immediately backfilled.

4.0 GRANULAR RESOURCES

Observations from the field reconnaissance indicate that suitable granular resources can be obtained at locations in the near vicinity of each proposed truck fill sites. Utilization of these natural gravelly materials would likely require that the boulders and cobbles be removed prior to transport and placement.

It is understood that a crusher operation was producing aggregate for the community in recent years at a location situated on a ridge to the northeast of the winter fill location. A sieve analysis on a sample indicates that the source is a reasonably well graded gravelly sand (25mm minus) with approximately 8 percent fines. Based on this result, the material would be suitable for the construction of the foundation pads for the truckfill/pumphouse.

5.0 RECOMMENDATIONS

5.1 PUMPHOUSE FOUNDATION

Based on the typical configurations at other truckfill sites, it is envisaged that the pumphouse for the truckfill station will consist of an insulated building of wood construction that is mounted on skids and supported on a compacted granular pad. Such a foundation is considered to be feasible for both of the proposed truckfill sites. It is not likely that other foundation types, such as piles (adfreeze or bedrock grouted) or spread footings would be necessary or economical.

It is conceivable that the new pumphouse building would be located in the immediate vicinity of the existing truckfill at the summer location and in the vicinity of the shoreline at the winter location. However, the actual location of the pumphouse at the selected site should be established with shoreline engineering input. The pumphouse must be positioned at locations where the safety of the structure would not be jeopardized by shoved ice blocks.

For both sites, the granular pad should be placed directly on the existing surface underlain by permafrost ground. The granular pad should be a minimum of 1 metre thick such that the annual depth of thaw is maintained within the granular pad and not in the native soils. At the winter location, the pad should be 1 to 1.5 metres thick and placed directly on the existing organic mat.

Backfill for pad construction should be a well graded gravel that is free of organics and compressible material. Ideally, the backfill should contain less than 5% fines (particles passing the 0.075mm/#200 screen) to reduce the potential for frost heave. The maximum particle size is dependent on the compactive equipment available for construction; however, in the absence of a specified value, a maximum size of 75mm is recommended.

At the existing truckfill location and approach pad at the summer location, which has been in use for several years, the surficial soils at this location are expected to be moderately

dense due to the daily truck traffic. Although the test pits did not encounter any "soft" spots or weak zones, such zones may still exist elsewhere in the near vicinity.

The gravel fill should be placed in lifts not exceeding 200 mm in loose thickness and should be compacted to at least 95% of standard Proctor maximum dry density (ASTM D698). The compacted fill pad should be placed a minimum of 2 metres beyond the perimeter of the building. To facilitate the recommended compaction of the gravel fill in the pad construction, a geotextile should be placed on the existing surface. The geotextile would act as a separator and minimize the potential of displacement of the gravel into the soft subgrade. The initial lift of gravel fill may be increased to 300mm, and spread over the geotextile with light tracked equipment.

The allowable soil bearing of a well compacted pad may be taken as 150 kPa. Long term settlement of the fill structure, if constructed according to the above guidelines, may be expected to be in the order of 2% of the fill thickness. Monitoring of the construction of the granular pad would verify that good construction procedures are implemented and reduce the potential for differential settlement.

5.2 WATER INTAKE LINE AND EROSION PROTECTION

The potential ice forces and ice shove at the intake have been analyzed using the following data:

- a design wind speed of 85 kph. This is equivalent to the maximum hourly wind speed observed at Resolute Bay in July, when the breakup occurs. At Resolute, the maximum observed wind speeds in summer are consistently from the east, but the same value was assumed for the southeast exposure at the site.
- a fetch of 1 km from the southeast
- a beach slope of 1V:44H, based on the bathymetry data obtained during the site reconnaissance.

The 85 kph wind over the 1 km wide ice sheet would generate a force of 1.5 kN/m of shoreline. Assuming an ice thickness of 0.6

metres, such a force would push the ice almost 13 metres up the beach. Thicker ice may not be pushed as far. The ice shove could be greater than 13 m at exposed structures or points of land. If the pumphouse is located at A1 (bathymetry profile, as shown on Figure 1.3 attached), the site does not project into the lake and is in fact sheltered slightly by the adjacent shoreline. At this location, a setback of 13 metres is considered to be adequate to protect the pumphouse against ice shove.

If a location closer to the shoreline is desired, or for additional protection against ice forces, the pumphouse could be located northeast of A1 to take advantage of the shelter provided by the protruding shoreline between A1 and A2. Moving the site northeast would require a review of the bathymetry to verify that the mouth of the intake would have enough submergence to function under the assumed 2 metre ice thickness.

For the winter fill location, this 13 metre setback would be conservative, as the prevailing wind direction is from the east. A setback distance in the order of 10 to 13 metres is considered appropriate for the winter location.

To protect the intake pipeline against ice damage, it may be covered by a riprap berm. Details of the berm design are shown on the appended Figures 1, and 2. The riprap size is based on ice damage experienced at other site. The riprap should be angular in shape, and have an average diameter (D_{50}) of 400mm. It should consist of rock sizes from 200mm to 600mm diameter.

Although the riprap will provide a good degree of protection, it can not be considered to be immune to damage. Some maintenance is likely to be necessary because the berm protrudes from the shore and is therefore subject to much higher forces than the rest of the shoreline.

An alternative solution is to bury the pipeline for all or part of its length as shown on the appended Figure 3. Option 1, complete burial requires no riprap at all. In this case, the ice forces are not concentrated at the pipeline, but are spread out along the beach. Complete burial is preferable from the point of view of mitigating the effects of ice forces, but may have other

drawbacks related to disturbing the permafrost by trenching. Therefore, a second option, partial burial, is also presented. In this case, the above-ground portion of the pipeline is protected by a riprap berm. The berm does not extend into the lake and as such, it is easier to construct and requires much less riprap than the complete riprap protection.

This assessment was limited strictly to the assessment of ice shove. Other hydrotechnical issues which should be addressed are:

- the potential range of water levels which could occur on the lake and the impact of extremely high or low levels on the intake;
- wave effects on the shoreline and the design of wave erosion protection; and,
- design of the water intake.

AGRA Earth & Environmental would be pleased to address any of these issues and provide a hydrotechnical review of the proposed pumphouse and water intake on request.

5.3 SLOPE STABILITY

As stated in Section 2.2.1 above, the large ridge located at the winter fill location rises to an elevation in excess of 25 metres higher than the surrounding area with a slope angle that is locally as steep as 2H:1V. At this angle, the slope is stable with factors of safety against failure in the range of 1.4 to 1.5 or greater.

Any construction activities that would adversely affect the stability of the slope should be avoided. Examples of these activities would include, but are not limited to, the following:

- excavation or cuts near the toe of the slope;
- scraping the surficial materials from the slope, thereby creating a deeper zone of thaw; and,


a toe berm and serve to provide restraint against any potential slope movements. Additionally, a suitable geotextile (filter fabric) could be placed between the existing soils on the slope and the overlying rip rap so that the potential for migration and washing of the soils from wave action is reduced.

6.0 CLOSURE

We trust the foregoing is sufficient for your present purposes. Should any questions arise, please contact the undersigned at your convenience.

Yours truly,

AGRA Earth and Environmental Limited



James L. Anklewich
Manager, Yellowknife Office

Reviewed by:


Marv J. Cherniawski, P.Eng. (Alberta)
Senior Project Engineer

YX00388.REP


APPENDIX A



SCALE 1:10000



GRAPHIC SCALE
(IN METRES)



DILLON
Consulting Engineers - Planners
Environmental Scientists

PROJECT

PLANNING STUDY

PROJECT NUMBER

94-2214-01

TITLE

CLYDE RIVER TRUCKFILL STATION


FIGURE NUMBER

1.2


DATE

AUG 94

129
67



SCALE 1:1000



 Bilcon Consulting Engineers, Planners Environmental Scientists	PROJECT PLANNING STUDY ARCTIC BAY TRUCKFILL STUDY	PROJECT NUMBER 94-2213-01
DATE OCT 94	TITLE SUMMER FILL LOCATION SITE	FIGURE NUMBER 1.3

130
68





FIGURE 1
RIPRAP PROTECTION

File _____ Subject _____ Page _____ of _____
Prepared _____ Date _____ Checked _____ Date _____

RIPRAP - MAX SIZE 600 mm
MIN SIZE 200 mm



SECTION A-A
1:20

FIGURE 2

RIPRAP BERM DETAIL

132
70

File _____ Subject _____ Page _____ of _____
Prepared _____ Date _____ Checked _____ Date _____

PUMPHOUSE




FIGURE 3
BURIAL OPTIONS

133
71

Option	Pros	Cons	Recommendations
Winter Intake Site	- If a road can be built to the high ground to the south (the ancient alluvial fan of the Marcil Creek), then the problems of the soft low-lying ground at the existing site can be overcome. - Water quality (suspended solids) may be at acceptable levels as there are no major streams entering the lake in the vicinity.	- The site is exposed to west and northwest winds, and resultant wave action and ice movement. The effects of waves and ice action are evident in the rocks and boulders piled up on the shoreline immediately south of the present winter water intake site. - The low-lying ground at the existing site is soft, and may be prone to inundation. - Soft and low-lying ground conditions exist at the site, necessitating the importation of fill. (The winter site cannot be accessed in the summer, hence the summer fill site.)	Not the preferred site from a hydrotechnical standpoint. Geotechnical considerations dealing with the pump house and access road foundations would need to be overcome. Significant fill would need to be added to bring the pump house and road above the high water level of the lake. The site is prone to more significant wave and ice action than the summer site.
Summer Intake Site	Generally firmer ground conditions appear to be available at this site, due primarily to the coarse bed material transported and deposited by Marcil Creek.	The site is close to the mouth of Marcil Creek, which may result in water quality problems at the intake during peak runoff periods.	Recommended as the better site from a hydrotechnical standpoint, provided that water quality is acceptable. Of the local sites proposed, site A1 is preferred because of the separation from the mouth of Marcil Creek and the short distance to adequate depths.

134
72

Option	Pros	Cons	Recommendations
	The site surveys indicate that adequate depths for the intake can be provided offshore.	The input of coarse sediment from Marcil Creek may build up a delta which could affect the water intake, especially at site A2.	
	The exposure of the site to wind and wave action appears to be less than for the winter site, because there is not the same accumulation of boulders along the shoreline. (the presence of the wind driven ice pile-up along the shoreline during the July 1994 site visit appears to have been a minor event, because the ice was well-candled and easily broken up, and therefore posed no significant danger to the shoreline or any structure.		
	The site is only a short distance off the main all-weather road between Arctic Bay and Nanisivik.		

January 16, 1995

File No. YX00387

M. M. Dillon Limited
201-5102 51 Street
Yellowknife, N.W.T.
X1A 1S7

Attention: Mr. Gar Strong, P.Eng.
Manager

Dear Sir:

Re: Report on Geotechnical Conditions
Water Supply Improvements
Arctic Bay, N.W.T.

This letter summarizes the results of a geotechnical investigation undertaken by AGRA Earth & Environmental Limited at two alternate sites for the proposed Water Supply Improvements and Truckfill Station in Arctic Bay, N.W.T.

1.0 TERMS OF REFERENCE

The Terms of Reference for the investigation, as outlined in the GNWT's Request for Proposal, and AGRA E&E's proposal of June 7, 1994 were to include:

- review available geotechnical information and examine aerial photographs;
- conduct a field investigation limited to test pits (with locally contracted equipment) in order to identify the soil and bedrock conditions at the proposed truckfill sites and turn-around areas;
- provide recommendations for the design and construction of the foundation for the pumphouse/truckfill station, water intake line, and armour rock/rip-rap; and,
- provide comments as to the availability of suitable granular materials in the community.

2.0 FIELD INVESTIGATION

The field investigation was conducted under the supervision of Mr. James Anklewich, P.Eng., of AGRA Earth and Environmental's Yellowknife Office. Mr. Gary Strong, P.Eng., of M. M. Dillon's (MMD) Yellowknife Office was also present during the field investigation. The field program included a visual reconnaissance of the sites, excavating test pits in the vicinity of the proposed pumphouse/truckfill station, and inspection of potential granular borrow sources.

Asistance was provided by AGRA Earth and Environmental to MMD in conducting the topographic and bathometric surveys, the results of which are reported by M. M. Dillon separately.

The following sections summarize the geotechnical observations.

2.1 BACKGROUND

The hamlet of Arctic Bay receives its potable water from Marcil Lake, which is some 9 kilometres from the community toward Nanisivik. Two sites on Marcil Lake presently are being used for the water supply. The selection of sites is dependent on the season (that is, winter versus summer) as access to the relatively closer winter location is not available during the warmer periods of the year. The relative locations of the two sites, and the major topographic features of the general area are shown on Figure 1.1 attached to this letter-report.

As it is desired to have a single, all-season truckfill/water supply station, the objective of the present study was to provide an assessment of the geotechnical conditions at the respective sites. It is anticipated that the results of this assessment and the geotechnical recommendations contained herein would assist in the selection of a permanent facility. However, non-geotechnical considerations may govern the site selection.

4.0 SITE CONDITIONS

4.1 PHYSICAL FEATURES

The subject lake is located in a natural depression with an elevation difference between lake level and the surrounding ridges being in the order of 7 to 10 metres. A second lake, which is located some 100 metres to the east, is approximately 6 metres higher in elevation and as such, drains into the subject lake. Based on the results of the topographic survey (reported by M. M. Dillon), the total area of the water shed affecting the subject lake is in the order of 50 hectares.

At the time of the field reconnaissance, the subject lake was clear of ice; however, the second lake still had a considerable amount of ice on the surface. A multibead thermoprobe was lowered into the water of the subject lake during the bathometric survey in order to establish the water temperature and confirm the presence of a thermocline. The thermoprobe data showed that the water was at a temperature of approximately +5°C (+/- 0.5°C) over the entire depth.

A nominal 3 metre wide and 75 metre long access road lies adjacent to portions of the south and east sides of the lake. The alignment of the road at this location is in an approximately north-south direction. At the approach to the lake, the top of the road is about 5.5 metres above the lake and gently slopes down to the location of the proposed new truckfill location, where the road surface is approximately 1 metre above the lake. The west bank of this access road (adjacent to the lake) has a slope angle of approximately 2.5H:1V. Although the bank appeared to be relatively stable at present, small cracks were observed in the road surface and were oriented parallel to the alignment of the road at a location where the top of the road is about 3 to 4 metres above the lake level. These cracks are indicative of movements of the active layer beneath the slope toward the water's edge (shoreline). These slope instabilities are likely attributed to saturated conditions of the active layer during prolonged rainfall whereby the unfrozen soil moves downwards over top of the frozen soil towards the shoreline.

At the most easterly edge of the lake, a 400mm diameter CMP culvert provides (outflow) drainage from the lake to the lower elevations to the east. Both inverts of the culvert, particularly the eastern invert, were noted to be damaged as a result of repeated vehicle traffic since minimal soil cover was observed on the culvert crowns. At the time of the site reconnaissance, the flow rate through the culvert was such that little to no sediment was being transported; however, several erosion scours were observed within 50 metres of the downstream invert of the culvert. These scours suggest that relatively high flow rates have occurred in the past, perhaps during peak runoff at spring thaw, or during prolonged rainfall.

4.2 SUBSURFACE CONDITIONS

A total of three test pits were excavated in the vicinity of the access road and truckfill location using a rubber-tired loader provided by the Hamlet of Clyde River. The test pits locations are shown on the attached Site Plan. The test pits were advanced to a depth of approximately 1 metre below existing grade whereupon frozen ground was encountered. Seepage from the active layer immediately above the permafrost table was observed in all of the test pits. The test pits were terminated at this depth and backfilled immediately.

The soils encountered at the test pit locations generally consisted of a fine to coarse grained, loose, brown sand overlying a brown, frozen silt. Thin beds of low plastic, brown silt were noted within the sand as well. Based on our experience elsewhere in the community, the deposit of silt observed at the 1 metre depth is expected to be ice rich and potentially unstable if allowed to thaw.

5.0 GRANULAR RESOURCES

AGRA Earth & Environmental previously reported on the availability of suitable granular materials in the community of Clyde River. The information was summarized in our June 11, 1993 letter to M. M. Dillon Ltd.

Based on a review of recent aerial photographs and available geotechnical data, several potential borrow deposits in the community were identified. All of the potential borrow sources identified, which are located in the vicinity of the existing airstrip, were reported to be poorly graded gravelly sands with a variable fines content (material passing 0.075mm/#200 sieve screen). This information is summarized in a letter to M. M. Dillon Ltd., dated June 11, 1993.

Sieve analyses were conducted on samples of granular materials, which were obtained by MMD field personnel and delivered to our Yellowknife laboratory. The results of these tests confirm that the samples are poorly graded, gravelly sands with a fines content varying from 10 percent to 22 percent. These results were reported in a letter dated July 26, 1993. The June 11, 1993 and July 26, 1993 letters are appended.

Other potential granular borrow sources exist in the immediate vicinity of the proposed truckfill station; however, the quantity remaining in these sources is not confirmed, nor has the quality of the material been identified. Moreover, it is uncertain whether the hamlet prefers to use the sources located near the airstrip or those located near the truckfill station. Regardless of which granular borrow source is chosen, samples of the materials should be shipped to our laboratories prior to construction in order to determine the specific construction criteria (standard Proctor density, grain size distribution).

6.0 RECOMMENDATIONS

6.1 PUMPHOUSE FOUNDATION

Based on AGRA E&E's past experience, it is envisaged that the pumphouse for the truckfill station will consist of an insulated building of wood construction that is mounted on skids and supported on a compacted granular pad. Such a foundation is considered to be feasible for the present truckfill site. It is not likely that other foundation types, such as piles (adfreeze or bedrock grouted) or spread footings would be necessary or economical.

It is likely that the new pumphouse building would be located in the immediate vicinity of the existing truckfill location. In such a case, the granular pad should be placed directly on the existing surface. The granular pad should be a minimum of 1 metre thick such that the summer depth of thaw is maintained within the granular pad and not the native soils.

Backfill for pad construction should be a well graded gravel that is free of organics and compressible material. Ideally, the backfill should contain less than 5% fines (particles passing the 0.075mm/#200 screen) to reduce the potential for frost heave. The maximum particle size is dependent on the compactive equipment available for construction; however, in the absence of a specified value, a maximum size of 75mm is recommended.

As the existing truckfill location and approach pad have been in use for several years, the surficial soils at this location are expected to be relatively dense due to the daily vehicular traffic; however, there may still exist localized "soft" spots, or zones of weaker material. As such, preparation of the existing surface should include proof-rolling with heavily loaded trucks. Where appreciable deflections are observed beneath the truck tires, the soils at this location should be subexcavated for a depth of at least 300mm and recompacted to a minimum of 95 percent of standard Proctor density.

All fill for the granular pad should be placed in lifts not exceeding 200 mm in loose thickness and should be compacted to not less than 95% of standard Proctor density. The compacted fill pad should be placed a minimum of 2 metres beyond the perimeter of the building. The bearing capacity of a well compacted pad may be taken as 150 kPa.

Long term settlement of the fill structure, if constructed according to the above guidelines, may be expected to be in the order of 1 to 2 percent of the fill thickness. However, if the granular pad is saturated prior to freezing, some heave can be expected during freezeback. For the minimum fill thickness specified above, potential heave in the order of 30mm to 40mm can be expected. Monitoring of the construction of the granular

pad would verify that high quality construction is maintained and would reduce the potential for differential settlement.

6.2 WATER INTAKE LINE AND EROSION PROTECTION

At the time of the field reconnaissance, strong southerly winds were noted. During the spring breakup, such winds could cause any large blocks of loose ice on the lake to be deposited onshore and could infringe on the pumphouse building. Hence, consideration should be given to selecting the final locations for the pumphouse intake facility.

The need for a protective berm is envisaged near the shoreline for the water intake line. It is anticipated that sufficient quantities of the larger diameter rocks (boulders) which are required for the armour rock are available in a neighboring borrow source in the near proximity of the proposed pumphouse location. Recommendations with respect to the extent of erosion protection and rip rap size can be provided on request, when the design profile details have been established.

6.3 STABILITY OF ROAD EMBANKMENT

As noted in Section 4.1 above, small cracks were observed in the surface of the road adjacent to the lake and were oriented parallel to the alignment of the road. These cracks are likely due to slope instabilities caused by displacement of the soil in the active layer downslope. The concern is that this portion of the road could continue to move and become increasingly unstable. Saturated soil conditions resulting from extended rainfall events, combined with strong winds and wave action on the toe of the slope, could result in undermining the road embankment and failure of a portion of the access road. Periodic regrading of the road and slope will be required as future instabilities and slope movements occur.

Consideration could be given to improving the stability conditions of this slope. The most feasible mitigating measure includes placing large diameter rocks (cobble and boulder sizes) along the shoreline, particularly at the toe of the road embankment. These large diameter rocks would effectively act as

- restricting active layer and surficial seepage along the slope by constructing, for example, a swale or berm immediately adjacent to the toe of the slope.

5.0 CLOSURE


We trust the foregoing is sufficient for your present purposes. Should any questions arise, please contact the undersigned at your convenience.

Yours truly,

AGRA Earth and Environmental Limited



James L. Anklewich, P.Eng.
Manager, Yellowknife Office



THE ASSOCIATION OF
PROFESSIONAL ENGINEERS,
GEOLOGISTS and GEOPHYSICISTS
OF THE NORTHWEST TERRITORIES
PERMIT NUMBER
P 047
AGRA Earth &
Environmental Limited

Reviewed by:

Marv J. Cherniawski, P.Eng. (Alberta)
Senior Geotechnical Engineer

Gary R. Beckstead, M.Sc., P.Eng. (Alberta)
Senior Water Resources Engineer

YX00387.REP



DILLON
Consulting Engineers · Planners
Environmental Scientists

DATE

OCT 94

PROJECT
TRUCKFILL STATION PLANNING STUDY
ARCTIC BAY

TITLE

LOCATION PLAN

PROJECT NUMBER

94-2213-01


FIGURE NUMBER

1.1

82
65



GRAPHIC SCALE
(IN METERS)



BILCON
Consulting Engineers, Planners
Environmental Scientists

DATE
AUG 94

PROJECT

CLYDE RIVER
WATER SUPPLY ANALYSIS

TITLE

WATER SUPPLY LAKE
ELEVATIONS & CONTOURS

PROJECT NUMBER

94-2214-01

PLATE NUMBER

1.1

83
66

Appendix-4.0

Schematics and Functional Data

4.0 SCHEMATICS AND FUNCTIONAL DATA


4.1 General

Chapter 4 contains tables and sketches that list components and a short description of their function.

For each system in the plant, there is a Table listing each component, it's function and cross references to the attached Figure and the Manufacturer's data in Chapter 9.

Five (5) systems are shown:

	Table	Figure
Water Treatment System	4.1	4.1
Power Distribution System	4.2	4.2
Controls and Alarms	4.3	4.3
Intake Casing, Pipe, and Cables	4.4	4.4
Heat Trace System	4.4	4.4, 4.5



PROCESS SCHEMATIC

NTS

EDIT DATE: 06/02/98 ACAD FILE: G:\953817\CLYDE_OM\OM_41.DWG
 BASE NAME: a.dwg LOC FILE: NA

DILLON
CONSULTING

PROJECT

CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT

TITLE

WATER TREATMENT SYSTEM

PROJECT NUMBER

96-3817

DATE

JUNE 98

FIGURE NUMBER

4.1

86
68

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**WATER TREATMENT SYSTEM
TABLE 4.1**

Figure	No.	Section 5 Tab	Component	Function	Remarks
4.1	1	9.1	Intake Screen	Prevents larger solids from entering intake line and submersible pump	Stainless Steel Drum Screen
4.1	2	9.2	Submersible Pump	Pumps water from lake through intake pipe for treatment and distribution	Submersible 150 mm Diameter centrifugal pump, 7.5 HP, mounted on skid. Spare pump supplied.
4.1	3	9.1	Intake Casing	Screen flanged to casing. Casing houses and protects intake line and submersible pump.	Casing is insulated 300 mm Diameter DR17 HDPE pipe.
4.1	4	9.1	Throttling Valve	Control flow rate of water being pumped through system	Butterfly Valve
4.1	5	9.8	Flow Switch	Activates chlorine feed pump in a flow condition. Deactivates pump in no-flow condition	-
4.1	6	9.3	Pressure Gauge	Measures the water's gauge pressure in the system piping	-
4.1	7	9.3	Thermometer	Measures water's temperature	-
4.1	8	-	Chlorine Injector	Allows chlorine to be injected into raw water. Does not allow raw water into chlorine line.	-
4.1	9	-	Future Fluoridation Injector	For future fluoridation system	-
4.1	10	9.8	Flow Sensor	Paddle wheel that turns proportional to the flow rate. Connected to flow meter and accumulator.	-


87
69

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**WATER TREATMENT SYSTEM
TABLE 4.1**

Figure	No.	Section 9 Tab	Component	Function	Remarks
4.1	11	9.3	Flow Meter	Displays flow rate of system	Flow Meter/Accumulator housed in control panel.
4.1	12	9.4	Chlorine Feed Pump	Pumps chlorinated stock from feed tank to raw water in system piping.	Positive displacement pump with adjustable stroke and rate.
4.1	13	9.4	Mixer	Physically mixes calcium hypochlorite and water for treating raw water.	Neptune 120 V, 1/20 HP agitator.
4.1	14	9.4	Chemical Mix Tank	Vessel used to mix calcium hypochlorite and water for treating raw water.	Translucent plastic tank with lid.
4.1	15	9.4	Chemical Feed Tank	Stores mixed stock of calcium hypochlorite and water for injection into raw water.	Translucent plastic tank with lid.
4.1	16	-	Water Truck	Delivers treated water	-

88
70



POWER DISTRIBUTION SYSTEM

NTS

EDIT DATE: 06/02/98 ACAD FILE: G:\963817\CLYDE_OM\DM_41.DWG
 BASE NAME: a.dwg LOG FILE: NA

DILLON
CONSULTING

PROJECT

CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT

TITLE

POWER DISTRIBUTION SYTEM

PROJECT NUMBER

96-3817

DATE

JUNE 98

FIGURE NUMBER

4.2

89
71


**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**POWER DISTRIBUTION SYSTEM
TABLE 4.2**


Figure	No.	Section 9 Tab	Component	Function	Remarks
4.2	1	-	N.W.T Power Corp. Overhead line	Supplies power to pumphouse.	-
4.2	2	-	Transformers	Converts utility and power to 120/240V, 1 phase, 3W for pumphouse use.	Owned by N.W.T. Power Corp.
4.2	3	-	Power Mast	Provides entrance of converted power line into conduit.	-
4.2	5	-	Meter	Measures power used by facility.	Owned by N.W.T. Power Corp.
4.2	10	-	Ground Rod	Provides ground for circuits in pumphouse.	19mm x 3048 long ground rod.
4.2	11	-	Ground Bus	Provides grounding connections for breaker panel and intake pump.	On isolation standoffs 25mm long.
4.2	12	9.2	Motor Starter	Starter for intake pump.	-
4.2	13	-	Wire	Connects intake pump to motor starter.	-
4.2	14	9.2	Intake Pump	Pump water from reservoir to water truck.	-
4.2	15	-	Wire	Connects combination main disconnect/breaker panel to utility power.	-
4.2	16	9.6	Combination Disconnect/Breaker Panel	Facilitates circuit connections for pumphouse.	-
4.2	17	-	Breaker	20 Amp Breaker for UPS circuit.	-
4.2	18	9.7	UPS Controller Switch	The controller switch allows bypassing of the UPS, disconnecting AC or DC current.	-
4.2	19	9.7	Uninterruptible Power System (UPS)	Provides power to system when main power is interrupted.	-

90
72

⑦ PANALARM ANNUNCIATOR



CONTROL PANEL ①
NTS



REMOTE CONTROLLER ⑧
NTS

EDIT DATE: 06/02/98 ACAD FILE: G:\963817\CLYDE_OM\OM_41.DWG
BASE NAME: a.dwg LOG FILE: NA

 DILLON CONSULTING	PROJECT	CLYDE RIVER TRUCKFILL CLYDE RIVER, NT	PROJECT NUMBER 96-3817
	TITLE	CONTROLS AND ALARMS	DATE JUNE 98
			FIGURE NUMBER 4.3

91
78


CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT

CONTROLS AND ALARMS
TABLE 4.3

Figure	No.	Section 9 Tab	Component	Function	Remarks
4.3	1	9.8	Control Panel	Houses flow gauge/accumulator, alarm annunciator, pilot lights, pump control, and pump control switch.	-
4.3	2	9.8	Pump Control Switch	Switch is used to enable pumping mode — automatic, manual, or off.	-
4.3	3	9.8	Chlorine Pump Pilot Light	Turns on when chlorine pump is activated.	-
4.3	4	9.8	Water Intake Pump Pilot Light	Turns on when submersible intake pump is activated.	-
4.3	5	9.8	Push to Test	Tests the alarms circuit by activating the strobe light, and horn.	-
4.3	6	9.3	Flow Gauge/ Accumulator	Displays flow rate and cumulative flow of water pumped through system.	-
4.3	7	9.9	Panalarm Annunciator	Allows operator to respond and control alarm conditions that occur with truckfill station.	-
4.3	8	9.8	Remote Controller	Allows water truck operator to fill truck without having to enter pumphouse.	Located on truckfill arm. Comes with weatherproof sheath.
4.3	9	9.8	Key Switch	Closes circuit allowing operator to start or stop the truckfilling process.	-
4.3	10	9.8	Start Switch	Pushing button starts truckfilling process, provided that key switch is turned on.	
4.3	11	9.8	Stop Switch	Pushing button stops truckfilling process, provided that key switch is turned on.	
4.3	12	9.8	Pump Timer	Timer may be set to run pump for period of time. Stop switch will interrupt timer setting, and stop the filling process.	Automates filling process. Different sized trucks will have different fill times.

92
74

HDPE INSULATION CASING
 50 URETHANE INSULATION
 300 HDPE DR17 CASING PIPE
 100 HDPE DR17 IN TAKE PIPE
 19 COPPER CONDUIT FOR
 HEAT TRACE CABLE (3)



(1) TEMP. SENSOR CABLE
 IN 19 NYLON TUBING

PUMP POWER CABLE

SS BANDING
 STRAP EVERY
 1 M LENGTH

(2) 19 COPPER CONDUIT FOR
 HEAT TRACE CABLE C/W,
 HEAT TRANSFER TAPE AS
 REQUIRED BY HEAT TRACE
 CABLE SUPPLIER

4 SS WIRE ROPE PUMP
 PULL CABLE

EDIT DATE: 06/03/98 BASE NAME: d10002.dwg
 ACAD FILE: C:\CAD\963817\CLYDE_ON\ON_44.DWG



DILLON
 CONSULTING

PROJECT

CLYDE RIVER TRUCKFILL
 CLYDE RIVER, NT

TITLE

INTAKE CASING, INTAKE PIPE,
 AND CABLES

PROJECT NUMBER

96-3817


DATE

JUNE 98

FIGURE NUMBER

4.4

93
 95



HEAT TRACE SCHEMATIC

N/S

EDIT DATE: 06/03/98 BASE NAME: eland2.dwg
 ACAD FILE: G:\CAD\963817\CLYDE_ON\ON_45.DWG



DILLON
 CONSULTING

PROJECT

CLYDE RIVER TRUCKFILL
 CLYDE RIVER, NT

TITLE

HEAT TRACE SYSTEM

PROJECT NUMBER

96-3817

DATE

JUNE 98

FIGURE NUMBER

4.5

CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT

HEAT TRACE SYSTEM
TABLE 4.4

Figure	No.	Section 9 Tab	Component	Function	Remarks
4.4	1	9.11	Temperature Sensor Cable in Nylon Tubing	Sensor cable detects temperature against intake pipe. Heat trace control and alarms based on sensed temperatures.	-
4.4	2	-	Copper Conduit for Heat Transfer Cable	Encases heat trace cable and conducts heat to 100 HDPE intake pipe	19 copper conduit. Located at 7 O'clock.
4.4	3	-	Other Copper Conduit for Heat Transfer Tape	Encases heat trace cable and conducts heat to 100 HDPE intake pipe	19 copper conduit. Located at 5 O'clock.
4.5	1	9.11	Heat Trace Controller	Turns heat trace system on and off depending on sensed temperatures. Controls alarming of heat trace.	Accutron TS202 controller. Separate control for two heat trace cables.
4.5	2	9.11	Heat Trace Cable	Uses power to generate heat that will be transferred through copper conduit into intake pipe.	
4.5	3	-	Stainless Steel Strapping	Hold copper conduit against intake pipe.	
4.5	4	-	Copper Conduit for Heat Trace Cable	Encases heat trace cable, and conducts heat to 100 HDPE intake pipe	19 copper conduit. Located at 7 O'clock.
4.5	5	9.1	Intake Pipe	Carries water to steel piping system leading to water truck	100 HDPE DR17 pipe
4.5	6	9.1	Intake Casing and Insulation	Encloses intake pipe	50 Insulation
4.5	7	9.11	Heat Trace Cable	Identical circuit on other side of intake pipe	Circuit location at 5 O'clock

95
77

Appendix-5.0

Component Data

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**COMPONENTS, MANUFACTURERS, AND SUPPLIERS
TABLE 5.1**

Section 9 Tab	Section 4 Tables and Figs	Description	Manufacturer and Model	Supplier
9.1	4.1, 4.4, 4.5	HDPE Insulated Pipe	Sclairpipe with Urecon Insulation	Perma Engineered Sales (1983) Limited P.O. Box 76 Group 200, R.R. #2 34 Roy Roche Drive Winnipeg, Manitoba R3C 2E6 Ph: (204) 633-7213 Fax: (204) 694-7228 Contact: David Sylvestre
9.1	4	Intake Screen	Screen Services StatiOrb Drum Screen	Screen Services 16748 - 110 Street Edmonton, Alberta T5X 2V1 Ph: (403)460-8043 Fax: (403) 460-8045 Contact: Kevin Whitham
9.1	-	Throttling Valve	Jenkins Lever Operated 100 mm	CCTF Quebec 1840 O'Gagnon Lahcine, Quebec H8T 3M6 Ph: (514) 636-1886 Fax: (514) 636-6022
9.1	4.1, 4.4	Pipe Fittings	Various Victaulic	CCTF Quebec 1840 O'Gagnon Lahcine, Quebec H8T 3M6 Ph: (514) 636-1886 Fax: (514) 636-6022
9.2	4.1, 4.2, 4.3, 4.4, 4.5	Intake Pump & Various Fittings	Berkley 6T250 150mm Submersible Pump	Deschesne 8335, St.. Michel Montreal, Quebec H1Z 3E6 Ph: (514) 374-3110 Fax: (514) 374-5141 Contact: Pierre Milot
9.2	4	Pump Starter	NEMA Combination 512	LUMEN 120 Dubois St.. Eustache, Quebec Ph: (514) 436-3225 Fax: (514) 436-2537 Contact: M. Collin

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**COMPONENTS, MANUFACTURERS, AND SUPPLIERS
TABLE 5.1**

Section 9 Tab	Section 4 Tables and Figs	Description	Manufacturer and Model	Supplier
-	-	Pump Skid	-	TAC 264 Montigny St. Jerome, Quebec J7Z 5P9 Ph: (514) 438-1279 Fax: (514) 438-0813 Contact: D. Desjardins
9.3	4.1, 4.3	Flow Meter & Accumulator	Signet 5500 Flow Monitor	Brian Control 8600 St. Patrick Ville Lasalle, Quebec H8N 1V1 Ph: (514) 366-5757 Fax: (514) 366-1134 Contact: Joe au Rolland
9.3	4.1	Pressure Gauge	Chevrier SG500	Chevrier Instruments Montreal, Quebec Ph: (514) 328-2550 Fax: (514) 327-0604
9.3	4.1	Thermometer	Ashcroft 30 EL 60 R040 0150 CENT	Chevrier Instruments Montreal, Quebec Ph: (514) 328-2550 Fax: (514) 327-0604
9.4	-	Chlorine	Calcium Hypochlorite 65%	Hall-Chem 11865 70 Ave Montreal, Quebec Ph: (514) 648-6050 Fax: (514) 648-9235
9.4	4.1, 4.3	Chlorine Injection Pump	Wallace & Tiernan Premia 75 Micro MPM4	US Filter 243 Bren, bur.210 Repentigny, Quebec J6A 6M4 Ph: (514) 585-5464 Fax: (514) 585-5464 Contact: Marcel Comtois
9.4	4.1	Chlorine Mixer	Neptune Flange Mount	US Filter 243 Bren, bur.210 Repentigny, Quebec J6A 6M4 Ph: (514) 585-5464 Fax: (514) 585-5464 Contact: Marcel Comtois

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**COMPONENTS, MANUFACTURERS, AND SUPPLIERS
TABLE 5.1**

Section 9 Tab	Section 4 Tables and Figs	Description	Manufacturer and Model	Supplier
9.4	4.1	Chlorine Mix and Feed Tanks	Wallace & Tiernan 55 gal	US Filter 243 Bren, bur.210 Repentigny, Quebec J6A 6M4 Ph: (514) 585-5464 Fax: (514) 585-5464 Contact: Marcel Comtois
9.4	4.1	PVC Ball Valves on Tanks and Injectors	Chemtrol 25 mm	Miller 10229 Cote de Liesse Dorval, Quebec H9P 1A3 Ph: (514) 631-4355 Fax: (514) 631-6695 Contact: Roy Seguin
-	4.1	Flex Tube for Chemical Tanks	-	Flexi-Tube 1116 Berlier Laval, Quebec H4S 1V8 Ph: (514) 384-6157 Fax: (514) 384-6157
9.5	-	Radiant Heaters	Chromalox CRT-3512	Binette 1231 Berri Montreal, Quebec H2J 4A2 Ph: (514) 274-2583 Fax: (514) 274-2583 Contact: J.M. Lambert
9.5	-	Electric Heater Thermostat	Tradeline T498B1678	Binette 1231 Berri Montreal, Quebec H2J 4A2 Ph: (514) 274-2583 Fax: (514) 274-2583 Contact: J.M. Lambert
9.5	-	Percentage Input Controller for Radiant Heaters	Caloritech Type OKT	Binette 1231 Berri Montreal, Quebec H2J 4A2 Ph: (514) 274-2583 Fax: (514) 274-2583 Contact: J.M. Lambert
9.6	4.2	Electrical Panel	Square D PS-1	CDE 2522 LeCorbusier Laval, Quebec H7S 2K3 Tel: (514) 438-1263 Fax: (514) 438-3728 Contact: Yvon Clement

8079

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**COMPONENTS, MANUFACTURERS, AND SUPPLIERS
TABLE 5.1**

Section 9 Tab	Section 4 Tables and Figs	Description	Manufacturer and Model	Supplier
9.6	-	Receptacles	Hubbel 5252	CDE 2522 LeCorbusier Laval, Quebec H7S 2K3 Tel: (514) 438-1263 Fax: (514) 438-3728 Contact: Yvon Clement
9.6	-	Switches	Hubbel HBL 1201	CDE 2522 LeCorbusier Laval, Quebec H7S 2K3 Tel: (514) 438-1263 Fax: (514) 438-3728 Contact: Yvon Clement
9.6	-	Junction Boxes, and Unilets	Various	CDE 2522 LeCorbusier Laval, Quebec H7S 2K3 Tel: (514) 438-1263 Fax: (514) 438-3728 Contact: Yvon Clement
9.7	4.2	Uninterruptible Power Supply (UPS)	Best Ferrups Model FE2.1 KVA	Best Power Technology of Canada Limited 1555 Bonhill Road, Unit 11 Mississauga, Ontario L5T 1Y5 Ph: (905) 564-7655 Fax: (905) 564-7657
9.8	4.3	Control Panel	Optoinfo	Optoinfo Electric Inc. 542 Bran St.. Jerome, Quebec J7Z 2B1 Ph: (514) 436-6050 Fax: (514) 436-4846
9.8	4.3	Pilot Lights	Allen Bradly 800T-QH10G	Optoinfo Electric Inc. 542 Bran St.. Jerome, Quebec J7Z 2B1 Ph: (514) 436-6050 Fax: (514) 436-4846
9.8	4.3	Push Buttons	Allen Bradly 800T-ATA	Optoinfo Electric Inc. 542 Bran St.. Jerome, Quebec J7Z 2B1 Ph: (514) 436-6050 Fax: (514) 436-4846

81 00

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**COMPONENTS, MANUFACTURERS, AND SUPPLIERS
TABLE 5.1**

Section 9 Tab	Section 4 Tables and Figs	Description	Manufacturer and Model	Supplier
9.8	4.1	Flow Switch	McDonnel Miller FS4-3D	Optoinfo Electric Inc. 542 Bran St.. Jerome, Quebec J7Z 2B1 Ph: (514) 436-6050 Fax: (514) 436-4846
9.8	4.1	Flow Sensor	Signet 515 Rotor-X P51530-P0	Optoinfo Electric Inc. 542 Bran St.. Jerome, Quebec J7Z 2B1 Ph: (514) 436-6050 Fax: (514) 436-4846
9.8	-	Relays	Allen Bradley 700-HG45A1 and Potter & Brumfield KRPA-14AN-120	Optoinfo Electric Inc. 542 Bran St.. Jerome, Quebec J7Z 2B1 Ph: (514) 436-6050 Fax: (514) 436-4846
9.8	-	Time Delay Relays	Potter & Brumfield CNS-35-76	Optoinfo Electric Inc. 542 Bran St.. Jerome, Quebec J7Z 2B1 Ph: (514) 436-6050 Fax: (514) 436-4846
9.8	-	Terminal Blocks	Entrelec	Optoinfo Electric Inc. 542 Bran St.. Jerome, Quebec J7Z 2B1 Ph: (514) 436-6050 Fax: (514) 436-4846
9.8	4.3	Remote Control Enclosure	Telemecanique W913065520111	Optoinfo Electric Inc. 542 Bran St.. Jerome, Quebec J7Z 2B1 Ph: (514) 436-6050 Fax: (514) 436-4846
9.8	4.3	Key Switch	Allen Bradley 800T	Optoinfo Electric Inc. 542 Bran St.. Jerome, Quebec J7Z 2B1 Ph: (514) 436-6050 Fax: (514) 436-4846

101
82

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**COMPONENTS, MANUFACTURERS, AND SUPPLIERS
TABLE 5.1**

Section 9 Tab	Section 4 Tables and Figs	Description	Manufacturer and Model	Supplier
9.8	4.3	Fill Timer	Paragon SWP15M	Optoinfo Electric Inc. 542 Bran St.. Jerome, Quebec J7Z 2B1 Ph: (514) 436-6050 Fax: (514) 436-4846
9.9	4.3	Annunciator	Panalarm 910	Provan Meter 2011 Halpern Ville St.. Laurent H4S 1S3 Ph: (514) 332-3230 Fax: (514) 332-3552 Contact: M. Lachance
9.9	4.3	High/Low Temperature Thermostat	Honeywell Farm-O-Stat T631A	Denbec 9855 B.Hyp. Lafontaine Anjou, Montreal, Quebec H1J 2A3 Ph: 1-800-465-0950 or (514) 355-4540 Fax: (514) 355-4346
9.9	-	Horn	Panalarm	Provan Meter 2011 Halpern Ville St.. Laurent H4S 1S3 Ph: (514) 332-3230 Fax: (514) 332-3552 Contact: M. Lachance
9.9	-	Strobe Beacon	Adapta Beacon	Edwards Unit Of General Signal 625 6th St. E Owen Sound, Ontario N4K5P8 Ph: (519) 376-2430
9.10	-	Exterior Truckfill Light	Caretaker HPCT-35-120V-LL	Cooper Industries, Inc Crouse-Hinds Airport Lighting Canada 5925 McLaughlin Road Mississauga, Ontario L5R 1B8 Ph: (905) 507-4187 Fax: (905) 501-4078
9.10	-	High Pressure Sodium Lamps	Cermalux ED-231/2 Mog. 52V	Wesco 281 Traders Blvd. Mississauga, Ontario L4Z 2E5 Ph: (905) 890-3344 Fax: (905) 890-8533

102
83

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**COMPONENTS, MANUFACTURERS, AND SUPPLIERS
TABLE 5.1**

Section 9 Tab	Section 4 Tables and Figs	Description	Manufacturer and Model	Supplier
9.10	-	Exterior Wall Light	Holopane Wallpackette WP2B	Lumen 500- Boul. Daniel Johnson St.-Jerome, Quebec J7Y 4C5 Ph: (514) 436-3225 or 1-800-363-3678 Fax: (514) 436-2537
9.10	-	Interior Fluorescent Lights	K172120	CDE 2522 LeCorbusier Laval, Quebec H7S 2K3 Tel: (514) 438-1263 Fax: (514) 438-3728 Contact: Yvon Clement
9.10	-	Exit Light	Emergi-Lite EX42WEM12R120V	Emergi-Lite 1800 Hymus Blvd Dorval, Quebec H9P 2N6 Ph: (514) 685-2270 Fax: (514) 685-2394
9.10	-	Emergency Lights	Emergi-Lite 12ESL250	Emergi-Lite 1800 Hymus Blvd Dorval, Quebec H9P 2N6 Ph: (514) 685-2270 Fax: (514) 685-2394
9.11	4.4, 4.5	Self Regulating Heat Trace Cable	Accutron SRL5-1	Accutron 6600 Trans.Can Pointe-Claire H9R 4S2 Ph: (514) 695-7032 Fax: (514) 695-4784 <i>Two Terminals</i> <i>1-800-453-4661</i>
9.11	4.5	Heat Trace Control Panel	Accutron TS202 Controller	Accutron 6600 Trans.Can Pointe-Claire H9R 4S2 Ph: (514) 695-7032 Fax: (514) 695-4784 <i>4661</i>
9.12	-	Chlorine Tester	HACH Pocket Colorimeter for Chlorine	Anachemia Science 15006-116 Avenue Edmonton, Alberta T5M 3T4 Ph: (403) 451-0665 Fax: (403) 452-2478
9.12	-	Fire Extinguisher	Flag 400-11155ULC 20lb Nitrogen	Fyremaster Equipment Sales 4101 49a Ave Yellowknife, NT X1A 1A3 Ph: (867) 873-6990

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**COMPONENTS, MANUFACTURERS, AND SUPPLIERS
TABLE 5.1**

Section 9 Tab	Section 4 Tables and Figs	Description	Manufacturer and Model	Supplier
9.12	-	Eyewash Station	Fisher Scientific EYE2	Fisher Scientific 112 Colonnade Road Nepean, Ontario K2E 7L6 Ph: 1-800-234-7437 Fax: 1-800-463-2996
9.12	-	Valved Respirators	NIOSH 8500 by 3M	Fisher Scientific 112 Colonnade Road Nepean, Ontario K2E 7L6 Ph: 1-800-234-7437 Fax: 1-800-463-2996
9.12	-	Safety Gloves	Trionic Special Blend	Fisher Scientific 112 Colonnade Road Nepean, Ontario K2E 7L6 Ph: 1-800-234-7437 Fax: 1-800-463-2996
9.12	-	Rubberized Safety Apron	Fisherbrand 01-357	Fisher Scientific 112 Colonnade Road Nepean, Ontario K2E 7L6 Ph: 1-800-234-7437 Fax: 1-800-463-2996
9.12	-	Face Shield	Nalgene 11-409-5	Fisher Scientific 112 Colonnade Road Nepean, Ontario K2E 7L6 Ph: 1-800-234-7437 Fax: 1-800-463-2996
9.13	-	Combination Storage Wardrobe Unit	Kleton Combination FB041	Tenaquip 20701 Ste-Marie Ste. Anne Bellevue, Quebec H9X 3L2 Ph: 1-800-263-7576 or (514) 457-7800 Fax: 1-800-263-3324 or (514) 457-9807
9.13	-	Cabinet Table	Kleton Model FF075	Tenaquip 20701 Ste-Marie Ste. Anne Bellevue, Quebec H9X 3L2 Ph: 1-800-263-7576 or (514) 457-7800 Fax: 1-800-263-3324 or (514) 457-9807

104
85

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**COMPONENTS, MANUFACTURERS, AND SUPPLIERS
TABLE 5.1**

Section 9 Tab	Section 4 Tables and Figs	Description	Manufacturer and Model	Supplier
9.13	-	Winch	Posi-Brake LA692 1500lb	Tenaquip 20701 Ste-Marie Ste. Anne Bellevue, Quebec H9X 3L2 Ph: 1-800-263-7576 or (514) 457-7800 Fax: 1-800-263-3324 or (514) 457-9807
9.13	-	Winch Cable	Stainless Steel 3.2 MM 2100 lb	General Bearing 789 St.. Georges St.. Jerome, Quebec Ph: (514) 438-3315 Fax: (514) 438-3315
9.13	-	Janitorial Equipment	Misc.	Belisle & Carriere 1313 St.. Antoine boul. St.-Antoine, Quebec H1P 1Y5 Ph: (514) 438-7834 Fax: (514) 438-2806
9.13	-	Interior Paint	Laurentide Interior Semi-gloss Latex 694-500	Cyr & Nepveu St.-Anne Des Plain 323, Monte Gagnon Montreal, Quebec J0N 1H0 Ph: (514) 478-0907

105
86

Appendix-6.0

Operating Procedures

6.0 OPERATING PROCEDURES

6.1 General

The water supply system for Clyde River, N.W.T. consists of:

- .1 An intake screen connected to a 300 mm diameter high density polyethylene (HDPE) intake casing. The casing accesses the water supply lake, and enters the pump house through a wall.
- .2 A submersible pump connected to a 100 mm HDPE intake pipe is situated inside the 300 HDPE casing at a depth near the intake screen.
- .3 A chlorine solution is made in a mix tank by mixing calcium hypochlorite with water. The chlorine solution is drained to a feed tank after mixing.
- .4 A flow switch is activated when water is flowing through the truckfill line. This switch activates an injection pump.
- .5 The injection pump pumps the chlorine solution from the feed tank into the truckfill line. The injection pump stops when a no-flow condition exists in the truckfill line.

6.2 Start-up Procedures

Throughout the normal life of the facility, it should rarely have to be started from an off condition. If, for some reason, all power to the truckfill station has been switched off, follow the procedure below to restore power.

6.2.1 Start-up from Utility Power

- .1 **Location:** inside station at the truckfill pump starter.
Turn the pump starter to the OFF position.

- .2 **Location:** inside station at the combination electrical panel.
Turn the main disconnect on. Power should be connected to the station.
If there is no power, call the utility company.
- .3 Turn the truckfill pump starter to the AUTO position.
- .4 Turn UPS AC Line disconnect switch to "On" if not already in this position.

6.3 Normal Operating Procedures

The normal operating procedures for the water supply system includes:

- Filling of water trucks.
- Chlorination system preparation.
- Main control panel operation.
- Intake screen backwashing.
- Heat trace system operation.
- Heating system operation.

Each of these procedures is discussed in the following sub-sections.

6.3.1 Truckfilling Procedure

Trucks are filled with chlorinated water from the truckfill station for delivery to houses in Clyde River. The trucks are filled by either using the truckfill controller hanging from the truckfill arm, or by using the "manual" position on the pump motor starter switch on the control panel inside the pumphouse. Normally the pump motor starter switch is set to "Auto" and the truckfill controller is used for filling trucks.

- .1 **Location:** Under the truckfill arm.
Drive the truck under the truckfill arm so that the fill hole of the truck tank is directly under the pipe. Watch the arm to make sure that the truck does not hit it.
- .2 **Location:** On top of the truck.
Open the fill hole and place the fill hose in the hole.
- .3 **Location:** Hanging from truckfill arm.
Insert your key and turn the key switch to the 'on' position in the remote controller.
- .4 There are two ways you can fill the truck with the truckfill controller:

1. Using the Timer

- .1 Turn the timer to the desired time setting. Different water truck tank sizes will have different time settings.
- .2 Press the 'Start' button on the truckfill controller.
- .3 The pump will start pumping after a short delay. It will continue pumping until the timer completes its cycle.
- .4 If the timer is set too long (i.e. tank overfilling), press the 'Stop' button on the truckfill controller. Please note that severe weather conditions may have an impact on the timer's accuracy.
- .5 The 'Stop' button may be used any time during truckfilling to stop filling operations.

Manual Control

- .1 To manually fill the truck, simply press the 'Start' button on the truckfill timer.
- .2 The pump will start pumping after a short delay.
- .3 When the truckfill tank is full, press the 'Stop' button on the

truckfill controller. The pump will stop.

- .5 The filling is NOT automatic. The driver should observe the filling process, and be ready to stop the pump if the truck starts overfilling. Once the pumping rate is set, the operator should be able to time how long it takes the truck to fill.
- .6 Following the truckfill, turn the key switch to the 'off' position and remove the key.
- .7 **Location:** On top of the truck.
Remove the fill hose from the truck and close the fill hole. Hang the hose on the hook at the end of the arm.
- .9 Deliver water.

6.3.2 Chlorination Process

Chlorine is injected into the truckfill piping with a chemical injection pump. The injection pump is turned on by a flow switch when the water starts being pumped to the water truck. Chlorine kills bacteria and microorganisms in the water that might cause people to become sick. Chlorine **MUST** be added to all water leaving the truckfill station or residents may become sick. Never turn the chlorine system off, always ensure that it is working properly, and ensure there is sufficient solution for operation.

6.3.2.1 Chlorine Solution Mixing

Chlorine solution is mixed using calcium hypochlorite powder (65%) and water. The calcium hypochlorite powder is in 1 kg (liter) containers in the standing storage closet.

Appendix-5.0

Component Data

- .1 **Location:** Tap for hose connection on truckfill pipe (close to temperature and pressure gauges).
Connect the water hose to the threads on tap. Put the other end of the hose into the top tank on the workbench.
- .2 Close the butterfly valve on the truckfill pipe, or ensure there is a truck underneath the fill arm if the valve is open.
- .3 Close the valve on the bottom of the mix tank, and feed tank.
- .4 **IMPORTANT:** Open the 25 mm ball valve on the intake bypass hose. The open valve allows the pump to circulate the water without damaging the pump, and relieves some of the high pressure. Caution should be taken when filling the tanks as the pump does produce a very high pressure.
- .5 **Location:** The control panel.
Turn the starter to the MANUAL position. The pump will start.
- .6 Partially open the tap and fill the chemical tank on top of the bench to the 120 litre mark.
- .7 Turn off tap.
- .8 Turn the truckfill pump starter to the AUTO position. The pump will stop.
- .9 Open the butterfly valve on the truckfill pipe.
- .10 Close valve for the 25 mm bypass hose.

11 ✓
26

- .11 **NEVER** operate the truckfill pump with all valves closed. Either the butterfly valve must be open and a truck placed under the truckfill arm, or the bypass valve must be open. Operating the pump with no flow **will damage** it, and **high pressures are dangerous** to personnel.
- .12 Put on rubber apron, rubber gloves, and face shield.
- .13 Read manufacturer's safety data sheet for Calcium Hypochlorite.
- .14 Add five (5) liters (bottles) of Calcium Hypochlorite 65% to water. This will give a 1 bottle of Calcium Hypochlorite to 24 liters of water ratio.
- .15 Plug in mixer for two (2) hours. Unplug mixer.
- .16 Let the solution settle overnight if possible.
- .17 Open the valve at the bottom of the chemical mixing tank. The chlorine solution will drain into the chemical feed tank.
- .18 Close valve at bottom of mix tank. Disassemble piping by unscrewing collar after the mixing tank valve.
- .19 Thoroughly rinse the agitator paddle and tank with water from hose to prevent corrosion of paddle.
- .20 Reassemble mix tank piping.

113
21

- .21 Test first truck of day for adequate chlorination by using the HACH Colorimeter test kit. See details in following section 6.3.2.2 Chlorine Testing.
- .22 Adjust the stroke length and/or rate of the injection pump to either increase or decrease the chlorine dosage if required. Retest FREE CHLORINE after adjusting the stroke and/or rate.

This procedure mixes the chlorine stock to approximately 3% chlorine by volume. A higher chlorine ratio may be used if it is found that the injection pump can not achieve adequate chlorination. A lower chlorine ratio may be used if the pump's stroke and rate are set below 40%.

6.3.2.2 Chlorine Testing

Chlorine levels must be tested for the water in the delivery truck. For safety, chlorine should be delivered to homes with a minimum free chlorine level of 0.5 mg/L. However, as there may be bacteria in the storage tanks in homes, higher levels of chlorine to 1.0 mg/L would be safer to allow for some chlorine to kill the bacteria in the tanks. The chlorinated water should be sampled and tested daily prior to any deliveries. This will ensure that the following deliveries will be adequately chlorinated, provided that the chemical injection pump settings remain the same for that day.

The operator of the truck will have to balance the chlorine level to satisfy both the tastes of the people of the community and safety. Too much chlorine may result in the residents refusing to use the treated water. Not enough chlorine is unsafe.

6.3.2.3 Using the HACH Pocket Colorimeter Chlorine Tester

The following procedure may be used to test for free chlorine in a sample taken from the truck:

- .1 Rinse both 20 ml tubes in kit with distilled water.
- .2 Obtain a sample of treated water from the water truck after it has been sitting for 20 minutes (the chlorine has had time to disinfect). The sample should be taken from the top hatch of the truck. A clean measuring cup or jar may be used for this purpose.
- .3 Fill both tubes to the **10 mL** fill line (the first line) with sample water from the truck.
- .4 Differentiate between the two sample tubes so they do not get mixed up. One cell is the "blank", the other will be the "sample".
- .5 Put the blank cell in the slot of the Colorimeter with the diamond facing you. Cover the sample with the instrument cap. Press the "ZERO" key. The instrument will display 0.00. Remove the blank cell from the slot.
- .6 Take a foil package marked **FREE CHLORINE**, and tear the top off. Carefully pour the contents (reagent) into the sample tube.
- .7 Agitate the contents by shaking the capped tube for 15 to 20 seconds. The tube contents should start to turn to a pink, or magenta colour. If the contents **do turn to a pink colour, go to step 10.**

- .8 If the sample does not turn colour at all or turns very little, the truck water is inadequately chlorinated, and should not be delivered to the residents unless its chlorine dosage is increased. You may manually add bleach to the truck to increase the dosage.
- .9 If you do add additional bleach, another 20 minutes will be required for reaction time. 10 ml of bleach will raise the chlorination of 1000 litres of water by approximately 0.6 mg/l. If the truck size is 2500 litres, then 25 ml of bleach will also raise the chlorine content by approximately 0.6 mg/l. By adding bleach to under-chlorinated truck loads, you will not waste any truck loads by having to discard inadequately chlorinated water.
- .10 If the sample turns pink or magenta, place the tube in the chlorine tester's slot, and cover the capped sample with the instrument cap.
- .11 Press the "READ" key. The instrument will display the FREE CHLORINE result in mg/L or parts per million (ppm). It should read at 1.0 mg/l to be considered safe to deliver.
- .12 Empty and rinse tubes after using.

6.3.2.4 Chlorine Injection Pump Adjustment

The chlorine injection pump is located beside the chlorine mixing tank. This pump can have both the rate of pumping and the length of the stroke adjusted to obtain the correct chlorine injection rate that will provide enough chlorine for disinfection in the water truck.

The chlorine pump will be set to provide 1.0 mg/l of residual chlorine in the water truck. It may be required to pump more than 1.0 mg/l of chlorine into the truckfill pipe to obtain a residual chlorine of 1.0 mg/l.

The test should be performed on a full truck. The filling of the truck will mix the water resulting in a test that shows the average chlorine residual of the water.

- .1 **Location:** Inside the truckfill station beside the chemical pump.
Ensure the chemical pump is plugged into the receptacle labelled CHLORINE PUMP.
- .2 Set the pump knobs to a rate of 80% and a stroke of 100%. This has been found to be a good starting place.
- .3 **Location:** Outside at the truckfill arm.
Fill the truck per the instructions above in section 6.3.1.
- .4 Allow the truck to sit for 20 minutes.
- .5 Take a small sample in a measuring cup or some clean container from the fill hole in the top of the truck.
- .6 Test the sample as per section 6.3.2.3, "Using the HACH Pocket Colorimeter Chlorine Tester".
- .7 If the test result is below 1.0 mg/l, increase the stroke of the pump and/or the rate. However, the stroke and rate should always be between 30% and 100%.
- .8 Empty the truck and repeat steps 3 to 7. Repeat the test until 1.0 mg/l residual chlorine is reached.

117
31

- .9 If the test is above 1.0 mg/l, decrease the stroke and/or the rate. Follow the limits stroke and rate limits in step .7.
- .10 Empty the truck and repeat steps 3 to 7. Repeat the steps until 1.0 mg/l residual chlorine is reached.

6.3.3 Intake Screen Backwashing

The intake screen has been sized such that cleaning should not ever be required. In the unlikely event that the screen is becoming plugged, the intake screen may be backwashed by recirculating water from the existing intake line through the casing. This procedure may help to remove some silt or material that otherwise plugs the screen. However, it is not a completely effective cleaning because the intake pump recirculates more than it will backwash. The only practical methods to completely clean the screen is to have divers unclog and clean the screen by hand, or by applying high pressure air from the inside of the screen.

6.3.4 Heat Trace System

There is a heat trace system installed against the intake pipe inside the intake casing. The electric heat trace cables in the casing will prevent freezing and aid in thawing of the pipe should it ever become frozen.

The heat trace cables are operated by a dual temperature monitor and controller called the Accutron TS 202a.

Use of the heat trace during summer is not required. The controller will be enabled, but the heat trace cables will not be activated during warmer weather.

The heat trace controller has been set to perform optimally. However, should power to the controller be disrupted for a long period, the controller may require reprogramming. See the TS-202 Programming Manual in Section 9.11 for programming details. The following identifies the general steps to setup the controller as well as some settings found to be specific for the truckfill station.

- .1 **Location:** The Heat Trace Controller is inside the truckfill station above the intake pipe coming into the building.
Open the cover on the controller panel. When the unit is powered up, a power loss alarm will occur. This is normal. Press the ACK on the controller to acknowledge the alarm. You will also need to acknowledge this alarm on the main control panel (horn, strobe, and buzzer in panel) by pushing the BLACK acknowledge button, and the red ACK button on the panalarm.
- .2 Press the SHIFT key to enter the TS 202 programming mode.
- .3 Press the MAINTAIN TEMP key to set the operating temperature. Enter '12' which sets the operating temperature to 12°C.
- .4 Press the DEAD BAND key. The DEAD BAND is defined as the number of degrees above the setpoint at which the tracer is de-energized. Set to 1°C. Whenever the intake water temperature is above 13°C the heat trace cables will be turned off.
- .5 Press the AUTO TEST key. The controller will perform diagnostic tests on the circuit at preset time intervals. Enter the YES key. Set the CYCLE HOURS to 24. This will automatically test the circuits once/day. Set this alarm so that it is timed to check during normal delivery hours.

- .6 Press the CURRENT ALARM key. The TRIP ON HIGH AMPS will be displayed. Enter NO for this option. This will ensure power is maintained in the heat trace cables during a high amp alarm condition. The alarm must be cleared, and the problem attended to, even though the heat traces will remain in operation.
- .7 Press the NEXT key. The LOW TRACER CURRENT ALARM function option is displayed. This value should be left at the default value, unless an electrician or heat trace expert recommends it be changed.
- .8 Press the NEXT key. The HIGH TRACER CURRENT ALARM function option is displayed. This value should be left at the default value, unless an electrician or heat trace expert recommends it be changed.
- .9 Press the NEXT key. The TRIP ON HI AMPS TRIP TRACER function option is displayed. This value should be left at the default value, unless an electrician or heat trace expert recommends it be changed.
- .10 Press the HI GND CURRENT key. The GND FAULT MILLIAMPS function option is displayed. This value should be left at the default value, unless an electrician or heat trace expert recommends it be changed.
- .11 Press the HI GND CURRENT key, then the NEXT key. The TRIP ON HI GND TRIP TRACER function option is displayed for tracer #1. Set this value to NO. This will enable heat tracing even with ground current leakage. An alarm will sound, and the problem must be remedied as soon as possible to ensure safe operation.

- .12 Press the NEXT key. The TRIP ON HI GND TRIP TRACER function option is displayed for tracer #2. Set this value to NO. This will enable heat tracing even with ground current leakage. An alarm will sound, and the problem must be remedied as soon as possible to ensure safe operation.
- .13 Press the ENABLE TRACER key. The ENABLE TRACER #1 CHANGE function option is displayed for tracer #1. Set this value to YES. This will enable heat tracing, and monitoring for tracer #1. Press the NEXT key. The ENABLE TRACER #2 CHANGE function option is displayed for tracer #2. Set this value to YES. This will enable heat tracing, and monitoring for tracer #2.
- .14 Press the UNITS key. The SETTINGS IN DEG C CHANGE function option is displayed. Leave this value at NO. This will display units in degrees Celsius.
- .15 Press the HI TEMP SEEN key. The #1 RTD HI=??? C RESET function option is displayed. YES will reset the present high temperature being measured as the new value. NO will retain the high temperature read previously. Normally leave the setting at NO.
- .16 Press the HI TEMP SEEN key, then the NEXT key. The #1 LOW=??? C RESET function option is displayed. YES will reset the present temperature being measured as the new low value. NO will retain the low temperature read previously. Normally leave the setting at NO.
- .17 Press the DATA HIGHWAY key, then the NEXT key. The DATA HIGHWAY ON ENABLE function option is displayed. Set this option to NO, unless connecting to a computer.

- .18 Press the HI TEMP ALARM key. The #1 HI TEMP ALARM SET function option is displayed. This value should be left at the default value, unless consistent false alarms are occurring. Try increasing the setting to reduce false alarms.
- .19 Press the HI TEMP ALARM key, then the NEXT key. The #1 HI TEMP ALARM TRIP TRACER function option is displayed. This value should be set to YES. This will shut off the heat trace if the set HI TEMP is exceeded. Tripping the tracer could prevent possible melting through the intake pipe.
- .20 Press the HI TEMP ALARM key, then the NEXT key twice. The #1 RTD FAILURE TRIP TRACER function option is displayed. This value should be set to NO. This will enable heat tracing even with a failing RTD sensor. An alarm will sound, and the problem must be remedied as soon as possible to ensure safe operation.
- .21 Repeat the programming of steps .18 through .20 for tracer #2 by using the NEXT key.
- .23 Press the TRACER CURRENT key. The CURRENT CLAMPING #1 ENABLE function option is displayed for tracer #1. Normally set this value to NO. This setting will not restrict amperage allowed to the heat trace.

Any alarm conditions that occur with either tracer, the TS 202 will illuminate the ALARM ON indicator and alternate the Main Operations Display with the ALARM CODE display and corresponding tracer circuit. Any alarms can be acknowledged by pressing the ACK key on the heat trace controller. The alarm will also have to be acknowledged on the Panalarm in the main control panel. Acknowledging an alarm does not clear its condition.

For TRIP ALARMS, the alarm must be acknowledged before automatic control of the heat trace system is restored. Consult section 9.11 Appendix A of the TS202 programming manual for details on alarm messages.

6.3.5 Heating System

Heat is supplied to the truckfill station by two electric radiant heaters mounted on the ceiling. Each heater is controlled by a thermostat and a proportional controller.

The thermostat for each heater controls the room temperature. They should be both set to the same value. The normal setting is 16°C. This temperature is above the low temperature alarm setting of 13°C and below the high temperature alarm setting of 35°C. The setting should always be between the high and low alarm temperatures. There should not normally be a need to change the thermostat settings.

The amount of heat provided by the heaters is controlled by the proportional controllers located beside each thermostat. These controllers can be set from MIN to MAX which determines the time that the heater is turned on per cycle. If the heaters are failing to maintain room temperature, the controller settings can be increased. In warmer weather, the controller settings can be reduced.

For fast warmup of the building, adjust the proportional controllers to MAX (100%). This is recommended if personnel are going in and out of the pumphouse frequently in cold weather, i.e. servicing.

123
37

Appendix-6.0

Operating Procedures

6.4 SPECIAL PROCEDURES

6.4.1 Truckfill Pump Removal

If the truckfill pump, or other equipment within the intake casing, fails, the intake pipe and all attached equipment can be removed from inside the truckfill station. DO NOT attempt to remove the pump unless an electrician is present to disconnect the power cables.

It has been found that the winch for removal of the intake pipe is useful for the initial start, but that a loader or truck connected to the cable reduces the time required for removal. Care must be taken when using a vehicle to assist removal to ensure that the cable is not snapped which could cause injury, and make the remaining pump removal extremely difficult.

Water from the pumphouse will not be available during the pump removal and replacement.

Location: All of the following procedure can be completed within the truckfill station or just outside the door.

- .1 **Location:** At the main breaker panel.

Turn off the breakers for the truckfill pump and the heat trace controllers.

- .2 **Location:** At the UPS controller.

Turn the UPS controller switch to OFF. This will turn off the control panels.

- .3 **Location:** At the intake casing.

Turn the truckfill pump starter to the OFF position.

125
35

- .4 Disconnect the truckfill pump power cable from the starter. This **MUST** be done by a certified electrician.
- .5 Unplug the heat trace cables from the receptacle.
- .6 Disconnect one of the victaulic fittings on the truckfill pipe closest to the intake casing.
- .7 Move the truckfill pipe out of the way. More fittings may need to be removed to accommodate the pump removal.
- .8 Remove the outer set of bolts on the intake casing flange.
- .9 Loosen the inner set of four bolts on the flange which loosens the rubber plug.
- .10 Pull the flange and plug out of the casing.
- .11 Remove the four bolts from the flange.
- .12 Remove the flange and plug.
- .13 Set the winch stand pipe in the hole in the floor.
- .14 Wind the intake pull cable onto the winch.
- .15 Winch out the intake pipe, carefully supporting the pipe and cables. Once the pipe is a meter or so out of the casing it may be easier to connect the cable to a loader to continue pulling.

- .16 Carefully support the pipe and cables during pulling. Watch for snags, and any wedging that may occur during removal.
- .17 The pipe is approximately 80 metres long and will go out the door.
- .18 Once the pipe is pulled, the pump, heat trace RTD sensors, or heat trace cables can be maintained, repaired or replaced.
- .19 Reverse the above procedures to replace the pump and pipe.

6.5 TROUBLE SHOOTING PROCEDURES

6.5.1 Alarm System

The alarm system for the Clyde River pumphouse consists of an external horn and a flashing strobe beacon to indicate the alarm. There is a ten alarm annunciator set into the front of the main control panel, even though all ten positions are not occupied by an alarm. The record drawings and control panel schematics in Section 4 show the physical layout of the annunciators within the panel. Alarms are indicated by a red light flashing on the annunciator. Alarms sound the outside horn and the strobe beacon flashes.

The alarm annunciators each have four control buttons: ACK, FLRST, RST, and TEST. The TEST button causes each alarm light to illuminate while it is pressed. The FLRST (flash reset) button is not used with the operating mode the annunciators are programmed for in this facility. The ACK (acknowledge) button stops the flashing and horn, but the alarm light remains lit. The RST (reset) button cancels all alarms. However, if a device continues to send an alarm to the annunciator, the RST button will not reset that alarm.

127
40

The alarms are emergency conditions which may result in a failure of the facility to deliver treated water as required or may result in damage to the facility or persons. Therefore, these alarms are to be treated as emergencies and must be corrected immediately. To ensure that alarms are corrected immediately, the alarm annunciator is connected to an external horn and strobe beacon.

The alarms are listed, along with the response to each alarm condition.

Alarms

.1 Low Building Temperature

This alarm is transmitted from the low temperature alarm thermostat. It indicates that the building temperature is lower than the set point (initially set at 10 °C) and may indicate a heater failure. THIS ALARM MUST BE DEALT WITH PROMPTLY TO ENSURE THAT THE FACILITY AND INTERNAL EQUIPMENT DOES NOT FREEZE. Freezing of water within the facility may cause very severe damage to the piping, UPS batteries, and chlorine injector..

One of the following conditions may be causing the alarm:

- The building thermostat may have failed and the infrared heater is not operating.
 - Acknowledge the alarm annunciator (ACK). Increase the setting on the building thermostat to above room temperature, and turn on the infrared heaters. Have an electrician repair the heating system if the heaters do not turn on.
- The building thermostat may be set too low.
 - Acknowledge the alarm annunciator (ACK). Increase the setting on the building thermostat to above the low temperature alarm thermostat setting. Wait a few hours for the building to warm. The

alarm light should turn off when the room temperature rises above the alarm thermostat setting.

- The low temperature alarm thermostat may be set too high.
 - Acknowledge the alarm annunciator (ACK). Decrease the setting to approximately 10 °C. The alarm light should turn off as long as the room temperature is above 10 °C.
- The low temperature alarm thermostat may have failed.
 - Acknowledge the alarm annunciator (ACK). Check the thermostat for function by decreasing the setting to below the room temperature. The alarm light should turn off. If the thermostat fails to operate properly, have an electrician repair the heating system.
- The outside temperature may be very low and doors or vents may be open. Therefore, the heaters may not be able to heat the building to the thermostat setting.
 - Acknowledge the alarm annunciator (ACK). Ensure the door is not open, and look for major air leaks. Seal up the building as well as possible.

.1 High Building Temperature

This alarm is transmitted from the high temperature alarm thermostat. It indicates that the building temperature is higher than the set point (initially set at 32 °C). THIS ALARM MAY INDICATE A FIRE IN THE BUILDING.

Upon determining that the high building temperature alarm is on, look for signs of fire within the facility, or excess heat output. Small fires may be controlled with the fire extinguishers located at each exterior door. Larger fires will require the assistance of the Clyde River fire crew.

If fire is not the cause of the high temperature alarm, then one of the following conditions may be causing the alarm:

- The high temperature alarm thermostat may be set too low.
 - Acknowledge the alarm annunciator (ACK). Increase the setting to approximately 32 °C. The alarm light should turn off.
- The high temperature alarm thermostat may have failed.
 - Acknowledge the alarm annunciator (ACK). Check the thermostat for function by increasing the setting to above the room temperature. The alarm light should turn off.
- The building thermostat may be set too high.
 - Acknowledge the alarm annunciator (ACK). Reduce the setting on the building thermostat to below the high temperature alarm thermostat setting. Wait a few hours for the building to cool. The alarm light should turn off when the room temperature drops below the alarm thermostat setting.
- The temperature control thermostats may have failed and the infrared heaters are not turning off.
 - Acknowledge the alarm annunciator (ACK). Reduce the setting on the building thermostat to below room temperature, and turn the heaters' controls off. Have an electrician repair heating system if controls are not functioning properly.
- The outside temperature is very high and, therefore, the building is overheated. This would be indicated by both an outside temperature and a building temperature above the high temperature alarm thermostat setting the alarm off. Adjust the high thermostat alarm setting to a temperature higher than the room temperature.

130
43

.3 Heat Trace Alarm

An alarm will be activated when the heat trace controller sends an alarm signal to the control panel. Consult the TS202 Programming Manual, Appendix A for specific alarm messages, and potential problems. Also refer to section 6.3.4 and the TS202 Programming Manual for programming details if required.

The heat trace alarm on the control panel can be cleared by taking the following actions:

- Acknowledge the alarm on the heat trace controller by pushing the ACK button.
- Acknowledge the alarm on the control panel by pushing the black ACK button on the panel, and then the red ACK button on the panalarm.
- Determine the cause of the alarm.
- After resolving the problem, press the RST button on the Panalarm to clear the alarm.

.4 Hydro Power Alarm

An alarm will be activated if the hydro power fails. The UPS will be engaged and the alarm will continue until the main power is restored.

The hydro power alarm on the control panel can be cleared by taking the following actions:

- Acknowledge the alarm on the control panel by pushing the red ACK button on the panalarm.

131
44

- Restore the main power to the pumphouse.
- Press the RST button on the Panalarm to clear the alarm.

.5 Uninterruptible Power System Fails with Power On

An alarm will be activated if the Uninterruptible Power System (UPS) fails but the main building power is present, or the main building power and UPS fail simultaneously. This is serious because if the main power fails, there will be no backup power system.

- Turn the switch above the UPS to bypass the UPS.
- Acknowledge the alarm (ACK) on the alarm annunciator in the main control panel. The alarm light should turn off.
- Attend to the UPS' own alarm sounding from the UPS itself. There are a number of UPS alarms that may be causing the alarm on the main control panel to activate. Consult the Best Ferrups User Manual p.15. If the problem cannot be remedied by the operator, an appropriate technician or electrician must be contacted for servicing.
- If the problem can be remedied by the operator, return the switch above the UPS to the UPS on position.

Appendix-7.0

Maintenance Procedures

7.0 MAINTENANCE PROCEDURES

7.1 General

Section 7 contains tables describing the periodic maintenance tasks to be performed in the plant. The tables are organized By Schedule and By Equipment and contain cross references to Sections 4 and 9. For detailed descriptions of each maintenance task, refer to the manufacturers' manuals in Section 9.

Tables for spare parts and miscellaneous equipment are included in this section.

Finally, a clear plastic sleeve contains maintenance, chlorination, and consumable logs. Make copies as required. **DO NOT USE THE LAST COPY** before making more copies. Keep a clean copy in the sleeve. The logs are an important part of facility operation. They should be filled out immediately following maintenance. They are critical to trouble shooting when problems arise, determining "rules of thumb" for operation, and are used for designing changes to the facility when required.

Consumables and spare parts are provided for convenient and fast maintenance, thereby causing very little down time. When consumables are used be sure to record the usage on the consumables log. Order replacement consumables with plenty of lead time so no disruption in water delivery occurs.

Sleeve	Contents: Chlorination Log, Maintenance Logs, and Consumables Usage/Reorder Log.
Table 7.1	Maintenance Tasks by Equipment
Table 7.2	Maintenance Tasks by Schedule
Table 7.3	Spare Parts and Miscellaneous Equipment

7.2 Maintenance Logs

The following tables are maintenance logs for facility operation. Please make copies from the clear sleeve, ensuring that a clean copy remains in the sleeve for future copying.

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**MAINTENANCE TASKS BY EQUIPMENT
TABLE 7.1**

Section 9 Tab	Section 4 Tables and Figs	Item	Maintenance Item	Schedule
9.1 PIPES, PIPE SUPPORT, VALVES, INTAKE SCREEN, AND FITTINGS				
9.1	-	Throttling Valve	Check For Leakage, And Smooth Operation	Daily
9.1	4.1, 4.4	Pipe Fittings	Check For Leakage	Daily
-	-	Bypass Hose	Check For Leakage, Tighten Monthly	Daily
9.2 PUMPS				
9.2	4.1	Submersible Intake Pump	Inspect For Wear	Annually
9.2	4.1	Submersible Pump Engine	Reactive Maintenance, page 25 of Franklin Electric Submersible Motor Manual	As Required
9.3 METERS AND GAUGES				
9.3	4.1, 4.3	Flow Meter & Accumulator	Record Flow Rate and Accumulator Reading	Daily
9.3	4.1	Pressure Gauge	Record Reading	Daily
9.3	4.1	Thermometer	Record Reading	Daily
9.4 WATER TREATMENT				
9.4	-	Chlorine	Inspect Containers for Leaks and Moisture	Weekly
9.4	4.1, 4.3	Chlorine Injection Pump	Replace and Clean Cartridge Valves as Required	Every 8 Months
9.4	4.1, 4.3	Chlorine Injection Pump	Clean or Replace Diaphragm as Required	Every 8 Months
9.4	4.1, 4.3	Chlorine Injection Pump	Clean or Replace Diaphragm on 5-way Valve as Required	Every 8 Months
9.4	4.1	Chlorine Mixer	Rinse Off Shaft and Agitator	Following Each Chlorine Mixing
9.4	4.1	Chlorine Mix and Feed Tanks	Inspect for Leaks and Clean	Following Each Chlorine Mixing
9.4	4.1	PVC Ball Valves on Tanks	Check For Leakage, And Smooth Operation	During Each Chlorine Mixing

136
-48

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**MAINTENANCE TASKS BY EQUIPMENT
TABLE 7.1**

Section 9 Tab	Section 4 Tables and Figs	Item	Maintenance Item	Schedule
9.5 HEATING SYSTEM				
9.5	-	Radiant Heaters	Check For Correct Operation	Daily
9.5	-	Electric Heater Thermostat	Check For Correct Operation	Daily
9.5	-	Percentage Input Controller for Radiant Heaters	Check For Correct Operation	Daily
9.6 ELECTRICAL PANELS, AND ASSOCIATED ITEMS				
9.6	4.2	Breaker Panel	Test Breakers	Monthly
9.6	4.2	Main Disconnect in Breaker Panel	Test	Annually
9.6	4.2	Motor Starter for Submersible Pump	Check all Switches	Monthly
9.6	4.2	Meter Socket	Check that Meter is Operating	Monthly
9.7 UNINTERRUPTIBLE POWER SYSTEM				
9.7	4.2	Uninterruptible Power System	Periodic Maintenance As Per Manual	6 Months or Per Alarm Conditions.
9.8 CONTROL PANEL, REMOTE CONTROL, AND ASSOCIATED ITEMS				
9.8	4.3	Pilot Lights	Observe Operation	Daily
9.8	4.3	Push Buttons	Observe Operation	Daily
9.8	4.3	Flow Switch	Inspect O Rings, Wheel And Paddles	Annually
9.8	4.3	Flow Sensor	Replace Paddle and/or Sensor	Per False Readings on Flow Gauge
9.9 ALARM ITEMS				
9.9	-	Alarm Thermostats	Check Operation	Weekly
9.9	-	Horn	Check Operation	Weekly
9.9	-	Strobe Beacon	Check Operation	Weekly
9.9	4.3	Annunciator	Press Test Button	Weekly
9.10 LUMINARIES				
9.10	-	Emergency Light	Push To Test Button	Weekly
9.10	-	Exit Light	Test	Annually
9.10	-	Exterior Lighting	Check Lamps	Monthly
9.10	-	Overhead Lighting	Check Lamps	Monthly
9.10	-	Truck Arm Light	Check Lamps	Monthly

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**MAINTENANCE TASKS BY EQUIPMENT
TABLE 7.1**

Section 9 Tab	Section 4 Tables and Figs	Item	Maintenance Item	Schedule
9.11 HEAT TRACE SYSTEM				
9.11	4.5	Heat Trace Controller	Check for Messages on Panel	Daily
9.11	4.4, 4.5	Heating Cable	Feel Conduit for Heat	Daily During Cold Weather Conditions
9.12 LABORATORY AND SAFETY EQUIPMENT				
9.12	-	Chlorine Tester	Inventory Chemicals and Reorder as Necessary	Monthly
9.12	-	Fire Extinguisher	Maintain Per Manual's Instructions	Annually
9.12	-	Eyewash Station	Inventory Saline and Reorder as Necessary	Monthly
9.12	-	Valved Respirators	Inventory and Reorder as Necessary	Monthly
9.12	-	Safety Gloves	Inventory and Reorder as Necessary	Monthly
9.12	-	Rubberized Safety Apron	Inspect for Wear and Reorder if Necessary	Annually
9.12	-	Face Shield	Inspect for Wear and Reorder if Necessary	Annually
9.13 MISCELLANEOUS ITEMS				
9.13	-	Winch	Lubricate and Inspect Cable on Spool	Annually
9.13	-	Winch Cable	Inspect for Corrosion and Fraying	Annually
9.13	-	Janitorial Equipment	Restock as Required	Monthly
9.13	-	Interior Paint	Inspect and Repaint as Necessary	Annually

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**MAINTENANCE TASKS BY SCHEDULE
TABLE 7.2**

Schedule	Section 9 Tab	Section 4 Tables and Figs	Item	Maintenance Required
DAILY MAINTENANCE				
Daily During Cold Weather Conditions	9.11	4.4, 4.5	Heating Cable	Feel Conduit for Heat
Daily	9.1	-	Throttling Valve	Check For Leakage, And Smooth Operation
Daily	9.1	4.1, 4.4	Pipe Fittings	Check For Leakage
Daily	9.11	4.5	Heat Trace Controller	Check for Messages on Panel
Daily	9.3	4.1	Thermometer	Record Reading
Daily	9.3	4.1	Pressure Gauge	Record Reading
Daily	9.3	4.1, 4.3	Flow Meter & Accumulator	Record Flow Rate and Accumulator Reading
Daily	9.5	-	Percentage Input Controller for Radiant Heaters	Check For Correct Operation
Daily	9.5	-	Radiant Heaters	Check For Correct Operation
Daily	9.5	-	Electric Heater Thermostat	Check For Correct Operation
Daily	9.8	4.3	Pilot Lights	Observe Operation
Daily	9.8	4.3	Push Buttons	Observe Operation
Daily	-	-	Bypass Hose	Check For Leakage, Tighten Monthly
WEEKLY MAINTENANCE				
Weekly	9.4	-	Chlorine	Inspect Containers for Leaks and Moisture
Weekly	9.9	4.3	Annunciator	Press Test Button
Weekly	9.9	-	Horn	Check Operation
Weekly	9.9	-	Strobe Beacon	Check Operation
Weekly	9.9	-	Alarm Thermostats	Check Operation
Weekly	9.10	-	Emergency Light	Push To Test Button
MONTHLY MAINTENANCE				
Monthly	9.6	4.2	Breaker Panel	Test Breakers
Monthly	9.6	4.2	Meter Socket	Check that Meter is Operating
Monthly	9.6	4.2	Motor Starter for Submersible Pump	Check all Switches
Monthly	9.10	-	Exterior Lighting	Check Lamps
Monthly	9.10	-	Overhead Lighting	Check Lamps
Monthly	9.10	-	Truck Arm Light	Check Lamps

139
-51

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**MAINTENANCE TASKS BY SCHEDULE
TABLE 7.2**

Schedule	Section 9 Tab	Section 4 Tables and Figs	Item	Maintenance Required
Monthly	9.12	-	Safety Gloves	Inventory and Reorder as Necessary
Monthly	9.12	-	Valved Respirators	Inventory and Reorder as Necessary
Monthly	9.12	-	Chlorine Tester	Inventory Chemicals and Reorder as Necessary
Monthly	9.12	-	Eyewash Station	Inventory Saline and Reorder as Necessary
Monthly	9.13	-	Janitorial Equipment	Restock as Required
ANNUAL MAINTENANCE				
Annually	9.2	4.1	Submersible Intake Pump	Inspect For Wear
Annually	9.6	4.2	Main Disconnect in Breaker Panel	Test
Annually	9.8	4.3	Flow Switch	Inspect O Rings, Wheel And Paddles
Annually	9.10	-	Exit Light	Test
Annually	9.12	-	Face Shield	Inspect for Wear and Reorder if Necessary
Annually	9.12	-	Rubberized Safety Apron	Inspect for Wear and Reorder if Necessary
Annually	9.12	-	Fire Extinguisher	Maintain Per Manual's Instructions
Annually	9.13	-	Winch	Lubricate and Inspect Cable on Spool
Annually	9.13	-	Interior Paint	Inspect and Repaint as Necessary
Annually	9.13	-	Winch Cable	Inspect for Corrosion and Fraying
MISCELLANEOUS				
As Required	9.2	4.1	Submersible Pump Engine	Reactive Maintenance, page 25 of Franklin Electric Submersible Motor Manual
During Each Chlorine Mixing	9.4	4.1	PVC Ball Valves on Tanks	Check For Leakage, And Smooth Operation
Every 8 Months	9.4	4.1, 4.3	Chlorine Injection Pump	Clean or Replace Diaphragm as Required
Every 8 Months	9.4	4.1, 4.3	Chlorine Injection Pump	Replace and Clean Cartridge Valves as Required
Every 8 Months	9.4	4.1, 4.3	Chlorine Injection Pump	Clean or Replace Diaphragm on 5-way Valve as Required

140
52

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**MAINTENANCE TASKS BY SCHEDULE
TABLE 7.2**

Schedule	Section 9 Tab	Section 4 Tables and Figs	Item	Maintenance Required
Following Each Chlorine Mixing	9.4	4.1	Chlorine Mixer	Rinse Off Shaft and Agitator
Following Each Chlorine Mixing	9.4	4.1	Chlorine Mix and Feed Tanks	Inspect for Leaks and Clean
Per False Readings on Flow Gauge	9.8	4.3	Flow Sensor	Replace Paddle and/or Sensor

**CLYDE RIVER TRUCKFILL
CLYDE RIVER, NT**

**TABLE OF SPARE PARTS & MISCELLANEOUS EQUIPMENT
TABLE 7.3**

Item	Part Description	Number	Location
1	Submersible Pump Motor	1	Inside Pumphouse
2	Submersible Pump	1	Inside Pumphouse
3	Throttle Valve	1	shelves in storage cabinet
4	Thermostats	2	shelves in storage cabinet
5	Chemical Injection Pump - replacement part kits.	3	shelves in storage cabinet
6	Flow Switch	1	shelves in storage cabinet
7	Chemical Feed Pump	1	shelves in storage cabinet
8	Eyewash - Spare container of fluid.	1	shelves in storage cabinet
9	Lighting Lamps & Ballasts	2 for each light type.	shelves in storage cabinet
10	Breakers	2 for each size and type.	shelves in storage cabinet
11	Terminal Blocks c/w end caps, end plates, cross connectors, and tear off markers.	1 for each size and type.	shelves in storage cabinet
12	Motor Starter - pilot light and over load heaters.	6 of each type.	in motor starter panel
13	Motor Starter - Coil and Contact.	1	in motor starter panel
14	Pilot Light and Lense	1 of each type.	in control panel
15	Panalarm Alarm Annunciator	1	shelves in storage cabinet
16	Flow Gauge/Accumulator	1	shelves in storage cabinet
17	Heat Trace Controller	1	shelves in storage cabinet
18	Termination Boots	2	shelves in storage cabinet
19	Mini Breakers	2 of each relay and timer. 1 of each relay and timer base.	shelves in storage cabinet
16	Fuses	6 of each type.	shelves in storage cabinet
20	Dustmasks	150	shelves in storage cabinet
21	Rubber Gloves - Fisher large, extra long, heavyweight.	12	shelves in storage cabinet
22	Face Shield	1	shelves in storage cabinet
23	Rubber Apron	1	shelves in storage cabinet
24	Fire Extinguisher	1	mounted by exit
25	Floor Cleaner - Industrial Quality, 20L.	1	on floor of pumphouse

142
84

Appendix-8.0

Testing and Certification data

8.0 TESTING AND CERTIFICATION DATA

8.1 General

Section 8 contains copies of the Commissioning Checklist, test results, initial settings for equipment, and warranties. If a warranty is not found in this section, it is probably part of the operating manuals in "Manufacturer Data and Service Information", Section 9. Please search the related material in Section 9 if a warranty for a certain component is not found here.

If a warranty for an item cannot be found anywhere in this manual, please contact the appropriate supplier as listed in Section 5. The supplier will be able to provide service information for the item.