

5.0 SUMMARY AND IMPLEMENTATION

Arctic Bay

The truckfill facility at Arctic Bay will consist of:

- A skid mounted building constructed on a 1.0 m thick well compacted granular pad.
- An intake pipeline constructed of a 300 mm HDPE casing pipe with 50 mm of insulation and protected with riprap.
- A intake screen, 6 kw pump, and 100 mm conveyance piping.
- Prime power will be by on site 11 kw diesel electric generator. On site fuel storage will be a 1,100 l tank mounted on the building skids.
- Freeze protection of the intakes will be by 2 self-limiting heat trace cables.
- The building will be constructed off site and be a cold stream building. Electric unit heaters will provide freeze protection.
- Disinfection will be by injection of calcium hypochlorite.
- The truckfill control will be from the truckfill arm, with one customer key.
- The alarm in the system will consist of:
 - Major
 - High building temperature
 - Generator failure
 - Low fuel level 2
 - Minor
 - Truckfill pump failure
 - Building low temperature
 - Low fuel level 1

Major alarms will be annunciated on site, and to the plant operator by auto dialler.

The estimated cost of construction for this facility is \$550,000.00 GST and engineering not included. This estimate is based on the actual cost of construction for Lake Harbour, which is of similar construction.

The project is to go to tender in January 1997, with construction completed by November 1997.

Clyde River

The truckfill facility at Clyde River will consist of:

- A skid mounted building constructed on a 1.0 m thick well compacted granular pad.
- An intake pipeline constructed of a 300 mm HDPE casing pipe with 50 mm of insulation and protected with riprap.
- A intake screen, 6 kw pump, and 100 mm conveyance piping.
- Prime power will be by Grid power from NWTPC.
- Standby power will be by UPS system.
- Freeze protection of the intakes will be by 2 self-limiting heat trace cables.
- The building will be constructed off site and be of wood construction. Electric unit heaters will provide freeze protection.
- Disinfection will be by injection of calcium hypochlorite. Soda Ash will be supplied for possible pH control.
- The truckfill control will be from the truckfill arm, with one customer key.
- The alarm in the system will consist of
 - Major
 - High building temperature alarms
 - UPS failure with power on power off / UPS with less than 1 hour
 - Minor
 - Truckfill pump failure
 - Building low temperature
 - Power off / UPS on

Major alarms will be annunciated on site, and to the plant operator by auto dialler.

The estimated cost of construction for this facility is \$380,000.00 GST and engineering not included. The power line to the facility is estimated to cost \$95,000. This estimate is based on the annual cost of construction for Trout Lake, which is of similar construction. The estimate has been adjusted to the community location. The project is to go to tender in January 1997, with construction completed by November 1997.

January 16, 1995

File No. YX00387

M. M. Dillon Limited
201-5102 51 Street
Yellowknife, N.W.T.
X1A 1S7

Attention: Mr. Garv Strong, P.Eng.
Manager

Dear Sir:

Re: Report on Geotechnical Conditions
Water Supply Improvements
Arctic Bay, N.W.T.

This letter summarizes the results of a geotechnical investigation undertaken by AGRA Earth & Environmental Limited at two alternate sites for the proposed Water Supply Improvements and Truckfill Station in Arctic Bay, N.W.T.

1.0 TERMS OF REFERENCE

The Terms of Reference for the investigation, as outlined in the GNWT's Request for Proposal, and AGRA E&E's proposal of June 7, 1994 were to include:

- review available geotechnical information and examine aerial photographs;
- conduct a field investigation limited to test pits (with locally contracted equipment) in order to identify the soil and bedrock conditions at the proposed truckfill sites and turn-around areas;
- provide recommendations for the design and construction of the foundation for the pumphouse/truckfill station, water intake line, and armour rock/rip-rap; and,
- provide comments as to the availability of suitable granular materials in the community.

2.0 FIELD INVESTIGATION

The field investigation was conducted under the supervision of Mr. James Anklewich, P.Eng., of AGRA Earth and Environmental's Yellowknife Office. Mr. Gary Strong, P.Eng., of M. M. Dillon's (MMD) Yellowknife Office was also present during the field investigation. The field program included a visual reconnaissance of the sites, excavating test pits in the vicinity of the proposed pumphouse/truckfill station, and inspection of potential granular borrow sources.

Asistance was provided by AGRA Earth and Environmental to MMD in conducting the topographic and bathometric surveys, the results of which are reported by M. M. Dillon separately.

The following sections summarize the geotechnical observations.

2.1 BACKGROUND

The hamlet of Arctic Bay receives its potable water from Marcil Lake, which is some 9 kilometres from the community toward Nanisivik. Two sites on Marcil Lake presently are being used for the water supply. The selection of sites is dependent on the season (that is, winter versus summer) as access to the relatively closer winter location is not available during the warmer periods of the year. The relative locations of the two sites, and the major topographic features of the general area are shown on Figure 1.1 attached to this letter-report.

As it is desired to have a single, all-season truckfill/water supply station, the objective of the present study was to provide an assessment of the geotechnical conditions at the respective sites. It is anticipated that the results of this assessment and the geotechnical recommendations contained herein would assist in the selection of a permanent facility. However, non-geotechnical considerations may govern the site selection.

3.0 SITE CONDITIONS

3.1 WINTER FILL LOCATION

3.1.1 Site Description

The winter fill site, which is situated furthest to the west, is accessed from the Arctic Bay-Nanisivik Road by an all-weather, narrow road over a distance of about 600 metres. Based on visual observations, the road was constructed by dozing local gravel materials from the slopes of an adjacent ridge on to the native tundra terrain which prevails along the lake shore at the winter fill location. The thickness of the road embankment was estimated to be in the order of 1 to 1.5 metres. The surface of the road is rutted extensively suggesting that the granular materials were not compacted during construction and that possible soft, unfrozen native soils exist beneath the fill.

In the winter time, the trucks must travel beyond the end of this road on the frozen tundra and ice for a distance of approximately 45 metres to the fill point on Marcil Lake. When thawing conditions exist, truck access to the fill point over the tundra and ice is not possible.

At the time of the field reconnaissance, the water level in the lake appeared to be raised (from winter levels) such that the truck fill location and the possible area for the proposed pumphouse was flooded. The ground surface of the possible pumphouse location is about 2 metres below the top of the access road. The adjacent tundra terrain above the water level in the lake was observed to be soft and spongy.

As noted above, the winter fill site and the access road lie adjacent to an elevated ridge, the height of which is in excess of 25 metres above the level of the road. The slopes of the ridge are inclined at about 2H:1V and are underlain by coarse gravel beneath a thin cover of lichen and moss. On some slopes, the organic cover was stripped. The materials comprising the ridge are likely similar to that observed on an exposed portion of the ridge near the end of the existing access road (sand and gravel).

A substantial quantity of cobble and boulder sized rocks, some as large as 600mm diameter, have accumulated along a stretch of the shoreline in the vicinity of the proposed water intake line at the winter truckfill site. These rocks were piled along the lake shoreline to a height of 1 to 1.5 metres above the water level in the lake on that date (July 21/94). It is conceivable that the rocks piled against the shoreline were deposited by ice movements resulting from wave action and frost processes.

3.1.2 Subsurface Conditions

A single test pit was excavated near the end of the access road using a front end loader contracted from Enokseot Holdings of Arctic Bay. The soils observed at the test pit location generally consisted of a nominal 300mm thick cover of sandy, gravel fill underlain by a sand with a high silt content and scattered gravel sizes up to 150mm. Based on the relative ease of excavation by a loader, the gravel fill is considered to be loose. Organic soil inclusions were observed in the upper portions of the native soil. The native brown sand was observed to be saturated and in a loose state. Due to the fines content, the sand displayed a low plasticity.

Movement of the front end loader on the tundra immediately beyond the access road was difficult as it soon became bogged down in the saturated organic and sandy soils. Manoeuvring became increasingly difficult as the excavation proceeded, indicating that the native sand is somewhat sensitive to disturbance.

Groundwater seepage into the excavation was noted. After a period of several minutes, approximately 150mm of water was recorded. Frozen ground was encountered at a depth of 1 metre; however, the depth to frozen ground may be deeper in the immediate vicinity of the lake shoreline. The excavation was terminated at this depth and immediately backfilled.

3.2 SUMMER FILL LOCATION

3.2.1 Site Description

The summer fill location is located approximately 1 km east along the lake shore from the winter fill location. It is located some 150 metres away from the main road and is accessed by a sloping all-weather road. A turn-around pad is available for the trucks at the fill location. The existing summer fill location is not used during the winter due to the greater distance.

Drainage down the access road is poorly defined with the surface runoff flowing over the road in a random fashion. Several runoff gulleys have been created near the shoulders of the road.

Marcil Creek provides drainage of the uplands to the north and drains into Marcil Lake in the immediately vicinity of the fill location. Within approximately 100 to 150 metres upstream from the point of discharge at the lake shore, the river is braided with numerous wide and shallow channels. The soils in the vicinity of the point of discharge at the lake shore are generally rounded, gravel and cobble sizes with an abundance of particles exceeding 200mm to 300mm (boulders) in average diameter. The ground surface in this area is strewn with many such cobbles and boulders. Similar sizes of granular materials were noted in the water in the immediate vicinity of the shoreline.

At the time of the field reconnaissance (July 21/94), a considerable number of ice blocks were shoved on to the shoreline from the lake. At one location, which was situated approximately 30 metres southwest of the proposed fill location, the ice was pushed some 3 to 5 metres on to the shore. These blocks of ice were not observed the previous day, suggesting that the lake ice is relatively mobile during the breakup season.

3.2.2 Subsurface Conditions

Two test pits were excavated in the immediate vicinity of the proposed pumphouse location and turn-around pad. The soils encountered at these two test pit locations comprise a sandy gravel with a trace to little silt (less than 20 percent passing 0.075mm/#200 sieve screen). Cobble-sized materials (greater than 100mm diameter) were frequently noted in the test pits. The soils were moist to wet near the surface, but became saturated at a depth of approximately 500mm. Excavating beyond this depth was difficult as caving conditions prevailed in response to the groundwater seepage. Frozen ground was observed at a depth of 1 metre; however, the depth to frozen ground may be deeper in the immediate vicinity of the lake shoreline. The excavations were terminated at this depth and the test pits were immediately backfilled.

4.0 GRANULAR RESOURCES

Observations from the field reconnaissance indicate that suitable granular resources can be obtained at locations in the near vicinity of each proposed truck fill sites. Utilization of these natural gravelly materials would likely require that the boulders and cobbles be removed prior to transport and placement.

It is understood that a crusher operation was producing aggregate for the community in recent years at a location situated on a ridge to the northeast of the winter fill location. A sieve analysis on a sample indicates that the source is a reasonably well graded gravelly sand (25mm minus) with approximately 8 percent fines. Based on this result, the material would be suitable for the construction of the foundation pads for the truckfill/pumphouse.

dense due to the daily truck traffic. Although the test pits did not encounter any "soft" spots or weak zones, such zones may still exist elsewhere in the near vicinity.

The gravel fill should be placed in lifts not exceeding 200 mm in loose thickness and should be compacted to at least 95% of standard Proctor maximum dry density (ASTM D698). The compacted fill pad should be placed a minimum of 2 metres beyond the perimeter of the building. To facilitate the recommended compaction of the gravel fill in the pad construction, a geotextile should be placed on the existing surface. The geotextile would act as a separator and minimize the potential of displacement of the gravel into the soft subgrade. The initial lift of gravel fill may be increased to 300mm, and spread over the geotextile with light tracked equipment.

The allowable soil bearing of a well compacted pad may be taken as 150 kPa. Long term settlement of the fill structure, if constructed according to the above guidelines, may be expected to be in the order of 2% of the fill thickness. Monitoring of the construction of the granular pad would verify that good construction procedures are implemented and reduce the potential for differential settlement.

5.2 WATER INTAKE LINE AND EROSION PROTECTION

The potential ice forces and ice shove at the intake have been analyzed using the following data:

- a design wind speed of 85 kph. This is equivalent to the maximum hourly wind speed observed at Resolute Bay in July, when the breakup occurs. At Resolute, the maximum observed wind speeds in summer are consistently from the east, but the same value was assumed for the southeast exposure at the site.
- a fetch of 1 km from the southeast
- a beach slope of 1V:44H, based on the bathymetry data obtained during the site reconnaissance.

The 85 kph wind over the 1 km wide ice sheet would generate a force of 1.5 kN/m of shoreline. Assuming an ice thickness of 0.6

metres, such a force would push the ice almost 13 metres up the beach. Thicker ice may not be pushed as far. The ice shove could be greater than 13 m at exposed structures or points of land. If the pumphouse is located at A1 (bathymetry profile, as shown on Figure 1.3 attached), the site does not project into the lake and is in fact sheltered slightly by the adjacent shoreline. At this location, a setback of 13 metres is considered to be adequate to protect the pumphouse against ice shove.

If a location closer to the shoreline is desired, or for additional protection against ice forces, the pumphouse could be located northeast of A1 to take advantage of the shelter provided by the protruding shoreline between A1 and A2. Moving the site northeast would require a review of the bathymetry to verify that the mouth of the intake would have enough submergence to function under the assumed 2 metre ice thickness.

For the winter fill location, this 13 metre setback would be conservative, as the prevailing wind direction is from the east. A setback distance in the order of 10 to 13 metres is considered appropriate for the winter location.

To protect the intake pipeline against ice damage, it may be covered by a riprap berm. Details of the berm design are shown on the appended Figures 1, and 2. The riprap size is based on ice damage experienced at other site. The riprap should be angular in shape, and have an average diameter (D_{50}) of 400mm. It should consist of rock sizes from 200mm to 600mm diameter.

Although the riprap will provide a good degree of protection, it can not be considered to be immune to damage. Some maintenance is likely to be necessary because the berm protrudes from the shore and is therefore subject to much higher forces than the rest of the shoreline.

An alternative solution is to bury the pipeline for all or part of its length as shown on the appended Figure 3. Option 1, complete burial requires no riprap at all. In this case, the ice forces are not concentrated at the pipeline, but are spread out along the beach. Complete burial is preferable from the point of view of mitigating the effects of ice forces, but may have other

drawbacks related to disturbing the permafrost by trenching. Therefore, a second option, partial burial, is also presented. In this case, the above-ground portion of the pipeline is protected by a riprap berm. The berm does not extend into the lake and as such, it is easier to construct and requires much less riprap than the complete riprap protection.

This assessment was limited strictly to the assessment of ice shove. Other hydrotechnical issues which should be addressed are:

- the potential range of water levels which could occur on the lake and the impact of extremely high or low levels on the intake;
- wave effects on the shoreline and the design of wave erosion protection; and,
- design of the water intake.

AGRA Earth & Environmental would be pleased to address any of these issues and provide a hydrotechnical review of the proposed pumphouse and water intake on request.

5.3 SLOPE STABILITY

As stated in Section 2.2.1 above, the large ridge located at the winter fill location rises to an elevation in excess of 25 metres higher than the surrounding area with a slope angle that is locally as steep as 2H:1V. At this angle, the slope is stable with factors of safety against failure in the range of 1.4 to 1.5 or greater.

Any construction activities that would adversely affect the stability of the slope should be avoided. Examples of these activities would include, but are not limited to, the following:

- excavation or cuts near the toe of the slope;
- scraping the surficial materials from the slope, thereby creating a deeper zone of thaw; and,



- restricting active layer and surficial seepage along the slope by constructing, for example, a swale or berm immediately adjacent to the toe of the slope.


5.0 CLOSURE

We trust the foregoing is sufficient for your present purposes. Should any questions arise, please contact the undersigned at your convenience.

Yours truly,

AGRA Earth and Environmental Limited



James L. Anklewich, P.Eng.
Manager, Yellowknife Office





Reviewed by:

Marv J. Cherniawski, P.Eng.(Alberta)
Senior Geotechnical Engineer

Gary R. Beckstead, M.Sc., P.Eng. (Alberta)
Senior Water Resources Engineer

YX00387.REP



DILLON Consulting Engineers · Planners Environmental Scientists	PROJECT TRUCKFILL STATION PLANNING STUDY ARCTIC BAY	PROJECT NUMBER 94-2213-01
	TITLE LOCATION PLAN	FIGURE NUMBER 1.1

DATE
OCT 94





FIGURE 1
RIPRAP PROTECTION

File _____ Subject _____ Page _____ of _____
Prepared _____ Date _____ Checked _____ Date _____

RIPRAP - MAX SIZE 600 mm
MIN SIZE 200 mm



SECTION A-A
1:20

FIGURE 2

RIPRAP BERM DETAIL

File _____ Subject _____ Page _____ of _____
Prepared _____ Date _____ Checked _____ Date _____




FIGURE 3
BURIAL OPTIONS

Option	Pros	Cons	Recommendations
Winter Intake Site	<ul style="list-style-type: none"> If a road can be built to the high ground to the south (the ancient alluvial fan of the Marcil Creek), then the problems of the soft low-lying ground at the existing site can be overcome. 	<ul style="list-style-type: none"> The site is exposed to west and northwest winds, and resultant wave action and ice movement. The effects of wave and ice action are evident in the rocks and boulders piled up on the shoreline immediately south of the present winter water intake site. 	<p>Not the preferred site from a hydrotechnical standpoint. Geotechnical considerations dealing with the pump house and access road foundations would need to be overcome. Significant fill would need to be added to bring the pump house and road above the high water level of the lake. The site is prone to more significant wave and ice action than the summer site.</p>
	<ul style="list-style-type: none"> Water quality (suspended solids) may be at acceptable levels as there are no major streams entering the lake in the vicinity. 	<ul style="list-style-type: none"> The low-lying ground at the existing site is soft, and may be prone to inundation. 	
		<ul style="list-style-type: none"> Soft and low-lying ground conditions exist at the site, necessitating the importation of fill. (The winter site cannot be accessed in the summer, hence the summer fill site.) 	
Summer Intake Site	<ul style="list-style-type: none"> Generally firmer ground conditions appear to be available at this site, due primarily to the coarse bed material transported and deposited by Marcil Creek. 	<ul style="list-style-type: none"> The site is close to the mouth of Marcil Creek, which may result in water quality problems at the intake during peak runoff periods. 	<p>Recommended as the better site from a hydrotechnical standpoint, provided that water quality is acceptable. Of the local sites proposed, site A1 is preferred because of the separation from the mouth of Marcil Creek and the short distance to adequate depths.</p>

Option	Pros	Cons	Recommendations
	<ul style="list-style-type: none"> The site surveys indicate that adequate depths for the intake can be provided offshore. 	<ul style="list-style-type: none"> The input of coarse sediment from Marcil Creek may build up a delta which could affect the water intake, especially at site A2. 	
	<ul style="list-style-type: none"> The exposure of the site to wind and wave action appears to be less than for the winter site, because there is not the same accumulation of boulders along the shoreline. (the presence of the wind driven ice pile-up along the shoreline during the July 1994 site visit appears to have been a minor event, because the ice was well-candled and easily broken up, and therefore posed no significant danger to the shoreline or any structure. 		
	<ul style="list-style-type: none"> The site is only a short distance off the main all-weather road between Arctic Bay and Nanişivik. 		

APPENDIX B

GEOTECHNICAL REPORT CLYDE RIVER

December 21, 1994

File No. YX00388

M. M. Dillon Limited
201-5102 51 Street
Yellowknife, N.W.T.
X1A 1S7

Attention: Mr. Gary Strong, P.Eng.
Manager

Dear Sir:

Re: Report on Geotechnical Conditions
Water Supply Improvements, Clyde River, N.W.T.
MMD Reference 94-2214, MMD-GNWT Ref. SC320524

This letter summarizes the results of a geotechnical investigation undertaken by AGRA Earth & Environmental Limited (AGRA E&E) at the site of the proposed Water Supply Improvements and Truckfill Station in Clyde River, N.W.T.

1.0 TERMS OF REFERENCE

The Terms of Reference for the investigation, as outlined in AGRA E&E's proposal to M. M. Dillon of June 7, 1994 were to include:

- review available geotechnical information and examine aerial photographs;
- conduct a field investigation consisting of test pits (with locally contracted equipment) in order to identify the soil and bedrock conditions at the proposed truckfill sites and turn around areas;
- provide recommendations for the design and construction of the foundation for the pumphouse/truckfill station, water intake line, and armour rock/rip rap, and any site improvements, if required; and,

- provide comments as to the availability of suitable granular sources in the community.

2.0 PROJECT BACKGROUND

The hamlet of Clyde River receives its potable water from a lake which is approximately 1.6 kilometres northwest of the community. The lake has been chosen to fulfill the potable water supply needs of the community for the next 20 years. As such, a single, all-weather truckfill/pumphouse facility is required.

The truckfill station is understood to comprise the following:

- a pumphouse building of wooden construction with dimensions that are approximately 3.5m x 7.5m; it will be heated to +10°C;
- 300mm nominal diameter HDPE intake pipe will extend from the pumphouse to a depth in the order of 2 metres (design ice thickness); and,
- the intake line will be equipped with a heat trace line to reduce the potential for freezing; it will also be covered with 50mm of rigid foam insulation.

3.0 FIELD INVESTIGATION

The field investigation was conducted under the direct supervision of Mr. James Anklewich, P.Eng., of AGRA E&E's Yellowknife Office. Mr. Gary Strong, P.Eng., of M. M. Dillon's (MMD) Yellowknife Office was also present during the field investigation. The field program, which was conducted on July 26, 1994, included a visual reconnaissance of the site, excavation of test pits in the vicinity of the proposed pumphouse/truckfill station, and inspections of potential granular borrow sources.

The field program also included assisting MMD during the topographic and bathometric surveys, the results of which are reported by M. M. Dillon separately.

4.0 SITE CONDITIONS

4.1 PHYSICAL FEATURES

The subject lake is located in a natural depression with an elevation difference between lake level and the surrounding ridges being in the order of 7 to 10 metres. A second lake, which is located some 100 metres to the east, is approximately 6 metres higher in elevation and as such, drains into the subject lake. Based on the results of the topographic survey (reported by M. M. Dillon), the total area of the water shed affecting the subject lake is in the order of 50 hectares.

At the time of the field reconnaissance, the subject lake was clear of ice; however, the second lake still had a considerable amount of ice on the surface. A multibead thermoprobe was lowered into the water of the subject lake during the bathometric survey in order to establish the water temperature and confirm the presence of a thermocline. The thermoprobe data showed that the water was at a temperature of approximately $+5^{\circ}\text{C}$ ($\pm 0.5^{\circ}\text{C}$) over the entire depth.

A nominal 3 metre wide and 75 metre long access road lies adjacent to portions of the south and east sides of the lake. The alignment of the road at this location is in an approximately north-south direction. At the approach to the lake, the top of the road is about 5.5 metres above the lake and gently slopes down to the location of the proposed new truckfill location, where the road surface is approximately 1 metre above the lake. The west bank of this access road (adjacent to the lake) has a slope angle of approximately 2.5H:1V. Although the bank appeared to be relatively stable at present, small cracks were observed in the road surface and were oriented parallel to the alignment of the road at a location where the top of the road is about 3 to 4 metres above the lake level. These cracks are indicative of movements of the active layer beneath the slope toward the water's edge (shoreline). These slope instabilities are likely attributed to saturated conditions of the active layer during prolonged rainfall whereby the unfrozen soil moves downwards over top of the frozen soil towards the shoreline.

At the most easterly edge of the lake, a 400mm diameter CMP culvert provides (outflow) drainage from the lake to the lower elevations to the east. Both inverts of the culvert, particularly the eastern invert, were noted to be damaged as a result of repeated vehicle traffic since minimal soil cover was observed on the culvert crowns. At the time of the site reconnaissance, the flow rate through the culvert was such that little to no sediment was being transported; however, several erosion scours were observed within 50 metres of the downstream invert of the culvert. These scours suggest that relatively high flow rates have occurred in the past, perhaps during peak runoff at spring thaw, or during prolonged rainfall.

4.2 SUBSURFACE CONDITIONS

A total of three test pits were excavated in the vicinity of the access road and truckfill location using a rubber-tired loader provided by the Hamlet of Clyde River. The test pits locations are shown on the attached Site Plan. The test pits were advanced to a depth of approximately 1 metre below existing grade whereupon frozen ground was encountered. Seepage from the active layer immediately above the permafrost table was observed in all of the test pits. The test pits were terminated at this depth and backfilled immediately.

The soils encountered at the test pit locations generally consisted of a fine to coarse grained, loose, brown sand overlying a brown, frozen silt. Thin beds of low plastic, brown silt were noted within the sand as well. Based on our experience elsewhere in the community, the deposit of silt observed at the 1 metre depth is expected to be ice rich and potentially unstable if allowed to thaw.

5.0 GRANULAR RESOURCES

AGRA Earth & Environmental previously reported on the availability of suitable granular materials in the community of Clyde River. The information was summarized in our June 11, 1993 letter to M. M. Dillon Ltd.

Based on a review of recent aerial photographs and available geotechnical data, several potential borrow deposits in the community were identified. All of the potential borrow sources identified, which are located in the vicinity of the existing airstrip, were reported to be poorly graded gravelly sands with a variable fines content (material passing 0.075mm/#200 sieve screen). This information is summarized in a letter to M. M. Dillon Ltd., dated June 11, 1993.

Sieve analyses were conducted on samples of granular materials, which were obtained by MMD field personnel and delivered to our Yellowknife laboratory. The results of these tests confirm that the samples are poorly graded, gravelly sands with a fines content varying from 10 percent to 22 percent. These results were reported in a letter dated July 26, 1993. The June 11, 1993 and July 26, 1993 letters are appended.

Other potential granular borrow sources exist in the immediate vicinity of the proposed truckfill station; however, the quantity remaining in these sources is not confirmed, nor has the quality of the material been identified. Moreover, it is uncertain whether the hamlet prefers to use the sources located near the airstrip or those located near the truckfill station. Regardless of which granular borrow source is chosen, samples of the materials should be shipped to our laboratories prior to construction in order to determine the specific construction criteria (standard Proctor density, grain size distribution).

6.0 RECOMMENDATIONS

6.1 PUMPHOUSE FOUNDATION

Based on AGRA E&E's past experience, it is envisaged that the pumphouse for the truckfill station will consist of an insulated building of wood construction that is mounted on skids and supported on a compacted granular pad. Such a foundation is considered to be feasible for the present truckfill site. It is not likely that other foundation types, such as piles (adfreeze or bedrock grouted) or spread footings would be necessary or economical.

It is likely that the new pumphouse building would be located in the immediate vicinity of the existing truckfill location. In such a case, the granular pad should be placed directly on the existing surface. The granular pad should be a minimum of 1 metre thick such that the summer depth of thaw is maintained within the granular pad and not the native soils.

Backfill for pad construction should be a well graded gravel that is free of organics and compressible material. Ideally, the backfill should contain less than 5% fines (particles passing the 0.075mm/#200 screen) to reduce the potential for frost heave. The maximum particle size is dependent on the compactive equipment available for construction; however, in the absence of a specified value, a maximum size of 75mm is recommended.

As the existing truckfill location and approach pad have been in use for several years, the surficial soils at this location are expected to be relatively dense due to the daily vehicular traffic; however, there may still exist localized "soft" spots, or zones of weaker material. As such, preparation of the existing surface should include proof-rolling with heavily loaded trucks. Where appreciable deflections are observed beneath the truck tires, the soils at this location should be subexcavated for a depth of at least 300mm and recompacted to a minimum of 95 percent of standard Proctor density.

All fill for the granular pad should be placed in lifts not exceeding 200 mm in loose thickness and should be compacted to not less than 95% of standard Proctor density. The compacted fill pad should be placed a minimum of 2 metres beyond the perimeter of the building. The bearing capacity of a well compacted pad may be taken as 150 kPa.

Long term settlement of the fill structure, if constructed according to the above guidelines, may be expected to be in the order of 1 to 2 percent of the fill thickness. However, if the granular pad is saturated prior to freezing, some heave can be expected during freezeback. For the minimum fill thickness specified above, potential heave in the order of 30mm to 40mm can be expected. Monitoring of the construction of the granular

pad would verify that high quality construction is maintained and would reduce the potential for differential settlement.

6.2 WATER INTAKE LINE AND EROSION PROTECTION

At the time of the field reconnaissance, strong southerly winds were noted. During the spring breakup, such winds could cause any large blocks of loose ice on the lake to be deposited onshore and could infringe on the pumphouse building. Hence, consideration should be given to selecting the final locations for the pumphouse intake facility.

The need for a protective berm is envisaged near the shoreline for the water intake line. It is anticipated that sufficient quantities of the larger diameter rocks (boulders) which are required for the armour rock are available in a neighboring borrow source in the near proximity of the proposed pumphouse location. Recommendations with respect to the extent of erosion protection and rip rap size can be provided on request, when the design profile details have been established.

6.3 STABILITY OF ROAD EMBANKMENT

As noted in Section 4.1 above, small cracks were observed in the surface of the road adjacent to the lake and were oriented parallel to the alignment of the road. These cracks are likely due to slope instabilities caused by displacement of the soil in the active layer downslope. The concern is that this portion of the road could continue to move and become increasingly unstable. Saturated soil conditions resulting from extended rainfall events, combined with strong winds and wave action on the toe of the slope, could result in undermining the road embankment and failure of a portion of the access road. Periodic regrading of the road and slope will be required as future instabilities and slope movements occur.

Consideration could be given to improving the stability conditions of this slope. The most feasible mitigating measure includes placing large diameter rocks (cobble and boulder sizes) along the shoreline, particularly at the toe of the road embankment. These large diameter rocks would effectively act as


a toe berm and serve to provide restraint against any potential slope movements. Additionally, a suitable geotextile (filter fabric) could be placed between the existing soils on the slope and the overlying rip rap so that the potential for migration and washing of the soils from wave action is reduced.

6.0 CLOSURE

We trust the foregoing is sufficient for your present purposes. Should any questions arise, please contact the undersigned at your convenience.

Yours truly,

AGRA Earth and Environmental Limited





James L. Anklewich
Manager, Yellowknife Office

Reviewed by:

Marv J. Cherniawski, P.Eng.(Alberta)
Senior Project Engineer

YX00388.REP



DILLON
Consulting Engineers · Planners
Environmental Scientists

PROJECT

PLANNING STUDY

PROJECT NUMBER

94-2214-01

TITLE


CLYDE RIVER TRUCKFILL STATION

FIGURE NUMBER

1.2

DATE

AUG 94



NOTE: CONTOURS 91.00m
AND 92.00m CLOSED FOR
BASIN STORAGE CALCULATIONS

PRESENT TRUCKFILL
SIGHT

TEST PPT 1

OUTFLOW

TEST P11 1

400mm Ø CMP 9.60m

TEST PIT 3

EXISTING
ACCESS ROAD

OLD TRUCKEYE SIGHT

~~SHORELINE
(JULY 26/1994)~~

RECHARGE CREDIT

UPPER
LAKE

GRAPHIC SCALE
(IN METRES)



PROJECT

CLYDE RIVER
WATER SUPPLY ANALYSIS

BILTON
Consulting Engineers, Planners
Environmental Scientists

AUG 94

PROJECT NUMBER

94-2214-01

FIGURE NUMBER

1.1

**WATER SUPPLY LAKE
ELEVATIONS & CONTOURS**