

**LIST OF UNIT PRICES FOR UNIT PRICE CONTRACTS ONLY- APPENDIX D FOR  
HALL BEACH LAGOON ( MARCH 2015 )**

(Information to be Completed by Tenderer and Submitted with Tender)

- (a) The conditions in Tender Form apply to the completion of this Appendix  
 (b) Type or print tendered values clearly. An illegible submission may be disqualified at the sole discretion of the owner

ITEM	DESCRIPTION	CLAUSE	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
1	<b>Mobilization / Demobilization</b>	2.1	L.S.	1		
2	<b>a) Supply and deliver silt fence, including wood stake</b>	2.3.1	m	440	\$	\$
	<b>b) Installation of silt fence, including wood stake and trenching</b>	2.3.1	m	440	\$	\$
3	Supply, deliver, and place granular material to construct new berms	2.3.3	cu.m	22,500	\$	\$
4	Excavation, grading, and disposal on site of berm materials	2.3.18	cu.m	12,000	\$	\$
5	<b>a) Supply and deliver liner for proposed lagoon</b>	2.3.4	sq.m	21,100	\$	\$
	<b>b) Installation of liner for proposed lagoon including sand bedding, sand cover, and</b>	2.3.4	sq.m	21,100	\$	\$
6	<b>a) Supply and deliver materials for spillway structure</b>	2.3.8	ea.	1	\$	\$
	<b>b) Installation of spillway structure</b>	2.3.8	ea.	1	\$	\$
7	Remove existing truck discharge chute, bollards, and rocks	2.3.13	L.S.	1	\$	\$
8	Supply, deliver, and place 300mm granular 'C' material to top existing road	2.3.7	cu.m	780	\$	\$
9	Supply, deliver, and place 200mm granular B material for travelled portion of berm, truck discharge areas, and pumping area	2.3.6	cu.m	1,150	\$	\$
10	Supply, deliver, and place 150mm of granular A material to top road, truck discharge areas,	2.3.5	sq.m	5,500	\$	\$
11	<b>a) Supply and deliver piping for inlet structure including 150 dia. HDPE series 100 pipe, concrete block and pipe support</b>	2.3.11	ea.	1	\$	\$
	<b>b) Installation of piping for inlet structure</b>	2.3.11	ea.	1	\$	\$
12	<b>a) Supply and deliver all piping for outlet structure including 300 dia. HDPE series 100 pipe, 150 dia. HDPE series 100 pipe and wood support</b>	2.3.12	ea.	1	\$	\$
	<b>b) Installation of all piping for outlet structure</b>	2.3.12	ea.	1	\$	\$
13	<b>a) Supply and deliver truck discharge structures, including erosion protection and bollards</b>	2.3.10	ea.	2	\$	\$
	<b>b) Installation of truck discharge structures, including erosion protection and bollards</b>	2.3.10	ea.	2	\$	\$
14	Supply, deliver, and install boulder barriers	2.3.14	ea.	85	\$	\$
15	<b>a) Supply and deliver signage</b>	2.3.15	ea.	1	\$	\$
	<b>b) Installation of signage</b>	2.3.15	ea.	1	\$	\$
16	<b>a) Supply and deliver pump including engine, wheel kit 150mm dia. Hose, pressure gauge, ball valve, flange and coupling</b>	2.3.16	ea.	1	\$	\$
	<b>b) Installation of pump including engine, wheel kit, 150mm dia. Hose, pressure gauge, ball valve, flange and coupling</b>	2.3.16	ea.	1	\$	\$

**LIST OF UNIT PRICES FOR UNIT PRICE CONTRACTS ONLY- APPENDIX D FOR  
HALL BEACH LAGOON ( MARCH 2015 )**

ITEM	DESCRIPTION	CLAUSE	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
17	a) Supply and deliver 1.2m x 2.4m Project Information Sign	2.1.3	ea.	1	\$	\$
	b) Installation and Maintain 1.2m x 2.4m Project Information Sign	2.1.3	ea.	1	\$	\$
18	New swale construction and disposal of excavated material off site	2.3.9	m	250	\$	\$
19	Sub-excavate all landfill material under footprint of new lagoon	2.3.2	cu. m	12,000	\$	\$
20	Replace all sub-excavated landfill material with granular material and compact	2.3.2	cu. m	12,000	\$	\$
21	a) Supply and deliver gabion mats c/w impervious liner for erosion protection at toe of	2.3.17	sq.m.	1,000	\$	\$
	b) Installation of gabion mats c/w impervious liner for erosion protection at toe of berm	2.3.17	sq.m.	1,000	\$	\$

**SUBTOTAL**

**\$** \_\_\_\_\_

**G.S.T.**

**\$** \_\_\_\_\_

**TOTAL**

**\$** \_\_\_\_\_