

[illegible]

May 12, 2014

Phyllis Beaulieu  
Manager of Licensing  
Nunavut Water Board  
P.O. Box 119  
Gjoa Haven, NU X0B 1J0  
Phone: (867) 360-6338, Ext. 27  
Fax: (867) 360-6369  
Email: [phyllis.beaulieu@nwb-oen.ca](mailto:phyllis.beaulieu@nwb-oen.ca)

Attention : Erik Skiby, Assistant Technical Advisor

**Re: Shut down WWTP during Construction: Contingency Plan and Notice**

Dear Ms. Beaulieu,

I am writing you to clarify the e-mail of Mr. Erik Skiby on dated May 08 as follows:

**Monitoring station PAN-3:** Monitoring station PAN-3 is at the end of sewage effluent discharge pipe. From the pipe, effluent falls on the gravel pad of the wetland and then follows the downslope and finally meets the sea water. The distance of surface water (receiving body) from the effluent discharge pipe end varies due to tidal action of the sea from roughly 100m to 300m.

**During Construction Season:** Yes, effluent will run through the pipe after initial screening without proper treatment. The final effluent quality might be different. Test results will be represented.

**exp 's Design Brief:** Please see attached exp's Design Brief.



Department of Community and Government Services  
Nunalingni Kavamatkunnilu Pivikhaqautikkut  
Ministère des Services Communautaires et gouvernementaux