

QUOTATION: RB10023
REVISION: 0

Prepared by: Russ Boyer
June 3, 2010

To : EA Energy Alternatives Ltd.
City : Victoria, BC
Attention : Kevin Pegg
Project : Taloyaak Water System Upgrade
Engineer : Dillon Consulting

Phone : 250-727-0522
Fax :
E-Mail :

Item # 1 ASCO Series 7000 Delayed Transition Automatic Transfer Switch

Qty: 2 Catalogue # : J7ADTSA20200F5XC
Amperage : 200 (WCR 65kA @ 240V)
Voltage : 120/240V (2 Pole – Solid Neutral)
Enclosure : EEMAC 1 (ASA 61 Grey)
Controller : Group 5 Microprocessor c/w LCD Display

Accessories:

Acc. 1	TD Engine Start (0 to 6 Sec)	Acc. 11C	System Exerciser - Programmable
Acc. 2B	TD Transfer (0 to 60 Min)	Acc. 12	Engine Control Selector Switch
Acc. 2E	TD Engine Cool-Down (0 to 60Min)	Acc. 14A/B	ATS Position Contacts
Acc. 3A	TD Retransfer (0 to 60 Min)	Acc. 17	Provisions for Remote Test Input
Acc. 5A	System Test Switch (Maintained)	Acc. 85L	Digital Power Manager (Load Side)
Acc. 6J	Auto/Manual Control Switches		
Acc. 7	Engine Start Contact (Closes to Start)		
Acc. 9A/B	ATS Position Pilot Lights		
Acc. 9C/D	Source Availability Pilot Lights		

Lot Price: \$14,508.00 + applicable taxes

Clarifications & Exceptions:

1. Quotations based on project specification section 26 36 23.
2. Clause 2.2.3: qty 2 – 200Amp/240Volt, 1Phase/2Pole transfer switches have been quoted as per customer.
3. Clause 2.2.9 & 2.2.10: 2Pole with solid neutral has been quoted as per customer.
4. Clause 3.3.1: Manual operation under load not recommended as per CSA; ASCO will provide manual maintenance handle & manual load transfer via selector switches.
5. Part 2.3.3.6 & 2.3.4: Delayed transition has been quoted in lieu of open transition with in-phase monitoring as per customer.
6. Standard delivery 5 to 6 weeks after final approval; for expedited delivery requirements please consult ASCO.
7. Net price does not include commissioning; if required please consult ASCO.
8. Warranty coverage is two years from date of shipment; if extended warranty required please consult ASCO.
9. Installation & all external wiring to be provided by others.

General Notes:

1. Prices do not include taxes. Terms of payment **NET** 30 days.
2. Prices do not include special conductor entry provisions and special terminations unless otherwise specified; Solder-less set screw type cable lugs included.
3. Prices are based on delivery requirements not longer than 6 months after receipt of order. An order, which extends the 6-month period, will be invoiced at prices in effect at time of shipment unless otherwise specified.
4. This proposal is based upon information provided. Plans and specifications may not have been consulted by ASCO Power Technologies Canada. Please verify that the equipment quoted is as specified.
5. Quotations are firm for 30 days from date of quotation unless otherwise specified and are subject to ASCO Power Technologies Canada standard Terms and conditions of Sales. A copy is available upon request.
6. Upon receipt of an order, ASCO Power Technologies Canada requires all data pertinent to the order. Failure to supply all required information may cause delays in shipping.
7. Freight: Enclosed Motor Freight of ASCO Power Technologies Canada choice is included to all major centres within Canada excluding Yukon, NWT & Nanuvut; FOB Brantford, ON. Any other shipping methods are to be requested at time of order; all associated charges are additional to the quoted price.

Division of Emerson Electric Canada Limited

Page 1 of 1

SHOP DRAWING REVIEW
THIS DRAWING HAS BEEN REVIEWED FOR GENERAL CONFORMANCE WITH THE DESIGN CONCEPT ONLY. SUCH REVIEW SHALL NOT RELIEVE THE CONTRACTOR OF HIS RESPONSIBILITY FOR ERRORS OR OMISSIONS OR OF MEETING THE REQUIREMENTS OF THE CONTRACT DOCUMENTS. NO RESPONSIBILITY IS ASSUMED FOR CORRECTNESS OF DIMENSIONS OR DETAILS.

☒	NO COMMENT
☐	SEE COMMENTS
☐	AMEND & RESUBMIT
☐	REJECTED

Submission No.

Project No.

By

Date

07-8407
Truitt
June 4/10

DILLON CONSULTING LIMITED

