


AIRPORT COMMUNITY ROAD
WASHOUT REHABILITATION PROJECT
CORAL HARBOUR, NU

SPILL CONTINGENCY & EMERGENCY RESPONSE PLAN

ISSUED FOR USE
APRIL 2016



TETRA TECH EBA

FILE NO.: 704-V13203282-01.001

This page intentionally left blank.

EXECUTIVE SUMMARY

This document is the Spill Contingency and Emergency Response Plan (Plan) for the proposed Airport Community Road Washout Rehabilitation Project located near Coral Harbour, on Southampton Island Nunavut. This Plan was prepared by Tetra Tech EBA Inc. (Tetra Tech EBA) on behalf of the Department of Community and Government Services (CGS) of the Government of Nunavut for use by the contractor to be retained to implement the Project in 2016.

This Plan has been prepared in general accordance with the Federal Government's Guidelines for Spill Contingency Planning (AANDC 2007). All project employees and contractors are required to familiarize themselves with this plan.

The Plan serves to formalize the actions to be taken in the event of a spill of hydrocarbon product, other hazardous material or emergency. The responsibilities of key personnel are defined, along with procedures for spill and emergency response that will minimize hazards to health and safety, damage to the environment and clean-up costs. This plan has been prepared to provide easy access to the required information needed for effective spill and emergency response.

TABLE OF CONTENTS

EXECUTIVE SUMMARY	i
1.0 SPILL CONTINGENCY PLAN	1
1.1 Introduction	1
1.2 Spill Reporting.....	1
1.3 Spill Response Personnel.....	2
1.3.1 Construction Foreman Responsibilities	3
1.3.2 Construction Manager Responsibilities	3
1.3.3 Government of Nunavut CGS Responsibilities.....	4
1.3.4 Environmental Monitor Responsibilities.....	4
1.4 Initial Spill Response Procedures	5
1.4.1 Spills on Land	5
1.4.2 Spills on Snow	6
1.4.3 Spills on Water.....	6
1.5 Spill Response Equipment.....	6
1.6 Training	7
1.7 Materials Safety Data Sheets (MSDS)	7
1.8 Fuel Management.....	7
1.9 Waste Management (Including Hazardous Wastes and Potentially Contaminated Soils)	8
2.0 EMERGENCY RESPONSE PLAN	9
2.1 Emergency Communications.....	9
2.2 Emergency Action Plan	9
2.2.1 General Actions for Initial Response	9
2.2.2 Priorities for Response	9
2.2.3 General Emergency Response Guidelines	10
REFERENCES	11

LIST OF TABLES IN TEXT

Table 1: Response Resources and Regulatory Contact Numbers.....	2
Table 2: Key Spill Response Personnel.....	3
Table 3: Emergency Contact Numbers	9

APPENDIX SECTIONS

FIGURES

Figure 1	Site Location and Drainage Plan
Figure 2	Proposed Site Plan

APPENDICES

- Appendix A Tetra Tech's General Conditions
- Appendix B NT-NU Spill Report Form
- Appendix C Materials Safety Data Sheets

LIMITATIONS OF PLAN

This Spill Contingency and Emergency Response Plan and its contents are intended for the sole use of the Department of Community and Government Services (CGS) of the Government of Nunavut and their agents. Tetra Tech EBA Inc. (Tetra Tech EBA) does not accept any responsibility for the accuracy of any of the data, the analysis, or the recommendations contained or referenced in the report when the Plan is used or relied upon by any Party other than the CGS, or for any Project other than the proposed development at the subject site. Any such unauthorized use of this Plan is at the sole risk of the user. Use of this Plan is subject to the terms and conditions stated in Tetra Tech EBA's Services Agreement. Tetra Tech EBA's General Conditions are provided in Appendix A of this document.

1.0 SPILL CONTINGENCY PLAN

1.1 Introduction

The spill contingency component of this Spill Contingency and Emergency Response Plan has been prepared in general accordance with the Federal Government's Guidelines for Spill Contingency Planning (AANDC 2007). All project employees and contractors are required to familiarize themselves with this plan.

The Spill Contingency Plan serves to formalize the actions to be taken in the event of a spill of hydrocarbon product or other hazardous material. The responsibilities of key personnel are defined, along with procedures for spill response that will minimize hazards to health and safety, damage to the environment and clean-up costs. This plan has been prepared to provide easy access to the required information needed for effective spill response.

Equipment to be used for the proposed construction program includes one excavator, two/three dump trucks, one loader and several pick-up trucks. Fuel types used by these types of equipment include diesel and gasoline. Other materials used will include lubricants, hydraulic fluids and anti-freeze for equipment operation.

To minimize the risk of leaks or spills, the following preventative measures should be implemented:

- A pre-construction meeting should be held to identify all materials of a deleterious nature that could be spilled;
- Hazardous materials and wastes must be stored in covered containers and in secondary containment;
- Appropriate spill cleanup materials should be readily available and easily accessible;
- Construction team members should be aware of the materials required to clean up various spills; and,
- If a spill occurs, stop work immediately to respond. Action should be taken to contain the spill and then, if necessary, reported.

In addition, to minimize the risk of leaks or spills:

- Equipment and machinery should be in good operating condition (power washed), free of leaks, excess oil and grease;
- Equipment should operate above the high water mark of all watercourses. Where instream work is necessary (and has been approved through appropriate regulatory processes) equipment should work from a dry location such as a gravel bar or from an area that has been isolated and dewatered where possible;
- No equipment servicing should be undertaken within 30 m of any watercourse;
- Refueling of equipment should occur on land at least 30 m from any watercourse.; and,
- A spill containment kit should be readily accessible onsite in the event of a release of a deleterious substance to the environment. All members of the construction team should be trained in its use.

1.2 Spill Reporting

Any spill of a substance that is toxic, polluting, or deleterious to aquatic life of reportable quantities must immediately be reported to the Nunavut Spill Report Line at **867-920-8130** – 24 hours a day. It is also necessary to complete a spill report form and fax it to 867-873-6924 or email it to spills@gov.nt.ca.

A copy of the NT-NU Spill Report form is provided in Appendix B.

If the spill is over 100 L of fuel, or if you do not know how much was spilled, you are legally required to report it.

When reporting a spill, the caller should be prepared to provide the following information, if possible:

- Your name and contact phone number;
- Location and time of the spill;
- Description of the spill location and surrounding area;
- Type and quantity of the substance spilled;
- Cause and anticipated effect of the spill;
- Details of containment/response actions taken or proposed;
- Names of agencies on scene or contacted; and
- Names of other persons or agencies advised or to be advised concerning the spill.

In addition to calling the Nunavut Spill Report Line, depending on the nature and potential environmental consequences of the spill incident, Table 1 provides a list of response resources and regulatory contacts that will be contacted for information reporting or response assistance as appropriate.

Table 1: Response Resources and Regulatory Contact Numbers

Agency	Phone Number
Health Centre - Coral Harbour	(867) 925-9916
RCMP - Coral Harbour detachment	(867) 925-0123
Fire Department - Coral Harbour	(867) 925-4422
Search and Rescue	(867) 925-8045
Coral Harbour Hamlet Office	(867) 925 8867
Environment and Climate Change Canada	(867) 975-4638
Department of Fisheries and Oceans	(867) 979-8000
GN Department of Environment	(867) 975-7700
Nunavut Spill Report Line	(867) 920-8130

1.3 Spill Response Personnel

Effective response to a spill incident requires a well-coordinated effort from all individuals involved. The following sections outline the responsibilities of key personnel involved with the Project.

Because of the limited human resources associated with this small project, the key personnel identified in Table 2 will lead any spill response activities as may be required. The site response personnel will be drawn from the contractor's resources and as necessary other personnel to be brought in from the Hamlet of Coral Harbour.

Table 2: Key Spill Response Personnel

Name	Role	Phone Number
TBD	Construction Foreman	TBD
David Moschini	Construction Manager	778-875-4842
Ashwani Sharma	CGS Representative	867 645 8180
TBD	Environmental Monitor	TBD

1.3.1 Construction Foreman Responsibilities

The Project Construction Foreman (Construction Foreman) will undertake and supervise construction activities and is responsible for adherence to the project design, including environmental mitigation measures.

In the event of a spill or other emergency incident, the following are the main responsibilities assumed by the Construction Foreman with respect to environmental protection, spill incident response and management:

- The Construction Foreman will review the contents of this Spill Contingency and Emergency Response Plan with their staff and sub-contractors prior to undertaking any work;
- The Construction Foreman will ensure that the Project conforms with all laws, orders, rules, regulations, and codes of Territorial or Federal environmental agencies or like authorities, which are applicable to the Project;
- Upon becoming aware of a spill or emergency incident, the Construction Foreman will assess the situation and initiate notification and response activities;
- The Construction Foreman will ensure that the Construction Manager and GN CGS are immediately notified;
- The Construction Foreman will lead the spill containment/cleanup effort and the response activities to be implemented by the construction crew;
- The Construction Foreman will identify the need for additional supplies and resources as may be required;
- The Construction Foreman will arrange provision of appropriate on-site waste containers and appropriate disposal at approved locations (e.g. the existing contaminated soil land farm at Coral Harbour); and,
- The Construction Foreman will be responsible for the restoration of all disturbed areas resulting from any of spill response activities undertaken.

1.3.2 Construction Manager Responsibilities

The Construction Manager will oversee the construction program and will support the Construction Foreman in the event of a spill or emergency incident. The following are the main responsibilities assumed by the Construction Manager with respect to environmental protection, spill incident response and management:

- The Construction Manager will provide management support for the Construction Foreman as appropriate to ensure effective response to the spill or emergency incident;
- Upon being notified of the incident by the Construction Foreman, the Construction Manager will immediately report the incident to the GN CGS Contact and the Nunavut Spill Report Line at **867-920-8130**;

- The Construction Manager will ensure completion of the required spill report form and fax it to 867-873-6924 or email it to spills@gov.nt.ca;
- The Construction Manager will keep the GN CGS informed of cleanup activities;
- The Construction Manager will assist the Construction Foreman in obtaining additional required resources not available onsite for spill response and cleanup;
- The Construction Manager will serve as the spokesperson with government agencies as appropriate;
- The Construction Manager will assist in documenting the cause of the spill and effectiveness of the cleanup effort, and recommend appropriate measures to prevent a recurrence of the spill; and,
- The Construction Manager will ensure that follow-up documentation required by regulators is prepared and submitted as appropriate.

1.3.3 Government of Nunavut CGS Responsibilities

The Government of Nunavut CGS representative will provide high-level management support and government oversite for the response effort as appropriate to ensure effective response to the spill or emergency incident. In addition:

- The CGS representative will assist the overall response effort in obtaining additional required resources not available onsite for spill response and cleanup;
- The CGS representative will monitor the actions of the Construction Manager and Construction Foreman and assist with government agency communications as appropriate;
- The CGS representative will ensure the coordination and establishment of an incident debriefing session; and,
- The CGS representative will be responsible for media relations as may be needed for the duration of the incident response and remediation efforts.

1.3.4 Environmental Monitor Responsibilities

The construction Environmental Monitor is responsible for ensuring that all construction activities adhere to the regulatory conditions of the Nunavut Water Board Water Licence, as well as the general environmental protection and legislative requirements of the Territorial and Federal governments.

In the event of a spill or other emergency incident, the following are the main responsibilities assumed by the Environmental Monitor with respect to environmental protection, spill incident response and management:

- The Environmental Monitor will assist the Construction Foreman in evaluating the initial situation and assessing the magnitude of the spill incident;
- The Environmental Monitor will assist in developing an overall plan of action including the identification of measures to protect potentially threatened environmental resources;
- The Environmental Monitor will collect photographic records of the spill event and cleanup efforts;
- The Environmental Monitor will provide recommendations on resource requirements (additional manpower, equipment, material) to complete the cleanup effort;

- The Environmental Monitor will document the cause of the spill and effectiveness of the cleanup effort, and recommend the appropriate measures to prevent a recurrence of the spill; and,
- The Environmental Monitor will prepare and submit follow-up documentation required by appropriate regulators.

1.4 Initial Spill Response Procedures

Initial spill response procedures include:

- **Assess safety** – ensure unnecessary people are kept clear of the area and that people with proper training and equipment deal with the spill. Put on any required personal protective equipment and consult Material Safety Data Sheets;
- **Stop the source** – if required, and when it is safe to do so, stop the spill at its source. This may simply be righting an overturned container or sealing a hole;
- **Contain and control the spill** – the spill should be prevented from infiltrating into the ground or entering a watercourse. If the spill occurs on water, booms should be deployed to prevent its spread;
- **Clean up the spill** – utilize appropriate absorbent pads or other materials based on the type of substance spilled. The method of disposing of the waste is dependent on the amount and type of deleterious substance that was spilled;
- **Notify appropriate authority** – spills of a reportable quantity must be reported to the Nunavut Spill Report Line. Minor spills should be immediately reported to the Construction Foreman; and
- **Record the incident** – make a note of what, how and where the incident happened as well as what was done to clean it up.

The Construction Foreman must be familiar with the Spill Contingency Plan and should ensure that the entire construction team is aware of the Plan and its contents.

1.4.1 Spills on Land

Spills on land should be contained as close to the source as possible with every effort being made to ensure that a spill does not reach water (taking into account the safety of everyone involved). Spills on land should be contained and cleaned up as follows:

- Construct a temporary berm/barrier down slope of spilled material (typically fuel);
- Place impermeable material (e.g. liner) at the foot of and over top of the berm to allow pooling of spilled material;
- Use appropriate absorbent material to soak up the fuel. It may also be possible to transfer fuel into drums or pails for re-use of the pads. Larger quantities of fuel may be pumped into empty drums;
- Use a light covering of absorbent material (e.g. absorbent pads or kitty litter) to remove films of petroleum products; and
- Collected material must be transported to an approved disposal/recovery site.

1.4.2 Spills on Snow

Containment on snow is readily achieved and is generally very effective due to its natural absorbent qualities. Liquid spills (petroleum) will become immobile within the snow and can be easily removed for transport and recovery or disposal. Spills on snow should be contained and cleaned up as follows:

- Construct a trench or ditch in the snow to channel and control the flow of spilled product;
- Compact any snow lying along the outside perimeter of the control ditch;
- Construct a snow dyke or dam;
- Use impermeable lining material to create an impervious barrier;
- Locate the topographic lowest point of the spill area and create snow channels to direct unabsorbed material away from water courses; and
- Collect the contaminated snow for disposal or product recovery.

1.4.3 Spills on Water

Spills on water should be contained and cleaned up as follows:

- Contain spill as close to release point as possible;
- Use floating booms obtained from spill kit for containment;
- Use absorbent pads to capture/recover floating product;
- Place contaminated absorbent pads in a container for subsequent disposal; and
- Dispose of fuel-soaked materials in a timely manner.

1.5 Spill Response Equipment

Available construction equipment (excavator, two/three dump trucks, one loader and several pick-up trucks) and supplies will be used as appropriate for emergency use to assist in responding to a spill incident. A suitably equipped spill kit will be located at the active construction site to assist with rapid response. The typical inventory of a spill kit contains the following items:

- One (1) 16 Gauge Open-Top Drum with Bolting Ring and Gasket (205 litre)
- One (1) Pkg. of 10 Disposable Polyethylene Bags (5 mil)
- One (1) Shovel (spark proof)
- Four (4) 5" x 10' Absorbent Booms
- One (1) 10 lb. Bag of Absorbent Particulate (e.g. Speedy Dry)
- One (1) Bail of 17' x 19' x d = Sorbent Pads (100 pads)
- Two (2) PVC Oil Resistant Gloves
- Two (2) Respirators
- Two (2) Pairs Splash Protective Goggles.

Additional spill response resources, including spill kits, are available from the Coral Harbour Main Site Bulk Storage Facility and the Airport Fuel Depot Facility. Both of these facilities are owned by the Government of Nunavut Petroleum Products Division.

1.6 Training

The construction equipment operators must have a valid equipment operator licence. The Construction Foreman must be trained and aware of all applicable health, safety, and environmental requirements and regulations. All project personnel will be oriented as to the location of spill kits, their contents and use, potential and nature of spill hazards, and locally available spill control materials. In addition, all project personnel will be familiarized with documented procedures.

1.7 Materials Safety Data Sheets (MSDS)

The MSDS sheets for diesel, gasoline, hydraulic fluid and anti-freeze are provided in Appendix C of this Spill Contingency and Emergency Response Plan.

1.8 Fuel Management

Potential environmental risks from the transportation, storage, and transfer of fuel can be minimized by adhering to the following measures:

- Equipment should not be fuelled within 30 m of a waterbody. If possible, one area should be designated for fuel transfer. Refuelling should occur on a flat surface to minimize potential off-site runoff;
- All fuels, oils, lubricants and other petrochemical products should not be stored within 30 m of any waterbody;
- Refuelling equipment and tanks should be clean and in good working order. Fuel tanks should be situated within appropriate secondary containment (an impermeable containment facility capable of holding 110% of the storage tank contents). This may be achieved through the use of double-walled storage tanks or sit-in containers constructed out of impermeable material, such as aluminum or plastic;
- Fuel storage containers and equipment should be inspected daily for leaks and wear points, kept clean and any measurable rainwater removed and disposed of appropriately. If practical, the containment area should be covered to prevent infilling with rainwater. Where leaks and/or wear points are found, they should be repaired promptly to restore full containment;
- Small containers (i.e., jerry cans) should be stored in a secure location, protected from weather. These containers must be designed solely for the purpose of storing and pouring fuel and should not be more than five years old. Containers must not leak and must be sealed with a proper fitting cap or lid;
- Tanks, hoses and connections should be inspected before use. All hose connections should be wrapped and secured with absorbent pads during fuel/oil transfers. All hoses, valves and equipment should be kept in a containment area whenever possible. Hose length and the number of connections should be minimized. Dripless connections should be used if possible and hoses should be drained upon completion of work;
- Smoking is not permitted during refuelling or near fuel storage areas; and
- Spill kits should be available on equipment and at the site. Construction team members should be trained in their use.

1.9 Waste Management (Including Hazardous Wastes and Potentially Contaminated Soils)

- Contractors are expected to adhere to all applicable legislation with respect to the handling, transportation, and/or disposal of all materials related to this Project (waste or otherwise). These regulations may include (but not be limited to) the Spill Reporting Regulations, Workers' Safety and Compensation Commission Regulations, and Transportation of Dangerous Goods Regulations;
- Hazardous wastes generated could include waste petroleum products (engine oils, lubricants) from machinery and equipment, spent batteries, solvents and cleaning agents, etc. Contractors should provide labelled separate container(s) for potentially hazardous waste such as oily rags and hydrocarbon absorbent pads;
- All hydrocarbon products and other hazardous wastes potentially present during project activities should be identified and the associated Workplace Hazardous Materials Information System (WHMIS) and Materials Safety Data Sheets (MSDS) made available to all Project members;
- Any waste considered to be hazardous will be labeled and disposed of according to the WHMIS criteria and the Transportation of Dangerous Goods (TDG) Regulations;
- Non-hazardous construction waste should be collected at designated areas on the site and removed to appropriate facilities on a regular basis;
- Maintain a tidy work area to minimize loose waste from leaving the Site;
- Recycle materials whenever possible;
- Waste materials should not be buried or burned; and
- If hazardous or contaminated material (including suspect soils) is encountered stop work immediately and report it to the Construction Foreman and Environmental Monitor who will determine appropriate BMPs. Hazardous materials should only be handled by appropriately trained personnel.

2.0 EMERGENCY RESPONSE PLAN

2.1 Emergency Communications

Table 3 lists emergency contact numbers. Recognizing that cell phone service is not available at the project site, alternative means of contact, such as radio or satellite phone, should be planned.

Table 3: Emergency Contact Numbers

Agency	Phone Number
Health Centre - Coral Harbour	(867) 925-9916
RCMP - Coral Harbour detachment	(867) 925-0123
Fire Department - Coral Harbour	(867) 925-4422
Search and Rescue	(867) 925-8045
Coral Harbour Hamlet Office	(867) 925-8867
Environment and Climate Change Canada	(867) 975-4638
Department of Fisheries and Oceans	(867) 979-8000
GN Department of Environment	(867) 975-7700
Nunavut Spill Report Line	(867) 920-8130

2.2 Emergency Action Plan

Potential emergencies may include but are not limited to:

- Vehicle or construction equipment accident
- Personnel injury
- Reportable fuel or chemical spills.

2.2.1 General Actions for Initial Response

- Immediately assess the situation for emergency medical and/or spill response needs
- Initiate notification and reporting to Construction Foreman who will initiate contact with emergency resources identified in Table 3 as applicable
- Monitor for changes in seriousness of the incident while awaiting response assistance.

2.2.2 Priorities for Response

- Safety of personnel and residents
- Protection of the Environment
- Safety of equipment.

2.2.3 General Emergency Response Guidelines

- Ensure the safety of yourself and others – ensure the scene is safe;
- Shut off ignition sources – NO SMOKING
- Attend to injured. Begin first aid if required
- Identify the type of spilled material
- Assess the severity of the incident
- Keep unnecessary people out of the area

REFERENCES

Aboriginal Affairs and Northern Development Canada (AANDC). 2007. Guidelines for Spill Contingency Planning. http://www.aadnc-aandc.gc.ca/DAM/DAM-INTER-NWT/STAGING/texte-text/ntr_pubs SCP 1330712728397_eng.pdf

BC Ministry of Transportation and Infrastructure. 2013. Culverts and Fish Passage. http://www.th.gov.bc.ca/publications/eng_publications/environment/references/3824_CulvertFishPassage_Inf oSheet.pdf

Department of Fisheries and Oceans (DFO). 1985. *Fisheries Act*. Revised Feb. 2015. <http://www.dfo-mpo.gc.ca/pnw-ppe/changes-changements/index-eng.html>

Department of Fisheries and Oceans (DFO). 1992. Land Development Guidelines for the Protection of Aquatic Habitat. <http://www.dfo-mpo.gc.ca/Library/165353.pdf>

Environment and Climate Change Canada. Species at Risk Act. 2002. Revised May 2015. <https://www.ec.gc.ca/alef-ewe/default.asp?lang=en&n=ED2FFC37-1>

Environment and Climate Change Canada. Migratory Birds Convention Act. 1994. Revised Sept. 2015. <https://www.ec.gc.ca/alef-ewe/default.asp?lang=en&n=3DF2F089-1>

Nunavut Department of Environment. *Environmental Protection Act*. 1988. Revised March 2011. <http://www.canlii.org/en/nu/laws/stat/rsnwt-nu-1988-c-e-7/latest/rsnwt-nu-1988-c-e-7.html>

Nunavut Dept. of Environment. 1999. Environmental Guideline for the Management of Contaminated Sites. Revised Dec. 2014. http://gov.nu.ca/sites/default/files/contaminated_sites_remediation_2014.pdf

Nunavut Dept. of Environment. Contingency planning and spill reporting in Nunavut. Accessed on December 15, 2015 at <http://gov.nu.ca/sites/default/files/Spill%20Planning%20and%20Reporting%20Guide.pdf>


Tetra Tech EBA. 2015. Supplemental Information Report - Coral Harbour Airport Community Road Washout Rehabilitation Project, NU. Report prepared by Tetra Tech EBA for the Nunavut Department of Community and Government Services. December, 2015.

Tetra Tech EBA. 2016. Airport Road Washout Rehabilitation , Coral Harbour NU, Detailed Design Drawings Package. Prepared by Tetra Tech EBA for the Government of Nunavut. February 2016.

FIGURES

Figure 1 Site Location and Drainage Plan

Figure 2 Proposed Site Plan



DRAINAGE PLAN

SCALE: 1:10 000

LEGEND



Water Level Monitoring Location

NOTES

SCALE 1:10,000



100 0 100 200 400m

CLIENT



AIRPORT RD. WASHOUT REHABILITATION
CORAL HARBOUR, NU

SITE LOCATION AND DRAINAGE PLAN


PROJECT NO. V13203282 OFFICE VANC DES MAN CKD DNM REV DRAWING

TETRA TECH EBA BUCKLAND & TAYLOR COWI

DATE SHEET No. DWN APP STATUS

February 3, 2016 of JDM DNM -

Figure 1



SITE PLAN
SCALE: 1:2000

LEGEND	NOTES
SCALE 1:4000 	

NUM	DATE	DWN	CKD	APR	DESCRIPTION	REVISIONS

PROFESSIONAL SEAL



**AIRPORT RD. WASHOUT REHABILITATION
CORAL HARBOUR, NU**

PROPOSED SITE PLAN



PROJECT NO.	OFFICE	DES	CKD	REV	DRAWING
V13203282	VANC	MAN	DNM	0	Figure 2
DATE February 3, 2016	SHEET No. of	DWN JDM	APP DNM	STATUS -	

APPENDIX A

TETRA TECH'S GENERAL CONDITIONS

GENERAL CONDITIONS

GEOENVIRONMENTAL REPORT

This report incorporates and is subject to these “General Conditions”.

1.0 USE OF REPORT AND OWNERSHIP

This report pertains to a specific site, a specific development, and a specific scope of work. It is not applicable to any other sites, nor should it be relied upon for types of development other than those to which it refers. Any variation from the site or proposed development would necessitate a supplementary investigation and assessment.

This report and the assessments and recommendations contained in it are intended for the sole use of Tetra Tech EBA's client. Tetra Tech EBA does not accept any responsibility for the accuracy of any of the data, the analysis or the recommendations contained or referenced in the report when the report is used or relied upon by any party other than Tetra Tech EBA's Client unless otherwise authorized in writing by Tetra Tech EBA. Any unauthorized use of the report is at the sole risk of the user.

This report is subject to copyright and shall not be reproduced either wholly or in part without the prior, written permission of Tetra Tech EBA. Additional copies of the report, if required, may be obtained upon request.

2.0 ALTERNATE REPORT FORMAT

Where Tetra Tech EBA submits both electronic file and hard copy versions of reports, drawings and other project-related documents and deliverables (collectively termed Tetra Tech EBA's instruments of professional service), only the signed and/or sealed versions shall be considered final and legally binding. The original signed and/or sealed version archived by Tetra Tech EBA shall be deemed to be the original for the Project.

Both electronic file and hard copy versions of Tetra Tech EBA's instruments of professional service shall not, under any circumstances, no matter who owns or uses them, be altered by any party except Tetra Tech EBA. The Client warrants that Tetra Tech EBA's instruments of professional service will be used only and exactly as submitted by Tetra Tech EBA.

Electronic files submitted by Tetra Tech EBA have been prepared and submitted using specific software and hardware systems. Tetra Tech EBA makes no representation about the compatibility of these files with the Client's current or future software and hardware systems.

3.0 NOTIFICATION OF AUTHORITIES

In certain instances, the discovery of hazardous substances or conditions and materials may require that regulatory agencies and other persons be informed and the client agrees that notification to such bodies or persons as required may be done by Tetra Tech EBA in its reasonably exercised discretion.

4.0 INFORMATION PROVIDED TO TETRA TECH EBA BY OTHERS

During the performance of the work and the preparation of the report, Tetra Tech EBA may rely on information provided by persons other than the Client. While Tetra Tech EBA endeavours to verify the accuracy of such information when instructed to do so by the Client, Tetra Tech EBA accepts no responsibility for the accuracy or the reliability of such information which may affect the report.

APPENDIX B

NT-NU SPILL REPORT FORM



Canada

NT-NU SPILL REPORT

OIL, GASOLINE, CHEMICALS AND OTHER HAZARDOUS MATERIALS

NT-NU 24-HOUR SPILL REPORT LINE

TEL: (867) 920-8130

FAX: (867) 873-6924

EMAIL: spills@gov.nt.ca

REPORT LINE USE ONLY

A	REPORT DATE: MONTH – DAY – YEAR		REPORT TIME		<input type="checkbox"/> ORIGINAL SPILL REPORT, OR <input type="checkbox"/> UPDATE # _____ TO THE ORIGINAL SPILL REPORT	REPORT NUMBER _____ - _____
B	OCCURRENCE DATE: MONTH – DAY – YEAR		OCCURRENCE TIME			
C	LAND USE PERMIT NUMBER (IF APPLICABLE)		WATER LICENCE NUMBER (IF APPLICABLE)			
D	GEOGRAPHIC PLACE NAME OR DISTANCE AND DIRECTION FROM NAMED LOCATION		REGION <input type="checkbox"/> NWT <input type="checkbox"/> NUNAVUT <input type="checkbox"/> ADJACENT JURISDICTION OR OCEAN			
E	LATITUDE DEGREES	MINUTES	SECONDS	LONGITUDE DEGREES	MINUTES	SECONDS
F	RESPONSIBLE PARTY OR VESSEL NAME		RESPONSIBLE PARTY ADDRESS OR OFFICE LOCATION			
G	ANY CONTRACTOR INVOLVED		CONTRACTOR ADDRESS OR OFFICE LOCATION			
H	PRODUCT SPILLED		QUANTITY IN LITRES, KILOGRAMS OR CUBIC METRES		U.N. NUMBER	
I	SECOND PRODUCT SPILLED (IF APPLICABLE)		QUANTITY IN LITRES, KILOGRAMS OR CUBIC METRES		U.N. NUMBER	
J	SPILL SOURCE		SPILL CAUSE		AREA OF CONTAMINATION IN SQUARE METRES	
K	FACTORS AFFECTING SPILL OR RECOVERY					
L	DESCRIBE ANY ASSISTANCE REQUIRED		HAZARDS TO PERSONS, PROPERTY OR ENVIRONMENT			
M	ADDITIONAL INFORMATION, COMMENTS, ACTIONS PROPOSED OR TAKEN TO CONTAIN, RECOVER OR DISPOSE OF SPILLED PRODUCT AND CONTAMINATED MATERIALS					
N	REPORTED TO SPILL LINE BY POSITION STATION OPERATOR		EMPLOYER		LOCATION CALLING FROM	TELEPHONE
M	ANY ALTERNATE CONTACT POSITION		EMPLOYER		ALTERNATE CONTACT LOCATION	ALTERNATE TELEPHONE

REPORT LINE USE ONLY

N	RECEIVED AT SPILL LINE BY POSITION STATION OPERATOR	EMPLOYER	LOCATION CALLED YELLOWKNIFE, NT	REPORT LINE NUMBER (867) 920-8130
LEAD AGENCY <input type="checkbox"/> EC <input type="checkbox"/> CCG <input type="checkbox"/> GNWT <input type="checkbox"/> GN <input type="checkbox"/> ILA <input type="checkbox"/> INAC <input type="checkbox"/> NEB <input type="checkbox"/> TC			SIGNIFICANCE <input type="checkbox"/> MINOR <input type="checkbox"/> MAJOR <input type="checkbox"/> UNKNOWN	FILE STATUS <input type="checkbox"/> OPEN <input type="checkbox"/> CLOSED
AGENCY		CONTACT NAME	CONTACT TIME	REMARKS
LEAD AGENCY				
FIRST SUPPORT AGENCY				
SECOND SUPPORT AGENCY				
THIRD SUPPORT AGENCY				

APPENDIX C

MATERIALS SAFETY DATA SHEETS

1. Diesel Fuel
2. Gasoline
3. Hydraulic Fluid
4. Anti-freeze

Material Safety Data Sheet

DIESEL FUEL



1 . Product and company identification

Product name	: DIESEL FUEL
Synonym	: Seasonal Diesel, #1 Diesel, #2 Heating Oil, #1 Heating Oil, D50, D60, P40, P50, Arctic Diesel, Farm Diesel, Marine Diesel, Low Sulphur Diesel, LSD, Ultra Low Sulphur Diesel, ULSD, Mining Diesel, Naval Distillate, Dyed Diesel, Marked Diesel, Coloured Diesel, Furnace special, Biodiesel blend, B1, B2, B5, Diesel Low Cloud (LC).
Code	: W104, W293; SAP: 120, 121, 122, 125, 126, 129, 130, 135, 287, 288
Material uses	: Diesel fuels are distillate fuels suitable for use in high and medium speed internal combustion engines of the compression ignition type. Mining Diesel has a higher flash point requirement, for safe use in underground mines.
Manufacturer	: PETRO-CANADA P.O. Box 2844 150 – 6th Avenue South-West Calgary, Alberta T2P 3E3
<u>In case of emergency</u>	: Petro-Canada: 403-296-3000 Canutec Transportation: 613-996-6666 Poison Control Centre: Consult local telephone directory for emergency number(s).

2 . Hazards identification

Physical state	: Bright oily liquid.
Odour	: Mild petroleum oil like.
WHMIS (Canada)	:   Class B-3: Combustible liquid with a flash point between 37.8°C (100°F) and 93.3°C (200°F). Class D-2A: Material causing other toxic effects (Very toxic). Class D-2B: Material causing other toxic effects (Toxic).
OSHA/HCS status	: This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).
Emergency overview	: WARNING! COMBUSTIBLE LIQUID AND VAPOUR. CAUSES EYE AND SKIN IRRITATION. Combustible liquid. Severely irritating to the skin. Irritating to eyes. Keep away from heat, sparks and flame. Do not get in eyes. Avoid breathing vapour or mist. Avoid contact with skin and clothing. Use only with adequate ventilation. Wash thoroughly after handling.
Routes of entry	: Dermal contact. Eye contact. Inhalation. Ingestion.
<u>Potential acute health effects</u>	
Inhalation	: Inhalation of this product may cause respiratory tract irritation and Central Nervous System (CNS) Depression, symptoms of which may include; weakness, dizziness, slurred speech, drowsiness, unconsciousness and in cases of severe overexposure; coma and death.
Ingestion	: Ingestion of this product may cause gastro-intestinal irritation. Aspiration of this product may result in severe irritation or burns to the respiratory tract.
Skin	: Severely irritating to the skin.
Eyes	: Irritating to eyes.
<u>Potential chronic health effects</u>	
Chronic effects	: No known significant effects or critical hazards.
Carcinogenicity	: Diesel engine exhaust particulate is probably carcinogenic to humans (IARC Group 2A).
Mutagenicity	: No known significant effects or critical hazards.
Teratogenicity	: No known significant effects or critical hazards.

2 . Hazards identification

Developmental effects : No known significant effects or critical hazards.

Fertility effects : No known significant effects or critical hazards.

Medical conditions aggravated by over-exposure : Avoid prolonged or repeated skin contact to diesel fuels which can lead to dermal irritation and may be associated with an increased risk of skin cancer.

See toxicological information (section 11)

3 . Composition/information on ingredients

<u>Name</u>	<u>CAS number</u>	<u>%</u>
Kerosine (petroleum), hydrodesulfurized / Fuels, diesel / Fuel Oil No. 2	64742-81-0 / 68334-30-5 / 68476-30-2	95 - 100
Fatty acids methyl esters	61788-61-2 / 67784-80-9 / 73891-99-3	0 - 5

There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health or the environment and hence require reporting in this section.

4 . First-aid measures

Eye contact : Check for and remove any contact lenses. Immediately flush eyes with plenty of water for at least 15 minutes, occasionally lifting the upper and lower eyelids. Get medical attention immediately.

Skin contact : In case of contact, immediately flush skin with plenty of water for at least 15 minutes while removing contaminated clothing and shoes. Wash skin thoroughly with soap and water or use recognised skin cleanser. Wash clothing before reuse. Clean shoes thoroughly before reuse. Get medical attention immediately.

Inhalation : Move exposed person to fresh air. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. Loosen tight clothing such as a collar, tie, belt or waistband. Get medical attention immediately.

Ingestion : Wash out mouth with water. Do not induce vomiting unless directed to do so by medical personnel. Never give anything by mouth to an unconscious person. Get medical attention immediately.

Protection of first-aiders : No action shall be taken involving any personal risk or without suitable training. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation.

Notes to physician : No specific treatment. Treat symptomatically. Contact poison treatment specialist immediately if large quantities have been ingested or inhaled.

5 . Fire-fighting measures

Flammability of the product : Combustible liquid

Extinguishing media

Suitable : Use dry chemical, CO₂, water spray (fog) or foam.

Not suitable : Do not use water jet.

Special exposure hazards : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool.

Products of combustion : Carbon oxides (CO, CO₂), nitrogen oxides (NO_x), sulphur oxides (SO_x), sulphur compounds (H₂S), smoke and irritating vapours as products of incomplete combustion.

Special protective equipment for fire-fighters : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

5 . Fire-fighting measures

Special remarks on fire hazards : Flammable in presence of open flames, sparks and heat. Vapours are heavier than air and may travel considerable distance to sources of ignition and flash back. This product can accumulate static charge and ignite.

Special remarks on explosion hazards : Do not pressurise, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition. Runoff to sewer may create fire or explosion hazard.

6 . Accidental release measures

Personal precautions : No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilt material. Shut off all ignition sources. No flares, smoking or flames in hazard area. Avoid breathing vapour or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment (see section 8).

Environmental precautions : Avoid dispersal of spilt material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

Methods for cleaning up

Small spill : Stop leak if without risk. Move containers from spill area. Dilute with water and mop up if water-soluble. Alternatively, or if water-insoluble, absorb with an inert dry material and place in an appropriate waste disposal container. Use spark-proof tools and explosion-proof equipment. Dispose of via a licensed waste disposal contractor.

Large spill : Stop leak if without risk. Move containers from spill area. Approach the release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see section 13). Use spark-proof tools and explosion-proof equipment. Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the same hazard as the spilt product. Note: see section 1 for emergency contact information and section 13 for waste disposal.

7 . Handling and storage

Handling : Put on appropriate personal protective equipment (see section 8). Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Do not ingest. Avoid contact with eyes, skin and clothing. Avoid breathing vapour or mist. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless adequately ventilated. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical (ventilating, lighting and material handling) equipment. Use non-sparking tools. Take precautionary measures against electrostatic discharges. To avoid fire or explosion, dissipate static electricity during transfer by earthing and bonding containers and equipment before transferring material. Empty containers retain product residue and can be hazardous. Do not reuse container.

Storage : Store in accordance with local regulations. Store in a segregated and approved area. Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see section 10) and food and drink. Eliminate all ignition sources. Separate from oxidizing materials. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabelled containers. Use appropriate containment to avoid environmental contamination. Ensure the storage containers are grounded/bonded.

8 . Exposure controls/personal protection

Ingredient	Exposure limits
Kerosine (petroleum), hydrodesulfurized	ACGIH TLV (United States). Absorbed through skin. TWA: 200 mg/m ³ 8 hour(s).
Fuels, diesel	ACGIH TLV (United States). Absorbed through skin. TWA: 100 mg/m ³ , (Inhalable fraction and vapour) 8 hour(s).
Fuel oil No. 2	ACGIH TLV (United States). Absorbed through skin. TWA: 100 mg/m ³ , (Inhalable fraction and vapour) 8 hour(s).

Consult local authorities for acceptable exposure limits.

Recommended monitoring procedures : If this product contains ingredients with exposure limits, personal, workplace atmosphere or biological monitoring may be required to determine the effectiveness of the ventilation or other control measures and/or the necessity to use respiratory protective equipment.

Engineering measures : Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapour or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.

Hygiene measures : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

Personal protection

Respiratory : Use a properly fitted, air-purifying or air-fed respirator complying with an approved standard if a risk assessment indicates this is necessary. Respirator selection must be based on known or anticipated exposure levels, the hazards of the product and the safe working limits of the selected respirator. Recommended: organic vapour cartridge or canister may be permissible under certain circumstances where airborne concentrations are expected to exceed exposure limits. Protection provided by air-purifying respirators is limited. Use a positive-pressure, air-supplied respirator if there is any potential for uncontrolled release, exposure levels are unknown, or any other circumstances where air-purifying respirators may not provide adequate protection.

Hands : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Recommended: nitrile, neoprene, polyvinyl alcohol (PVA), Viton. Consult your PPE provider for breakthrough times and the specific glove that is best for you based on your use patterns. It should be realized that eventually any material regardless of their imperviousness, will get permeated by chemicals. Therefore, protective gloves should be regularly checked for wear and tear. At the first signs of hardening and cracks, they should be changed.

Eyes : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists or dusts.

Skin : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

Environmental exposure controls : Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

9 . Physical and chemical properties

Physical state	: Bright oily liquid.
Flash point	: Diesel fuel: Closed cup: $\geq 40^{\circ}\text{C}$ ($\geq 104^{\circ}\text{F}$) Marine Diesel Fuel: Closed Cup: $\geq 60^{\circ}\text{C}$ ($\geq 140^{\circ}\text{F}$) Mining Diesel: Closed Cup: $\geq 52^{\circ}\text{C}$ ($\geq 126^{\circ}\text{F}$)
Auto-ignition temperature	: 225°C (437°F)
Flammable limits	: Lower: 0.7% Upper: 6%
Colour	: Clear to yellow (This product may be dyed red for taxation purposes).
Odour	: Mild petroleum oil like.
Odour threshold	: Not available.
pH	: Not available.
Boiling/condensation point	: 150 to 371°C (302 to 699.8°F)
Melting/freezing point	: Not available.
Relative density	: 0.80 to 0.88 kg/L @ 15°C (59°F)
Vapour pressure	: 1 kPa (7.5 mm Hg) @ 20°C (68°F).
Vapour density	: 4.5 [Air = 1]
Volatility	: Semivolatile to volatile.
Evaporation rate	: Not available.
Viscosity	: Diesel fuel: 1.3 - 4.1 cSt @ 40°C (104°F) Marine Diesel Fuel: 1.3 - 4.4 cSt @ 40°C (104°F)
Pour point	: Not available.
Solubility	: Insoluble in cold water, soluble in non-polar hydrocarbon solvents.

10 . Stability and reactivity

Chemical stability	: The product is stable.
Hazardous polymerisation	: Under normal conditions of storage and use, hazardous polymerisation will not occur.
Materials to avoid	: Reactive with oxidising agents and acids.
Hazardous decomposition products	: May release CO _x , NO _x , SO _x , H ₂ S, smoke and irritating vapours when heated to decomposition.

11 . Toxicological information

Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
Kerosine (petroleum), hydrodesulfurized	LD50 Dermal LD50 Oral LC50 Inhalation Vapour	Rabbit Rat Rat	>2000 mg/kg >5000 mg/kg >5000 mg/m ³	- - 4 hours
Fuels, diesel	LD50 Dermal	Mouse	24500 mg/kg	-
	LD50 Oral	Rat	7500 mg/kg	-
Fuel oil No. 2	LD50 Oral	Rat	12000 mg/kg	-

Conclusion/Summary : Not available.

Chronic toxicity

Conclusion/Summary : Not available.

Irritation/Corrosion

Conclusion/Summary : Not available.

Sensitiser

Conclusion/Summary : Not available.

Carcinogenicity

Conclusion/Summary : Diesel engine exhaust particulate is probably carcinogenic to humans (IARC Group 2A).

11 . Toxicological information

Classification

Product/ingredient name	ACGIH	IARC	EPA	NIOSH	NTP	OSHA
Kerosine (petroleum), hydrodesulfurized	A3	-	-	-	-	-
Fuels, diesel	A3	3	-	-	-	-
Fuel oil No. 2	A3	3	-	-	-	-

Mutagenicity

Conclusion/Summary : Not available.

Teratogenicity

Conclusion/Summary : Not available.

Reproductive toxicity

Conclusion/Summary : Not available.

12 . Ecological information

Environmental effects : No known significant effects or critical hazards.

Aquatic ecotoxicity

Conclusion/Summary : Not available.

Biodegradability

Conclusion/Summary : Not available.

13 . Disposal considerations

Waste disposal

: The generation of waste should be avoided or minimised wherever possible. Empty containers or liners may retain some product residues. This material and its container must be disposed of in a safe way. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Avoid dispersal of spilt material and runoff and contact with soil, waterways, drains and sewers.

Disposal should be in accordance with applicable regional, national and local laws and regulations.

Refer to Section 7: HANDLING AND STORAGE and Section 8: EXPOSURE CONTROLS/PERSONAL PROTECTION for additional handling information and protection of employees.

14 . Transport information

Regulatory information	UN number	Proper shipping name	Classes	PG*	Label	Additional information
TDG Classification	UN1202	DIESEL FUEL	3	III		-
DOT Classification	Not available.	Not available.	Not available.	-		-

PG* : Packing group

15 . Regulatory information

United States

HCS Classification : Combustible liquid
Irritating material

Canada

WHMIS (Canada) : Class B-3: Combustible liquid with a flash point between 37.8°C (100°F) and 93.3°C (200°F).
Class D-2A: Material causing other toxic effects (Very toxic).
Class D-2B: Material causing other toxic effects (Toxic).

15 . Regulatory information

This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations and the MSDS contains all the information required by the Controlled Products Regulations.

International regulations


- Canada inventory** : All components are listed or exempted.
- United States inventory** : All components are listed or exempted.
- (TSCA 8b)**
- Europe inventory** : All components are listed or exempted.

16 . Other information

Label requirements : COMBUSTIBLE LIQUID AND VAPOUR. CAUSES EYE AND SKIN IRRITATION.

Hazardous Material Information System (U.S.A.)	<table border="1"> <tr> <td>Health</td><td>2</td></tr> <tr> <td>Flammability</td><td>2</td></tr> <tr> <td>Physical hazards</td><td>0</td></tr> <tr> <td>Personal protection</td><td>H</td></tr> </table>	Health	2	Flammability	2	Physical hazards	0	Personal protection	H
Health	2								
Flammability	2								
Physical hazards	0								
Personal protection	H								

National Fire Protection Association (U.S.A.) :



References : Available upon request.

TM Trademark of Suncor Energy Inc. Used under licence.

Date of printing : 7/6/2010.

Date of issue : 6 July 2010

Date of previous issue : 7/3/2009.

Responsible name : Product Safety - JDW

☒ Indicates information that has changed from previously issued version.

For Copy of (M)SDS : Internet: www.petro-canada.ca/msds

Canada-wide: telephone: 1-800-668-0220; fax: 1-800-837-1228

For Product Safety Information: (905) 804-4752

Notice to reader

To the best of our knowledge, the information contained herein is accurate. However, neither the above-named supplier, nor any of its subsidiaries, assumes any liability whatsoever for the accuracy or completeness of the information contained herein.

Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist.

Material Safety Data Sheet

GASOLINE, UNLEADED



1 . Product and company identification

Product name	: GASOLINE, UNLEADED
Synonym	: Regular, Unleaded Gasoline (US Grade), Mid-Grade, Plus, Super, WinterGas, SummerGas, Supreme, SuperClean WinterGas, RegularClean, PlusClean, Premium, marked or dyed gasoline, TQRUL, transitional quality regular unleaded, BOB, Blendstock for Oxygenate Blending
Code	: W102E, SAP: 102 to 117
Material uses	: Unleaded gasoline is used in spark ignition engines including motor vehicles, inboard and outboard boat engines, small engines such as chain saws and lawn mowers, and recreational vehicles.
Manufacturer	: PETRO-CANADA P.O. Box 2844 150 – 6th Avenue South-West Calgary, Alberta T2P 3E3
<u>In case of emergency</u>	: Petro-Canada: 403-296-3000 Canutec Transportation: 613-996-6666 Poison Control Centre: Consult local telephone directory for emergency number(s).

2 . Hazards identification

Physical state	: Clear liquid.
Odour	: Gasoline
WHMIS (Canada)	:   Class B-2: Flammable liquid Class D-2A: Material causing other toxic effects (Very toxic). Class D-2B: Material causing other toxic effects (Toxic).
OSHA/HCS status	: This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).
Emergency overview	: WARNING! FLAMMABLE LIQUID AND VAPOUR. CAUSES RESPIRATORY TRACT, EYE AND SKIN IRRITATION. CANCER HAZARD - CONTAINS MATERIAL WHICH CAN CAUSE CANCER. CONTAINS MATERIAL WHICH CAN CAUSE HERITABLE GENETIC EFFECTS. Flammable liquid. Irritating to eyes, respiratory system and skin. Keep away from heat, sparks and flame. Avoid exposure - obtain special instructions before use. Do not breathe vapour or mist. Avoid contact with eyes, skin and clothing. Contains material which can cause cancer. Risk of cancer depends on duration and level of exposure. Contains material which can cause heritable genetic effects. Use only with adequate ventilation. Keep container tightly closed and sealed until ready for use. Wash thoroughly after handling.
Routes of entry	: Dermal contact. Eye contact. Inhalation. Ingestion.
Potential acute health effects	
Inhalation	: Inhalation of this product may cause respiratory tract irritation. Inhalation of this product may cause respiratory tract irritation and Central Nervous System (CNS) Depression, symptoms of which may include; weakness, dizziness, slurred speech, drowsiness, unconsciousness and in cases of severe overexposure; coma and death.
Ingestion	: Ingestion of this product may cause gastro-intestinal irritation. Aspiration of this product may result in severe irritation or burns to the respiratory tract. Ingestion of this product may cause Central Nervous System (CNS) Depression, symptoms of which may include; weakness, dizziness, slurred speech, drowsiness, unconsciousness and in cases of severe overexposure; coma and death.

2 . Hazards identification

Skin : Irritating to skin.
Eyes : Irritating to eyes.

Potential chronic health effects

Chronic effects : This product contains an ingredient or ingredients, which have been shown to cause chronic toxic effects. Repeated or prolonged exposure to the substance can produce blood disorders.

Carcinogenicity : Contains material which can cause cancer. Risk of cancer depends on duration and level of exposure.

Mutagenicity : Contains material which can cause heritable genetic effects.

Teratogenicity : No known significant effects or critical hazards.

Developmental effects : No known significant effects or critical hazards.

Fertility effects : No known significant effects or critical hazards.

Medical conditions aggravated by over-exposure : Repeated or prolonged contact with spray or mist may produce chronic eye irritation and severe skin irritation. Repeated skin exposure can produce local skin destruction or dermatitis.

See toxicological information (section 11)

3 . Composition/information on ingredients

<u>Name</u>	<u>CAS number</u>	<u>%</u>
Gasoline	86290-81-5	85-100
Ethanol	64-17-5	0.1-1
Benzene	71-43-2	0.5-1.5
Toluene	108-88-3	15-40*

*Montreal: may vary from 3-40%

*Edmonton: may vary from 1-5%

There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health or the environment and hence require reporting in this section.

4 . First-aid measures

Eye contact : Check for and remove any contact lenses. Immediately flush eyes with plenty of water for at least 15 minutes, occasionally lifting the upper and lower eyelids. Get medical attention immediately.

Skin contact : In case of contact, immediately flush skin with plenty of water for at least 15 minutes while removing contaminated clothing and shoes. Wash skin thoroughly with soap and water or use recognised skin cleanser. Wash clothing before reuse. Clean shoes thoroughly before reuse. Get medical attention immediately.

Inhalation : Move exposed person to fresh air. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. Loosen tight clothing such as a collar, tie, belt or waistband. Get medical attention immediately.

Ingestion : Wash out mouth with water. Do not induce vomiting unless directed to do so by medical personnel. Never give anything by mouth to an unconscious person. Get medical attention immediately.

Protection of first-aiders : No action shall be taken involving any personal risk or without suitable training. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Wash contaminated clothing thoroughly with water before removing it, or wear gloves.

Notes to physician : No specific treatment. Treat symptomatically. Contact poison treatment specialist immediately if large quantities have been ingested or inhaled.

5 . Fire-fighting measures

Flammability of the product	: Flammable liquid (NFPA) .
<u>Extinguishing media</u>	
Suitable	: Use dry chemical, CO ₂ , water spray (fog) or foam.
Not suitable	: Do not use water jet.
Special exposure hazards	
	: Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool.
Products of combustion	
	: Carbon oxides (CO, CO ₂), nitrogen oxides (NO _x), polynuclear aromatic hydrocarbons, phenols, aldehydes, ketones, smoke and irritating vapours as products of incomplete combustion.
Special protective equipment for fire-fighters	
	: Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.
Special remarks on fire hazards	
	: Extremely flammable in presence of open flames, sparks, shocks, and heat. Vapours are heavier than air and may travel considerable distance to sources of ignition and flash back. Rapid escape of vapour may generate static charge causing ignition. May accumulate in confined spaces.
Special remarks on explosion hazards	
	: Do not pressurise, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition. Containers may explode in heat of fire. Vapours may form explosive mixtures with air.

6 . Accidental release measures

Personal precautions	: No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilt material. Shut off all ignition sources. No flares, smoking or flames in hazard area. Avoid breathing vapour or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment (see section 8).
Environmental precautions	: Avoid dispersal of spilt material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).
<u>Methods for cleaning up</u>	
Small spill	: Stop leak if without risk. Move containers from spill area. Dilute with water and mop up if water-soluble or absorb with an inert dry material and place in an appropriate waste disposal container. Use spark-proof tools and explosion-proof equipment. Dispose of via a licensed waste disposal contractor.
Large spill	: Stop leak if without risk. Move containers from spill area. Approach the release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see section 13). Use spark-proof tools and explosion-proof equipment. Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the same hazard as the spilt product. Note: see section 1 for emergency contact information and section 13 for waste disposal.

7 . Handling and storage

Handling	: Put on appropriate personal protective equipment (see section 8). Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Do not get in eyes or on skin or clothing. Do not ingest. Avoid breathing vapour or mist. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless adequately ventilated. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical
-----------------	---

7 . Handling and storage

(ventilating, lighting and material handling) equipment. Use non-sparking tools. Take precautionary measures against electrostatic discharges. To avoid fire or explosion, dissipate static electricity during transfer by earthing and bonding containers and equipment before transferring material. Empty containers retain product residue and can be hazardous. Do not reuse container.

Storage

- Store in accordance with local regulations. Store in a segregated and approved area. Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see section 10) and food and drink. Eliminate all ignition sources. Separate from oxidizing materials. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabelled containers. Use appropriate containment to avoid environmental contamination. Ensure the storage containers are grounded/bonded.

8 . Exposure controls/personal protection

Ingredient	Exposure limits
Gasoline	ACGIH TLV (United States). TWA: 300 ppm 8 hour(s). STEL: 500 ppm 15 minute(s).
Ethanol	ACGIH TLV (United States). STEL: 1000 ppm 15 minute(s).
Benzene	ACGIH TLV (United States). Absorbed through skin. TWA: 0.5 ppm 8 hour(s). STEL: 2.5 ppm 15 minute(s).
Toluene	ACGIH TLV (United States). TWA: 20 ppm 8 hour(s).

Consult local authorities for acceptable exposure limits.

Recommended monitoring procedures : If this product contains ingredients with exposure limits, personal, workplace atmosphere or biological monitoring may be required to determine the effectiveness of the ventilation or other control measures and/or the necessity to use respiratory protective equipment.

Engineering measures : Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapour or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.

Hygiene measures : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

Personal protection

Respiratory

- Use a properly fitted, air-purifying or air-fed respirator complying with an approved standard if a risk assessment indicates this is necessary. Respirator selection must be based on known or anticipated exposure levels, the hazards of the product and the safe working limits of the selected respirator. Recommended: A NIOSH-approved air-purifying respirator with an organic vapour cartridge or canister may be permissible under certain circumstances where airborne concentrations are expected to exceed exposure limits. Protection provided by air-purifying respirators is limited. Use a positive-pressure, air-supplied respirator if there is any potential for uncontrolled release, exposure levels are unknown, or any other circumstances where air-purifying respirators may not provide adequate protection.

8 . Exposure controls/personal protection

Hands	: Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Recommended: polyvinyl alcohol (PVA), Viton. Consult your PPE provider for breakthrough times and the specific glove that is best for you based on your use patterns. It should be realized that eventually any material regardless of their imperviousness, will get permeated by chemicals. Therefore, protective gloves should be regularly checked for wear and tear. At the first signs of hardening and cracks, they should be changed.
Eyes	: Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists or dusts.
Skin	: Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.
Environmental exposure controls	: Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

9 . Physical and chemical properties

Physical state	: Clear liquid.
Flash point	: Closed cup: -50 to -38°C (-58 to -36.4°F) [Tagliabue.]
Auto-ignition temperature	: 257°C (494.6°F) (NFPA)
Flammable limits	: Lower: 1.3% (NFPA) Upper: 7.6% (NFPA)
Colour	: Clear to slightly yellow or green, undyed liquid. May be dyed red for taxation purposes.
Odour	: Gasoline
Odour threshold	: Not available.
pH	: Not available.
Boiling/condensation point	: 25 to 220°C (77 to 428°F) (ASTM D86)
Melting/freezing point	: Not available.
Relative density	: 0.685 to 0.8 kg/L @ 15°C (59°F)
Vapour pressure	: <107 kPa (<802.5 mm Hg) @ 37.8°C (100°F)
Vapour density	: 3 to 4 [Air = 1] (NFPA)
Volatility	: Not available.
Evaporation rate	: Not available.
Viscosity	: Not available.
Pour point	: Not available.
Solubility	: Hydrocarbon components virtually insoluble in water. Soluble in alcohol, ether, chloroform and benzene. Dissolves fats, oils and natural resins.

10 . Stability and reactivity

Chemical stability	: The product is stable.
Hazardous polymerisation	: Under normal conditions of storage and use, hazardous polymerisation will not occur.
Materials to avoid	: Reactive with oxidising agents, acids and interhalogens.
Hazardous decomposition products	: May release CO _x , NO _x , phenols, polycyclic aromatic hydrocarbons, aldehydes, ketones, smoke and irritating vapours when heated to decomposition.

11 . Toxicological information

Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
Gasoline	LD50 Dermal	Rabbit	>5000 mg/kg	-
	LD50 Oral	Rat	13600 mg/kg	-
Ethanol	LD50 Dermal	Rabbit	>15800 mg/kg	-
	LD50 Oral	Mouse	3450 mg/kg	-
Benzene	LC50 Inhalation Vapour	Rat	8850 mg/m ³	4 hours
	LD50 Dermal	Rabbit	>8240 mg/kg	-
Toluene	LD50 Oral	Rat	930 mg/kg	-
	LC50 Inhalation Vapour	Rat	13228 ppm	4 hours
LD50 Dermal	Rabbit	12125 mg/kg	-	
LD50 Oral	Rat	636 mg/kg	-	
LC50 Inhalation Vapour	Rat	7585 ppm	4 hours	

Conclusion/Summary : Not available.

Chronic toxicity

Conclusion/Summary : Not available.

Irritation/Corrosion

Conclusion/Summary : Not available.

Sensitiser

Conclusion/Summary : Not available.

Carcinogenicity

Conclusion/Summary : Not available.

Classification

Product/ingredient name	ACGIH	IARC	EPA	NIOSH	NTP	OSHA
Gasoline	A3	2B	-	-	-	-
Ethanol	A3	-	-	-	-	-
Benzene	A1	1	A	+	Proven.	+
Toluene	A4	3	D	-	-	-

Mutagenicity

Conclusion/Summary : Not available.

Teratogenicity

Conclusion/Summary : There is a wealth of information about the teratogenic hazards of Toluene in the literature; however, based upon professional judgement regarding the body of evidence, WHMIS classification as a teratogen is not warranted.

Reproductive toxicity

Conclusion/Summary : Not available.

12 . Ecological information

Environmental effects : No known significant effects or critical hazards.

Aquatic ecotoxicity

Conclusion/Summary : Not available.

Biodegradability

Conclusion/Summary : Not available.

13 . Disposal considerations

Waste disposal

: The generation of waste should be avoided or minimised wherever possible. Empty containers or liners may retain some product residues. This material and its container must be disposed of in a safe way. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Avoid dispersal of spilt material and runoff and contact with soil, waterways, drains and sewers.

Disposal should be in accordance with applicable regional, national and local laws and regulations.

Refer to Section 7: HANDLING AND STORAGE and Section 8: EXPOSURE CONTROLS/PERSONAL PROTECTION for additional handling information and protection of employees.

14 . Transport information

Regulatory information	UN number	Proper shipping name	Classes	PG*	Label	Additional information
TDG Classification	UN1203	GASOLINE	3	II		-
DOT Classification	Not available.	Not available.	Not available.	-		-

PG* : Packing group

15 . Regulatory information

United States

HCS Classification

: Flammable liquid
Irritating material
Carcinogen

Canada

WHMIS (Canada)

: Class B-2: Flammable liquid
Class D-2A: Material causing other toxic effects (Very toxic).
Class D-2B: Material causing other toxic effects (Toxic).

This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations and the MSDS contains all the information required by the Controlled Products Regulations.

International regulations

Canada inventory

: All components are listed or exempted.

United States inventory (TSCA 8b)

: All components are listed or exempted.

Europe inventory

: All components are listed or exempted.

16 . Other information

Label requirements


: FLAMMABLE LIQUID AND VAPOUR. CAUSES RESPIRATORY TRACT, EYE AND SKIN IRRITATION. CANCER HAZARD - CONTAINS MATERIAL WHICH CAN CAUSE CANCER. CONTAINS MATERIAL WHICH CAN CAUSE HERITABLE GENETIC EFFECTS.

Hazardous Material Information System (U.S.A.)

Health	*	2
Flammability		3
Physical hazards		0
Personal protection		H

16 . Other information

National Fire Protection
Association (U.S.A.) :



References

: Available upon request.
™ Trademark of Suncor Energy Inc. Used under licence.

Date of printing :

4/21/2010.

Date of issue :

9 April 2010

Date of previous issue :

No previous validation.

Responsible name :

Product Safety - RS

Indicates information that has changed from previously issued version.

For Copy of (M)SDS :

Internet: www.petro-canada.ca/msds

Canada-wide: telephone: 1-800-668-0220; fax: 1-800-837-1228

For Product Safety Information: (905) 804-4752

Notice to reader

To the best of our knowledge, the information contained herein is accurate. However, neither the above-named supplier, nor any of its subsidiaries, assumes any liability whatsoever for the accuracy or completeness of the information contained herein.

Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist.

Material Safety Data Sheet

MATERIAL SAFETY DATA SHEET

602698-00 MOBIL DTE 13M

1. PRODUCT AND COMPANY IDENTIFICATION

PRODUCT NAME: MOBIL DTE 13M

SUPPLIER: EXXONMOBIL OIL CORPORATION

3225 GALLONS RD.

FAIRFAX, VA 22037

24 - Hour Health and Safety Emergency (call collect): 609-737-4411

24 - Hour Transportation Emergency:

CHEMTREC: 800-424-9300 202-483-7616

LUBES AND FUELS: 281-834-3296

Product and Technical Information:

Lubricants and Specialties: 800-662-4525 800-443-9966

Fuels Products: 800-947-9147

MSDS Fax on Demand: 613-228-1467

MSDS Internet Website: <http://emmsds.ihssolutions.com/>

2. COMPOSITION/INFORMATION ON INGREDIENTS

CHEMICAL NAMES AND SYNONYMS: PET. HYDROCARBONS AND ADDITIVES

GLOBALLY REPORTABLE MSDS INGREDIENTS:

None.

OTHER INGREDIENTS:

Substance Name Approx. Wt%

HYDROTREATED LIGHT NAPHTHENIC 25-35

DISTILLATE (PETROLEUM)

(64742-53-6)

See Section 8 for exposure limits (if applicable).

3. HAZARDS IDENTIFICATION

Under normal conditions of use, this product is not considered hazardous according to regulatory guidelines (See section 15).

EMERGENCY OVERVIEW: Amber Liquid. Note: Pressurized mists may form a flammable mixture. DOT ERG No. : NA

POTENTIAL HEALTH EFFECTS: Under normal conditions of intended use, this product does not pose a risk to health. Excessive exposure may result in eye, skin or respiratory irritation.

For further health effects/toxicological data, see Section 11.

4. FIRST AID MEASURES

EYE CONTACT: Flush thoroughly with water. If irritation occurs, call a physician.

SKIN CONTACT: Wash contact areas with soap and water. Remove and clean oil soaked clothing daily and wash affected area.

INJECTION INJURY WARNING: If product is injected into or under the skin, or into any part of the body, regardless of the appearance of the wound or its size, the individual should be evaluated immediately by a physician as a surgical emergency.

Even though initial symptoms from high pressure injection may be minimal or absent, early surgical treatment within the first few hours may significantly reduce the ultimate extent of injury.

INHALATION: Not expected to be a problem. However, if respiratory irritation, dizziness, nausea, or unconsciousness occurs due to excessive vapor or mist exposure, seek immediate medical assistance. If breathing has stopped, assist ventilation with a mechanical device or mouth-to-mouth resuscitation.

INGESTION: Not expected to be a problem. Seek medical attention if discomfort occurs. Do not induce vomiting.

5. FIRE-FIGHTING MEASURES

EXTINGUISHING MEDIA: Carbon dioxide, foam, dry chemical and water fog.

SPECIAL FIRE FIGHTING PROCEDURES: Water or foam may cause frothing. Use water to keep fire exposed containers cool. Water spray may be used to flush spills away from exposure. Prevent runoff from fire control or dilution from entering streams, sewers, or drinking water supply.

SPECIAL PROTECTIVE EQUIPMENT: For fires in enclosed areas, fire fighters must use self-contained breathing apparatus.

UNUSUAL FIRE AND EXPLOSION HAZARDS: Note: Pressurized mists may form a flammable mixture.

COMBUSTION PRODUCTS: Fumes, smoke, carbon monoxide, sulfur oxides, aldehydes and other decomposition products, in the case of incomplete combustion.

Flash Point C(F): 210(410) (ASTM D-92).

Flammable Limits (approx. % vol.in air) - LEL: 0.9%, UEL: 7.0%

NFPA HAZARD ID: Health: 0, Flammability: 1, Reactivity: 0

6. ACCIDENTAL RELEASE MEASURES

NOTIFICATION PROCEDURES: Report spills/releases as required to appropriate authorities. U.S. Coast Guard and EPA regulations require immediate reporting of spills/releases that could reach any waterway including intermittent dry creeks. Report spill/release to Coast Guard National Response Center toll free number (800)424-8802. In case of accident or road spill notify CHEMREC (800) 424-9300.

PROCEDURES IF MATERIAL IS RELEASED OR SPILLED:

LAND SPILL: Shut off source taking normal safety precautions. Take measures to minimize the effects on ground water. Recover by pumping or contain spilled material with sand or other suitable absorbent and remove mechanically into containers. If necessary, dispose of adsorbed residues as directed in Section 13.

WATER SPILL: Confine the spill immediately with booms. Warn other ships in the vicinity. Notify port and other relevant authorities. Remove from the surface by skimming or with suitable absorbents. If permitted by regulatory authorities the use of suitable dispersants should be considered where recommended in local oil spill procedures.

ENVIRONMENTAL PRECAUTIONS: Prevent material from entering sewers, water sources or low lying areas; advise the relevant authorities if it has, or if it contaminates soil/vegetation.

PERSONAL PRECAUTIONS: See Section 8

7. HANDLING AND STORAGE

HANDLING: High pressure injection under the skin may occur due to the rupture of pressurized lines. Always seek medical attention. No special precautions are necessary beyond normal good hygiene practices. See Section 8 for additional personal protection advice when handling this product.

STORAGE: Keep containers closed when not in use. Do not store in open or unlabelled containers. Store away from strong oxidizing agents and combustible materials. Do not store near heat, sparks, flame or strong oxidants.

SPECIAL PRECAUTIONS: Prevent small spills and leakages to avoid slip hazard.

EMPTY CONTAINER WARNING: Empty containers retain residue (liquid and/or vapor) and can be dangerous. DO NOT PRESSURIZE, CUT, WELD, BRAZE, SOLDER, DRILL, GRIND OR EXPOSE SUCH CONTAINERS TO HEAT, FLAME, SPARKS, STATIC ELECTRICITY, OR OTHER SOURCES OF IGNITION; THEY MAY EXPLODE AND CAUSE INJURY OR DEATH. Do not attempt to refill or clean container since residue is difficult to remove. Empty drums should be completely drained, properly bunged and promptly returned to a drum reconditioner. All containers should be disposed of in an environmentally safe manner and in accordance with governmental regulations.

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

OCCUPATIONAL EXPOSURE LIMITS:

When mists/aerosols can occur, the following are recommended: 5 mg/m³ (as oil mist)- ACGIH Threshold Limit Value (TLV), 10 mg/m³ (as oil mist) - ACGIH Short Term Exposure Limit (STEL), 5 mg/m³ (as oil mist) - OSHA Permissible Exposure Limit (PEL)

VENTILATION: If mists are generated, use adequate ventilation, local exhaust or enclosures to control below exposure limits.

RESPIRATORY PROTECTION: If mists are generated, and/or when ventilation is not adequate, wear approved respirator.

EYE PROTECTION: If eye contact is likely, safety glasses with side shields or chemical type goggles should be worn.

SKIN PROTECTION: Not normally required. When splashing or liquid contact can occur frequently, wear oil resistant gloves and/or other protective clothing. Good personal hygiene practices should always be followed.

9. PHYSICAL AND CHEMICAL PROPERTIES

Typical physical properties are given below. Consult Product Data Sheet for specific details.

APPEARANCE: Liquid

COLOR: Amber

ODOR: Mild

ODOR THRESHOLD-ppm: NE

pH: NA

BOILING POINT C(F): > 316(600)

MELTING POINT C(F): NA

FLASH POINT C(F): 210(410) (ASTM D-92)

FLAMMABILITY (solids): NE

AUTO FLAMMABILITY C(F): NA

EXPLOSIVE PROPERTIES: NA

OXIDIZING PROPERTIES: NA

VAPOR PRESSURE-mmHg 20 C: < 0.1

VAPOR DENSITY: > 2.0

EVAPORATION RATE: NE

RELATIVE DENSITY, 15/4 C: 0.874

SOLUBILITY IN WATER: Negligible

PARTITION COEFFICIENT: > 3.5

VISCOSEITY AT 40 C, cSt: 32.0

VISCOSEITY AT 100 C, cSt: 6.1

POUR POINT C(F): -45(-49)

FREEZING POINT C(F): NE

VOLATILE ORGANIC COMPOUND: NE

DMSO EXTRACT, IP-346 (WT.%): <3, for mineral oil only

NA=NOT APPLICABLE NE=NOT ESTABLISHED D=DECOMPOSES

FOR FURTHER TECHNICAL INFORMATION, CONTACT YOUR MARKETING REPRESENTATIVE

10. STABILITY AND REACTIVITY

STABILITY (THERMAL, LIGHT, ETC.): Stable.

CONDITIONS TO AVOID: Extreme heat and high energy sources of ignition.

INCOMPATIBILITY (MATERIALS TO AVOID): Strong oxidizers.

HAZARDOUS DECOMPOSITION PRODUCTS: Product does not decompose at ambient temperatures.

HAZARDOUS POLYMERIZATION: Will not occur.

11. TOXICOLOGICAL DATA

—ACUTE TOXICOLOGY—

ORAL TOXICITY (RATS): Practically non-toxic (LD₅₀: greater than 2000 mg/kg). —Based on testing of similar products and/or the components.

DERMAL TOXICITY (RABBITS): Practically non-toxic (LD₅₀: greater than 2000 mg/kg). —Based on testing of similar products and/or the components.

INHALATION TOXICITY (RATS): Practically non-toxic (LC₅₀: greater than 5 mg/l). —Based on testing of similar products and/or the components.

EYE IRRITATION (RABBITS): Practically non-irritating. (Draize score: greater than 6 but 15 or less). —Based on testing of similar products and/or the components.

SKIN IRRITATION (RABBITS): Practically non-irritating. (Primary Irritation Index: greater than 0.5 but less than 3). —Based on testing of similar products and/or the components.

OTHER ACUTE TOXICITY DATA: Although an acute inhalation study was not performed with this product, a variety of mineral and synthetic oils, such as those in this product, have been tested. These samples had virtually no effect other than a nonspecific inflammatory response in the lung to the aerosolized mineral oil. The presence of additives in other tested formulations (in approximately the same amounts as in the present formulation) did not alter the observed effects.

—SUBCHRONIC TOXICOLOGY (SUMMARY)—

No significant adverse effects were found in studies using repeated dermal applications of similar formulations to the skin of laboratory animals for 13 weeks at doses significantly higher than those expected during normal industrial exposure. The animals were evaluated extensively for effects of exposure (hematology, serum chemistry, urinalysis, organ weights, microscopic examination of tissues etc.).

—REPRODUCTIVE TOXICOLOGY (SUMMARY)—

No teratogenic effects would be expected from dermal exposure, based on laboratory developmental toxicity studies of major components in this formulation and/or materials of similar composition.

—CHRONIC TOXICOLOGY (SUMMARY)—

Repeated and/or prolonged exposure may cause irritation to the skin, eyes or respiratory tract. Overexposure to oil mist may result in oil droplet deposition and/or granuloma formation. For mineral base oils: Base oils in this product are severely solvent refined and/or severely hydrotreated. Chronic mouse skin painting studies of severely treated oils showed no evidence of carcinogenic effects. These results are confirmed on a continuing basis using various screening methods such as Modified

Ames Test, IP-346, and/or other analytical methods. For synthetic base oils: The base oils in this product have been tested in the Ames assay and other tests of mutagenicity with negative results. These base oils are not expected to be carcinogenic with chronic dermal exposures.

—SENSITIZATION (SUMMARY)—

Not expected to be sensitizing based on tests of this product, components, or similar products.

12. ECOLOGICAL INFORMATION

ENVIRONMENTAL FATE AND EFFECTS:

In the absence of specific environmental data for this product, this assessment is based on information for representative products.

ECOTOXICITY: Available ecotoxicity data (LL50 >1000 mg/L) indicates that adverse effects to aquatic organisms are not expected from this product.

MOBILITY: When released into the environment, adsorption to sediment and soil will be the predominant behavior.

PERSISTENCE AND DEGRADABILITY: This product is expected to be inherently biodegradable.

BIOACCUMULATIVE POTENTIAL: Bioaccumulation is unlikely due to the very low water solubility of this product, therefore bioavailability to aquatic organisms is minimal.

13. DISPOSAL CONSIDERATIONS

WASTE DISPOSAL: Product is suitable for burning in an enclosed, controlled burner for fuel value. Such burning may be limited pursuant to the Resource Conservation and Recovery Act. In addition, the product is suitable for processing by an approved recycling facility or can be disposed of at an appropriate government waste disposal facility. Use of these methods is subject to user compliance with applicable laws and regulations and consideration of product characteristics at time of disposal.

RCRA INFORMATION: The unused product, in our opinion, is not specifically listed by the EPA as a hazardous waste (40 CFR, Part 261D), nor is it formulated to contain materials which are listed hazardous wastes. It does not exhibit the hazardous characteristics of ignitability, corrosivity, or reactivity. The unused product is not formulated with substances covered by the Toxicity Characteristic Leaching Procedure (TCLP). However, used product may be regulated.

14. TRANSPORT INFORMATION

USA DOT: NOT REGULATED BY USA DOT.

RID/ADR: NOT REGULATED BY RID/ADR.

IMO: NOT REGULATED BY IMO.

IATA: NOT REGULATED BY IATA.

STATIC ACCUMULATOR (50 picosiemens or less): YES

15. REGULATORY INFORMATION

US OSHA HAZARD COMMUNICATION STANDARD: When used for its intended purposes, this product is not classified as hazardous in accordance with OSHA 29 CFR 1910.1200.

EU Labeling: Product is not dangerous as defined by the European Union

Dangerous Substances/Preparations Directives. EU labeling not required.

Governmental Inventory Status: All components comply with TSCA,

EINECS/ELINCS, AICS, DSL, and KEI.

U.S. Superfund Amendments and Reauthorization Act (SARA) Title III:

This product contains no "EXTREMELY HAZARDOUS SUBSTANCES".

SARA (311/312) REPORTABLE HAZARD CATEGORIES: None.

This product contains no chemicals subject to the supplier notification requirements of SARA (313) toxic release program.

THIS PRODUCT HAS BEEN AUTHORIZED BY USDA FOR USE UNDER THE FOLLOWING

CATEGORY: This product is acceptable as a lubricant where there

is no possibility of food contact (complies with earlier USDA

guidelines for H-2 lubricant use).

The following product ingredients are cited on the lists below:

CHEMICAL NAME CAS NUMBER LIST CITATIONS *

ZINC (ELEMENTAL ANALYSIS) (0.08%) 7440-66-6 22

ZINC ALKYL DITHIOPHOSPHATE 68649-42-3 22

(0.67%)

— REGULATORY LISTS SEARCHED —

1=ACGIH ALL 6=IARC 1 11=TSCA 4 16=CA P65 CARC 21=LA RTK
2=ACGIH A1 7=IARC 2A 12=TSCA 5a2 17=CA P65 REPRO 22=MI 293
3=ACGIH A2 8=IARC 2B 13=TSCA 5e 18=CA RTK 23=MN RTK
4=NTP CARC 9=OSHA CARC 14=TSCA 6 19=FL RTK 24=NJ RTK
5=NTP SUS 10=OSHA Z 15=TSCA 12b 20=IL RTK 25=PA RTK
26=RI RTK

* EPA recently added new chemical substances to its TSCA Section 4 test rules. Please contact the supplier to confirm whether the ingredients in this product currently appear on a TSCA 4 or TSCA 12b list.

Code key:CARC=Carcinogen; SUS=Suspected Carcinogen; REPRO=Reproductive

16. OTHER INFORMATION

USE: HYDRAULIC OIL

NOTE: PRODUCTS OF EXXON MOBIL CORPORATION AND ITS AFFILIATED COMPANIES
ARE NOT FORMULATED TO CONTAIN PCBs.

Health studies have shown that many hydrocarbons pose potential human health risks which may vary from person to person. Information provided on this MSDS reflects intended use. This product should not be used for other applications. In any case, the following advice should be considered:

INDUSTRIAL LABEL

Under normal conditions of intended use, this product does not pose a risk to health. Excessive exposure may result in eye, skin or respiratory irritation. Always observe good hygiene measures. First Aid: Wash skin with soap and water. Flush eyes with water. If overcome by fumes or vapor, remove to fresh air. If ingested do not induce vomiting. If symptoms persist seek medical assistance. Read and understand the MSDS before using this product.

For Internal Use Only: MHC: 1* 1* 1* 1* 1*, MPPEC: A, TRN: 602698-00, CMCS97: 970705, REQ: US - MARKETING, SAFE USE: L EHS Approval Date: 25APR2003

Information given herein is offered in good faith as accurate, but without guarantee. Conditions of use and suitability of the product for particular uses are beyond our control; all risks of use of the product are therefore assumed by the user and WE EXPRESSLY DISCLAIM ALL WARRANTIES OF EVERY KIND AND NATURE, INCLUDING WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE IN RESPECT TO THE USE OR SUITABILITY OF THE PRODUCT. Nothing is intended as a recommendation for uses which infringe valid patents or as extending license under valid patents. Appropriate warnings and safe handling procedures should be provided to handlers and users. Alteration of this document is strictly prohibited. Except to the extent required by law, republication or retransmission of this document, in whole or in part, is not permitted. Exxon Mobil Corporation and its affiliated companies assume no responsibility for accuracy of information unless the document is the most current available from an official ExxonMobil distribution system. Exxon Mobil Corporation and its affiliated companies neither represent nor warrant that the format, content or product formulas contained in this document comply with the laws of any other country except the United States of America.

Prepared by: ExxonMobil Oil Corporation

Environmental Health and Safety Department, Clinton, USA

Copyright 2001 Exxon Mobil Corporation. All Rights Reserved.

Material Safety Data Sheet

PETRO-CANADA ANTIFREEZE



1 . Product and company identification

Product name	: PETRO-CANADA ANTIFREEZE
Synonym	: Universal Antifreeze, Radiator Antifreeze, Diesel Antifreeze, Petro-Canada Antifreeze-Coolant, Petro-Canada Heavy Duty Antifreeze-Coolant, Pre-Mix Antifreeze, Petro-Canada Premium Radiator Antifreeze, Diesel Engine Coolant, Pre-Mixed Radiator Antifreeze/Coolant Petro-Canada.
Code	: W269
Material uses	: Used as an engine antifreeze coolant.
Manufacturer	: PETRO-CANADA P.O. Box 2844 150 – 6th Avenue South-West Calgary, Alberta T2P 3E3
<u>In case of emergency</u>	: Petro-Canada: 403-296-3000 Canutec Transportation: 613-996-6666 Poison Control Centre: Consult local telephone directory for emergency number(s).

2 . Hazards identification

Physical state	: Clear viscous liquid.
Odour	: Odourless.
WHMIS (Canada)	: Class D-1B: Material causing immediate and serious toxic effects (Toxic). Class D-2A: Material causing other toxic effects (Very toxic).
OSHA/HCS status	: This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).
Emergency overview	: CAUTION! MAY BE HARMFUL IF SWALLOWED. MAY CAUSE EYE AND SKIN IRRITATION. CONTAINS MATERIAL THAT MAY CAUSE TARGET ORGAN DAMAGE, BASED ON ANIMAL DATA. POSSIBLE BIRTH DEFECT HAZARD - CONTAINS MATERIAL WHICH MAY CAUSE BIRTH DEFECTS, BASED ON ANIMAL DATA. POSSIBLE DEVELOPMENTAL HAZARD - CONTAINS MATERIAL WHICH MAY CAUSE ADVERSE DEVELOPMENTAL EFFECTS, BASED ON ANIMAL DATA. May be harmful if swallowed. Slightly irritating to the eyes and skin. Avoid exposure - obtain special instructions before use. Do not breathe vapour or mist. Do not ingest. Avoid contact with eyes, skin and clothing. Contains material that may cause target organ damage, based on animal data. Contains material which may cause birth defects, based on animal data. Contains material which may cause developmental abnormalities, based on animal data. Avoid exposure during pregnancy. Wash thoroughly after handling.
Routes of entry	: Dermal contact. Eye contact. Inhalation. Ingestion.
Potential acute health effects	
Inhalation	: Inhalation of this product may cause respiratory tract irritation.
Ingestion	: Harmful if swallowed. Ingestion of this product may cause gastro-intestinal irritation, nausea, vomiting, abdominal pain, and diarrhea. Ingestion of this product may cause Central Nervous System (CNS) Depression, symptoms of which may include; weakness, dizziness, slurred speech, drowsiness, unconsciousness and in cases of severe overexposure; coma and death.
Skin	: Slightly irritating to the skin.
Eyes	: Slightly irritating to the eyes.
Potential chronic health effects	

2 . Hazards identification

Chronic effects	: Contains material that may cause target organ damage, based on animal data.
Carcinogenicity	: No known significant effects or critical hazards.
Mutagenicity	: No known significant effects or critical hazards.
Teratogenicity	: Contains material which may cause birth defects, based on animal data.
Developmental effects	: Contains material which may cause developmental abnormalities, based on animal data.
Fertility effects	: No known significant effects or critical hazards.
Target organs	: The substance may be toxic to kidneys and liver. Repeated or prolonged exposure to the substance can produce target organs damage. Repeated exposure to a highly toxic material may produce general deterioration of health by an accumulation in one or many human organs.
Medical conditions aggravated by over-exposure	: Pre-existing disorders involving any target organs mentioned in this MSDS as being at risk may be aggravated by over-exposure to this product.

See toxicological information (section 11)

3 . Composition/information on ingredients

<u>Name</u>	<u>CAS number</u>	<u>%</u>
Ethylene glycol	107-21-1	45 - 50

There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health or the environment and hence require reporting in this section.

4 . First-aid measures

Eye contact	: Check for and remove any contact lenses. Immediately flush eyes with plenty of water for at least 15 minutes, occasionally lifting the upper and lower eyelids. Get medical attention immediately.
Skin contact	: In case of contact, immediately flush skin with plenty of water for at least 15 minutes while removing contaminated clothing and shoes. Wash skin thoroughly with soap and water or use recognised skin cleanser. Wash clothing before reuse. Clean shoes thoroughly before reuse. Get medical attention immediately.
Inhalation	: Move exposed person to fresh air. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. Loosen tight clothing such as a collar, tie, belt or waistband. Get medical attention immediately.
Ingestion	: Wash out mouth with water. Do not induce vomiting unless directed to do so by medical personnel. Never give anything by mouth to an unconscious person. Get medical attention immediately.
Protection of first-aiders	: No action shall be taken involving any personal risk or without suitable training. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Wash contaminated clothing thoroughly with water before removing it, or wear gloves.
Notes to physician	: No specific treatment. Treat symptomatically. Contact poison treatment specialist immediately if large quantities have been ingested or inhaled.

5 . Fire-fighting measures

Flammability of the product	: Non-flammable.
Extinguishing media	
Suitable	: Use an extinguishing agent suitable for the surrounding fire.
Not suitable	: None known.
Special exposure hazards	: Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training.

5 . Fire-fighting measures

Products of combustion : Carbon oxides (CO, CO₂), smoke and irritating vapours as products of incomplete combustion.

Special protective equipment for fire-fighters : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

Special remarks on explosion hazards : Do not pressurise, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition.

6 . Accidental release measures

Personal precautions : No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilt material. Avoid breathing vapour or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment (see section 8).

Environmental precautions : Avoid dispersal of spilt material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

Methods for cleaning up

Small spill : Stop leak if without risk. Move containers from spill area. Dilute with water and mop up if water-soluble or absorb with an inert dry material and place in an appropriate waste disposal container. Dispose of via a licensed waste disposal contractor.

Large spill : Stop leak if without risk. Move containers from spill area. Approach the release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see section 13). Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the same hazard as the spilt product. Note: see section 1 for emergency contact information and section 13 for waste disposal.

7 . Handling and storage

Handling : Put on appropriate personal protective equipment (see section 8). Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Avoid exposure during pregnancy. Do not get in eyes or on skin or clothing. Do not ingest. Avoid breathing vapour or mist. If during normal use the material presents a respiratory hazard, use only with adequate ventilation or wear appropriate respirator. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Empty containers retain product residue and can be hazardous. Do not reuse container.

Storage : Store in accordance with local regulations. Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see section 10) and food and drink. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabelled containers. Use appropriate containment to avoid environmental contamination.

8 . Exposure controls/personal protection

Ingredient	Exposure limits
Ethylene glycol	ACGIH TLV (United States). CEIL: 100 mg/m ³ , (aerosol)

Consult local authorities for acceptable exposure limits.

Recommended monitoring procedures : If this product contains ingredients with exposure limits, personal, workplace atmosphere or biological monitoring may be required to determine the effectiveness of the ventilation or other control measures and/or the necessity to use respiratory protective equipment.

8 . Exposure controls/personal protection

Engineering measures	: If user operations generate dust, fumes, gas, vapour or mist, use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits.
Hygiene measures	: Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.
Personal protection	
Respiratory	: Use a properly fitted, air-purifying or air-fed respirator complying with an approved standard if a risk assessment indicates this is necessary. Respirator selection must be based on known or anticipated exposure levels, the hazards of the product and the safe working limits of the selected respirator. Recommended: organic vapour filter
Hands	: Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Recommended: neoprene, nitrile, polyvinyl chloride (PVC). Consult your PPE provider for breakthrough times and the specific glove that is best for you based on your use patterns. It should be realized that eventually any material regardless of their imperviousness, will get permeated by chemicals. Therefore, protective gloves should be regularly checked for wear and tear. At the first signs of hardening and cracks, they should be changed.
Eyes	: Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists or dusts.
Skin	: Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.
Environmental exposure controls	: Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

9 . Physical and chemical properties

Physical state	: Clear viscous liquid.
Flash point	: Not available.
Auto-ignition temperature	: Not available.
Flammable limits	: Not available.
Colour	: Yellow.
Odour	: Odourless.
Odour threshold	: Not available.
pH	: Not available.
Boiling/condensation point	: 129°C (264.2°F)
Melting/freezing point	: -37°C (-34.6°F)
Relative density	: 1.06 to 1.09
Vapour pressure	: 0.008 kPa (0.06 mm Hg)
Vapour density	: 2.1 [Air = 1]
Volatility	: Not available.
Evaporation rate	: Not available.
Viscosity	: Not available.
Pour point	: Not available.

9 . Physical and chemical properties

Solubility : Soluble in water, methanol and diethyl ether.

10 . Stability and reactivity

Chemical stability : The product is stable.

Hazardous polymerisation : Under normal conditions of storage and use, hazardous polymerisation will not occur.

Materials to avoid : Reactive with oxidising agents, acids and alkalis.

Hazardous decomposition products : May release CO_x, smoke and irritating vapours when heated to decomposition.

11 . Toxicological information

Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
Ethylene glycol	LD50 Dermal	Rabbit	9530 mg/kg	-
	LD50 Oral	Rat	4700 mg/kg	-
	LC50 Inhalation	Rat	2725 mg/m ³	4 hours
	Dusts and mists			

Conclusion/Summary : Not available.

Chronic toxicity

Conclusion/Summary : Not available.

Irritation/Corrosion

Conclusion/Summary : Not available.

Sensitiser

Conclusion/Summary : Not available.

Carcinogenicity

Conclusion/Summary : Not available.

Classification

Product/ingredient name	ACGIH	IARC	EPA	NIOSH	NTP	OSHA
Ethylene glycol	A4	-	-	-	-	-

Mutagenicity

Conclusion/Summary : Not available.

Teratogenicity

Conclusion/Summary : Not available.

Reproductive toxicity

Conclusion/Summary : Not available.

12 . Ecological information

Environmental effects : No known significant effects or critical hazards.

Aquatic ecotoxicity

Conclusion/Summary : Not available.

Biodegradability

Conclusion/Summary : Not available.

13 . Disposal considerations

Waste disposal

: The generation of waste should be avoided or minimised wherever possible. Empty containers or liners may retain some product residues. This material and its container must be disposed of in a safe way. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Avoid dispersal of spilt material and runoff and contact with soil, waterways, drains and sewers.

Disposal should be in accordance with applicable regional, national and local laws and regulations.

Refer to Section 7: HANDLING AND STORAGE and Section 8: EXPOSURE CONTROLS/PERSONAL PROTECTION for additional handling information and protection of employees.

14 . Transport information

Regulatory information	UN number	Proper shipping name	Classes	PG*	Label	Additional information
TDG Classification	Not regulated.	-	-	-		-
DOT Classification	UN3082	ENVIRONMENTALLY HAZARDOUS SUBSTANCE, LIQUID, N.O.S. (Ethylene glycol based coolant)	9	III		Special provisions In single containers of 5000 lbs capacity or less this product is exempt from DOT regulations (not regulated).

PG* : Packing group

15 . Regulatory information

United States

HCS Classification : Target organ effects

Canada

WHMIS (Canada) : Class D-1B: Material causing immediate and serious toxic effects (Toxic).
Class D-2A: Material causing other toxic effects (Very toxic).

This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations and the MSDS contains all the information required by the Controlled Products Regulations.

International regulations

Canada inventory : All components are listed or exempted.

United States inventory (TSCA 8b) : All components are listed or exempted.

Europe inventory : Not determined.

16 . Other information

Label requirements


: MAY BE HARMFUL IF SWALLOWED. MAY CAUSE EYE AND SKIN IRRITATION. CONTAINS MATERIAL THAT MAY CAUSE TARGET ORGAN DAMAGE, BASED ON ANIMAL DATA. POSSIBLE BIRTH DEFECT HAZARD - CONTAINS MATERIAL WHICH MAY CAUSE BIRTH DEFECTS, BASED ON ANIMAL DATA. POSSIBLE DEVELOPMENTAL HAZARD - CONTAINS MATERIAL WHICH MAY CAUSE ADVERSE DEVELOPMENTAL EFFECTS, BASED ON ANIMAL DATA.

Hazardous Material Information System (U.S.A.)

Health	*	2
Flammability		0
Physical hazards		0
Personal protection		H

16 . Other information

National Fire Protection Association (U.S.A.) :



References

- : Available upon request.
TM Trademark of Suncor Energy Inc. Used under licence.

Date of printing

: 3/11/2010.

Date of issue

: 11 March 2010

Date of previous issue

: No previous validation.

Responsible name

: Product Safety - JDW

Indicates information that has changed from previously issued version.

For Copy of (M)SDS

- : Internet: www.petro-canada.ca/msds

Canada-wide: telephone: 1-800-668-0220; fax: 1-800-837-1228

For Product Safety Information: (905) 804-4752


Notice to reader

To the best of our knowledge, the information contained herein is accurate. However, neither the above-named supplier, nor any of its subsidiaries, assumes any liability whatsoever for the accuracy or completeness of the information contained herein.

Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist.



Tetra Tech EBA
Suite 1000 - 10th Floor,
885 Dunsmuir Street
VANCOUVER, BC V6C 1N5
p. 604.685.0275



TETRA TECH EBA